

Library of

Wellesley




College.

Purchased from
Sweet Fund

No.



WESTERN ASIA IN THE SECOND MILLENNIUM B.C.



SCALE 1:7,000,000

0 50 100 200 300 400 500 Miles

THE BOOK OF JUDGES

WITH INTRODUCTION AND NOTES

EDITED BY

THE REV. C. F. BURNEY, D.LITT.

ORIEL PROFESSOR OF THE INTERPRETATION OF HOLY SCRIPTURE
IN THE UNIVERSITY OF OXFORD,
CANON OF ROCHESTER,
AND FELLOW OF ST. JOHN BAPTIST'S COLLEGE, OXFORD

SECOND EDITION

RIVINGTONS

34 *KING STREET, COVENT GARDEN*
LONDON

1920

14

Under the General Editorship of
THE REV. C. F. BURNEY, D.LITT.

St. Mark's Gospel. With Introduction and Notes.

Edited by the Ven. W. C. ALLEN, M.A., Rector of Chorley,
and Archdeacon of Blackburn. 7s. 6d. *net*.

'Archdeacon Allen has succeeded in writing another exposition of the earliest Gospel on entirely independent lines, and it will take high rank as one of those Commentaries that the keen student of the Gospels cannot afford to do without.
—Methodist Recorder.

The Book of Wisdom. With Introduction and Notes.

Edited by the Rev. A. T. S. GOODRICK, M.A., Late Rector of
Winterbourne, Bristol. 10s. 6d. *net*.

'Mr. Goodrick's Preface at once arrests attention. Here is evidently a scholar taking his task seriously. He knows the literature, writes in terse, trenchant style, and has reached original conclusions. The expectation roused is not disappointed in the rest of the book.'—Guardian.

LONDON: RIVINGTONS

P.5
1305
.P5
1920

COPYRIGHT

TO MY WIFE

P R E F A C E .

A NEW commentary upon one of the books of the Old Testament seems to call for a few words in justification of its appearance, and for an indication of the special features which it aims at offering. The Book of Judges is not a book which has suffered from neglect on the part of scholars in the past : indeed, the last thirty years have witnessed the accession of much valuable work devoted to its elucidation. The Commentary by Professor Moore (1895)—to cite but a single example—is, by general consent, one of the most thorough and scholarly volumes even of so eminent a series as the *International Critical Commentary*. Biblical science, however, does not stand still. We are—or should be—daily widening the basis of our research. Fresh knowledge of the languages, literature, and antiquities of the peoples who were kindred to Israel, by race or by environment, is constantly being brought within reach ; and the Old Testament scholar who would keep abreast of the possibilities of Biblical interpretation must spread his nets wide if he is to gather in the available material for his studies.

For myself, I can say with truth that such first-hand acquaintance with the Babylonian and Assyrian language and literature as I have been able to acquire during the past fourteen years or so, has revolutionized my outlook upon Old Testament studies. The possibilities for fresh investigation offered within this sphere, together with an instinctive preference for study of the Biblical sources themselves, prior to consultation of that which has been written about them by other scholars, have, I hope, imparted some measure of originality to my work ; though

originality, as an end in itself, was not what I was striving after. I have, so far as I was able, made myself acquainted with the work of my predecessors in the same field ; and I trust that I have regularly discharged the duty incumbent upon every scholar by making due acknowledgment to them whenever I have cited their opinion. An apparent exception to this rule may be found in the introductory discussions on the composition and sources of the various narratives contained in the book ; but here I have always worked out my own conclusions and argued them in detail, and anything like a regular citation of my agreement with, or divergency from, other scholars must have led to undue prolixity, and would only have tended to confuse the reader.

I trust that the somewhat lengthy § 6 of my Introduction, on 'External information bearing on the period of Judges,' may not be deemed superfluous to the purpose of the commentary. The Book of Judges occupies a position on the borderland between history and legend. In order to place our feet on firm ground, and gain as much as may be for veritable history, it is most important to examine the external sources, so far as they are accessible, which bear upon the condition of Cana'an and its inhabitants at and before the period covered by the book. It is important also—in view of the frequent reference made in the commentary to Babylonian influence and analogy—to understand how it was that such influence had permeated Cana'an to so large an extent at this early period. Throughout my work I have had in view, not merely the elucidation of the text of Judges, but as thorough an investigation as I could make of the early period of Israel's residence in Cana'an for which Judges forms our principal text-book. My volume, therefore, may perhaps be described as a collection of material for this early history rather than as a commentary pure and simple ; and if this view is taken of it I shall be content.

Since the basis of correct exegesis of the Old Testa-

ment consists in a sound philological knowledge of Hebrew, and such knowledge is mainly advanced through comparative study of the cognate Semitic languages, considerable attention is devoted in the notes to questions of comparative philology. In discussions which fall under this head I have adopted the plan of transliterating both the Hebrew words and those from cognate languages which are brought into comparison with them, in order that the Hebrew student who is unacquainted with the cognate languages may be able, to some extent at least, to appreciate the argument. A table explaining the method of transliteration is given on pp. xxxi f., and an index of the transliterated forms will be found at the end of the volume. The use of Hebrew and other Semitic types has been minimized as far as possible, in the hope that the commentary may prove useful, not merely to Hebrew scholars, but to the larger class of Biblical students who are ignorant of the language. Whenever a quotation is made in the original it is accompanied by a translation.

Among the notes on the text there will be found some which are of very considerable length, *e.g.* those on the Ashera (p. 195), the Ephod (p. 236), the representation of Samson as a Nazirite (p. 342), the line of the Midianites' flight, and the site of Abel-meholah (p. 219), as well as some of the other geographical notes, and many of the textual notes upon the Song of Deborah. Notes such as these have been expanded without compunction, because I believed that I had new light to throw upon very difficult problems; and readers who are really desirous of getting to the bottom of such problems will not, I think, quarrel with me upon this score.

It is possible that one of the Additional Notes—that on the use of writing in the time of the Judges, and the antiquity of the Alphabetic Script (p. 253)—may be thought to hang upon rather a slight peg in the reference to writing in *ch.* 8¹¹, so far as the necessities of the com-

mentary are concerned ; but the many-sided interest of the subject and the manner in which it has entered into recent discussions (some of them not untinged with controversial bias) seemed to call for an explicit statement of the facts, and of such deductions from them as appear to be justified. The notes on 'Yahweh or Yahu originally an Amorite Deity' (p. 243), and 'Early identification of Yahweh with the Moon-god' (p. 249), form integral parts of my theory as to the Ashera ; and I am unaware of any source of information which brings together the facts which I was desirous of marshalling.

Among those to whom I owe thanks for assistance rendered in the preparation of this commentary, there are two whose help has been of a very special character. Dr. Driver read through the whole of my new translation of the text of Judges (which I completed before beginning to write the notes upon it), and made many suggestions which materially improved it. He also saw, in one form or another, all or most of what I have written on *chs.* 1-8 ; and since he was without stint accessible to all who desired to consult him, I was accustomed constantly to discuss points of difficulty with him, and many of my conclusions and theories embodied in the commentary have, needless to say, much profited through his advice and revision. Dr. C. J. Ball has undertaken the heavy task of reading the whole of my proof-sheets and discussing them personally with me. All that my book owes to him it is impossible for me adequately to estimate ; a small part of it may be seen in the number of fresh suggestions which he has allowed me to include in my notes.*

When all has been said, however, my debt to these two scholars for actual co-operation in the work put into my book is but a tithe of what I and the book owe to them in a wider sense. Enjoying as I did the close friendship of Dr. Driver from the year that I came up

* Cf. pp. 114, 119, 122, 129, 144, 148, 250, 325, 421, 476 f.

to Oxford as an undergraduate until the year of his death, I cannot but feel that most of what I have learned in method and thoroughness of scholarship is due to his teaching and example. Under Dr. Ball I began as a schoolboy to study the elements of Hebrew; under him some twenty years later I began to grapple with Assyriology, and the marvellous gifts which he possesses as a teacher caused the early stages of a study which might otherwise have seemed tedious and repellent to appear in the light of an easy and fascinating pastime.

I have also to express my grateful thanks to Professor L. W. King for much advice upon matters connected with Babylonian studies. He has read, in particular, § 6 of my Introduction and all my Additional Notes which deal with the influence of Babylonian civilization upon Cana'an; and my confidence in the lines which I have taken in dealing with this side of my subject has been greatly strengthened by his approval and support. Professor R. W. Rogers of Drew Theological Seminary, Madison, New Jersey, whose regular visits for research in the Bodleian Library have made him as much a son of Oxford as of the United States, was in residence here during the greater part of the years 1913-14. During our long friendship we have grown accustomed to discuss the Biblical questions in which our common interests lie; and I owe much to his judicial mind and expert knowledge of Assyriology.

With my wife I have talked over many of the points, both small and great, which have arisen in the course of my researches; and the book owes not a little to her quick apprehension, sound common sense, and unerring feeling for style and lucidity.

Finally, I must thank the Trustees of the British Museum for permission to reproduce the seal-cylinder impressions figured in Plate III., and the two reliefs from the Report on excavations at Carchemish, edited by Dr. D. G. Hogarth, which appear in Plate V.;

M. Leroux, the publisher of Delaporte's *Catalogue des Cylindres orientaux . . . de la Bibliothèque Nationale*, for a similar permission in the case of the seal-cylinder impressions given in Plate II.; the Committee of the Palestine Exploration Fund for kindly allowing me to make the sketch-map of the district round Gibe'ah (opposite p. 465) upon the basis of their large survey-map; and the British Academy for permission to make use of the map of Western Asia which has been prepared for my Schweich Lectures.

C. F. B.

OXFORD,
Easter 1918.

NOTE TO SECOND EDITION

I WISH to call attention to the new Addenda (pp. cxxix ff.), in which I have endeavoured, so far as is possible, to bring Hittite questions up to date by insertion of references to new discussions which were not available when the First Edition was published.

C. F. B.

Christmas 1919.

CONTENTS

	PAGE
ADDENDA,	xiii
PRINCIPAL ABBREVIATIONS EMPLOYED,	xxii
TRANSLITERATION OF SEMITIC WORDS,	xxxii
 INTRODUCTION:—	
§ 1. TITLE, SCOPE, AND PLACE IN THE CANON,	xxxiii
§ 2. STRUCTURE,	xxxiv
§ 3. THE OLD NARRATIVES,	xxxvii
§ 4. THE EDITORS,	xli
§ 5. CHRONOLOGY,	1
§ 6. EXTERNAL INFORMATION BEARING ON THE PERIOD OF JUDGES,	lv
§ 7. THE PERMANENT RELIGIOUS VALUE OF JUDGES,	cxviii
§ 8. HEBREW TEXT AND ANCIENT VERSIONS,	cxxii
 TRANSLATION AND COMMENTARY,	1
 ADDITIONAL NOTES:—	
EXTERNAL EVIDENCE FOR THE USE OF THE TERMS ‘CANA’AN’ AND ‘THE LAND OF THE AMORITE,’	41
ŞEDEK AS A DIVINE NAME,	41
THE MEANING OF THE NAME KIRIATH-ARBA’,	43
THE CONQUEST OF THE NEGEE,	44
THE ORIGINAL FORM OF J’S ACCOUNT OF THE SETTLEMENT OF THE TRIBES OF ISRAEL IN CANA’AN,	47
A DETAILED EXAMINATION OF THE RHYTHM OF THE SONG OF DEBORAH,	158
THE CLIMACTIC PARALLELISM OF THE SONG OF DEBORAH,	169
THE LANGUAGE OF THE SONG OF DEBORAH,	171
YAHWEH OR YAHU ORIGINALLY AN AMORITE DEITY,	243

	PAGE
EARLY IDENTIFICATION OF YAHWEH WITH THE MOON-GOD,	249
THE USE OF WRITING AMONG THE ISRAELITES AT THE TIME OF THE JUDGES,	253
HUMAN SACRIFICE AMONG THE ISRAELITES,	329
THE WOMEN'S FESTIVAL OF JUDGES II ⁴⁰ ,	332
THE MYTHICAL ELEMENTS IN THE STORY OF SAMSON,	391
THE ORIGIN OF THE LEVITES,	436
DESCRIPTION OF THE PLATES,	495
NOTE ON THE MAPS OF PALESTINE,	498
INDICES :—	
I. GENERAL INDEX,	503
II. INDEX OF GRAMMATICAL AND PHILOLOGICAL OBSERVA- TIONS,	520
III. INDEX OF FOREIGN TERMS :—	
HEBREW (INCLUDING CANA'ANITE),	522
BABYLONIAN AND ASSYRIAN (INCLUDING SUMERIAN),	524
ARAMAIC (INCLUDING SYRIAC),	525
ARABIC,	526
GREEK,	527
LATIN,	527
IV. INDEX OF PASSAGES FROM OTHER BOOKS DISCUSSED,	527
MAPS :—	
WESTERN ASIA IN THE SECOND MILLENNIUM B.C.,	<i>Frontispiece</i>
THE DISTRICT ROUND GIBE'AH,	<i>to face p. 465</i>
PALESTINE (<i>five Maps</i>),	<i>End of Volume</i>
PLATES,	" "

ADDENDA

p. 17. *Ch.* 1¹⁷. Against the identification of Şephath with Sebaita (Esbeita), cf. Lawrence in *PEF. Annual*, iii. (1914-15), p. 91, who points out that the site Esbeita cannot have existed before the Christian era.

p. 29. *Footnote* *. The disappearance of the *k* in אֶכְזִיב 'Akzib = ez-Zib is highly remarkable. Kampffmeyer (*ZDPV.* xv. p. 31) suggests that, as a first stage, *k* may have been weakened into *h* (as in Mikmash = modern Muḥmās) and then into *ʾ*, the first syllable being eventually treated as though it were the Ar. Article (cf. ed-Dāmiyyeh for 'Adam, er-Restân for Arethusa, etc.).

p. 62. *Note* on 'the Hittites . . . mount Lebanon.' Meyer, *IV.* pp. 332 ff., defends the *𐤇* text in Judg 3³, Josh. 11³, which places the Hivvites in the Lebanon district, and proposes to substitute *חֲרִי* 'Horites,' on the authority of *𐤇* in Gen. 34², Josh. 9⁷, passages which, as they stand in *𐤇*, place the Hivvites in central Cana'an (Shechem and Gib'eon). The introduction of the Horites into these latter passages is opposed by Kit., *GVI.*² i. p. 37, *n*¹, upon good grounds.

p. 69. *Footnote* on אטר. The common biliteral element DAR, ṬAR, etc., underlying a series of trilateral roots has been noted and further illustrated by Ball, *Semitic and Sumerian (Hilprecht Anniversary Volume, pp. 41 f.)*.

p. 88. *Ch.* 4⁷. The root-meaning of Heb. *nāḥal* is stated by BDB. to be unknown. It seems obvious that the root נחל must be allied to חלל in the sense 'to pierce,' and that *nāḥal* therefore properly denotes a *cutting* or *boring*: cf. especially Job 28⁴, if *nāḥal* is there rightly understood as meaning a *mine-shaft*. Other instances of allied פ"נ and ע doubled verbs (*i.e.* of the same biliteral differently trilateralized) are נטף 'to drip,' and New Heb. טפף whence טפה 'drop'; נסך 'to weave' and סנך 'to intertwine'; נפץ and פצץ 'to break in pieces'; נצה and צחה 'to shine, be brilliant'; נקב and קבב 'to curse.' Similarly, נפח and ע"ו 'to breathe'; נפץ 'to break in pieces,' and פוץ 'to be dispersed' (by breaking); נצץ and צוץ 'to shine, blossom'; נקר and קור 'to bore, dig.'

p. 95. Add to the list of authorities, P. Haupt, *Die Schlacht von Taanach*, pp. 193-225 of *Studien zur semit. Philol. u. Religionsgesch. Julius Wellhausen . . . gewidmet*, 1914. (He treats the text of Judg. 5 with the greatest freedom, subjecting it to a drastic rearrangement.)

p. 96. On the analogy to Hebrew poetry offered by the old Anglo-Saxon poetry, and by *Piers Ploughman*, cf. Gray, *Forms of Hebrew Poetry* (1915), pp. 128 ff.

p. 158. The extreme variation in the number of unstressed syllables which may accompany a stressed syllable in Hebrew poetry, according to our theory, is well illustrated by the passage from *Piers Ploughman* quoted by Gray, *Forms of Hebrew Poetry*, p. 130:—

‘On Good Friday I fynde | a felon was y-saved,
That had lyved al his life | with lesynges and with thefte ;
And for he bekned to the cros, | and to Christ shrof him,
He was sonner y-saved | than seint Johan the Baptist ;
And or Adam or Ysaye | or any of the prophetes,
That hadde y-leyn with Lucifer | many longe yeres,
A robbere was y-raunsoned | rather than thei alle,
Withouten any penaunce of purgatorie | to perpetual blisse.’

Here we find not merely $\simeq \simeq \simeq \simeq$ (‘and for he békned,’ ‘that hadde y-léyen’), but even $\simeq \simeq \simeq \simeq \simeq \simeq$ (‘withouten any pénaunce’). The resemblance is rather striking between the line

‘Withouten any pénaunce of púrgatorie | to perpétual blisse’

and ν^{9b} of the Song of Deborah,

hammithnaddabkím báám | barrakhú Yahwáh.

p. 210. *Ch. 7^{5.6}*. Mez, *ZATW*. xxi. (1901), pp. 198-200, notes the fact that Ar. *kará'a*, which is formally identical with Heb. *kārā'* ‘bend down’ (used in our passage in the description of one form of drinking), has the meaning ‘drink with the muzzle in the water,’ *i.e.* by sucking the water in, as is done by ruminants, and animals such as the horse and ass, in contrast to Ar. *walaḡa* ‘lap with the tongue’ (equivalent in meaning to Heb. *lāḡaḡ*), the method of drinking practised by the dog, as well as by the wolf and other beasts of prey. His conclusion is that ‘those that bent down (כרעו) upon their knees to drink water’ put their mouths into the water like cattle ; whereas the lappers (המלקקים) were those who flung the water into their mouths with their hands—this being (in his opinion) the nearest approach to lapping, the actual practice of which is impossible for a human being. These latter, he thinks, were chosen on account of this dog-like or wolf-like characteristic as betokening their fitness for the enterprise ; and he seeks to fortify this inference by quotation of two Ar. proverbs which compare a razzia with the licking of a wolf, *i.e.* in respect of its lightning-rapidity, as appears from another

proverb, 'more swiftly than a dog licks its nose.' Mez's arguments are reproduced, with additional remarks, by M^cPherson, *J.A.O.S.* xxii. (1901), pp. 70-75; and the two articles are cited as authoritative in Gesenius-Buhl, *Handwörterbuch*¹⁶ (1915) *s.v.* ברע. BDB., *s.v.* ברע, compares the Ar. verb, and offers (with a query) the suggestion that it may bear a derivative sense, the ground-meaning being 'kneel to drink.'

Objection may be made to the identification of Heb. *kāra'* in our passage with Ar. *karā'a* on several grounds.

1. The phrase אשר יכרע על ברכיו לשתות 'who bendeth down upon his knees to drink' is very different from the Ar. usage of *karā'a*, in which the verb is always followed by the prep. فی 'in'—'drink with the muzzle *in* the water, or, *in* a vessel' (cf. the Dictionaries of Freytag, Lane, Kazimirski). M^cPherson, who perceives this difficulty, thinks that אשר יכרע על ברכיו may be a later scribal expansion, אשר יכרע לשתות מים meaning 'who drinks putting his mouth to the water.' Such an English rendering would seem to require an original אשר ישקה פְּרָע, the Heb. sentence as given by M^cPherson meaning rather 'who puts his mouth in the water as regards drinking.' But, if כרע really has the meaning of the Ar. verb, לשתות is obviously redundant; whereas, on the other hand, the omission of במים, which is demanded on the analogy of the Ar. فی الماء, appears to be fatal to the theory. It cannot be doubted that the expression אשר יכרע על ברכיו is original, and has the meaning which it possesses elsewhere (1 Kgs. 8³⁴, 2 Kgs. 1¹³, Ezr. 9⁵).

2. The philological analogue of Heb. *kāra'* appears to be the Ar. *rakā'a* (as rightly recognized by Ges., *Thes.*, Ges.-Buhl, though not by BDB.), with transposition of radicals (cf., probably, the converse transposition in Ar. *ḡarā'a*, which is surely to be compared with Heb. *rāḡā'*, and not with *ḡarā'* as in BDB.). If, however, *karā'a* bears a derived sense 'kneel to drink,' we are faced by the phenomenon that the root with more primitive meaning has undergone transposition, whereas the presumably later derived form has not. Again, if the point of connexion between Heb. *kāra'* and Ar. *karā'a* is that the latter properly means 'kneel to drink' (BDB.), such a posture is true of the camel only, but not of the ox, sheep, goat, horse, ass, or of the wild ruminants. We must suppose, therefore, that *karā'a* got its specialized sense through observation of the camel only; but of this there seems to be no trace in Ar. Such a sense as 'bow the head *or* neck' (true for the other animals mentioned) would be expressed by another verb.

3. Mez's theory, in postulating that Heb. *kāra'* denotes the putting the mouth into the water, is obliged to assume that the lappers, in contrast, put their hands to their mouths (retaining, therefore,

כִּירָם אַ פִּיהֶם in the position which it occupies in 𐤁). But no amount of special pleading can make it appear that the scooping of water into the mouth with the hand has any resemblance to lapping 'as the dog lappeth.'

If these arguments are sound, the resemblance between Heb. *kāra'* and Ar. *karū'a* is probably merely fortuitous; and the comparison with *karū'a* should be expunged from Heb. Lexicons, or at any rate marked as highly precarious.

p. 214. *Note on ch. 7*¹⁵. In explaining Heb. *šibhrô*, 'its elucidation,' by comparison of Bab. *šabrû*, *šabrûtu*, it is of course not intended to affirm that *šēbher* is actually the formal equivalent of *šabrû*, i.e. a Shaph'ēl from a so-called trilateral form (כרה), since such a form would naturally exhibit a ל"ה nominal termination. What is affirmed is that there are in Heb. originally-biliteral forms which have been trilateralized by prefixed שׁ in the sense 'make,' which is the preformative employed in this sense in the Shaph'ēl. This has already been pointed out by Ball in his article *Semitic and Sumerian* in the *Hilprecht Anniversary Volume*, pp. 54 f. שִׁבֵּר 'to make the action of seeing' is precisely on the analogy of יִשְׁכֵּב 'to make the action of reclining,' from root KAB=כפ in כָּפַף 'to bend, bow down' (cf. also נָכַב, נָכַף); יִשְׁקֵל 'to weigh,' properly 'to make light' (cf. קָלַל), i.e. 'to heave, lift.' We may add the ordinary Heb. שִׁבֵּר (not included in Ball's list) 'to make the action of breaking' (cf. Ar. *bara* 'to fashion by cutting,' Heb. פָּרַר, Bab. *parāru* 'to break or shatter').

The distinction between שִׁבֵּר, properly 'make + see' or 'make + bright' (cf. בָּרַר 'to make bright,' Bab. *barāru* 'to be bright'; שִׁפֵּר 'to make bright,' or, internally, 'to show brightness'),* and the ordinary Heb. שָׁבַר, properly 'make + break,' is the same as exists between Bab. *ka-pāru* 'to be bright or brighten,' Piel *kuppuru*, Heb. כִּפֵּף properly 'to make bright, purge,' so 'to atone' (cf. the evidence adduced by the present writer in *ET*. xxii. pp. 325 ff.), and Bab. *ka-pāru* 'to cut.' The identity in form combined with diversity in meaning is explained by the fact that there is a Sumerian BAR, PAR with the idea of 'brightness' (standing in syllabaries for *barû* 'to see,' *barāru* 'to shine,' *namāru* 'to be bright,' *nūru* 'light,' etc.), and another Sumerian BAR, PAR which is distinct (at least as known to us) in meaning, and carries the idea of 'breaking, splitting,' etc. (standing in syllabaries as the equivalent of *parāru* 'to break,' *kapāru* 'to cut,' *palāku* 'to divide,' *hasāsu* 'to cogitate—animam dividere,' *parāsu* 'to decide,' etc.).

* For the connexion between *seeing* and *brightness*, cf. Heb. אָרַר 'to be bright'. = Bab. *amāru* 'to see' (a relation in form like that between Heb. נֹר Bab. *namāru*, both 'to shine'). When a man *sees clearly* again after faintness, his eyes are said to *become bright*: cf. 1 Sam. 14^{27,29}, Ps. 133³ (𐤁¹).

p. 221. Discussion of 1 Kgs. 4¹². The writer, having independently suggested that the words 'which is in proximity to Šarēthan' have been accidentally transposed and should properly refer to 'Abel-mēḥolah,' now notices that the same conjecture has been put forward with a query by Prof. Moore in *JBL*. xiii. (1894), p. 79, n⁹.

pp. 253 ff. Since the printing of *Addit. note* on 'The use of writing, etc.' there has appeared a valuable article by J. H. Breasted entitled *The Physical Processes of Writing in the Early Orient and their Relation to the Origin of the Alphabet*, in *AJSL*. xxxii. (July 1916), pp. 230-249. Breasted deals, on pp. 241 ff., with Assyrian Reliefs depicting scribes writing cuneiform on a clay tablet (cf. our *Addit. note*, p. 255), and he regards the second scribe, who is occasionally present, using pen, ink, and scroll, as an Aramaean (cf. our *Addit. note*, p. 256, footnote; *Description of the Plates*, p. 495).

p. 255. *Footnote* *. The form of the stylus used for writing cuneiform, and the method of using it, have been discussed by P. Zehnpufund, *Ueber babylonisch-assyrische Tafelschreibung*, in *Actes du 8^e Congrès International des Orientalistes tenu en 1889 à Stockholm et à Christiania* (1893), pp. 265-272; J. de Morgan, *Note sur Procédés techniques en Usage chez les Scribes babyloniens* in *Recueil de Travaux*, xxvii. (1905), pp. 240 f.; A. T. Clay, *Documents from the Temple Archives of Nippur* (1906), pp. 17-20; L. Messerschmidt, *Zur Technik des Tontafelschreibens* in *OLZ.* (1906), cols. 185-196, 304-312, 372-380. The fact that the wedges were made by impression merely, without drawing, which is emphasized by the present writer, is confirmed by Clay: 'To produce long horizontal wedges for the purpose of filling out lines, as was frequently done, it is not necessary to draw the stylus over the soft clay. By simply lowering the handle it is possible to make a wedge as long as the stylus' (p. 20).

p. 332. *Addendum to Additional Note on the Women's Festival of Judg.* 11⁴⁰. The conclusion that the myth of Demeter and Kore is to be connected, in its origin, with the myth of Ištar and Tammuz may be substantiated by the following facts:—

(1) The brilliant discovery of Ball (*PSBA*. xvi., 1894, pp. 195 ff.) that the Sumerian name of Tammuz, DUMU.ZI* (Bab. *Dū'ūzu*, *Dūzu* ‡) is identical with the Turkish *dōmūz* 'pig,' and that there is thus an 'original identity of the god with the wild boar that slays him in the developed legend,' is confirmed, quite independently and along

* Usually explained to mean 'Son of life,' or as an abbreviation of DUMU.-ZI.ABZU, 'True son of the deep water.' It is possible that one or the other of these meanings may have been read into the name after its original signification had been forgotten.

‡ On the evolution of the name-forms in Sumerian and Semitic, cf. Zimmern, *Der Bab. Gott Tamūz*, pp. 703 f.

totally different lines, by Robertson Smith's scarcely less brilliant conjecture that the pig was originally regarded as the theriomorphic representative of the deity. 'My own belief,' says this latter writer, 'is that the piacular sacrifice of swine at Cyprus on April 2 represents the death of the god himself, not an act of vengeance for his death. . . . Adonis, in short, is the Swine-god, and in this, as in many other cases, the sacred victim has been changed by false interpretation into the enemy of the god' (*Religion of the Semites*,¹ p. 392, *n*¹; *id.*² p. 411, *n*¹). Among the Greeks 'the pig is the victim specially consecrated to the powers of the lower world' (Farnell, *The Cults of the Greek States*, iii. p. 32). The ceremonial of the Thesmophoria, celebrated by women in the cult of Demeter and Persephone, is especially noteworthy in this connexion. Lucian's scholiast states that 'At the Thesmophoria it is the fashion to throw living pigs into the underground sanctuaries . . . and certain women called ἀντητρίαι descend and bring up the decaying remnants and place them on the altars: and people believe that the man who takes (part of them) and mixes them up with his grain for sowing will have an abundant harvest. And they say that there are serpents down below about the vaults, which eat the greater part of the food thrown down' (quoted from Farnell, *op. cit.* p. 89; cf. also Miss Harrison, *Prolegomena to the Study of Greek Religion*,² ch. iv.). Here it is questioned whether the swine were regarded merely as gifts to the earth-goddess, or as incarnations of the divinities themselves. The former view is taken by Frazer (*Spirits of the Corn*, ii. pp. 16 ff.); while Farnell regards the evidence as insufficient to establish it, and supposes that 'as these goddesses may be supposed to have partaken of the swine's flesh that was thrown down to them, the remnant would be regarded as charged with part of their divinity, and would be valuable objects to show (? strew) over the fields. But no Greek legend or ritual reveals any sense of the identity between Demeter and the pig' (*op. cit.* pp. 90 f.). We may remark, however, that, at any rate from the Semitic side, the method of sacrifice—the *throwing down* of the *living* animal—is wholly in favour of the theriomorphic conception. The slaying of the victim by a method which avoided bloodshed, or which might be interpreted as an act of self-immolation, suggests that it was a totem-animal too sacred to be slaughtered by any individual worshipper (cf. Robertson Smith, *Religion of the Semites*,² pp. 418 ff.).* The term μέγαρον, or μίγαρον, which is used to describe the underground caves (τὰ μέγαρα) into which the pigs were thrown, and also the adytum of the temple at Delphi where the oracular responses were

* The reference in Isa. 65⁴, 66¹⁷ to the eating of swine's flesh by the renegade Palestinian Jews or Samaritans, probably in early post-exilic times, reprobates the practice not simply because the animal was regarded as unclean upon arbitrary or sanitary grounds, but as a definite act of idolatry; and there can be little doubt that the allusion is to the ceremonial partaking of the flesh of the totem-animal in Tammuz-ritual. Cf. Cheyne, *Prophecies of Isaiah*, *ad loc.*

received, seems to be distinct from the Homeric term μέγαρον, which denotes a large chamber, hall, or palace, and has been supposed with considerable probability to be the Phoen. and Heb. *mē'ârā*, Ar. *muğ'âra*, 'cave,' with γ for rough ʿ in transliteration, as in Γαζα = חֲזַי, etc.*; and, if this is so, the Semitic connexions of the rites of which we are speaking receive further substantiation.

(2) One of the titles most frequently applied to Tammuz in Sumerian dirges is AMA.UŠUMGAL.ANNA. This means lit. 'Mother, great serpent, heaven,' i.e. 'the divine Mother who is the great serpent.'† Tammuz is also occasionally equated with the goddess KA.DI. Now KA.DI (as has been noted by Jensen, *KB.* vi. 1, p. 565) is stated in iv.² R. 30, No. 2, Obv. 18 and Rev. 6 to be a deity of the Underworld; according to v. R. 31, 30 she is identical with the divine Serpent (*ilu šīru*); from a text published by Scheil (*Textes Élam.-Sémit.*, 1^{re} série, p. 91, l. 23) we gather that the Serpent is the 'child' (*mīru*), or, it may be, the 'messenger' (*šīpru*) of KA.DI; while, according to v. R. 46, 29, the constellation of the Serpent represents the goddess Ereškigal, the counterpart of the Greek Persephone as mistress of the Underworld. For the Greeks also, however, the serpent is the incarnation of the earth-goddess Ge, the prototype of Demeter (cf. Farnell, *op. cit.* pp. 9 f.); and, as is clear from the passage relating to the Thesmophoria which we have already quoted, 'this animal that was once the incarnation of the earth-spirit remains the familiar representative of the chthonian goddesses of the Olympian period' (Farnell, *op. cit.* p. 91). Further comment is needless.

p. 340. Note on Šor'ah. The city *Ša-ar-ḥa*, mentioned in the T.A. Letters, together with *A-ia-lu-na*, i.e. Aijalon (Kn. 273), can hardly be other than the Biblical Šor'ah. It may be questioned, in view of the concurrence of the vocalization of *Ša-ar-ḥa* with the modern Šar'ah, whether the Biblical form ought not likewise to be vocalized not שָׂרָה but שָׂרָח. Cf. Σαπαα.

p. 351. Note on *ch.* 14⁶. To the parallels adduced for the method employed by Samson in rending the lion, add the duplicated figure rending a lion on the seal-cylinder impression figured in *Revue d'Assyriologie*, xxx. (1916), Plate I, fig. 6.

p. 359. Since the footnote dealing with the *Βουγγορία*-myth was written, there has appeared an article on the subject by A. E. Shipley in *Journal of Philology*, xxxiv. (1915), pp. 97-105.

p. 408. J. Halévy, *RÉJ.* xxi. (1890), pp. 207-217, treats the narrative

* Cf. Robertson Smith, *Religion of the Semites*,² p. 200; Lagarde, *Symmicta*, ii. p. 91; Muss-Arnolt, *Semitic Words in Greek and Latin*, in *Trans. of the American Philol. Assoc.* xxiii. (1892), p. 73; Boisacq, *Dict. Étym. de la Langue Grecque*, p. 617.

† Cf. Zimmern, *Der Bab. Gott Tamūz*. p. 7, n²; Langdon, *Tammuz and Ishtar*, pp. 114 ff.

of Judg. 17, 18 as a single document, and regards it as probably the work of a Judæan patriot and convinced partisan of the Temple at Jerusalem, who aimed at defaming the rival Israelite sanctuaries of Bethel (Micah's temple) and Dan by imputing to them a discreditable origin—both of them owed their origin to a theft; whereas the site of the Temple at Jerusalem was honestly purchased by David at a high price (2 Sam. 24²⁷). Halévy's arguments are ingenious but not convincing.

J. A. Bewer (*The Composition of Judges*, Chaps. 17, 18, in *AJSL*. xxix. (1913-14), pp. 261-283) attacks the critical theories of compilation or of interpolation in this narrative, maintaining that 'the story is a unity throughout with very few redactional touches (17⁶, 18^{1a,b,β}, and possibly 18^{20a,β-11}). His arguments do not lead the present editor to modify his conclusions, as expressed in pp. 442 ff., in any respect.

The credit must, however, be given to Bewer of recognizing the Levite's name in **וְהוּא נֵר שֵׁם** of 17⁷, which he emends **וְהוּא בֶן-גֵּרְשֹׁם** 'and he was a son of Gershom'—thus anticipating the suggestion made independently by the present writer in his *note ad loc.* Bewer also favours the emendation **הָאֲרֹן** for **הָאֲרֹץ**, which has been adopted in 18³⁹.

p. 430. *Footnote* † on *Nephtoah* = *Liftâ*. Another instance of the change of *n* to *l* in a modern Ar. name as compared with its ancient equivalent is seen in *Shunem* = *Sôlem*. On the loss of the final *h* after a long vowel cf. *Kampffmeyer*, *ZDPV*. xv. p. 26, who cites the similar disappearance of the *ע* in **אִשְׁתָּמָה** (Josh. 13⁶⁰) by the side of the normal **אִשְׁתָּמַע**.

p. 442. *Chs.* 19¹⁻²¹²³. To the authorities named add J. A. Bewer, *The Composition of Judges*, Chap. 19, in *AJSL*. xxx. (1914-15), pp. 81-93; *The Composition of Judges* 20, 21, *id.* pp. 149-165. The narrative is regarded as 'derived from one old, in the main reliable, source, which was worked over by a late theocratic editor. It is not improbable that a still later annotator, imbued with the same spirit as the editor, inserted a few characteristic interpolations.'

p. 462. *Ch.* 19⁹ *note* on 'the day hath waned, etc.' The connexion of Heb. **רָבָה** with Bab. *rabû* or *rapû* 'to sink' (of the sun setting) has been affirmed (since the printing of our note) by Haupt in *AJSL*. xxxiii. (Oct. 1916), p. 48. Haupt also connects *r^hphû'im* with *rapû* as meaning 'those who have "sunk" into their unseen abode' (as is done by the present writer in *note* on 'Teraphim,' p. 421, after the suggestion of Ball), though he denies connexion between *r^hphû'im* and *Terāphîm*. Since Haupt makes no reference to Ball's remarks in *Proc. Brit. Acad.* vii. p. 16 (a paper read before the British Academy on June 3, 1915, and published shortly afterwards), we must assume that the two scholars have independently reached similar conclusions.

p. 486. *Ch.* 20⁴⁵. *Note* on 'the crag of Rimmon.' The ordinary identification with Rammôn, three and a half miles east of Bethel, is opposed by W. F. Birch (*PEF. Qy. St.*, 1879, pp. 127-129), who makes a strong point of the use of *sēla'* 'crag' or 'cliff' as denoting 'a rock more or less perpendicular' (cf. 2 Chr. 25¹², Jer. 51²⁵, Ps. 141⁶). He states that there is no such cliff at Rammôn, which Stanley (*Sinai and Palestine*, p. 214) describes as 'a white chalky height,' and Rob. (*BR.*³ i. p. 440) as 'a conical chalky hill'; and maintains that this want is a fatal defect in the identification of this site with 'the crag of Rimmon.' All that is left, therefore, in favour of the identification is the identity of name: but modern place-names indicating the presence of a pomegranate tree (*Rummâneh*) or group of such trees (*Rummân*), happen to be extremely common in Palestine (the present writer has counted eighteen such in *SWP. Great Map*); thus by itself identity of name argues nothing.

The claims of Rammôn to be the site mentioned in our narrative were investigated by Finn (*Byeways in Palestine*, 1868, pp. 205 ff.), who visited the spot in order to inquire for a cavern which might be capable of containing six hundred men for four months. He saw four (not large) caverns, and was told of two others; and his conclusion was that 'all the refugees might sleep in these places if there was no village at the time, which seems probable.' On Finn's return from Rammôn, the guide told him of a vast cavern in the Wâdy Suwênîṭ capable of holding many hundred men, near which there is a watercourse half-way down the precipice (cf. p. 208). This cave, which is known as Muġâret el-Ġa'y, has been carefully investigated and described by H. B. Rawnsley (*PEF. Qy. St.*, 1879, pp. 118-126). It occupies a precipitous position on the south-west side of the Wâdy Suwênîṭ, and is near a spring which affords an adequate supply of water. There is a current tradition in Ġeba' that the cave will hold six hundred men, and the main entrance-cave is said to afford shelter for sixteen flocks of one hundred sheep each. Rawnsley thought that six hundred men might hide there in case of emergency; while three hundred could find ample lodging.

This is the site which Birch (in the article above mentioned) advocates as the real 'crag of Rimmon.' If he is correct, we have an explanation of the question raised by *Ch.* 20⁴³, why the pursuit of the Benjaminites ceased when they had reached a point to the east of Geba', viz. the fact that at this point they would disappear over the side of the Wâdy Suwênîṭ, and reach their refuge. It certainly seems improbable that, when the fugitives could reach such a stronghold as this at a comparatively short distance (four or five miles) from Gibe'ah, and were at any rate in its immediate neighbourhood when they came 'east of Geba'', they should have travelled double the distance in order to reach Rammôn, which can in no way be compared as a defensive position.

PRINCIPAL ABBREVIATIONS EMPLOYED

I. TEXTS AND VERSIONS

- ℌ** . . . The Hebrew consonantal text, as represented by all MSS. and printed editions.
ℌ̄ . . . The same as supplied with vowels and accents by the Massoretes. Ordinarily, **ℌ** represents the Massoretic text, unless the reading in question depends upon vowels or accents, when **ℌ̄** is employed.
 Variation in reading between **ℌ** and **ℌ̄** is represented in the usual way, viz. by
K^t . . . *K^thībḥ*, the 'written,' i.e. consonantal, text.
K^r . . . The 'read' text, i.e. the emendation of the Massoretes.
℣ . . . The Greek (Septuagint) version (ed. Swete, 1887). Different MSS. are represented by **℣^A** (Alexandrinus, edd. Brooke and M^cLean, 1897); **℣^B** (Vaticanus), etc. **℣^L**=the recension of Lucian as edited by Lagarde (cf. p. cxxvi.).
Ἀ. . . . The Greek version of Aquila;
Σ. . . . " " Symmachus;
Θ. . . . " " Theodotion;
 cited from Field, *Origenis Hexaplorum quae supersunt* (1875).
ℒ . . . The Old Latin (pre-Hieronymian) version, fragments of which have been collected and edited by Sabatier (*Biblorum . . . Latinae Versiones*, vol. i. 1751), and Vercellone (*Variae Lectiones Vulg. Lat. Bibl.*, vol. ii. 1864). **ℒ^L**=Codex Lugdunensis (ed. Ul. Robert, 1881-1900), as cited by Kit. *BH*.
ס^b . . . The Syro-hexaplar version (ed. Lagarde, *Bibliothecae Syriacae*, 1892).
ס^p . . . The Syriac (Peshittā) version.
ת . . . The Targum of Jonathan on the Prophets (ed. Lagarde, *Prophetæ Chaldaice*, 1872; Praetorius, *Das Targum zum Buch der Richter*, 1900). This Targum is sometimes cited as **ת^J**. **ת^O**=the Targum of Onkelos on the Pentateuch.

℣	.	The Latin version of Jerome (Vulgate).
Ar.	.	The Arabic version (based on ℣ ^r).
Copt.	.	The Coptic version.
A.V.	.	The Authorized version.
R.V.	.	The Revised version.
O.T.	.	Old Testament.

2. SOURCES.

D	.	The Deuteronomist.
D ²	.	A later hand influenced by the former.
E	.	The Elohist narrative in the Hexateuch, Judg., and 1 Sam.
E ²	.	Later work by a member (<i>or</i> members) of the Elohist school.
H	.	The Law of Holiness in Leviticus.
J	.	The Jehovistic (<i>or</i> Yahwistic) narrative in the Hexateuch, Judg. and 1 Sam.
JE	.	The combined narrative of J and E—a symbol used when it is not possible, or not necessary, to distinguish the sources.
R ^D	.	The Deuteronomic redactors of Kgs. and of JE in Josh.
R ^{E2}	.	Redactor of the school of E ² , the principal editor of Judg. (cf. pp. xli ff.).
R ^{JE}	.	Redactor of J and E in the Hexateuch, Judg., and 1 Sam.
R ^P	.	Redactors of the Priestly school (influenced by the Hexateuchal document P) of Judg. and Kgs.
P	.	The Priestly document in the Hexateuch.
X	.	An unknown source in Judg. 20, 21 (cf. p. 457 f.).

3. AUTHORITIES.

[See also the literature cited at the head of the various sections of the Commentary. The works there mentioned are cited, within the section to which they refer, by the authors' names only.]

AJSL.—*The American Journal of Semitic Languages and Literatures* (vols i.-xi., entitled *Hebraica*, 1884-95).

AJTh.—*American Journal of Theology* (1897 ff.).

Bach.—J. BACHMANN, *Das Buch der Richter* (1868).

Vol. i. on chs. 1-5 is all that ever appeared.

Baethgen, *Beiträge*.—F. BAETHGEN, *Beiträge zur Semitischen Religionsgeschichte* (1888).

BDB.—F. BROWN, S. R. DRIVER, and C. A. BRIGGS, *A Hebrew and English Lexicon of the Old Testament* (1891-1906).

Ber.—E. BERTHEAU, *Das Buch der Richter und Ruth* (2nd ed., 1883): *Kurzgef. Exegest. Handbuch zum A.T.*

- Black—J. S. BLACK, *The Book of Judges* (1892): *The Smaller Cambridge Bible for Schools*. Containing suggestions by W. Robertson Smith (RSm).
- Bochart, *Hierozoicon*.—S. BOCHARTUS, *Hierozoicon; sive Bipertitum Opus de Animalibus Sacrae Scripturae*, cum notis E. F. C. Rosenmüller (1793-6).
- Böhl, *KH*.—F. BÖHL, *Kanaanäer und Hebräer: Untersuchungen zur Vorgeschichte des Volkstums und der Religion Israels auf dem Boden Kanaans* (1911).
- Br.—R. E. BRÜNNOW, *A Classified List of all Simple and Compound Cuneiform Ideograms* (1887-9).
- Breasted, *AR*.—J. H. BREASTED, *Ancient Records of Egypt* (5 vols., 1906-7).
- *Hist. Eg.*—*A History of Egypt* (1906).
- Bu., [*Comm.*].—K. BUDDE, *Das Buch der Richter* (1897): *Kurzer Hand-Commentar zum A.T.* herausg. von K. Marti.
- *RS*.—*Die Bücher Richter und Samuel, ihre Quellen und ihr Aufbau* (1890).
- Buhl, *Geogr.*—F. BUHL, *Geographie des Alten Palästina* (1896).
- Burch.—M. BURCHARDT, *Die Altkanaanäischen Fremdworte und Eigennamen in Aegyptischen* (1909-10).
- Camb. Bib.*—*The Cambridge Bible for Schools and Colleges*.
- CH.—J. ESTLIN CARPENTER and G. HARFORD-BATTERSBY, *The Hexateuch according to the Revised Version . . . with Introduction, Notes, etc.* (1900).
- CH.^J, CH.^E, etc., refer to the lists of Words and Phrases characteristic of J, E, etc., as contained in vol. i. pp. 185 ff. In such references the number following is the number in the list.
- CIS*.—*Corpus Inscriptionum Semiticarum* (1881 ff.).
- Le Clerc—J. CLERICUS, *Veteris Testamenti Libri Historici* (1708).
- Cooke—G. A. COOKE, *The Book of Judges* (1913): *Cambridge Bible*. Often cited as Cooke, *Comm.* in the notes on *chs.* 4 and 5, when supplementary to, or divergent from, the monograph noticed on p. 78.
- *NSI*.—*A Text-book of North-Semitic Inscriptions* (1903).
- Cor.—C. CORNILL, *Introduction to the Canonical Books of the Old Testament*, trans. by G. H. Box (1907).
- COT*.—E. SCHRADER, *The Cuneiform Inscriptions and the Old Testament*, 2nd ed., trans. by O. C. Whitehouse (1885-88).
- CT*.—*Cuneiform Texts from Babylonian Tablets, etc., in the British Museum* (1896 ff.).
- Davidson, *Syntax*.—A. B. DAVIDSON, *Hebrew Syntax* (1894).
- DB*.—*A Dictionary of the Bible*, ed. by J. Hastings (1898-1902).

- Delitzsch, *Paradies*.—FRIED. DELITZSCH, *Wo lag das Paradies? Eine Biblisch-Assyriologische Studie* (1881).
- *Prolegomena*.—*Prolegomena eines Neuen Hebr.-Aram. Wörterbuchs zum AT.* (1886).
- *HWB*.—*Assyrisches Handwörterbuch* (1896).
- Doorn.—A. VAN DOORNINCK, *Bijdrage tot de Tekstkritiek van Richteren*, i.-xvi. (1879).
- Dozy—R. DOZY, *Supplément aux Dictionnaires Arabes* (1881).
- Driver, *Tenses*.³—S. R. DRIVER, *A Treatise on the Use of the Hebrew Tenses* (3rd ed., 1892).
- *LOT*.⁹—*An Introduction to the Literature of the Old Testament* (9th ed., 1914).
- *NHTS*.²—*Notes on the Hebrew Text and the Topography of the Books of Samuel* (2nd ed., 1913).
- *Schweich Lectures*.—*Modern Research as illustrating the Bible (Schweich Lectures, 1908).*
- EB*.—*Encyclopaedia Biblica*, ed. by T. K. Cheyne and J. Sutherland Black (1899-1903).
- Ehr.—A. B. EHRLICH, *Randglossen zur Hebräischen Bibel* (vol. 3, 1910).
- ET*.—*Expository Times* (1889 ff.).
- Ew., *HI*.—H. EWALD, *The History of Israel* (Eng. trans. of vols. i.-v., 1869-74).
- *DAB*.—*Die Dichter des Alten Bundes* (2nd ed., 1854-67).
- Field, *Hex*.—F. FIELD, *Origenis Hexaplorum quae supersunt* (1875).
- Frankenberg—W. FRANKENBERG, *Die Composition des Deuteronom. Richterbuches (Richter ii. 6—xvi.) nebst einer Kritik von Richter xvii.-xxi.* (1895).
- Garstang, *Hittites*.—J. GARSTANG, *The Land of the Hittites* (1910).
- Ges., *Thes*.—W. GESENIUS, *Thesaurus Philologicus Criticus Ling. Hebr. et Chald. Veteris Testamenti* (1826-58).
- G.-K.—*Gesenius' Hebrew Grammar as edited and enlarged by the late E. Kautzsch*, 2nd English ed. revised in accordance with the 28th German ed. (1909) by A. E. Cowley (1910).
- Grä.—H. GRÄTZ, *Emendationes in Plerosque Sacrae Scripturae Veteris Testamenti Libros*, ed. G. Bacher: (fasc. tert. 1894).
- Gress.—H. GRESSMANN, *Die Anfänge Israels* (1912-14), Part I. 2 of *Die Schriften des Alten Testaments*, edited by various scholars.
- Hall, *NE*.—H. R. HALL, *The Ancient History of the Near East* (1913).
- Holzinger—H. HOLZINGER, *Richter 2⁶-16³¹ untersucht*, as quoted from the manuscript by Budde in his Commentary.
- Hommel, *AHT*.—F. HOMMEL, *The Ancient Hebrew Tradition as illustrated by the Monuments*, trans. by E. McClure and L. Crosslé (1897).

Hommel, *Grundriss*.—*Grundriss der Geographie und Geschichte des Allen Orients* (1904).

Houb.—C. F. HOUBIGANTIUS, *Notae Criticae in Universos Veteris Testamenti Libros* (1777).

HP.—R. HOLMES and J. PARSONS, *Vetus Testamentum Graecum cum Variis Lectionibus* (1798-1827).

ICC.—*The International Critical Commentary*.

JAOS.—*Journal of the American Oriental Society* (1851 ff.).

Jastrow, RBA.—M. JASTROW, jr., *Die Religion Babyloniens und Assyriens* (1905-12).

— RBBA.—*Aspects of Religious Belief and Practice in Babylonia and Assyria* (1911).

JBL.—*Journal of Biblical Literature and Exegesis* (1890 ff.).

Jensen, *Kosmologie*.—P. JENSEN, *Die Kosmologie der Babylonier* (1890).

Jos.—FLAVIUS JOSEPHUS (*Opera* ed. Niese, 1888-94).

— *Ant.*—*Antiquitates Judaicae*.

— *BJ.*—*De Bello Judaico*.

— *C.Ap.*—*Contra Apionem*.

JQR.—*Jewish Quarterly Review* (1888 ff.).

JTS.—*Journal of Theological Studies* (1900 ff.).

KAT.³—H. ZIMMERN and H. WINCKLER, *Die Keilinschriften und das Alte Testament* (1903).

Published as the 3rd ed. of E. Schrader's work which bears the same title (see under *COT.*), though really an entirely new work in plan and contents.

KB.—*Keilinschriftliche Bibliothek: Sammlung von Assyrischen und Babylonischen Texten in Umschrift und Übersetzung*, ed. E. Schrader in collaboration with various scholars (vols. i.-vi. 2 (1), 1889-1915).

Ke.—C. F. KEIL and F. DELITZSCH, *Biblical Commentary on the Old Testament*—vol. iv., *Joshua, Judges, Ruth*, ed. by Keil, trans. by J. Martin (1865).

Kennicott—B. KENNICOTT, *Vetus Testamentum Hebraicum cum Variis Lectionibus*, 2 vols. (1776-80).

Kent—C. F. KENT, *Narratives of the Beginnings of Hebrew History* (1904).

Kimchi—Rabbi DAVID KIMCHI (A.D. 1160-1235), *Commentary on Judges* as printed in Buxtorf's Rabbinic Bible.

King, *Hammurabi*.—L. W. KING, *Letters and Inscriptions of Hammurabi* (1898-1900).

— *Chron.*—*Chronicles concerning Early Babylonian Kings* (1907)

— *Sum. and Akk.*—*A History of Sumer and Akkad* (1910).

— *Bab.*—*A History of Babylon* (1915).

- Kit.—R. KITTEL, *Das Buch Richter* (*Die Heilige Schrift des A. T.*, ed. E. Kautzsch, 3rd ed. 1909, pp. 340-377).
- BH.—*Biblia Hebraica* (*Liber Judicum*, 1905).
- HH.—*A History of the Hebrews*, trans. by J. Taylor (1895-6).
- GVI.²—*Geschichte des Volkes Israel* (2nd ed., 1909-12).
- Kn[udtzon]—*Die el-Amarna-Tafeln, mit Einleitung und Erläuterungen*, herausgegeben von J. A. KNUDTZON: *Anmerkungen und Register*, bearbeitet von O. WEBER und E. EBELING (1907-15).
- König, *Syntax*.—F. E. KÖNIG, *Historisch-comparative Syntax der Hebräischen Sprache: Schlussheil des Historisch-kritischen Lehrgebäudes des Hebräischen* (1897).
- Kue., *Ond*.—A. KUENEN, *Historisch-kritisch Onderzoek naar het Ontstaan en de Verzameling van de Boeken des Ouden Verbonds* (2nd ed., 1885-89); *German Trans.* (1890-92).
- La.—M. J. LAGRANGE, *Le Livre des Juges* (1903).
- ÉAS.²—*Études sur les Religions Sémitiques* (2nd ed. 1905).
- Lane—E. W. LANE, *An Arabic-English Lexicon* (1863-93).
- Levi ben-Gershon—Rabbi LEVI the son of Gershon (A.D. 1288-1344), *Commentary on Judges* as printed in Buxtorf's *Rabbinic Bible*.
- Maspero, *Mêlées*.—G. MASPERO, *Les Premières Mêlées des Peuples* (Part II. of *Histoire Ancienne des Peuples de l'Orient Classique*), 1897.
- MDOG.—*Mitteilungen der Deutschen Orient-Gesellschaft* (1898 ff.).
- Meyer, *IN*.—E. MEYER, *Die Israeliten und ihre Nachbarstämme* (1906).
- GA.²—*Geschichte des Altertums* (2nd ed., vol. i., 1907-9).
- Mo., [Comm.].—G. F. MOORE, *A Critical and Exegetical Commentary on Judges* (*International Critical Commentary*), 2nd ed., 1903.
- SBOT.—*The Book of Judges; Critical Edition of the Hebrew Text*, 1900; *A New English Translation*, 1898 (*The Sacred Books of the Old Testament*).
- Müller, *AE*.—W. MAX MÜLLER, *Asien und Europa nach Altägyptischen Denkmälern* (1893).
- Muss-Arnolt, *Dict*.—W. MUSS-ARNOLT, *A Concise Dictionary of the Assyrian Language* (1894-1905).
- MVAG.—*Mitteilungen der Vorderasiatischen Gesellschaft* (1896 ff.).
- NHTK.—C. F. BURNEY, *Notes on the Hebrew Text of the Books of Kings* (1903).
- NHTS.²—See under Driver.
- No.—W. NOWACK, *Richter, Ruth u. Bücher Samuelis* (1902): *Handkommentar zum A. T.* herausg. von W. Nowack.
- Oet.—S. OETTLI, *Das Deuteronomium und die Bücher Josua und Richter* (1893): *Kurzgefasster Kommentar*, edd. H. Strack and O. Zöckler.

OLZ.—*Orientalistische Litteratur-Zeitung* (1878 ff.).

Oort—*Textus Hebraici Emendationes quibus in Vetere Testamento Neerlandice vertendo usi sunt A. Kuenen, I. Hooykaas, W. H. Koster, H. Oort*, ed. H. OORT (1900).

OS.—*Onomastica Sacra*, ed. P. de Lagarde (1887). This contains the 'Name-lists' of Eusebius and Jerome.

OTLAE.—A. JEREMIAS, *The Old Testament in the Light of the Ancient East*, trans. by C. L. Beaumont, ed. by C. H. W. Johns (1911).

PEF.—*Palestine Exploration Fund* (founded 1865).

— *Qy. St.*—*Quarterly Statement* (1869 ff.).

Petrie, *Hist. Eg.*—W. M. FLINDERS PETRIE, *A History of Egypt*. Vol. 1. *Dynasties i-xvi* (1894); Vol. 2. *Dynasties xvii-xviii* (1896); Vol. 3. *Dynasties xix-xxx* (1905).

PSBA.—*Proceedings of the Society of Biblical Archaeology* (1878 ff.).

i-v. R.—H. C. RAWLINSON, *The Cuneiform Inscriptions of Western Asia*, i-v. (1861-84, iv.², 1891).

Rashi—Rabbi SHELOMO YIṢḤAQI (A.D. 1040-1105), Commentary on Judges as printed in Buxtorf's Rabbinic Bible.

RB.—*Revue Biblique* (1892 ff.).

RÉJ.—*Revue des Études Juives* (1880 ff.).

Reuss—E. REUSS, *La Bible: Traduction Nouvelle avec Introductions et Commentaires* (1874).

Riehm, *HIVB.*²—E. K. RIEHM, *Handwörterbuch des Biblischen Alterthums* (2nd ed. 1893-4).

Rob., *BR.*³—E. ROBINSON, *Biblical Researches in Palestine and the Adjacent Regions: a Journal of Travels in the Years 1838 and 1852* (3rd ed., 1867).

Rogers, *CP.*—R. W. ROGERS, *Cuneiform Parallels to the Old Testament* (1912).

— *HBA.*⁶—*A History of Babylonia and Assyria* (6th ed., 1915).

Ros.—E. F. C. ROSENMÜLLER, *Scholia in Vetus Testamentum—Judices et Ruth* (1835).

de Rossi—J. B. DE ROSSI, *Variae Lectiones Veteris Testamenti*. 4 vols. (1784-8).

RSm.—W. ROBERTSON SMITH, as cited by Black, *g.v.*

Sayce, *HCM.*—A. H. SAYCE, *The 'Higher Criticism' and the Verdict of the Monuments* (1894).

— *Archaeology.*—*The Archaeology of the Cuneiform Inscriptions* (1907).

SBOT.—*The Sacred Books of the Old Testament*, edited by various scholars, under the editorial direction of P. Haupt.

- Smith, *HG.*—G. A. SMITH, *The Historical Geography of the Holy Land* (13th ed., 1906).
- Smith, *DB.*²—*A Dictionary of the Bible*, edited by Sir W. Smith and J. M. Fuller (2nd ed. of vol. i., 1893).
- Stade, *GVI.*²—B. STADE, *Geschichte des Volkes Israel* (2nd ed., 1888-9).
- Stu.—G. L. STUDER, *Das Buch der Richter grammatisch und historisch erklärt* (2nd ed., 1842).
- SWP.*—*Survey of Western Palestine.*
- *Great Map.*—*Map of Western Palestine in 26 Sheets, from Survey conducted for the Palestine Exploration Fund by Lieutenants C. R. Conder and H. H. Kitchener, R.E., during the Years 1872-77. Scale One Inch to a Mile* (1897).
- *Name Lists.*—*Arabic and English Name Lists* to above (1881).
- *Mcm.*—*Memoirs* to above in 3 vols. (1881-3).
- T.A. Letters.—The letters in cuneiform discovered at Tell el-Amarna.
- TB.*—*Altorientalische Texte und Bilder zum Alten Testaments*, ed. H. Gressmann in collaboration with A. Ungnad and H. Ranke (1909).
- Thomson, *LB.*—W. M. THOMSON, *The Land and the Book* (ed. of 1861).
- Vincent, *Canaan.*—H. VINCENT, *Canaan d'après l'Exploration Récente* (1907).
- Wellh., *Comp.*³—J. WELLHAUSEN, *Die Composition des Hexateuchs und der Historischen Bücher des Alten Testaments* (3rd ed., 1899).
- *TBS.*—*Der Text der Bücher Samuelis* (1871).
- *Prolegomena.*—*Prolegomena to the History of Israel* (trans. by J. S. Black and A. Menzies, 1885).
- Westm. Comm.*—*Westminster Commentaries.*
- Winckler, *GI.*—H. WINCKLER, *Geschichte Israels* (1895-1900).
- *KT.*—*Keilinschriftliches Textbuch zum A.T.* (1892).
- *AF.*—*Altorientalische Forschungen* (1893-1906).
- When cited for the T.A. Letters the reference is to *KB.* vol. v.
- ZA.*—*Zeitschrift für Assyriologie und Verwandte Gebiete* (1886 ff.).
- ZATW.*—*Zeitschrift für die Alttestamentliche Wissenschaft* (1881 ff.).
- ZDMG.*—*Zeitschrift der Deutschen Morgenländischen Gesellschaft* (1846 ff.).
- ZDPV.*—*Zeitschrift des Deutschen Palästina-Vereins* (1878 ff.).

4. OTHER ABBREVIATIONS AND SIGNS.

Ar., . . .	Arabic.
Aram., . . .	Aramaic.
Assyr., . . .	Assyrian.
Bab., . . .	Babylonian.
Eg., . . .	Egyptian.
Heb., . . .	Hebrew.
New Heb., . . .	New Hebrew, the language of the Mishna, etc.
Syr., . . .	Syriac.
al., . . .	<i>et aliter</i> or <i>et alii</i> .
וְ . . .	וְנוֹמֵר 'and the rest'; used when a Heb. quotation is incomplete.
' . . .	Sign of abbreviation in Heb. words.

The sign † after a series of Biblical references means that all occurrences in the O.T. of the word or phrase in question have been cited.

Biblical references are given in accordance with the numeration of chapter and verse in the English versions. When this varies in the Hebrew, the variation is usually noted: thus, Hos. 14², 15³.

The first and second halves of a verse are specified as, e.g., τ^{1a} , τ^{1b} , the guide to such division being the Heb. accent *Athnah*, which halves the verse. When it is necessary to refer to quarter-verses, these are specified as, e.g., τ^{1a} , $\tau^{1a\beta}$, τ^{1b} , $\tau^{1b\beta}$, the dividing factor being usually the accent *Zākeph*, which commonly halves the *Athnah*- and *Silluk*-clauses.

In the translation of the Hebrew text the following signs are employed as indications of correction:—

Emendations are placed between ׀ ׀.

Additions are placed between < >.

Excisions are indicated by [].

Italics are used in the ordinary way to mark *emphasis*; and not, as in A.V., R.V., as an indication that the words so marked are not represented in the original.

A small superlinear figure attached to the title of a work (e.g. Driver, *Tenses*³) denotes the *edition* to which reference is made.

TRANSLITERATION OF SEMITIC WORDS

CONSONANTS.

ARABIC.

HEBREW AND ARAMAIC.

أ	'	ف	<i>f</i>
ب	<i>b</i>	ق	<i>k</i>
ت	<i>t</i>	ك	<i>k</i>
ث	<i>t̤</i>	ل	<i>l</i>
ج	<i>ǧ</i>	م	<i>m</i>
ح	<i>h</i>	ن	<i>n</i>
خ	<i>ħ</i>	ه	<i>h</i>
د	<i>d</i>	و	<i>u, w</i>
ذ	<i>d̤</i>	ي	<i>i, y</i>
ر	<i>r</i>		
ز	<i>z</i>		
س	<i>s</i>		
ش	<i>ʃ</i>		
ص	<i>s̥</i>		
ض	<i>ḍ</i>		
ط	<i>t̤</i>		
ظ	<i>ẓ</i>		
ع	'		
غ	<i>ǧ</i>		

א	'		
ב	<i>b,</i>	ב	<i>bh</i>
ג	<i>g,</i>	ג	<i>gh</i>
ד	<i>d,</i>	ד	<i>dh</i>
ה	<i>h</i>		
ו	<i>w, v</i>		
ז	<i>z</i>		
ח	<i>ħ</i>		
ט	<i>t̤</i>		
י	<i>y</i>		
כ	<i>k,</i>	כ	<i>kh</i>
ל	<i>l</i>		
מ	<i>m</i>		
נ	<i>n</i>		
ס	<i>s̥</i>		
ע	'		
פ	<i>p,</i>	פ	<i>ph</i>
צ	<i>ʒ</i>		
ק	<i>k̤</i>		
ר	<i>r</i>		
ש	<i>ʃ</i>		
ת	<i>t̤</i>	ת	<i>th</i>

BABYLONIAN.
 Non-gutturals
 as in Hebrew

VOWELS.

	<i>Long.</i>	<i>Short.</i>	<i>Half-vowels.</i>
Hebrew W. Aramaic	\bar{a} , $\bar{ā}$, \bar{e} , $\bar{ē}$, \bar{i} , \bar{o} , $\bar{ō}$, \bar{u}	a , e , i , o , u	\bar{a} , \bar{e} , \bar{o} or a, e, o
Syriac . . .	\bar{a} , \bar{i} , \bar{u}	a , e	
Arabic . . .	\bar{a} , \bar{i} , \bar{u}	a , i , u , and modifications to e and o where usual.	
Babylonian	\bar{a} , \bar{e} , \bar{i} , \bar{u}	a , e , i , u	

In Hebrew place- and personal names the familiar forms of A.V. and R.V. are usually retained ; except that **צ** is always represented by ζ and not z , certain letters are marked by diacritic points (thus **ח**= h , **ט**= t , **ס**= s , **פ**= k), and **צ** is regularly marked by ' , except where it already stands as g (*i.e.* $\dot{g} = \dot{c}$) through the influence of **צ**, as in **חָצָא**= $\Gamma a\zeta a$, \dot{G} aza). **א** is occasionally represented by ' . The divine name **יהוה** is regularly represented by Yahweh.

INTRODUCTION

§ 1. Title, Scope, and Place in the Canon.

THE title of the Book is in מִשְׁפָּטִים, *Šophetīm*, whence comes our English title 'Judges.' The principal versions render & KPITAI; *U Liber Judicum*, *Hebræice Sophetim*; *S* ^פ סֵפֶר הַמִּשְׁפָּטִים . סֵפֶר הַמִּשְׁפָּטִים 'The book of the Judges of the children of Israel, which is called in Hebrew *Šophetīm*.'

The title *Šophetīm* is doubtless derived from *ch.* 2¹⁶ ff., which is due to the main editor (R^{E2}; cf. § 4), who employs the term 'Judges,' not in the sense in which we are accustomed to use it in English of officials who *decide* legal cases and act as *arbitrators* between man and man, but with the meaning '*Indicators*,' or '*Deliverers*' from the power of foreign oppressors.* There exist, however, passages in the Book, not due to this editor, in which the term is used in the more general sense of 'Arbitrators' or 'Magistrates' (cf. further, on this distinction in usage, p. 1, *footnote*). In this latter sense, the Carthaginian title *sufes* (*suffes*), plur. *sufetes* (i.e. שֹׁפֵטִים, שֹׁפֵטִים), as cited by Livy and other Latin writers, has been aptly compared. On the occurrence of the term in Phœnician inscriptions, cf. Cooke, *NSI*, pp. 115 f.†

The Book of Judges deals with the period during which the tribes of Israel were still struggling to maintain their footing in Canaan, before they had attained such an amount of cohesion among themselves as entitled them to rank as a nation rather than as a collection of separate units, and enabled them to establish their independence against the foreign races by whom they were surrounded. During this period we repeatedly find one or more of the tribes falling under the foreign yoke for a time, until the uprising of some one of sufficient personality to revive and unite the

* In some passages Heb. *Môšîa'* 'Saviour' is used by the editor as an alternative title (cf. *ch.* 3^{9.15}); and we also find the verb *hōšîa'* 'to save' similarly used as a synonym of 'to judge.'

† Jensen (*Z.A.* iv., 1889, pp. 278 ff.) quotes evidence in proof that in Assy. *šāpītu* was used to denote the commander of a host. Cf. *KAT*,³ pp. 647, 650.

scattered energy of the clans, and thus to enable them to shake themselves free. Such leaders (the *Šōphētim*, 'Judges'), after the success of their efforts, seem generally to have continued to hold a position of authority which, though doubtless merely local and uninvested with the prerogatives of the kingship of later times, yet represents a stage of development preparatory to the monarchy; just as their partial success in uniting the tribes to take common action against the foe is a stage towards the later unity which made possible the ideal of a nation organically combined under the rule of one king.

Of the three divisions of the Hebrew Canon—the Law, the Prophets, and the *Kethūbhim*, 'Writings' (Hagiographa)—the Book of Judges finds its place among the Prophets. This second division is sub-divided into two parts, each of which is reckoned as containing four books—'the Former Prophets,' consisting of Joshua, Judges, Samuel, and Kings; and 'the Latter Prophets,' comprising Isaiah, Jeremiah, Ezekiel, and 'the Twelve.'

The justification of this inclusion of Judges among the Prophets is found, as in the case of the other books assigned to 'the Former Prophets,' in the fact that the mere compilation of an historical record was not the purpose with which the book was put into shape, but rather the inculcation of the religious truths which were to be deduced from Israel's past history. It is abundantly evident that the ancient narratives (for the most part) which form the basis of the history, and also—and especially—the editorial framework into which these older narratives have been fitted, are the work of the Prophetical schools or guilds of Israel which, in pre-exilic times, were the chief literary conservators of the records of national history. The lines along which the religious bearing of Israel's past history is worked out in Judges are indicated in the sections which follow.

§ 2. Structure.

The Book of Judges opens with a section extending from *ch.* 1¹ to 2⁵, which describes the settlement of the tribes of Israel in the promised land, and pictures this settlement as very gradual and partial, and as effected, in the main, through the independent efforts of individual tribes. The facts which are thus narrated are stated in *v.* 1 to have taken place 'after the death of Joshua'; but it is clear that the standpoint of *v.* 1 is not the standpoint of the main part of the narrative, which pictures the tribes as starting their movements from 'the City of Palms,' *i.e.* Jericho (*v.* 16), or from Gilgal in the near neighbourhood (2¹); *i.e.* from the position in which they were stationed after their first crossing of the Jordan, and which formed their headquarters during their invasion of the hill-country, as narrated in Josh. 4¹⁹ P, 9⁶, 10^{6.7.9.15} JE, 10⁴³,

14⁶ R^D. It is obvious, moreover, that the narrative of *ch.* 1 cannot be correlated with the narrative of the conquest of Canaan under Joshua, as this now stands in the Book of Josh.; since this latter pictures the conquest as the work of the tribes of Israel as a whole, and as much more complete and far-reaching than is pictured in Judg. 1. Clearly, therefore, Judg. 1¹ to 2⁵ cannot originally have stood as the proper sequel of the closing chapter of Josh., which pictures the death of Joshua as taking place subsequently to the dispersion and settlement of the tribes throughout the land of Canaan; but is out of place in its present connexion, and really offers another account of the original settlement in the land, in many respects different from that which is found in Josh. as that Book now stands.

Looking, however, at the next section of the Book, which runs from *ch.* 2⁶ to 3⁶, we seem at once to discern the true sequel to Josh. 24; this section opening, in *vv.* 6-9, with an actual repetition of the words of Josh. 24²⁸⁻³¹, with one slight variation in order. That these *vv.* 6-9 are not a later insertion from Josh., but stand in proper connexion with the narrative which immediately follows them in Judg. 2, requires no proof. While *v.* 6 reiterates the mention of Joshua's dismissal of the people to their homes after his final exhortation to them at Shechem, as narrated in Josh. 24^{1 ff.}, *v.* 7 states that they remained faithful to his injunctions during his lifetime, and the lives of the elders who survived him, and *vv.* 8, 9 give a summary account of his death and burial. The narrative is immediately taken up by *v.* 10, which states that, after the death of the surviving elders mentioned in *v.* 7, there arose a new generation that did not know Yahweh nor the work which He had done for Israel, and thus were guilty of defection from His service, as related in *vv.* 11 ff.

In these latter verses the narrator propounds his philosophy of Israel's history in general terms. We are told that defection from Yahweh and the worship of the deities of Canaan (the Ba'als and 'Ashtarts) led to divine punishment which took the form of deliverance into the hand of foreign oppressors; punishment was followed by repentance and appeal to Yahweh for deliverance; Yahweh thereupon raised up a 'Judge,' *i.e.* a saviour or vindicator (*cf.* §1), who effected deliverance by the help of Yahweh; but, when the Judge died, defection from Yahweh again ensued, and the same cycle of punishment, repentance, and deliverance was re-enacted.

If we examine the narratives which follow after this introductory section, forming the main body of the Book, we find that this 'pragmatic' scheme of history (as it has been styled),* which has been stated in general terms in the introduction 2^{11 ff.}, is applied

* The term 'pragmatic' is used as defined in *The Concise Oxford Dictionary of Current English*: 'treating facts of history with reference to their practical lessons.'

to particular cases as they occur, the striking phraseology of the general introduction being, for the most part, repeated practically *verbatim* in the introductions to particular narratives (cf. pp. 54 ff. of the *notes*). Of such a character are the introductions to the narratives of 'Othniel, 3⁷ ff., Ehud, 3¹² ff., Deborah and Barak, 4¹ ff., Gide'on, 6¹ ff., Jephthah, 10⁶ ff. (perhaps originally intended as an introduction to the judgeship of Samuel; cf. *note ad loc.*), and Samson, 13¹. Corresponding to these introductions to the narratives, we find that more or less stereotyped formulae are employed at their close, referring to the subjugation of the foreign oppressor, and the length of the period during which 'the land had rest': so, after the victories of 'Othniel, 3¹¹, Ehud, 3³⁰, Deborah and Barak, 4²³, 5^{31b}, Gide'on, 8²⁸. Elsewhere, as a variation, the length is given of the period during which the Judge 'judged Israel': so of Jephthah, 12^{7a}, Samson, 15²⁰, repeated in 16^{31b}, the so-called 'minor' Judges, 10^{2a.3}, 12^{8.11.14}; cf., in 1 Sam., 'Eli 4¹⁸, Samuel 7¹⁵.

It will readily be noticed that the religious pragmatism of the main introduction and the special headings is not characteristic of the histories as a whole. In these the religious motive, in so far as it is put forward, is of a much more ingenuous and primitive character. Yahweh commissions men to act as deliverers, and His Spirit incites them to deeds of valour; but, if we except certain special sections, such as 6⁷⁻¹⁰ and 10⁶⁻¹⁶ (this latter a much expanded form of the ordinary introduction to a narrative), we find that the conceptions of sin, punishment, and repentance, so far from being prominently brought forward, are altogether ignored and unmentioned. In the history of Samson, in particular, the conception of the hero as a divinely appointed deliverer of his people seems little suited to the narrative; since his actions, so far as his personal volition is concerned, are wholly dictated by his own wayward inclinations, and he does not in any way effect deliverance or even respite from the foreign yoke.

We observe also that, whereas the stereotyped introduction to the various narratives speaks as though the apostasy of Israel from time to time, and their ensuing punishment, were *national* and *general*, the actual illustrations adduced in the narratives themselves are, at any rate in most cases, merely *local*, some particular tribe or group of tribes falling temporarily under the dominion of a foreign oppressor, but Israel as a whole (*i.e.* the entity of twelve tribes, which is clearly intended by 'the children of Israel' of the introductory formula) being unaffected.

It is obvious, therefore, that the main narratives of the Judges and their exploits cannot emanate from the author who was responsible for the framework in which they are set, which enforces the lesson already sketched in a preliminary way in *chs.* 2⁶⁻³⁶, containing (as we have noticed above) the original introduction to the Book. Clearly, the main narratives represent older material, which

has been utilized by a later editor for the working out of the religious philosophy which he reads into Israel's past history.

The work of the editor who was responsible for the pragmatic introduction, 2⁶-3⁶, and the framework of the narratives following, extends no further than the history of Samson, the last of the Judges. The final narratives of the Book, viz. the story of Micah and the Danites, *chs.* 17, 18, and the story of the outrage at Gibe'ah with its consequences, *chs.* 19-21, though in the main of the same literary character as the other old narratives, do not serve to illustrate this editor's scheme as laid down in his general introduction, and altogether lack traces of his hand as seen in the stereotyped introductions and conclusions to the stories of the Judges. We must conclude, therefore, that these two stories, though derived ultimately from the same history-book (*or* books) as the other old narratives, were not embraced within the main editor's Book of Judges. There is reason for supposing that this editor also omitted, as alien to his purpose, the story of Abimelech, *ch.* 9 (substituting in its place the brief summary which is found in *ch.* 8²³⁻³⁵; cf. p. 266), and such exploits of Samson as are now related in *ch.* 16 (cf. p. 338). These stories must have been re-inserted into Judg. at a later period—very possibly by the editor who added the later Introduction to the Book which we now find in *chs.* 1¹-2⁵. This later editor appears also to have been responsible for the brief notices of the 'minor' Judges contained in 10¹⁻⁵, 12⁸⁻¹⁵ (the reasons for supposing that the 'minor' Judges did not belong to the main editor's scheme are given on pp. 289 f.). The notice of Shamgar, *ch.* 3³¹, seems to have been inserted at a still later period (cf. p. 76).

§ 3. The Old Narratives.

From examination of the old narratives which form the basis of the history of Judg. the fact at once emerges that the main editor is dependent, not upon a single source, but upon two main sources, sections from which have been pieced together without any thoroughgoing attempt to harmonize existing inconsistencies in detail; much as different documents have been combined into a single history in the Pentateuch and Josh., and in 1 Sam. The proof of this fact has been sufficiently established in the special Introductions to the various sections of the Book which follow in the Notes. The most noteworthy illustration is the history of Gide'on, *chs.* 6¹⁻⁸²⁸; but a similar combination of two different narratives may also be traced in the stories of Ehud, *ch.* 3⁷⁻³⁰, Abimelech, *ch.* 9, Jephthah, *chs.* 10¹⁷-12⁷, and (in the Appendix to Judges) in the narratives of *chs.* 17, 18, and 19-21.*

* The prose-history of Deborah and Barak, *ch.* 4, likewise exhibits combination with elements derived from another narrative, relating probably to different events. It is not unlikely, however, that this combination was effected when the story was still in the oral stage: cf. pp. 81 ff.

It is generally recognized that the main characteristics of the old narratives thus combined in Judges are similar to those of the old 'Prophetical' narrative which runs through the Pentateuch and Josh. (the Hexateuch); and which is formed, likewise, by combination of two main documents, one of which must be supposed to have emanated from the Kingdom of Judah, and probably took shape as a written document *cir.* B.C. 850 (the reign of King Jehoshaphat); while the other is doubtless the work of the prophetic schools of the Northern Kingdom, and should probably be dated, in the main, somewhat later, *i.e. cir.* B.C. 750 (the reign of king Jeroboam II. and the period of the writing prophets, 'Amos and Hosea'). The former of these two narratives, owing to its predilection for the divine name Jehovah or Yahweh, is commonly known as the Jehovistic or Yahwistic narrative, and cited under the symbol J; while the latter, which exhibits a preference for the divine title *Elohim* ('God'), is termed the Elohistie narrative, and is cited as E.*

Since J and E carry the history of Israel from the earliest times down to the death of Joshua, and were certainly not put into writing until some centuries after the latter event, there is no *a priori* reason why they should be supposed each to have terminated with the narrative of Joshua's death: but, on the contrary, when we find in Judg. and 1 Sam. a similar combination of two old narratives possessing much the same characteristics as J and E, the question is at once raised whether these narratives should not be regarded as the proper continuation of J and E in Josh.; J and E thus representing, in their original forms, continuous prophetic histories of the nation of Israel down to the foundation of the monarchy, if not further.† Observing, moreover, that the closing verses of Josh., *ch.* 24²⁸⁻³¹ E, are repeated practically *verbatim* in Judg. 2⁶⁻⁹, the point at which the main editor opens his history, and that these verses point both backwards and forwards—Israel served Yahweh in accordance with the injunctions of Joshua's speech, which is detailed at length in Josh. 24¹ ff. E, during the lifetimes of Joshua and the elders who survived him; but the setting of a period to this service immediately raises the question

* For the evidence upon which these approximate dates are assigned to J and E, cf. CH. I. pp. 107 f., 117 ff.

† The purpose of the present argument being merely to suggest that the old narratives of Judg. are essentially of a piece with J and E in the Hexateuch, we are not here concerned to inquire whether these same two narratives continue later than 1 Sam. 12, which forms the close of the history of the circumstances which led to the institution of the monarchy in Israel. 1 Sam. 1-12 stands in essential connexion with the history of Judg., and examination of the old narrative of Judg. cannot be carried out apart from some consideration of these earlier chapters of 1 Sam. With regard to 1 Sam. 13 ff. it will be sufficient here to remark that a similar combination of two narratives runs on to the end of the book; whereas 2 Sam., on the contrary, consists, in the main, of a single very early source narrating the court-history of David.

what happened *after* the elders were dead, which forms the subject of the book of Judg. as a whole (cf. the direct transition from Judg. 2⁶⁻⁹ to *v.*¹⁰, on which see p. 52)—we may fairly claim that the fact that the document E of the Hexateuch continues beyond the end of Josh., and provides material for the history of Judg., seems to be placed beyond the range of controversy.

A similar conclusion must be drawn with regard to the companion-document J. The fact is generally admitted that the old document which forms the basis of the later introduction to Judg. *chs.* 1¹⁻²⁵, is derived from J (cf. pp. 1 f., 47 ff.), and that the concluding portion of this old account of the settlement of the tribes of Israel in Canaan has been utilized by the main editor in his own introduction, *ch.* 2^{23a}, 3^{2a.5a.6} (cf. pp. 52, 55). These concluding verses, however, tell us that, as the result of the survival of some of the races of Canaan, 'the children of Israel dwelt in the midst of the Canaanites; and they took their daughters to themselves for wives, and their own daughters they gave to their sons; and they served their gods'; and this seems to indicate that some account of Israel's defection from Yahweh, and the consequences thereby entailed, must have followed in J. Since, therefore, the main editor knew and employed the J document thus far, the inference is that he also made use of its material for his subsequent history.

The fact that the main editor thus appears to have utilized both J and E in his introduction to Judg. does not, however, amount to a demonstration that the old narratives which follow must necessarily be derived from the same documents. Such a conclusion can only be based upon detailed examination of each separate story, and this has been attempted in the Introductions prefixed to each section of the book in the Notes. It may be freely acknowledged that the evidence which can be adduced in proof of it is not of equal cogency throughout. Close connexion with J is undeniable in 6¹¹⁻²⁴ (p. 177), 13²⁻²⁵ (pp. 336 f.), the main narrative in 19 (pp. 443 ff.), and parts of 20 (pp. 455 ff.); and the same is true of E in the main thread of 2⁶⁻³⁶ (pp. 52 ff.), 6⁷⁻¹⁰ (p. 177), 8^{22.23.27aβb} (pp. 183 f.), 10⁶⁻¹⁶ in the main (p. 294), 11¹²⁻²⁸ (pp. 303, 310-317). In other parts of the composite narrative the criteria are frequently very slight; while occasionally they are practically non-existent, and the only ground which we have for assigning a narrative to J is the fact that the parallel narrative seems to emanate from E, or *vice-versâ*. This, however, is a state of affairs which we find also in the Hexateuch, where it frequently happens that, while the fact is clear that we are dealing with a narrative composed of elements derived from the two Prophetic sources, yet criteria for accurate distinction of these sources are hardly to be discovered.*

* This is especially the case with the JE narrative contained in Josh. 1-12. Cf. CH. ii, pp. 305 ff.; Driver, *LOT*,³ pp. 104 ff. (who with characteristic caution does not attempt to separate the two sources).

It is scarcely necessary to emphasize the fact that when we refer to J and E we must think, in each case, rather of a school of historians than of a single historian. Clearly, neither J nor E in the Hexateuch is homogeneous throughout; both of them must have made use of pre-existing material, written as well as oral, the product of very various ages, and embodying divergent and sometimes conflicting traditions.*

Illustrations from Judg. of the use of earlier material in J are seen in the Samson-stories, *chs.* 14-16, which have been edited and fitted with a strongly characteristic introduction, *ch.* 13 (pp. 337 f.), and in one of the narratives in *chs.* 19-21, which appears to be constructed throughout upon a basis of earlier J narratives (p. 456). Similarly, the Song of Deborah, *ch.* 5, is obviously much older than the accompanying prose-narrative, *ch.* 4, though both appear to belong to E (p. 83); and the inference that the former was excerpted from an ancient written source (probably a collection of poems such as 'the Book of the Wars of Yahweh' mentioned in Num. 21¹⁴), is confirmed by the fact that the prefixed statement as to the occasion on which the song was composed, seems to have been excerpted with it from the old source (cf. *note* on v.²). Again, the E² element which is so clearly marked both in Judg. and in 1 Sam. 1-12 (originally a part of the history of the Judges; cf. p. 294), can never have formed an independent document, but presupposes the earlier history of E, to which it forms a religious expansion and interpretation. This incorporation of earlier material and the existence of more than one hand in J and E are sufficient to explain the unequal distribution of characteristic phraseology, and also the occurrence in certain sections of striking words and phrases which are not found elsewhere in the histories.†

While, however, J and E undoubtedly embody the work of *two schools* of prophetic historians, it is natural to suppose that the work of these schools has survived through being gathered together into two continuous prophetic histories; and that it was these *two*

* Cf. CH. i. pp. 108 ff., 119 ff. Skinner (*Genesis* (ICC.), pp. 181 f.) points out that J seems to embody a tradition which knew nothing of the Flood, and also (cf. pp. 418, 450, 570) one which ignored the sojourn in Egypt and the Exodus. The discussion in *Adlit. note*, pp. 44 ff. leads us to the conclusion that J has embodied an ancient Calibbite tradition narrating the conquest of the Negeb by a northward movement from Kadesh-Barnea, and that this has been modified in J as we know it by later influences. Such examples of composite authorship might be multiplied.

† Such are not frequent; but we may notice that the Divine title 'Yahweh Š'bhā'ôth,' which occurs in 1 Sam. 13¹¹, 44, 15², 17⁴⁵, as also in 2 Sam., is not found at all in the Hexateuch and Judg.; and 'Belial,' which occurs in Judg. 19²², 20¹³; 1 Sam. 11¹⁶, 21¹², 10²⁷, 25^{17,25}, 30²², is only found in the Hexateuch in Deut. 13¹⁴, 15⁹. The instances from Judg. of words not found in JE in the Hexateuch which are cited by Kit., *Studien und Kritiken*, 1892, pp. 57, 61; König in *DB.* ii. pp. 811b-812b, would not be significant enough to tell against our theory even if that theory involved the supposition that J and E were respectively the composition of a single hand throughout.

documents, and not two collections of disconnected narratives, which were wrought into one by the redactor R^{JE}. There is thus a sense in which it is perfectly legitimate to speak of 'the J writer' and 'the E writer,' i.e. the actual individuals who were responsible for the composition of the continuous history-books; and since, as we have seen, evidence points to an original uninterrupted sequence between the Hexateuch narratives of J and E, and the narratives of J and E in Judg., we may without excessive boldness maintain that, when we use the symbols J and E in Judg., they have for us no less definite meaning than they possess for us as titles of documents in the Hexateuch.*

§ 4. The Editors.

The portions of Judg. which we assign to the main editor, who, as we have seen (§ 2), is responsible for the pragmatic setting of the book, are as follows:—

Introduction: *ch.* 2^{6b} (in part), 11a, 14abc, 16, 17.

Framework: *chs.* 3⁷⁻¹¹, 3^{12-15a} (working up extracts from the old narrative), 3²⁰, 4¹⁻⁴ (working up old extracts), 4^{23, 24}, 5^{31b}, 6¹⁻⁶ (working up old extracts), 8^{28, 23-25}, 10^{6aa†}, 11^{33b}, 13¹, 15²⁰.

Modern critical scholars unanimously regard this editor as a member of the Deuteronomic School, i.e. as influenced by the standpoint and phraseology of Deuteronomy: thus the signature which is generally adopted for him is R^D (Deuteronomic Redactor). The present writer has, however, convinced himself that this view is not correct. Deuteronomy was (in his opinion) unknown to our

* That we have in Judg. the continuation of the documents contained in the Hexateuch was maintained by J. J. Stahelin, *Specielle Einleitung in die kanon. Bücher des A.T.* (1862), pp. 66 ff., and by E. Schrader in de Wette's *Einleitung in die Bibel, A. u. N.T.* (1869), pp. 327 ff. The subject was first systematically worked out for different parts of Judg. by Ed. Meyer, Stade, and Böhme in articles in *ZATW.* (cf. references in the present Commentary, pp. 1, 176, 293, 335). The merit of attempting to distinguish J and E throughout the book belongs, however, to Budde in his *Richter und Samuel* (1890); and Budde's view has been accepted in the main by Cornill, Moore, Nowack, and Lagrange. Kue. (*Ond.* § 19¹²) speaks with some scepticism of the theory, and it is opposed by Kittel in *Theol. Studien und Kritiken*, 1892, pp. 44 ff.; *HH.* ii. pp. 14 ff.; *GVV.* ii. pp. 15 ff., and by König, *Einleitung in das A.T.*, pp. 252 ff.; *DB.* ii. pp. 811b-812b. The arguments advanced by these two latter scholars, however, would for the most part only be valid if J and E were to be regarded as each the work of a single individual—a view which is maintained by no one. Cf. e.g. Kittel's argument that the history of Abimelech cannot be from E, because in it Shechem is a Canaanite city, whereas in Josh. 24 E² it is Israelite; or, again, that in view of Gen. 22 E, the story of Jephthah's sacrifice of his daughter can hardly belong to the same source.

† It is impossible in 10⁶⁻¹⁶ to be sure how much is due to the main editor and how much to his source, E²: cf. p. 294. Most scholars assign a larger portion of the section to the editor.

editor. The influence which really moulded his thought and diction was the influence of the later Ephraimitic school of prophetic teachers, whose work is generally marked as E². Thus the signature which is adopted in the present commentary to mark the work of the main editor is R^{E2} (Redactor of the late Ephraimitic School). The grounds upon which this view is based have now to be stated.

The passages in Judg., 1 Sam. 1-12, which are characteristically the work of E² are as follows:—Judg. 2 6 (in part), 7-10, 13, 20, 21, 6 7-10, 8 22, 23, 27aβb, 10 6-16 (in the main), 1 Sam. 7 1-14, 8 1-22, 10 17-27a, 12 1-25.* These passages are united together by a common phraseology and theological outlook, the characteristics of which, so far as they distinguish the passages in Judg., are noticed on pp. 55, 177, 183 ff., 294; cf. further Bu., *RS.* pp. 180 ff., Driver, *LOT*⁹, p. 177. Their connexion with Joshua's last address, as related in Josh. 24 (generally assigned, except for a few minor details, to the later stratum of E, *i.e.* E²) is very close; and more especially is this the case with 1 Sam. 12, which relates Samuel's last address before his retirement from the office of judge after the election of Saul as king. The following comparison illustrates the closeness of connexion between the two chapters:—

- Josh. 24¹ And they took their stand before Yahweh.
 1 Sam. 12⁷ And now take your stand, that I may plead with you before God.
- Josh.⁵ And I sent Moses and Aaron.
 Sam.⁸ And Yahweh sent Moses and Aaron. (Cf.¹¹ And Yahweh sent Jerubba'al, etc.).
- Josh.⁶ And I brought forth your fathers out of Egypt.
 Sam.⁸ And they brought forth your fathers out of Egypt.
- Josh.⁷ And they cried unto Yahweh.
 Sam.¹⁰ And they cried unto Yahweh.
- Josh.⁸ And they fought with you. ^{9a} And he fought with Israel.
 Sam.^{9b} And they fought with them.
- Josh.^{10b} And I delivered you from his hand.
 Sam.^{11b} And he delivered you from the hand of your enemies.
- Josh.¹⁴ And now fear Yahweh, and serve him in integrity and in truth.
 Sam.^{24a} Only fear Yahweh, and serve him in truth with all your heart. ¹⁴ If ye will fear Yahweh and will serve him.
- Josh.¹⁶ Far be it from us to forsake Yahweh.
 Sam.²³ Far be it from us to sin against Yahweh.

* Omitting, in Judg., 6 25-32, 35b, 7 2-7, passages which, though assigned to E² upon adequate grounds, have not the same special characteristics as the passages above cited.

- Josh.¹⁷ For Yahweh our God, he it is that brought up us and our fathers from the land of Egypt, from the house of bondmen.
- Sam.⁶ Yahweh . . . that brought up your fathers from the land of Egypt.
- Josh.¹⁷ And who did these great signs before our eyes.
- Sam.¹⁶ Behold the great thing which Yahweh is about to do before your eyes.
- Josh.²² And Joshua^a said unto the people, Ye are witnesses against yourselves. And they said, We are witnesses.
- Sam.⁵ And he said unto them, Yahweh is a witness against you, and his anointed is a witness . . . And ¹they¹ said, He is a witness.

This correspondence between the phraseology of the two addresses—which is so close as to make it obvious that they must both have assumed their present form at the hands of the same author, or else that 1 Sam. 12 must have been modelled upon Josh. 24—is of the first importance in proof that 1 Sam. 12, and the sections in Judg. and 1 Sam. which are similar to it, are rightly to be regarded as *pre-Deuteronomic*.* The fact is familiar that JE in Josh. has been edited by a redactor of the Deuteronomic School (R^D), and the portions of Josh. which are the work of this redactor bear unmistakably the impress of the thought and phraseology of D. Now though there already existed in his source the farewell-address of Joshua^a which belongs to E² (*ch.* 24), R^D was so little satisfied with this as an adequate expression of the Deuteronomic ideal that he inserted side by side with it (*ch.* 23) another address of his own composition in which he enforces that ideal in language which repeats and echoes the language of D almost sentence by sentence. It is worth while to give a full summary of the D phrases in this address in order to exhibit what is properly to be understood as the influence of D upon the members of its ‘school’:—

Josh. 23³. ‘Ye have seen all that Yahweh your God did.’ Cf. Deut. 29² (H¹), 3²¹, 4³; ‘That which Yahweh thy God did,’ Deut. 7¹⁸, 24⁹, cf. 11^{4,5}.

v.³. ‘For Yahweh your God, He it is that fighteth for you.’ So v.¹⁰, Deut. 3²² †.

v.⁵. ‘As Yahweh your God spake unto you.’ So v.¹⁰. Cf. Deut. 1²¹, 2¹, 6^{3,19}, 9³, 10⁹, 11²⁵, 12²⁰, 15⁶, 18², 26^{18,19}, 27³, 29¹³ (H¹²), 31³; Josh. 13^{14,33}, 14¹², 22⁴, all R^D; Judg. 2¹⁵ D², 1 Kgs. 5^{5,12} (H^{19,26}), 8²⁰; 2 Kgs. 24¹³, all R^D. ‡

* That the presentation of Samuel as we have it in this narrative in 1 Sam. was familiar to Jeremiah and his hearers is clear from Jer. 15¹, where Samuel is coupled with Moses as a typical *intercessor* on behalf of Israel; for he only appears in this light in 1 Sam. 7^{8 ff.}, 12^{19,23}, and not in the older narrative with which this is combined. Cf. Cornill as cited by Bu., *RS.* p. 178; Driver, *LOT.*⁹ p. 178.

‡ In several of these passages R.V. renders ‘promised’ for ‘spake’; but the verb is in every case the same in the Hebrew.

*v.*⁶ 'All that is written in the Book of the Law of Moses' (a direct reference to the Deuteronomic Code). Cf. Josh. 1^{7,8}, 8^{31,34} R^D; 1 Kgs. 2³; 2 Kgs. 14⁶ R^D.

*v.*⁶ 'So as not to turn aside therefrom to the right hand or to the left.' Cf. Deut. 17²⁰; also 5³² (\mathfrak{H}^{20}), 17¹¹, 28¹⁴; Josh. 1⁷ R^D; 2 Kgs. 22² R^D.

*v.*⁸ 'Cleave to' ($\text{ב} \text{קרי}$, of adherence to the worship of Yahweh). Cf. Deut. 4⁴, 10²⁰, 11²², 13⁴ (\mathfrak{H}^7), 30²⁰; Josh. 22⁵ R^D; 2 Kgs. 18⁶ R^D. Of adherence to idolatry, or to the representatives of it, *v.*¹²; 1 Kgs. 11²; 2 Kgs. 3³ R^D.

*v.*⁹ 'And Yahweh hath dispossessed from before you nations great and mighty.' Cf. Deut. 4³⁸, 9¹, 11²³ *.

*v.*¹¹ 'And ye shall take great heed to yourselves.' Cf. Deut. 2⁴ †.

*v.*¹¹ 'To love Yahweh your God.' Cf. Deut. 10¹², 11^{13,22}, 19⁹, 30^{6,16,20}; Josh. 22⁵ R^D.

*v.*¹³ 'Until ye perish.' Cf. Deut. 28^{20,22}.

*v.*¹³ 'Which Yahweh your God hath given you.' Cf. *vv.*^{15,16}; Josh. 18³ R^D; with 'about to give you' (*or* 'thee,' 'us,' 'them'), constantly in Deut.

*v.*¹⁴ 'With all your heart and with all your soul.' Cf. Deut. 11¹³, 13³ (\mathfrak{H}^4); Josh. 22⁵ R^D; 'with all thy heart, etc.,' Deut. 4²⁹, 6⁵, 10¹², 26¹⁶, 30^{2,6,10}; 'with all his heart, etc.,' 2 Kgs. 23²⁵ R^D; 'with all their heart, etc.,' 1 Kgs. 2⁴, 8⁴⁸ (=2 Chr. 6³⁸) R^D; 2 Chr. 15¹²; 'with all the heart, etc.,' 2 Kgs. 23³ (=2 Chr. 34³¹) R^D.

*v.*¹⁴ 'There hath not fallen one word out of all the good words, etc.' Cf. Josh. 21⁴⁵ (\mathfrak{H}^{13}) R^D; 1 Kgs. 8⁵⁶ R^D.

*v.*¹⁵ 'Until He destroy you.' Cf. Deut. 28⁴⁸; 'to destroy you' (Yahweh as subj.), Deut. 9^{8,19,25}, 28⁶³.

*v.*¹⁶ 'Shall go and serve other gods, and worship them.' So 1 Kgs. 9⁶ (=2 Chr. 7¹⁹) R^D; cf. Deut. 11¹⁶, 17³; 'serve other gods,' Josh. 24^{2,16} E; Judg. 10¹³ E²; 1 Sam. 8⁸, 26¹⁹; Deut. 7⁴, 13^{6,13} ($\mathfrak{H}^{7,14}$), 28^{36,64}; Jer. 16¹³, 44³; 'other gods,' with 'serve' closely following with suffix of reference, Deut. 8¹⁹, 13² (\mathfrak{H}^3), 28¹⁴, 30¹⁷, 31²⁰; Judg. 2¹⁹ D²; 1 Kgs. 9⁹ (=2 Chr. 7²²) R^D; 2 Kgs. 17³⁵ R^D; Jer. 11¹⁰, 13¹⁰, 16¹¹, 22⁹, 25⁶, 35¹⁵; 'other gods,' without 'serve,' Ex. 20³ E, 23¹³ E; 2 Kgs. 5¹⁷ (Ephraimitie); Hos. 3¹; Judg. 2¹⁷ R^{E2}; Deut. 5⁷, 6¹⁴, 11²⁸, 18²⁰, 31¹⁸; Judg. 2¹² D²; 1 Kgs. 11^{4,10}, 14⁹; 2 Kgs. 17^{7,37,38}, 22¹⁷ (=2 Chr. 34²⁵) all R^D †.

*v.*¹⁶ 'And the anger of Yahweh be kindled against you.' Cf. Deut. 7⁴, 11¹⁷.

*v.*¹⁶ 'And ye perish quickly from off the good land which He hath given you.' Cf. Deut. 11¹⁷. 'The good land,' Deut. 1³⁵, 3²⁵, 4^{21,22}, 6¹⁸, 8¹⁰, 9⁶.

The close and constant echo of the phraseology of D as seen in this address—which is equally characteristic of other portions of

* Heb. *hōriš*, translated 'hath dispossessed,' is rendered by R.V., sometimes 'possess,' sometimes 'drive out.' Cf. *note* on 1¹⁹.

Josh. belonging to this redactor, and also of the handiwork of the Deuteronomic redactor of Kgs.*—sufficiently illustrates what is properly to be taken as the work of ‘the Deuteronomic School.’ It is evident at a glance that it is to the pre-Deuteronomic address Josh. 24 E², and not to Josh. 23 R^D, that the address in 1 Sam. 12 and the kindred sections in Judg. and 1 Sam. exhibit a close affinity; and that therefore we have not erred in marking them as E², and in regarding them as dating from a period *prior* to the promulgation of Deuteronomy. It is true that the religious ideas of E² and D are in many points closely kindred, and that there are a certain number of phrases which are common to them (such *e.g.* as ‘Yahweh your God,’ ‘other gods,’ ‘forget Yahweh,’ etc.); but the explanation of this surely is that the thought and phraseology of E² have exercised a well-marked influence upon D. Had the opposite been the case—*i.e.* had our so-called E² been modelled under the influence of D, it would be difficult to explain why only a limited number of characteristic D phrases were employed, whereas the most striking ones (as seen in R^D in Josh. and Kgs.) are wholly absent. As a matter of fact, a large number of the ideas and phrases which characterize E² are already to be found in Hosea[†]; and it is doubtless to the influence of Hosea[†] and his school that we owe the presenta-

* Cf. the long list of phrases characteristic of R^D in Kgs. which is given by the present writer in his article ‘Kings I. and II.’ in *DB.* ii. pp. 859 ff.

† The following is a rough list of phrases and thoughts contained in Hosea[†] which have influenced E², as well as somewhat later thought (D and Jeremiah):—

Defection from Yahweh characterized as whoredom, 1², 2²⁻⁵ (H 4-7), 4^{12, 15, 18}, 5^{2, 4}, 6¹⁰, 9¹.

‘The Ba’als,’ 2^{12, 17} (H 15, 19), 11²; ‘the Baal,’ 13¹.

‘Go after,’ of adherence to false worship, 2^{5, 13} (H 7, 15); of following Yahweh, 11¹⁰.

Verb ‘love’ (אהב) applied to Yahweh’s feeling for Israel, 3¹, 9¹⁵, 11¹, 14⁴ (H 5); cf. subs. ‘love,’ 11⁴.

‘Yahweh, their God,’ 3⁵, 7¹⁰; ‘Yahweh, thy God,’ 12⁹ (H 10), 13⁴, 14¹ (H 2).

‘Forget,’ of defection from Yahweh, 2¹³ (H 15, ‘Me she forgot’), 4⁶ (‘Thou hast forgotten the tōrā of thy God’), 8¹⁴ (‘Israel forgot his maker’), 13⁶ (‘they have forgotten Me’).

‘Practices’ (מעללים) with *evil* connotation, 4⁹, 5⁴, 7², 9¹⁵, 12² (H 3); cf. Judg. 2¹⁹ E²; Deut. 28²⁰; eighteen occurrences in Jer.

‘They have forsaken to observe Yahweh,’ 4¹⁰.

‘Return unto Yahweh,’ of repentance, 6¹, 7¹⁰, 14^{1, 2} (H 2, 3); ‘unto God,’ 5⁴.

‘I desire mercy (חסד) and not sacrifice;

And the knowledge of God more than burnt offerings,’ 6⁶; cf. 1 Sam. 15²² E².

Verb ‘cry,’ of supplication to Yahweh, 7¹⁴, 8².

‘Transgress covenant,’ 6⁷, 8¹.

‘Provoke’ (הכעיס, obj. ‘Yahweh’ understood) 12¹⁴; characteristic of D.

Reference to the deliverance from Egypt, 2¹⁵ (H 17), 11¹, 12⁹ (H 10), 13⁴.

Depreciatory reference to the paraphernalia of cultus, 3⁴, 10^{1, 2}.

Depreciatory reference to the existing form of kingship as opposed to the Theocratic ideal, 8^{4, 10} (as emended; cf. p. 184), 10³, 13^{10, 11} (cf. Judg. 8^{22, 23} E²; 1 Sam. 8^{6, 7}, 10¹⁹, 12^{17, 19} E²).

Antipathy to bull-worship of Northern Kingdom, 8^{5, 6}, 10⁵, 13² (cf. R^D in Kgs.).

tion of Israel's early history as it appears in E², and (it may well be) ultimately the Deuteronomic revival itself.*

Now, even a cursory examination of the phrasology of the main editor of Judg. makes it clear that this is modelled upon the E² sections which we have been discussing. The address of 1 Sam. 12 especially, which properly rounds off the history of the Judges with the final address of Samuel, the last of their number, after the election of the first king, seems to have been used by our editor as the type to which he sought to conform his pragmatic setting of Judg. Examination of his phraseology in detail yields the following results:—

1. 'Did that which was evil in the sight of Yahweh,' Judg. 2¹¹, 3^{7,12}, 4¹, 6¹, 10⁶, 13¹, all R^{E2}. Elsewhere, Num. 32¹³ JE?; 1 Sam. 15¹⁹ E²; 2 Sam. 12⁹; Deut. 4²⁵, 9¹⁸, 17², 31²⁹; twenty-two occurrences in R^D's framework to Kgs., and parallel passages in 2 Chr.; Jer. 32³⁰, 52²; Isa. 65¹², 66⁴; Ps. 51⁴ (~~11~~ 6).

2. 'And they forsook Yahweh, and served the Ba'als and the 'Ashtarts,' Judg. 2¹³ E² (worked in by R^{E2}). Cf. 1 Sam. 12¹⁰ E², 'We have sinned, because we have forsaken Yahweh, and have served the Ba'als and the 'Ashtarts'; so very similarly (exc. om. 'and the 'Ashtarts'), Judg. 10¹⁰ E²; with inverted order, 'and they served the Ba'als and the 'Ashtarts . . . and forsook Yahweh,'

* The present writer is of the opinion that the origin of Deuteronomy is to be sought in the prophetic school, not of the Southern, but of the *Northern* Kingdom, and that we have a gradually developing stream of thought represented by E, Hosea, E², and finally D. If this view is correct, the composition of D must have taken place some time *subsequently* to the fall of Samaria and the end of the Northern Kingdom. Sargon only claims to have carried captive 27,290 of the inhabitants of Samaria, and definitely states that he allowed the remainder to retain their possessions (? *inušunu*, of doubtful meaning), set his officers as prefects over them, and laid upon them the tribute of the former kings (cf. Winckler, *Sargon*, p. 101; Rogers, *CP*, p. 331). Doubtless (as was the case with Nebuchadnezzar's first deportation from Jerusalem; 2 Kgs. 24¹²⁻¹⁴) those whom he removed were the politically influential and the skilled artificers; and he would have no reason for interfering with the members of the prophetic order, who belonged to the poorer classes, and would hardly have been clustered in and about the capital city. During the period after B.C. 722, Samaria remained the centre of an Assyrian province, with a population to some extent leavened by foreign settlers (cf. Winckler, *Sargon*, pp. 5, 21; Rogers, *CP*, p. 326). The mainly late narrative of 2 Kgs. 17²⁴⁻⁴¹, which reads almost as though the foreign element were in sole possession and the religion of Yahweh had died out, is without doubt coloured by bitter antipathy to the Samaritans of later times. But, in fact, a not inconsiderable body of Israelites had survived the conquest; amongst whom the prophets of the north may be supposed to have continued their literary labours quietly and unobtrusively, setting their hopes upon a future when the whole of Israel (both of the north and of the south) should be united in faithful worship of Yahweh at one common centre. The grounds upon which this theory is based have not yet been published by the writer, but he hopes to produce them in the near future in a work entitled *The Prophetic School of Northern Israel and the Mosaic Tradition*.

Judg. 10⁶ E²; 'served the Ba'als and the 'Ashtarts' coupled with 'forgot Yahweh' (cf. No. 3), Judg. 3⁷ R^{E2}.

(a) 'Forsook Yahweh' occurs elsewhere in Judg. 2¹² I² (based on E² r.¹³), Josh. 24¹⁶ E²; Isa. 1⁴; 1 Kgs. 9⁹; 2 Kgs. 21²², both R^D; Jer. 2^{17,19}; 2 Chr. 7²², 21¹⁰, 24^{20,24}, 28⁶; cf. 'forsakers of Yahweh,' Isa. 1²⁸, 65¹¹; 'forsook Him' (Yahweh as obj.), 2 Chr. 13¹⁰, 24²⁵; 'shall forsake Him,' 1 Chr. 28⁹; 2 Chr. 15²; 'His forsakers,' Ezr. 8²²; 'Thy forsakers,' Jer. 17¹³ (both referring to Yahweh); 'ye (they) have forsaken Me' (Yahweh as speaker), Judg. 10¹³ E²; 1 Kgs. 11³³; 2 Kgs. 22¹⁷ both R^D; Jer. 1¹⁶, 5^{7,19}, 16^{11bis}, 19⁴; 2 Chr. 12⁵, 34²⁵; 'hast forsaken Me,' Deut. 28²⁰; 'shall forsake Me,' Deut. 31¹⁶ (source?).

Similar phrases are 'forsook to observe Yahweh,' Hos. 4¹⁰; 'forsook the covenant of Yahweh,' Deut. 29²⁵ (~~¶~~²⁴); Jer. 22⁹; 'forsook the commandments of Yahweh,' 1 Kgs. 18¹⁸ R^D; 'forsook my *tôrâ*,' Jer. 9¹³ (~~¶~~¹²).

(b) 'The Ba'als and the 'Ashtarts,' 1 Sam. 7⁴ E² (obj. of 'put away').

'And the 'Ashtarts,' coupled with 'put away the foreign gods from your midst,' 1 Sam. 7³ E².

'The Ba'als' alone, Judg. 8³³ R^{E2} (obj. of 'went a whoring after'), Hos. 2^{13,17} (~~¶~~^{15,19}), 11² (obj. of 'sacrificed to'), 1 Kgs. 18¹⁸; Jer. 2²³, 9¹⁴, ~~¶~~¹³ (in each case obj. of 'went after'); 2 Chr. 17³, 24⁷, 28², 33³, 34⁴.

3. 'And they forgot Yahweh their God,' Judg. 3⁷ R^{E2}, based on 1 Sam. 12⁹ E².

'Forget Yahweh' occurs elsewhere, Deut. 6¹², 8^{11,14,19}; Jer. 3²¹; Isa. 51¹³; 'forgot (*or* forgottest) Me' (Yahweh as speaker), Hos. 2¹³ (~~¶~~¹⁵), 13⁶; Jer. 2³², 13²⁵, 18¹⁵; Ezek. 22¹², 23³⁵; 'forgotten Thee' (Yahweh as obj.), Ps. 44¹⁷ (~~¶~~¹⁸).

4. 'And the anger of Yahweh was kindled against Israel,' Judg. 2¹⁴, 3⁸, 10⁷ R^{E2}, based on 2²⁰ E². Elsewhere, Num. 25³ E or J, 32¹³ JE?; 2 Kgs. 13³ R^D.

'The anger of Yahweh was kindled' occurs again in Num. 11¹⁰ J?, 12⁹ E, 32¹⁰ JE?; Deut. 29²⁷ (~~¶~~²⁶); Josh. 7¹ R^P; 2 Sam. 6⁷ = 1 Chr. 13¹⁰; 2 Chr. 25¹⁵; Ps. 106⁴⁰; cf. 'and Yahweh heard, and His anger was kindled,' Num. 11¹ E; 'and the anger of God was kindled,' Num. 22²² J revised; 'and the anger of Yahweh (*or* my anger) shall be kindled,' Deut. 7⁴, 11¹⁷, 31¹⁷; Josh. 23¹⁶ R^D.

5. 'And He gave them into the hand of spoilers, and they spoiled them,' Judg. 2¹⁴ R^{E2}. * Cf. 2 Kgs. 17²⁰ R^D, 'and He gave them into the hand of spoilers.'

'Give into the hand' (of delivering up enemies; Yahweh as subj.) is found again in R^{E2}, Judg. 6¹ (of Midian), 13¹ (of Philistines), and is frequent elsewhere both in pre- and post-Deut. literature.

* It is doubtful whether this phrase belongs to R^{E2}. It may be later: cf. p. 55.

6. 'He sold them into the hand of,' Judg. 2¹⁴, 3⁸, 4² R^{E2}, based on Judg. 10⁷ E², 1 Sam. 12⁹ E²; cf. Judg. 4⁹ E. 'Sold them' (sc. 'to their enemies'; subj. 'their Rock,' = 'Yahweh'), Deut. 32³⁰.

7. 'Their enemies round about,' Judg. 2¹⁴, 8³⁴ R^{E2}, based on 1 Sam. 12¹¹ E²; cf. 2 Sam. 7¹; Deut. 12¹⁰, 25¹⁹; Josh. 23¹ R^D.

8. 'And the children of Israel cried unto Yahweh,' Judg. (2¹⁶),* 3^{9.15}, 4³ †, 6⁶ R^{E2}, based on Judg. 10¹⁰ E²; 'and your fathers cried unto Yahweh,' 1 Sam. 12⁸ E²; 'and they cried unto Yahweh,' 1 Sam. 12¹⁰ E²; Josh. 24⁷ † E, Ex. 14¹⁰ E (source of preceding). Elsewhere, with Israel as subj., Ps. 107⁶ †.13.19.28 †; cf. 2 Chr. 13¹⁴ †; Hos. 8²; Mic. 3⁴.

9. 'Yahweh raised up judges,' Judg. 2¹⁶ R^{E2}, 21⁸ D² (based on v.16); 'Yahweh raised up a saviour,' Judg. 3^{9.15} R^{E2}. No close parallel. הָקִים is used, with Yahweh as subj., of *raising up* men to fill particular positions in Deut. 18^{15.18} (a prophet), Josh. 5⁷ R^D (the sons of those who died in the wilderness), § 1 Sam. 2³⁵ (a faithful priest), 2 Sam. 7¹² = 1 Chr. 17¹¹ (thy seed as king), 1 Kgs. 11^{14.23} (an adversary), 1 Kgs. 14¹⁴ (a king), Am. 2¹¹ (prophets and Nazirites), Jer. 6¹⁷ (watchmen), 23⁴ (shepherds), 23⁵ (a righteous sprout), 29¹⁵ (prophets), 30⁹ (a king), Ezek. 34²³ (a shepherd), Zech. 11¹⁶ (*id.*).

10. 'Went a whoring after' (of intercourse with deities other than Yahweh), Judg. 2¹⁷, 8³³ R^{E2}, 8²⁷ E², Ex. 34^{15.16} J, Deut. 31¹⁶ (source?), Lev. 17⁷, 20^{5bis} (both H), Ezek. 6⁹, 20³⁰, 1 Chr. 5^{25.¶}

11. 'They turned aside quickly from the way,' Judg. 2¹⁷ R^{E2}. Cf. Ex. 32⁸ E †, source of Deut. 9^{12.16} †.

12 (a) 'Was (were) subdued,' Judg. 3³⁰ (Moab), 8²⁸ (Midian), 11³³ (the children of 'Ammon), all R^{E2}, based on 1 Sam. 7¹³ E² 'and the Philistines were subdued.' The verb נִכְנַע Niph'al is used elsewhere in a *passive* sense in 1 Chr. 20⁴, 2 Chr. 13¹⁸, Ps. 106⁴². In other occurrences the sense is *reflexive* ('humble oneself').

(b) 'God subdued' (הִכְנִיעַ Hiph'il) Judg. 4²³ R^{E2} (Jabin, king of Canaan). Cf. Deut. 9³, 1 Chr. 17¹⁰, 2 Chr. 28¹⁹, Ps. 81¹⁴ (יְיָ¹⁵); with David as subj., 2 Sam. 8¹ = 1 Chr. 18¹.

13. 'And the land had rest' (וַתִּשְׁקט הָאָרֶץ), Judg. 3^{11.30}, 5³¹, 8²⁸ R^{E2}. Cf. Josh. 11²³, 14¹⁵ R^D (וְהָאָרֶץ שְׁקֵטָה מִמְּלָחָמָה), Isa. 14⁷, Zech. 1¹¹, 1 Chr. 4⁴⁰, 2 Chr. 14^{1.6} (יְיָ¹³ 13²³, 14⁵).

As the result of these statistics, it appears that phrases Nos. 2, 3, 6, 8, 10, 12 appear definitely to be modelled upon 1 Sam. 12 or other sections of E², or at least to be drawn from a similar source

* Restored here upon the analogy of parallel passages.

† With the variant spelling וַיִּזְעֲקוּ for וַיִּזְעֹקוּ.

§ Here, however, the context seems to demand הִקְמִים 'that arose,' in place of הִקִּים.

¶ Cf. the characteristics of Hosea' given in *Footnote* †, p. xlv.

of inspiration; and Nos. 4, 7, 9, 11, 13, while too general to form the basis of any inference, at the same time fully fit in with the theory of E² influence. There remain Nos. 1 and 5, which, taken by themselves, may seem to support the theory of D influence. We observe, however, that No. 1, while frequent in Deut. and R^D in Kgs., is by no means the creation of the D school, as the occurrences in 1 Sam. and 2 Sam. show; while No. 5, which is doubtfully assigned to R^{E2}, is paralleled merely by the single occurrence from R^D in Kgs., and no weight can be laid upon the connexion. Evidence thus surely indicates that the main editor of Judg. did his work under the influence of E² prior to the promulgation of D; such connexion with D as he exhibits being due to the fact that he contributes to the stream of prophetic thought which resulted ultimately in the latter work. Some traces of the work of a genuine Deuteronomic hand are to be found in the introductory section to Judg. (cf. 2 12.14b, 15.18.19, 3 1a.3, marked as D²); but these are clearly distinct from, and later than, the work of R^{E2} (cf. p. 55).

It is clear that R^{E2}, though the principal editor of Judg. as we know the book, was not the first editor who brought together the old narratives of J and E and combined them into a continuous whole. The story of Abimelech, *ch.* 9 1-57, which was known to R^{E2} and omitted by him from his work as alien to his purpose, was already a composite narrative, containing elements from the two ancient sources (cf. pp. 267 f.); and the same is true at any rate of the story of Micah and the Danites, *chs.* 17-18, which undoubtedly belonged to the original history of the period of the Judges, though it was not utilized by R^{E2}. We must conclude, therefore, that there existed a composite history of the Judges prior to the work of R^{E2}; and since we have found reason to believe that the double strand of ancient narrative in Judg. is of a piece with JE in the Hexateuch (cf. § 3), it is natural to assume that J and E in Judg. were first brought together as part of a continuous history of the origins of Israel by the redactor of the same sources in the Hexateuch, R^{JE}. The handiwork of this redactor is also to be traced in the combination of the two strands in 1 Sam. 1-12, which doubtless originally formed the concluding part of the history of the period of the Judges.

Traces of R^{JE}, as we find them in Judg., are for the most part harmonistic merely,* and he does not seem to have been dominated by any definite pragmatic purpose akin to that of R^{E2}. Whether he set the narratives of individual Judges in a stereotyped framework is doubtful. It may be noticed, however, that the closing formula in the narratives of Jephthah (12 7a) and Samson (16 31b), 'And he judged Israel *x* years,' occurs in the same form at the close of the judgeship of Eli, 1 Sam. 4 18b (cf. also of Samuel, 1 Sam. 7 15), and is therefore presumably prior to R^{E2} (whose regular concluding formula is 'and the land had rest *x* years'); while, on the other

* Cf. references in *Index* to R^{JE} under 'Redactors of Judges.'

hand, the fact that the statement generalizes the scope of the Judges' influence (over *Jahel*, and not merely over one or more tribes) is an indication that it is later than the old narratives themselves, and therefore in all probability redactional.*

The date of the redaction of Judg. can only be approximately determined. E², which exhibits strongly the influence of Hosea[†], must be subsequent to that prophet, who flourished *cir.* B.C. 750-735, but not necessarily very long subsequent. It is reasonable to suppose that R^{JE} may have done his work of combining J and E (including E²) *cir.* B.C. 700 or a little later. R^{E2} may then be placed *cir.* B.C. 650. The book took its final form at the hands of the editor (or school of editors) imbued with the priestly conceptions of post-exilic times, for whose work we use the symbol R^P. The extent of R^P's work has been sufficiently indicated in the final paragraph of § 2. Cf. also references in the *Index* under 'Redactors of Judges.'

§ 5. Chronology.

In attempting to estimate the length of the period covered by the Book of Judg. we turn naturally to examine the chronological data supplied by the editors, which may seem at first sight to afford us an exact basis for our calculations. Unfortunately, however, this is not the case.

In 1 Kgs. 6¹ we find a statement from the hand of the priestly reviser of the book ‡ that the period from the Exodus until the building of the Temple in the fourth year of Solomon was 480 years. Addition of the data which we possess for this period gives the following result:—

Wanderings in the wilderness,	40 years.
Conquest under Joshua,	Not stated.
Oppression of Cushan-rishathaim (3 ⁸),	8 years.
Interval after deliverance by 'Othniel (3 ¹¹),	40 „
Oppression of Eglon (3 ¹⁴),	18 „

* A difference is to be discerned in the use of *šāphat* 'to judge,' *šōphēṭ* 'judge' by R^{E2} and R^{JE}. For R^{E2} a 'judge' is so termed as a *vindicator* or *deliverer* (cf. *ch.* 2^{16,17,18}, 3¹⁰); but in the passages above noticed which we assign to R^{JE} 'to judge' means simply *to exercise the judicial functions of a magistrate or ruler*. This latter usage is also found in the mention of the periods covered by the minor Judges (*ch.* 10^{2,3}, 12^{9,11,14}), where R^P seems to have copied the formula of R^{JE}, since it is scarcely possible that the brief notices of these Judges, the whole conception of which belongs to the post-exilic school of thought, should have existed in R^{JE}'s Book of Judges (cf. pp. 289 f.). We assign to R^{E2} the notice of *ch.* 15²⁰, which states that Samson 'judged Israel . . . twenty years'; but this simply means that R^{E2}, when he deliberately rejected the Samson-stories which now stand in *ch.* 16, concluded his narrative with R^{JE}'s formula which we find in *ch.* 16^{31b}.

‡ Evidence is conclusive that the verse in question belongs to the latest additions to Kings. Cf. *NHTK.* pp. 58 f.

Interval after deliverance by Ehud (3 ³⁰),	80 years.
Oppression of Jabin (4 ³),	20 „
Interval after deliverance by Deborah (5 ³¹),	40 „
Oppression of Midian (6 ¹),	7 „
Interval after deliverance by Gide'on (8 ²⁸),	40 „
Reign of Abimelech (9 ²²),	3 „
Tola's judgeship (10 ²),	23 „
Ja'ir's judgeship (10 ³),	22 „
Oppression of 'Ammon (10 ⁸),	18 „
Jephthah's judgeship (12 ⁷),	6 „
Ibsan's judgeship (12 ⁹),	7 „
Elon's judgeship (12 ¹¹),	10 „
'Abdon's judgeship (12 ¹⁴),	8 „
Oppression of the Philistines (13 ¹),	40 „
Samson's judgeship (15 ²⁰ , 16 ³¹),	20 „
'Eli's judgeship (1 Sam. 4 ¹⁸),	40 „
Samuel's judgeship,	Not stated.
Reign of Saul,	„
Reign of David (1 Kgs. 2 ¹¹),	40 years.
Portion of Solomon's reign (1 Kgs. 6 ¹),	4 „

Here we have a total of 534 years, exclusive of three periods of unstated length, representing the domination of Joshua^c, Samuel, and Saul.

As regards the first of these indefinite periods—we find that, at the beginning of the wilderness-wanderings, Joshua^c first appears in the old narrative of E, Ex. 17^{8 ff.}, as the leader of Israel in the battle with the 'Amalekites at Rephidim, and subsequently, in the same E narrative, as Moses' attendant (cf. Ex. 24¹³, 32¹⁷, 33¹¹), being described in 33¹¹ by the Hebrew term *na'ar* which can hardly denote more than a youth approaching man's estate. If we are justified in combining these two representations—a warrior, and yet a very young man—we may picture him as about 20 years old at the time of the Exodus; and adding to this the 40 years of the wanderings, we get an approximate 60 years; which, subtracted from his age at his death, 110 years (Josh. 24²⁹ = Judg. 2⁸ E), gives 50 years as the period of his leadership in the conquest of Canaan. According to *ch.* 2^{7,10}, however, a further period of indefinite length has to be assumed between the death of Joshua^c and the oppression of Cushan-rish'athaim; since we are here informed that Israel remained faithful all the days of the elders that outlived Joshua^c, and apostasy only began after the death of the latter.

The length of Samuel's judgeship must have been considerable. According to 1 Sam. 7¹⁵, 'he judged Israel all the days of his life'; and it was not until he was an old man that he appointed his sons in his place, and their mismanagement of affairs led to the demand for a king (1 Sam. 8^{1 ff.}, probably E²). We have no data, however,

for forming an approximate estimate of the duration of this judgeship; and, similarly, we are unable to arrive at the length of Saul's reign by any reference, direct or indirect, in the O. T. Such a note of time was desiderated by the scribe who added the gloss which stands in 1 Sam. 13¹, framed upon the analogy of the recurring formula in Kgs. :—'Saul was x years old when he began to reign, and he reigned y years over Israel.'*

If we add 50 years for Joshua's judgeship to the 534 years, the result is 584 years, without reckoning the two (or, if we take account of *ch.* 2^{7,10}, *three*) periods of undetermined length, which, upon the lowest computation, can scarcely have amounted together to much less than 50 or 60 years.† This is far too long to have formed the basis for the calculation of 480 years for the period given in 1 Kgs. 6¹. Yet it is probable that the author of this late addition to Kgs. had precisely the same data as we now possess.

Thus Nöldeke (*Untersuchungen zur Kritik des A. T.*, 1869, pp. 173 ff.) supposes that the calculator followed the oriental practice of ignoring periods of oppression and usurpation, and so cut out of his reckoning the periods during which Israel is said to have served Cushan-rish'athaim, 'Eglon, Jabin, Midian, 'Ammon, the Philistines, and the reign of Abimelech—in all a total of 114 years.§ Subtracting this from the 534, and allowing 40 years (evenly or unevenly divided) for Joshua' and Saul, and 20 for Samuel, Nöldeke reaches the total of 480 years.

Moore (*Comm.* xli. f.) agrees with Nöldeke in his omissions; but differs in thinking that, for the Judæan author of the chronology, the rule of Saul, like that of Abimelech, was regarded as illegitimate and so not reckoned; and that for 'Eli's judgeship we should follow \mathfrak{E} rather than \mathfrak{H} , and read 20 years and not 40 years. Then, upon the supposition that Joshua's life fell into three periods

* The formula as it stands in \mathfrak{H} is simply a skeleton, both of the requisite numbers being omitted, as in the rendering given above. The word וּשְׁתִּי is probably corrupt dittography of the following שְׁנִים 'years'; and we are scarcely justified in rendering ' x and two years,' since this would require וּשְׁתֵּי שָׁנִים . . .

† The history of 'Eli's family during the periods of Samuel and Saul requires a considerable lapse of time. The death of 'Eli synchronizes with the death of his son Phinehas in the battle of Aphek (1 Sam. 4). Since Phinehas was still an able-bodied man, his son Ahitub must have been a young man at most at this date. Yet according to 1 Sam. 14³, it is Ahitub's son Ahijah (apparently = Ahimelech of *ch.* 22¹¹) who is priest in the early or middle part of Saul's reign; and at the slaughter of the priests of Nob, Abiathar, the son of Ahimelech and grandson of Ahitub, escapes to David carrying the Ephod with him, and is old enough to exercise the priestly office on David's behalf by manipulation of the sacred lot.

§ Wellh. (*Prolegomena*, p. 230) has noted the striking fact that, after making the necessary assumption that the 40 years of Philistine domination coincide with the judgeship of 'Eli, and include that of Samson, the total of the remaining foreign dominations, viz., 71 years, nearly coincides with the total assigned to the minor Judges, viz., 70 years; and he infers that the latter were intended to take the place of the former in the scheme of reckoning.

of 30 + 40 + 40 years, he assigns 40 years for the conquest of Canaan under Joshua¹; and gives 40 years for Samuel's judgeship on the ground of the importance of his work, and the fact that he is represented as an old man when he died, and is said to have 'judged Israel all the days of his life.' This produces the required total of 480 years.

These and similar calculations can only, however, possess a relative importance; since it is evident that the author of the statement in 1 Kgs. 6¹ must have been employing an artificial method of reckoning. We know that the Exodus probably took place under Mineptah, the successor of Ramesse II. (cf. p. civ); and, on the other hand, we are able, by aid of Assyrian chronology, to determine approximately the date of Solomon's accession.* These data force upon us the conclusion that the period which we are considering cannot really have occupied much more than 250 years; or possibly, if the Exodus took place not under Mineptah, but subsequently to his death, an even shorter space of time.

Evidence also leads us to conclude that the instances of the oppression of the Israelites by various foreign races, and of deliverance and respite effected by the Judges, were in most, if not in all, cases, local rather than general. Thus, supposing that the terms of years mentioned are based upon accurate information, it is highly probable that they not infrequently coincide with or overlap one another. Thus, *e.g.*, the south Palestinian tribes may have been suffering from the oppression of the Philistines while the east Jordan tribes were exposed to the encroachments of the 'Ammonites. The period

* Mineptah's reign is dated by Petrie B.C. 1234-1214, and by Breasted B.C. 1225-1215. Solomon's accession must be placed *cir.* B.C. 970. This latter date is obtained by back-reckoning from the earliest O.T. date fixed by Assyrian chronology, viz. B.C. 854, the date of Ahab's presence at the battle of Karkar in alliance with Bir-idri of Damascus, the Biblical Ben-Hadad II. Ahab is most likely to have been allied with Ben-Hadad at the end of his reign, when, as we are informed by 1 Kgs. 22¹, after the treaty concluded between the two kings as related in 1 Kgs. 20^{33,34}, 'there continued three years without war between Aram and Israel.' It may be plausibly assumed that this period of three years was really less. 1 Kgs. 22² states that 'in the third year' Ahab determined to recover by force of arms from Ben-Hadad the city of Ramah of Gilead which he had failed to cede in accordance with his compact. It is not unlikely that the first of the three years as reckoned was really the remnant of the year which elapsed after the treaty of 20^{33,34}, so that there remains only one full year for the working of the alliance in the form of a combined resistance to Assyria. Now Ahab reigned 22 years according to the Biblical reckoning; therefore 854 must have been his 21st year, 853 according to the predating method (*i.e.* the reckoning of the still unexpired portion of the year in which a king came to the throne as his first reigning year) being his 22nd year and also the 1st year of Ahaziah. Back-reckoning from B.C. 854 according to the chronology of 1 Kgs., with reduction of the length of each reign by one year to allow for predating (which comparison of the synchronisms of the reigns of the two kingdoms proves to have been the historian's method of reckoning) gives B.C. 931 for the accession of Jeroboam and Rehoboam, and B.C. 970 for the accession of Solomon whose reign is given as lasting 40 years.

of the Philistine oppression extended not merely over the judgeship of Samson, but also over that of 'Eli; and, at any rate partially, into the periods of Samuel and Saul. Possibly Samson and 'Eli may have been contemporaries. This is a consideration which by itself suggests to us the futility of any attempt to construct a chronology of the period upon the evidence which we possess.

But are the data given in the Biblical sources to be relied upon as defining with accuracy the various periods to which they are referred? The fact can scarcely escape notice that the number 40 or its multiple occurs with singular frequency. Thus, 40 years represents the length of the wilderness-wanderings, of the peace enjoyed after the victories of 'Othniel, Deborah, and Gide'on, of the Philistine oppression, of 'Eli's judgeship, and of the reigns of David and Solomon. Ehud's judgeship occupies twice 40 years, and that of Samson half 40. This fact suggests to us that 40 years may be employed as a round number, representing approximately the length of a generation. Bearing this in mind, we notice that the 480 years of 1 Kgs. 6¹ is also a multiple of 40, viz. 40×12 , *i.e.* twelve generations. That twelve generations were supposed, as a matter of fact, to cover the period in question appears from the genealogy of Aaron and his successors in 1 Chr. 6³⁻¹⁰ (¶ 5²⁹⁻³⁶), where twelve names are given between Ele'azar the son of Aaron and 'Azariah, who is specified as 'he that executed the priest's office in the House that Solomon built in Jerusalem.' These twelve generations might naturally be reckoned as follows: (1) Moses, (2) Joshua', (3) 'Othniel, (4) Ehud, (5) Barak, (6) Gide'on, (7) Jephthah, (8) Samson, (9) 'Eli, (10) Samuel, (11) Saul, (12) David, these being the twelve national leaders who were specifically divinely-appointed; and that this scheme—or something like it—was in the mind of the chronologist is suggested by the facts that six of these generations (viz. 1, 3, 5, 6, 9, 12) are actually reckoned as 40 years, and a seventh, viz. Joshua', may also have been so reckoned if we suppose that his 110 years fell into periods of $30 + 40 + 40$ years. Such a scheme, however, if it was ever fully worked out, may have been subsequently vitiated by various influences, *e.g.* the desire to exclude Saul as illegitimate, and the raising of the number of Judges within the Book of Judges to twelve by the addition of the minor Judges in an attempt to find representatives for each of the twelve tribes of Israel.

This discussion may suffice to illustrate the hopelessness of any attempt to construct a chronology of our period from the Biblical sources available. We can only, as we have already noticed, conjecture that the total length of the period from the Exodus to the fourth year of Solomon was approximately 250 years; but for the formation of a chronological scheme within this period, or even for a conjectural estimate of the length of that portion of it which is covered by the Book of Judges, we are absolutely without data.

§ 6. External information bearing on the period of Judges.

Our knowledge of the history of Canaan at this period, as derived from extra-Biblical sources, is for the most part such as can be drawn by inference from evidence which properly concerns an earlier period.

We possess no certain evidence as to the earliest settlement of Semitic peoples in Canaan. The earliest Semites of whom we have authentic knowledge in Babylonia were settled in Akkad in the north. The recently published dynastic lists from Nippur prove the existence of an early tradition relating to a succession of dynasties in Babylonia from post-diluvial times, which had their seats at Kiš, Erech, Ur, Awan, and other cities.* There is obviously a large element of myth in the tradition;† but, if we may judge from the royal names that are preserved, it would seem that the earliest rulers of Kiš, Erech, and Ur were non-Semitic. Unfortunately, the lists are too fragmentary to admit of any estimate of the date at which Semites made their appearance in Babylonia. We first find them enjoying full political power in the north, under the famous Semitic dynasty of Akkad, which was founded by Šarru-kin or Sargon I.,§ around whose name a number of traditions clustered in later times. It is related that 'he subdued the country of the West (sun-setting) in its full extent,'|| i.e. the Mediterranean sea-board including Canaan; and this tradition has now been proved to have an authentic basis.¶ Other famous rulers of the

* Cf. Poebel, *Historical Texts* (Univ. of Pennsylvania Mus. Publ., Vol. iv. No. 1, 1914), pp. 73 ff.

† In addition to the occurrence of the names of gods and demigods among the early rulers, the chronological calculations of the early scribes of Nisin, who compiled the lists in the twenty-second century B.C., present a striking resemblance to the chronological system of Berossus with its mythical and semi-mythical dynasties: cf. King, *Bab.* p. 114, n¹; pp. 116 f., n².

§ The name Sargon is the Biblical form (used in Isa. 20¹ of the Assyrian king of the 8th century B.C.) of the Babylonian name Šarru-ukin or Šarru-kin. A not quite complete list of the early Semitic rulers of Akkad (and of other Babylonian dynasties) was published by Scheil, *Comptes rendus de l'Acad. des Inscriptions et Belles-Lettres*, 1911 (Oct.), pp. 606 ff., and *Revue d'Assyr.*, ix. p. 69. This document proves the correctness of the Neo-Babylonian tradition that Šarru-kin, or Sargon, was the founder of the Dynasty of Akkad. It used to be assumed that he and two other early Semitic rulers were kings of Kiš, on the strength of the title *šar Kiš* which they bear in their inscriptions; but it is now clear that this should always be read *šar kiššatu*, 'king of the world,' a title to which they laid claim in virtue of their power as kings of the dynasty of Akkad (cf. King, *Britannica Year-Book*, 1913, pp. 256 ff.). The powerful king Šar-Gani-šarri (or Šar-Gali-šarri), with whom Sargon I. used to be identified, was not the founder, but a later ruler, of the Dynasty of Akkad.

|| For the inscription, cf. King, *Chron.* ii. pp. 3 ff.; Rogers, *CP.* pp. 203 ff.; *TB.* i. pp. 105 ff.

¶ Cf. the highly important series of inscriptions of kings of Agade (Akkad) recently published by Poebel (*op. cit.* ch. vi.). In one of these Sargon, in ascribing his conquests to the god Enlil, says, 'and he gave him the upper land, Mari, Yarmuti, and

same dynasty were Narâm-Sin,* and Šar-Gani-šarri, who was probably his grandson. We have contemporary evidence of the activity of the latter in Amurru or the West-land.†

While Akkad in the north of Babylonia was thus dominated by Semites, Sumer in the south was still occupied by the people who are known to us, from their habitat, as Sumerians; a non-Semitic race possessing an advanced civilization, to which the Semites who succeeded them owed an incalculable debt. The date at which the Semites gained the ascendancy in Akkad is a matter of uncertainty. It may have been at some time in the fourth millennium B.C.; and was at any rate not later than the earlier decades of the third millennium.§

The early common home of the Semites, prior to their dispersion throughout western Asia, was probably central Arabia;|| and the fact that the first Semites who are known to us as occupying Babylonia are found to be settled in the north and not in the south, lends colour to the theory that they may represent a wave of Semitic immigration into Babylonia which first entered the country not from the south but from the north-west.¶ If this was so, these Semites, after quitting their early home, may have first traversed Canaan and northern Syria, leaving in all probability settlements

Ibla, as far as the cedar-forest and the silver mountains. Unto Šarru-kin, the king, Enlil did not give an adversary' (pp. 177 ff.). Here 'the upper land' is the West-land, so-called, apparently, as reached by going up the Euphrates. Poebel adduces reasons for taking 'the cedar-forest' to be the Lebanon and Anti-Lebanon, and 'the silver mountains' the Taurus (cf. pp. 222 ff.).

* According to the Neo-Babylonian tradition, Narâm-Sin was the son of Sargon. This is possible; but it may be noted that two other members of the house probably occupied the throne between Sargon and Narâm-Sin; and if so, eighty or ninety years separated Narâm-Sin's accession from that of his father.

† A tablet of accounts from Tello is dated 'in the year in which Šar-Gani-šarri conquered Amurru in Basar.' Cf. King, *Sum. and Akk.* p. 225.

§ The date which was formerly accepted by scholars is that which is given by Nabonidus, the last king of Babylon (B.C. 550), who states that, when digging in the foundations of the temple of the sun-god at Sippar, he discovered the foundation-memorial which had been laid by Narâm-Sin 3200 years previously (for the inscription, cf. *KB.* iii. 2, pp. 102 ff.). This would place Narâm-Sin's date B.C. 3750. Modern investigation, however, has tended to discredit Nabonidus' statement; and though the reduction of a thousand years or more which at one time was suggested is doubtless too drastic (cf. the discussion in Rogers, *HBA.*⁶ i. pp. 494 ff.), it is quite possible that Nabonidus' calculation is a good deal too high (resulting, it may be, in part from the reckoning of early contemporaneous dynasties as though they were consecutive). Indeed, the evidence of the recently-discovered dynastic lists has been interpreted by King as supporting the view which would place Sargon's accession not so very much before the end of the fourth millennium B.C. But, in the present very partial state of excavation in Babylonia, it is possible that we may still be totally uninformed with regard to a period of considerable length in these early times.

|| For a summary of the views which have been put forward on this subject, and the authorities who support them, cf. Barton, *Semitic Origins*, pp. 1 ff.; Rogers, *HBA.*⁶ i. pp. 452 f.

¶ Cf. King, *Sum. and Akk.* p. 55.

in these districts in their wake; or they may have come up from Arabia along the western bank of the Euphrates, where in later times we find settlements of Aramaeans, and may have left the further west, including Canaan, wholly untouched.*

Be this as it may, we cannot point to a period, within the range of our historical knowledge, when Canaan was unoccupied by a Semitic population. Excavation of ancient sites in Palestine has revealed the fact that the earliest inhabitants were neolithic cave-dwellers who burned their dead, and who were therefore probably non-Semitic;† but how long this race continued to occupy the country cannot be estimated with any approach to certainty.§

We stand on surer ground in speaking of a later wave of Semitic migration northwards and westwards from Arabia, which founded

* Evidence is lacking in justification of any definite theory as to the approximate date of the earliest migrations of the Semites northward and westward. The use of the Semitic Babylonian language in the inscriptions of the early rulers of Akkad implies the lapse of a period of indefinite length (probably many centuries) since the first departure of their ancestors from Arabia, to allow for the development of this language. We may contrast, in this respect, the later immigration into Babylonia of the 'Amorites' who founded the First Dynasty of Babylon (cf. pp. lviii ff.); the West Semitic language spoken by these immigrants (as evidenced by their proper names), with its Arabian affinities, implying a much less remote separation from the parent-stock. An interesting point in connexion with the earliest settlement of Semites in Babylonia, is the fact that the closely shaven Sumerians always represent their deities as *bearded*, and therefore, apparently, as Semites (cf. figures in King, *Sum. and Akk.* pp. 47 f.; Hall, *NE.* plate xiv. p. 204). The significance of this fact is as yet unelucidated; but the theory (put forward by Ed. Meyer, *Semiten und Sumerier; Abhandl. d. k. p. Akad.*, 1906) is somewhat plausible that these Sumerian deities may have been Semitic in origin, and that there may therefore have been a Semitic population in Babylonia even prior to the coming of the Sumerians. This theory is criticized by King, *Sum. and Akk.* pp. 47 ff.; and favoured by Jastrow, *Heb. and Bab. Traditions.* pp. 8 f. A further fact which admits of no doubt is the ultimate linguistic connexion between Sumerian and many of the primitive biliterals which can be proved to underlie Semitic trilateral roots (cf. Ball, *Semitic and Sumerian in Hilprecht Anniversary Volume; Shumer and Shem in Proceedings of the British Academy*, 1915). This must carry back the connexion between Sumerians and Semites to a hoary antiquity; but the study of the subject is not at present sufficiently advanced to admit of any theory in explanation.

† Cf. Vincent, *Canaan*, pp. 73 ff., 208 ff.

§ The primitive inhabitants of the hill-country of Se'ir, to the south of Canaan, who were dispossessed by the children of 'Esau, are called *Hôrîm* in Deut. 2^{12,22} (cf. Gen. 14⁶, 26²⁰⁻³⁰); and the view has frequently been advocated that this name is connected with Heb. *hôr* 'hole,' and denotes 'Troglodytes' or 'cave-dwellers'; but this is highly precarious. More probably *Hôrîm* is to be connected with the name *Haru*, which was a designation applied by the Egyptians to a portion of southern Palestine. Cf. Müller, *AE.* pp. 137, 148 ff., 240; Jensen, *ZA.* x. pp. 332 f., 346 f.; Hommel, *AHT.* p. 264, n²; Paton, *Syria and Palestine*, p. 37; Meyer, *IN.* pp. 330 f.; *GA.*² I. 2, p. 600; Kit., *GVI.*² i. p. 36; Lehmann-Haupt, *Israel*, p. 37, *al.* Connexion of *Hôrîm* and *Haru* with *Harri*=Aryans, proposed by Winckler, *MDOG.* xxxv. pp. 49 ff., and adopted by Gemoll, *Grundsteine zur Geschichte Israels*, p. 17, is very improbable. Cf. Meyer, *GA.*² I. 2, p. 601; Kit., *GVI.*² i. p. 37 f. The *Hôrîte* genealogies in Gen. 36²⁰⁻³⁰ consist of Semitic names.

a dynasty at Babylon, and was also responsible for peopling the region to the west of the Euphrates, including the Mediterranean sea-board, with a race who were doubtless the ancestors of the Amorites of Biblical times.*

The First Babylonian Dynasty, which probably lasted from *cir.* B.C. 2225 to 1926,† consisted of eleven kings. The fourth and fifth of these kings bear good Semitic Babylonian names, Apil-Sin ('son of Sin,' the moon-god) and Sin-muballit ('Sin gives life'); but the remaining names are foreign, and present close analogies to Arabic and Hebrew. Thus three of them, Hammurabi or Ammurabi, Ammiditana, and Ammizaduga, contain the element *Ammu* or *Ammi* which is familiar to us from its occurrence in Arabic and Hebrew. Cases of its occurrence in Hebrew proper names are 'Ammi'el, 'Ammihud, 'Ammizabad, 'Ammiadab, 'Ammishaddai, and perhaps 'Amram. The meaning of this *amm* in Arabic is 'paternal uncle'; in Hebrew perhaps more generally 'kinsman' (on the father's side), since the term is used in the plural in the expression וַיִּגְרַף אֶל-עַמּוּי וַיִּקְרָף 'and he was gathered to his kinsmen,' Gen. 25⁸, *al*§

If proof were needed that these *Ammi*-names were foreign to the Babylonians, it would be found in the fact that a list exists in which a Babylonian scribe has explained the names Hammurabi and Ammizaduga by what seemed to him to be their Babylonian equivalents; the former by *Kimla rapastum*, 'a widely-extended kindred,'

* We say 'Amorites' because they are thus described ('men of the land of Amurru') by the Babylonians (cf. p. lix); but the use of this term does not imply the holding of any theory as to a racial distinction between 'Amorites' and 'Cana'anites' (such *e.g.* as that the Canaanites were in origin the earliest Semitic settlers in Syria-Palestine, prior to the coming of the Amorites). Since the name Amurru applied to Syria-Palestine is certainly older than the flowing into this region of the Semitic wave of which we are speaking (cf. Böhl, *KH.* p. 33), the name 'Amorite' would be equally suitable to the (assumed) earlier Semitic population inhabiting it. We are wholly in the dark as to the original *racial* distinction (if such existed) between Canaanite and Amorite; and speculations on the subject are of the nature of guess-work pure and simple. On the geographical and literary distinctions in the usage of the two terms, cf. p. 3 (O.T.), p. 41 (extra-Biblical).

† This reckoning results from King's discovery that the so-called 'Second' Babylonian Dynasty (of 'the Country of the Sea,' *i.e.* Lower Babylonia), which lasted three hundred and sixty-eight years, was partly contemporary with the First Dynasty and partly with the Third (Kassite) Dynasty: cf. *Chron.* i. pp. 93-113. Previously, the three dynasties had been assumed to have been successive, and the beginning of the First Dynasty was placed *cir.* B.C. 2440. In view of this new evidence, King assumed, as the most probable conclusion, that the Third Dynasty immediately succeeded the First (cf. *op. cit.* pp. 136 f.; followed by Meyer, *GA.*² I. ii. pp. 341 ff.; Hall, *N.E.* pp. 28, 192 ff.), and so dated the First Dynasty B.C. 2060 to 1761. Now, however, in the light of further evidence, he concludes (as already conjectured by Ungnad, *ZDMG.* lxi. pp. 714 ff., and Thureau-Dangin, *ZA.* xxi. pp. 176 ff.) that the Second Dynasty, though partly contemporary with the First and the Third, yet dominated Babylonia for a period of about one hundred and sixty years. Cf. the full chronological discussion in *Bab. ch.* iii.

§ On 'Ammi'-names in Semitic, cf. Gray, *EB.* 138 ff.

and the latter by *Kintum kettum* 'a just kindred.'* More probably the names really contain a predicative statement:—Uammurabi, 'the (divine) kinsman is great,' Ammizaduga, 'the (divine) kinsman is just.' Both names, so far as the form is concerned, might have occurred in Hebrew, the former as 'Ammirab or 'Amrab, the later as 'Ammişadoḳ. ‡

Space forbids our examining in detail the remaining names of this dynasty; but we may notice in passing that Abi-esbu' (the name of the eighth king) is the exact equivalent of the Hebrew Abishua', and that in the seventh name Samsu-iluna, 'Samsu is our god,' we have the Arabic form of the suffix of the 1st plural in *iluna*, the Babylonian form being *ilunī*. The second name Sumula-ilu, is only satisfactorily to be explained from Arabic, the *la*, as in Arabic, giving emphasis to the predicative statement—'The Name (κατ' ἐξοχήν) indeed is god.'

In addition to the evidence afforded by these king-names, we have abundant evidence in the proper names contained in the documents belonging to this dynastic period, which proves the influx into Babylonia of a very large foreign element. § Many of these display the same characteristics as we have found in the king-names—a close resemblance to Hebrew, and more particularly to Arabic; especially to the forms of southern Arabic which are known to us from inscriptions (Minæan and Sabæan). ||

The question which we now have to ask is, Who were these foreign immigrants, and from what region did they enter Babylonia? There exists a tablet belonging to the reign of Zabum (the third king of the dynasty) which deals with a dispute between two contending parties about a certain piece of property. In this document the names are of the characteristically foreign type of which we have been speaking, and they are described as 'men as well as women, children of Amurru' (*ištu zikarim adi sinnistum mārē A-murru-um*). ¶ The Babylonian name Amurru (=Sumerian MAR.TU, 'West-land') was applied by the Babylonians to the whole region west of the Euphrates including Syria and Palestine, and bounded on the west by the Mediterranean (cf. *Addit. note*, p. 41). We infer, therefore, that the First Babylonian Dynasty was founded by foreign conquerors from Amurru, the country to the west of the Euphrates, who entered Babylonia probably from the north-west, just as the earlier wave of Semitic immigration appears to have

* Cf. v. R. 44, col. 1, ll. 21, 22.

‡ עֲמִישָׁדוֹק is known as a South Arabian name: cf. Ranke, *Early Bab. Personal Names*, p. 27. According to Weber, the name עֲמִישָׁדוֹק occurs in a South Arabian inscription: cf. *OLZ.* x. (1907), 146 ff.; *MF.* 16., 1907. 2, pp. 95 ff.

§ Cf. Ranke, *Early Bab. Personal Names*; Thureau-Dangin, *Lettres et Contrats de l'Époque de la Première Dynastie Babylonienne*.

|| Cf. Hommel, *AHT.* ch. iii; *Grundriss*, pp. 129 ff.; Ranke, *Early Bab. Personal Names*, pp. 27 ff.

¶ Cf. Ranke, *Early Bab. Personal Names*, p. 33.

done. The presence of two Babylonian names among the foreign names of the other kings is no doubt due to the fact that the immigrant settlers gradually tended to assimilate their language and civilization to the superior civilization into the midst of which they entered.*

The language spoken by these immigrants, which we have seen to be illustrated by their proper names, has been variously described

* It is worth while here to call attention to the later prevalence and persistency of the Semitic Babylonian language as proof of the deep-seated influence of the *first* Semitic settlement; just as we have already (p. lvii, *footnote* *) called attention to the development of this language as we first know it (in the inscriptions of the early rulers of Akkad), as proof of the long-prior antiquity of the separation of this branch of Semites from the parent-stock. Neither of these facts, it may be thought, has received sufficient attention; and they are most strikingly overlooked by Myres in *The Dawn of History*—a little book which, for all its imaginative power and grace of style, is somewhat superficial and unreliable when dealing with *facts* as they concern Sumerians and Semites (*chaps.* 4 and 5). It is not 'possible to discover with certainty the period of emigration' from Arabia (p. 106) of the first Semitic wave which entered Babylonia; such records as we possess of the dynasty of Akkad do not suggest a recent occupation of the country, nor does it appear that Sargon of Akkad was leader of a horde of 'Mesopotamian nomads' (p. 111). The remarks (p. 106) as to the modifications which produced the different Semitic languages are somewhat obscure, but they certainly seem to *suggest* that these modifications took place in the course of ages *at the fountainhead*, i.e. *ex hypothesi* in central Arabia (it is difficult to attach any other meaning to the statements that 'the intervals between' the successive Semitic migrations from Arabia 'have been sufficient to ensure that the characteristics of "Semitic" speech, which is common to all emigrants from Arabia, should have had time to alter slightly,' and that 'these successive groups of dialects retained their peculiarities—and if anything added to them—after their separation from the parent language'), while each offshoot from the parent-stock as it were registered and retained the particular stage of linguistic development which had been reached at the date of its breaking off, with such later modifications as are implied by the parenthesis, 'and, if anything, added to them.' If this statement were at all true to fact, then Arabic (whether we call it the latest offshoot or the residuary representative of the parent-language) ought to exhibit the most advanced condition of phonetic decay—whereas it is a commonplace that the reverse is true, and that in many respects this language exhibits the most primitive formations. Clearly the truth is that the parent-stock, owing to its comparative immunity from outside influences ensured by the monotony of the desert, remained in a relatively unmodified condition through incalculable ages; whereas the offshoots, so soon as through migration they became subject to such influences, underwent a more or less rapid modification. This is the reason why (as already noted, p. lvii, *footnote* *) we must conclude that the Semitic Babylonian of the dynasty of Akkad, which is substantially the Semitic Babylonian of later times, indicates that the users of the language, when we first meet with them, had long been separated from the parent-stock; whereas the language of the Western Semites who founded the First Dynasty of Babylon (as evidenced by their proper names; cf. pp. lviii f.), which exhibits striking resemblances to South Arabian as known to us some 1500 years and more later, indicates that *this* branch of Semites, when they come into the light of history, must have left the common home comparatively recently. The influence of environment upon a Semitic language is most strikingly illustrated by Aramaic, which from the accident of its position has experienced the most rapid development (or decay), and has been most receptive of external influences. Lastly, Myres' statement that

as South Arabian, Cana'anite, Amorite, or West Semitic. Of these titles, the two latter are no doubt the most suitable.*

It cannot be doubted that this Amorite or West Semitic tongue was the ancestor of the Hebrew language of later times, which, as is well known, was not the speech of the Israelites only, nor shared by them only with other 'Hebrew' races, which are represented in Genesis as closely related to them—*e.g.* the Moabites, whom we know from Mesha's inscription (*cir.* B.C. 850), to have spoken a language which only differed dialectically from the Hebrew of the Old Testament; but, as is apparent from the 'Cana'anite glosses' of the Tell el-Amarna Letters to which we shall shortly refer, and from the Phœnician inscriptions of much later times, was but one form of the common language of at least the southern portion of the Mediterranean sea-board.† This is a fact which seems to be recognized in Isa. 19¹⁸, where the Hebrew language is designated as 'the language (lit. "lip") of Cana'an.'

There is evidence which suggests—if it does not certainly prove—that from the time of Hammurabi onwards the First Babylonian Dynasty ruled not only over Babylonia, but also over Amurru.§ The whole of Sin-muballit's reign and a great part of that of Hammurabi were occupied with a long struggle with the Elamites for the possession of southern Babylonia.|| Kudur-Mabuk, king of western Elam (Emutbal), having conquered the city of Larsa, installed his sons, Warad-Sin and Rim-Sin, successively as its rulers; and the power of Elam was gradually extended over the neighbouring city-states until it embraced eventually the whole of southern and central Babylonia. It was not until Hammurabi's thirtieth year that he was able to effect a turn in the tide; but his success was then so decisive that he not only captured Larsa but even invaded the land of Emutbal and defeated the Elamites upon their own ground. Now we know that the Elamite Kudur-Mabuk styled himself ADDA of Amurru,¶ just as he styled himself ADDA of Emutbal. Precisely how much the claim to this title implied we are unable to affirm; but, however much or little of an historical element we may find in the much-debated *ch.* 14 of Gen., it can

'the second wave of emigration . . . overflowed and washed out, as it were, whatever was left of the first' (p. 113) is seen to be very wide of the truth when we consider that the language of the first wave (Semitic Babylonian) became the dominant language of Babylon and Assyria as long as these kingdoms lasted.

* 'Amorite' (or more correctly 'Amurrite': cf. p. 168) is a proper designation of the language of Amurru, as also of its people.

‡ That Aramaic, which, as known to us from the close of the ninth century B.C. and onwards, was the speech of the Semitic races inhabiting the more northerly portion of the Mediterranean sea-board (north and north-east of the Lebanon) was also at an earlier period merely a dialectical form of the language of Amurru, is suggested in the discussion of *Addit. Note*, pp. 173 ff.

§ Cf., on this question, Winckler, *AF* i. pp. 143-152.

|| Cf. the detailed account given by King, *Bab.* pp. 150 ff.

¶ Cf. i. R. 2, No. 3; *CT* xxi. 33; Rogers, *CP*. pp. 247 f.

hardly be denied that it affords ground for the assumption that Amurru, even as far south as south-eastern Canaan, was at one time under the suzerainty of Elam and subject to a yearly tribute.* After Hammurabi's successes and the consolidation of his power, we find him claiming a like suzerainty over Amurru. The Diarbekir-stele, which bears a portrait of him, describes him as 'King of Amurru' without any further title. Ammiditana, a subsequent king of the same dynasty, is likewise termed 'King of the land of Amurru.'[†] Hammurabi was not merely a conqueror, but in the best sense an organizer and ruler: and it is probable that any region over which he claimed the title of 'king' was not a mere sphere for occasional razzias aimed at the collection of booty and tribute,[§] but would experience, at least to some extent, the benefits of his good government and civilizing influence.||

* The name of Chedorla'omar (Kudur-Lagamar), who is represented as leader of the confederation, is genuinely Elamite in formation, though the bearer of it is otherwise unknown (on the supposed discovery of the name, cf. King, *Hammurabi*, i. pp. livf.). The name of the goddess Lagamal occurs fairly frequently in proper names on contract-tablets of the First Dynasty period (so several times on tablets in the library of St. John's College, Oxford; cf. also Ungnad, *Babylonische Briefe*, No. 249; *Beiträge zur Assyriologie*, vi. 5, p. 95). 'Amraphel, King of Shinar' is generally accepted as Hammurabi. 'Arioch, King of Ellasar' may be Warad-Sin of Larsa, since Warad-Sin might be represented in Sumerian form by ERI.AGU (cf., however, King, *Hammurabi*, i. pp. xlix ff.). 'Tidal, king of peoples' (Heb. *gôyim*), may have been a Hittite chieftain. His name has been plausibly connected with Dud-halia, a name which is borne in later times by one of the last rulers of the Hittite empire (cf. Sayce's note in Garstang, *Hittites*, p. 324, n⁴). The term *gôyim* may represent the Bab. *umman Mandu*, i.e. semi-barbarian hordes from the north. On the historical probability of such an alliance as is pictured, cf. King, *Bab.* p. 159; Rogers, *HBA.*⁶ ii. pp. 83f.; Skinner, *Genesis* (*ICC.*), pp. 257 ff. The Larsa Dynastic list recently published by Clay (*Miscellaneous Inscriptions in the Yale Babylonian Collection*, 1915, pp. 30 ff.), seems to prove that Warad-Sin was considerably anterior to Hammurabi.

[†] Cf. Winckler, *AP.* i. pp. 141-146; King, *Hammurabi*, pp. 195 f., 207 f.; Jeremias, *OTLAE*, i. p. 322; Bohl, *KH.* p. 35.

[§] Against the view of Hogarth, *The Ancient East*, pp. 24 f.

|| The list of cities mentioned in the prologue to Hammurabi's Code enables us to form an estimate of the extent of his empire during the latter years of his reign. It includes the principal religious centres not only of Akkad and of Sumer as far south as Eridu, but stretches northward to Assur and Nineveh and westward to Aleppo—if, as is generally supposed, this city is to be understood by Hallabim (KI). Both Aleppo and also, probably, 'the settlements on the Euphrates,' which he claims to have subdued, would be reckoned as part of Amurru. The fact that no more southerly cities of Amurru are enumerated is, it must be confessed, a point which may be advanced against the view which is advocated above. May we, however, explain the omission by the fact that in Amurru, which, as contrasted with Sumer and Akkad, was a comparatively new and uncivilized country, there existed no ancient and celebrated centres of culture, the deities of which Hammurabi was concerned to propitiate? At any rate he specially distinguishes the west Semitic deity Dagan as 'his creator' (*banīšu*).

A striking example of the influence of the Semitic Babylonian *language* upon the language of Canaan (Hebrew), which it is difficult to assign to any other period than

We have, then (it may be assumed), in the First Dynasty of Babylon a dynasty of 'Amorite' origin, bearing sway both over Babylonia and (from the time of Hammurabi) over Amurru to the west as far as the Mediterranean sea-board. This dynasty, as facts abundantly prove, must have fallen rapidly under the influence of Babylonian civilization. It will be sufficient, in this regard, to allude to the legal Code of Hammurabi, in which the far-reaching and highly-detailed character of the legislation proves (as indeed we know from extraneous evidence) that the great king was not the initiator of the whole system, but embodied earlier elements, many, if not most, of which were doubtless due to Sumerian civilization.* These facts help us to understand two phenomena

that of the First Babylonian Dynasty, is seen in the uses of the Bab. *Pemansive* (in form identical with the Heb. Perfect) and *Praeterite* (in form identical with the Heb. Imperfect), as compared respectively with the uses of the Heb. Perfect and Imperfect with *wāw consecutive*. The Bab. *Pemansive*, like the Heb. Perfect, essentially regards an action as existing apart from any idea of time-relations: whereas the Bab. *Praeterite*, like the Heb. Imperfect with *wāw consecutive*, comes into use as soon as an action can be brought into a time-relation, *i.e.* can be regarded as springing out of a defined point in time. A good illustration of the two usages in Bab. may be seen in the opening lines of the Creation-epic, where *Pemansives* describe the condition of things prior to creation (*lu nabâ, lu zakkat, lu kaggura, lu še', lu šapâ*, etc.), but *Praeterites* are employed so soon as the actions of creation begin to *take their start* out of conditions as defined by the *Pemansives* (so *ihîkîd-ma, ibbatû-ma*, etc.). Since the mode of thought thus defined in language is peculiar to Babylonian and to Hebrew (with which we may group the inscriptions of Mesha' and of Zakir: cf. p. 174), and is otherwise unknown in Semitic, it is reasonable to explain the connexion as due to the influence of the older civilization upon the younger at a specially formative period in the history of the latter.

* Cf. *e.g.* what is known as to the reforms of Urukagina, Sumerian *patesi* of Laggaš, *cir.* B.C. 2800: King, *Sum. and Akk.* pp. 178 ff. The fragment of a Sumerian code of laws (published by Clay, *Miscellaneous Inscriptions in the Yale Bab. Coll.*, 1915, pp. 18 ff.) also contains instructive evidence upon this point. The fragment preserves nine laws. Two of these, which fix compensation for injury resulting in miscarriage, are condensed in Hammurabi's Code; the latter also adds other laws on the subject to suit the peculiar conditions of Babylonian society under the First Dynasty. Another law, dealing with compensation for the loss of a hired boat, is amplified to form four laws in the Code. Two of the newly-recovered Sumerian laws, relating to the loss of a hired ox, are practically reproduced in the Code; while others on unfilial conduct, elopement, and seduction find Semitic Babylonian parallels in certain features, but no precise equivalents. One law, which provides for the payment of his portion to a son who renounces his sonship, and which enacts his subsequent legal separation from his parents, is not paralleled in the Code, but, as Clay points out, is strikingly illustrated by the parable of the prodigal son in Luke 15¹¹. The Sumerian Code bears the title 'the law of Nisaba and Ġani.' Nisaba was patroness of writing, and Ġani in later periods is described as 'lord of the seal' and 'god of the scribes': they may well have been patrons of law under the Sumerians. It is noteworthy that Nisaba is here mentioned before her consort, a fact which suggests that he was a deity of less consideration. The divine name Ġani occurs in proper names of the Dynasty of Ur and the First Dynasty of Babylon; and we know of a West Semitic kingdom of Ġana (later Ġani) on the middle Euphrates not far from the mouth of the Ġabûr (cf. King, *Bab.* pp. 129 ff.). If the Sumerian god

which, in later times, are very striking: (i) the influence of Babylonian civilization upon Canaan, and, eventually, upon Israel, both in regard to legislation and also to legends and early traditions;* and (ii) the use of the Babylonian language and the cuneiform script in Syria and Canaan as a medium of communication in the fourteenth century B.C. (as witnessed by the T.A. Letters), and probably also in later times.†

The empire of Hammurabi was maintained, on the whole, unimpaired under his son and successor Samsu-iluna. This king, however, experienced considerable trouble in the south, both from the Elamites and also from the people of the Sea-country on the borders of the Persian Gulf, where a ruler named Iluma-ilu appears as the founder of an independent dynasty. After Samsu-iluna the power of the First Dynasty gradually declined. Its fall was hastened, if not actually brought about, by a raid of the Hittites,‡ an Anatolian people from beyond the Taurus, who now for the first time appear upon the arena of western Asia. The reins of government in Babylon seem then to have been seized by the dynasty of the Sea-country to which we have already alluded (reckoned as the Second Babylonian Dynasty in the Kings' list; cf. *Footnote* †, p. lviii). This dynasty may be inferred to have been, in the main, Sumerian, perhaps with a certain Semitic admixture.§

After a lapse of some 160 years the Sea-country rulers were

Hani was ultimately of West Semitic origin—a possibility which these facts seem to suggest, we have recovered a very noteworthy result of Sumerian contact with the west prior to the age of Hammurabi. It should be added that, though the Sumerian Code is undated, both script and contents suggest a rather earlier date than that of the First Dynasty.

* It does not of course follow that the 'Amorites' were in all respects debtors to the earlier Babylonian civilization, and contributed nothing of their own. Certain elements, both in their civilization and in their traditions, may be, so far as we know, distinctively Amorite in origin. If it were possible to analyse the sources of the traditions which are unmistakably common in origin to the Babylonians on the one hand and to the Canaanites and Hebrews on the other, we should, in all probability, distinguish three successive sources from which, in turn, material has been drawn:—(i) Sumerian, (ii) Semitic Babylonian, (iii) Amorite. Clay, in his book *Amurru, the Home of the Northern Semites* (1909), seeks to prove that Amurru was the cultural centre of the Northern Semites, and that 'the influence of Babylonian culture upon the peoples of Canaan was almost nil' (p. 91); but this is a paradox.

† Cf. Hommel, *AHT*, pp. 45 f.

‡ A chronicle published by King states that 'against Samsu-ditana the men of the land of Hatti ~marched~, against the land of Akkad'. King connects this statement with the fact that in later years the Kassite king Azum-Kakrime brought back the images of the god Marduk and his consort Sarpanitum from the Hittite state of Hani in northern Syria, and installed them again in the temple of Esagila at Babylon. Cf. *Chron.* i, pp. 148 f.; ii, p. 22.

§ For possibly older references to the Hittites (time of Hammurabi) cf. *Footnote* * on Gen. 14, p. lxii, and Garstang, *Hittites*, p. 323.

* The names of the first three kings and of the last king are Semitic, while the remaining seven are Sumerian.

driven out of Babylon by Kassite invaders from the east who founded a new dynasty (the Third Dynasty) which lasted for the long period of 576 years, and is to be dated c. 1760-1185. The latter part of this period is therefore coincident with part of the period covered by the Book of Judg.; and it is possible that in Judg. 3⁷⁻¹¹ we may have the echo of a Kassite raid upon the west in which the name of the raiding chieftain has been perverted by late Jewish ingenuity (cf. p. 64). The fact seems to be established that the Kassites were, in origin, Indo-Germanic;* but they speedily adapted themselves to the Semitic Babylonian civilization, though their king names remain, with few exceptions, Kassite throughout the dynastic period. The Kassite success in conquering Babylon was probably due in large measure to their possession of horses and chariots; and the foundation of their dynasty marks the introduction of the horse into Babylonia, and thence very speedily into Syria and Egypt.†

The domination of Egypt by the Hyksos, and their subsequent expulsion, have an important bearing upon the history of Canaan at the period of Babylonian history with which we have been dealing. That the Hyksos were Asiatic Semites may be regarded as certain; but that they were uncivilized nomads pouring into Egypt directly from Arabia is unlikely. If Manetho's explanation of the name Hyksos as 'shepherd-king' (from *Hyk* = 'king' and *sos* = 'shepherd')‡ be approximately correct,§ it was probably applied by the Egyptians to the invaders in contempt and derision. The fact that, according to Manetho, the first Hyksos king, Salitis, rebuilt and fortified the city of Avaris in the Delta (probably the modern Tell el-Yahudiyyeh in the Wādī Tūmīlāt¶) because he

* Cf. Hall, *N.E.* p. 201.

† Bab. *sīd* 'horse,' is regularly written ideographically ANŠU.KURRA; and the accepted conclusion is that this Sumerian equivalent means 'ass of the mountain,' and preserves record of the fact that the horse was introduced into Babylonia from the high-lying steppes of central Asia, across the eastern mountains. Though it is, of course, an elementary fact that ANŠU means 'ass,' and that KURRA may mean 'mountain,' the analogy of parallel cases in which ANŠU is prefixed as a determinative before the names of other beasts of burden (the mule and camel) serves to cast doubt upon this explanation, and to suggest that ANŠU.KURRA is properly to be understood as 'ass-like animal (*i.e.* beast of burden) called KURRA.' KURRA is then, in all probability, a foreign name for the horse, introduced into Babylonia together with the animal which bore it. It is tempting to associate the name with Persian *ghour*, Hindi *ghor-khur*, Baluchi *ghur* or *ghuran*, Kirghi *koulun*—names which are applied to the charger. The transference of a name from one animal to another of kindred (or even of diverse) species is not without analogy.

§ Cf. Jos., *C. Ap.* i. 14.

¶ On this interpretation *sos* is probably the Egyptian *sasu*, a term applied to the Asiatic Bedawin. Breasted (*Hist. Eg.* p. 217) objects to this explanation, and suggests that the real meaning of Hyksos is 'ruler of countries'—a title which Hyksos, one of the Hyksos kings, often gives himself on his monuments. Cf. Griffith in *PSBA.* xix. (1897), pp. 296 f.; W. M. Müller in *M.F.A.G.*, 1898, 3, pp. 4 ff.

¶ Cf. Petrie, *Hyksos and Israelite Cities*, pp. 9 f.

feared the incursion of 'the Assyrians' (a term loosely used to denote the dominant power in Babylonia at the time)* seems to be an indication that the Hyksos had connexions beyond the borders of Egypt in a north-easterly direction, *i.e.* throughout Canaan and northern Syria: and inasmuch as we find them, after the reduction of Avaris by Ahmose I., next making a stand in Sharuhēn (*i.e.* no doubt the city of that name mentioned in Josh. 19⁶ as assigned to Simeon in southern Judah) where they are besieged for three years, and finally defeated by Ahmose in northern Syria,† we have good ground for concluding that they were, in origin, the more or less civilized people of Amurru, and that their line of retreat lay, as was natural, into the land occupied by their kindred.§ This conclusion is strengthened by the fact (accepted by Egyptologists) that it was they who introduced horses and chariots into Egypt, and that Ahmose succeeded in expelling them by turning this powerful engine of warfare against them. As we have already noticed, it was the Kaššites who introduced the horse into western Asia, and the peoples of Amurru must speedily have obtained it through their Mesopotamian connexion. The name of the most important Hyksos king known to us, Hyān, is certainly Semitic,|| and among the scarab-names of kings or autonomous chieftains collected by Petrie¶ there occurs *Ypk-hr* or *Ykb-hr* which may represent a Semitic Ja'cob-el—a name which raises speculation on account of its Israelite connexions. Another name, 'nt-hr, seems to represent 'Anath-el.**

The length of the period covered by the Hyksos invasion and domination of Egypt is most uncertain. Petrie‡‡ accepts and defends Manetho's statement that five hundred and eleven years elapsed from their first invasion to their ultimate expulsion; but

* Cf. Hall, *NE.* p. 215, n³.

† Cf. the autobiographies of the two Egyptian officers named Ahmose, who took part in this war: Breasted, *AR.* ii. §§ 1 ff.

§ The cause originally conducing to the invasion of Egypt by the Western Semites can only be conjectured. Hall may be correct in supposing that the almost contemporary incursion of the Kaššites from Irān and the Hittites from Asia Minor into Mesopotamia and northern Syria 'must have caused at first a considerable displacement of the Semitic population, which was pressed south-westwards into southern Syria and Palestine,' with the result that it 'burst the ancient barrier of Egypt': *NE.* p. 212. Cf. also Luckenbill, *AJTh.* xviii. (1914), p. 32.

|| The name is borne by an Aramaean king of Ya'di in northern Syria in the ninth century B.C., and is written Ha-ia-ni in the annals of Shalmaneser III. (cf. *KB.* i. p. 170), and 𐤇𐤓𐤏 in the inscription of Kalumu, the succeeding king of Ya'di (on which cf. p. 174).

¶ Cf. Petrie, *Hyksos and Israelite Cities*, pp. 68 f. and Pl. LI.; Hall, *NE.* p. 217.

** Cf. Spiegelberg in *OLZ.* vii. (1904), 131; Hall, *NE.* p. 217. There seems to be no justification for Spiegelberg's proposal to interpret the Hyksos name *Smkn* as Simeon (*loc. cit.*; *Agypt. Randglossen zum A.T.* p. 12), since the equivalent *k=y* appears to be unproven (on the equivalents of Eg. *k*, cf. Burch. §§ 113 f.).

‡‡ Cf. *Hist. Eg.* pp. 204, 228; *Historical Studies*, p. 14.

Ed. Meyer and his followers* allow conjecturally no more than a hundred years. Hall† seems to have good sense on his side in arguing for a figure between these two extremes—perhaps about two hundred years. The accession of Ahmose I., who expelled them from Egypt, is dated *cir.* B.C. 1580.§

Invasion of Palestine and Syria, thus begun by Ahmose I., was carried further by subsequent kings of the Eighteenth Egyptian Dynasty. It is a moot point whether Amenhotep I. (*cir.* B.C. 1559), the successor of Ahmose, undertook a Syrian campaign; but his successor, Thutmose I. (*cir.* B.C. 1539), advanced victoriously through Syria as far as Naharin, *i.e.* the district between the Orontes and the Euphrates (cf. *note* on 'Aram-naharaim,' ch. 37), and set up a boundary-tablet on the bank of the Euphrates to mark the northern limit of his kingdom.|| Such incursions of Egyptian kings into Syria, though productive of booty, failed to bring the Western Semites permanently under the Egyptian yoke or to ensure payment of a regular tribute.

It was Thutmose III. (*cir.* B.C. 1501), the most famous king Egypt ever had, who, after a long period of inaction enforced upon him by the powerful Queen Hatshepsut, with whom he was associated as ruler, began on her death a series of seventeen campaigns in Syria (*cir.* B.C. 1479-1459), resulting in its thorough conquest and consolidation as a part of the Egyptian Empire.¶ In the first of these he met a confederation of north Palestinian kinglets, under the leadership of the Prince of Kadesh—possibly an immigrant Hittite from the north; a combination which reminds us of the league of the kings of northern Canaan under Sisera, as recorded in Judg. A battle at Megiddo, graphically described, resulted in his complete success, and Megiddo was invested and soon fell into his hands. The list (on the walls of the Temple of Amon, at Karnak) of 'the people of Upper Retenu [southern Syria, including Palestine] whom his majesty shut up in wretched Megiddo' contains a hundred and nineteen names, and is of great geographical interest.** Among the names occur *Y'-h-b-'u-ra* and *Y'-š-p-'u-ra* (Nos. 102

* Cf. Meyer, *GA.*² I. ii. p. 293; Breasted, *Hist. Eg.* p. 221.

† Cf. Hall, *NE.* pp. 23 ff., 216 f., 218.

§ The accession-dates given for Egyptian kings are those of Breasted, whose chronological table at the end of his *History of the Ancient Egyptians*, 1908 (an abbreviation of the *History of Egypt*, 1906) may usefully be consulted. The only deviation is in the dates given for Amenhotep I. and Thutmose I., where a complicated question of succession arises, involving the reign of Thutmose II. (who for our purpose is a nonentity) in relation to that of Thutmose III. Cf. Hall, *NE.* pp. 286 ff., whose conclusions are assumed, and whose dates, as given in the Table, p. 228, have been adopted.

|| Cf. Breasted, *AR.* ii. §§ 79, 81, 85.

¶ *Ibid.* ii. §§ 391 ff.

** Cf. Müller, *AE.* pp. 157 ff.: *Die Palästinaliste Thutmosis III.*, *MVAG.*, 1907, 1. Petrie, *Hist. Eg.* ii. pp. 320 ff., attempts to find a systematic arrangement in the list, and offers identifications, many of which must be deemed highly precarious.

and 78), which have been read respectively as Ja'cob el and Joseph-el.* The remainder of this campaign was occupied with the reduction of three cities on the southern slopes of the Lebanon.

The second, third, and fourth campaigns seem to have been fully spent in consolidating the conquests of the first. During the course of the second campaign it is interesting to note that Thutmosi received a present (which he describes as 'tribute') from the far-off kingdom of Assyria, which at this period was beginning to rise into prominence. Northern Syria, however, with Kadesh on the Orontes as a centre of disaffection, still remained untouched; but the fifth campaign made substantial progress towards this objective through the reduction of the coast-cities of Phoenicia. The sixth campaign is highly important as marking the first transport of the Egyptian army by sea to Syria. The establishment of a base in the Phoenician harbours meant that thenceforward Thutmosi could get within striking distance of northern Syria after a few days' sail; and the hold of Egypt upon the coast-land of western Asia was thus materially strengthened. In the sixth campaign Kadesh was captured after a long siege. The account of this campaign is interesting as preserving record of Thutmosi's policy for securing the future allegiance of Syria. The sons of the conquered chieftains were carried back to Egypt to be educated, in order that, imbued, as it was hoped, with Egyptian ideals and sympathies, they might in time succeed their fathers as faithful vassals of their suzerain.

After a seventh campaign directed against Arvad and Simyra, Thutmosi reached, in his eighth campaign, the climax of his successes. Advancing into Naharin, he met and defeated 'that foe of wretched Naharin,' *i.e.*, probably, the king of Mitanni,† captured Carchemish, and crossing the Euphrates, set up his boundary-tablet upon its eastern bank beside that of Thutmosi I. 'Heta the Great,' *i.e.* the Hittites of Cappadocia, now sent him presents; and it is even possible that he may have received them from Babylon.§ Thutmosi's remaining campaigns in Syria were occupied in quelling revolts and generally consolidating the broad territory which he had won.

Egypt's Asiatic Empire was maintained unimpaired under the

* The latter equivalence is very doubtful, since the sibilants do not correspond. Nos. 35 and 18, which have been read *Š-m'-n* and understood as Sime'on, appear to lack the ' (y). W. M. Müller (*Die Palästinaliste Thutmosis III.*) transcribes both as *Ša-ma-na*. Cf. his remarks on p. 15.

† Cf. Breasted, *AR.* §§ 476, 479; Hall, *NE.* p. 241. W. M. Müller regards the view that the king of Mitanni was overlord of the whole of Naharin as questionable: cf. *AE.* p. 251.

§ It is a disputed question whether we should find allusion to 'tribute of the chief of Shin'ar,' or whether the reference is to Singara, *i.e.* the modern Gebel Singar, north-west of Nineveh. Cf. Breasted, *AR.* ii. § 184 (*footnote*); Hall, *NE.* p. 242.

next two Pharaohs, Amenhotp II. (*cir.* B.C. 1448) and Thutmosi IV. (*cir.* B.C. 1420), though both these monarchs had to quell rebellions which broke out in northern Syria and Naharîn at or shortly after their accessions.* The authority of Egypt was, however, effectively maintained by official representatives and garrisons in the larger towns; and the system of allowing the Syrian cities a large measure of autonomy under their petty chieftains proved, on the whole, to be justified. The marriage of Thutmosi IV. with the daughter of Artatama, king of Mitanni in northern Mesopotamia,† was a judicious measure which gained for Egypt an ally upon the north-eastern limit of her Asiatic kingdom; and it was probably owing to this that Amenhotp III., the son of Thutmosi by his Mitannian queen, succeeded to the empire without having to meet any insurrection on the part of the turbulent elements in Naharîn.

For the reigns of Amenhotp III. (*cir.* B.C. 1411) and his successor Amenhotp IV. (*cir.* B.C. 1375), we possess the evidence of the correspondence discovered at Tell el-Amarna in Egypt in 1887,‡ which is of unique importance for the history of Syria and of the surrounding countries of western Asia in their relation with Egypt. At this period (as the T.A. Letters first proved to us||) the language of diplomacy and commerce in western Asia was Babylonian, and correspondence was carried on in the cuneiform script, written upon clay tablets. Many of these letters are addressed to the king of Egypt by the independent rulers of the neighbouring kingdoms of western Asia—Babylonia or Karduniaš (to give the kingdom its Kaššite name), Assyria, Mitanni, etc.—who were naturally concerned to preserve good diplomatic relations with Egypt. These,

* Cf. Breasted, *AR.* §§ 780 ff. ; 816 ff.

† Cf. T.A. Letters, Knudtzon, No. 29, ll. 16 ff.

§ The most recent edition of the T.A. Letters is that of J. A. Knudtzon, *Die el-Amarna Tafeln* (1908-15), which takes the place of H. Winckler's edition (*KB.* v, 1896) as the standard edition for scholars. The cuneiform text of the Berlin collection of tablets has been published by Abel and Winckler, *Der Thontafelfund von El-Amarna* (1889), and that of the British Museum collection of tablets by Bezold in Budge and Bezold, *Tel el-Amarna Tablets in the Brit. Mus.* (1892). All the original tablets were exhaustively collated by Knudtzon for his transliteration and translation of the texts. Böhl, *Die Sprache der Amarnabriefe* (1909) is important for philology.

|| Since the discovery of the T.A. Letters a few cuneiform tablets have been found at various Palestinian sites which have undergone excavation (cf., for the more important ones, Rogers, *CP.* pp. 278 ff.). The most important evidence for the widespread use of cuneiform Babylonian is found in the great store of tablets discovered by Winckler in his excavation of the site of the ancient Hittite capital (Uatti at Boghaz Keui east of the river Halys in Asia Minor. The first instalment of autographs of these documents has been published very recently (H. H. Figulla and E. F. Weidner, *Keilschrifttexte aus Boghazköi*, parts 1 and 2, Oct. 1916); but prior to this we possessed only Winckler's account of them in *MDOG.* xxxv. (Dec. 1907), containing extracts from some few which appeared to the discoverer to be among the more important. A fairly full abstract of this account has been translated into English in the *Annual Report of the Smithsonian Institution*, 1908 (some misprints in proper names).

though of first importance for the history of the times, do not here concern us, except incidentally. It is interesting, however, to notice the way in which such constant correspondence could be conveyed backwards and forwards through Syria, together with the valuable presents with which the letters were often accompanied, apparently without great risk of miscarriage.* There exists a passport-letter, addressed by an unnamed king—very possibly the king of Mitanni†—‘to the kings of Canaan, the servants of my brother’ (*i.e.* the king of Egypt), exhorting them to see that his messenger, Akiya, receives no hindrance, but is safely and speedily forwarded on his way to the Egyptian court (cf. Kn. 30).

It is the correspondence of the subject-kinglets which brings most vividly before us the condition of Syria at the time, and the causes which were leading to the gradual weakening of Egypt’s hold upon her Asiatic possessions. In the reign of Amenhotp III. the Egyptian empire was at its zenith, and the luxury and magnificence of the kingdom had never been surpassed. This, however, was due to the continuous efforts of the Pharaoh’s warlike ancestors: he seems himself to have been content to enjoy the fruits of past achievement, and not to have been greatly concerned with the maintenance of the tradition of empire-building. Thus already in his reign we discern the beginning of movements which were destined ultimately to bring about the decline of Egypt’s suzerainty over Syria.

It was under Amenhotp IV., however, that the crisis became acute. This king is remarkable as the introducer into Egypt of a new form of religion, a kind of philosophic monotheism which centred in the worship of the solar disc (called in Egyptian Aton). Repudiating his own name, he adopted the name Akhaton (‘Spirit of Aton’); and having removed his capital from Thebes, where the power and influence of the old religion were naturally at their strongest, he founded a new capital, some three hundred miles lower down the Nile and about one hundred and sixty miles above the Delta, to which he gave the name Akhetaton (‘Horizon of Aton’). This is the modern Tell el-Amarna. Wholly absorbed in his religious speculations and in domestic life, the king cared little about the fate of his Asiatic provinces; and letters from the native princes and governors of Syria speak again and again of the growing spirit of disaffection towards Egypt, or beg for assistance in the face of open revolt.

* There are, as might be expected, some complaints of molestation and robbery. Thus we find that the caravan of Šalmu, the messenger of Burnaburiaš, king of Karduniaš, was twice plundered on the way to Egypt in Egyptian territory (Syria-Palestine), and compensation is demanded of the Egyptian king (Kn. 7). On a later occasion (during the unsettled period of the north Syrian revolt) the merchants of Burnaburiaš were robbed and murdered (Kn. 8). Ašur-uballit, king of Assyria, says that Egyptian messengers have been waylaid by the Šutû, a nomad people (Kn. 16). Some of the Syrian chieftains express their willingness to provide provisions and safe escort for caravans (cf. Kn. 226, 255).

† Cf. Weber’s discussion in Knudtson, pp. 1072 ff.

The trouble arose principally from the encroachments of the Hittites upon northern Syria. As we have already remarked, in alluding to an incursion of this people into Babylonia some five hundred years earlier (cf. p. lxiv), the Hittites were an Anatolian race whose principal centre lay west of the Taurus, in the region which is known to us later on as Cappadocia. Our knowledge of them has been placed on a new footing in recent times (1907) through the excavations of Winckler at an ancient site near the modern village of Boghaz Keui, which proved to have borne the name of Hatti, and to have been the capital of the Hittite kingdom.* We are still, however, at a loss as to the racial origin of the Hittites. Their physiognomy, as depicted on their own and on Egyptian monuments—a prominent nose, high cheek-bones, and a retreating forehead and chin—is closely reproduced at the present day among the Armenians. They were certainly non-Semitic: and it does not seem probable (as has been variously suggested) that they were of Iranian or Mongolian origin. The inscriptions upon rock and stone, which are assumed (with practical certainty) to be Hittite work, are written in a peculiar pictographic script, and are still undeciphered. Attempts at decipherment have been made by several scholars upon different lines; † but they have not met with general acceptance or yielded results which are capable of utilization. The Hittite language, as written in cuneiform on tablets found at Boghaz Keui, and in the Arzawa letters which were found among the T.A. correspondence, cannot be connected with any known language.§ Fortunately, a large number of the documents from Boghaz Keui are written in Babylonian; and it is these which have so largely extended our knowledge.||

* Cf. *MDOG.* xxxv. pp. 12 ff.

† Cf. especially the articles by Sayce in *PSBA.* xxv.-xxvii. (1903-5).

§ Knudtzon has argued from the Arzawa letters that the language is Indo-Germanic (*Die zwei Arzawa-Briefe, die ältesten Urkunden in indogermanischer Sprache, mit Bemerkungen von S. Bugge und A. Torp*, 1902); but the theory has failed to gain acceptance (cf. e.g. the criticism of Bloomfield in *American Journal of Philology*, xxv. pp. 12 ff.), and, according to Weber (*Kn.* p. 1074), the author of it himself had some misgivings with regard to it. F. Hrozný (*MDOG.* lvi., December 1915, pp. 17-50) maintains the same conclusions upon the evidence of the Hittite documents from Boghaz Keui, which he is engaged in transcribing; but until some part at least of the rich material from Boghaz Keui has become the common property of scholars, it is impossible to pass judgment upon the theory. Hrozný has been criticized by Bork, *OLZ.* Okt. 1916, 289 ff., and by Cowley in a paper read before the Royal Asiatic Society in December 1916, which is as yet unpublished: cf. brief abstract in *JRAS.* for January 1917, pp. 202 f. The important Sumerian-Akkadian-Hittite vocabularies from Boghaz Keui, published in transcription by Delitzsch for the Berlin Academy (*Abhandl. k. p. Akad.*, 1914. 3), though of the greatest value for our interpretation of Hittite words, have not thrown any further light upon the linguistic affinities of the Hittite language.

|| The fullest and most recent book on Hittite excavation and history is Garstang, *The Land of the Hittites* (1910). See also King, *Bob.* pp. 225-41; Hall, *NE. ch.*

Of the early history of the Hittites we know nothing. Probably they formed at first a collection of semi-independent tribes, loosely united by the bond of a common extraction, and only temporarily acting together under one leader on such occasions as the raid on northern Syria and Babylonia which brought about the downfall of the First Babylonian Dynasty, *cir.* B.C. 1926 (cf. p. lxiv). Hattušili I., who was king of the city of Kuššar* (*cir.* B.C. 1400), was succeeded by his son Šubbiluliuma, who bound the Hittite clans into a strong confederation, and whose reign of probably some forty years (*cir.* B.C. 1385-1345) was a career of conquest resulting in the creation of an empire which lasted under one dynasty for nearly two hundred years.

In the latter years of Amenhotp III. we find Šubbiluliuma crossing the Taurus, and leading his forces to the attack of northern Syria. The safe retention of Naharín as an Egyptian province depended, as we have noticed (p. lxix), largely upon the goodwill of the king of Mitanni; and the alliance which had been contracted through the marriage of Thutmōsi IV. with a Mitannian princess had been further cemented by the union of Amenhotp III. with Gilu-Hipa, sister of Tušratta, the reigning king of Mitanni, and subsequently with Tadu-Hipa, Tušratta's daughter, who, after the death of Amenhotp III., became a wife of his successor, Ahnaton.† Tušratta, however, had succeeded to a kingdom weakened by internal intrigues, his brother, Artasšumara, who reigned before him, having been assassinated. He was strong enough to repel the Hittites from Mitanni for the time being,§ but could not prevent Šubbiluliuma from invading Naharín, where the projects of the Hittite king were furthered by another brother of Tušratta, named (like his grandfather) Artatama. This prince, having very possibly been implicated in the murder of Artasšumara, had been obliged to fly from Mitanni to Naharín, and, with his son Šutatarra, and grandson Itakama, of whom we hear later on as prince of Kinza or Kidša (*i.e.* the district of which the principal city was Kadesh on the Orontes) welcomed the opportunity of intriguing with the Hittites against Tušratta. Further south, in the district of the Lebanon, Abd-

viii.; Hogarth, article 'Hittites' in *Encyc. Britann.*,¹¹ vol. xiii.; Weber in Kn., pp. 108 ff.; Ed. Meyer, *Reich und Kultur der Chetiter* (1914); Luckenbill, *AJTh.* xviii. (1914), pp. 24 ff. For the Boghaz Keui documents, cf. Winckler, *MDOG.* xxxv.; *OLZ.* xiii. (1910), 289 ff. For an account of the excavations at Boghaz Keui, cf. Puchstein, *Boghazköi: die Bauwerke* (1912).

* The site of this city is unknown.

† Unlike the Mitannian wife of Thutmōsi IV., who was the mother of Amenhotp III., both Gilu-Hipa and Tadu-Hipa occupied the position of inferior wives only. The influential Tii, who was chief wife of Amenhotp III. and mother of Ahnaton, seems to have been of Semitic origin on her father's side. Nefertiti, the queen of Ahnaton, is now known to have been his full sister (the daughter of Tii); and Petrie's view (*Hist. Eg.* ii. p. 207) that she is identical with Tadu-Hipa is thus disproved; cf. Hall, *NE.* pp. 255 f., 258, n².

§ Cf. Kn. 17.

Aširta, who was chieftain of Amurru,* perceived that his own interests would best be served by making common cause with the Hittites, and attacking the rulers of the Phoenician coast-cities, who were loyal to Egypt. For a time this Amorite prince and his son Aziru managed with amazing astuteness to pass themselves off as faithful vassals of Egypt, in spite of the urgent representations of Rib-Adda, the governor of Gebal, who displayed the utmost energy in the Egyptian cause. Amenhotp III. seems at length to have been convinced of the true state of affairs and to have despatched an army; and the tension was temporarily relieved.† Under Ahnaton, however, no such help was forthcoming; and the Phoenician cities fell one after another into the hands of the Amorites.§

Meanwhile in the south affairs were little better; local dissensions were rife among the petty Canaanite princes, and we find them engaged in active intrigue against their suzerain, and at the same time sending letters to the Pharaoh full of protestations of loyalty and accusations against their neighbours. So far as we can judge, ARAD-Hiba, the governor of Jerusalem, stood faithfully for the interests of the Egyptian king; but he seems to have stood almost alone. His letters make urgent and repeated requests for the despatch of Egyptian troops, and state that unless they can speedily be sent the whole country will be lost to Egypt. The part played by the Hittites and Amorites in the north is filled in the south by a people called Habiru.||

The Habiru are mentioned under this name in the letters of ARAD-Hiba only.¶ He states that they have plundered all the king's territory and occupied his cities; unless the king can send troops before the end of the year, the whole of his territory will certainly fall away to them. Certain of the vassals, notably one Milkili and the sons of Labaya, are accused of conspiring with the Habiru and allowing them to occupy the king's territory; and the district of Shechem** seems to be specified as having thus passed into their hands. The cities of Gezer, Ashkelon, and Lachish

* On the sense in which the term Amurru is used in the T.A. Letters, cf. p. 41.

† Cf. Kn. 117, ll. 21 ff.

§ For a fully detailed account of the movements of Šubbiluliuma, and the north Syrian rebellion, cf. the admirable section in Hall, *NE.* pp. 341 ff., whose view of the relation of Artatama and his descendants to the reigning king of Mitanni is followed above.

|| Most writers refer to this people as Habiri; but, as Knudtzon points out (cf. p. 45, n), out of the seven (or eight) passages in which they are mentioned the form is *Habiru* in the two cases in which the name stands as a Nominative, *Habiri* (with the Genitive termination) being in all occurrences an oblique form. So Dhorme, *RB.*, 1909, p. 67, n².

¶ This series of letters has been translated into English by Ball, *Light from the East*, pp. 89-93, and by Rogers, *CP.* pp. 268-278.

** (*Mātu*) *Ša-ak-mi*, according to Knudtzon's reading (289, l. 23). Winckler (185) fails to make satisfactory sense of the passage.

appear to have been implicated in assisting them.* Indeed, ARAD-Ḥiba states that he has been obliged to tax the king's own high commissioner with paying into their hands, and that on this account he has been slandered to the king. In this last reference (Kn. 286, ll. 16 ff.) the question addressed to the commissioner—'Wherefore lovest thou the Ḥabiru, and hatest the city-governors?'—sets them in contrast to the latter,† who represented the delegated authority of Egypt.

The question of the identity of the Ḥabiru has aroused greater interest and keener discussion than any other point raised by the T.A. Letters. Were they, as has often been alleged, identical with the *Hebrews*, i.e. with the clans which are pictured in Gen. as the descendants of Abraham the Hebrew, who may very well have been pressing into Canaan at about this period? Were they even (as has been more boldly suggested‡) the tribes of Israel engaged under Joshua in the invasion and conquest of the Promised Land? The acceptance of this latter view involves the abandonment of the commonly received conclusion as to the date of the Exodus, and the placing of this event at least some two hundred years earlier (cf. pp. cxvif.).

The philological equivalence of (*amēlûtu*) *Ḥa-bi-ru* || with עִבְרִי *'ibhrî*, 'Hebrew'—or rather, since the form is not a gentile, with עֵבֶר *'Ebher*, Εβερ (Gen. 10²¹, 11¹⁴, *al.*)—is perfect. About this there can be doubt at all.§

* This is an inference only; though a fairly certain one. In the letter in question (Kn. 287) there comes a break of about eight lines, after which ARAD-Ḥiba continues, 'let the King know that all the states are leagued in hostility against me. Behold, the land of Gezer, the land of Ashkelon, and Lachish gave unto them food, oil, and everything that they needed; so let the King have a care for his territory, and despatch bowmen against the men who have done evil against the King my lord.' Here it can scarcely be doubted that the object implied in 'gave unto them' is the Ḥabiru, who must have been mentioned in the missing passage. So Weber in Kn. p. 1337.

† The term *ḥazan(n)u*, *ḥazianu*, plur. *ḥazanātu*, is doubtless the same as New Heb. *ḥazzān*, which means *inspector* or *overseer*. Cf. the reference to Ja'cob as a 'city-overseer' (*ḥazzan mātā*) under Laban, quoted by Buxtorf, *Lexicon*, s.v. from *Baba meṣia*. The ordinary New Heb. usage of *ḥazzān* to denote a synagogue-overseer or minister is technical and secondary. Besides the title *ḥazzan*, the ordinary title by which the Syrian and Palestinian vassal-chieftains describe themselves to the Egyptian king, and are described by him (cf. Kn. 99), is *amēlu*, 'man' of such and such a city. To outsiders they are *šarrānū* 'kings' (cf. Kn. 30), a title which is familiar to us as applied to them in the O.T., and which was doubtless always claimed by them when independent of the suzerainty of Egypt.

§ So, most recently, Hall, *N.E.* pp. 469 ff.

|| *Amēlātu* 'men,' or sing. *amēlu* 'man,' are used as Determinatives before the names of tribes or classes.

¶ Handcock (*The Latest Light on Bible-lands*, pp. 79-81) is mistaken in supposing that 'the crucial point' in the identification is whether the Heb. *y* can be equated with the Bab. *ḥ*, and in concluding that such an equation 'is totally at variance' with 'the ordinary rules of philological transmutation'; and his pronouncement—

Discussion of the identity of the Ḥabiru with the Hebrews is closely bound up with another question of identification. As we have observed, the (*amēlātu*) *Ḥa-bi-ru* (or *-ri*) are only mentioned in this form (i.e., their name only occurs spelt out syllabically) in the letters of ARAD-Ḥiba. Many other letters, however, mention a people whose name is written ideographically (*amēlātu*) SA.GAZ, who occupy a position as freebooters and aggressors against constituted authority identical with that occupied by the Ḥabiru. The question is whether SA.GAZ is merely the ideographic method of writing *Ḥabiru*, and the reading *Ḥabiru* to be assumed wherever the ideogram occurs. The importance of this is to be found in the widespread character of the aggressions of the SA.GAZ. If the Ḥabiru are identical with them, they must have permeated not merely southern and central Canaan, but also Phœnicia and northern Syria; for the SA.GAZ are mentioned, e.g., with especial frequency in the letters of Rib-Adda of Gebal as employed by

coming as it does in a popular work—is liable to mislead. Granted that the *y* in עֲבָרִי is probably soft (as may be assumed from the *ḡ* form 'Εἰσπαῖος), we have, in addition to *Kinahhi*=כִּנְחִי (rightly cited by Handcock) the following examples of Bab. *ḥ*=Heb. soft *y* among the Canaanite 'glosses' in the T.A. Letters:—*ḥi-na-ia*=עִינִי; *ḥa-pa-ru* (also *a-pa-ru*)=עָפָר; *ḥa-zi-ri*=עֲצִיר (עֲצִיר); *zu-ru-uḥ*=זָרוּעַ (cf. references in Böhl, *Die Sprache der Amarnabriefe*, p. 15). Cf. also *ba-aḥ-lum*=בָּעַל in the proper names *Pu-ba-aḥ-la* (Kn. 104, l. 7), and *Mu-ut-ba-aḥ-lum* (Kn. 255, l. 3); and the place names (*ḥlu*) *Ṣa-ar-ḥa* (Kn. 273, l. 21)=צָרְחָה, ḡ Σαπαα; (*ḥlu*) *Ḥi-ni-a-nu-bi* (Kn. 256, l. 26)=עֵין עֲנַב, the עֲנַב of Josh. 11²¹, 15⁵⁰; (*ḥlu*) *Ṣa-am-ḥu-na* (Kn. 225, l. 4) perhaps=שִׁמְעוֹן, Jos. (*Vita*, 24) Σιμωνίως, modern Semūniyyeh, five miles west of Nazareth, perhaps the Biblical נִשְׁמֶרוֹן, Josh. 11¹, 12²⁰, 19¹⁵, which appears in ḡ as Συμων (cf. Buhl, *Geogr.* p. 215); (*ḥlu*) *Ta-aḥ-[nu-ka]* (Kn. 208, l. 14)=Ta'anakh (Tell Ta'annuk). Were it necessary to go outside the T.A. Letters, we might add to this list by such Amorite proper names in First Dynasty tablets as *Ḥam-mu-ri*, where the first element in the West Semitic עֲמוֹ (cf. *Ḥa-mu-ni-ri* by the side of *Am-mu-ni-ra* in the T.A. Letters); *A-bi-e-ṣu-uḥ* (by the side of *A-bi-e-ṣu*)=אֲבִישֻׁעַ; *Ya-di-iḥ-el*=יְדִיעֵאל (cf. 1 Chr. 7^{6 ff}, 11⁴⁵, 12²¹, 26²); *Ya-aṣ-ma-aḥ-(ilu)-Da-gan*=יִשְׁמַעֲדָן, etc.

As for the vowels—they offer no difficulty. Dhorme's statement (*RE.*, 1909, p. 72) that *Ḥabiru* is a participial form is unwarranted (we never find it written *Ḥa-a-bi-ru*, i.e. *Ḥābiru*). *Ḥabiru* is of course not a gentilic form like Heb. sing. 'ibhrī, plur. 'ibhrīm (the Bab. gentilic form would be *Ḥabirā*; cf. p. lxxxi), but a substantive form like עֲבָר 'ēbher (the eponym of 'ibhrī) with the nominative case-ending. The short *i* vowel in *Ḥabiru* might very well vary: cf. *Armu*, *Aramu*, *Arīmu*, *Arumu*=Heb. אֲרָם 'Arām. A good analogy for *Ḥabiru*=עֲבָר may be seen in *Bit Adini*=בֵּית-עֵדֵן, Beth-'Eden (probably עֵדֵן should be עֵדֵן, but is differentiated by 𐎠 from the עֵדֵן of Gen. 2: cf. Müller, *AE.* p. 291, n⁴).

Abd-Aširta and Aziru in the reduction of the Phoenician cities.* The view that SA.GAZ is to be read as *Ḫabiru*, which has always been regarded with favour by the majority of scholars, is now generally supposed to have been placed beyond question by Winckler's discovery of the interchange of the two terms in documents from Boghaz Keui. This scholar states ‡ that, besides mention of the SA.GAZ-people, there is also allusion to the SA.GAZ-gods, and that as a variant of this latter there exists the reading *ilāni Ḫa-bi-ri*, i.e. 'Ḫabiru-gods.' This discovery, while certainly proving a general equivalence of the Ḫabiru with the SA.GAZ, does not, however, necessarily involve the conclusion that SA.GAZ in the T.A. correspondence was always and everywhere *understood and pronounced as Ḫabiru*: indeed, the contrary can be shown to be the case.

In a syllabary given in ii. R. 26, 13 *g-h*, (*amēlu*) SA.GAZ is explained by *ḫab-b[a-tum]*, 'robber' or 'plunderer.' In another tablet the ideogram is glossed by *ḫab-ba-a-te*.§ No doubt the common Bab. verb *šagāšu*, which means *to destroy, slay*, and the like, is a Semiticization of the Sumerian ideogram; and the element GAZ, which in its pictographic form clearly represents a cutting or striking weapon, has by itself the values *dāku*, 'to kill, fight, strike,' *muhāšu*, 'to smite, wound' (Heb. מַחֵה, etc. || Possibly the root *ḫabātu*, from which *ḫabbatum* is derived, though it regularly means 'to plunder,' may have an original connexion with the root *ḫbt* which runs through Heb., Aram., and Ar., with the sense 'to strike or beat,' in which case the root-sense of *ḫabbatum* would be 'cut-throat' rather than 'thief' (the two actions are commonly united among the nomad tribes of the Arabian desert). That (*amēlu*) SA.GAZ has its normal value in the T.A. Letters is placed beyond a doubt by the occurrence in a letter from Yapahi of Gezer (Kn. 299, l. 26) of the form (*amēlu*) SA.GAZ.MEŠ(-*tum*).¶ Here *-tum* is a Phonetic Complement,** pointing to a Bab. equivalent which ends with this syllable, a fact which indicates *ḫabbatum* and excludes *Ḫabiru* (or *-ri*). In view of this we may infer that in a passage in

* A summary of all allusions to the SA.GAZ is given by Weber in Kn. p. 1147.

‡ Cf. *MDOG.* xxxv. p. 25, n. For the former, cf. Figulla and Weidner, *Keilschrifttexte* 1, No. 1, Rev. l. 50; No. 3, Rev. l. 5; for the latter, No. 4, Rev. col. iv. l. 29.

§ Cf. R. C. Thompson, *The Reports of Magicians and Astrologers of Nineveh and Babylon*, i. No. 103, Obv. 7.

|| Cf. Br. 4714 ff.

¶ MEŠ, which means 'multitude,' is used as the sign of the plural.

** A Phonetic Complement is often used in cuneiform in order to obviate doubt as to the precise Bab. word or form denoted by an ideogram. Thus, e.g., the name Uta-napištim, which is commonly written ideographically UD.ZI, often has the syllable *-tim* added to indicate that ZI has the value *napištim*. MU, which means 'to speak' in Sumerian, and so can be used for the Bab. *zakaru* with the same meaning, may be written MU (-*ar*), MU (-*ra*) to indicate the precise form of the verb *izakkar*, *izakkaru*. Thus perfect clearness is gained without the labour of writing the forms syllabically *i-zak-kar*, *i-zak-ka-ra*.

a letter from Dagan-takala (Kn. 318) in which he begs help of the King of Egypt—‘Deliver me from the mighty foes, from the hand of the (*amēlātu*) SA.GA.AZ.MEŠ, the robber-people (*amēlātu ha-ba-ti*), the Šutû (*amēlātu Šu-ti-i*)’—we have, not the specification of *three* distinct classes of foes, but of two only, *amēlātu ha-ba-ti* being simply an explanatory gloss on (*amēlātu*) SA.GA.AZ.MEŠ *

We conclude, then, that wherever the ideogram SA.GAZ stands in the T.A. Letters, the equivalent that was *understood and read* was not *Ḥabiru* but *habbatum*, ‘the robber-people’ or ‘brigands.’ It is a different question whether the *Ḥabiru* were included among the people who could be classed as *habbatum*. That this is to be affirmed appears to be certain from the equivalent ‘SA.GAZ-gods’=‘*Ḥabiru*-gods’ discovered by Winckler in the documents from Boghaz Keui (cf. p. lxxvi). When, further, while ARAD-Ḥiba refers exclusively to the encroachments of the *Ḥabiru* and does not mention the SA.GAZ, other princes in the south refer in a similar connexion and in similar terms to the encroachments of the SA.GAZ and make no allusion to the *Ḥabiru*, the inference is inevitable that the terms *Ḥabiru* and SA.GAZ refer in these letters to one and the same people.†

We must notice next that SA.GAZ, though meaning *habbatum*, ‘robbers,’ is not, as used in the T.A. Letters, a *mere* class-term (*i.e.* applicable to any body of people, of whatever race, who might

* It is true that *amēlātu ha-ba-ti* is not preceded by the diagonal wedge which as a rule marks a gloss; but this is sometimes omitted (cf. Kn. 148, l. 31; 288, l. 34. In 288, l. 52, the wedge *follows* the gloss at the beginning of the next line). The fact that Dagan-takala (or his scribe) did not know the ideogram GAZ, and so was obliged to write GA.AZ (which only occurs in this passage), favours the view that he may have glossed the ideogram in order to avoid misunderstanding. Dhorme (*RB.*, 1909, p. 69) compares Kn. 195, ll. 24 ff., where Namyawaza offers to place his SA.GAZ and his Šutû at the disposal of the Pharaoh. ‘These in fact are the two designations which describe the soldiers of the irregular and rebel army. There is no ground for regarding the *Ḥa-ba-ti* as a third group. Everything thus favours reading GAZ or SA.GAZ as *Ḥabbatu*.’ In Kn. 207, l. 21, we actually find (*amēlu*) GAZ.MEŠ followed by the diagonal wedge and then the syllable *ha-*, after which the tablet is broken and illegible.

† Cf. especially ARAD-Ḥiba’s statement, ‘Behold, this deed is the deed of Milkili and the sons of Labaya, who have given up the King’s territory to the *Ḥabiru*’ (Kn. 287, ll. 29 ff.), with the statement of Biridiya of Megiddo, ‘Behold, two sons of Labaya have gi[ven] their money to the SA.GAZ’ (Kn. 246, ll. 5 ff.). Cf. also the words of Labaya, ‘I do not know whether Dumuya has gone with the SA.GAZ’ (Kn. 254, ll. 32 ff.); and of Milkili, ‘Let the King my lord know that hostility is mighty against me and Šuwardata; and let the King deliver his land out of the hand of the SA.GAZ’ (Kn. 271, ll. 9 ff.); and of Bēlit-UR.MAḤ.MEŠ (Ba’alath-Leba’oth? Cf. Josh. 15²², 19⁶. UR.MAḤ.MEŠ means ‘lions’), ‘the SA.GAZ have sent to Aijalon and Sor’ah, and the two sons of Milkili were nearly slain’ (Kn. 273, ll. 18 ff.). The fact that Labaya and Milkili should themselves represent their relations with the SA.GAZ somewhat differently from ARAD-Ḥiba and Biridiya is only to be expected. The statements of ARAD-Ḥiba—‘Let the King hearken unto ARAD-Ḥiba thy servant, and send bowmen, and bring back the King’s territory to the King. But if there be no bowmen, the King’s territory will certainly fall away to the *Ḥabiru*’

adopt a bandit-life), but is definitely employed of a tribe or tribes from a *particular locality*, and united by racial affinity. This is clear from the fact that the ideogram is followed in two of its occurrences by the affix KI, 'country or place,'* which is used both with the names of countries and districts and with the names of tribes emanating from such districts. In one occurrence of Ḥabiru we likewise find KI added,† marking the term similarly as racial and not merely appellative. We may assume, then, with confidence that the connexion between the Ḥabiru and the SA.GAZ was a racial one; though it does not necessarily follow that *all* the SA.GAZ were Ḥabiru—since, on the evidence which we have reviewed, there is nothing to forbid the theory that the Ḥabiru may have been but a single clan of a larger body of people called SA.GAZ.‡

Is it probable, then, that the Ḥabiru were merely the southern branch of the racial movement into western Syria represented by the aggressions of the SA.GAZ? That they had gained a footing not only in the extreme south (the district round Jerusalem) but also in central Canaan is clear from the facts that they are mentioned as in occupation of Shechem (cf. p. lxxiii), and that the prince of Megiddo expresses anxiety as to their movements (cf. p. lxxvii, *footnote*). But there is another reference in one of ARAD-Ḥiba's letters which seems to identify them with the SA.GAZ still further north. 'When there was a ship (*or* a fleet?) at sea,' he writes, 'the king's strong arm held the land of Naḥrima and the land of Kapasi(?); but now the Ḥabiru hold all the king's cities' (Kn. 288, ll. 33 ff.).§ Here the allusion undoubtedly is to the Egyptian fleet which, since the victorious campaigns of Thutmose III., had possessed a base in the Phoenician harbours (cf. p. lxxviii), and enabled the Pharaoh to reach Naharin (Naḥrima) with little delay and suppress any inclination to revolt in the extreme northern part of his Asiatic empire. Now, however, in the absence of this fleet, the Ḥabiru are in the ascendant, and are holding either the cities of Naḥrima in the north, or (more probably) the Phoenician cities which it was necessary for Egypt to hold in order to maintain her footing in the ports. Adopting this latter hypothesis, we see at once that the SA.GAZ to whom Rib-Adda of Gebal so constantly alludes as employed by the Amorite chieftains Abd-Aširta and Aziru for the reduction of

(Kn. 290, ll. 19 ff.); 'Should there be no bowmen this year, the King my lord's territories are lost' (Kn. 288, ll. 51 ff.)—are strikingly similar to the statement of Bayawa, 'Unless Yanḥamu [the Egyptian plenipotentiary] arrives this year, the entire territories are lost to the SA.GAZ' (Kn. 215, ll. 9 ff.); and it can hardly be doubted that the reference in each case is to the same peril.

* Kn. 215, l. 15; 298, l. 27.

† Kn. 289, l. 24.

‡ So Dhorme, *RB.*, 1909, p. 69.

§ The rendering here adopted is that which is generally accepted (cf. Winckler, Ball, Rogers, etc.), from which there seems no reason to depart. It is difficult to believe that Knudtzon's rendering is correct; still less that of Ungnad in *TB.* i. p. 133.

the Phoenician cities were Uabiru, as well as the southern aggressors. This is a point of the first importance for the elucidation of the Habiru-question.

The close connexion of the SA.GAZ-Habiru with the people called Sutû is evident. Both peoples are in the service of Namya-waza as mercenaries (Kn. 195, ll. 27 ff.); both commit aggressions upon Dagan-takala (Kn. 318), and, apparently, upon Yapahi of Gezer (Kn. 297-99). Rib-Adda of Gebal, who complains repeatedly of the aggressions of the SA.GAZ, also states that one Pahura has sent Sutû who have killed his Šerdanu mercenaries (Kn. 122, ll. 31 ff). Concerning the Sutû we happen to be fairly well informed. We learn from a chronicle that the Kaššite king Kadašman-Ḫarbe I. (cir. end of the fifteenth century B.C.) 'effected the conquest of the marauding Sutû from east to west, and destroyed their power, built fortresses in Amurru,' etc.* Adad-Nirari I. of Assyria (cir. B.C. 1325) states that his father Arik-dên-ili 'conquered the whole of the wide-spreading Kutû, the Aḫlamû, and Sutû.'† The Aḫlamû are known to have been an Aramaean nomadic or semi-nomadic people. The Hittite king Hattušili II. makes 'the Aḫlamû-peril' his excuse for having ceased diplomatic relations with the king of Karduniaš (Kadašman Enlil II. §). Tiglath-Pileser I. (cir. B.C. 1100) tells us that he defeated 'the Aramaean Aḫlamû' who inhabited the district in the neighbourhood of Carchemish.|| It is clear from these references that the Sutû must have been a nomad tribe inhabiting the northern part of the Syrian desert to the west of the upper Euphrates¶; and with this agrees the statement of Ašur-uballiṭ that the Sutû have detained the messengers of Aḫnaton (Kn. 16, ll. 37 ff.), since the Egyptian envoys would have to cross the desert on their way to Assyria.

Now the Egyptian term for the Semitic nomads of the Asiatic desert is *šasu*, a word which seems to be foreign to the language, and which has been plausibly connected with the West Semitic root שָׁסַ *šāsā*, 'to plunder.'** The *šasu*, then, are simply 'the plun-

* Cf. Winckler, *AF*. i. p. 115. Winckler makes Kadašman-Ḫarbe the second king of that name (cir. B.C. 1252); but cf. King, *Bab.* p. 243, n¹.

† Cf. Tablet, ll. 19 f. in *KB*. i. p. 4; Budge and King, *Annals of the Kings of Assyria*, p. 6; and, for the reading Arik-dên-ili and not Pudi-ilu, King and Hall, *Egypt and Western Asia*, p. 396.

§ *MDOG*. xxxv. p. 22. Text in Figulla and Weidner, *Keilschrifttexte* 1, No. 10, Obv. ll. 36 f.

|| Cf. *Annals*, v. ll. 44 ff. in *KB*. i. p. 32; Budge and King, *op. cit. supra*, p. 73.

¶ It is generally supposed the Shoa' and Koā' of Ezek. 23²³ are the Sutû and Kutû. On the Sutû in relation to the Aramaeans, cf. Streck, *Ueber die älteste Geschichte der Aramäer*, in *Klio*, vi. (1906). pp. 209 ff.

** Cf. Müller, *AE*. p. 131; Meyer, *IV*. p. 324. The Semitic root is only known to occur in Heb. where it is fairly frequent. Meyer (*loc. cit.*, n¹) notices the interesting fact that it is used in 1 Sam. 14⁴⁸, which relates Saul's conquest of the Amalekite Bedawin on the border of Egypt:—'he smote 'Amalek, and delivered Israel from the hand of his plunderer' (שָׁסָהוּ).

derers or brigands'; and the agreement of this designation with the Bab. *habbatum*, which, as we have seen, is the equivalent of the ideogram SA.GAZ, can hardly be merely accidental (cf. p. lxxxviii). While, therefore, the meaning of SA.GAZ favours the conclusion that the appellation belongs to a nomad people, the connexion of the SA.GAZ with the Sutû suggests that, like these latter, they belonged to the north Syrian desert, the region which both cuneiform and Biblical records associate with the Aramaeans. These facts should be taken in connexion with the further facts that the SA.GAZ are principally mentioned as employed by Abd-Aširta and his sons, and that the land of Amurru, over which these chieftains held sway, extended (as Winckler has proved from the Boghaz Keui documents *) from the Lebanon eastward across the Syrian desert to the Euphrates, thus embracing precisely the northern part of the desert inhabited by Aramaean nomads. Thus the conclusion that the SA.GAZ—and therefore the Ḫabiru—were Aramaean nomads seems to be raised to a practical certainty. ‡

Now the O. T. definitely connects the ancestors of the Hebrews with the Aramaeans. Abraham is not himself termed an Aramaean, but he has Aramaean connexions. Rebeḳah, the wife of his son Isaac, is brought from Aram-naharaim, and is the daughter of Bethuel, the son of Nahor, his brother (Gen. 24 J.). Bethuel is termed 'the Aramaean' (Gen. 25²⁰ P, 28⁵ P), and so is his son Laban, the brother of Rebeḳah (Gen. 31^{20,21} E). Ja'cob's wives are Aramaeans (the daughters of Laban), and he himself is called 'a vagabond Aramaean' (אַרְמִי אֹנֶיֶךָ, Deut. 26⁵). On his return from Paddan-Aram he re-enters Canaan bearing the new name Israel (Gen. 32²⁸ J, 35¹⁰ P) together with his many sons (or *clans*), and takes up his abode at or near Shechem, concerning his relations with which city variant traditions are extant.§ The mere fact, then, that the situation pictured in the T.A. Letters is that Aramaean nomads are flocking into Syria-Palestine and taking

* *MDOG.* xxxv. pp. 24 f. Cf. also King, *Bab.* pp. 237 f.

‡ That Abd-Aširta and his sons were aspiring to raise Amurru to the status of an independent kingdom like the powerful kingdoms on its borders was the opinion of Rib-Adda, as appears from Knudtzon's reading of three passages in his letters, as interpreted by Weber (cf. Kn. p. 1101; so Dhorme, *RB.*, 1909, p. 69). In Kn. 76, ll. 11 ff., Rib-Adda says, 'Who is Abd-Aširta, the dog, that he should seek to take for himself all the cities of the King, the Sun? Is he the king of Mitanni, or the king of Kaššu [Karduniaš] that he should seek to take the King's land for himself?' In Kn. 104, ll. 17 ff.; 116, ll. 67 ff., we find similar rhetorical questions with regard to the sons of Abd-Aširta, the last passage adding comparison with 'the king of Ḫata,' i.e. the Hittites. Comparison of these three passages one with another proves that this interpretation is correct, rather than that offered by Winckler, which suggests that Abd-Aširta and his sons were acting *in the interests of* the king of Mitanni, etc. The passages, then, indicate the wide scope of Abd-Aširta's schemes, and also suggest that he and his sons were largely responsible for organizing the flow of the Aramaean tribesmen westward into Syria-Palestine.

§ Cf. note on 'Shechem,' pp. 260 f.

forceful possession of many of its cities might by itself lead us plausibly to infer that the southern wing of this immigration probably included the ancestors of Israel—more especially since ARAD-Hiba states that they (the Habiru) are in possession of the land of Shechem (cf. p. lxxiii). When, moreover, we add to this the fact that the equivalence between the names 'Habiru' and 'Hebrew' is perfect (p. lxxiv f.), the inference is surely raised to a high degree of probability.

The only fact which should make us hesitate in assuming the identity of the Habiru with the Hebrews as proved beyond the possibility of a doubt is the occurrence of the term *Ha-bir-a-a*, i.e. a gentile form 'Habiraeon,' in two Babylonian documents: in each case in application to men who bear Kaššite names—Harbišihu* and Kudurra.† If, as it is reasonable to suppose, *Ha-bir-a-a* is the gentile of *Habiru*,‡ the fact that the only two names of Habiru-people that are known to us should be Kaššite is certainly remarkable; and the conclusion that the Habiru were Kaššites has been adopted by several scholars.¶ Recently, Scheil has published a tablet bearing a brief memorandum which mentions the Habiru (*amēlu Ha-bi-ri* exactly as in the T.A. Letters) at Larsa in the reign of Rim-Sin, six centuries earlier than the T.A. Letters.¶ This scholar's conclusion (based on this occurrence and on the Kaššite names above-mentioned) is as follows:—'The Habiru were in origin an Elamite, Kaššite, or Lower Mesopotamian people. . . . In any case they served among the forces of the Elamite dynasty at Larsa. Without doubt they were also employed in the far countries to the west, where the supremacy of Kudur-Mabuk, Hammurabi, Ammiditana, etc., maintained itself with more or less authority, thanks to the presence of armed troops.' The proof that Kaššite troops were stationed by these monarchs in Amurru (Syria-Palestine) is, however, non-existent: and still less (apart from the

* Cf. iv. 2 R. 34, 2; and, for a transliteration and translation of the document, Winckler, *AF* i. pp. 389-396. The letter, written by an unnamed Babylonian king, mentions a king of Assyria named Ninib-Tukulti-Ašur, who seems to have reigned towards the end of the thirteenth century B.C. (cf. Johns, *Ancient Assyria*, pp. 66 ff.), i.e. during the latter part of the Kaššite period in Babylon.

† Cf. Scheil, *Recueil de Travaux*, xvi. (1894), pp. 32 f. The name occurs on a boundary-stone of the time of Marduk-ahi-erba of the Fourth Babylonian Dynasty (B.C. 1073).

§ Hommel, however, regards the similarity between Habiru and Habirâ as purely fortuitous, taking the latter to mean an inhabitant of the land of Hapir or Apir, i.e. that part of Elam which lay over against eastern Arabia. Cf. *AHT*. p. 236; *Grundriss*, p. 7.

¶ So Halévy in *Journal Asiatique* (1891), p. 517; Scheil in *Recueil de Travaux*, loc. cit.; Hilprecht, *Assyriaca* (1894), p. 33, n.; Reiner in *JBL*. (1897), pp. 143 ff.; Lagrange in *RB*. (1899), pp. 127 ff.

¶ *Revue d'Assyriologie*, xii. (1915), pp. 114 f. The memorandum runs: 'These are 4 (or 5?) garments for the officers of the Habiru which Ibni-Adad . . . has received. Levied (?) on the property of the temple of Šamaš by Ili-ippalzam. [Month of] Nisan, 11th day, [year of] Rim-Sin, King.'

assumption that the Ḫabiru were Kaššites) can the presence of such troops in the west be proved for six centuries later.*

* It is true that ARAD-Ḫiba speaks of the outrages committed by the Kaši people, who seem on one occasion nearly to have killed him in his own house (Kn. 287, ll. 32 f., 71 ff.); and Biridiya of Megiddo apparently couples them with the SA.GAZ as in the pay of the sons of Labaya (Kn. 246, ll. 5 ff.: the reading is uncertain, as the tablet is broken; but traces of *Ka-* can be seen after *amēlāt māt*). Since, however, Rib-Adda of Gebal more than once begs the Pharaoh to send him Kaši troops to protect Egyptian interests in Phoenicia (Kn. 131, l. 13; 133, l. 17: conjecturally restored in 127, l. 22), and in one of these passages (133, l. 17) *Ka-[ki]* is a gloss upon [*Me-lu-ḫa*, i.e. Ethiopia (Heb. מִצְרַיִם *Miṣṣar*)], it can scarcely be doubted that the people of identical name mentioned by ARAD-Ḫiba and Biridiya were likewise Sudanese mercenaries at the disposal of the Egyptian high-commissioner, who may well have proved themselves hostile and troublesome to the governors of Jerusalem and Megiddo. It must be recollected that ARAD-Ḫiba actually charged the high-commissioner with favouring the Ḫabiru and hating the city-governors (Kn. 286, ll. 16 ff.). The identity of the Kaši with the Sudanese mercenaries in all these passages is assumed by Weber (Kn. pp. 1100 f.). There is the same ambiguity in regard to the term (Kushite or Kaššite) in cuneiform as exists in the case of the Heb. מִצְרַיִם (cf. p. 64, *footnote*).

Sayce (*ET*. xv., 1903, pp. 282 f.) bases his theory that the Ḫabiru were 'Hittite condottieri' upon a discovery which he claims as the result of his attempted decipherment of the Hittite inscriptions, viz. that the name Kas was used throughout the Hittite region, the kings of Carchemish, for example, calling themselves 'kings of the country of Kas.' He takes references in the T.A. Letters to the land of Kaššu (Kašši in oblique forms) to refer to the land of the Hittites, alleging that reference to Babylonia (ordinarily assumed) is out of the question, since this is called Karduniaš—in answer to which it is sufficient to remark that the full title claimed by the kings of the Third Babylonian Dynasty, as appears from a short inscription of Kara-indaš I. (cir. B.C. 1425) is 'King of Babylon, King of Sumer and Akkad, King of Kaššu (*Ka-aš-šu-u*), King of Karduniaš' (cf. iv.² R. 36 [38], No. 3; Delitzsch, *Paradies*, p. 128). Sayce then claims that the Kaši people of ARAD-Ḫiba's letter are identified with the Ḫabiru in the passage in which the writer, having accused Milkili and the sons of Labaya of giving the king's land to the Ḫabiru, then goes on to say, 'Behold, O King my Lord, I am righteous as regards the Kaši people: let the King ask the high-commissioner whether [or no] they have dealt very violently and brought serious evil to pass' (Kn. 287). Most readers, however, must surely infer that the passage, on the contrary, distinguishes between the two peoples. Why should the writer apply different appellations to one people in successive sentences? Obviously ARAD-Ḫiba, having made his own accusation against his enemies, then proceeds to deal with an accusation which *they* have made against *him*—probably resistance to the Sudanese troops of Egypt involving bloodshed, as we may infer from his later statement that they had nearly killed him in his own house. The letters from the Candanite princes are full of such mutual recriminations. Equally groundless is the statement that the sons of Arzawa—who must certainly have been Hittites (cf. pp. lxxxiii f.)—mentioned in one letter (Kn. 289 = Winckler 182 + 185) take the place of the Ḫabiru in other letters. The passage in question says, 'Behold, Milkili, does he not revolt with the sons of Labaya and the sons of Arzawa to give up the King's territory to them'? Here, if the sons of Arzawa are Ḫabiru, we should surely draw the same inference with regard to the sons of Labaya. In two of the three other passages in question, however (Kn. 287, 290, 289, ll. 21 ff. = Winckler, 180, 183, 185), the sons of Labaya are distinguished from the Ḫabiru, for the former are associated with Milkili in giving up the King's territory to the latter.

There is no reason, so far as we can say, why Rîm-Sin should not have employed Aramaean (Hebrew) tribesmen as mercenaries *cir.* B.C. 2100. Abraham 'the Hebrew,' who is assigned to this period in Gen. 14, is earliest associated with the city of Ur (Gen. 11^{28,31}, 15⁷) on right bank of the Euphrates and bordering on the Syrian desert, with which Larsa on the left of the river was closely connected.* There were SA.GAZ in Babylonia in Hammurabi's reign, and their overseer bore a Semitic Babylonian name, Anum-pî-Sin.† If such tribesmen came later on into the regular employ of the Kaššite kings, it would not be strange if some of them adopted Kaššite names.‡ We find, then, in this last mentioned evidence, no insuperable objection to the identification of the Habiru with the Hebrews in the widest sense of the term.||

Another fact which we have learned from the T.A. Letters, and which is of high interest for the history of Canaan in the period prior to the Israelite settlement, is that a large and influential portion of the population of Syria-Palestine at this time was non-Semitic. That part of this foreign element was Hittite is now placed beyond a doubt. We have already alluded to 'the sons of Arzawa' and 'the sons of Labaya' as leagued with the Habiru in rebellion against the constituted authority of Egypt. There exists among the T.A. correspondence the copy of a letter addressed by Amenhotp III. to Tarhundaraba, king of Arzawa (Kn. 31). This letter is written for the most part in a language which we must infer to be the language of the addressee; and the fact that this is Hittite has now been certainly proved by the discovery of a number

Lastly, Sayce's statement that *Habiru* (-ri) cannot be a proper name because it is not *Habirâ* (a gentile form) is directly contradicted by the fact that we have *Sutâ* (-tî), *Ahlamâ* (-mî) which are certainly tribal names and yet are not gentiles (on these people, cf. p. lxxix): his explanation of the name as meaning 'confederates' (like Heb. *hābhēr*, plur. *hābhērīm*, the ordinary philological equivalent for which in Bab. is *ibru*, which occurs in the T.A. Letters, Kn. 126, l. 16) is ruled out by the occurrence of the gentile *Habirâ* with the two Kaššite names which we have already noticed (p. lxxxi), since such a gentile can only be formed from a proper name, and is excluded no less by the occurrence once of (*amêlâtû*) *Ha-bi-ri* (KI) which marks the name as racial (a tribe from a particular district: cf. p. lxxviii); and his finding in this last-mentioned method of writing the name an indication of the association of the 'confederates' with the city of Hebron (assumed to mean 'confederate-city') takes no account of the fact that we cannot dissociate *Habiri* (KI) from the two occurrences of SA.GAZ (KI) which we have discussed with it.

* A regular part of the title claimed by Rîm-Sin is 'he that cared for Ur.' Cf. Thureau-Dangin, *Die Sumerischen und Akkadischen Königsinschriften*, pp. 216 ff.

† Cf. King, *Hammurabi*, no. 35; Ungnad, *Babylonische Briefe*, no. 26, with note b.

‡ Cf. Winckler, *KAT*,² p. 197, n¹. Knudtzon (p. 47, n⁸) maintains (against Scheil) that the name of Kudurra's father, which is read as *Ba-si-is*, seems not to be Kaššite.

|| Discussions of the Habiru and SA.GAZ which take fullest account of available evidence are Winckler, *Gl.* i. (1895), pp. 16-21; *AF*, iii. (1902), pp. 90-94; *KAT*,² (1903), pp. 196 f.; Knudtzon, pp. 45-53; Weber in Knudtzon, pp. 1146-1148, 1336; Dhorme in *RE*, 1909, pp. 67-73; Böhl, *KH*, (1911), pp. 82-96.

of documents in the same language among the Boghaz Keui documents. The precise position of Arzawa is at present unascertained; but it seems to have been a subordinate Hittite kingdom in Asia Minor.* 'The sons of Arzawa' can hardly mean anything else than 'men from the land of Arzawa.'† Labaya, on the other hand, seems to be a personal name. There are three letters from Labaya (Kn. 252-254); and the first of these, though mainly written, like the others, in Babylonian, is so much coloured by a curious foreign jargon that in places it is incomprehensible. Another letter, written wholly in the Arzawa language and undeciphered (Kn. 32), mentions the name of Labaya three times; and the position of the earliest occurrence of the name in the first line leaves little doubt that the writer was Labaya himself.

Other non-Semitic names in the Syrian and Palestinian letters—Šuwardata, Yašdata, Zirdamyašda, Artamanya, Rušmanya, Manya, Biridašwa, Biridiya, Namyawaza, Teuwatti, Šubandu, Šutarna, etc.—appear to be Aryan; and some of them have certainly been identified as such.§ They are found throughout Canaan as well as to the north of the Lebanon. Šuwardata, who was in antagonism to ARAD-Hiba of Jerusalem, was chieftain of Kelti, *i.e.* in all probability the Biblical Keilah (1 Sam. 23¹, *al.*) some eight miles north-west of Hebron. Biridiya and his brother (?) Yašdata were princes of Megiddo. Rušmanya was prince of the city of Šaruna, a name which is identical with the Biblical Sharon, the maritime plain north of Joppa. The presence of this Aryan element in Syria and Palestine is doubtless to be connected with the fact that the kingdom of Mitanni was at this period dominated by an aristocracy who described themselves as *Harri*, *i.e.* Aryans, bore Aryan-sounding names, and venerated the Aryan deities Mitra, Varuna, Indra, and the Nāsatya-twins.|| The bulk of the Mitannian population appears, however, to have been related to the Hittites, and very possibly owed its origin to the Hittite invasion of western Asia in

* Cf. Winckler in *OLZ.* ix. p. 628; *MDOG.* xxxv. p. 40; and especially the detailed discussion of Knudtzon, *Die zwei Arzawa-Briefe* (1902), pp. 16 ff.

† Similarly the appellation *Arzawiya* applied to the chieftain of Rubizzi (probably in central Syria) seems to mean 'the Arzawan' (cf. Kn. 53, 54, *al.*).

§ Hall (*PSBA.* xxxi., 1909, p. 234; cf. also *NE.* p. 410, *n*⁵) identifies Šuwardata or Šuyardata with the Aryan Surya-dāta, *i.e.* 'Sun-given' (Ἡλιοδωπος). Böhl (*KH.* p. 17, *n*¹) quotes G. J. Thierry as comparing Biridašwa with Sanskrit *Bṛhad-aśwa* 'He who owns a) great horse.' Biridiya appears to contain the same first element. The element *arta* in Artamanya is seen in the names Artakšumara and Artatana of the Aryan dynasty of Mitanni: cf. the Old Persian Artakšāstrā (Artaxerxes) from *arta* 'great' and *kšāstrā* 'kingdom.' The second element appears in Manya and Rušmanya. Šutarna, the father of Namyawaza, bears a name which is also borne by a member of the Mitannian dynasty. Namyawaza may be compared with Mattinaza of the Mitannian dynasty. Cf. Hommel, *Sitzungsberichte der k. böhm. Gesellsch.*, 1898, vi.; E. Meyer, *Zeitschr. f. vergl. Sprachforschungen*, xlii (1909), pp. 18 ff.; Weber in Kn. *passim*.

|| Cf. Winckler, *MDOG.* xxxv. pp. 37 ff., 51; *OLZ.* xiii. 289 ff. The names occur in Figulla and Weidner, *Keilschrifttexte* 1, No. 1, Rev. ll. 55 f.; No. 3, Rev. l. 24.

the 20th century B.C., which, as we have seen (p. lxiv), brought about the end of the First Babylonian Dynasty;* or, it may be, to a still earlier settlement of Hittites, superimposed upon an older population. This Hittite population was governed, but not absorbed, by its Aryan conquerors, just as the Semitic population of Babylonia was governed by the Kaššite aristocracy who doubtless belonged to the same wave of Indo-European invasion that founded the Aryan Dynasty of Mitanni. The language of Mitanni appears to be neither Hittite nor Indo-European, but is said to have connexion with the Vannic or Caucasian type.†

Now it seems to be clear that prior to the conquests of Thutmose I. and Thutmose III. the kingdom of Mitanni extended southwest of the Euphrates, and included Naharîn, if not some portion of Syria still further south. We have noticed, in speaking of the campaigns of Thutmose III., that the leader of the forces of Naharîn was probably the king of Mitanni (cf. p. lxviii). The glosses which occur in the letter from the inhabitants of Tunip prove that Mitannian was the language which was ordinarily spoken in this Syrian city.§ The inference is plausible that the cessation of the West Semitic Babylonian predominance in Amurru, which is marked by the fall of the First Babylonian Dynasty *cir.* B.C. 1926, laid this region open to Mitannian (*i.e.* Hittite-Aryan) influence and occupation, the permeation of this strain in the population extending ultimately up to the frontier of Egypt. The campaigns of the Pharaohs of the Eighteenth Dynasty curtailed and eventually destroyed Mitannian claims to suzerainty in Amurru, confining the Mitannian kingdom to the eastern side of the Euphrates. The Hittite-Aryan strain still, however, formed a well-marked element in the population of Syria and Canaan; and there should be no doubt that it is this strain which is denoted in the O.T. by the term 'Hittites,' when this term is used in enumeration of 'the seven races' inhabiting Canaan at the time of the Israelite occupation (cf. *ch.* 3 ⁵ *note*).||

* The Hittite state of Hanî on the middle Euphrates was apparently the outcome of this invasion. Cf. King, *Bab.*, p. 210, *n* 4.

† Cf. Jensen, *ZA.* v. (1890), pp. 166-208; vi. pp. 34-72; Brünnow, *ZA.* v. pp. 209-259; Sayce, *ZA.* v. pp. 260-274; *PSBA.* xxii. (1900), pp. 171-225; Messerschmidt, *MVAG.*, 1899, 4; Bork, *MVAG.*, 1909, 1 and 2.

§ Cf. Messerschmidt, *MVAG.*, 1899, 4, pp. 119 ff. Tunip has been placed as far south as Ba'albek in the Lebanon-district, and as far north as Tinnab, some 25 miles to the north of Aleppo. The largest consensus of opinion would locate it in the neighbourhood of Kadesh on the Orontes. Cf. Weber's discussion in *Kn.* pp. 1123 ff.; and, for Egyptian evidence, Müller, *AE.* pp. 257 f.

|| The proved existence of Hittites in southern Canaan in the 14th century B.C. is not, of course, a proof that they were there 700 years earlier in the time of Abraham (assuming this to have been the period of Hammurabi), as is pictured in Gen. 23 P where they appear as inhabitants of Hebron; nor can this be regarded as proved until it can be shown that there is good ground for believing Gen. 23 to be based on *contemporary* information, or until external contemporary information has been brought to light. For if (as there is reason to believe) Gen. 23 owes its composition (or even its

The existence of this Hittite-Mitannian element in Canaan seems to throw light upon the origin of another people enumerated among 'the seven races,' viz., the Jebusites of Jerusalem. The fact that ARAD-Hiba the governor of Jerusalem bears a name of this class seems to be clear. The Sumerian ideogram ARAD 'servant,' which forms the first element in his name, proves that the second element Hiba (also written Hēba) is a divine name. There can be little doubt that this is the Hittite-Mitannian goddess Hīpa or Hēpa, who figures in the names of the Mitannian princesses Gilu-Hīpa and Tadu-Hīpa (cf. p. lxxii), and in that of Pudu-Hīpa, the wife of the Hittite king Hattusili II.; and who is enumerated among the great deities in the Boghaz Keui documents.* The name of the Jebusite of David's time, אֲרֻנָּה Arawna (2 Sam. 24^{20.22.23.24}) or אֲרָנָה Aranya (Kt., 2 Sam. 24¹⁸), which is certainly non-Semitic, is Hittite in appearance: we may perhaps compare the Hittite king-names Arandaš and Arnunta for the first element in the name.† On the other hand, Adoni-sedeḫ of Josh. 10 (cf. Judg. 1⁵⁻⁷)

present form only) to an age much later than the time to which it refers, the possibility that the author or editor may have assumed the conditions of a later age for the more or less remote period of which he is writing has obviously to be taken into account. Cf. the way in which the Philistines are represented in Gen. 26 (J in the main) as inhabitants of the maritime plain in the Patriarchal period, although evidence leads us to conclude that they did not settle in Palestine until a much later date (cf. pp. xcii ff.). While making this criticism of Prof. Sayce's contention that the historical fact that there were Hittites at Hebron in Abraham's time can now be proved (cf. *ET*, xviii. pp. 418 ff.; *HCM*, pp. 143 f.; and elsewhere), the fact should be noted that, while the historical existence of Hittites in southern Palestine at *any* period has been called in question by many scholars, Prof. Sayce has the merit of having all along maintained its truth upon evidence which might have been patent to all at least since the discovery of the Boghaz Keui documents (which certified the fact that the Arzawa language was a Hittite dialect, if not since that of the T.A. Letters. There is no *a priori* reason (so far as we know) why there should not have been Hittite clans in southern Canaan before 2000 B.C.; and evidence that such was the case may yet come to light. Sayce's evidence (*Biblical World*, Feb. 1905, pp. 130 ff.; cf. *Archaeology*, p. 206) in proof that the Hittites were already settled in southern Palestine at least as early as the Twelfth Egyptian Dynasty (cir. 2000-1788 B.C.) breaks down under the criticism of Breasted, *AJSL*, xxi. (1905), pp. 153-158. Cf. also W. M. Müller, *OLZ*, xii. (1909), 427 f.

* Cf. *MDGG*, xxxv. p. 48. The reason why we transcribe the first element of ARAD-Hiba's name according to its value as a Sumerian ideogram is that if, as the honorific mention of Hīpa implies, he was a Hittite-Mitannian, the ideogram probably stands for the Hittite or Mitannian word for 'servant,' which is unknown to us. Hommel (*Sitzungsberichte der k. böhm. Gesellsch.*, 1898, vi. p. 10) and Dhorme (*RB.*, 1909, p. 72) propose the form Arta-Hēpa (cf. Artašumara, Artatama, Artamanya); while Gustavs (*OLZ*, 1911, 341 ff.) offers the form Put-i-Hēpa, the Mitannian root, *put* being interpreted by Bork (*MTAG.*, 1909, I. p. 126) in the sense 'to serve.' Cf. Weber in Kn. pp. 1333 f. The ordinarily-accepted form Abdi-Hiba is based upon the assumption that the man was a Semite, which is very improbable.

† It is likely that the termination in Arau-ya may be hypocoristic, the name bearing the same relation to a fuller form such as Aran-daš as Aki-ya does to Aki-Tešub, Aki-izbi, Gili-ya to Gilu-Hēpa, and Biridi-ya to Birid-ašw

is good Semitic, and so is Malki-sedek (Gen. 14¹⁸), if this can be accepted as the genuine name of a king of Jerusalem.

Now Ezekiel, in characterizing figuratively Jerusalem's idolatrous career from the earliest times, states at the opening of his description, 'Thy father was the Amorite, and thy mother a Hittite' (Ezek. 16³; cf. v.⁴⁵). This statement has been often understood to be merely metaphorical—*morally* considered, Jerusalem may be said to have affinity with the early heathen races of Canaan. In the light, however, of the facts which we have just noticed, viz.: the mixture of Hittite and Semitic names among the pre-Israelite inhabitants of Jerusalem as known to us, it becomes highly probable that Ezekiel's words preserve an ethnographical fact, and that the Jebusites of Jerusalem actually derived their origin from the amalgamation of two strains, Amorite and Hittite.*

By the end of Ahnaton's reign Egypt had practically lost her hold upon the whole of her Asiatic dominions. North of the Lebanon Šubbiluliuma had thoroughly consolidated the Hittite domination. Aziru's duplicity in posing as the supporter both of Egyptian and of Hittite interests had at length proved disastrous to him, and the Hittite king had attacked and defeated him and reduced Amurru to vassalage.† The murder of Tušratta in a court-conspiracy, producing anarchy in Mitanni, gave Šubbiluliuma the opportunity of intervening in the affairs of that kingdom; and having placed Mattiuaza, an exiled son of the late king, upon the throne, he married him to his daughter and assumed to himself the rôle of suzerain.§ Šubbiluliuma seems not to have attempted to extend his domination to Canaan; and here the Habiru and other turbulent elements in the population were left to work their will unchecked by any effective control by Egypt. The death of Ahnaton was speedily followed by the sweeping away of the new religion which he had endeavoured to impose upon Egypt, and the restoration of the ancient cultus. The reigns of the succeeding Pharaohs of the Eighteenth Dynasty, Sakere, Tut'anhaton, and Ay, cover in all a period of not more than eight years (*cir.* B.C. 1358-1350), during which the power was really in the hands of the Amon-priesthood at Thebes, and the reigning monarchs themselves were little more than figureheads. Tut'anhaton (the change of whose name to Tut'anhamon marks the re-establishment of Thebes as the seat of government and the triumph of the god Amon), may possibly have attempted an expedition into Canaan as well as into Nubia; for under him envoys from Syria are represented, together

* Cf. Sayce, *Archaeology*, p. 205; Hommel, *Grundriss*, p. 55; Jeremias, *OTLAE*. i. p. 340; Böhl, *KH*. p. 26; Luckenbill, *AJTh*. xviii. pp. 57 f.

† Cf., for the circumstances, *MDOG*. xxxv. p. 43; Weber in Kn. pp. 1134 f.; Hall, *NE*. p. 350; Böhl in *Theologisch Tijdschrift*, 1916, pp. 206 ff. Text in Figulla and Weidner, *Keilschrifttexte* 1, No. 8.

§ Cf. *MDOG*. xxxv. p. 36; Böhl in *Theologisch Tijdschrift*, 1916, pp. 170 ff. Text in Figulla and Weidner, *Keilschrifttexte* 1, Obv. ll. 48 ff.

with Ethiopians from the south, as bringing tribute,* and Haremheb is described, when commander-in-chief of the Egyptian forces, as 'king's follower on his expeditions to the south and north country.' ‡

It is doubtful, again, whether Haremheb, § who succeeded Ay (*cir.* 1350), attempted to wage war in Syria. The name of Heta (the Hittites) appears in a list of names belonging to his reign, and the captives whom he is represented as presenting to the gods of Egypt may include some Asiatics. || It was probably Haremheb who concluded the treaty with Šubbiluliuma (written *Š-p³-rw-rw* in Egyptian) to which reference is made in the treaty of Ra'messe II. with Hattušili (*cf.* p. xci).

Ra'messe I., the founder of the Nineteenth Dynasty, must have been an old man at his accession (*cir.* B.C. 1315), and his reign of two years or less was uneventful. His son and successor, Sety I. (*cir.* B.C. 1313), early turned his attention to the recovery of Egypt's Asiatic dominions. At the beginning of his reign he received a report of the condition of affairs in Canaan:—'The vanquished Šasu, they plan rebellion, rising against the Asiatics of Haru. They have taken to cursing and quarrelling, each of them slaying his neighbour, and they disregard the laws of the palace.' ¶ This report, which summarizes the situation in Canaan as we have it in the T.A. Letters, is of high interest as indicating that the SA.GAZ-Habiru of the latter were identical with the people whom the Egyptians called Šasu, i.e. Asiatic Bedawin.**

Pushing through the desert without delay, Sety easily routed the outposts of the Šasu, and then marched through the whole length of Canaan, conquering or receiving the submission of various fortified cities on his route. A boundary-stone discovered by G. A. Smith, at Tell eš-Šihâb, 22 miles due east of the southern end of the sea of Galilee, proves that he must have extended his arms east of Jordan to the Haurân. †† His main object, however, was to regain possession of the Phœnician coast-cities, in order that,

* *Cf.* Breasted, *AR.* ii. §§ 1027 ff. The fact that the tribute of the north is represented as presented to the Pharaoh by the two viceroys of Nubia creates suspicion that it may have been added, in imitation of earlier representations, as the conventional pendant of the tribute of the south.

‡ *Cf.* Breasted, *AR.* iii. § 29.

§ Haremheb, who first rose to position as a general and administrator in the reign of Ahnaton, seems to have been the real wielder of power during the reigns of the weaklings who succeeded this monarch. On the death of Ay he succeeded to the kingship as the nominee of the priesthood of Amon (to whose worship he seems all along to have adhered), and his position was legitimized by marriage with a princess of the royal line. *Cf.* Breasted, *Hist. Eg.* pp. 399 ff.; Hall, *NE.* pp. 310 ff.

|| *Cf.* Breasted, *AR.* iii. § 34.

¶ *Cf.* Breasted, *AR.* iii. § 101.

** *Cf.* the remarks on p. lxxix as to the identity in meaning of Šasu with SA.GAZ=*gabhatum*.

†† *Cf.* *PEF. Qy. St.*, 1901, pp. 347 ff.; 1904, pp. 78 ff.

following the example of Thutmose III., he might obtain a naval base for the provision of reinforcements in a future campaign against the further north. This successfully accomplished, he returned to Egypt with his captives and spoil.

Resolved in a second (undated) campaign to try conclusions with the Hittites—whose king, Muršili (Eg. *M-r'-s'-r'*), the son of Šubbiluliuma, had succeeded to the throne after the brief reign of his brother Arandaš—Sety advanced between the Lebanons, and for the first time Egyptian and Hittite forces met in conflict. Sety claims to have reached Naharin; but since he did not gain any decisive success against the Hittites, we may suspect that this is an exaggeration. After this campaign Sety concluded a treaty with Muršili,* the terms of which probably left Canaan and Phœnicia to Egypt, and the whole of Syria north of the Lebanons to the Hittites. During the remainder of Sety's reign (which lasted some 21 years in all) we hear of no further campaign in Syria. It is interesting to note that Sety (like Ramesse II.) mentions a district called 'A-sa-ru, corresponding to the hinterland of southern Phœnicia ‡—precisely the position assigned in the Old Testament to the Israelite tribe of Asher (cf. *ch.* 1³¹ note).

His successor, Ramesse II. (*cir.* B.C. 1292), was fired with the ambition of recovering Egypt's Asiatic empire as it had existed at the end of the reign of the great conqueror Thutmose III. This was a task more difficult than ever before. The Hittite king Muršili, and his son and successor Muwattalli (Eg. *Mw-t-n-r'*), profiting by the long period of peace, had occupied Kadesh on the Orontes as a frontier-fortress, and rendered it a very formidable obstacle to be overcome by an Egyptian army advancing northward between the Lebanons. Of Ramesse's earliest moves we know no more than the fact that a limestone stele, cut in the rock at the mouth of the Nahr el-Kelb near Bêrût, bears the Pharaoh's name, and is dated the fourth year of his reign. § This shows that, like his father Sety, his initial move was to follow the policy of Thutmose III. and to make sure of his hold upon the Phœnician cities; but whether this cost him any fighting we have no means of determining. In any case, his ulterior object was sufficiently obvious to forewarn the Hittite king; and when next year he advanced against northern Syria in order to try conclusions with the Hittites, Muwattalli || had

* Mentioned in the treaty of Ramesse II. with Hattušili. This speaks of a treaty with Muwattalli; but there can be no doubt that the name is an error for Muršili; cf. Breasted, *AR.* iii. § 377, note c.

‡ Cf. Müller, *AE.* pp. 236 ff.

§ Another stele in the same place has been thought to be dated 'year 2' (so Petrie, *Hist. Eg.* iii. p. 46), but the date should more probably be read 'year 10.' There was but one campaign before that against Kadesh in 'year 5.' Cf. Breasted, *AR.* § 297.

|| Hall makes Muršili the Hittite king whom Ramesse met at Kadesh, and supposes that he died shortly after, 'crushed by the disaster that had befallen his armies' (*NE.* p. 361); but the treaty of Hattušili with Ramesse certainly speaks as

mustered an army of some 20,000 including his north Syrian dependants and allies from Asia Minor, among whom we recognize Dardanians (Dardeny), Lyeians (Luka), Mysians (Mesa), Kataonians (Katawaden), and Cilicians (Kelekeš). The bad strategy displayed by Ra'messe nearly involved him in defeat, his first and second divisions (the first led by the king himself) encountering a surprise-attack from behind the city of Kadesh, whilst the third and fourth divisions were still straggling some miles in the rear. The second division appears to have been cut to pieces in the first onset of the Hittites, while the first division (already in camp) was largely put to flight; but the personal bravery of Ra'messe (rallying no doubt his own bodyguard and some part of the first division) succeeded in holding the foe at bay until reinforcements arrived, when the aspect of affairs was changed and the Hittites were beaten off with heavy losses. Next day both armies seem to have been too exhausted to renew the combat; and Ra'messe had to be content to return to Egypt without attempting to reduce the fortress of Kadesh.*

It is easy to see that this campaign, though much magnified by Ra'messe on account of the personal part which he played in retrieving the issue of the battle, must have been somewhat disastrous to the prestige of Egypt in Syria. We are not surprised, therefore, to find that within the next year or so the whole of Canaan, stirred up doubtless by Hittite influence, was in revolt; and in his eighth year Ra'messe had to undertake a campaign for its reconquest, and was obliged to lay siege to and reduce even a city so far south as Ashkelon.

Pushing northward, he then captured a number of cities in the district of Galilee, among which we recognize the name of Beth-Anath (cf. *ch.* 1³³ *note*), and seems also to have extended his arms into the Lebanon-district, for he records the conquest of a city named Dapur 'in the land of Amor' (Amurru), which was garrisoned by Hittites.† Possibly the stele discovered by Schumacher at

though peace had been broken in the time of Muwattalli (Breasted, *AR.* iii. § 374), and this is the view which is taken by Breasted (*Hist. Eg.* pp. 423 ff.), Garstang (*Hittites*, p. 343), Luckenbill (*ASTh.* xviii. p. 49), and King (*Bab.* p. 235).

* The fullest accounts of this battle (with plans and Egyptian reliefs) will be found in Breasted, *AR.* iii. §§ 298 ff.; *The Battle of Kadesh (Decennial Publications of the University of Chicago, 1904)*; *Hist. Eg.* pp. 425 ff.; Petrie, *Hist. Eg.* iii. pp. 47 ff.

† The view commonly held (cf. Petrie, *Hist. Eg.* iii. p. 61; Breasted, *AR.* iii. §§ 356 f.; *Hist. Eg.* p. 436; Hall, *NE.* p. 362) that Dapur is the Biblical Tabor in the plain of Esdraelon is not very probable. Heb. **ד** is not usually represented by Eg. *d* (no instances cited by Burch.), nor **ד** by Eg. *p* (very rare; cf. Burch. § 50); and the fact that this city alone is distinguished as 'in the land of Amor' surely dissociates it from the group in which it occurs. No Hittite remains have been discovered further south than Restân, north of the Lebanons. Elsewhere Dapur is associated with Kadesh: cf. Müller, *AE.* p. 221. We find Tabor normally spelt among the Asiatic names in the great list of Ra'messe III. at Medinet Habu: cf. W. M. Müller, *Egypt. Researches* (1904) Pl. 65, No. 27; Burch. No. 1083.

Šēly Sa'd in the Haurân,* about three miles north of Tell 'Aštara, may have been set up during this campaign.

The records for the following years are scanty, but it is clear that they witnessed a long and arduous struggle to recover northern Syria from the Hittites. Ra'messe must have advanced into Naharin as far as Tunip, conquered this city, and then lost it again; for in a subsequent campaign we find him once more capturing it, together with Katna and Arvad, and claiming to have subdued the whole of northern Syria and Naharin.† It is unlikely that he retained possession of his conquests for any length of time. Muwattalli, though he might be temporarily worsted, was by no means beaten, and probably wrested back most if not all of the captured territory as often as Ra'messe returned with his army to Egypt. At length, in or shortly before the twenty-first year of Ra'messe's reign, Muwattalli died and was succeeded by his brother Hattušili II. (Eg. *Ḫ-t'-s'-r'*), who immediately proposed a treaty of peace which the Egyptian king was not loath to accept. The Egyptian text of this treaty is engraved on the walls of Karnak and the Ramesseum, and has long been known‡; and parts of a copy in cuneiform Babylonian were discovered among the Hittite archives at Boghaz Keni.§ It is a diplomatic document of the highest interest, dealing in legally phrased clauses with obligations of alliance and the mutual right of extradition of emigrants and political refugees. Both parties are placed upon a footing of exact equality—a fact which proves that neither had any permanent advantage to claim as the result of many years of conflict. There is no definition of the boundary-line between the two kingdoms; and our inference must be that it remained as defined or recognized in the earlier treaties of Šubbiluliuma (cf. p. lxxxviii) and Muršili (cf. p. lxxxix), to which the present treaty refers. Thirteen years later Ra'messe married the eldest daughter of Hattušili, and the Hittite king actually accompanied his daughter to Egypt for the ceremony.¶

During the remainder of Ra'messe's long reign of sixty-seven years he was never again obliged to take the field in Syria.** His son Mineptah was an elderly man when he succeeded him (*cir.* B.C. 1225), and his accession seems to have been the signal for a revolt in Canaan, which he quelled in his third year. Mineptah's reference

* Cf. *ZDPV.* xiv. pp. 142 ff.

† Cf. Breasted, *AR.* iii. §§ 363 ff.

‡ Cf. Breasted, *AR.* iii. §§ 367 ff.; Petrie, *Hist. Eg.* iii. pp. 63 ff.

§ Cf. *MDOG.* xxxv. pp. 12 f.

¶ Cf. Breasted, *AR.* iii. §§ 416 ff.

** To the reign of Ra'messe II. is assigned the composition of the document contained in *Papyrus Anastasi I.*, which gives an imaginative and satirical description of the perils and difficulties attendant upon travel in Palestine. This document, which is of the highest interest on account of the typographical and descriptive information which it offers, has been most recently edited by A. H. Gardiner, *Egyptian Hieratic Texts, Series I. Part I.* (1911).

to this campaign is, from the Biblical point of view, of the highest interest, for in it we find Israel mentioned among Palestinian localities—Pe-kanan (*i.e.* 'the Canaan'), Ashkelon, Gezer, Yeno'am, Haru (*i.e.* southern Palestine)—as plundered and subdued.* Mineptah's statement is 'Israel (*y-s-r-'r*) is desolated, his seed is not,'† and the name Israel is marked by the Determinative which means 'men,' showing that it denotes a people and not a country.

The next event which is of interest for Biblical history is the settlement of the Philistines in Canaan. Already in the reign of Mineptah we can trace the beginning of a migratory movement among the peoples of the north-eastern Mediterranean. Mineptah was obliged, in his fifth year, to repel an extensive invasion into the western Delta on the part of the Libyans, together with various peoples who came by sea to assist in the raid, those who are named being the 'Aḳaywaša, Turuša, Luka, Šardina, and Šakaluša.§ After a lapse of nearly thirty years we find that history repeats itself, and the Libyans, profiting by the period of confusion and weakness which ensued in Egypt after the death of Mineptah (*cir.* B.C. 1215), again invaded the western Delta in force in the fifth year of Ra'messe III. of the Twentieth Dynasty (*cir.* B.C. 1193), assisted by sea rovers called Pulasati and Takkara,|| some of whom joined the land forces of the Libyans, whilst others entered the Nile-mouths in their ships. Ra'messe claims a decisive victory against these

* The inscription in which this reference occurs was discovered by Petrie in 1896, and a full account of it was given by him in the *Contemporary Review* for May of the same year. Cf. also Petrie, *Hist. Eg.* iii. p. 114; Breasted, *AR.* iii. §§ 602 ff.

† In the expression 'his seed is not,' *seed* seems to mean *posterity*; and the phrase does not mean 'their crops are destroyed,' as explained by Petrie and many scholars after him. This is clear from the fact that the same expression is used five times elsewhere of other conquered foes (cf. Breasted, *AR.* iii. § 604), *e.g.* of the sea-peoples who endeavoured to invade Egypt in the reign of Ra'messe III., of whom this king says, 'Those who reached my border are desolated, their seed is not.' Here reference to 'crops' is obviously out of the question.

§ Cf. Breasted, *AR.* iii. §§ 569 ff. The 'Aḳaywaša are probably the 'AḳaiFoi, *Achivi*, or proto-Greeks; the Turuša may be the *Tυρρηνοί* or Tyrrhenians, whose migration from Asia Minor to Italy probably took place at about this period; the Luka, as we have already noticed (p. xc), are certainly the Lycians; the Šardina were perhaps originally from Sardis in Asia Minor, and subsequently gave their name to Sardinia (some of them had been in the employ of Egypt as mercenaries since the days of Aḳhaton: they appear in the T.A. Letters as *amēlu Šerdani*; cf. Kn. 122, l. 35); the Šakaluša were probably from Sagalassos in Asia Minor (Sagalassian mercenaries are perhaps intended by *šabē alu Šehlali*, 'soldiers of the city of Šehlal,' mentioned by Abd-Aširta in one of his letters, Kn. 62; so Hall in *PSBA.* xxxi. p. 231, n.⁸⁶). Cf. Müller, *AE.* pp. 357 f., 372 ff.; Hall, *NE.* pp. 68 ff., 377. On the -ša and -na terminations of many of these names as nominal suffixes in Asia Minor (illustrated by the Lycian -āzi, -aza, etc.), cf. Hall, *Oldest Civilization of Greece*, pp. 178 f.

|| Or Zakkala, if Hommel (*PSBA.* xvii., 1895, p. 205; *Grundriss*, pp. 28, 32, n.²) is right in connecting with the city-name Zaḳḳalû, mentioned in a Babylonian inscription of the Kaššite period (the same that has already been cited for the name Ḫarbišihû: cf. p. lxxxix).

combined forces.* But a greater peril awaited him. In his eighth year he had to meet a threatened invasion of the sea-peoples, which was clearly no casual raid, but a migration on a large scale. The invaders came both by land, moving down the coast of Syria, and also by sea, the land-contingent bringing their families and possessions in heavy two-wheeled ox-carts. 'The isles were disturbed,' Rāmesse tells us, and 'no one stood before their hands,' even the Hittites being mentioned as wasted before their advance. 'They set up a camp in one place in the land of Amor [Amurru]. They desolated his people and his land like that which is not. Their main support was Pulasati, Takkara, Šakaluša, Danauna, Wašaša. These lands were united, and they laid their hands upon the land as far as the Circle of the Earth. Their hearts were confident, full of their plans.'† Rāmesse equipped a fleet to meet the invaders, and marched into Canaan himself at the head of his land-army, which was composed partly of Egyptians and partly of Sardina mercenaries. Somewhere upon the coast of Phoenicia a battle was fought in which Rāmesse was victorious; and his army, having accounted for their foes by land, turned their arrows to the assistance of the Egyptian ships which were engaged in a naval battle inshore in one of the harbours.‡ Rāmesse thus succeeded for the time in checking the southern progress of the tide of invasion; but it cannot have been long afterwards—whether later in this Pharaoh's reign or in the period of national decay which supervened at his death—that the immigrant tribes pressed on and occupied the whole of the maritime plain of Canaan from Carmel to the border of Egypt, extending ultimately, as it seems, across the plain of Esdraelon to Beth-she'an (cf. p. 24).

However much doubt may attach to the identification of the other invading tribes,|| it is certain that the Pulasati (written *Pw-r'-s'-t* or *Pw-r'-s'-ty*) are the *Pelīstīm* of the O.T. The Philistines were recognized by the Israelites as immigrant settlers, and their earlier home is said to have been קַפְתֹּר Kaphtor (Deut. 2²³, Am. 9⁷),

* Cf. Breasted, *AR.* iv. §§ 35 ff.

† Cf. Breasted, *AR.* iv. § 64.

‡ Cf. the Egyptian relief as figured by Rosellini, *Monumenti dell' Egitto*, i. Pl. cxxxi.; Maspero, *Mémoires*, p. 469; Macalister, *Schwab Lectures*, p. 119.

|| The name Takkara has been connected by Petrie (*Hist. Eg.* iii. p. 151) with the place-name Zakro in eastern Crete, and this view is favoured by Hall (*NE.* p. 71). The older identification with the Τευκροί of the Troad, adopted by Lauth, Chabas, Lenormant, and ultimately by Brugsch (cf. references in Maspero, *Mémoires*, p. 464, *n*²) may also connect this people originally with Crete, whence the Trojan Teucer is said to have come (Virgil, *Aen.* iii. ll. 102 ff.): cf. Hall, *Oldest Civilization of Greece*, p. 176. Maspero (*Revue Critique*, 1880, p. 110) and Breasted (*Hist. Eg.* p. 477) think of the pre-Greek Sikeli or Sicilians. The Danauna may have been the Δαναοί, as is commonly thought, in spite of the fact that there was a settlement of them in Canaan some two hundred years before this date (cf. p. xcv). On the Šakaluša as the Sagalasians, cf. p. xcii. Most difficult of all to identify are the Wašaša, who Hall thinks may be 'the people of *Ψαξός* (Waxos), the *Ῥαξός* of Herodotus and *Ῥαξός* of later days, a prominent city of Crete' (cf. *op. cit.* p. 177).

which is defined in Jer. 47⁴ by the term כַּפְתֹּר , always applied to the islands and coast-lands of the Mediterranean. The identity of Kaphtor with the Egyptian Keftiu,* and of both with the island of Crete, admits of no reasonable doubt: but it is not unlikely that the ancestors of the Philistines had at one time or another connexion with the mainland of Asia Minor, especially with Lycia and Caria (which may, indeed, be included under the term Keftiu, if, as Hall states, it is derived from an Egyptian word meaning 'behind,' and so denotes somewhat vaguely 'the back of beyond').† The term כֶּרֶתִּי *Keréthî*, which is often applied in the O.T. to a section of the Philistines (especially David's foreign bodyguard), bears a close

* The absence of the final *r* in Keftiu as compared with Kaphtor is explained by Spiegelberg (*OLZ.* xi. 426 f.) as due to elision; and this seems more probable than the rival explanation offered by Wiedemann (*OLZ.* xiii. 53) that Kaphtor is the Egyptian *Kaft-hor* 'Upper Kefti' (like *Retenu-hor* 'Upper Retenu'), since it is more likely that the Israelites learned the name directly from the Philistines themselves than through an Egyptian medium. W. M. Müller (*MLA G.*, 1900, p. 6) cites the Ptolemaic form *Kpt'r* with retention of *r*.

† The men of Keftiu figured on Egyptian tombs of the Eighteenth Dynasty period bear striking resemblance to the Minoans, the remains of whose civilization have been excavated at Knossos and other sites in Crete, and the vases which they carry are identical in workmanship. It is impossible, however, to regard the Philistines as identical with these Keftians. The former, as represented in Egyptian reliefs, are quite unlike the latter, and always wear a high feathered headdress, such as, according to Herodotus (vii. 92) was worn at the battle of Salamis by the Lycians (*περὶ δὲ τῇσι κεφαλῇσι πύλους πτεροῖσι περιστεφανωμένους*), whom the same writer believes to have come originally from Crete (i. 173). Cf. the feathered headdress worn by the figures depicted on an Assyrian relief from Kuyunjik of the seventh century B.C.: Layard, *Monuments of Nineveh*, 2nd Series, Plate 44. Herodotus also states that the Carians came to the mainland from the islands, and were originally subjects of King Minos (i. 171; cf. also Strabo, xiv. 2, 27), and he ascribes to them, among other inventions borrowed by the Greeks, the fastening of crests on helmets—which, however, were clearly quite different from the feathered skull-caps of the Lycians and Philistines. A head with feathered headdress, identical with that of the Philistines, forms one of the pictographs upon the clay disk discovered by Pernier in the palace of Phaestos in Crete. The human figures included among the pictographs on this disk are non-Minoan in outline and costume, and the signs as a whole differ considerably from those of the Minoan signary. Whether the disk should 'be regarded as a record of a peaceful connexion between the Minoan lords of Phaestos and some neighbouring race enjoying a parallel form of civilization,' or as 'the record of an invading swarm, the destroyers perhaps of Phaestos itself,' is a question which cannot at present be settled. Cf. Evans, *Scripta Minoa*, i. pp. 22-28, with Plates xii. and xiii.

The Aegean pottery which has been discovered at sites in Palestine which come within the Philistine sphere (Tell es-Sâfiyyeh, Gezer, 'Ain-šems) is of the inferior style called 'Late Minoan III. i.e. belonging to the period subsequent to the destruction of Knossos which marks the end of 'Late Minoan II.' cir. B.C. 1400. Late Minoan III. style, which follows immediately on Late Minoan II., was very possibly the inferior imitation of Minoan art already developed in south-western Asia Minor by the invaders of Crete, who may have been the ancestors of the Philistines.

On the Keftian and Philistine questions, cf. Hall in *Annual of the Brit. School at Athens*, viii (1901-2), pp. 157-188; *NE.* pp. 68-74; Macalister, *The Philistines: their History and Civilization* (*Schweich Lectures*, 111, published 1914), chap. i.

resemblance to 'Cretan,' and is so rendered by C in Ezek. 25¹⁵, Zeph. 2⁵; and an allied tribe, also employed as mercenaries by the Judæan kings, bore the name 'כְּרִי *Kārî* (2 Sam. 20²³ *Kt.*, 2¹ *Kgs.* 11^{4,19}), *i.e.* Carians.

The O.T. tells us nothing as to the other sea-peoples allied with the Philistines; but we gather from the narrative of the Egyptian Wenamon (cf. p. xevi), that there was a Takkara settlement at Dor a little south of Carmel about eighty years after the invasion. It is possible that the Danauna may have settled on the sea-coast to the north of Phœnicia, where, as we learn from a letter of Abimilki of Tyre to Ahnaton, there was a settlement of them some 200 years earlier.* So late as the latter half of the 9th century B.C. Kahumu king of Ya'di in northern Syria was harassed by the king of the Danonim (כַּלְךְ דַּנַּיִם), and was obliged to hire the assistance of the king of Assyria†—a fact which favours the inference that this people is to be looked for somewhere upon the north Syrian littoral.

After having successfully repulsed another invasion of the Libyans (this time in alliance with the Mašawaša, a north African people dwelling to the west of the Libyans), which took place in his eleventh year, Ra'messe III. undertook (probably within the next year or two) a second campaign in Syria concerning which our very scanty information is derived solely from pictorial reliefs.§ He seems to have stormed and captured several fortified cities, one of which is described as 'in the land of Amor,' whilst another, which is represented as surrounded by water, is probably Kadesh. Two others are pictured as defended by Hittite troops, and one of these bears the name Eret.

After the death of Ra'messe III. the Twentieth Dynasty was continued by a series of nine rulers, all of whom bore the name Ra'messe (IV-XII). The total period covered by their reign was under 80 years (B.C. 1167-1090); and since in the whole line there was not one monarch possessing the slightest vigour or initiative, the power of the empire suffered a swift and irretrievable decline. Early in Ra'messe XII.'s reign we find that a Tanite noble named Nesubenebded has made himself ruler of the whole Delta-region,

* Cf. Kn. 151, ll. 49 ff. Abimilki's words are, 'The King my lord has written to me, "What news hast thou of Canaan? Send me word." The king of the land of Danuna is dead, and his brother has become king in succession, and the land is at rest.' It is generally assumed that the O.T. references to the Philistines as occupying the maritime plain of southern Canaan in Patriarchal times (Gen. 21^{32,34} R, 26 J; cf. also Ex. 13¹⁶ E, 15¹⁴ J) are necessarily anachronistic; but the fact that there were Danauna in Syria some two hundred years before the days of Ra'messe III. should give us pause before we assert this categorically, since for aught we know there *may* have been an earlier Philistine settlement just as there was an earlier Danauna settlement. The existence of such an earlier Philistine settlement has been argued by Noordzij (*De Filistijnen*, p. 59), mainly on the ground that by the time of Samson and Saul the Philistines were already largely Semitized.

† Inscription of Kahumu, ll. 7 f. Cf. references p. 174, *footnote* 2.

§ Cf. Breasted, *A.R.* iv. §§ 115-135.

while at Thebes the supreme power is in the hands of the high-priest of Amon, Hrihor by name.

A document dated in the fifth year of this reign (*cir.* B.C. 1114) is of the highest interest to us as illustrating Egypt's total loss of power and prestige in Syria.* This is the report of a certain Wenamon, an official despatched by Hrihor to Phœnicia in order to procure timber from the Lebanon for the sacred barge of Amon. The report, which is a chapter of misfortunes, is undoubtedly authentic, and was apparently drawn up to explain the emissary's waste of time and ill-success in accomplishing his errand.

Starting from Thebes in charge of an image of the god named 'Amon-of-the-Way,' Wenamon goes to Tanis, and on exhibition of his credentials Nesubenebbed and his wife Tentamon give him a passage on board a trading-vessel commanded by a Syrian in order that he may reach Gebal and obtain the timber from Zakar-ba'al (Eg. *ṯ^p-k'-r'-b'-r*), the Phœnician prince of that city. In the course of the voyage the ship touches at Dor, which belongs to a settlement of the Takkara under a prince named Badyra, or, it may be, Bod'el (Eg. *B'-dy-r*). ‡ Whilst the ship is in harbour one of the crew steals Wenamon's money, amounting to 5 *deben* of gold and 31 *deben* of silver, § and decamps. Wenamon interviews Badyra and endeavours to make him responsible for the robbery, on the ground that it took place in his harbour; but the Takkara prince not unnaturally disclaims all obligation to make good the money, while politely promising to search for the thief. After waiting in harbour nine days without result, Wenamon is obliged to continue his journey. Unfortunately at this point there comes a lacuna in the MS.; but we are able to gather from what remains || that the ship put in at Tyre, and that either here or at some other port Wenamon met some Takkara travellers bearing a bag of silver amounting to 30 *deben*, and incontinently seized it as surety for his own money.

Arrived at Gebal, Zakar-ba'al refuses to see him, and sends a message, 'Begone from my harbour!' Wenamon waits patiently for nineteen days, in spite of daily orders to depart: then one of the youths in the prince's retinue falls into a prophetic frenzy, and demands that the god, and the messenger of Amon who has him in

* The Golénischeff papyrus, discovered in 1891 at El-Ḥibeh in Upper Egypt. For translation and discussion, cf. W. M. Müller in *MLA*, 1900, 1, pp. 14-29; Erman in *Zeitschr. für ägypt. Sprache*, xxxviii (1900), pp. 1-14; Breasted, *AR* iv. §§ 557 ff.; Maspero, *Contes populaires de l'Égypte* (4^e éd. 1911), pp. 214-230; *Popular Stories of Ancient Egypt* (trans. of preceding by Mrs. Johns, revised by Maspero, 1915), pp. 202-216.

‡ In favour of taking the name as Semitic בראל we may compare the Phœnician names ברעשתרת Bod'-Aštart, ברמלקרת Bod-Melkart, ברתנת Bod-Tanith. בר is probably a shortened form of עבר 'servant of': cf. Cooke, *NSL* p. 41.

§ That is (according to Petrie, *Hist. Eg.* iii. p. 197) about £60 in gold and £12 in silver.

|| Maspero (*op. cit.*) offers a conjectural restoration of the missing section.

his care, shall be brought into the presence of Zakar-ba'al. Thus Wenamon, who, having abandoned hope of accomplishing his mission, is loading his belongings on to a ship bound for Egypt, is stopped by the harbour-master and ordered to remain until the morning. He is then granted an interview with Zakar-ba'al, who, in spite of the prophecy, is by no means disposed to receive him with open arms, but demands his credentials which he has foolishly left in the hands of Nesubenebbed and Tentamon, and asks why he and his god have been sent, not in a special ship, but in a mere merchant-vessel, in which he might easily have been wrecked and have lost the image of the god.* On Zakar-ba'al's inquiring his business, he replies, 'I have come after the timber for the great and august barge of Amon-Re, king of gods. Thy father did it, thy grandfather did it, and thou wilt also do it.' Zakar-ba'al admits that this is true, and professes himself quite willing to do business at a price; then sending for the journal of his fathers he proves from it that they were paid in full for all the timber which they supplied, and were under no obligation to supply anything freely to Egypt as overlord.† This documentary evidence is clinched by an argument which is very noteworthy as proving how utterly the Phœnician cities had shaken off the Egyptian suzerainty. 'If,' says Zakar-ba'al, 'the ruler of Egypt were the owner of my property, and I were also his servant, he would not send silver and gold, saying, "Do the command of Amon." It was not the payment of 'tribute' which they exacted of my father. As for me, I am myself neither thy servant nor am I the servant of him that sent thee. If I cry out to the Lebanon, the heavens open, and the logs lie here on the shore of the sea.'§

Wenamon blusters in vain; even the production of the image of Amon, and the solemn assurance that the life and health which the god is able to bestow is of far greater value than a mere money-payment, are without effect. He agrees, therefore, to send his scribe back to Egypt with a request to Nesubenebbed and Tentamon to despatch various goods in payment for the timber; and, as an earnest that he is ready to perform *his* side of the bargain, Zakar-ba'al embarks a small part of the timber on the ship by which the messenger sails. The goods arrive from Egypt in due course, and Zakar-ba'al immediately gives orders that the timber shall be felled and dragged down to the shore. When all is ready for embarka-

* The precise meaning of Zakar-ba'al's remarks about the ship seems to be open to doubt. The interpretation adopted above is based on the rendering of Breasted.

† The keeping of this journal by Zakar-ba'al and his ancestors, coupled with the fact that among the goods supplied him from Egypt in payment for the timber are 500 rolls of papyrus, is of the first importance in proof of the high antiquity of the use in Canaan of an alphabetic script written upon papyrus or leather, alongside of the use of cuneiform Babylonian written upon clay tablets. Cf. *Addit. Note* on 'The use of writing in Canaan at the time of the Judges,' p. 258.

§ The actual quotations here given are derived from Breasted's translation.

tion he sends for Wenamon, and points out that he himself has done as his fathers did, whereas the Egyptian can scarcely make the same claim. Then somewhat sarcastically he congratulates Wenamon on being more fortunate than his predecessors—certain messengers of Hamwese (probably Ra'messe IX.) who were detained in the land seventeen years until their deaths: and he suggests that Wenamon should go and see their tomb!

Wenamon, however, having secured his timber, is only bent on embarking it as soon as possible and setting sail; but, unfortunately for him, before he can accomplish this, eleven ships of the Takkara appear outside the harbour with the object of stopping his departure and arresting him—doubtless on account of his seizure of the silver belonging to the Takkara travellers.* Wenamon is in despair; but Zakar-baal manages to enable him to embark and slip through their fingers. His ship is then driven by a contrary wind to the land of Alasa (probably Cyprus); and here he is (or fancies that he is) in imminent danger of death at the hands of the islanders, and only escapes through finding some one who understands Egyptian, and who interprets his words to the queen of the country. At this point, unfortunately, the MS. breaks off; and we do not know what further adventures Wenamon encountered before he managed to reach Egypt.

This narrative of Wenamon—lengthy as it is even when reduced to a mere summary—has seemed worthy of inclusion both on account of its intrinsic interest as exemplifying Egypt's loss of even the shadow of authority in her former Asiatic dominion, and also because, illustrating as it does most vividly the condition of civilization in Canaan, it falls into the middle of the period covered by the Book of Judges, and happens to be the solitary piece of extra-Biblical evidence known to us which belongs to that period. The reason why—whilst earlier centuries have proved comparatively rich in extra-Biblical material bearing on the history of Syria and Palestine—the period of the Judges of Israel is thus so barren is not far to seek. We have arrived at an age in which no external great power was strong enough or free enough to interfere in the affairs of Canaan. This period extends from the early middle part of the twelfth century B.C. (end of the reign of Ra'messe III.) down to the middle of the ninth century B.C. when the co-operation of Ahab of Israel in the league against Shalmaneser III. of Assyria (B.C. 854) foreshadows the speedy interference of this great power in the affairs of the small kingdoms of Canaan.†

* The narrative here suggests that a previous attempt to arrest Wenamon had been made by the Takkara, and that the account of this has disappeared in the lacuna in the middle of the MS.

† The incursion into southern Canaan of the Pharaoh of whom it is recorded in 1 Kgs. 9¹⁶ that he captured Gezer and presented it as a dowry to his daughter on her marriage with Solomon (early middle part of the tenth century B.C.), and the invasion of Judah and Israel by Shishak (Sheshonk I.) in the reign of Rehoboam of

The decline of Egyptian power we have outlined. The Hittite empire, shaken to its foundations by the irresistible movement of the sea-peoples of which we have already spoken (cf. p. xciii), appears to have been wiped out, perhaps some two decades later (*cir.* B.C. 1170) through the invasion of a people whom the Assyrians called Muškaya,* the Meshech of the Old Testament (Gen. 10², *al.*), and the Μόσχου of Herodotus (iii. 94; vii. 78), who were probably akin to the Phrygians of later times. Thenceforward Carchemish became the chief centre of Hittite civilization; but there were other independent or semi-independent principalities throughout northern Syria, extending apparently as far south as Kadesh on the Orontes, the former frontier-city of the great Hittite empire.† The rulers

Judah (latter half of the same century), as recorded in 1 Kgs. 14²⁵ and upon the walls of the temple of Amon at Karnak, are isolated incidents merely, and do not mark a recrudescence of Egyptian power in Palestine.

* Tiglath-Pileser I. tells us that in the first year of his reign (*cir.* B.C. 1120) he attacked and defeated 20,000 Muškaya and their five kings who fifty years previously had held the lands of Alzi and Purukuzzi, and after a course of unbroken victory had 'come down' and seized the land of Kummuh (Commagene, south of the Taurus and north of Mesopotamia): cf. Budge and King, *Annals of the Kings of Assyria*, pp. 35 f.; *KB*. i. p. 18. In later times their land, to the north-west of Kummuh on the borders of Cappadocia, is known as Mušku or Musku: cf. for collected references Delitzsch, *Paradies*, pp. 250 f. It is on Tiglath-Pileser's information as to this Muškaya-movement—coupled with the facts that Arnuata, who must have reigned *cir.* B.C. 1200 or a little earlier, is the last Hittite king whose archives have been found at Boghaz Keui, and that both Boghaz Keui and Carchemish exhibit signs of destruction and subsequent reconstruction at a period not much later than Arnuata—that the conclusion is based that the Muškaya were the destroyers of the Hittite empire. Cf. Hogarth, *The Ancient East*, p. 38; Garstang, *Hittites*, p. 53; King, *Bab.* p. 211.

‡ This conclusion depends on the emendation of 2 Sam. 24⁶, according to which the northern limit of David's kingdom extended 'to the land of the Hittites, unto Kadesh' (reading אֶרֶץ הַחִתִּים קְדֵשׁ after אֶל in place of the unintelligible אֶרֶץ תַּחְתִּים חֲדָשׁ 'land of Tahtim Hodshi' of 18). There is no reason for doubting the restoration 'unto Kadesh'—with Driver (*NHTS.*² *ad loc.*) and others—on the ground that David's kingdom could not have extended so far north, the ordinary northern limit of the kingdom of Israel being Dan (probably Tell el-Kâdy, south of Hermon: cf. *notes* on 'Laish,' *ch.* 187, and on 'from Dan, etc.,' *ch.* 20¹), which is one hundred miles south of Kadesh, if, as is probable, the latter city is to be located on the Orontes at a point a little south of the lake of Homs (cf. Maspero, *Mémoires*, pp. 140 f.). The ideal northern limit of the kingdom, which was realized in the reigns of David and Solomon and again in that of Jeroboam II., was 'the entry of Hamath' (cf. *ch.* 3³ *note*), which is clearly proved by *ch.* 3³, Josh. 13⁵ to have been the *northern* and not the southern end of the pass (el-Bukâ) between the Lebanon and Anti-Lebanon ranges. The attempt to identify 'the entry of Hamath' with Merǧ Ayyûn, the southern mouth of el-Bukâ (so e.g. van Kasteren, *R.B.* 1895, pp. 23-36; cf. Buhl, *Geogr.* p. 66), produces the ridiculous result that the *terminus a quo* in these two passages ('mount Ba'al-Hermon,' *ch.* 3³= 'Ba'al-Gad,' Josh. 13⁵) and the *terminus ad quem* are in the same locality, or at most separated by five or six miles only; and how 'all Lebanon' can be said to lie between these two points, or, so situated, to be 'eastward' of 'the land of the Gebalites,' passes comprehension.

of these principalities are 'the kings of the Hittites,' mentioned in 1 Kgs. 10²⁹, 2 Kgs. 7⁶.

Lastly, Babylon and Assyria were, during the period of the Judges as also two centuries earlier, so much engaged in mutual suspicions or open hostilities, that they had no scope for raids of conquest in the west. The Synchronistic History of Babylonia and Assyria* is a record of boundary-treaties and their violation, of invasions and counter-invasions, sufficiently preoccupying to absorb the main output of each kingdom's energy so long as their power remained, upon the whole, fairly evenly balanced. Taking a comprehensive survey of the four centuries from B.C. 1400 to B.C. 1000,† we observe that the tendency of Babylon is towards decline of power, whereas the tendency of Assyria is towards the gathering of strength and energy, which gives promise of the predominant position which she was to attain in western Asia from the ninth until nearly the close of the seventh century B.C. This may be largely explained by difference of temperament, the strong infusion of Sumerian and Kassite strains in the Semitic blood of the Babylonians apparently tending towards a peace-loving and mercantile disposition; whereas such infusion as entered into the more purely Semitic blood of the Assyrians seems to have been furnished, at the beginning of their national history, by an Anatolian strain, which has been plausibly supposed to account for the lust of war and ruthlessness which distinguished them so markedly in comparison with their southern kinsmen.‡

With the rejection of the southern end of el-Buḳâ' as 'the entry of Hamath,' and acceptance of the northern end, van Kasteren's attempt to trace a line south of the Lebanon for the ideal description of Israel's northern boundary in Num. 34^{7 ff.} P, Ezek. 47^{15 ff.} breaks down entirely. Furrer's attempt (*ZDPV.* viii., 1885, pp. 27-29) to find the line north of the Lebanon-region and including it is probably approximately correct, except that he goes too far north in placing 'the entry of Hamath' at er-Restân (Arethusa), nearly fourteen miles north of Homs (which would bring Kadesh—if it is to be sought at the site above indicated—nearly thirty miles within the border), and in identifying Ziphron of Num. 34⁹ with Safrâneh, by the expedient of placing it *before* and not *after* Ṣedad of v. 8, i.e. the modern Ṣadal. Probably the boundary crossed the Orontes near Riblah (modern Ribleh) some twenty miles south of Homs (cf. Ezek. 6¹⁴, reading מִן־דָּבָר רִבְלָתָה), ran east-south-east to Ṣadal, and then to the modern Zifrân, described by Wetzstein (*Reisebericht über Haurân und Trachonen*, p. 88) as an extensive ruined site fourteen hours north-east of Damascus. That such a northern extension of territory could be and was claimed by David as the result of his successful wars with the Aramaeans and his treaty with To'i, king of Hamath (2 Sam. 8, 10) is extremely probable—more especially if the territory of Aram-Ṣobah is to be placed approximately in the neighbourhood of Homs (cf. Nöldeke in *EB.* 280).

* This chronicle has been edited by Peiser and Winckler in *KB.* i. pp. 194 ff.

‡ Cf., on this period of Assyrian and Babylonian history, Budge and King, *Annals of the Kings of Assyria*, pp. xxiv-lvi; King, *Records of the reign of Tukulti-Ninib I.*; *Bab.*, chaps. vii., viii.; Rogers, *HBA.* 6 pp. 109-132, 144-179; Johns, *Ancient Babylonia*, pp. 94-106; *Ancient Assyria*, pp. 50-78; Hall, *NE.* pp. 368-370, 381-389, 398f.

§ Cf. King, *Bab.* pp. 139 ff.

In the first half of the thirteenth century B.C. the rise of Assyrian power was remarkably rapid, culminating in the reign of Tukulti-Ninib I. (*cir.* B.C. 1275), who actually conquered Babylon and held it for seven years. This monarch's reign, however, terminated in rebellion and civil war which brought about a period of retrogression, during which Assyria had to suffer at least one serious invasion by the Babylonians.* In the reign of Ašur-dān I. (*cir.* B.C. 1167) the power of Assyria began to revive,† and reached a height never before attained in the reign of Tiglath-Pileser I. (*cir.* B.C. 1120), the first really great empire-builder of this kingdom. Tiglath-Pileser's conquests, however, extensive as they were (including Babylon, and great tracts of country to the north and north-west of Assyria, even as far as the land of Kumanî in the Taurus region), did not reach so far south-west as the land of Canaan, where at this period the tribes of Israel were slowly gaining their footing under the Judges; though he came into conflict with Aramaean tribes in the neighbourhood of Carchemish and drove them westward across the Euphrates, and the fact that he claims to have set sail on the Mediterranean in ships of Arvad, and to have slain a great dolphin or whale,§ indicates some extent of penetration into northern Syria. After Tiglath-Pileser I. we possess practically no knowledge of the course of Assyrian history for a hundred and thirty years; and the silence of the Synchronistic History as to Assyrian victories is a sure indication that the kingdom must have undergone a long period of decline.||

Failing thus the interference of any great power in Syria and Palestine for a period of some three centuries, a unique opportunity was afforded to the smaller peoples of the country to settle down and consolidate their power. In the north the Aramaeans, whose gathering force and westward migratory movements came into evidence in the period of the T.A. Letters, now spread both eastward across the Euphrates into the district of Harran and south-westward into Syria, north and east of the Lebanons, founding in northern and central Syria a number of small principalities interspersed among the principalities which, as we have seen, were the survivals of the great Hittite Empire.¶ South of the Lebanons

* According to the Synchronistic History, Adad-šum-našir of Babylon slew Enlil-kudur-usur of Assyria in battle, and besieged the city of Aššur (*cir.* B.C. 1213). It is probable that this reassertion of Babylonian power was continued under his immediate successors: cf. King, *Bab.* p. 244; Rogers, *HBA.*⁶ p. 125; Hall, *NE.* p. 385.

‡ He attacked Babylonia and captured several cities from Zamama-šum-iddin, the last king of the Kaššite Dynasty. This defeat of Babylon was doubtless contributory to the fall of the Third Dynasty, which took place shortly after at the hands of the Elamites.

§ Cf. 'Broken Obelisk,' col. iv. ll. 2f. (Budge and King, *op. cit.*, p. 183.)

¶ Cf. Budge and King, *op. cit.* p. lvi.

¶ Our knowledge of north Syrian history is far too scanty to enable us even to draw inferences as to the relative strength and persistency of the Hittite and

opportunity favoured the southern branch of the Aramaean stock which is known as the Hebrews, among whom the tribes of Israel formed an important element. It is a fact worthy of notice that the Book of Judges, in recording the experiences of Israel in their struggle to obtain a footing in Canaan, makes no sort of allusion to any collision with, or aggression at the hands of, a great power such as Egypt or Assyria—as might well have happened had the information embodied in the book been merely vague and anachronistic. The absence of such allusion—which, as we have seen, is in strict accord with the historical circumstances of the period—should considerably strengthen our confidence that the course of history as described is in the main based upon a trustworthy tradition. The historical value of this tradition is discussed in the special introductions to the various sections of the book.*

Aramaean elements. Even the evidence of proper names is fallacious, since it is likely that, where Aramaean influence was strong, the Hittites may eventually have undergone Semiticization and have adopted Semitic names, just as we know that the Philistines did. It is at any rate a fair conjecture that it was in the far north (neighbourhood of Carchemish) that the Hittites longest retained their individuality, while further south Aramaean influence more speedily prevailed, as much by peaceful penetration as by conquest. Hamath, which—until the recent discovery of a Hittite inscription at er-Restân (cf. Garstang, *Hittites*, p. 85, n²)—was the most southerly site at which Hittite remains were known, is a state concerning which it is possible to bring together a few facts bearing on this question. Originally an important Hittite centre (on the Hittite remains, cf. Garstang, *Hittites*, pp. 93 ff.), it was probably still purely Hittite in David's time (B.C. 1000), since its king To'i or To'u was anxious to secure David's support against the encroachments of the Aramaeans (2 Sam. 8^{9f} = 1 Chr. 18^{9f}). The name To'i may well be identical with the name which appears in the T.A. Letters as Tuhi, and is borne by the regent of Mitanni during the minority of Tušratta (Kn. 17, l. 12); cf. Luckenbill, *AJTh.* xviii. p. 57. The next king known to us is Irhulêni, mentioned by Shalmaneser III. as allied against him with Bir-idri (Ben-Hadad II.), Ahab, etc., at the battle of Karkar (B.C. 854). His name is not convincingly Semitic, though we cannot affirm it to be Hittite. Zakir, King of Hamath (a little before B.C. 800), whose inscription we possess (cf. p. 173), bears a Semitic name and writes in Aramaic, though some at any rate of the seven kings with whom he is at war are also Aramaeans ('Bar-Hadad the son of Hazael' = Ben-Hadad III. of 2 Kgs. 13²⁴; ברנש = 'Bar-Gus, probably = 'Arami the son of Gus' mentioned by Shalmaneser III., *KB.* i. p. 170—a fact not hitherto noticed; and 'the King of Sam'al'). Later Kings of Hamath are Eniel (who paid tribute to Tiglath-Pileser IV., B.C. 738), and Ilu-bi'di or Ya'n-bi'di (subdued by Sargon, B.C. 720), both of whom bear Semitic names. Here, then, from the time of Zakir onwards, we have evidence for the Semiticization of Hamath; but whether this implies an Aramaean conquest or merely a gradual assimilation it is impossible to determine.

* Taking a comprehensive and summary survey of Judges as a whole, we may confidently conclude that the figures of Deborah and Barak, Gideon-Jerubbab, Abimelech, and Micah are historical, and that the narratives concerning them contain a very solid substratum of fact. The same may be affirmed with considerable probability of Ehud and Jephthah; though in the case of the narrative of the latter it remains ambiguous whether the enemy was Ammon or Moab. Balance of probability inclines (in the opinion of the present writer) against the historical character of Samson; though in any case the picture which is drawn of relations between

Thus we conclude our survey of the condition of affairs in Canaan and the surrounding countries prior to and during the period of the Judges of Israel. It is probable that the reader may notice a seeming omission: viz. that throughout we have advanced no theory as to the relation of Israel's early traditions to the course of history with which we have been dealing. This has been intentional. Throughout the section our aim has been to bring together relevant information derived from sources contemporary with the events to which they refer. The early traditions of the O.T. (and here we are speaking of the traditions of Gen. to Josh.) are embodied in sources which, in their written form, are certainly many centuries later than the events which they narrate. Opinions vary greatly as to their historical value; but, whatever view be held upon this question, it can hardly be disputed that, for our present purpose, the wiser course is not to mix contemporary historical evidence with other evidence into the interpretation of which the theoretical element is bound to enter in a greater or less degree.

This principle, however, calls for a certain qualification. External history of Canaan, though unfortunately very barren of information bearing directly upon the early movements of the tribes of Israel, *does* offer a few facts which call for correlation with the O.T. traditions; and the interpretations of these facts—especially in their chronological relation to the Exodus and the settlement in Canaan—has its bearing upon the historical period covered by the Book of Judges. The facts in question have been mentioned as they occur. It may be convenient here to tabulate them:—

Ja'cob-el, the name of a Hyksos chieftain, before B.C. 1580 (cf. p. lxvi).

Israelites and Philistines possesses a real historical interest. 'Othniel and the five minor Judges, Tola', Ja'ir, Ibsan, Elon, and 'Abdon, are undoubtedly not individuals but personified clans. Shamgar, the son of 'Anath, is proved to be an historical name by the allusion in *ch.* 5⁶; though, since this bare allusion is probably all that the author of the late insertion in 3³¹ had to go upon, it is at least as likely that he was a foreign oppressor as a deliverer (cf. p. 113). Comparison of the contemporary Song of Deborah with the parallel prose-narrative in *ch.* 4 affords incontrovertible evidence of the large amount of genuine history which may be found in the old prose-sources (cf. p. 82), even though (as we must probably assume) they were handed down orally for many generations before being committed to writing; and it is a fair inference that other old narratives which contain intrinsic evidence of their appropriateness to the circumstances of the period (*e.g.* the J narrative of Gide'on, and the stories of Abimelech and Micah) are no less historical. The only narrative which appears not to possess any historical value is the story of the outrage at Gibe'ah and the ensuing vengeance taken by Israel on the tribe of Benjamin; since the oldest form of the story (which we assign to J) is clearly constructed in close imitation of earlier J narratives, and appears to offer marked evidence of a special motive, viz. animosity to the memory of Saul. Even here, however, it would be bold to assert categorically (especially in view of the Shiloh-story in 21^{19ff.}) that no historical elements at all have entered into the narrative

Ja'cob-el and Jo'seph-el (?), place-names in Canaan, *cir.* B.C. 1479 (cf. pp. lxxvii f.).

Habiru pressing into Syria-Palestine, *cir.* B.C. 1375 (cf. pp. lxxiii ff.).

Samhuna, a place-name in Canaan, *cir.* B.C. 1375, possibly = Sime'on (cf. p. lxxv, *footnote*).

The name Asher occurs in western Galilee, *cir.* B.C. 1313 (cf. p. lxxxix).

Mineptah defeats a people called Israel in Canaan, *cir.* B.C. 1223 (cf. p. xcii).

The question of prime importance to us here is the *terminus a quo* which we are to assign to the period of the Judges. This depends upon the date at which the Exodus is placed; and on this point, fortunately, we possess reliable information. Ex. 1¹¹ J states that the Israelites, under the system of forced labour imposed upon them, 'built for Pharaoh store-cities, Pithom and Ra'am'ses'; and Naville has proved that the site of Pithom (called in Egyptian P-etôm, *i.e.* 'the abode of Etôm,' a form of the Sun-god) was the modern Tell el-Mashûta, in the east of the Wâdy Tûmilât, near the ancient frontier of Egypt, and that the founder of the city was Ra'messe II.* Thus, granted the historical truth of the Israelite tradition (and in such a matter there is no reason to suspect it), it follows that Ra'messe II. (*cir.* B.C. 1292-1225) was the Pharaoh of the oppression, and his successor Mineptah (*cir.* B.C. 1225-1215), probably the Pharaoh of the Exodus.†

If this is so, however, we observe at once that the external allusions above noted, which seem to refer to the presence of Israelite tribes in Canaan, are all prior to the Exodus; and that at any rate the last two appear to postulate the existence there of Israelite elements which must have been distinct from those that made their escape from Egypt under Mineptah. Asher is occupying in the reigns of Sety I. and Ra'messe II. the precise position in Galilee which, according to later Biblical tradition, was allotted to him *after* the settlement in Canaan effected through the conquests of Joshua; and a people named Israel forms a tribal element in Canaan (as is implied by its mention in the midst of Canaanite

* Cf. Naville, *The Store City of Pithom and the Route of the Exodus* (ed. 1, 1885; ed. 4, 1903); W. M. Müller in *EB.* 3782 ff.; Sayce in *DB.* iii. pp. 886 f.; McNeile, *Exodus* (*Westm. Comm.*), p. xciii; Driver, *Exodus* (*Camb. Bib.*), pp. xxx, 4.

† So at least we infer from Ex. 2²³, 4¹⁹ J, which indicate that, in the view of the narrator, the Pharaoh of the Exodus was the next after the great oppressor. Obviously, however, we cannot postulate the same degree of accuracy for this conclusion as for the statement of Ex. 1¹¹. Mineptah's reign was not very long (about ten years); and supposing that the Exodus took place not under him but in the period of weakness and anarchy which immediately followed his reign, we cannot be sure that the J writer would have known of this, or, knowing it, would have thought it necessary to make the point clear. In any case, however, it is obvious from the Hebrew narrative that the Exodus followed at no long interval after the death of the Pharaoh of the oppression.

place-names*) at a date nearly coincident with (or rather earlier than) the Biblical Exodus.

The conclusion that the historical Exodus from Egypt did not include the whole of the tribes which were subsequently known as 'Israel' is not, however, to be drawn from these external references merely, but is inherent in the earliest traditions of the O.T. itself, if they be read between the lines. It is clear that the conception of Israel as a unity of twelve tribes, effecting the conquest of Canaan in a body under the leadership of Joshua, can only have arisen long after these twelve tribes had been welded into a political whole under the monarchy. Indeed, we can trace, in the different strata of the Biblical narrative, the growth and hardening of this conception.

The oldest account of Israel's settlement in Canaan, as we have it in Judg. 1¹⁻²⁵ from the narrative of J, representing as it does Israel's occupation as very gradual and partial, effected largely by the individual efforts of each of the tribes rather than by a great united movement, differs widely from the impression produced by R^d in Josh., according to which the whole of Canaan, except the maritime plain and the Lebanon district (cf. Josh. 13¹⁻⁶), was conquered by the combined tribes under the leadership of Joshua; and the impression produced by the theory of R^d has been heightened and stereotyped in the document which forms the main part of Josh. 13¹⁵⁻²¹⁴², in which a post-exilic priestly writer (P) represents the detailed allocation of the whole of Canaan among the tribes as the work of Joshua subsequent to the conquest (cf. pp. 1 f.). In choosing between these differing conceptions of the conquest of Canaan, we cannot hesitate for an instant in selecting the presentation of J as nearer to the truth, and in explaining that of R^d and P as coloured by the circumstances of later times. It is true that even J, as we have the historian's work in Judg. 1 (cf. the original form of the narrative as reconstructed in *Addit. note*, p. 47), seems to represent the tribes as assembled at Gilgal (2¹) or at Jericho (1¹⁶), and as starting their individual efforts from this point largely under the direction of Joshua (cf. *ch.* 1³, *note*); but that this conception sits very lightly upon the narrative is clear. Careful examination of the movements of separate tribes in the light of all available Biblical information proves *e.g.* that Judah must have conquered his inheritance, not by moving southward from Jericho, but by moving northward from Kadesh-Barnea into the Negeb, and subsequently into the district of Hebron (cf. *Addit. note*, p. 44)—therefore independently of Joshua. The settlement of half-Manasseh east of Jordan, in northern Gilead, which the later

* In view of the grouping in which the reference to Israel occurs, the alternative explanation which suggests itself—viz. that we may have here Mineptah's version of the Exodus, the disappearance of Israel in the waterless desert being, from the Egyptian point of view, regarded as equivalent to their extinction—may be dismissed as out of the question.

sources in the Biblical narrative assume to have been decided upon by Moses and confirmed by Joshua' (cf. Dent. 3¹³, Num. 32³³ R¹, * Josh. 13²⁹⁻³¹ P), is shown by the J narrative of the settlement (if Josh. 17¹⁴⁻¹⁸ as slightly modified, and, in sequence, Num. 32^{39,41,42}, Josh. 13¹³, are rightly assigned to it: cf. pp. 49 ff.) to have been really an overflow-movement from the west of Jordan owing to want of room in the latter district; and though the J narrator himself assumes that the movement was made at the advice of Joshua', the reference to the Machir-clan of Manasseh in Judg. 5¹⁴ as still west-Jordanic in the time of Deborah leads us to infer that it did not take place until some time after Joshua's death (cf. note on 'Machir,' pp. 134 f.).

Concluding, therefore, as we seem bound to do, that the representation of Joshua' as the head of a united body of twelve tribes, their leader in the conquest of the main part of Canaan, and the subsequent arbiter as to the precise extent of their heritages, is a comparatively late conception, finding little or no support in the earliest information which we possess, the way is prepared for the further inference that the tribes which he *did* lead across Jordan to the conquest of a footing in Canaan were probably a part merely and not the whole of the elements which went to form united Israel in later times: and, since tradition is doubtless correct in making him the successor of Moses in the leadership of Israel, that therefore the Israelites whom Moses led out of Egypt at the Exodus were not the whole of Israel, as the term was subsequently understood; but that certain elements which eventually formed part of the nation must have gained their heritages in Canaan by other means and at other periods.

This inference, which, as we have seen, is pressed upon us by the extra-Biblical evidence which seems to postulate the existence of Israelite tribes already settled in Canaan at the period when the tribes eventually delivered from bondage by Moses must have been still in Egypt, is further borne out by the evidence of the O.T. The tribe Asher, which appears from Egyptian evidence to have been settled in its permanent heritage by the reign of Sety I., *i.e.* about one hundred years before the Exodus, belongs to the group of tribes which Israelite tradition represents as descended from the sons of handmaids and not full wives—a tradition which can hardly mean anything else than that these tribes were regarded in later times as holding an inferior position in the Israelite confederacy, perhaps because they were not purely Israelite by race. The terms in which Dan—another member of the same tribal group—is mentioned in the old poem called 'The Blessing of Jacob,' Gen. 49¹⁶, are best explained as meaning that full tribal rights in the con-

* Num. 32, which appears to be a mixed narrative formed by combination of JE and P (cf. Driver, *LOT*,⁹ pp. 68 f.; Gray, *Numbers* (*ICC.*), pp. 425 ff.) deals throughout with the negotiations of Gad and Reuben alone. It is only in v³² that half-Manasseh is introduced—evidently by a very late hand.

federacy, though eventually won, were not won until some little time at least had elapsed after the final settlement of all the tribes in Canaan (cf. p. 392). Other facts which make in the same direction are the detachment of the handmaid-tribes Gad, Dan, and Asher from the common interests of Israel in the time of Deborah, as evinced by their failure to respond to the call to arms (Judg. 5¹⁷ *); and the names of these same three tribes, which point to their primitive adhesion to forms of cultus other than pure Yahweh-worship (cf. pp. 197, 392).† In J's account of the settlement, Asher, Naphtali, and Dan are very far from appearing in the light of recent and successful invaders. The two former 'dwelt in the midst of the Canaanites,' i.e. it is the Canaanites who hold the predominance, both in numbers and in power§; while the last-named is actually ousted from his territory and driven up into the hills (ch. 1³¹⁻³⁴).|| Gad is unmentioned.

* Naphtali, the remaining handmaid-tribe, forms an exception—probably because, owing to his geographical position, his interests were directly concerned.

‡ If there was a god Asher who was a form of the Moon-god (as is suggested by the evidence brought together on pp. 196 ff.), he may also have been regarded as a particular aspect of the God Yahweh (cf. p. 197, *footnote* *; *Addit. note*, p. 249) by the Canaanite worshippers of that Deity; and this may explain why the symbol of his (assumed) consort Ashera was so often set up by the side of Yahweh's altar, and also the keen antipathy with which the Ashera was regarded by the exponents of the ethical (Mosaic) form of Yahweh-religion. For the theory of two forms of Yahweh-religion, one long indigenous in Canaan and marked by naturalistic characteristics, the other, highly ethical in character, owing its origin to Moses (or rather to the revelation vouchsafed to him), and introduced into Canaan by the Israelite tribes who came under Moses' influence, cf. the present writer's article in *JTS*. ix. (1908), pp. 321 ff. If Dan, however, is a title of the Sun-god (cf. p. 392), then here we can trace no connexion with Yahweh, however remote; and it is open to conjecture that this tribe may not have embraced the worship of Yahweh until their migration to the north and forcible appropriation of Micah's *sacra* and his Yahweh-priest, whose worth had been proved for them by the oracle indicating the success of their undertaking. If the interpretation of ch. 18⁵ suggested in the *note ad loc.* is correct, the Danite spies do not ask for an oracle from Yahweh in the first place, but from the Teraphim ('*Elôhim*'); and it is the latter which returns the answer as from Yahweh. As to Gad, the god of Fortune, in relation to Yahweh we can affirm nothing.

§ Contrast the statement with regard to Ephraim (ch. 1²⁹), from which we learn that, though this tribe 'did not dispossess the Canaanites that dwelt in Gezer,' yet 'the Canaanites dwelt in the midst of Ephraim,' and not *vice-versa*.

|| Steuernagel (*Die Einwanderung der israelitischen Stämme in Kanaan*, pp. 28f.) has suggested with some plausibility that, since Naphtali and Dan were originally one tribe (Bilhah), and Dan at first dwelt south-west of Ephraim, Naphtali's earliest home was probably in the same neighbourhood, and he, like Dan, eventually had to seek a new home further north. Thus, in the statement of Judg. 1³³ that 'Naphtali did not dispossess the inhabitants of Beth-shemesh and Beth'anath,' the reference may be to the southern Beth-shemesh ('Ain-šems). The mention of these two cities in the north in Josh. 19³⁸ P is then a later assumption based on the fact that Naphtali later on occupied a northern position. This view gains some support from the blessing of Naphtali in Dent. 33²³—'Possess thou the Sea and the South' (ים ודרום ירשה). Here Naphtali (according to Steuernagel) appears, like Dan, to

Not merely the four handmaid-tribes, however, but probably also some of the tribes which were reckoned as full members of the Israelite confederacy, may be conjectured to have taken no part in the historical Exodus. The northern tribe Zebulun stands in J's narrative (*ch.* 1³⁰) on much the same footing as the handmaid-tribes Asher, Naphtali, and Dan; *i.e.* so far as the information offered us is concerned, he is *there* in Canaan maintaining a precarious footing among the Canaanites, and nothing is told us as to how he *came to be* there. Another northern tribe, Issachar, is unmentioned in the document as we know it; and the same is true of the trans-Jordanic Reuben. In fact, the only tribes of which the J writer records *conquests* fall into two groups: (1) Judah and Simeon, and (2) the house of Joseph. We have found reason to believe that the conquests of the first group took place not under Joshua from the east of Jordan, but by a northward move from Kadesh-Barnea. The house of Joseph, on the other hand, is explicitly connected with Joshua in the part of the narrative which now stands in Josh. 15^{14,18}; and there are indications which suggest that the southern campaign as described by JE in Josh.—viz. the conquest of Jericho, Ai, and Bethel, and the defeat of the Amorite league at the descent of Beth-horon—was really carried out by these Joseph-tribes under Joshua's leadership, and not by united Israel (*cf.* 1²² *notes*).

It is clear that the tradition which connects the Joseph-tribes with Egypt is primitive and authentic. Whether they were the only tribes which suffered under Egyptian bondage and were delivered by Moses is a further question. We find in early times certain Israelite or related clans dwelling in the south of the Negeb close to the borders of Egypt. These are the north Arabian clans which ultimately went to form the tribe of Judah (Kenites, Jerahme'elites, etc.; *cf.* p. 45); the remnant of Simeon which, after a tribal disaster in central Canaan, appears to have sought a home in the extreme south, in the neighbourhood of the Judah-clans (*cf.* *ch.* 1³ *note*); and probably the remnant of Levi—as we may conjecture from the early association of this tribe with Simeon in the raid on Shechem with its disastrous results, and from its subsequent association chiefly with the tribe of Judah (*cf.* *Addit. note*, pp. 436 ff.). Whether any of these Israelite clans crossed the frontier into Egypt we cannot say for certain; but considering the comparatively hard conditions of existence in the region south of the Negeb, and the readiness with which permission

be hard-pressed by foes, and the wish is expressed for him that he may exert his power and conquer the Philistine maritime plain (*yām*) and the *dārôm*, *i.e.* the Shephelah, which is so designated in late Jewish usage (*cf.* Neubauer, *Géographie du Talmud*, pp. 62 f.; Buhl., *Geogr.* p. 85, and references to Daroma in *OS.*, where we find cities such as Eleutheropolis, 'Anab, Eshtemoa', and Šiklag assigned to the region). On the ordinary assumption that Naphtali is here pictured as occupying his final northern position, 'sea' is explained as the sea of Galilee; but no commentator has succeeded in offering a plausible explanation of *dārôm*.

to pass into the region of Goshen (the Wâdy Tûmilât) was granted by Egyptian kings of the Empire-period to similar tribes when impelled by stress of famine,* it is highly probable that they may have crossed and recrossed on more than one occasion—as often in fact as the pinch of hunger compelled them to seek a more fertile pasture-land, or the return of favourable seasons lured them back to the nomadic life to which they were accustomed. Evidence that Simeon was in Egypt at the period of the oppression may perhaps be found in the Joseph-story, according to which Simeon is the brother selected to be bound and retained as a hostage (Gen. 42^{24.36} E). That Levi, at least in part, was also there, seems to follow with the acceptance of the traditional view of the identity of the earlier secular tribe with the later priestly body (the view maintained in *Addit. note*, p. 436), since Moses was a Levite, and the Egyptian names borne by him and by Phinehas offer valid evidence both for the historical existence of the bearers and for their Egyptian connexions (cf. *ch.* 20²⁸ *note*, and *footnote*). Tradition is clear that some of the elements which subsequently went to form the tribe of Judah (*e.g.* the Kenites) were not in Egypt but in the wilderness (Midian); though it is conceivable that other elements of the tribe may have taken part in the Exodus. In any case there is good reason to believe that the Joseph- and Judah-groups were associated at Kadesh-Barnea for a considerable period, and together came under the influence and teaching of Moses (cf. *Addit. note*, pp. 439 f.).

Another point, which for our purpose it is important to notice, is the fact that the O.T. traditions represent the migration of Israel's ancestors from their early home in the east westward into Canaan, not as a single movement completed in a short space of time, but as a series of movements extending over a very considerable period. Assuming (as we are bound to do) that these early traditions deal in the main with the movements of *tribes* under the guise of individuals,† the earliest of these tribal move-

Cf. the inscriptions mentioned on p. 439, *footnote* *.

† The explanation of individuals as personified tribes, and of their doings as tribal movements, which is in fact forced upon us in regard to much that is related in the patriarchal narratives (cf., as typical instances, the accounts of Abraham's descendants by his second wife, Keturah, Gen. 25^{1ff.}, and of the relations of Jacob's 'sons' with Shechem, Gen. 34), must of course not be pressed to account for every detail in the stories; since some elements may possibly be due to the admixture of reminiscences as to actual individuals (tribal leaders, etc.), and a good deal in the setting of the stories (especially of those which are most picturesque and lifelike) undoubtedly belongs to the art of the story-teller. The literature which deals with this subject is endless. It is sufficient here to refer to the Introduction to Skinner's *Genesis* (*ICC.*), pp. iii-xxxii, and to Kittel, *GI*.² i. pp. 386-455, as offering markedly sane and judicious estimates of the character of the Genesis-narratives. Guthe (*Gesch. des Volkes Isr.* pp. 1-6) lays down canons for the interpretation of the narratives in their historical reference to tribal movements which are helpful so long as the qualifications above suggested are borne in mind.

ments is represented by the journey of Abraham (Abram) and his nephew Lot from Harran into southern Canaan—a movement which tradition regarded as responsible for the formation of the different divisions of the 'Hebrew' race, Ja'cob, Edom, Moab, and 'Ammon, not to mention various Arabian tribal groups to whom Israel acknowledged a relation more or less remote. Now the tradition embodied in Gen. 14 makes Abraham contemporary with Hammurabi (Amraphel), dating him therefore *cir.* B.C. 2100. The traces of lunar worship in early Hebrew religion centre primarily round the Abraham-tradition, and undoubtedly connect Abraham with Ur and Harran, and with the First Dynasty period (cf. the facts cited in *Addit. note*, pp. 249 ff.). Whether, therefore, we regard Abraham as an historical clan-chieftain or as the ideal personification of the clan itself, there is good ground for believing in the historical truth of a Semitic clan-movement at this period from Ur to Harran, and thence to southern Canaan (Be'er-sheba'). And since, as we have seen (pp. lxxxi, lxxxiii), there were Habiru in Babylonia as early as the time of Hammurabi and Rim-Sin, it is reasonable to conclude that this migration was (as the O.T. tradition represents it) the beginning of the Hebrew westward movement—itsself but a part of the larger Aramaean movement which indisputably continued during a period of many centuries.

A subsequent accession from the east seems to be represented by the arrival of the Aramaean tribe Rebekah, who, by union with Isaac, Abraham's 'son,' produces the two tribal groups, 'Esau-Edom and Ja'cob. These for a while dwell together in southern Canaan, until the hostile pressure of the former compels the latter to cross the Jordan in the direction of his ancestral home, where, in course of time, he unites with fresh Aramaean elements (Ja'cob's wives). Ultimately the whole tribal body thus formed moves once more towards Canaan, impelled as it appears by the westward pressure of other Aramaeans (the pursuit of Laban), with whom eventually a friendly treaty is formed, fixing the tribal boundary at or near Misphah in Gilead.* When this Hebrew group, thus modified by fresh accessions, once more enters Canaan, it no longer bears the common name of Ja'cob, but is known as Israel.†

We may now observe that this tribal interpretation of early Israelite traditions—taken in broad outline *as they stand*, and with-

* Cf., for the interpretation of early tradition embodied in this paragraph, Steuernagel, *Die Einwanderung der israelitischen Stämme in Kanaan* (1901), §§ 6 ff. Steuernagel's book is a far-seeing and suggestive examination of early Israelite tradition which merits careful study.

† It is possible, as Steuernagel assumes, that the Le'ah- and Zilpah-tribes may have been in Canaan earlier than the Bilhah- and Ja'cob-Rachel-tribes, and, coming subsequently to be regarded as 'brothers' of the latter, were not unnaturally traced back to a common 'father.' Thus, owing to priority of settlement, Le'ah comes to be regarded as the earlier wife, while Rachel is the more closely united and better-loved wife. Cf. *op. cit.* p. 51.

out any shuffling or rearrangement to fit in with a preconceived theory—offers us a chronological solution of most of the facts derived from extra-Biblical evidence (pp. ciii f.) which seem to have a bearing upon the history of Israel's ancestors. If the Hebrew immigration into Canaan represented by Abraham really took place as early as *cir.* B.C. 2100, it is natural that a tribe called Jacob, descended from Abraham, should have given its name to a site Jacob-el in southern or central Canaan by B.C. 1479.* And if the Jacob-tribe, having again crossed the Jordan eastward, returned to Canaan at a later period increased by fresh Aramaean accessions, this may well have been in process of happening, *cir.* B.C. 1375, when, as we know from the T.A. Letters, an Aramaean people called Habiru were pressing into Canaan, and gradually gaining a footing there upon a semi-nomadic basis (*i.e.* transitional between the nomadic and the settled stage), much as Jacob-Israel and his 'sons' are represented in Gen. as doing.† The fact that Jacob, in making his westward migration, is pressed by the Aramaean Laban agrees with the T.A. presentation of the Habiru-movement as of a part with a widespread Aramaean movement as represented by the SA.GAZ and the Sutû; and the seizure of the district of Shechem by the Habiru (cf. p. lxxiii) may well be identified with the events of which we have an echo in Gen. 34, 48^{21,22}. Indeed, the latter passage can hardly be explained except upon the assumption that the Shechem-district, which eventually came in post-Exodus times to form part of the possession of the Joseph-tribes, had been captured at an earlier period by another section of Israel. Finally, the allusion to *Israel* as a people in Canaan in the reign of Mineptah, *cir.* B.C. 1223, agrees with the Biblical tradition that Jacob on his second entry into Canaan assumed the new name Israel. If it be merely a coincidence that prior to the Habiru-invasion we have external evidence for Jacob in Canaan, while subsequently to it we have like evidence for Israel, it is certainly a remarkable one.

A further question upon which we have not yet touched concerns the period at which the Joseph-tribes broke off from the rest of Israel and migrated to Egypt. It has commonly been

* The name Jacob (*Ya'āqōb*), like Isaac (*Yishāq*), Joseph, etc., is a verbal form implying the elision of 'ēl, 'God,' as subject of the verb. Cf. the personal and place-name *Yiphtah* (Judg. 11¹ ff., Josh. 15⁴³) with the place-name *Yiphtah'el* (Josh. 19^{14,27}), and the place-name *Yabneh* (2 Chr. 26⁶) = *Yabne'el* (Josh. 15¹¹). Other examples of tribal-names thus formed are *Yisrā'el* and *Yismā'el* (but probably not *Yerahmē'el*; cf. p. 252). Other place-names so formed are *Yizre'el*, *Yekabs'el* (Neh. 11²⁵ = *Kabsē'el*, Josh. 15²¹, 2 Sam. 23²⁰), *Yokthe'el* (Josh. 15³⁸, 2 Kgs. 14⁷), *Yirpe'el* (Josh. 18²⁷). On the transference of tribal names to places or districts, cf. Burch. ii. p. 84. The West Semitic names *Yabkub-el*, *Yakub-el* (without expression of *y*, which is represented in the first example by *l*), *Yakubum* (hypocoristic, exactly like Jacob) occur in early Bab. documents; though we cannot be quite sure of their equivalence to Jacob, since the syllable *kub* may also stand for *kup*, *kub*, *kup*. Cf. Ranke as cited by Gressmann, *ZATW.* xxx. (1910), p. 6.

† Cf. Kit. *GVZ* i. p. 410.

assumed that this must have taken place during the Hyksos domination. This conclusion is based partly upon the assumption that the entry of Semitic tribes into Egypt would have been most likely to have occurred under the Hyksos, who were themselves in all probability Asiatic Semites; partly upon the fact that the duration of Israel's sojourn in Egypt, as given in Ex. 12⁴⁰ P, viz. 430 years, if reckoned backward from the probable date of the Exodus in the reign of Mineptah—say, from B.C. 1220, gives B.C. 1650 as the date of entry, which falls well within the Hyksos-period, whether we adopt the long or the short scheme of reckoning that period (cf. p. lxvi). If, however, we are correct in identifying the immigration of Israel and his 'sons' into Canaan with the invasion of the Habiru, *cir.* B.C. 1400, and if, again, it is the fact that the O.T. traditions preserve a substantially correct recollection of the *order* of events (as we gathered from our preceding discussion), then it appears that Joseph did not break off from his brethren and go down into Egypt until *after* the Habiru-invasion, *i.e.* perhaps two centuries after the expulsion of the Hyksos by Ahmose I., the founder of the Eighteenth Dynasty. It is remarkable, indeed, that if the Pharaoh under whom Joseph is represented as rising to power was a member of the Hyksos-dynasty, the 'new king, who knew not Joseph' (Ex. 1⁸), and instituted an era of oppressive measures in order to check the increase of Israel, is found, not in Ahmose I., who expelled the hated Semitic invaders, but in Ramesses II. of the Nineteenth Dynasty, nearly 300 years later. The Biblical estimate of 430 years for the duration of the sojourn in Egypt belongs to the latest stratum of the narrative, and is clearly bound up with a purely artificial system of calculation (cf. p. cxvi). A different tradition is preserved in the \mathfrak{C} text of the passage, where the addition of the words $\kappa\alpha\iota\ \epsilon\iota\varsigma\ \gamma\eta\ \chi\alpha\upsilon\alpha\alpha\nu$ makes the 430 years include the whole patriarchal period as well as the sojourn in Egypt; and since on the Biblical reckoning the former lasted 215 years, the latter is therefore reduced to a like period. This reckoning would give us B.C. 1435 as the date of the entry, *i.e.* during the reign of Amenhotep II.

Increasing knowledge of the history of Egypt during the Empire proves beyond a doubt that the period of the Eighteenth Dynasty, from the reign of Thutmose III. onwards, when Canaan was a province of Egypt and the intercourse between the two countries was (as we learn from the T.A. Letters) close and constant, is in all respects suited to the condition of affairs which, according to the Genesis-tradition, brought about the entry of Israel's ancestors into Egypt. The Egyptian inscription noticed on p. 439 *footnote*, in which Asiatic refugees crave, and receive, admission into Egypt,* belongs either to the reign of Haremheb or to that of one of the successors of Ahnaton under whom Haremheb held the position of

* Cf. Breasted, *A.R.* iii. §§ 10 ff.

general. Here the Asiatics beg the Pharaoh to grant them a home within the border of Egypt 'after the manner of your fathers' fathers since the beginning'—a statement which indicates that it had long been customary for the Pharaohs to grant such admission. Under Amenhotp III., when the power and luxury of the Empire were at their height, the development of trade between Syria and Egypt left its mark upon the Egyptian language through the introduction of a large Semitic vocabulary.* The Semitic population of Egypt must have been considerable, partly drawn thither by trade and partly as slaves, the captives of Asiatic campaigns. 'As this host of foreigners intermarried with the natives, the large infusion of strange blood made itself felt in a new and composite type of face, if we may trust the artists of the day.'† Some of these Semitic foreigners rose to important positions of trust and authority in the state. Such were Dûdu and Yanhamu, two high officials bearing Semitic names who are often mentioned in the T.A. Letters.§ Indeed, the position of the latter, who was high commissioner over Yarimuta, a great corn-growing district,|| offers several points of analogy to the position of Joseph as pictured in Gen., and he has been thought with some plausibility to be the historical figure round whom the story of Joseph's rise to power in

* Cf. Breasted, *Hist. Eg.* p. 337.

† Cf. Breasted, *Hist. Eg.* p. 339.

§ On the name Dûdu, cf. p. 291. Yanhamu may stand for ינעם, which is known as a Sabea proper name: cf. Weber in Kn. p. 1171.

|| Yarimuta was reached by sea from Gebal, and thence the Gebalites imported the necessities of life, especially corn, for which, when reduced to straits, they were obliged to barter their sons and daughters, and the furniture of their houses (a fact which reminds us of Gen. 47^{18ff.}): cf. references given by Weber in Kn. p. 1153. The view that Yarimuta lay in the Delta, and was possibly identical with the land of Goshen, is favoured by Niebuhr in *MAG.*, 1896, 4, pp. 34-36; W. M. Müller in *MAG.*, 1897, 3, pp. 27 f.; Weber in Kn. p. 1153; Dhorme, *RB.*, 1909, p. 370; Hall, *NE.* p. 346. If, however, it is the same as Yarmuti in 'the upper land' to which Sargon of Akkad lays claim in the inscription recently published by Poebel (cf. p. lv, *footnote* ¶), it can hardly have lain in the Nile-Delta, but must be sought upon the Syrian seaboard. Poebel suggests 'the plain of Antioch, along the lower course and at the mouth of the Orontes river' (*op. cit.* pp. 225 f.). The resemblance of the Biblical name ירמות Yarmuth is striking; and so is that of the Benjaminite clan-name ירימות Y'rimôth or Y'erêmôth. The former was a Canaanite city of some importance (associated with Jerusalem, Hebron, etc., in Josh. 10^{3.5.23} JE), and situated in the Shephelah (Josh. 15²⁵ P)—a fact which would seem to exclude comparison with the maritime Yarimuta, unless (as is not impossible) the name was extended to denote not merely the city but the southern maritime plain which afterwards belonged to the Philistines, and which was, and still is, an excellent corn-growing country: cf. the description of it by Eshmun'azar, king of Sidon (quoted on p. 387, *footnote* *), which suggests that Sidon was dependent upon the district for its corn-supply. Whether, however, Yarimuta actually lay within the borders of Egypt or not, the fact that Yanhamu was constantly in Egypt and in close touch with the Pharaoh as a high official of the court remains undoubted: cf. the conspectus of allusions to him given by Weber in Kn. pp. 1169 ff.

Egypt was constructed.* If, then, we may assume that the entry of the Joseph-tribes into Egypt took place during the flourishing period of the Empire,† it is likely that the change of policy under Ramesse II., which led him to take measures to oppress and to check the increase of the Hebrews, may have been dictated by the fact that the loss of Egypt's hold upon her Asiatic empire, which resulted from the weakness of Ahnaton and his successors, tended to make the presence of a considerable body of Semitic aliens upon the north-east border of Egypt a menace to the safety of the state.‡

While, however, our theory places the entry of the Joseph-tribe into Egypt considerably later than the Hyksos-period, this does not forbid the view that earlier ancestors of Israel may have been in Egypt with the Hyksos. If Abraham represents a Hebrew migration to Canaan some centuries before the Hyksos-invasion of Egypt, and if this invasion was a southward movement of the people of Amurru (cf. p. lxvi), it seems not at all unlikely that some of Israel's ancestors, who (as tradition informs us) occupied southern Canaan,

* Cf. J. Marquart, *Chronologische Untersuchungen* (*Philologus Zeitschr. für das class. Alterthum: Supplementband* vii. 1899), pp. 677-680; Winckler, *Abraham als Babylonier, Joseph als Ägypter* (1903), p. 31; Cheyne in *EB.* 2593; Jeremias, *OTLAE.* ii. pp. 72 ff.; Weber in *Kn.* p. 1171.

‡ Evidence does not allow of our fixing a more exact date. We naturally infer that it was after the invasion of Canaan by the Habiru had begun, if this is rightly identified with the entry of the tribes of Israel into that country; but the T. A. Letters, though they show us this invasion in full flow, afford no evidence as to the date at which it began. The theory that the people (marked as foreigners by a Determinative) called 'Apu^{ri}u or 'Apu^{ri}u in Egyptian inscriptions were the Hebrews, which was first advanced by Chabas (*Mélanges Égyptologiques*, i. Ser., 1862, pp. 42-55; ii. Ser., 1864, pp. 108-165), accepted by Ebers (*Ägypten und die Bücher Mose's*, 1868, p. 316; *Durch Gosen zum Sinai*², 1881, pp. 505 f.), and then generally contested and rejected by Egyptologists, has been revived by Hommel (*AHT.* p. 259), and supported with strong arguments by Heyes (*Bibel und Ägypten*, 1904, pp. 146-158), and is regarded as plausible by Skinner (*Genesis* (ICC.), pp. 218 f.). Driver, *Exodus* (Camb. Bib.) pp. xli f.), and other Biblical scholars; though among modern Egyptologists Maspero (*Mémoires*, p. 443, n.³; *Contes populaires*, p. 119, n.³) and Breasted (*AR.* iv. § 281, n.^c) definitely reject it, while W. M. Müller (*EB.* 1243) more guardedly refuses to decide either for or against it. The chief objection to the identification seems to be found in the representation of Heb. *b* by Eg. *p*; but that this interchange, though rare, does actually occur is proved by Heyes (cf. *op. cit.* p. 148; his best instance is Eg. *hurpu* = Heb. *hērebh*, 'sword'): cf. also Burch. § 50. The 'Apu^{ri}u find mention in inscriptions ranging from the reign of Thutmose III. to that of Ramesse IV. (cir. B.C. 1167): thus, if they were really the Hebrews, the inference must be that some Hebrews (not necessarily Israelites) remained behind in Egypt after the Exodus. Cf. the discussion by Kit. (*GV.*² i. p. 453, n.²), who concludes that, though they may have been Hebrews in the wider sense, they can hardly have been Israelites. The inscriptions picture them as performing (like the Hebrews of Ex. 1^{11ff.}) heavy manual labour in connexion with the building operations of the Pharaohs, especially the quarrying and transportation of stone. Driver (*op. cit.*) gives a convenient conspectus of the passages in which they are mentioned.

§ Cf. Spiegelberg, *Der Aufenthalt Israels in Ägypten* (1904), pp. 35 ff.

may have been implicated in it. The tradition of Gen. 12¹⁰⁻²⁰ J, which brings Abraham and his wife and followers to Egypt in time of famine, looks not unlike an echo of the Hyksos-period; and the way in which the patriarch is represented as escorted out of the land may not impossibly amount to the placing of the best interpretation upon a dismissal which may really have been an expulsion—possibly based on a vague recollection of the actual expulsion of the Hyksos by Ahmose I. If this is so, it is not impossible that the Hyksos-chieftain Ja'cob-el may have been a representative of the Ja'cob-tribe.

Thus the only extra-Biblical allusion to Israel's ancestors for which, on our interpretation of the Biblical tradition, we fail to find an explanation is the supposed occurrence of Joseph-el as a place-name in Canaan, *cir.* B.C. 1479; since, on our theory, the Joseph-tribe can scarcely have been in Canaan at this date. The interpretation of *Y-s-p-'â-ra* as Joseph-el is, however, as we have noticed (p. lxviii), of very doubtful validity.

The view which makes Ra'messe II. the Pharaoh of the oppression, and Mineptah, or one of his immediate successors, the Pharaoh of the Exodus, though favoured by the majority of scholars, is not universally accepted. The fact is certainly remarkable that, if we take the Biblical scheme of computation as it stands, and adding 480 years to B.C. 967 (which is fixed with approximate certainty for the fourth year of Solomon: cf. p. liii, *footnote*), in accordance with the statement of 1 Kgs. 6¹ R^p, obtain B.C. 1447 (in the reign of Amenhotp II.) as the date of the Exodus; then add 430 years for Israel's residence in Egypt (cf. Ex. 12⁴⁰ P), and obtain B.C. 1877 (in the Hyksos-period according to Petrie's longer scheme of chronology, though earlier according to Breasted and Hall) for the entry into Egypt; then add 215 years for the Patriarchal period (according to Gen. 12^{4b}, 21⁵, 25^{26b}, 47^{9a}, all P*), and obtain B.C. 2092 for Abraham's departure from Haran; this last date falls within the reign of Hammurabi (*cir.* B.C. 2123-2081) in accordance with the tradition of Gen. 14. Thus Hommel ‡ adopts the reign of Amenhotp II. for the Exodus.

It should not, however, escape our notice that the one fact which makes this computation remarkable is the approximate correctness of the exterior dates, viz. that 1125 years appear accurately to represent the period from a date in Hammurabi's reign to a date in Solomon's reign. This is probably not the result of accident, but may well be due to the fact that a Jewish chronologist living in Babylon during the exile may easily have obtained from Baby-

* According to this scheme Abraham is seventy-five on his departure from Haran, and one hundred at the birth of Isaac; Isaac is sixty at the birth of Ja'cob, and Ja'cob is one hundred and thirty when he enters Egypt with his sons.

‡ *ET.* x. (1899), pp. 210 ff. Hommel assigns in each case a date nine years later than those given above. Orr, *Problem of the Old Testament* (1908), pp. 422-424, adopts the conclusions of Hommel.

lonian sources the figure which represented the period from Hammurabi to his own day.* This, however, argues nothing for the correctness of the sectional periods within the external limits. The back-reckoning to Solomon is of course based upon the (approximately correct) chronology of Kgs.; but the Babylonians could supply no information as to the date of the Exodus, or of Israel's entry into Egypt, or of the lives of the patriarchs. As we have seen (§ 5) in discussing the period assigned in 1 Kgs. 6¹ for the Exodus to the fourth year of Solomon, 480 years is a purely artificial computation, based on the theory of twelve generations of forty years each, and worked out within the period by the use of suspiciously recurrent periods of forty years. If, however, we cannot find even an approximately historical basis for the Biblical chronology of *this* period, why should we pin our faith to the correctness of the earlier periods given for Israel's sojourn in Egypt (based, apparently, on the assumption of four generations of one hundred years each!†), and for the lives of the patriarchs? The reign of Amenhotp II., when Egypt's hold upon her Asiatic empire was at its strongest immediately after the victorious reign of Thutmose III., may well be thought to be the least probable period for the Exodus and settlement in Canaan by force of arms.

Another view as to the date of the Exodus is represented by Hall (*NE.*, pp. 403 ff.), who attempts to revive the theory of Josephus (*C. Ap.* i. 14) by connecting the Exodus with the expulsion of the Hyksos; and further supposes that the aggressions of the Habiru, as we read of them in the T.A. Letters, are identical with the invasion of Canaan by the Israelites under the leadership of Joshua. This theory is obliged to do great violence to the Biblical tradition; for not only are the circumstances of Ahmose's expulsion of the Hyksos widely different from the Biblical account of the Exodus, but, in order to dispose of the inference (based on Ex. 1¹¹) that Raïmesse II. was the Pharaoh of the oppression, the names Pithom and Raïmsès have to be explained as 'the interpretations of a scribe who knew their names as those of Egyptian cities which existed in his time in and near the land of Goshen' (p. 405), and, to bridge the interval between Ahmose I. and Amenhotp III., the 'forty' years in the wilderness (probably intended to represent the length of a generation§) have to be expanded to nearly two hundred years (p. 408), and thus the possibility of a real historical connexion between Joshua and Moses is necessarily excluded. On the identification of Joshua's conquests with the Habiru-invasion we cannot, as Hall confesses (p. 410), identify any of the persons mentioned in the one source with those who are mentioned

* The care and accuracy with which the Babylonians preserved their chronological data, even back to the earliest period of their history, are familiar facts. Cf. Rogers, *HBA.* 6 i. pp. 470 ff.

† Cf. Driver, *Exodus* (*Camb. Bib.*), p. xlv, and notes on C 27, 12⁴⁰.

§ Cf. Num. 14²⁶⁻³⁵ JEP, 32¹³ P, Deut. 2¹⁴, and the remarks on p. liv.

in the other.* The question whether the character of the Habiru-aggressions closely resembles the Biblical narrative of Israel's doings as depicted in Josh. must be largely a matter of individual opinion. In the view of the present writer the position of Habiru and SA.GAZ in Canaan is more nearly analogous to that of the floating, semi-nomadic population which has at all times formed a feature of Palestine—a population living at peace with the settled inhabitants of cities and villages when the country is under a strong government, though even then ever ready to seize the opportunity for blackmail and petty aggression; but a really dangerous element when affairs are unsettled and the government is weak or non-existent, and without scruple as regards selling their services for warfare and intrigue to the highest bidder. Such a relation towards the Canaanites—normally peaceful, but sometimes aggres-

* Orr (*The Problem of the Old Testament*, pp. 423 f.) likewise holds that the invasion of the Habiru 'synchronises very closely with the conquest of Canaan by the Israelites,' and finds in this 'a coincidence of much importance.' It is curious that this writer, whose book is a defence of the historical character of the O.T. against the attacks of criticism (cf. especially *ch. iii.*), and who rightly (in the opinion of the present writer) objects to the sweeping statement of Kuenen that 'the description of the Exodus from Egypt, the wandering in the desert, and partition of Canaan . . . to put it in a word, are *utterly unhistorical*' (cf. p. 57), should fail to observe that the identification of the Habiru-invasion with that of Israel at once cuts at the roots of the historical character of the old narratives in Josh. Comparison of the names of Canaanite kings in Josh. and the T.A. Letters, where we have information from both sources, yields the following result:—

	<i>Book of Josh.</i>	<i>T.A. Letters.</i>
Jerusalem	Adoni-şedek (10 ³)	ARAD-Hiba (Kn. 285 ff.).
Lachish	Yaphia ^a (10 ³)	{ Yabni-el (Kn. 328). Zimrida (Kn. 329).
Gezer	Horam (10 ³³)	Yapahi (Kn. 297 ff.).
Haşor	Yabin (11 ¹)	Abdi-Tirši (Kn. 228).

Here, since the T.A. names, as derived from actual contemporary letters, must necessarily be correct, the Biblical names, if referred to identically the same period, are *ipso facto* declared to be false; and if this is the fact with every name which can be tested, what ground have we left for holding that any names, or indeed any facts, mentioned in the Biblical account of the conquest of Canaan are of the slightest historical value? The only supposed historical *gain* arising from identification of the Habiru-invasion with the conquests of Joshua^a, is that it fits in well enough with the late Biblical scheme of chronology which we have already discussed (p. cxv); yet, while we can attach a real historical value to an ancient narrative in which the main outline (*i.e.* as concerns names, scenes, and actions) appears to be approximately true to fact, even though chronological data are lacking (as in J and E upon the view which we maintain), it is difficult to see what importance can be attached to the maintenance of a chronological scheme which (on the test of external evidence) at once wrecks the historical character of the narratives to which it is applied. To do Dr. Orr justice, it is probable that he did not realize the further implications of his argument as they are here pointed out; yet, if this is so, what is the value of an argument which, basing itself upon the supposed identity between two sets of circumstances as pictured in Biblical and extra-Biblical sources, neglects so obvious a precaution as the comparison of the names of some of the principal actors?

sive—appears more nearly to correspond to the position of Israel in Canaan in patriarchal times (cf. for the aggressive side, Gen. 34), than to the invasion of the Joseph-tribes under Joshua which, when we have made all allowance for the exaggerations of R^p, was still a definitely organized campaign of conquest. In any case, since, as we have seen (cf. pp. lxxv ff.), it is impossible to separate the Habiru from the SA.GAZ, or to deny that the former were, at least to a large extent, identical with the latter, the Habiru-invasion must have extended over a far wider (more northerly) area than did Israel's career of conquest even as interpreted by the later editors of the old narratives in Josh.

The outstanding advantage which seems to accrue from Hall's theory of the Exodus, as also from that of Hommel, is that we gain a far longer period for the course of events from the Exodus to the fourth year of Solomon, for which, as we have seen, the late author of 1 Kgs. 6¹ assigns 480 years, but which, if we place the Exodus under Mineptah, cannot really have covered much more than 250 years (cf. p. liii). Considering, however, the facts noticed on pp. liii f., no valid reason can be advanced in proof that a longer period than 250 years is required. On the other hand, supposing that we identify Joshua's conquest of Canaan with the Habiru-invasion, we are faced by the very real difficulty that the Syrian campaigns of Sety I. (which dealt primarily with the Habiru-aggressions; cf. p. lxxxviii), Ra'messe II., Mineptah (who actually defeated *Israel*), and Ra'messe III. all fall within the period of the Judges; yet, while much is told us in Judg. of the aggressions of comparatively petty antagonists, not a word is said as to any collision with the great power of Egypt. Such an omission, which, on the theory of the Exodus which we adopt, is an argument from silence which may be taken to favour the general authenticity of the narratives of Judg. (cf. p. cii), must surely be deemed very strange if we are to throw Israel's occupation of Canaan under Joshua back to the period of the T.A. Letters.

§ 7. The Permanent Religious Value of Judges.

The religious value of any O.T. Book may be considered under a twofold aspect—(1) its place in the record of Revelation, *i.e.* the historical evidence which it affords as to the evolutionary process through which the religion of Israel attained its full growth; and (2) the extent to which its teaching is fitted to awaken a response in the human conscience of to-day. The value of the first aspect may be defined as *evidential*; that of the second as *spiritual*. Both these aspects are to be discerned in most of the O.T. writings; though it goes without saying that each aspect is not equally prominent in all. Without doubt the Prophetic writings exhibit the fullest combination of the two aspects, invaluable as they are, both

as marking stages in the development of Israel's religion, and also as making a direct appeal, whether it be to the collective or to the individual conscience, which can never become obsolete.

It should not, however, escape our notice that here there exists some amount of interaction between the two aspects. The spiritual value of the teaching of the Prophets has (as the outcome of modern critical study of the O.T. Scriptures) been greatly enhanced through the understanding of the circumstances of the times which called it forth, and of the relation which it bears to earlier thought.

In other parts of the O.T. literature we observe the one aspect greatly predominating over the other. Thus, *e.g.* a very large number of the Psalms, owing to an entire absence of historical allusions or any similar criteria of date, are difficult to place in their historical, or even in their logical, position in the line of religious development; yet at the same time their abiding spiritual worth, as evidenced by the manner in which they *touch* men's souls to-day, causing them to vibrate in spiritual sympathy, and voicing their highest and deepest aspirations in relation to God, is as great as that of any part of the O.T. Conversely, some portions of the historical literature—and perhaps most markedly the Book of Judges—are insignificant in their direct spiritual value as compared with the Prophets and the Psalms; yet their importance for the understanding of the historical evolution of Israel is unique.

Taking the O.T. as a whole, however, we notice, in part as compared with part, the same kind of interaction between the two aspects of religious value as we observed especially in the Prophetic writings when considered by themselves. The Psalm which voices the most inward feelings of Christian faith, invaluable as it is in itself, attains an enhanced value when the fact is clearly recognized that it is the product of a stage in a long line of religious development, for the tracing of which the historical books, as analysed and understood by modern critical methods, are of prime importance. For the question is at once raised how, out of beginnings exhibiting elements that are crude, primitive, and it may be even repulsive, there can have sprung to being thoughts and aspirations which, as the expression of all that we understand by *Religion*, have never been surpassed; and the only possible answer is found in the recognition of an inward Principle of Divine Inspiration, guiding and determining the course of Israel's religious evolution. Conversely, such a record of Israel's early history as the Book of Judges, which, taken by itself, might (so far as its religious aspect is concerned) be deemed to possess a value not much deeper than that represented by the interests of the anthropologist or student of comparative mythology, becomes, in the light of that which O.T. Religion *taken as a whole* has produced (*e.g.* the level of faith and practice represented by the Prophets and Psalms), of deep, if not of vital, importance for the study of the antecedents of historical and practical Christianity.

(1) The value of Judg. for the history of Israel's social and religious evolution is obvious. The Book covers a period of transition from the unsettled and disintegrated tribal life to the more or less organized federation of tribes on the way to be moulded into a nation. The extent of the disintegration of the tribal units which afterwards went to form the nation can only be gathered from Judg., and would hardly be realized by us if we only possessed the records contained in the Pentateuch and Josh. in the form in which they have come down to us. We see the tribes acting to a large extent independently of their fellows, settling down as best they could in the midst of an alien population, which for the most part they seem to have been unable to subdue, adopting forms of religious cultus which were coloured by the beliefs and practices of their heathen neighbours, if not identical with them. When, however, a period of oppression at the hands of a foreign foe and of desperate misfortune supervenes, the man whom the crisis produces as leader and deliverer, and who at least in some cases (witness the Song of Deborah) succeeds in rousing the scattered tribes to such a measure of common action as foreshadows the later unity of Israel as a nation, acts in the name and at the instigation, not of some local Canaanite or Israelite Ba'al, but of Yahweh, the warrior-God whose ancient seat was found, not within Canaan, but at Mount Sinai in the desert-region of Séir, external to the land of Israel's settlement (cf. *ch.* 5⁴).

Here, then, are raised problems which press for solution before we can attain any really satisfactory grasp of the development of the early religion of Israel. How did Yahweh, whose earlier sphere of influence appears to have been conceived as extraneous to the land of Canaan, come to be regarded as asserting and maintaining His influence over Israel, and in Israel's favour, when the tribes were settled in the land of their inheritance? What was there in Yahweh's character and claim which enabled Him at times of special crisis to exercise a *unifying* influence over the scattered and somewhat heterogeneous elements out of which the nation of Israel was eventually produced? How was it that, when evidence points to the recognition of 'gods many and lords many,' and that not merely among the earlier Canaanite inhabitants, but among the tribes of Israel themselves, in spite of all, the worship of Yahweh, fostered apparently by crisis and misfortune, emerged as the dominant religion, and came (amid such unpromising surroundings) to be of the lofty spiritual and ethical character which we find exemplified in the Prophetical writings of the eighth century B.C. and onwards? Biblical history, as we know it, claims to supply answers to these questions. A special Providence, a chosen people, a unique Revelation made at an early period in the history of the race to a leader and teacher endowed with exceptional qualifications for his office—these are factors which tradition

pictures as guiding and determining the evolution; and however much modern scientific study may modify our conceptions of the *process*, it will be found that, apart from the recognition of such factors, the history of Israel's religious development remains an insoluble enigma.

(2) While, however, it is true that there is nothing in *Judg.* which makes a direct spiritual appeal to men's consciences at the present day at all comparable to that which is made by the teaching of the later Prophets, the fact must not be overlooked that the book is placed in the Hebrew Canon among 'the Former Prophets,' and occupies this position because it is history written with a purpose, and that purpose a religious one (cf. § 1). This religious purpose stands out very prominently in the main redactor's philosophy of history, according to which neglect of Yahweh's ordinances and the worship of strange gods lead to punishment, but true repentance is followed by a renewal of the Divine favour. The fact that God deals with nations in accordance with their regard or disregard for His moral laws offers a lesson the emphasizing of which can never become superfluous, especially at such a crisis as that through which the world is passing at the present time (1918). If it be objected that the editor of *Judg.* is reading into past history the standpoint of his own much later time, and drawing conclusions as to Yahweh's moral government which could not have been drawn by Israel in the time of the Judges, it may be replied, firstly, that the lesson as deduced by the editor would remain for the instruction of subsequent ages, fortified by the teaching of the later Prophets and of our Lord Himself, as well as by the experience of history, even if the historical data upon which it is based were only susceptible of such an interpretation in the light of more developed experience of Yahweh's moral dealings with His people; but, secondly, that it is by no means certain (in view of what has been said above on the personality of Moses and his inculcation of ethical Yahwism as of the nature of historical postulates in the evolution of Israel's religion) that at any rate some part of Israel (*e.g.* those, such as the Joseph-tribes, who had incontestably come under the influence of Moses) were unconscious that, in rejecting Yahweh and following the Ba'als and the Ashtarts, they were lapsing from a higher form of religion to a lower, and infringing the covenant into which Israel had entered with Yahweh as the outcome of the signal deliverance from Egypt, and the events which immediately followed it. It should be noticed that the doctrine of sin, chastisement, repentance, and salvation is not confined to the main redactor's pragmatic setting, but is worked out and emphasized by the lessons of past history in portions of the book which belong to the later school of E—*ch.* 6⁷⁻¹⁰, 10⁶⁻¹⁶, and in parts of 1 Sam. which seem to emanate from the same hand, and doubtless originally belonged to the same connected work—1 Sam. 7²⁻¹⁴, 8⁷⁻⁸, 10^{18, 19a}, 12¹⁻²⁵. These passages,

as we have already noticed (§ 4), are closely connected in thought with the formulæ of R^{E2}, and seem to have supplied their model.

If we go back to the most ancient parts of the narrative, we find the utmost emphasis laid upon the fact that the Judges act in the Divine strength which inspires and supports them, enabling them to gain the victory against odds which, from the human point of view, might seem to be insuperable. It is Yahweh who commissions them either by a prophetic message (4⁶) or by a Self-manifestation (6^{11ff.}, 13^{3ff.}), who promises His presence and support (6^{14.16}), and vouchsafes special signs in confirmation of His promise (6^{17ff.36ff.}, 13^{19ff.}). His Spirit 'comes upon' them (11²⁹; cf. 3¹⁰ R^{E2}), or 'clothes itself in' them (6³⁴), or 'rushes upon' them (14^{6.19}, 15¹⁴), or strengthens them in answer to prayer (15^{18.19}, 16^{28ff.}). He goes forth before His host in the visible manifestations of nature (5^{4.5}; cf. 4¹⁴), discomfits (4¹⁵) and gives into their hands their foes (3²⁸, 6^{9.15}, 8^{3.7}, 11³⁰, 12³; with 'before me' in place of 'into my hand,' 11⁹), and gives them victory (15¹⁸).

It is this fact that the achievements of the Judges were wrought in reliance upon the Divine guidance and power which impresses the writer of the Epistle to the Hebrews, and enables him to regard them as the heroes of Faith:—'the time will fail me if I tell of Gide'on, Barak, Samson, Jephthah; . . . who through faith subdued kingdoms, . . . from weakness were made strong, waxed mighty in war, turned to flight armies of aliens' (Heb. 11³²⁻³⁴). Without inquiring too closely into the ethical character of this 'faith' as viewed from the Christian standpoint, it is sufficient for us to reflect that it fulfilled, in relation to the age which produced it, the function which is fulfilled by the quality as we understand it at the present in the full light of Revelation; and thus we are still able to number these ancient heroes among the 'great cloud of witnesses' whose example and inspiration may help us to 'run with patience the race that is set before us.'

§ 8. Hebrew Text and Ancient Versions.

Hebrew Text. If we except the Song of Deborah, the Heb. Text (H) of Judg. may be said to be well preserved, being comparable in this respect with the narrative-portions of Josh. and Kgs., and superior to Sam. Such corruptions as occur are due to the ordinary causes which have affected the Heb. Text of the O.T. as a whole, and a rough classification of them may be not without value for the purposes of textual criticism; though the fact must be borne in mind that, from the nature of the subject, anything like an exhaustive and well-defined classification is out of the question. Reference is made throughout to the pages of the Commentary where the points in question are discussed.

1. Alteration.

Confusion of letters.—ב for ב[†], pp. 122, 136; ב for מ, p. 114; ד for ב*, pp. 123, 149, 486; ד for מ, p. 231; ד for ר*, pp. 39, 119, 225, 428, 434; ה for י*, pp. 212, 383, 461; ה for ו[†], pp. 479, 485; ה for ש, p. 366; ו for ב*, p. 157; ו for ת, p. 62; ט for מ[†], p. 112; י for ו[†], pp. 122, 123, 131, 186, 273; כ for י*, p. 388, 483; ל for ג, p. 156; ל for מ, p. 122; ל for ת, p. 226; מ for א, p. 364; מ for ב, p. 390; מ for ל, p. 123; נ for ד, p. 419; נ for ל*, p. 328; נ for ת, p. 115; ס for ב[†], p. 232; ס for ר, p. 365; ע for ש, p. 233; פ for ג*, p. 112; צ for ב, p. 212; צ for נ (or נ[†] for נ[†]), p. 435; צ for ו[†], p. 282 (cf. p. 207); צ for ב, p. 366; צ for ק, p. 128; ר for ד*, pp. 33, 219, 365 (cf. pp. 65, 122); ר for ק, p. 217; ת for א*, p. 281 (cf. p. 325); ת for ל, p. 319.

Here the examples marked * are most likely to have arisen in the ancient script, and those marked † in the square script. Many examples, however, can hardly be explained as due to similarity, and may have arisen from such an accident as the obliteration or illegibility of a letter, combined with the influence of the context in determining what the original word in which it occurs may have been. Such a case is no doubt to be seen in the substitution of ד for original מ in ההריר for ההרים, ch. 8¹².

Transposition of letters.—pp. 33, 119, 120, 128, 129, 133, 225, 312, 326, 491 (cf. p. 208).

Transposition of clauses.—pp. 102, 120, 124, 210, 387, 417.

Confusion of similar words and forms.—pp. 65, 74, 119, 129, 132, 227, 228, 277, 279, 280, 323, 361, 429, 459, 463, 471, 474, 478, 479, 480, 484, 485.

Substitution through propinquity.—pp. 137 (נפתלי for יששכר), 369 (בשרות for בקמות), 376 (היום for הלילה), 474 (שבט for שבטי).

Wrong division (a) of words.—pp. 119 f., 136, 150, 230, 474, 484; (b) of sentences. —p. 130.

Error due to the use of abbreviation in writing.—pp. 119 f., 123 f., 129, 149, 150, 307, 466.

Error in vocalization.—pp. 90, 93, 114, 120, 130, 147, 152 f., 188, 230, 278, 287, 316, 317, 326, 334, 372, 488, 492, 493.

Grammatical solecisms.—Masc. for Fem., pp. 93, 321, 493 (cf. p. 129); Fem. for Masc., p. 383 bis, 463; Sing. for Plur., pp. 226, 229, 463, 474, 492; Plur. for Sing., pp. 61, 68, 285, 287, 310, 347, 348, 480, 483; False Tense, pp. 73, 214, 383, 483.

Intentional perversion.—pp. 5, 58, 64, 65 f., 228, 434, 461 (cf. p. 32).

2. Insertion.

Dittography (a) of words.—pp. 61, 225, 475, 482 (cf. p. 68); (b) of letters. —pp. 90, 114, 316, 470, 482 (cf. p. 35).

Doublets.—pp. 57, 130, 139, 232, 327, 350, 351 f., 415, 423 f., 474, 485.

Other marginal notes inserted in the text:—pp. 113, 350, 382, 415, 428 (cf. p. 484).

Insertions explicative of an already corrupt text:—pp. 148, 151, 327, 366, 470.

Unclassified:—pp. 142, 152, 273.

3. Omission.

Homocoteleuton:—pp. 380, 470.

Haplography of letters:—pp. 282, 472.

Unclassified omissions (a) *of single words or parts of words*:—pp. 17, 205, 319, 326, 369, 427 f., 473; (b) *of sentences or parts of sentences*:—pp. 22, 38, 140, 209, 490.

The Septuagint. The fact has long been remarked that in the \mathfrak{C} version of Judg. the uncial MSS. A and B exhibit a divergency which is without parallel in any other part of the O.T., and which raises the question whether they should not be ranked as two distinct translations from the Hebrew. The learned Septuagint scholar J. E. Grabe, writing in 1705 to Dr. John Mill, Principal of St. Edmund Hall, Oxford, deals with the subject of this divergency, remarking ‘Omnibus mediocriter tantum Graecae linguae peritis primo intuitu patet Vaticano et Alexandrino codice duas diversas dicti libri versiones, vel saltem duas editiones saepissime ac multum inter se discrepantes contineri.’ This *Epistola ad Millium*, which runs to 56 quarto pages, aims at establishing the fact that Cod. A represents the genuine \mathfrak{C} text; while Cod. B offers the recension of Hesychius, which, as we know from the often-quoted statement of Jerome, was current in Egypt at the time when he wrote. Whatever view be taken as to Grabe’s conclusions, the fact can hardly be disputed that he raised a very genuine problem when he emphasized the divergency of A and B in Judg.—a problem which calls for serious consideration before \mathfrak{C} can satisfactorily be employed for the elucidation of the text of the book.

The divergency between the two \mathfrak{C} versions of Judg. was most thoroughly exemplified by P. de Lagarde in his *Septuaginta Studien*, Erster Theil, 1891, in which he printed the two texts of *chs.* 1-5 on opposite pages, thus exhibiting their variation in as striking a manner as possible. Lagarde did not rest content with reproducing merely the texts of the two uncials A and B. Together with A he grouped the Aldine and Complutensian editions, the five cursive MSS. which appear in the notation of HP. as 108, 19, 54, 118, and 29, and the Armenian (Arm.), Old Latin (\mathfrak{L}), and Syro-hexaplaric (\mathfrak{S}^h) versions. With B he associated the text of the Sixtine edition, the *Coler. Musei Britannici Add.* 20,002, the *Catena Nicephori*, and the short extant fragments of the Sahidic and Bohairic versions. Lagarde printed the texts of A and B *in extenso*, and recorded in footnotes the variants which are found in his other authorities for each respective version of the \mathfrak{C} text.

Professor Moore, in the course of his studies in preparation for his Commentary on Judg., had reached independently the same con-

clusions as Lagarde in a paper read before the *Society of Biblical Literature* in May 1890; and when his Commentary appeared in 1895 he offered an enriched conspectus of the MS. and other authorities which represent each version respectively. His summary conclusion as to the \mathfrak{C} versions is as follows:—‘I say versions; for Lagarde has demonstrated in the most conclusive way, by printing them face to face through five chapters, that we have two Greek translations of Judges. It would probably be going too far to say that they are independent; the author of the younger of them may have known and used the older; but it is certain that his work is not a recension or revision of his predecessor’s, but a new translation.’*

The editors of the Larger Edition of the Cambridge Septuagint, Messrs. Brooke and M’Lean, have decided that it would be impossible to present the textual evidence for the \mathfrak{C} text of Judg. clearly if the text of B alone were taken as a standard, the readings of MSS. which contain the A recension being treated as variants. They are therefore proposing to follow the plan inaugurated by Lagarde, and to print the text of A and B on opposite pages.† Pending the preparation of this edition, they have published (1897) a trustworthy edition of the text of A in Judg. which forms the most available source for purposes of collation. The *prima facie* conclusion of these scholars as to the relationship of the two versions is as follows:—‘No final verdict can as yet be pronounced, but a preliminary investigation of the earlier chapters leads to the surmise that the true text of the Septuagint is probably contained neither in the one nor in the other exclusively, but must

* Moore’s notation is as follows:—

1. Older \mathfrak{C} version: Uncials:

\mathfrak{C}^A =*Cod. Alexandrinus*.

\mathfrak{C}^P (or \mathfrak{C}^{α} in *SBOT.*)=*Col. Coislianus*=HP. X.

\mathfrak{C}^V (or \mathfrak{C}^{β} in *SBOT.*)=*Cod. Basiliano-Vaticanus*=HP. XI.

\mathfrak{C}^S (\mathfrak{C}^{γ} in *SBOT.*)=*Cod. Sarravianus*=HP. IV, V.

Cursives in three groups:

\mathfrak{C}^L =HP. 19, 108, 118, the Complutensian Polyglot, and Lagarde’s *Libr. V. T. Canon. pars prior*, 1883 (cf. p. cxxvi).

\mathfrak{C}^M (or \mathfrak{C}^{μ} in *SBOT.*)=HP. 54, 59, 75, 82, and the fragments of a Leipzig uncial palimpsest.

\mathfrak{C}^O (or \mathfrak{C}^{ν} in *SBOT.*)=HP. 120, 121, and the Aldine edition (Venice, 1518).

2. Younger \mathfrak{C} version: Uncials:

\mathfrak{C}^B (or \mathfrak{C}^{ν} in *SBOT.*)=*Cod. Vaticanus*.

\mathfrak{C}^G (or \mathfrak{C}^{μ} in *SBOT.*)=*Cod. Mus. Brit.* 20, 002.

Cursives:

\mathfrak{C}^N =HP. 16, 30, 52, 53, 58, 63, 77, 85, 131, 144, 209, 236, 237, and the text printed in the *Catena Nicephori* (Leipzig, 1773).

‡ Since the above was written, the part containing Judges has appeared (1917). The editors have not carried out their original intention, but have printed the text of B in full, and have given prominence to the variant readings of the A-text by the use of Clarendon type.

be sought for by comparing in detail, verse by verse, and word by word, the two recensions, in the light of all other available evidence, and especially of the extant remains of the Hexapla.'

So much may suffice to illustrate the stage at which the question of the two \mathfrak{C} texts of Judg. has arrived at the present time. We may now proceed to statement of the main results which seem to accrue from examination of the two texts.

The outstanding fact is that the text of Cod. A, together with other members of the same family as noted by Lagarde and Moore, is really identical with that text of \mathfrak{C} which Lagarde has, with high probability, argued to be the recension which was the work of Lucian, the presbyter and martyr of Antioch—a recension which Jerome states to have been current in Constantinople and Asia Minor, as far west as Antioch.

The stages by which the recovery of Lucian's recension was effected were as follows. Vercellone, in his *Variae Lectiones Vulgatae Latinae Bibliorum Editionis*, Tom. ii. (1864), p. 436, had remarked that the four \mathfrak{C} MSS. which appear in HP. notation as 19, 82, 93, and 108 exhibited a text which very frequently coincided with the extant remains of \mathfrak{E} ; and that this is also the case with the \mathfrak{C} text of the Complutensian Polyglot, which has been shown to be based substantially upon HP.108. When Wellhausen published his *Text der Bücher Samuelis* (1871), he commented on the fact that the same four MSS. frequently offered readings which are intrinsically more probable than those contained in Cod. B. Ceriani in 1863 had suggested (*Hexapla*, p. lxxxvii) that the recension of Lucian was contained in these MSS.; but it was not till 1883 that Lagarde published his *Librorum Veteris Testamenti Canoniorum, pars prior*, containing the \mathfrak{C} text of the O.T. from Genesis to Esther based upon these four MSS. with the addition of HP. 118. In his preface to this work the editor pointed to the numerous agreements between the readings of these five MSS. and the Biblical quotations of St. Chrysostom, who, since he was a priest of Antioch and bishop of Constantinople, may be presumed to have made use of that recension of \mathfrak{C} which was current in Antioch and Constantinople, viz., as Jerome informs us, the recension of Lucian.

Of the five MSS. upon which Lagarde bases his text of Lucian, 118 is complete for Judg., while 19 and 108 exhibit considerable lacunae. 82, which is also available for Judg., is placed by Moore in another group of the A version family, which he distinguishes by the signature \mathfrak{C}^M . We have already noticed that the three Codd. 19, 108, and 118 are cited by Lagarde for his A group in *Septuaginta Studien*, together with the Complutensian (based upon 108), and \mathfrak{E} , the correspondence of which with Lucian's recension in the other historical books has been noted.*

* Cf. the examples cited by Driver for Samuel in *NHTS*.² pp. lxxvii-lxxx and by the present writer for Kings in *NHTK*. pp. xxxvi-xl.

Adequate discussion of the characteristics of the two \mathfrak{G} versions and their relation one to the other demands a separate treatise. It is only possible here to state summarily the conclusions which seem to result from comparison of the two texts.

1. They are distinct translations, in the sense that each presupposes the independent use of a Heb. original.

2. The two Heb. originals, while possessing much in common which differentiated them from \mathfrak{H} , yet varied in many important particulars. That used by \mathfrak{G}^B was the nearer to \mathfrak{H} . That used by \mathfrak{G}^{AL} exhibited many readings which possess the stamp of originality.*

3. Though the two \mathfrak{G} texts may be classed as distinct translations in the sense above specified, they exhibit identities in rendering which cannot be the result of chance, and which indicate that the younger translation (whichever that may have been) was made by the aid of reference to the older.

4. Both translations, and perhaps especially that represented by \mathfrak{G}^{AL} , have been extensively worked over, and contain many doublets.

The *Vulgate* (\mathfrak{V}), *Peshittâ* (\mathfrak{S}^P), and *Targum* (\mathfrak{T}) are of but slight critical value as compared with the two \mathfrak{G} texts, since all represent recensions of the original Heb. much more closely akin to \mathfrak{H} ; and their main importance lies in the early traditions of interpretation which they embody. The principal characteristics of these versions may be gathered from modern works and articles (such as those of *DB.*) which deal with the textual criticism of the O.T., and need not be noticed here. It is worth while, however, in the case of \mathfrak{S}^P —a version of which we possess no authoritative critical text, and of the origin of which little is known—to point out certain affinities with other versions which are apparent in the text of Judges.

1. Affinities with \mathfrak{G} are fairly frequent, especially with the version represented by \mathfrak{G}^{AL} .‡

2¹. אַעלָה וְנָ. \mathfrak{S}^P prefixes לְסַחֲבָא לְסַחֲבָא. Cf. \mathfrak{G}^B τὰδε λέγει κύριος.

5⁸. אִזְלָה לְחֵם שְׁעָרִים. \mathfrak{S}^P לְסַחֲבָא לְסַחֲבָא. Cf. \mathfrak{G}^{AL} ὡς ἄρτον κριθῖνον, \mathfrak{L} 'velut panem hordeaceum,' \mathfrak{S}^B לְסַחֲבָא לְסַחֲבָא.

* This version (as represented by \mathfrak{G} , \mathfrak{Z}^h , \mathfrak{L}) preserves superior readings to \mathfrak{H} and to \mathfrak{G}^B in the following passages in *Judg.*:—5^{4.14}, 7^{2.6}, 8⁴, 10¹¹, 11^{20.34}, 12^{2.3}, 13²³, 14^{11.19}, 15⁶, 16^{19.24}, 17³, 19^{2.3.30}, 20^{15.33}. In 5¹², 11^{26.35}, 18¹⁶, 16²⁵, 18⁹ the readings of the version have claims to consideration, though they are not actually adopted in the present commentary Cf. *notes ad loc.*

‡ The same phenomenon has been noted in the \mathfrak{S}^P text of *Sam.* by Driver, *NHTS.* 2 p. lxxi, and in that of *Kgs.* by the present writer in *NHTK.* p. xxxii. In citations from \mathfrak{S}^P the text of Walton's *Polyglot* has been collated with that of Ceriani's facsimile of the *Codex Ambrosianus*.

ADDENDA TO THE SECOND EDITION

p. lxii. *Footnote* ||. The relation between the Babylonian Perman-sive and the Hebrew Perfect, and between the Babylonian Praeterite and the Hebrew Imperfect with *wāw consecutive*, briefly mentioned at the end of this *footnote* (p. lxiii), has been worked out in detail by the present writer in *JTS*. April 1919, pp. 200-214.

p. lxxi. *Footnote* § on the Hittite language. The theory of the Indo-Germanic character of the Hittite language, outlined by Hrozný in *MDOG*. lvi. December 1915, has been more fully worked out by him in *Die Sprache der Hethiter, ihr Bau und ihre Zugehörigkeit zum indogermanischen Sprachstamm*, 1916-17 (*Boghazköi-Studien*, herausg. von O. Weber, 1, 2 Hefte), and he has followed this by a transcription and translation of seven important Hittite documents, the cuneiform autographs of which are contained in Figulla and Weidner, *Keilschrifttexte aus Boghazköi*, ii. (1916), iii. 1 (1919). Since these Hittite texts are largely written in Sumerian ideograms, with some admixture of phonetically-spelt Semitic Babylonian words and phrases, and we now know the meaning of a number of Hittite words given in the Sumerian-Akkadian-Hittite vocabularies from Boghaz Keui (*Keilschrifttexte aus Boghazköi*, i. Nos. 30-59), it is possible to gather at any rate the general drift of the documents, and so to some extent to test Hrozný's theory; and it must be admitted that his evidence—especially as regards case-endings, pronouns, and verbal forms—seems to make out a strong case; though whether he is further justified in claiming that it proves that Hittite belongs to the western or *Centum*-group* of Indo-Germanic languages, and is somewhat closely akin to Latin, is a question which calls for closer study upon the part of experts, and a fuller body of evidence. The Indo-Germanic theory is also maintained (upon the basis of a smaller

* The Indo-Germanic languages are divided by philologists into two groups, the one retaining certain original velar guttural sounds, *k* (*c*), *g*, *kh*, *gh*, the other converting them into spirants. A typical instance of this is seen in the word for 'hundred'—Greek *ἑκατόν*, Latin *centum* (pronounced *kentum*), Old Irish *cēt*, Gallic *cant*, Gothic *hund*; but Sanskrit *śatam*, Zend *saem*, Lithuanian *szimtas*, Old Slavonic *ſŕto*. The first group is therefore called the *Centum*-group, and embraces Greek, Italic, Celtic, Germanic, and, in addition to this European group, the Tocharian of Turkestan. The second group, named the *Satem*-group, consists of Aryan or Indo-Iranian, Armenian, Balto-Slavonic, Albanian, Thracian, and Phrygian.

amount of material than was available to Hrozný by C. J. S. Marstrander, *Caractère Indo-Européen de la langue Hittite*, 1919 (*Videnskabselskabet's Skrifter*).

On the other hand, E. F. Weidner, *Studien zur hethitischen Sprachwissenschaft*, i. 1917, while admitting (p. 32) that a certain Aryan admixture in Hittite is not to be denied, holds that the language belongs to the Caucasian group, and is akin to Mitannian and Elamite—a view which is also taken by Bork (*OLZ*, Okt. 1916, 289 ff.). Weidner, in the first part of his treatise (which is all that has as yet appeared), confines himself mainly to investigation of the phonology of the language, and, following closely in the footsteps of Bork (*Die Mitannisprache*, *MVAG.* 1909, 1 and 2), argues that Hittite, like Mitannian and Elamite, knew no distinction between the Lenes, *b, g, d*, and the Fortes, *p, k, t*, this being apparent from its indifferent employment of such signs as *bu, pa*; *gu, ku*; *du, tu*; etc. It should be noted that similar phenomena have been pointed out by Böhl (*Die Sprache der Amarnabriefe*, pp. 16 ff.) as specially characteristic of the T.A. Letters from Mitanni and from districts in northern Syria which were under Hittite domination, in contradistinction from the letters of the Semitic chieftains of Canaan (p. 21). This is an argument which may easily be pressed for more than it is worth; for it is clear (as a glance at Böhl's classified instances proves) that such confusion of cuneiform sign-groups is by no means confined in the T.A. Letters to Mitannians and Hittites, but also occurs with some frequency in letters from Egypt, from Babylon, from Abi-milki of Tyre, and from the Amorite chieftains Abd-Aširta and Aziru.

The one fact which is generally recognized is that the Hittite language, at the period at which it comes before us, is of an extraordinarily mixed character. The Indo-Germanic characteristics upon which Hrozný builds his argument are mainly pronominal and inflectional; and while he urges Indo-Germanic affinities for a limited number of nouns, verbs, and particles, he proves nothing for the Indo-Germanic character of the vocabulary in the main. Weidner, in holding that the Indo-Germanic characteristics of Hittite are merely due to admixture, seeks to explain this admixture as due to the Aryan invasion and conquest of the neighbouring state of Mitanni; and the same view has been offered by King as a possibility (*Journal of Egyptian Archaeology*, 1917, pp. 190 ff.). It should be remarked, however, that the question of an Indo-Germanic admixture in the Mitannian language does not seem to arise; whereas, on this theory, it ought to be even more marked in Mitannian than in Hittite. It is also worthy of note that, while Aryan names are frequent and striking among the Mitannians (cf. pp. lxxxiv f. of Commentary), such names are not similarly known to have existed among the Hittites themselves.

pp. lxxxix-xci. For material from the Boghaz Keui documents bearing on Hittite relations with Egypt during this period, cf. B.

Meissner, 'Die Beziehungen Ägyptens zum Hattireiche nach hattischen Quellen,' *ZDMG.* lxxii. (1918), pp. 32-64.

p. xci. Meissner (*ZDMG.* lxxii. p. 45) quotes a passage from a letter of Hattušili II. to the Kaššite king Kadašman-Enlil II. (cf. Figulla and Weidner, *Keilschrifttexte aus Boghazköi*, i. No. 10 Obv. ll. 59 ff.) as proving that war between the Egyptians and Hittites did not end at once on Hattušili's accession. The passage runs as follows:—⁶⁰ . . . And since the king of Egypt⁶⁰ [and I w]ere at variance, I wrote to thy father Kadašman-Turgu⁶¹ [thus: "The king of Egypt] is at hostilities with me"; and thy father replied⁶² [thus: "My troops] shall march against Egypt, and I will go with thee; ⁶³ [I will] go, and the hosts and chariots as many as I have [are ready] to march.⁶⁴ [N]ow, my brother, ask thy nobles (?), that they may tell thee (that this was so).' At the time when Hattušili wrote to Kadašman-Enlil, however, peace with Egypt had been concluded, as the Hittite king states (Obv. ll. 55 ff.; cf. Meissner, *op. cit.* p. 60).

The cuneiform fragment of the treaty between Ra'messe and Hattušili is given in Figulla and Weidner, *Keilschrifttexte aus Boghazköi*, i. No. 7. Meissner (*op. cit.* pp. 50 ff.) gives parallel translations of the Hittite and Egyptian copies of the treaty, so far as the cuneiform fragment extends (45 lines).

p. 41. The evidence that the term Amurru, as used at the period of the T.A. Letters and later (15th to 13th centuries B.C.), embraced not merely the Lebanon-district, but also the Syrian desert to the east of this as far as the Euphrates, is found in the important letter of the Hittite king Hattušili II. to Kadašman-Enlil II., king of Karduniaš (Babylon), the text of which is given in Figulla and Weidner, *Keilschrifttexte aus Boghazköi*, i. No. 10 (cf. Rev. ll. 26 ff.). The Babylonian king had made complaint against Bantišinni, chieftain of Amurru, a successor of Abd-Aširta and Aziru (cf. pp. lxxii f., lxxx, lxxxvii of our *Introduction*), and vassal of Hattušili, on the charge of harassing his land, and, when taxed by the Hittite king with the misdemeanour, Bantišinni had replied by advancing a counter-charge for thirty talents of silver against the people of Akkad. It seems, therefore, to follow that the district known as Amurru, which was under the sway of Bantišinni, must have extended to the Euphrates and been contiguous with the territory of the king of Karduniaš. The Amorite chieftain would thus have command of the important caravan-route from Babylonia to Syria along the line Ed-Dêr, Suḥneh, Tudmur, Damascus (see Frontispiece-Map), and failure to satisfy the demand for dues which he doubtless exacted from the caravans using the route seems to have led him to indemnify himself by encroachments upon Babylonian territory.

p. 97. *Footnote* *. On barred division of Babylonian verse-lines into four parts cf. also King, *The Seven Tablets of Creation*, i. (1902), pp. cxxii ff.

p. 210. *Ch.* 7^{5,6}. J. G. Frazer, *Folk-lore in the Old Testament*, ii. (1918), pp. 465 ff., illustrates the two methods of drinking practised by Gideon's men by a number of interesting parallels.

p. 250. *Footnote* †. The name *A-ba-ra-ḥa-am* occurs on an early Babylonian tablet from Larsa. Cf. H. F. Lutz, *Early Babylonian Letters from Larsa* (*Yale Oriental Series, Bab. Texts*, ii. 1917), No. 15, l. 13. Translation, p. 22 ; discussion, pp. 5 f.

p. 365. *Ch.* 14¹⁸. The practice of deferring the consummation of marriage until the seventh day, which appears in the case of Samson, is strikingly illustrated by the custom at Darfur, as described in *Travels of an Arab Merchant* [Mohammed Ibn-Omar El Tounsy] *in Soudan*, abridged from the French by Bayle St. John (1854), p. 107, quoted by J. G. Frazer, *Folk-lore in the Old Testament*, i. p. 514 : 'It must be observed that the marriage is seldom considered as completely celebrated until the seventh day, and never until the third. A husband always shuns the insulting epithet of the impatient man. Each day of temperance is dedicated to some particular person : the first to the father of the bride, the second to the mother, and so on.' A large number of instances of deferring consummation of marriage for various periods are cited by Frazer in this chapter.

p. 478. *Footnote* *. On the interchange of sibilants in Heb. *Môšē* = Eg. *Mosi*, and the use of Eg. *Mosi* by itself, without express mention of the name of a deity, cf. J. M. Powis Smith, *AJSL*. Jan. 1919, pp. 110 ff.

THE BOOK OF JUDGES

I. 1-2. 5. *Survey of Israel's settlement in Cana'an.*

Besides the Commentaries, etc., cited throughout the book, cf. Eduard Meyer, *Kritik der Berichte über die Eroberung Palaestinas*, ZATW. i. (1881), pp. 117-146; L. B. Paton, *Israel's Conquest of Canaan*, JBL. xxxii. (1913), pp. 1-53.

This section was added by a post-exilic editor of the Priestly school of thought (R^p) as a fresh introduction to his new edition of the history of the Judges. The introduction is composed in the main of extracts culled from the old Judaeen document (J) of the ninth century B.C. J's narrative originally gave an account of the first settlement of the tribes of Israel in Cana'an, describing the gradual and partial manner in which it was effected. Extracts from the same narrative are found in the Book of Joshua', several of them being parallel to passages in Judg. 1, and, where not identical in wording, appearing in a more original form. Thus Josh. 15¹⁴⁻¹⁹ = Judg. 1^{20-10b} (in part) 11-15; Josh. 15⁶³ = Judg. 1²¹; Josh. 16¹⁰ = Judg. 1²⁹; Josh. 17¹¹⁻¹³ = Judg. 1^{27,28}. Further extracts from the same narrative, not contained in Judg. 1, are found in Josh. 13¹³, 17¹⁴⁻¹⁸, 19⁴⁷, and probably in Num. 32^{39,41,42}. The original form of J's narrative of the settlement in Cana'an has been very skilfully reconstructed by Bu.: cf. *Additional note*, p. 47.

The reason why the old narrative of J did not appear in full in Josh. doubtless was that, as picturing the settlement in Cana'an as the work of individual tribes, and as only very partially effected, it conflicted with the view taken by the Deuteronomic editor (R^d) of JE in Josh., according to which practically the whole of the promised land, with the exception of the maritime plain, was summarily conquered by all Israel in a series of campaigns under the leadership of Joshua'; and was even more sharply opposed to the presentation of affairs as given by the Priestly writer (P) in Josh., which makes the accurate delimitation of the conquered territory among the twelve tribes to have been settled by Joshua' after the conquest. Cf. further *Introd.* pp. xxxiv f.

In utilizing J's matter for his introduction to Judges, R^p regards it as referring, not to the first settlement in Cana'an, but to the outcome of events 'after the death of Joshua' (v. 1). Thus, in order to illustrate (from his point of view) the slackness of Israel in failing to carry out

what they *might* have accomplished in obedience to Yahweh's command, he alters in several passages J's statement that they '*could not* dispossess' the Cana'anites into '*did not* dispossess.' So in *vv.* 21.27 as compared with the parallel passages in Josh.; and doubtless also in *v.* 19 (cf. *note*). R^p also adds statements with regard to the conquest of Jerusalem (*v.* 8) and the Philistine cities (*v.* 18) which actually conflict with statements from J which he incorporates (*vv.* 21.19). Cf. further *notes* following.

The standpoint of *ch.* 2 1-5 is clearly that of R^p. The severe censure of Israel as a whole on the ground that they have *wilfully* neglected Yahweh's command by failure to extirpate the inhabitants of Cana'an is of a piece (Bu. *R.S.* p. 20) with the deliberate alteration of 'could not dispossess' into 'did not dispossess' noticed above. The representation of the tribes of Israel as apparently assembled in one body at Bethel (cf. *note* on 2 1) is at variance with the narrative of J in *ch.* 1, which represents them as scattered throughout the land, and each making its own settlement as best it could. The speech which is put into the mouth of the Angel of Yahweh appears to be a free composition by R^p, based upon reminiscence of passages in the Pentateuch and Josh. (cf. *notes ad loc.*). Wellh., however, is doubtless correct in recognizing (*Comp.* 3 p. 210) that in *vv.* 1a.5b we have genuine fragments of the old narrative of J, describing the removal of the religious centre of Israel from Gilgal to Bethel after the conquest of the latter city by the house of Joseph, as narrated in 1 22 ff.

The purpose of R^p's introduction is to explain the unsettled condition of affairs as related in the narrative of Judges, by the addition of details known to him which had not been incorporated by the main editor (R^E 2) in *his* introduction, *ch.* 2 6-3 6.

The following words and phrases are to be noticed as characteristic of J:—'the Cana'anites,' as a general term for the inhabitants of Palestine, 1 1 (see *note*); 'the Cana'anites and the Perizzites' coupled, 1 5 (*note*); 'at the first' (בְּתַחֲלָה), 1 1; 'deal kindly with' (lit. 'do kindness with,' עֲשֵׂה חֶסֶד עִם), 1 24; 'dependencies' (lit. 'daughters,' בָּנוֹת), 1 27, five times; 'and it came to pass, when' (וַיְהִי כִּי), 1 28; 'dwelt in the midst of' (יָשַׁב בְּקֶרֶב), 1 29,30,32,33; 'prevailed' (lit. 'was heavy,' כָּבַד), 1 35; 'the Angel of Yahweh' (מַלְאֲךְ יְהוָה), 2 1(4). Cf. CH^J.

I. 1. R^p Now after the death of Joshua, J the children of

I. 1. *after the death of Joshua*. As related in Josh. 24 29,30 (E). R^p assumes that he is taking up the history from the point reached in the closing chapter of Josh. The proper continuation of Josh. 24 is found, however, in R^E 2's introduction to Judg., contained in *ch.* 2 6ff., where *vv.* 6-9 are nearly verbally identical with Josh. 24 28,31,29,30. So far from dealing with events which happened subsequently to Joshua's death, the old narrative of J pictures Israel as still at Gilgal (2 1), or

Israel enquired of Yahweh, saying, 'Who shall go up for us first against the Cana'anites to fight against them?' 2. And Yahweh said, 'Judah shall go up: behold, I have given the land into his hand.' 3. And Judah said to Sime'on his brother, 'Go up with me into my lot, that we may fight against the Cana'anites,

close by at Jericho (1¹⁶), shortly after the passage of the Jordan and before the tribes had entered upon their inheritances.

the children of Israel enquired, etc. Literally translated, *v.*¹ runs, 'And it came to pass, after the death of Joshua', and the children of Israel enquired, etc.', the use of 'and' to introduce the sentence to which the time-determination refers being idiomatic in Hebrew. Thus, apart from R^p's note of time, the sentence is to be rendered, 'And the children, etc.' This may have formed the commencement of J's narrative of the tribal conquests: cf. *Additional note*, p. 47.

enquired of Yahweh. The reference doubtless is to consultation of the oracle by means of the sacred lot; cf. the use of the phrase in 1 Sam. 14³⁷, 22¹⁰, 23², 30⁸, etc. This lot was cast by means of Urim and Tummim, as appears from the undoubtedly original form of 1 Sam. 14⁴¹, preserved by G. Here Saul's address to Yahweh runs, 'O Yahweh, God of Israel, wherefore hast thou not answered thy servant to-day? If this iniquity be in me, or in Jonathan my son, O Yahweh, God of Israel, give Urim; but if it be in thy people Israel, give Tummim.' Cf. also 1 Sam. 28⁶. Thus Urim and Tummim were apparently two concrete objects employed in connexion with the Ephod. Cf. 1 Sam. 14¹⁸, where G^{BL} preserves the true reading 'Ephod' in place of 'Ark of God' in H. On the nature of the Ephod, cf. *note on ch.* 8²⁷.

Who shall go up. From the Jordan valley, which is the point of departure in *v.*¹⁶, into the hill-country to the west. The expression 'ālā 'go up' is used, however, in a general way of a military expedition. Cf. *ch.* 12³, 18⁹, 1 Sam. 7⁷, Isa. 36¹⁰, *al.*

against the Cana'anites. The use of 'Cana'anite' as a general term to describe the inhabitants of the country west of Jordan is characteristic of J; while E uses 'Amorite' in the same general sense. When greater accuracy is deemed desirable, the Cana'anites are defined as the dwellers in the lowlands, *i.e.* the maritime plain and the Jordan valley, and the Amorites as inhabitants of the hill-country which lies between. So in Num. 13²⁹ (prob. R^{JE}), Josh. 11³ (R^v); cf. Deut. 1^{7,19,20}, Josh. 5¹, 13^{3,4} (both R^v). The inhabitants of the mountain-range east of Jordan and north of the Arnon are described as Amorites by E and by writers influenced by this source (R^{JE} and school of D). Upon the evidence as to the use of the terms from extraneous sources, cf. *Additional note*, p. 41.

3. *into my lot.* J, like E and R^v and P in Josh., doubtless represented the partition of Cana'an among the tribes of Israel as decided

and I also will go up with thee into thy lot.' So Sime'on went with him. 4. R^P And Judah went up; and Yahweh gave the Cana'anites and the Perizzites into their hand; and they smote them in Bezeḱ—ten thousand men. 5. J And they came upon

by lot under the direction of Joshua'. Cf. *Introd.* p. cv. The position and (ideal) extent of Judah's 'lot' is described in Josh. 15¹⁻¹² P. It was bounded on the east by the Dead Sea and on the west by the Mediterranean, while the northern border ran from the Jordan near its junction with the Dead Sea, and passing close to the south of Jerusalem (which fell within the territory of Benjamin), terminated at the Mediterranean near Jabne'el (Yebnâ). The southern border is noticed under v.³⁶ 'from the Crag.'

So Sime'on went with him. The cities assigned to Sime'on in Josh. 19¹⁻⁸ (P) fall within the territory of Judah; and most, if not all, of them are reckoned to Judah in Josh. 15^{26-32.42} (P). The tribe of Sime'on seems to have been very small. The story of Gen. 34 (J and P combined) probably reflects an early attempt made by this tribe and the tribe of Levi (*Additional note*, p. 437) to settle in central Palestine; when an attack made upon the Cana'anite city of Shechem, in violation of friendly treaty, provoked (as we may infer from Gen. 49⁷ J) such reprisals on the part of the Cana'anites as decimated the aggressors and caused the dispersion of the remnant of their clans to seek a settlement in other parts of the land. As to when this Shechem-incident may have occurred, cf. *Additional note*, pp. 437 ff. In the so-called 'Blessing of Moses,' Deut. 33 (E), dated by Driver (*Deut.*, ICC., p. 387) either shortly after the rupture under Jerobo'am I., or during the middle and prosperous part of the reign of Jerobo'am II. (c. 780 B.C.), Sime'on is not mentioned at all; unless we follow the suggestion of G^{AL} in v.^{6b}, and read, 'and let Sime'on be few in number' (שָׁמְעוֹן for מְתוֹן). The rendering πολλὸς ἐν ἀριθμῷ rests on a false interpretation of מִסְפָּר as implying a large number).

4. The verse seems to be a summary statement by R^P of the result of the campaign, based upon the information afforded by J in the following verses.

5. *And they came upon Adoni-bezeḱ in Bezeḱ.* The name Adoni-bezeḱ is open to grave suspicion, since nowhere else do we find a Hebrew proper name which describes a man as 'lord' of his city or country. The form of name which we should expect as a compound of Adoni is 'such and such a deity is lord': cf. Adonijah, 'Yah or Yahweh is lord,' Adoniram, 'the High one is lord,' and in Phoenician Adoni-eshmun, 'Eshmun is lord,' etc. It is conceivable that Bezeḱ may have been the name of a local Cana'anite deity; but such a deity is otherwise quite unknown, and it is scarcely possible that the city should bear the name of the deity, without some such prefix as Beth, 'house of' (cf. Beth-'anath, Beth-dagon). Moreover, no city

Adoni-bezek in Bezek, and they fought against him, and smote

named Bezek in southern Palestine is mentioned elsewhere in the O. T.; and the Bezek of 1 Sam. 11⁸ (the modern Hîrbet Ibzik, seventeen miles N.N.E. of Nâblus on the road to Bêsân) cannot be the place intended, since Judah and Sime'on are represented as moving in a westerly or south-westerly direction from Jericho (*v.*¹⁰), into the territory allotted to Judah. A site Hîrbet Bezkeh, six miles S.E. of Lydda, has been advocated by Conder (*SWP. Mem.* iii. 36), but this seems too far to the west to have been the scene of action.

The mention of Jerusalem in *v.*⁷, as the city to which the king was taken, apparently by his own followers (*cf. note*), after his mutilation by the Judaeans, makes it probable that we have here to do with Adoni-şedek, king of Jerusalem, who is named in Josh. 10¹ (E) as the head of the confederacy against Joshua in southern Palestine; in which case we would seem to have an account of his fate different from that given by E in Josh. 10²² ff. The view that, in Adoni-şedek, Şedek is the name of a Canaanite deity is plausible, but the evidence is inconclusive. *Cf. Additional note*, p. 41. Adoni-şedek may denote 'my lord is righteous' (lit. 'is righteousness'; in accordance with the common substitution of substantive for adjective in Heb.), or 'lord of righteousness.'

If Adoni-şedek be the original form of the name in our passage, the form Adoni-bezek, unless merely due to accidental corruption, is probably an intentional perversion made by a late scribe in order to cast ridicule upon the name of a heathen deity. Şedek, either the deity's name, or ascribing 'righteousness' to the heathen divine 'lord,' is changed into *bezek*, a word unknown to us in Heb., but very likely existing with the meaning 'pebble' or small 'fragment' of stone, as in Syr. *bezkā*, Aram. *bizkā*, perhaps in jesting allusion to the material and helpless idol: *cf.* Hab. 2¹⁹, where the idol is described as a 'dumb stone.' Such perversion of the title of a heathen deity is most probably seen in Baal-zebub, 'lord of flies,' 2 Kgs. 1^{2.3.6.16}, for an original Baal-zebul (*cf.* Βεελζεβουλ, Mk. 3²² and parallels, Matt. 10²⁵), 'lord of the mansion' (temple, or heavenly abode; applied to Yahweh's abode in 1 Kgs. 8¹³, Isa. 63¹⁵: *cf.* Cheyne in *EB.* col. 407 f.); and in the substitution of *bōšeth*, 'shameful thing,' for Ba'al where it occurs in proper names, as in Ishbosheth in 2 Sam. 2⁸, etc., for Eshba'al, 1 Chr. 8³³, 9³⁹, and in other cases: *cf.* the present editor's *Outlines of O. T. Theology*, pp. 27 f. Similar instances of the perversion of names in jest are noticed in *ch.* 3⁸ *note*. The form Αδωνιβεζεκ has been adopted by E in Josh. 10 (2 codd. Αδωνιζεβεκ; so Josephus and other writers: *cf.* Mo., *Comm.*, p. 17).

Upon this view of the origin of the name Adoni-bezek, it is probable that the words 'in Bezek' were added still later as an explanatory gloss, when the proper name had come to be understood as 'lord of Bezek.' The statement 'they came upon Adoni-

the Canaanites and the Perizzites. 6. And Adoni-bezek fled; and they pursued after him, and captured him, and cut off his thumbs and his great toes. 7. And Adoni-bezek said, 'Seventy kings, with their thumbs and their great toes cut off, used to pick up food under my table: as I did, so hath God required me.' And they brought him to Jerusalem, and he died there.

8. R^p And the children of Judah fought against Jerusalem, and

Šedek' does not necessarily postulate mention of the locality where the encounter took place, though this may have existed in the full narrative of J. Bu. would supply 'the king of Jerusalem' after the proper name.

The Canaanites and the Perizzites. The two terms are so coupled only in J, Gen. 13⁷, 34³⁰†: the occurrence in v.⁴ (R^p) being adopted directly from J in v.⁶.

The view that the Perizzites were a remnant of the pre-Canaanitish inhabitants of Palestine (cf. Kautzsch in Riehm, *HWB.*² ii. p. 1211) is based upon insufficient grounds. More probably the term, like *ḥ'rāzî* in 1 Sam. 6¹⁸, Deut. 3⁶, denotes the dwellers in unwall'd hamlets; just as the term Hivvites appears to denote communities of tent-dwellers (cf. *note* on ch. 10⁴).

6. *cut off his thumbs and his great toes.* Le Clerc and commentators after him compare the statement of Aelian (*Var. Hist.* II. 9) that the Athenians voted to cut off the thumb of the right hand of every one of the Aeginetans, that they might be unable to carry a spear, but able to propel an oar. Similar mutilations of prisoners of war are noticed by Mo. *ad loc.* Probably, however, La. is correct in concluding, with Calmet, that the mutilation was intended to degrade the captive to the position of a punished slave, rather than to prevent the bearing of arms; though the latter motive may also have been operative.

7. *Seventy kings.* A large round number. Cf. *note* on ch. 8³⁰.

as I did, etc. There is perhaps an etiological connexion between the tradition of Adoni-šedek's speech and the name which he bears; the idea of 'measure for measure' being suggested by 'the Lord is righteous' (*i.e. just*; cf. use of term in Deut. 25¹⁵, *al.*).

they brought him to Jerusalem. The subject of the verb must be Adoni-šedek's own followers; since J, the author of the narrative tells us in v.²¹ = Josh. 15⁶³ that the Judaeans were unable to conquer Jerusalem. It is likely, however, that R^p referred the verb to the victorious Judaeans, and so introduced his statement as to the conquest of Jerusalem in the verse following.

8. *And the children of Judah fought against Jerusalem, etc.* This statement by R^p is obviously incorrect. So far from the city having been captured and set on fire, we are told by J in Josh. 15⁶³ that the

took it, and smote it at the edge of the sword, and the city they set on fire. 9. And afterward the children of Judah went down to fight against the Canaanites dwelling in the hill-country and the Negeb and the Shephelah. 10. And Judah went against

sons of Judah *were unable to dispossess* the Jebusites dwelling in Jerusalem (so *v.*²¹, with the variation 'did not dispossess' noticed in the opening section). With this failure to capture Jerusalem agree the facts of history as otherwise known to us. In the old story of Judg. 19 Jerusalem or Jebus is a 'city of the Jebusites, . . . the city of foreigners who are not of the children of Israel' (*vv.*¹⁰⁻¹²). And in 2 Sam. 5^{6 ff.} the capture of the city from its Jebusite inhabitants is related as one of the great achievements of David. Even R^d in Josh., who relates in 10^{28 ff.} the capture and destruction of the cities of three of the kings who took part in the southern confederacy (10^{3 E}), viz. Lachish, 'Eglon, and Hebron, makes no statement as to the capture of Jerusalem; though it is true that the king of Jerusalem is included (*v.*¹⁰) in the list of vanquished kings given in Josh. 12.

at the edge of the sword. Lit. 'according to the mouth of the sword' (לְפִי הַחֶבֶל, *l'phi ha-chel*, as in לְפִי אֲכָלוּ, *l'phi akhalu*, lit. 'according to the mouth of his eating,' Ex. 16¹⁸), i.e. 'as the sword devours,' viz. *without quarter*.

9. *the children of Judah went down.* Jerusalem is 2593 feet above the Mediterranean sea-level, Hebron (*v.*¹⁰) 3040 feet; and the intervening country rises slightly on the whole rather than falls. Thus the expression 'went down' would be in this respect inappropriate. The writer, however, is thinking, not merely of the much lower Negeb and Shephelah, but also of the fall in the hill-country from the central plateau on which Jerusalem stands, both westward towards the Shephelah, and towards the wilderness of Judah in the direction of the Dead Sea.

the Negeb. The arid steppe-region extending from a little south of Hebron, where the hill-country gradually sinks, to Kadesh-Barnea' about fifty miles south of Be'er-sheba' on the border of the desert. The root נֹבֵךְ in New Heb. and Aram. means 'to be dry or parched'; and Negeb accordingly must denote 'the dry region': cf. *v.*¹⁵ where springs of water are named as a desideratum. From the standpoint of Palestine 'the Negeb,' or, 'towards the Negeb,' is a common designation of the south. Negeb is in R.V. always rendered 'the South' (with capital S); but its application to a particular region of southern Palestine requires the retention of the Hebrew term.

the Shephelah. A term meaning 'lowland,' and, according to Smith (*HG.* pp. 201 ff.), properly applied to the low hills or downs lying between the Judæan hill-country to the east and the maritime plain (called 'emek, 'the Vale,' by J in *v.*¹⁹) to the west—a region which, as distinct both from hill-country and plain, was constantly debatable ground between the Israelites and Philistines. Smith

the Canaanites who dwelt in Hebron : (now the name of Hebron

clearly proves the distinct character of this region, as separated from the hill-country of Judah by a series of valleys running southward from Aijalon, a distinction which does not exist north of Aijalon, where the hill-country slopes down directly into the maritime plain. Yet there are indications that the use of the term Shephelah was not always or at all times thus limited in its application. As Buhl (*Geogr.* p. 104, *n*¹⁶⁴) remarks, the specification of the cities in the Shephelah in Josh. 15^{33 ff.} points to a wider application, especially *vv.*⁴⁵⁻⁴⁷ which include the Philistine cities with their neighbouring villages as far west as the sea and as far south as the wâdy of Egypt (wâdy el-'Aris); these latter verses indicating the linguistic usage of the term at the period at which they were penned, even if they be regarded as a later interpolation. The same inference may be drawn from the \mathfrak{C} rendering $\pi\epsilon\delta\acute{\iota}\omicron\nu$ or $\eta\ \pi\epsilon\delta\iota\nu\acute{\eta}$, and from Eusebius' statement (*OS.* 296¹⁰) that the term includes all the low country ($\pi\epsilon\delta\iota\nu\acute{\eta}$) lying about Eleutheropolis (Bêt-Ġibrin) to the north and west.* On the other hand, the fact must not be overlooked that Ob.¹⁹, 2 Chr. 28¹⁸ appear expressly to distinguish the Shephelah from the territory of the Philistines (the maritime plain); and the same seems to be true of Zech. 7⁷, which refers to the period when the Shephelah was inhabited by Judah. The usage of the term thus appears to have fluctuated between a wider and narrower application, the wider and looser usage probably being relatively later.

10. *And Judah went, etc.* J's account of the conquest of Hebron and Debir is found in Josh. 15¹⁴⁻¹⁹. There, after a statement by a late Priestly writer (*v.*¹³) that Caleb was given Hebron or Ķiriath-arba' as his portion, we read:—¹⁴. 'And Caleb dispossessed from thence the three sons of 'Anak, Sheshai, and Ahiman, and Talmai. ¹⁵. And he went up thence against the inhabitants of Debir, etc.,' *vv.*¹⁶⁻¹⁹ being verbally identical with Judg. 1¹¹⁻¹⁵, except for the variation וַיֵּלֶךְ 'and he went,' Judg. 1¹¹, for וַיַּעַל 'and he went up,' Josh. 15¹⁵, and the addition $\text{הַקָּטָן מִמֶּנּוּ}$ 'who was younger than he,' in Judg. 1¹³, after the words 'the brother of Caleb.' The parallel to *v.*¹⁴ of Josh. is found in Judg. 1^{20b} and the names of the sons of 'Anak at the end of *v.*¹⁰.

Judg. 1^{20a}, 'And they gave Hebron to Caleb, as Moses had said,' is J's statement upon which Josh. 15¹³ is based by a late redactor who inserted the narrative of J into the midst of the P document in Josh. The original form of J's narrative is found if we place Judg. 1^{20a} before Josh. 15¹⁴⁻¹⁹: cf. *Additional note*, p. 48. The dislocation in Judg. 1 by which *v.*²⁰ comes later on instead of prior to *v.*^{10 end} is due to R^p, who, by his insertion of *vv.*^{9,10} down to 'and they smote,'

* Buhl's further objections to Smith's view appear to be satisfactorily met by the latter writer in *Expositor*, 1896, pp. 404 ff.

formerly was Kiriath-arba':) and they smote J Sheshai and Aḥiman, doubtless intended to represent the whole tribe of Judah as acting in concert.

Hebron. The modern el-Ḥalil, *i.e.* 'the Friend,' an abbreviation of 'Town of the Friend of God' (the Mohammedan title for Abraham), about eighteen miles a little west of due south of Jerusalem.

now the name of Hebron formerly, etc. So exactly Josh. 14¹⁵ (in a section 14⁶⁻¹⁵ R^D, but probably a later note). The statement that Kiriath-arba' was the same as Hebron is also found in Gen. 23², 35²⁷, Josh. 15^{13, 64}, 20⁷, 21¹¹ (all P), and the name appears in a list of cities inhabited by the children of Judah in Nehemiah's time, Neh. 11²⁵ †.

Kiriath-arba'. The name means 'City of Four'; and there can be little doubt that 'Four,' like 'Seven' in Be'er-sheba', 'Well of Seven,' is a divine title. Probably both 'Four' and 'Seven' represent aspects of the Moon-god, the former referring to the four phases of the moon, the latter to one quarter, or the seven-day week. For the evidence upon which this view is based, cf. *Additional note*, p. 43. The view generally adopted that 'City of Four' means Tetropolis, fourfold city or city of four federated tribes, is based merely upon conjecture; and no evidence can be adduced in support of it, unless it be found in the fact that the name Hebron may possibly be explained as 'association' or 'federation.' The Priestly writer in Josh. 15¹³, 21¹¹ **ו** would appear to suppose Arba' to have been the ancestor of the 'Anakite clans originally inhabiting Hebron; and in Josh. 14¹⁵ **ו** Arba' is stated to have been 'the greatest man among the 'Anakites.' In all these passages, however, **ע** reads 'the metropolis of 'Anak,' or 'of the 'Anakites' (*μητρόπολις* = **ממלכה** 'mother,' *i.e.* 'mother-city,' as in 2 Sam. 20¹⁹); and Mo. argues with reason that this was the original reading, and that the alteration in **ו** is due to a scribe who misunderstood the sense in which the term 'mother' is used.

Sheshai, and Aḥiman, and Talmai. Described in v. 20 as 'the three sons of 'Anak'—a statement with which the three proper names were originally connected in J's account. Cf. the first *note* on v. 10. The reference is to three 'Anakite clans rather than to three individuals. In Num. 13²² (JE) the spies, and notably Caleb (cf. *note* on v. 12), come across the same three in their reconnaissance of Hebron—a fact which perhaps has its bearing upon the question of Caleb's conquest of Hebron (cf. *Additional note*, p. 46). Mo. speaks of the 'Anakite names as 'of distinctively Aramaic type'; but it is more to the point to observe that they seem to exhibit the influence of North Arabia. It should be noticed that names with the termination *-ai*, as in Talmai and Sheshai, appear to have been specially numerous among the Judaeans, and not least among the Calibbite and Jerahme'elite elements of this mixed tribe. Cf. the genealogy of 1 Chr. 2, and notice besides Hushai, 2 Sam. 15³², *al.*, and the Gittite Ittai, 2 Sam. 15¹⁹, *al.* The name Talmai occurs in 2 Sam. 3³, 13³⁷ as

and Talmi. 11. 'And they went up' thence against the inhabitants of Debir. (Now the name of Debir formerly was

borne by a king of the Aramaean state Geshur (probably north of Gile'ad), and Talmi has been found in inscriptions from el-'Olâ near Têma as the name of two kings of Lihhyân (D. H. Müller, *Epigraphische Denkmäler aus Arabien*, p. 5, quoted by Sayce, *HCM.* p. 189 *n.*). The Nabatean form is Talmû or Talimû: cf. *CIS.* ii. 321, 344, 348. The name is closely akin to Bab. *talîmu*, Sam. *l'lim*, 'uterine brother'; cf. Aram. Bar-tulmai (Bartholomew). Shêshai (שֵׁשַׁי, $\text{E}^L \Sigma \epsilon \sigma \epsilon \iota$, $\text{B} \Sigma \epsilon \sigma \sigma \epsilon \iota$. Josh. 15¹⁴ $\text{E}^{\text{BL}} \Sigma \upsilon \upsilon \sigma \epsilon \iota$, $\text{A} \Sigma \upsilon \upsilon \sigma \alpha \iota$. Num. 13²² $\text{E}^L \Sigma \epsilon \sigma \epsilon \iota$, $\text{B} \Sigma \epsilon \sigma \sigma \epsilon \iota$. Cf. Shâshai, שִׁשַׁי, Ezr. 10⁴⁰ $\text{E}^{\text{BA}} \Sigma \epsilon \sigma \epsilon \iota$, identical with $\text{E}^{\text{B}} \Sigma \epsilon \sigma \epsilon \iota \varsigma$, $\text{A} \Sigma \epsilon \sigma \sigma \epsilon \iota \varsigma$ of 1 Esdr. 9³¹) is apparently a variation of the name Shîsha or Shavsha (שִׁשַׁי, שָׁוְשָׁה) borne by a Judaeen of the time of David and Solomon (1 Kgs. 4³, 1 Chr. 18¹⁶); and names with this termination -ā (with final ש) are likewise characteristic of Judah (cf. 1 Chr. 2), and point to North Arabian influence, which may thus be supposed to have been operative in southern Canaan as early as the time of the 'Anakites. Shavsha (more original than Shîsha: cf. *NHTA.* p. 38) undoubtedly stands for Shamsa, i.e. 'the Sun'; cf. Aram. Ki-šavaš (כִּישָׁוַשׁ) for Bab. Ki-šamaš in an inscription of B.C. 504: *CIS.* ii. 65 (cited by Cheyne in *EB.* 4433). Shêshai, which, as the E variants indicate, may have been originally Shavshai, Shashshai, or Shishshai (שִׁשַׁי, שָׁשַׁי, שִׁשִּׁי), may be compared with the late Bab. *šaššu* for *šamšu*, 'sun.' It is worth noticing that the Heb. Samson (properly Shimshôn; Bab. Šamšânu, BDB. *s.v.*) perhaps 'Sun-man,' and the place-name Beth-shemesh, 'House of the Sun,' also belong to southern Palestine. In Ahiman the element *mân* is probably the name or title of a deity, perhaps Mēni, the god of *fate* or *destiny* mentioned in Isa. 65¹¹. Cf. the goddess Manôthû in the Nabatean inscriptions; Ar. Manât, *Qurân* 53²⁰. The name belongs to the familiar class which claims relationship to a deity:—'Brother of Mân,' or 'Mân is my brother.' The occurrence of the name (וְאַחֵיהֶם) in the list of Levites in 1 Chr. 9¹⁷ is probably an erroneous dittography of the following וְאַחֵיהֶם, 'and their brethren.'

11. *And they went up.* Reading וַיַּעַל with E^{B} and || Josh. 15¹⁵, in place of וַיֵּלֶךְ. The singular verb is taken by R^p to refer, as a collective, to the tribe of Judah mentioned by him in *v.* 10; but in the original narrative of J it referred to Caleb. Cf. the first *note* on *v.* 10.

Debir. The site commonly accepted for Debir is ez-Zâhariyyeh, which lies about eleven miles south-west of Hebron, and which 'may

Kiriath-šepher.) 12. And Caleb said, 'He that smiteth Kiriath-

be regarded as the frontier town between the hill-country and the Negeb' (Smith, *HG.* p. 279; cf. Trumbull, *Kadesh-Barnea*, pp. 104 f.). This identification depends merely upon conjecture. It suits the connexion in which Debir stands in Josh. 15⁴⁸⁻⁵¹ with Socoh (the modern Šuwêkeh), 'Anab (Anâb), and Eshtemoh (elsewhere Esh-temoa', probably the modern es-Semû'), which are all in close proximity, and the narrative of *vv.* 14^{ff.} (cf. *note* on *v.* 15); but is opposed by the fact noticed by Sayce (*DB.* i. p. 578a) that Petrie found no traces at ez-Zâhariyyeh of anything older than the Roman period.*

It may also be observed that, while Hebron stands 3040 feet above the sea, the elevation of ez-Zâhariyyeh (2150 feet) is nearly 900 feet lower, and the descent from the former site to the latter appears, in the main, to be gradual and continuous.† Thus, if the reading 'And they went up from thence (*i.e.* from Hebron) to Debir' is correct, the identification of Debir with ez-Zâhariyyeh would seem to be excluded, unless we regard the expression 'went up' as used in the general sense of making a campaign (cf. *note* on *v.* 1), an explanation which the precise 'from thence' (עִירוֹ) may be thought to render somewhat improbable. The only site south of Hebron which seems to stand on a higher elevation is Yuṭṭâ (3747 feet); but this corresponds in name at least with the Biblical Juṭṭah, Josh. 15⁵⁵, 21¹⁶.

Kiriath-šepher. As vocalized, the name appears to mean 'book-city': Γ^{AL} πόλις γραμμάτων (and so Γ^{BAL} in Josh. 15^{15,16}, and in 15⁴⁹, where H reads Kiriath-šannah, probably a textual error); L 'civitas litterarum'; S^h 'city of writings'; T 'archive-city.' Upon this slight basis, merely, Sayce builds the theory that the city 'must have been the seat of a library like those of the great cities of Babylonia and Assyria,—a library which doubtless consisted in large measure

* Conder's statement (*Tent Work*, p. 245) that the name Debir 'has the same meaning' as ez-Zâhariyyeh is wholly incorrect. It may be true that the name of the modern village is 'derived from its situation on the "back" of a long ridge.' Zâhr means 'back,' and zâhâr is applied to 'the exterior and elevated part of a stony tract' (so Lane), both words being derived from a verb zâhara, 'to be outward, exterior, apparent.' But Debir, on the contrary, can only be explained from Ar. dabara, 'to be behind,' whence dabr and dubr, 'hindmost or back part,' and is the same, apparently, as the Heb. word used in 1 Kgs. 6¹⁶ *al.* as the older name of the most holy place in Solomon's temple, which, upon this etymology, may be rendered 'shrine.' The contrast in sense between the two roots is clearly seen if we compare zâhir, 'exterior' (commonly opposed to bâṭin, 'interior') with dabr, 'the location or quarter that is behind a thing' (so Lane).

† Cf. *SWP. Great Map*, xxi. Smith (*loc. cit.*), though regarding the identification of ez-Zâhariyyeh with Debir as probable, describes the journey from Hebron as a descent 'over moors and through wheat-fields, arranged in the narrower wadies in careful terraces, but lavishly spread over many of the broader valleys.'

shepher, and taketh it, I will give him 'Achśah my daughter as wife.' 13. And 'Othniel, the son of Kēnaz, the R^p younger

of books on clay which may yet be brought to light' (*HCM*. p. 54). If the name really meant 'city of books,' or rather 'records,' we should expect the form קִרְיַת סִפְרִים (Kiriath-šephārim : cf. Kiriath-yē'ārīm); and it is possible that the plur. סִפְרִים may have been written in the abbreviated form 'ספר, which came to be mistaken for the singular (cf. *footnote* § on p. 124). *Gr*^B in this passage reads *Καριασσωφap*, i.e., apparently, Kiriath-šōphēr, 'city of the scribe'; a name which W. M. Müller would recognize in the Egyptian *Bai-ti-tu-fa-ira*, 'house of the scribe' (*AE*. p. 174). This vocalization of the Heb. name is in itself more probable.

12. *And Caleb said.* The statement evidently points back to an earlier mention of Caleb in J's original narrative. Cf. the first *note* on *v.*¹⁰. Caleb is called 'the son of Jephunneh the Kēnizzite' in Num. 32¹² (P), Josh. 14^{6,14} (R^D). In JE's narrative of the mission of the spies to explore the Negeb (Num. 13, 14) he is the only spy mentioned by name, and the only one among the number who maintains the possibility of the conquest of the 'Anakites inhabiting the region (Num. 13³⁰). In the later narrative of P, which is interwoven with that of JE in these two chapters, and in which the twelve spies (one for every tribe, and all named) explore the whole of Canaan, Joshua' is associated with Caleb (the representative of Judah) in urging the immediate conquest of the land. Cf. for the analysis of the narrative, Gray, *Numbers* (*ICC*), pp. 128 ff. In Josh. 14⁶⁻¹⁵ (R^D based on JE) Joshua' grants Hebron to Caleb in response to his request, and in remembrance of the promise of Moses made to Caleb after the return of the spies.

Caleb's clan of the Kēnizzites appears from Gen. 36¹¹ to have belonged to the Edomites, and, like the allied clan of the Jeraħme'elites (1 Chr. 2^{9,18,42}), still remained distinct from Judah in the early days of David : cf. 1 Sam. 27¹⁰, 30¹⁴. Evidence seems to indicate that the Kēnizzites, like other elements which went to form the mixed tribe of Judah, really entered and settled in the Negeb by advancing northward from the neighbourhood of Kadesh-Barnea', and that the tradition which makes the granting of Hebron and Debir to Caleb subsequent to and dependent upon the invasion and conquest of Canaan under Joshua', represents a later adjustment of facts. Cf. *Additional note*, p. 44.

13. 'Othniel, the son of Kēnaz. The reference is probably, as in the case of Caleb, to a Kēnizzite family rather than an individual. 'Othniel is named in *ch.* 3⁹ as the deliverer of Israel from a foreign oppressor.

the younger brother of Caleb. The sentence may be construed grammatically as referring either to Kēnaz (so *Gr*) or to 'Othniel

J brother of Caleb, took it : and he gave him 'Achśah his daughter as wife. 14. And when she came, [he] incited [her] to ask of her father a field : and she lighted down from off the ass ; and Caleb said to her, 'What wouldest thou?' 15. And she said to him, 'Grant me a present ; for thou hast set me in the land of the Negeb ; so give me springs of water.' And Caleb gave her the upper spring^f and the nether spring^f.

(so *℣*) ; but, since Caleb is himself called 'the Kenizzite' (cf. *note* above), it seems clear that he too is regarded as a descendant or 'son' of Kenaz, and that Caleb and 'Othniel are ranked as brothers. This was the view of R^p, who added, after 'the brother of Caleb,' the words 'who was younger than he' (so *ch.* 3⁹), in order to explain how the fact that 'Othniel married his own niece did not imply a great disparity in age. R^p's addition is not found in the parallel narrative of J in Josh. Cf. the first *note* on *v.* 10.

he gave him 'Achśah, etc. Probably the story implies the union of two families of the Kenizzites.

14. *when she came.* Apparently, as Mo. suggests, 'Achśah is pictured as arriving to meet her father and her future husband from some place of safety, such as Hebron, where she had been left during the attack on Debir.

he incited her. Reading וִיסִיתָהּ with *℣*, *ℒ*, *ℑ*^b, *℣* here, and *℣* and some MSS. of *℣* in || Josh. 15¹⁸, in place of *℔* 'she incited him.' The correction is necessary in view of the fact that the request, as narrated, comes from 'Achśah.

15. *a present.* Lit. 'a blessing,' in the tangible form of a gift. The expression is so used in Gen. 33¹¹ (*E*), 1 Sam. 25²⁷, 30²⁶, 2 Kgs. 5¹⁵.

thou hast set me, etc. The character of the district (Negeb, 'the dry region' ; cf. *v.* 9 *note*) justifies the request.

springs of water. The Heb. word *gullôth*, here rendered 'springs,' is otherwise unknown, and the meaning can only be inferred from the context.* It may perhaps be an old Canaanite word which dropped into disuse in later Hebrew ; or, as Mo. thinks, 'a proper name of alien origin' (so Bu.).

the upper spring and the lower spring. Reading גִּלְתִּי sing. with the old fem. termination, as is demanded by the sing. adjectives עֲלִית and תַּחְתִּית. This old termination, as seen in *gullath*, is frequent,

* Cf., however, גִּל in Cant. 4^{12b}, which, if not merely a corruption of גִּן, 'garden,' which occurs in the first half of the verse (as presupposed by *℣*, *℣*, *ℑ*^b), probably means 'spring' : גִּל נְעֻל parallel to מַעְיֵן הַחַיִּים

16. And 'Hobab the' Kēnite, the father-in-law of Moses,

as Bu. remarks, in Cana'anite place-names, *e.g.* Šephath, Ba'alath, Šarephath: cf. *NHTK.* p. 42 f. || Josh. 15¹⁰ has the plur. 'the upper springs, etc.' The springs in question have been plausibly identified with the springs of Seil ed-Dilbeh between Hebron and ez-Zāhariyyeh, 'on the north, the 'Ain Hegīreh with a shadoof for irrigation, and on the south the 'Ain Dilbeh, a square pool covered with weeds' (Smith, *HG.* p. 279, *n*²). Cf. *SHP. Mem.* iii. p. 302. Mo. notices the fact that these springs are somewhat nearer to Hebron than to ez-Zāhariyyeh, and appositely remarks that the story 'is told to explain or establish the claim of 'Achśah, a branch of the Kēnizzite clan 'Othniel of Debir, to waters which by their situation seemed naturally to belong to the older branch, the Calebites of Hebron.'

16. *And Hobab the Kēnite.* Reading וְהָבָב הַקֵּינִי with Mo., Bu., No. (cf. *ch.* 4¹¹), in place of וּבְנֵי קֵינִי, 'And the children of Kēnite,' which cannot be original, since the gentilic adjective 'Kēnite' cannot be used of an individual without the Article, which is tacitly inserted in R.V. The words, 'the father-in-law of Moses,' which follow, seem to demand mention of the proper name. \mathfrak{C}^{AL} , \mathfrak{S}^{h} read, 'And the children of Hobab the Kēnite,' a text which suits the pl. verb עָלָה, 'went up,' in *v.*^{16a}, but not the sing. וַיֵּלֶךְ וַיָּשָׁב, 'and he went and dwelt,' in *v.*^{16b}. \mathfrak{C}^{B} reads 'Jethro' in place of 'Hobab.' These variations suggest that the original of \mathfrak{C} already lacked the proper name, and that the lacuna was differently supplied in different MSS. (Stu., Meyer); though it is possible that the reading 'Jethro' represents the substitution of the better known name of Moses' father-in-law, in place of Hobab (Mo., La.). The reading of \mathfrak{C}^{AL} is adopted by La., Kit., and may be original: but the sing. verbal forms in *v.*^{16b} favour the reading adopted above; and it is easy to suppose that the pl. verb in *v.*^{16a} has been altered from sing. עָלָה to suit the subject as it stands in \mathfrak{H} . Meyer (*IV.* p. 90) emends וְקַיִן simply, and thus reads, 'And Kain, the father-in-law of Moses, went up, etc.'; but, as Mo. notices, the mention of 'Hobab the Kēnite' in *ch.* 4¹¹, whether it be original or a later gloss, depends upon and substantiates the reading in our passage, Moses' father-in-law being elsewhere described not as a Kēnite but as a Midianite.

Kain occurs as the tribal name of the Kēnites in *ch.* 4¹¹, Num. 24⁴² (JE). The name may denote a worker in metal, and perhaps indicates that this form of industry was characteristic of the tribe. For the theory that the story of Cain (Kain) and his descendants (Gen. 4 J) was intended to explain the nomadic life of the Kēnites and their skill as artificers, cf. Cheyne, *EB.* 621 f.; Skinner, *Genesis (ICC.)*, pp. 111 ff.

Went up from the City of Palms with the children of Judah into the wilderness of Judah which is in the Negeb of 'Arad; and

the father-in-law of Moses. Moses' father-in-law, when first introduced in Ex. 2¹⁸ (J), is called Re'uel. The document E, which takes up the narrative in Ex. 3, speaks of him by the name Jethro; and this name is uniformly employed elsewhere in E. Num. 10²⁹ (J) mentions 'Hobab, the son of Re'uel, the father-in-law of Moses.' Here it is ambiguous whether the title 'father-in-law' refers to Hobab or Re'uel; and, if this passage stood alone in mentioning Hobab, we should naturally refer the title to Re'uel in agreement with Ex. 2¹⁸, and regard Hobab as brother to Šipporah, Moses' wife, and brother-in-law to Moses. But from Judg. 4¹¹ the title 'father-in-law' is clearly seen to refer to Hobab. It is true that R.V. *text*, in order to solve the difficulty, renders 'brother-in-law'; but this is quite unwarrantable. The Heb. term employed, *hōthēn*, is the same as the Ar. *ḥātin*, properly 'circumciser,' the original reference being to the nomadic custom by which the father-in-law performed the rite of circumcision upon the bridegroom (Heb. *ḥāthān*, 'the circumcised') shortly before marriage. Probably Hobab is the true name of Moses' father-in-law according to J, and Re'uel is a remoter ancestor—perhaps the clan-name.

went up. Cf. note on v.¹, 'who shall go up.' The 3rd sing. עָלָה is read in place of pl. עָלוּ in W. Cf. the first note on this verse.

the City of Palms. Mentioned again in ch. 3¹³, Deut. 34³, 2 Chr. 28¹⁵ †, the two latter passages showing the reference to be to Jericho. Jos. (*RJ.* IV. viii. 3) alludes to the 'many kinds of date-palms, differing from each other in flavour and name,' which flourished in his day in the neighbourhood of Jericho, owing to the fertilizing influence of Elisha's fountain. Other references are collected by Smith, *HG.* p. 266, n⁴. At the present day the palms have entirely disappeared. The site of Jericho is undoubtedly the modern Tell es-Sultān, a large mound which lies in the Jordan valley five miles west of Jordan, and at the foot of the central range of hills, close to the mouth of the Wādy el-Kelt, which affords a passage into the hill-country of Ephraim, and is thought to be the ancient valley of 'Achor. Just below Tell es-Sultān lies the 'Ain es-Sultān, which must be identified as Elisha's fountain. The modern Jericho (Eriḥâ) is a squalid village lying one and a half miles to the south.

with the children of Judah. Num. 10^{29ff.} (J) records Moses' invitation to Hobab to throw in his lot with Israel, and join in the occupation of Canaan.

into the wilderness of Judah which is in the Negeb of 'Arad. The description is somewhat obscure, and the text may be suspected; but the case for its rejection is not convincing. Mo. regards the statement as 'self-contradictory,' because 'the wilderness of Judah, the

he went and dwelt with 'the 'Amalekites'. 17. And Judah went barren steeps in which the mountains break down to the Dead Sea, and the Negeb are distinct regions.' The fact that in Josh. 15²¹⁻⁶² (P), the territory of Judah is divided into 'the Negeb' (נֶגֶב, 21-32), 'the Shephelah' (שְׁפֵלָה, 33-47), 'the Hill-country' (הַר, 48-60), and 'the Wilderness' (מִדְבָּר, 61-62), would seem at first sight to draw such a distinction; but the precise term, 'the wilderness of Judah,' only occurs once again in the O. T. in the heading of Ps. 63, and is there applied to the scene of David's wanderings during his outlaw life, including doubtless 'the wilderness of Ziph' (1 Sam. 23¹⁴, 26²; Tell Zif), 'the wilderness of Ma'on,' in the 'Arabah south of Jeshimon' (1 Sam. 23²⁴, 25¹ C^B; Tell Ma'in), close to Carmel (1 Sam. 25²; el-Kurmul, about one mile north of Ma'in), 'the wilderness of 'En-gedi' (1 Sam. 24¹; 'Ain Gidi). Ziph, Ma'on, and Carmel are assigned in Josh. 15⁶⁵ not to 'the Wilderness' but to 'the Hill-country.' The wilderness of Ziph and of Ma'on may be thought of, then, as the region immediately eastward of these cities breaking down towards the Dead Sea; but, if this part of the Wilderness actually took its name from two cities in the Hill-country, it might be said to extend into the Hill-country, and (conceivably) to be 'the Wilderness of Judah which is in the Hill-country.' 'Arad is to be identified with Tell 'Arâd, 'a barren-looking eminence rising above the country around' (Rob. BR³. ii. p. 101), which lies seventeen miles nearly due south of Hebron, and about half that distance due south of Ma'on. Some eight miles south-west of Tell 'Arâd is el-Milh, which is probably the City of Salt (Heb. *îr ham-mêlah*) mentioned in Josh. 15⁶² as one of the six cities in 'the Wilderness.' 'En-gedi, the only other one of these six cities which can be identified, lies approximately twenty miles north-east of Tell 'Arâd, and the three sites are so placed that a line drawn from 'En-gedi to el-Milh would fall upon Tell 'Arâd (cf. Map IV). Thus it would seem that 'Arad (though assigned to the Negeb in the possibly composite passage, Num. 21¹ JE) might have been included in 'the Wilderness' if it had been enumerated among the cities of Judah in Josh. 15. Just as the wilderness of Ziph and Ma'on appears to denote not precisely the region in which these cities were situated, but the barren country to the east which bordered upon them, so the Negeb of 'Arad may denote that part of the Negeb bordering upon 'Arad to the south, into which the wilderness of Judah might be said to extend (cf. 'the Negeb of the Kenites,' 1 Sam. 27¹⁰).

All suggested emendations of the passage base themselves, to some extent, upon C. C^B reads εἰς τὴν ἔρημον τὴν οὐσαν ἐν τῷ νότῳ Ἰουδα, ἣ ἐστὶν ἐπὶ καταβάσεως Αραδ. C^{AL}, S^h (besides omitting ἣ ἐστὶν) transpose Ἰουδα and place it after ἔρημον as in W; but the word is marked with an asterisk in S^h, and it seems clear that C^B represents the more original form of C. Hence La. reads בְּמִדְבָּר אֲשֶׁר בְּנֶגֶב, 'into the wilderness which is in the Negeb of

with Sime'on his brother, and they smote the Cana'anites who inhabited Şephath, and devoted it to destruction. And the name

Judah at the descent of 'Arad'; van Doorninck (*Theol. Literaturzeitung*, 1884, p. 211), followed by Bu. (*RS.* p. 10) מִדְּבַר יְהוּדָה אֲשֶׁר בְּמִדְּבַר עֲרָד, 'into the wilderness of Judah which is at the descent of 'Arad.' It is not clear, however, considering the site of Tell 'Arâd, to what 'the descent of 'Arad' could refer. The Heb. term rendered 'descent' is used in Josh. 10¹¹, Jer. 48⁵, and probably also in Josh. 7⁵, of a steep pass between mountains. La.'s contention that 'if Tell 'Arâd is on a plain, the plateau descends not far off from it, towards the east,' is not very convincing as to the appropriateness of the expression in this connexion. Examination of the rendering of Ἐ in can scarcely fail to suggest that the words τῇ οὐσαν ἐν τῷ νότῳ and ἡ ἐστὶν ἐπὶ καταβάσεως represent a double rendering of a single phrase in the Hebrew; in which case במורר or במרר (ἐπὶ καταβάσεως) is simply a corruption of בננב (ἐν τῷ νότῳ), the resemblance between the two words in the ancient character being not remote. Mo. regards במורר as an old error for במדבר, 'into the wilderness,' as in Josh. 8²⁴ Ἐ. In his view מִדְּבַר עֲרָד 'into the wilderness of 'Arad' represents the original text; אֲשֶׁר בְּנֶגֶב, 'which is in the Negeb,' is a gloss to 'Arad from Num. 21¹ introduced into the text in the wrong place (*i.e.* before instead of after 'Arad'); and במדבר, 'into the wilderness (of),' being thus left without a genitive, has finally been explained by the addition of 'הוּדָה', 'into the wilderness of Judah.' Mo.'s view is adopted by No., Kit., and approved by Bu. in his *Comm.*, except that Bu. favours retention of the words אֲשֶׁר בְּנֶגֶב after עֲרָד, thus reading, 'into the wilderness of 'Arad which is in the Negeb.'

with the 'Amalekites. Reading אֶת-הָעֲמֻלִּיקִי with all recent commentators. The reading occurs as a doublet (μετὰ τοῦ λαοῦ Ἀμαλῆκ) in Ḑ, 𐤁, Copt. The Kenites are found among the 'Amalekites in 1 Sam. 15⁶, and are associated with them in Bala'am's prophecy (Num. 24^{20,21} JE). 𐤁, 'and he went and dwelt with the people,' gives no intelligible sense. Heb. *hā-'ām*, 'the people,' is doubtless a remnant of the original reading *hā-'āmālēkī*.

17. *Şephath*. Only mentioned here. The ruined site Sebaita, nearly thirty miles south of Be'er-sheba', is favoured by many; but there is no philological connexion between this name and the Heb. Şephath. In this respect nothing can be alleged against Rob.'s finding of the name (*BR*³. ii. p. 181) in naḵb eṣ-Şafâ ('pass of the smooth rock'), a steep pass upon the route from Petra to Hebron, east-north-east of the ḡebel el-Madċrah; though no trace has been discovered of a city bearing the name.

and devoted it to destruction. The Heb. verb is the Hiph'il (causative) modification of a root *ḥāram* which does not occur in

of the city was called Hōrmah. 18. R^p And Judah took Ġāza

Heb. in the simple stem, but the sense of which may be illustrated from Ar. In Ar. *ḥaruma* means 'to be forbidden, prohibited, unlawful,' then 'to be sacred or inviolable.' Hence, in the first sense, *ḥarīm* denotes the forbidden or private part of a house, *i.e.* the women's apartments; *maḥram* is a female relation who comes within the prohibited degrees, and whom therefore it is unlawful to marry; *el-Muḥarram* is the first month of the Mohammedan year, during which fighting is prohibited. In the second sense we may notice *ḥaram*, the sacred territory of Mecca, *el-mesgid el-ḥarām*, the sacred mosque. In Heb. the causative *heḥērim* means to make a thing unlawful or *taboo*, by devoting it to God, and is commonly applied, as in this passage, to Israel's action in their religious wars, when the foes and their cities were devoted to wholesale destruction, and sometimes the cattle also (cf. Josh. 6²¹, 1 Sam. 15³), though not always (cf. Deut. 2^{34.35}, 3^{6.7}). Inanimate objects coming under the sacred ban were destroyed by fire; or, as in the case of gold and silver, and utensils of metal, dedicated to Yahweh's sanctuary (Josh. 6²⁴: the latter half of the verse appears, however, to be an addition by R^p to the older narrative). Everything so devoted was called *ḥérem*, 'devoted thing'; and appropriation of any such *ḥérem* was thought to incur Yahweh's dire displeasure, and could only be expiated by death, as in the case of 'Achan (Josh. 7^{1ff.}). The verb is used in a precisely similar sense by Mesha', king of Moab, when relating his treatment of a captured Israelitish city:—'And Chemosh said to me, "Go, take Nebo against Israel"; and I went by night, and fought against it from break of dawn until noon, and I took it and slew the whole of it, 7000 men, and . . ., and women, and . . ., and damsels; for to 'Ashtar-Chemosh had I devoted it (הִחֲרַמְתִּיהָ, *heḥēramtīhā*); and I took thence the vessels of Yahweh, and dragged them before Chemosh' (*Moabite Stone*, ll. 14-18).

And the name of the city was called Hōrmah. Tradition connects the name with the root *ḥāram* in the sense 'devoted to destruction.' Possibly the original meaning of the name may have been 'sanctuary' or 'sacred area.' Cf. Ar. *ḥaram* noticed above. The site of Hōrmah has not been identified. This narrative seems to be a duplicate of Num. 21¹⁻³ (JE), which is probably the immediate sequel of Num. 14⁴⁰⁻⁴⁵ (JE), and which places the conquest and extermination of the Cana'anites inhabiting a district of the Negeb, and hence the origin of the name Hōrmah, immediately after the mission of the spies, who, according to JE, were sent out from Qadesh-Barnea'. Probably the position of the narrative in Num. is the more original, and points to the capture and settlement of a portion of the Negeb by Judaeans (Calibbites) who advanced northwards from Qadesh at some time prior to the occupation of Cana'an by the Israelite tribes who entered from the east under Joshua'. Cf. further *Additional note*, p. 44.

and the border thereof, and Ashkelon and the border thereof, and 'Eḡron and the border thereof. 19. J And Yahweh was with Judah, and he gained possession of the hill-country; for <he was> not <able> to dispossess the inhabitants of the Vale, because they

18. *And Judah took Ġaza, etc.* The three Philistine cities here specified (the modern Ġazzeh, 'Asḡalân, and 'Āḡir) are all situated in the maritime plain, *i.e.* 'the Vale,' the inhabitants of which *v.*¹⁹ tells us Judah could not dispossess. Josh. 13³ (R^D) informs us that these three cities, together with Ashdod and Gath, remained uncaptured by Joshua; and in Judg. 3³ 'the five lords of the Philistines' are included among 'the nations which Yahweh left to test Israel by them' (3¹). There is no suggestion that Judah first captured the cities and then failed to hold them; and it thus seems probable that *v.*¹⁸, like the statement as to the capture of Jerusalem in *v.*⁸, is a mistaken editorial insertion. *¶* corrects to *καὶ οὐκ ἐκληρονόμησεν*.

'*Eḡron*. The *¶* form is *Ακκαρων*, while the name appears in the Assyrian inscriptions as Amḡaruna; and these two facts taken together suggest that the Heb. vocalization should be 'Aḡḡaron for Amḡaron, the double ḡ representing assimilated *m*, or the *m* arising through dissimilation of double ḡ.

19. *he gained possession*. The Heb. verb *hōriṣ* (causative of *yāraṣ*) means 'to cause to inherit *or* possess,' with the collateral idea of causing succession to the inheritance of the previous owner, and so disinheriting or dispossessing him. This double sense is illustrated by the present verse, where 'gained possession of' and 'to dispossess' are both represented by the same verb in the Heb. In *v.*²⁷ a single occurrence of the verb is applied, by a kind of *zeugma*, both to cities (Beth-she'an, Ta'anach), for which the rendering 'gain possession of' would be the more suitable, and to the inhabitants of cities (Dor, Ible'am, Megiddo), with regard to whom this rendering is impossible, and the sense postulated is 'dispossess.'

he was not able to dispossess. *¶* has simply 'not . . . to dispossess,' the governing verb *יכל*, 'was able,' being absent. It is theoretically possible to translate the Heb. as it stands 'was not for dispossessing,' *i.e.* 'could *or* did not dispossess' (cf. Driver, *Tenses*, § 204); but since we know, from the parallel narrative in Josh., that in *vv.*^{21.27} an original 'could not dispossess' has been altered by R^p into 'did not dispossess' for dogmatic reasons (cf. *introd. note* to section), it is reasonable to conclude that such an alteration was intended by R^p in this case also, and that he has carried it out imperfectly by simple excision of the verb *יכל* (we should have expected emendation to a perfect *הוריש*, as in *vv.*^{21.27}).

the Vale. The Heb. 'ēmeḡ, lit. 'depression,' is applied to a wide and

had chariots of iron. 20. And they gave Hebron to Caleb, as Moses had said: and he dispossessed from thence the three sons of 'Anāk. 21. But the Jebusites dwelling in Jerusalem the

open vale or lowland country, and here denotes the maritime plain to the west of the hill-country of Judah, or, more accurately, to the west of the low foothills which lie between the Hill-country and the Vale (cf. *note* on 'the Shephelah,' *v.*⁹). Cf. further, p. 203, *footnote*.

chariots of iron. These are also mentioned as forming the most effective part of the military equipment of the Canaanites inhabiting the vale (*ēmek*) of Jezreel: Josh. 17¹⁶ (J); cf. Judg. 4³. Among the steep and narrow passes of the Judæan hill-country they would have been useless: though in 1 Sam. 13⁵ the Philistines are described as bringing them up into the central hill-country as far as Michmash, doubtless through the pass of Aijalon. Here the incredibly large number of 30,000 chariots given by *Ḥ*, appears in *Ḥ*^L, *Ṣ*^P as 3000. The Aramaeans in later times found chariots ineffective among the hills surrounding Samaria: 1 Kgs. 20²³⁻²⁵.

20. *And they gave Hebron to Caleb.* Cf. Josh. 14⁶⁻¹⁵ (R^D based on JE).

as Moses had said. Referring back to Num. 14²⁴ (JE): cf. Deut. 1³⁶, Josh. 14⁹.

the three sons of 'Anāk. Sheshai, Ahiman, and Talmai, mentioned in *v.*¹⁰ *end*, which is the proper sequel to *v.*²⁰ in the original form of J's narrative (cf. the first *note* on *v.*¹⁰). Heb. 'ānāk means 'neck'; and it may be inferred that *bēnê 'ānāk* properly denoted 'long-necked (*i.e.* tall) men.' Cf. the spies' description of their size and stature in Num. 13³³ (JE), and the rendering of *Ḥ vīōs γιγάντων* in Deut. 1²⁸.

21. *the Jebusites.* Nothing is known of this people beyond the fact that they appear as the inhabitants of Jerusalem here and in || Josh. 15⁶³, and in the narrative of David's capture of the city, 2 Sam. 5^{6 ff.} 'Araunah the Jebusite' still lived at or just outside of Jerusalem after David had captured it and made it his capital (2 Sam. 24^{16 ff.}); and very possibly the Jebusites, after their expulsion from the stronghold of Sion (the south-east hill), which became the city of David, were still allowed to dwell upon the (presumably unwall'd) south-west hill, which is styled 'the cliff (lit. "shoulder") of the Jebusites' in Josh. 15⁸, 18¹⁶ (P). In Judg. 19^{10,11}, 1 Chr. 11^{4,5} the name Jebus is given to Jerusalem as an earlier name of the city. In the Tell el-Amarna tablets, however, we find the name Urusalim regularly employed so early as *cir.* B.C. 1400. Cf. further, on the Jebusites, *Introd.* pp. lxxxvi f.

the children of Judah. Reading 'Judah' in place of 'Benjamin' with || Josh. 15⁶³. The alteration in *Ḥ* has been made in accordance with Josh. 18¹⁶ (P), which, in describing the lot of the children of Benjamin, makes the border run south of Jerusalem so as to include the city, and mentions it among the cities belonging to the tribe in *v.*²⁸.

children of 'Judah¹ did not dispossess: and the Jebusites dwelt with the children of 'Judah¹ in Jerusalem, unto this day.

22. And the house of Joſeph also went up to Bethel: and

did not dispossess. An alteration of || Josh. 15⁶³ 'were not able to dispossess.' Cf. *introd. note* to section.

dwelt . . . unto this day. To what period does this note of time refer? We can scarcely imagine Jebusites and Judaeans dwelling side by side in Jerusalem prior to the capture of the ancient stronghold by David; and in fact in the old narrative of Judg. 19^{11,12} Jebuſ is described as 'the city of foreigners who are not of the children of Israel,' and so likely to prove inhospitable to the Levite in need of a night's lodging. On the other hand, the fact that Jebusites remained at Jerusalem after the capture of the city by David (cf. *note* on 'the Jebusites' above) appears to have been due rather to David's clemency than to the inability of the Judaeans to dispossess them. This consideration, however, may have been overlooked by the writer of J; and it seems the more probable view that the note refers to a period subsequent to David's capture of the city.

22. *the house of Joſeph.* So v.³⁵, Josh. 17¹⁷ (J), 2 Sam. 19²⁰, 1 Kgs. 11²⁸, Am. 5⁶. The reading of \mathfrak{C} , $\text{o}\acute{\iota}$ $\nu\acute{\iota}\text{o}\iota$ $\text{I}\omega\sigma\eta\phi$, is probably an alteration under the influence of the plural verb 'went up' (וַיַּעֲלוּ). The term may be used to include not merely Ephraim and Manasseh, but also Benjamin. Cf. 2 Sam. 19²⁰, where Shime'i, the Benjaminite (16¹¹), speaks of himself as belonging to the house of Joſeph.

went up to Bethel. Sc. from Gilgal: cf. v.¹ *note*; ch. 2¹. Bethel is the modern Bêtin,* about ten miles north of Jerusalem; and 'Ai, the first city captured in the hill-country, according to Josh., lay immediately to the east of Bethel (Josh. 7², 8^{9,12} JE; cf. Gen. 12⁸ J). The narrative seems to picture an independent attack made by the Joſeph-tribes upon the hill-country; and it is not improbable that it originally formed part of a longer account in which this section of Israel carried out its campaign under the leadership of Joshua'. This is the view of Bu., who suggests that J's narrative originally ran 'went up to 'Ai,' and then followed on with an account of the capture of 'Ai, as in Josh. 8, before mentioning the reconnaissance and capture of Bethel (v.²³). Cf. *RS.* pp. 57 f., and see further *Additional note*, p. 48. The mention of the men of Bethel in Josh. 8¹⁷ as joining with the men of 'Ai in repelling Israel's attack upon the latter city is clearly a late gloss, which finds no place in \mathfrak{C} , and is out of harmony with the context. We have no account in Josh. of the capture of Bethel, but Josh. 12¹⁶ (R¹⁰) mentions the king of Bethel in the list of kings smitten by Joshua'.

* For the modification of the final $\text{-}\acute{e}l$ to $\text{-}\acute{i}n$, cf. Zer'in for Jezre'el, Isrâ'in for Isra'el (in Birket Isrâ'in at Jerusalem), Bêt Gibrin, 'House of Gabriel,' and Wâdy Isma'in (Ishma'el).

Yahweh was with them. 23. And the house of Joseph made a reconnaissance at Bethel. (Now the name of the city formerly was Luz.) 24. And the watchers saw a man coming out of the city, <and they laid hold on him> and said to him, 'Show us, we pray thee, the way to enter the city, and we will deal kindly with thee.' 25. So he showed them the way to enter the city, and they smote the city at the edge of the sword; but the man and

and Yahweh was with them. Cf. *v.*¹⁹, 'and Yahweh was with Judah' (with נח= 'with' in place of עמם *v.*²²). E^{AL} καὶ Ἰουδας μετ' αὐτῶν. Bu. (*RS.* pp. 58 f.; *Comm.* p. 11, followed by Kit. *HH.* i. p. 269; *GV.*² i. p. 570) makes out a good case for the suggestion that under both readings, 'Yahweh' and 'Judah,' there lies an original 'Joshua.' If, as is generally acknowledged, Josh. 17¹⁴⁻¹⁸ belongs to this narrative, some mention of Joshua' is to be expected. A sufficient reason for the excision of the name of Joshua', and the substitution of the reading of our text, is furnished by the fact that R^p professes to be giving an account of events which happened 'after the death of Joshua' (cf. *introd. note* to section).

23. *made a reconnaissance.* The same Heb. verb *tār* is used of the exploration of Canaan by the spies (*hat-tārîm*, Num. 14⁶) in the parts of Num. 13, 14 which belong to P. In this passage we have the Hiph'il (causative) modification of the verb, which, if not merely an error for the simple stem (ויתירו for ויתרו), may mean 'caused a reconnaissance to be made.' E^{L} καὶ παρενέβαλον (so E^{BA} with doublet καὶ κατεσκέψαντο), H 'cum obsiderent,' suggest a reading וַיִּחְנֶנּוּ, 'and the house of Joseph encamped against Bethel.' Cf. the rendering of E in *ch.* 9⁶⁰.

now the name of the city formerly was Luz. Cf. Gen. 28¹⁹, 35⁶, 48³, Josh. 18¹³, all P, or redactional notes based on P—a fact which has led Mo. (*SBOT.*), No. to mark the statement here as due to R^p. The reference to Luz, however, in *v.*²⁰ J clearly points back to an earlier mention of the name in the same document. For conjectures as to the meaning of the name Luz, cf. *EB.* 2834.

24. *and they laid hold on him.* So E καὶ ἔλαβον αὐτόν, *i.e.* בָּו וַיִּקְחוּ (cf. *v.*⁶), which, as Bu. remarks, may easily have fallen out before וַיֹּאמְרוּ, 'and they said.'

the way to enter. So Mo. The Heb. *m'bhô* (lit. 'place or act of entry') might mean 'entrance' (so R.V.), as in 2 Kgs. 11¹⁶, 16¹⁸ *al.*; but, as the position of the city-gate must have been obvious to the spies, the expression probably means, as Mo. remarks, 'the most advantageous point for an assault or surprise.'

25. *at the edge of the sword.* Cf. *v.*⁸ *note.*

all his clan they let go. 26. And the man went to the land of the Hittites, and built a city, and called its name Luz: that is its name unto this day.

27. And Manasseh did not dispossess Beth-she'an and its

26. *the land of the Hittites.* The Hittite principalities (relics of the earlier mighty empire which embraced a great part of Asia Minor and northern Syria) extended as far south as Ḳadesh, near the sources of the Orontes in the Anti-Lebanon. The northern limit of the kingdom of Israel in David's time seems to have extended 'to the land of the Hittites unto Ḳadesh' (2 Sam. 24⁶, reading אֶרֶץ הַחִתִּים קְדֵשָׁה after \mathfrak{A}^L in place of the unintelligible text of \mathfrak{H}). On the Hittites, cf. further *Introd.* pp. lxxi f., lxxxiv ff., xcix f.

called its name Luz. The site of this northern Luz is unascertained. As Mo. notices, modern names compounded with the Ar. *laus*, 'almond,' are not infrequent, and any attempt at identification must therefore be wholly unreliable.

27. *And Manasseh did not dispossess, etc.* Upon the use of the verb *hōrīš*, here rendered 'dispossess,' cf. *note* on v. 19. Beth-she'an, which received the Greek name Scythopolis in Macedonian times (cf. \mathfrak{A} 's gloss ἡ ἐστὶν Σκυθῶν πόλις), is the modern Bēsân, situated above the Jordan valley at the mouth of the Wâdy Ġâlûd, which descends south-east from the plain of Esdraelon; Ta'anach, now called Ta'annuk, lies some seventeen miles a little north of due west of Bēsân, upon the southern edge of Esdraelon, and about eight miles north-north-west of the Wâdy Bel'ameh, which probably preserves the name of the ancient Ible'am; * Megiddo, coupled with Ta'anach in *ch.* 5¹⁹, Josh. 12²¹, 17¹¹, 1 Kgs. 4¹², is now identified with Tell el-Mutesellim ('the mound of the governor'), five miles north-west of Ta'annuk, an important site commanding the pass from the plain of Sharon to the plain of Esdraelon, which the recent excavations of the German Palestine Exploration Society (vol. i. of the Report 1908) have shown to have been a fortified city of the Canaanites many centuries before the Israelite occupation of Palestine. The statement of Josephus that Dor was situated on the Mediterranean seacoast, near Carmel (*Ant.* VIII. ii. 3; cf. *C. Ap.* ii. 116), is confirmed by the Egyptian narrative of Wenamon, the envoy of Hrihor of Thebes (*cir.* B.C. 1114), who in his voyage from Egypt to Phoenicia puts in at the harbour of Dor (Breasted, *AR.* iv. § 565; cf. *Introd.* p. xcvi).

* The modern Yebla, north-west of Bēsân, proposed by Conder (*SWP. Mem.* ii. p. 98) as the site of Ible'am, is philologically less probable. The dropping of the final syllable with its guttural \mathfrak{y} might be paralleled, however, by the modern el-Ġib for Gibe'on. For the dropping of the preformative ' of יִבְלָעַם in Bel'ameh, cf. the form בִּלְעָם Bile'am 1 Chr. 6⁷⁰ (\mathfrak{H} 55), and Zer'in for יִזְרְעֵאל.

dependencies, and Ta'anach and its dependencies, and the inhabitants of Dor and its dependencies, and the inhabitants of

OS. places the site eight Roman miles from Caesarea (283³), and this tradition is preserved in the identification with the modern Ṭanṭûrah, which lies north of Caesarea at a little less than eight English miles. The term *Nāphath* (*Nāphôth*) *Dôr* (Josh. 11², 12²³, 1 Kgs. 4¹¹), if rightly explained to mean 'the heights of Dor,' is difficult to account for upon this identification, unless it is applied to the outlying flanks of the Carmel-range some distance inland from Ṭanṭûrah.

As the text stands, it is rather strange that Dor, lying in the extreme west, should be interposed between the two cities Ta'anach and Ible'am, which occupy a central position in near neighbourhood to one another. Thus it is probable (as Mo. suggests) that the mention of Dor originally stood last, as in 1 Chr. 7²⁹, which is probably based upon this passage. With this change, the cities are mentioned approximately in their geographical order from east to west; and it is noticeable that they must have formed, with their dependencies, a strong belt of fortresses separating the central tribes of Israel from the tribes in the north. We learn from the narrative of Wenamon that the inhabitants of Dor at this period were not Canaanites but Takkara, a western people who invaded Canaan at the same time as the Philistines, and who were probably allied to them (cf. *Introd.* pp. xcii f.). This fact, coupled with the fact that we find Beth-she'an in the hands of the Philistines at the end of Saul's reign (1 Sam. 31¹⁰), suggests the possibility that the whole series of cities extending from Sharon across the plain of Esdraelon may have belonged to these western invaders in the times of the Judges.

The account of the inheritance of West Manasseh, as given in Josh. 17 (J and P combined), is somewhat perplexing. This much, however, is clear, as stated by P (*vv.* 9, 10). It was bounded on the west by the Mediterranean; on the north by the territory of Asher, which, we are told in Josh. 19²⁶ P, extended as far as Carmel; on the south by the territory of Ephraim, the boundary line being the Wâdy Kâna, *i.e.* it need not be doubted, the modern Wâdy Kâna* running into the Nahr el-'Auḡa, which reaches the sea a few miles north of Joppa. The eastern boundary is stated to have been the territory of Issachar; and it is here that our information is too slight and perplexing to allow of any certain inferences as to the delimitation. According to J in Josh. 17¹¹, the towns along the southern edge of the plain of Esdraelon which Manasseh was unable to conquer were (though rightly belonging to Manasseh) 'in Issachar and in Asher.'

dependencies. Lit. 'daughters,' a term applied to smaller cities or hamlets dependent upon the larger fortified cities. The use of the expression is characteristic of J. Cf. CH.^J 88.

* The Ar. name is spelt with K', but it seems likely that this is a transcriptional error for K', which is found in the Heb. name.

Ible'am and its dependencies, and the inhabitants of Megiddo and its dependencies; but the Canaanites persisted in dwelling in this land. 28. And when Israel was waxen strong, they impressed the Canaanites for labour-gangs, and did not dispossess them at all.

29. And Ephraim did not dispossess the Canaanites who

persisted. The Heb. verb (הוֹצִיל) is used in this special sense in

|| Josh. 17¹² and in v.³⁵ † of this chapter. Elsewhere, when used of an action undertaken of one's own accord, it has the sense *to resolve*: cf. Gen. 18^{27.31} (R.V. 'I have taken upon me'), Deut. 1⁶ (R.V. 'began'); and we may infer therefore for the special usage with which we are dealing the sense *to carry out one's resolution*, so *persist*. When the verb is employed of an action undertaken at the instance of some one else, *to consent* is the appropriate rendering: cf. ch. 17¹¹, 19⁶, 2 Sam. 7²⁹, 2 Kgs. 5²³, 6³ (R.V. 'be content' in all passages except 2 Sam. 'let it please thee').

28. *labour-gangs.* The Heb. term *maš* denotes a levy of men impressed for task-work, rather than the task-work itself (as in R.V.): cf. especially the phrase *maš 'ōbhēdh*, 'toiling labour-gang,' Gen. 49¹⁵, Josh. 16¹⁰, 1 Kgs. 9²¹. Such a levy was imposed upon the Israelites in Egypt (cf. Ex. 1¹¹, where, as Mo. points out, the term מַסֵּים שְׂרָי should be rendered 'gang-foremen' rather than 'task-masters' R.V.), and by Solomon not merely upon the Canaanites (as stated in 1 Kgs. 9^{15.22}) but also upon the Israelites for the purposes of his extensive building operations: cf. 1 Kgs. 5¹³ (27³⁰).

and did not dispossess them at all. The Heb. construction (וְהוֹצִיט לֹא הוֹצִיטוּ, Infinitive Absolute emphasizing the finite verb) lays stress upon the fact that the expulsion of the Canaanites was left absolutely unaccomplished. R.V., by its rendering 'and did not utterly drive them out,' suggests that the expulsion was partially but not completely accomplished, a sense which is directly at variance with the meaning of the Heb.

29. *Ephraim.* The account of Ephraim's heritage as given in Josh. 16^{5ff.} P is somewhat confused and perplexing: cf. Hogg in *EB*. 1319. Here we need only notice that the tribe occupied the central part of Canaan, its northern boundary marching with that of Manasseh along by the Wādy Kana (cf. *note* on Manasseh, v.²⁷) to the sea, while the southern boundary, starting from the Jordan near Jericho, met the territory of Benjamin and Dan, apparently turning north or north-west at Gezer. Cf. further p. 222.

Gezer. The modern Tell Gezer, situated in a commanding position to the east of the maritime plain of Philistia, upon an outlying spur of the low hills of the Shephelah, about eighteen miles west-north-west

dwelt in Gezer; but the Canaanites dwelt in the midst of them in Gezer.

30. Zebulun did not dispossess the inhabitants of Kithron, nor

of Jerusalem. The identity of the site with the ancient Gezer, inferred from the identity of the modern Ar. with the ancient Heb. name, was placed beyond doubt by the discovery in 1871 by Clermont-Ganneau of the inscription 'the boundary of Gezer,' cut in ancient Heb. characters upon several of the rocks at a short distance from the site: cf. Macalister, *Bible Sidelights from the Mound of Gezer*, pp. 22 ff.; Driver, *Schweich Lectures*, p. 46. The site of Gezer has been excavated by Mr. Macalister under the auspices of the Palestine Exploration Fund (1903-1905, 1907-1909), and a detailed Memoir has recently (1912) appeared. For a convenient summary of the discoveries, cf. Driver, *op. cit.*

The excavations have shown that Gezer was inhabited by a race of cave-dwellers as early as *cir.* B.C. 3000. It is first mentioned in history as captured by Thutmose III. (*cir.* B.C. 1501-1447). Among the Tell el-Amarna letters (*cir.* B.C. 1400) there are several from Yapaḥi, king or governor of Gezer, who appeals for help against a people whose name is written ideographically SA.GAZ, and who are generally supposed to be identical with the Habiru (cf. *Introd.* pp. lxxv ff.). Mineptah claims to have captured Gezer upon the celebrated 'Israel' stele: cf. Breasted, *AR.* iii. § 617. This must have been *cir.* B.C. 1223, a few decades before the Israelite invasion of Canaan under Joshua. The failure of the Ephraimites to capture Gezer is confirmed by 1 Kgs. 9¹⁶, where we learn that the city was still in the hands of the Canaanites in the days of Solomon, when it was taken and burnt by the Pharaoh who was king of Egypt at that time, and given as a dowry to his daughter on the occasion of her marriage with Solomon. These facts are for us difficult to reconcile with the statement of R¹⁹ in Josh. 10³³ that, when Horem king of Gezer came to the assistance of Lachish, 'Joshua' smote him and his people until he had left him none remaining.'

but the Canaanites . . . Gezer. *Gr* adds καὶ ἐγένετο (αὐτῶ) εἰς φόρον. || Josh. 16^{10b}, 'but the Canaanites dwelt in the midst of Ephraim unto this day, and became toiling labour-gangs': probably the more original form of J's statement. The words 'unto this day,' if they 'do not necessarily imply a time prior to the destruction of the city by the Egyptians' (Mo.), at any rate seem to point to the earlier monarchic period. Cf. *note* on the same expression in v. 21.

30. Zebulun. The description of Zebulun's territory given in Josh. 19^{10ff.} P is obscure. The southern boundary was contiguous with the territory of Issachar along a line which ran east and west across the plain of Esdraelon in the neighbourhood of Mount Tabor; while on the south-west the boundary marched with the territory of Manasseh,

the inhabitants of Nahalol; but the Canaanites dwelt in the midst of them, and became labour-gangs.

31. Asher did not dispossess the inhabitants of 'Acco, nor the north-west with the territory of Asher, and north, and apparently east, with that of Naphtali. Jos., however, states (*Ant.* v. i. 22) that their inheritance included the land which reached as far as Gennesaret, as well as that which lay about Carmel and the sea (cf. Gen. 49¹³).

Ḳiṭrōn . . . Nahalol. Neither site has been identified. Nahālōl (perhaps meaning 'watering-place' of flocks; cf. plural נְהָלִים, Isa. 7¹⁹) appears in Josh. 19¹⁵, 21³⁵ as Nahālāl. G^B Δωμava in the present passage must have read Dimnah, which is coupled with Nahālāl in Josh. 21³⁶. In Josh. 19¹⁵ Ḳaṭṭāth seems to stand in place of Ḳiṭrōn; but neither name occurs elsewhere. The Jerusalem Talmud (*Megillah*, i. 1) identifies Nahālāl with Mahlūl; and for this the modern Ma'lūl, 3½ miles west of Nazareth, has been advocated by Schwarz and others,* and Ain Māhil, about the same distance north-east of Nazareth, by Conder.

In the same passage in the Talmud Ḳaṭṭāth is said to be Ḳeṭīnith or Ḳeṭōnith ‡ (cf. Ε^B Καταναθ in Josh. 19¹⁵), a site which may be the modern Hirbet Kuteineh to the west of the plain of Esdraelon §: cf. Neubauer, *Géographie du Talmud*, p. 189. The view put forward in the Babylonian Talmud (*Megillah*, 6^a) that Ḳiṭrōn is the same as Šippōrī (Sepphoris), i.e. the modern Šeffūriyyeh, 3½ miles north of Nazareth, is opposed by Neubauer (*op. cit.* pp. 191 f.) upon the ground of a tradition (preserved in the same passage in the Talmud) that the tribe of Zebulun complained that, while Naphtali had been granted fields and vineyards, they had only been granted mountains and hills. Šippōrī, however, was famed for its fertility; and hence Neubauer argues that it must have belonged not to Zebulun but to Naphtali.

31. *Asher.* The tribe is mentioned as inhabiting western Galilee in the lists of the Egyptian kings, Sety I. and Ra'messe II., prior to

* The substitution of Ar. for Heb. *h* requires substantiation; and this is also needed as regards the interchange of *n* and *m* in Nahālāl, Mahlūl, if the two forms are to be regarded as philologically connected.

‡ Editions vary as to the form. Keṭonith (or Keṭunith) is given by Neubauer *loc. cit.*, and by Mo. and Cheyne (*EB.* 2654) following him. The Krotoschin edition (1866) has קטונית, Keṭonith, but the Jitomir (1866) and Petrokov (1899) editions read קטינית, Keṭīnith. The reference given by Neubauer from the Tosefta (*Sotah*, ch. 15) to איש קטונית, 'a man of Keṭonith,' should be, as a matter of fact (Pazewalk edition, 1881), בן קיטנית, 'a son of Kiṭnith,' with *var. lect.* קטנית, Kiṭnith or Kaṭnith.

§ The Heb. Keṭīnith corresponds exactly to the Ar. Kuṭeineh if this latter is to be regarded as a diminutive. Cf. for the vowel change modern Ar. *keṭīfah* for *kufeifah*, 'little basket': Wright, *Comparative Grammar*, p. 89.

Ḳaṭṭāth may very likely have arisen from an original Ḳaṭṭant or Ḳaṭṭint: cf. *bath* from *bint*, and, for the lengthening of the *a*, *ām* for 'amm.

inhabitants of Ṣidon, nor Aḥlab, nor Achzib, nor Ḥelbah, nor

the Israelite invasion under Joshua'; cf. *Introd.* p. lxxxix. The position of Asher's inheritance is described in Josh. 19^{21ff.} P. It seems to have been a strip of country reaching southward to Carmel, where it joined the territory of Manasseh, and apparently bordering the sea as far north as Achzib and Maḥaleb (cf. *note* following on Aḥlab). Farther north the western boundary must have been formed by the territory of the Ṣidonians, while the east and south-east boundary-line was formed by the territory of Naphtali and Zebulun. Probably the limits thus defined are largely ideal, a considerable portion of the territory which they include belonging properly to the Phoenicians; cf. *note* on v. ³².

'*Acco*. The modern 'Akkâ, situated on a rocky promontory at the northern extremity of the bay of 'Akkâ, the south side of which is formed by the promontory of Carmel. The town received the name Ptolemais during the Greek period; cf. *OS.* 224⁷⁵. The Acre of the Crusaders is a modification of the modern Ar. name; cf. Smith's article in *EB.* 3967 ff. 'Acco is wanting in the text of **א** in Josh. 19²⁴⁻³¹, but should probably be restored in place of Umma in v. ³⁰.

'*Sidon*. The modern Ṣaida, about twenty-five miles south of Beirût.

'*Aḥlab . . . Ḥelbah*. The two names are so similar that they look like variations of the same name. Schrader (*COT.* i. p. 161) and Delitzsch (*Paradies*, pp. 283 f.) compare the name *Maḥalliba* mentioned by Sennacherib in a list of Phoenician cities which capitulated to him in his third campaign: *Taylor Cylinder*, Col. ii. l. 38; cf. *KB.* ii. p. 90. Sennacherib names 'Great Ṣidunnu (cf. **צִירֹן רַבָּה**, Josh. 19²⁸) little Ṣidunnu, Bît-zitti, Ṣariptu (Ṣārēphath, 1 Kgs. 17^{9,10}, Ob. ²⁰, **Σαρεπτα** Lu. 4²⁶; the modern Ṣarafand), Maḥalliba, Uṣû, Akzibî, Akkû'; and the order running from north to south should place Maḥalliba somewhere between Ṣarafand, which lies eight miles south of Ṣidon, and Achzib (cf. *note* following), some thirty miles farther south. Mo. hazards the conjecture that the name may have been 'the old name of the *Promontorium album* of Pliny, the modern Râs el-Abyaḍ, midway between Tyre and Achzib,' a suitable site for an important town. The name may be connected with Heb. *ḥālābh*, 'milk,' in allusion to the whiteness of the headland.

The strange **מִחְבֵּל** of Josh. 19²⁹ (*mēḥēbel*; R.V. 'by the region'; *marg.* 'from Hebel') is almost certainly a corruption of **מַחְלֵב**, Maḥālēb (cf., in support of the transposition, **Ἐν ἀπὸ Λεβ**); and this fact lends support to the view of Müller (*AE.* p. 194, *n*¹), La. that the name should be so read in our passage, as against that of Mo. that Maḥalliba, Aḥlab, Ḥelbah were existing variations of the same name.

Aphik, nor Rehob: 32. but the Asherites dwelt in the midst of the Canaanites inhabiting the land; for they did not dispossess them.

33. Naphtali did not dispossess the inhabitants of Beth-

Achzib. The Εκδιππα of OS. 224⁷⁷, a form in which the δ seems to preserve the Aram. pronunciation. The modern identification is ez-Zib, eight and a half miles north of Accho.*

Aphik. Mentioned (in the form Aphēk) with Rehob among the cities of Asher in Josh. 19³⁰. That the Aphek of 1 Sam. 29¹ is the same (as suggested by Bu., La.) is scarcely likely, as this latter is probably to be sought in northern Sharon ‡ (Smith, *HG.* p. 350), and would therefore lie too far to the south. On the other hand, as Mo. points out, the modern Afkâ, north of Bêrût (probably the Aphek of Josh. 13¹), 'is much too far north for the present context and that of Josh. 19³⁰.' The name Aphek appears to have been by no means uncommon.

Rehob. The site is unknown. Müller cites the occurrence of the name in Egyptian lists; *AE.* p. 153. That the Beth-rehob of ch. 18²⁸, 2 Sam. 10⁶, inhabited by Aramaeans (probably the Rehob of Num. 13²¹), cannot be the same as the Asherite Rehob is perhaps too positively asserted by Mo. The identity is assumed by Nöldeke in *EB.* 279.

32. *the Asherites dwelt, etc.* In the case of Asher it is not claimed that the Canaanites eventually became a subject people. The maritime cities mentioned in v. 31 belonged to Phoenicia throughout the period covered by the history of the kingdom of Israel. In the Song of Deborah (ch. 5) the reference to Asher in v. 17 ('Asher sat still by the shore of the seas, dwelling beside his creeks') seems to indicate that the Asherites dwelt among the Phoenician Canaanites in a condition of dependence; and being thus unmolested by the central Canaanites, refused to make common cause against them with the other Israelite tribes.

33. *Naphtali.* The territory of Naphtali is described by P in Josh. 19³²⁻³⁹. It lay to the north of Zebulun, and was bounded by the territory of Asher on the west and by the Jordan on the east. The predominance of the foreign element in the region of Naphtali and Zebulun, as in that of Asher, is indicated by the title *G'ill hag-gôyîm*, 'the District (circuit) of the Nations' applied to it in

* If the name comes from the Heb. root פִּנָּה, Aram. פִּנָּה, as is suggested by the form Εκδιππα (cf. the word-play of Mic. 1¹⁴ in the case of the southern Achzib), we should expect ed-Dib. The substitution of *z* for *d* in modern Ar. is, however, not unparalleled.

‡ Probably Josh. 12¹⁸ ought to read מֶלֶךְ אֶפֶק לְשָׂרֹן אֶחָד, 'The king of Aphek pertaining to Sharon, one'; cf. Buhl, *Geogr.* p. 213, n⁶⁷⁴.

shemesh, nor the inhabitants of Beth-'anath; but they dwelt in the midst of the Canaanites inhabiting the land; and the inhabitants of Beth-shemesh and Beth-'anath became labourgangs for them.

34. And the Amorites pressed the children of Dan into the

Isa. 9¹ (\mathfrak{H} 8²³), or, in short form, *hag-Gālīl*, Josh. 20⁷, 21³²; 1 Kgs. 9¹¹; 1 Chr. 6⁷⁶ (\mathfrak{H} 61), whence the name Galilee. Cf. also 'Harosheth of the nations,' *ch.* 4^{2.13.16}, probably in Zebulun; cf. *note ad loc.*

Beth-shemesh . . . Beth-'anath. Both sites are unidentified (cf., however, *Introd.* p. cvii, *footnote* ||). Beth-'anath occurs in the Egyptian lists of the Eighteenth and Nineteenth Dynasties; cf. Müller, *AE.* pp. 193, 195, 220. 'Anāth is the name of a goddess, possibly the same as the Babylonian Antum or Anatum, consort of Anu, the god of heaven, and chief of the first triad of gods (Anu, Enlil, and Ea); cf. Jastrow in *DB.* v. p. 538 b, and *RBA.* i. p. 143. Further traces of the cult of this goddess in Canaan are preserved in the southern 'Anāthōth ('Anāta, two and a half miles north-north-east of Jerusalem), and in the proper name Shamgar ben-'Anāth, *ch.* 3³¹, 5⁶. She was worshipped in the fifth century B.C. by the Jewish garrison stationed at Elephantine on the southern border of Egypt. We meet with the compound name 'Anath-bethel, in which the deities 'Anath and Bethel (treated as a divine name) are probably equated; * and 'Anath-yahu also occurs. Probably she was 'the queen of heaven,' who, according to Jer. 44^{15 ff.}, was worshipped by the Jews who dwelt in Pathros, *i.e.* in Upper Egypt, where Elephantine was situated. Our information as to this Jewish garrison and its religious cultus is derived from recently discovered Aram. papyri which were edited in 1911 by Sachau under the title *Aramäische Papyrus und Ostraker aus einer jüdischen Militär-Kolonie zu Elephantine*. Cf. the present editor's article in *Church Quart. Rev.*, July 1912.

but they dwelt. \mathfrak{G}^{AL} , Σ^{h} καὶ κατόκησεν Ἰσραὴλ, very possibly the original text; cf. *note* on Josh. 13¹³, which belongs to the same narrative, in *Additional note*, p. 51.

34. *the Amorites.* The term is used, here and in *v.* 35, as a general name for the pre-Israelite inhabitants of Palestine, who elsewhere in this section (*vv.* 1.3.5.17.27.28.29.32.33; cf. also *vv.* 4.9 from the editor R^v) are described as Canaanites, in accordance with the regular practice of J. Such a use of 'Amorites,' on the contrary, is characteristic of E (cf. *note* on *v.* 1); and the difficulty of accounting for this deviation in usage on the part of J has led Meyer (*ZATW.* i. p. 126) to conclude that *vv.* 34³⁶ are the work of a later hand. So Stade, *GVI.* i. p. 138 *n.* Against this view Bu.'s arguments (*RS.* pp. 15 ff.) are cogent; notice

* Such a compound deity is seen in 'Ashtar-Chemosh, mentioned on the Moabite Stone, l. 17.

hill-country; for they did not suffer them to come down into

J's phrases in *v.*³⁵—'persisted in dwelling,' as in *v.*²⁷, Josh. 17¹², 'became labour-gangs,' as in *vv.*^{30,33}, Josh. 16¹⁰; and the fact that *v.*³⁴ clearly forms the lowest grade in a descending scale—in *vv.*²⁷⁻³⁰ the Cana'anites remain in the midst of Israel, and eventually become subject; in *vv.*³¹⁻³³ Asher and Naphtali dwell in the midst of the Cana'anites, the inference being that these latter retained the predominance, whether in power or in numbers (cf. *notes* on *vv.*^{32,33}); in *v.*³⁴ the 'Amorites' actually oust the Danites from their territory. It is probable that J originally wrote 'Cana'anites' in these two verses * (*Xavavaïos* is the reading of HP. 55 in *v.*³⁵), and that the substitution of 'Amorites' is due to a later hand, under the influence, it may be conjectured, of the textual corruption 'Amorites' for 'Edomites' in *v.*³⁶.

pressed the children of Dan, etc. Josh. 19⁴¹⁻⁴⁶ P assigns sixteen or seventeen (𐤁) cities to Dan, all of which, so far as they can be identified, lie in the Shephelah and vale-country to the east of the territories of Benjamin and northern Judah. Out of this list, however, Şor'ah, Eshta'ol, 'Eḡron, and Timnah are assigned by P to Judah in Josh. 15^{33,45,57}. In the narrative of Samson the Danites appear to be confined to a small district about Şor'ah and Eshta'ol, immediately contiguous to the hill-country, while Timnah is occupied by Philistines just as 'Eḡron is elsewhere. We may infer that the Amorites or Cana'anites who, as our narrative informs us, forced the Danites into the hills, were themselves suffering from the encroachments of the Philistines on the west. The Philistines, who entered Cana'an about the same time as, or a very short time before, the Israelite invasion under Joshua' (cf. *Introd.* pp. xcii ff.), must naturally have driven such of the original Cana'anite inhabitants of their territory as escaped extirpation (cf. Deut. 2²³) eastward towards the hill-country, where they would come into conflict with the Danites, who may have made their settlement prior to Joshua's invasion (cf. *Introd.* pp. cvi f.). Josh. 19⁴⁷, which originally formed part of J's narrative, informs us that finally a large portion of the tribe of Dan, if not the main portion, finding their district too narrow (read 𐤍𐤏𐤔𐤕 . . . 𐤍𐤏𐤔𐤕, 'was too strait for them,' in place of 𐤍𐤏𐤔𐤕 . . . 𐤍𐤏𐤔𐤕, R.V. 'went out beyond them'), migrated to the extreme north of Palestine, conquered the city of Leshem (or perhaps Lêshām: cf. *ch.* 18⁷ *note*), and established themselves in and about the city, which they renamed Dan. This migration is further related in *ch.* 18, where the conquered city is called Laish (*vv.*^{7,27}), and seems already to have taken place at the period to which the Song of Deborah relates (cf. *note* on *ch.* 5¹⁷). Thenceforward Dan figures in the common phrase 'from Dan to Beersheba' as the northernmost limit of Palestine.

* Meyer appears now to incline to this view: cf. *IN.* p. 525, *n*¹.

the Vale. 35. And the Amorites persisted in dwelling in Har-heres, in Aijalon, and in Sha'albim: yet the hand of the house

the Vale. Cf. v. ¹⁹ note.

35. *persisted in dwelling.* Cf. v. ²⁷ note.

Har-heres. The name means 'hill of the Sun,' and the fact that *heres* = *šemeš* has led Stu. and others after him to identify the site with Beth-shemesh ('house *or* temple of the Sun'), *i.e.* the modern 'Ain-šems ('spring of the Sun') which occupies an elevated site to the south of the Wādy Šarār (vale of Sorek), where it opens out upon the Shephelah. This identification is favoured by the fact that Beth-shemesh is mentioned with Sha'albim in 1 Kgs. 4⁹, and 'Ir-shemesh ('city of the Sun,' doubtless the same as Beth-shemesh) with Sha'albim and Aijalon in Josh. 19^{41,42}, just as Har-heres is in our passage.

Ⲭ^{AL} represents בְּהַר חֶרֶם by ἐν τῷ ὄρει τοῦ Μυ[ρ]σιωνῶνος (so S^h), Ⲭ^B by ἐν τῷ ὄρει τῷ ὀστρακώδει * (with the doublet ἐν τῷ Μυρσιωνῶνι), *i.e.*, in the first case חֶרֶם *h'adaš*, 'myrtle,' in the second חֶרֶשׁ *heres*, 'potsherd' in place of חֶרֶם *heres*; both variations being possibly attempts to get rid of the reference to the Sun with its idolatrous implications (so La.). Why such a reference should have been found more objectionable in the case of *heres* than in that of *šemeš* is not obvious: but it cannot be merely accidental that Timnath-heres of Judg. 2⁹ appears in || Josh. 24³⁰ and in Josh. 19⁵⁰ as Timnath-šeraḥ (סְרַח a transposition of the consonants of חֶרֶם). ‡

Aijalon. The identification of Rob. (*BR*³. ii. pp. 253 f., iii. pp. 144 f.) with the modern Yâlô, seven miles north-north-east of 'Ain-šems and in the south of the 'vale' into which the pass of Beth-ḥoron opens out ('the vale of Aijalon,' Josh. 10¹²) is universally accepted. The name 'Ayyālôn perhaps means 'haunt of deer' (ἄγυῖλ). How Ⲭ arrived at the rendering αἱ ἄρκοι is obscure, unless this may be regarded as a corruption of οἱ δόρκοι § (for the normal αἱ δορκάδες). Ⲭ, however,

* Cf. the gloss 'quod interpretatur testacco,' which appears in F.

‡ It must be considered doubtful whether 'ir *ha-heres*, 'city of destruction,' in Isa. 19¹⁸ Ⲭ is also to be considered as an alteration of an original 'ir *ha-heres*, 'city of the Sun,' *i.e.* Heliopolis. The phrase 'one shall be called' implies that one of the five cities mentioned is to be distinguished by a name which denotes its special character as representative of the worship of Yahweh; and this consideration weighs in favour of the view that the reading of Ⲭ, πόλις ἀσεδεκ, *i.e.* עִיר הַצֶּדֶק, 'city of righteousness' (as it were 'the Egyptian Jerusalem': cf. Isa. 1²⁶), is likely to be the original reading. Cf. Gray's acute discussion of the passage in *Isaiah* (ICC.) *ad loc.* This, however, may have been afterwards altered to 'ir *ha-heres* in allusion to Heliopolis, and the reading of Ⲭ, 'ir *ha-heres*, may represent a still later stage.

§ ὁ ἄρκος is found in Nicolaus of Damascus (B.C. 16), 46, 47; Dioscorides (*cir.* A.D. 60), 2, 85; Testamenta XII. Patriarcharum 1121 D: cf. Sophocles, *Greek Lexicon* s.v.

of Joseph prevailed, and they became labour-gangs. 36. And the border of the 'Edomites' was from the ascent of 'Akrabbim,

confines *δορκάς* to the Heb. *šēbī*, 'gazelle,' with which the 'ayyāl is often coupled, but never confused.

Sha'albim. Site unknown. The name appears in Josh. 19⁴² as Sha'alabbin, and probably means 'foxes': cf. Assy. *šēlibu*, Ar. *šalab*, and the rendering of *ἔαι ἀλώπεκες*. Apart from this place-name, the fact that the word was used in Heb. would be unknown to us, the ordinary Heb. word for 'fox' being *šū'āl*.

prevailed. Lit. 'became heavy.'

36. *the border of the Edomites.* Reading *הַאֲרָמִי* in place of *הַאֲמֹרִי* 'the Amorites' with Bu., Kit. (*HH.* i. p. 268), Buhl (*Edomiter*, p. 25), No., La., etc. The reading *τὸ ὄριον τοῦ Ἀμορραίου ὁ Ἰδουμαῖος* is found in *Ἑ^{AL}*, the group of MSS. cited by Mo. as *Ἑ^M*, Arm., Eth., *S^h* (with obelus before *ὁ* 1d.), and this is adopted by Hollenberg, *ZATW.* i. p. 103. But the writer's interest is centred upon the footing gained by the tribes of *Israel* in Palestine, and the frontier between Amorites and Edomites would scarcely concern him in this connexion; while such a use of the term 'Amorite' is contrary to the practice of J: cf. *v.*³⁴ *note*. It cannot be doubted that he is indicating the line along which the frontier of the southernmost tribe (Judah) marched with the frontier of *Edom*. *הַאֲמֹרִי* is an easy corruption of *הַאֲרָמִי*, and the versions as cited above present a doublet. A similar confusion occurs between *אֶדֶם* 'Edom' and *אֲרָם* 'Aram': 2 Sam. 8^{12,13} (cf. *v.*¹⁴, 1 Chr. 18^{11,12}, Ps. 60 *heading*), 2 Chr. 20², 2 Kgs. 16⁶.

from the ascent of 'Akrabbim. Usually identified with the Naḵb eṣ-Ṣafâ, a steep pass which runs up northward out of the Wâdy el-Fiḵrah: cf. *note* on Ṣephath *v.*¹⁷. An obvious objection to this identification lies in the fact that the frontier of Edom cannot be said to commence *from* this point, since this would leave out of account the twenty-five miles or so which intervene between the mouth of the Naḵb eṣ-Ṣafâ and the southern extremity of the Dead Sea at which the frontier is stated to begin in Num. 34³, Josh. 15² P. The same objection applies, in an enhanced degree, to the more westerly Naḵb el-Yemen, advocated by Trumbull (*Ḳadesh-Barnea*, p. 111). More probably we should find the ascent in the Wâdy el-Fiḵrah, which Trumbull (*op. cit.* pp. 94 f.) describes as 'a wâdy which ascends south-westerly from the 'Arabah, from a point not far south of the Dead Sea, and which separates Palestine proper from the 'Azâzimeh mountain tract, or Jebel Muḵrâh group. The northern wall of this wâdy is a bare and bold rampart of rock, forming a natural boundary.' Scorpions ('*akrabbim*') are said to abound in this district.

from the Crag and upwards.

from the Crag. Here we seem to have a second starting-point for the frontier-line between Judah and Edom, *i.e.* upon the most natural hypothesis, the other extremity of the frontier, farthest removed from the ascent of 'Akrabbim. The identification of *haš-šela'*, 'the Crag,' has caused difficulty. Clearly the reference cannot be to the city of Petra,* which was the capital of the Nabataeans from *cir.* B.C. 300 until the second century A.D.; for Petra lies some fifty miles a little east of due south of the southern end of the Dead Sea, among the mountains of Se'ir to the east of the 'Arabah; whereas the researches of Trumbull in connexion with his identification of the site of Kadesh-Barnea' at 'Ain-Kudês, nearly fifty miles south-south-west of Be'er-sheba' (generally accepted), have proved beyond a doubt that the territory of Edom must have extended for a considerable distance west of the 'Arabah: cf. Trumbull, *Kadesh-Barnea*, pp. 106 ff.; Buhl, *Edomiter*, pp. 23 ff. The course of the southern boundary of Judah is described in detail in Num. 34³⁻⁵, Josh. 15¹⁻⁴ P. From these passages we gather that its eastern extremity was the southern 'tongue' of the Salt Sea, and that thence it took its start (וַיֵּצֵא Josh. 15³) to the south of the ascent of 'Akrabbim (*i.e.* upon the identification of the ascent proposed above, upon the south side of the Wâdy el-Fikrah; the wâdy, or at least its north side, being claimed by Judah: cf. the analogy of Deut. 3³⁶, 'the middle of the wâdy being also a boundary'), made a turn (וַיִּסָּב Num. 34⁴) south of this ascent and passed on to Šin (an unknown site), and reached its extremity in this direction (וַיֵּצֵאָתָי Num. 34⁴) south of Kadesh-Barnea'. It then took a new start (וַיֵּצֵא Num. 34⁴), presumably to the west or north-west, and passing on by a number of unidentified sites, took a turn (וַיִּסָּב) to the 'Wâdy of Egypt,' *i.e.* the Wâdy el-Arîš, and found its end (וַיֵּצֵאָתָי) at the sea (the Mediterranean; Num. 34⁵). Here the line along which the frontier of Judah marched with that of Edom was, it must be assumed, in its course west-south-west from the Dead Sea along the Wâdy el-Fikrah, and then south-south-west to a point just south of Kadesh-Barnea'; and it is noteworthy that, in the narrative of Moses' embassy to the king of Edom (Num. 20¹⁴ ff. JE), he states that the Israelites are 'in Kadesh, a city in the extremity of thy border.' The natural inference

* Whether Šela' (without the article) in Isa. 16¹, 42¹¹ is the name of a city is very doubtful. Cheyne (*EB.* 4344) takes the word as a collective term, referring to the country as a whole—'the rocks.' In 2 Kgs. 14⁷, which relates Amaziah's defeat of the Edomites in the Valley of Salt and the capture of haš-Šela', the reference, if it stood alone, might most naturally be explained as referring to a city; but || 2 Chr. 25¹² takes haš-Šela' to be 'the crag' from the top of which the captured Edomites were cast headlong.

2. 1. And the Angel of Yahweh went up from Gilgal unto

is that *haš-šela'*, 'the Crag' of our passage, which formed one extremity of the frontier-line between Judah and Edom, is the same as *haš-šela'* 'the Crag' at or close to Kadesh, which tradition regarded as the crag which was smitten by Moses (Num. 20^{8,10,11} JEP). This conclusion, reached independently by the present editor, is also that of Buhl (*op. cit.* 25) and La.

Bu., Mo. regard the מ in מוהסלע as due to dittography of the preceding מ in עקרבִּים, and emend הפלע 'to Šela.' Mo. conjectures that the site of haš-Šela' may have been the modern eš-Šāfiyyeh, near the southern end of the Dead Sea; but his description of this as 'a bare and dazzling white sandstone promontory a thousand feet high' (derived from Buhl, *op. cit.* p. 20) is stated by La. to be incorrect; and moreover, if, as he supposes, the ascent of 'Akrabbim is the Nakb eš-Šafā, the boundary-line between the two points as specified extends for not more than twenty-five miles, and the description must be regarded as merely fragmentary.

and upwards. Upwards towards the first point of departure, the ascent of 'Akrabbim. As La. remarks, 'On indique deux points de départ, c'est-à-dire les deux extrémités de la frontière nord, et מעלה marque tout le reste d'une façon indéterminée.'

If the emendation 'to Šela' noticed above be adopted, the sense in which ומעלה is used is inexplicable, since Mo.'s rendering 'and beyond' cannot be justified. Bu. emends וְהָלַךְ in this sense.

2. 1-5. Upon the relation of these verses to the preceding narrative cf. *introductory note* to 1^{1ff}.

1. *the Angel of Yahweh.* The expression is characteristic of J. E's phrase being 'the Angel of God.' So used, it is always definite (not 'an angel of Y. '; still less a human messenger—*א* 'the prophet of Y. '), and denotes Yahweh Himself in manifestation to man. That this is so appears from a number of passages, both in J and E. Thus in *ch.* 6 'the Angel of Y.' of *vv.* 11, 12, 21, 22 ('the Angel of God, *v.* 20) = 'Yahweh' of *vv.* 14, 16, 23; in Ex. 3 'the Angel of Y.' of *v.* 2 = 'Yahweh' of *vv.* 4a, 7, and 'God' of E's narrative, *vv.* 4b, 6, a²; in Gen. 16 'the Angel of Y.' of *vv.* 7, 9, 10, who appears to Hagar speaks as Yahweh in the 1st person ('I will greatly multiply thy seed,' *v.* 10), and is referred to as 'Yahweh' in *v.* 13; and in E's narrative of Hagar in Gen. 21, 'the Angel of God,' *v.* 17, makes a similar promise in his own name, *v.* 18; in Gen. 22, 'the Angel of Y.' of *v.* 11 speaks as Yahweh in *v.* 12; in Gen. 31^{11,13}, 'the Angel of God' says 'I am the God of Bethel'; in Gen. 48^{15,16} E, Jacob's reference to 'the Angel who delivered me from all evil' is parallel to 'the God before whom my fathers walked,' etc. To these passages we may add the account of

the appearance of the Angel of Y. to Manoah in *ch.* 13, if it be assumed that R.V. is right in rendering in *v.*²² 'We must surely die, for we have seen God.' Possibly, however, *ʿēlōhīm* may here denote no more than 'a god' 'or divine being': cf. *note ad loc.* and *ch.* 6²².

There are, however, a few passages in which a distinction appears to be drawn between Yahweh and His Angel. So in Gen. 24, Yahweh sends His Angel before Abraham's servant *vv.*^{7,40} (yet in *vv.*^{27,48} the servant acknowledges that it is Yahweh who has led him); in Num. 22³¹ Yahweh uncovers Bala'am's eyes so that he sees the Angel of Y. In Ex. 23²³ Yahweh promises to send His Angel before Israel, who is described in 23²⁰ as 'an Angel' (מַלְאָךְ indef.; but, according to G, F, Sam., 'mine Angel' as in *v.*²³ H). Similarly 'mine Angel' of Ex. 32³⁴ is described as 'an Angel' in 33² (G 'mine Angel'), and appears to be something less than Yahweh's full manifestation; since Yahweh says in *v.*⁶ 'If I go up into the midst of thee for one moment, I shall consume thee,' and it is only as the result of importunate intercession on the part of Moses that Yahweh promises 'My Face shall go' (33¹⁴), *i.e.*, clearly, Yahweh Himself as distinct from His Angel.*

It must be observed, however, that both in Ex. 23 and 32, 33, the narrative largely consists of redactional matter which is relatively late as compared with J and E (cf. the analysis of CH. *ad loc.*); and probably at the period to which this redaction belongs, the tendency to modify reference to Yahweh's self-revelation to Israel by the introduction of an intermediary was already operative. It is not unlikely, indeed (as suggested by the alternation of 'the Angel of Y.' with 'Yahweh' in the passages first noticed), that the original conception of the Angel represents an early attempt (imperfectly carried out) to interpose such an intermediary, where the primitive narratives simply spoke of Yahweh Himself as appearing and holding direct intercourse with men. If this is so, we may trace a very early anticipation of the far more drastic introduction in the Targums of the 'Memra' ('Word') of Yahweh in passages where reference to Yahweh's direct communication with man was offensive to the taste of later times.

from Gilgal. Gilgal was the headquarters of Joshua' and the Israelites during the invasion of the hill-country, and before the tribes

* If Isa. 63⁹, as the passage stands in H, could be relied upon as original, it might be argued that the Angel of Yahweh has the same meaning as His Face, since 'the Angel of His Face' can scarcely mean anything but 'the Angel who is His Face,' *i.e.* His manifestation (so Davidson in *DB.* i. p. 94 b: 'One in whom His face (presence) is reflected and seen'). The rhythmical structure of the section in which this passage occurs, however, confirms the text of G οὐ πρέσβυς οὐδέ ἀγγελος, ἀλλ' αὐτὸς ἔσωσεν αὐτοὺς, *i.e.* לֹא צִיר וּמַלְאָךְ <פִּי> פָּנָיו הוֹשִׁיעָם, 'It was not an envoy or angel, but His Face that saved them.' Thus 'His Face' is contrasted with any other form of manifestation, such as that of an angel.

‘Bethel’]. R^p And he said, ‘<I visited you indeed, and> brought

had effected a settlement in the land : cf. Josh. 4¹⁹ P, 9⁶, 10^{6,7,9,15} JE, 10⁴³, 14⁶ R^p. The name is preserved in the modern Birket (‘pool’) Ġilġūliyyeh, three miles east-south-east of the ancient site of Jericho, and about the same distance west of the Jordan. Several other places in Palestine bore the same name : cf. *EB. s.v.* Gilgal, which in Heb. always has the definite article prefixed, ‘the Gilgal,’ doubtless denotes ‘circle’ (cf. Heb. *gal/gal*, ‘wheel’), and seems to refer to a circle of stones of a primitive religious character. The Gilgal of our passage was probably so named from the stones which tradition related to have been set up by Joshua at the first ‘lodging place’ (Josh. 4^{3,8} J) after the passage of the Jordan, which is stated (4¹⁹ P) to have been Gilgal. The explanation of Josh. 5⁹ J, which connects the name with the ‘rolling away’ of the reproach of uncircumcision (Heb. *gallôthî*, ‘I have rolled away,’ from root *gālāl*), is merely a play of words, such as is frequent in J’s narrative.

unto Bethel. **℣** ‘unto hab-Bochim’ : but (1) it is unnatural that the name should be given before the occasion which was its cause is related, and (2) **℣** preserves the name Bethel in the doublet ἐπὶ τὸν Κλαυθμῶνα καὶ ἐπὶ Βαιθηλ, and since there can have been no reason for the introduction of this latter if ἐπὶ τὸν K. (*i.e.* the reading of **℣**) already stood in the text, we may infer (with most moderns) that ‘unto Bethel’ was the reading of **℣**’s original. Adopting this reading, the passage comes into connexion with the narrative of *ch.* 1²³ *if.*, which relates the capture of Bethel by the house of Joseph. The Ark, which was the visible symbol of Yahweh’s presence, was carried up from Gilgal and found a resting-place at Bethel, where sacrifices were offered to Yahweh (*v.* 5^b). The Ark is still at Bethel in the narrative of *ch.* 20²⁷ : cf. also 20¹⁸, 21². Of the circumstances which led to its removal to the Ephraimite sanctuary of Shiloh, where it appears in 1 Sam. 3³, we have no information.

After ἐπὶ Βαιθηλ **℣** has the addition καὶ ἐπὶ τὸν οἶκον Ἰσραηλ. It is probable that this is merely an accidental doublet of בֵּית אֵל (so Mo.), the אֵל in an imperfectly legible MS. being mistaken for a contraction of יִשְׂרָאֵל such as יֵל. A similar process has taken place in Deut. 32⁸ **℣**, where לְמִסְפַּר בְּנֵי יִשְׂרָאֵל ‘according to the number of the children of Israel,’ appears in **℣** as κατὰ ἀριθμὸν ἀγγέλων θεοῦ (בְּנֵי אֵל), which probably represents the original text.* Bu., regarding the addition as genuine, would restore יִשְׂרָאֵל-בֵּית : and so Kit., La. If this is correct, it is likely, as Bu., No. suggest, that יִשְׂרָאֵל is an alteration

* If the passage pictures the ‘Sons of God,’ or subordinate angelic powers, as guardians of the foreign nations, the contrast offered by the following clause, ‘But Yahweh’s portion is his people,’ becomes more pointed and effective.

you up from Egypt, and brought you in unto the land which I

of an original יוֹסֵף, and the passage notes the fact that it was 'unto the house of Joseph' that the Angel of Yahweh went up, *i.e.* they had the charge of the sacred Ark.

I visited . . . up. Reading פָּקֹד פָּחַדְתִּי אֶתְכֶם וְאָעֹלָה אֶתְכֶם in place of אָעֹלָה אֶתְכֶם. The restoration is purely conjectural; but the use of the Heb. Imperfect in אָעֹלָה is inexplicable, since a future signification 'I will bring you up' is impossible; nor is it natural to explain the tense here as used pictorially to describe the event as still in progress—a usage which is not uncommon 'in the language of poetry and prophecy' (cf. Driver, *Tenses*, § 27), but is scarcely suited to a plain statement of fact such as the present. That an omission in the text was suspected by the Massoretes is perhaps indicated by the פסוקא or lacuna in פח before אָעֹלָה.* It is natural to suppose that ו consecutive originally stood before the Imperfect, in continuation of some event of which the statement has fallen out of the text of אָעֹלָה. This missing statement was supplied by Böttcher (*Neue exeget. Krit. Aehrenlese*) from Ex. 3¹⁶, Gen. 50²⁴, his restoration running פָּקֹד אָעֹלָה וְאָמַר אֶתְכֶם, 'I visited you indeed and said, "I will bring you up, etc."'; † and this suggestion has the advantage of accounting for the omission by homœoteuton, the scribe's eye passing from וְאָמַר to וְאָמַר. The text adopted above is that of Doorn. (who followed Böttcher in part), and is favoured by Bu., Oort. It makes, with its continuation, a statement in nearly identical terms of the fulfilment of the promise of Gen. 50²⁴ E: 'God will indeed visit you, and bring you up out of this land unto the land which he swore to Abraham, to Isaac, and to Jacob.' Cf. Ex. 13¹⁹ E.

Other suggestions have been made as to the text. Stu. simply inserts אָמַרְתִּי 'I said, "I will bring you up,"' and cites in favour of this v.³, 'And furthermore I said.' So also Ber. La. substitutes the Perf. for the Imperf., reading אָנֹכִי הָעֹלֵיתִי 'It was I who brought you up'—a cutting of the knot. Mo. thinks that, since the speech of the Angel is 'a cento of quotations and reminiscences,' it is possible that the author copied Ex. 3^{17a}, 'I will bring you up,' without correct-

* א^B supplies this lacuna by the words Τάδε λέγει Κύριος, and the same words are found in ξ^P, Ar. This, however, does not solve the difficulty of the Heb. tense. א^{AL}, ξ^h Κύριος ἀνεβίβασεν κ.τ.λ. turn the verbs into the 3rd person, but inconsistently preserve 1st person καὶ ἐγὼ εἶπα in v.³—a fact which tells against the originality of the preceding variations from אָעֹלָה.

† Böttcher offers the alternative אָמַר אֶתְכֶם וְאָמַרְתִּי בְכֶם 'I made choice of you and said, etc.'

sware unto your fathers; and I said, "I will never break my covenant with you. 2. And ye—ye shall not make a covenant with the inhabitants of this land; their altars ye shall break down." But ye have not hearkened to my voice: what have ye done? 3. And furthermore I said, "I will not drive them out from before you, but they shall be 'adversaries' to you, and their gods shall be a trap to you." 4. And it came to pass,

ing the tense: but we have no reason to suspect R^p of such gross carelessness.

the land which I sware unto your father. Cf. Ex. 33¹ JE, Num. 14²³ JE, 32¹¹ P, Deut. 1³⁵, 10¹¹, 31^{20.21.23}, 34⁴ JE, Josh. 1⁶ JE.

I will never break, etc. For the expression, cf. Lev. 26⁴⁴ H. The precise reference, however, is not to H, but to the covenant of Ex. 34²⁷ J: 'for after the tenor of these words I have made a covenant with thee and with Israel.' Cf. note following.

2. *And ye, etc.* A quotation from Ex. 34^{12.13a}: 'Take heed to thyself, lest thou make a covenant with the inhabitants of the land whither thou goest, lest it be for a snare in the midst of thee: but their altars ye shall break down.'

3. *And furthermore I said.* The reference is to Josh. 23¹³ R^p, Num. 33⁵⁵ P.

adversaries. Reading לְצָרִים with G, L, F, T, M^{mg}, Stu., Ber., Doorn., Mo. (in *SBOT.*), No., Kit., Ehr., in place of לְצָדִים. Cf. Num. 33^{55b} P וְצָרְרוּ אֹתְכֶם 'and they shall act as your adversaries.' According to the regular meaning of צָדִים in Heb., the statement of L can only be rendered 'they shall be to you *as sides*.' R.V. expands this into 'they shall be [as thorns] in your sides,' with marg. ref. to Num. 33⁵⁵. Such a sense cannot possibly be inherent in L as the text stands, though it is legitimate to suppose, with Mo. (*Comm.*), Bu., La., that לְצָדִים may be the remnant of an original reading בְּצַדֵּיכֶם לְצִנִּינִים as in Num. 33^{55a}: cf. Josh. 23¹³ R^p . . . וְהָיָה לְשִׁטְט בְּצַדֵּיכֶם 'and they shall be . . . as a scourge on your sides.' Delitzsch (*Prolegomena*, p. 75) compares צָדִים with Assyr. *ṣaddu*, 'net, snare, trap'; but this word is not elsewhere found in Heb., and the improbability of its occurrence here is enhanced by the fact that we expect to find in this passage (as elsewhere in the speech) a reference to an earlier warning. Grätz emends לְצִנִּינִים 'as thorns.'

a trap. The metaphor is that of bird-catching, and the Heb. term *môkēš*, lit. 'fowling instrument,' is commonly parallel to *palh*, *i.e.* probably a form of clap-net still employed in Palestine, and bearing

as the Angel of Yahweh spake these words unto all the children of Israel, that the people lifted up their voice, and wept. 5. So they called the name of that place Bochim. J And they sacrificed there to Yahweh.

the same name *faḥ* in Ar. : cf. Baldensperger in *PEF. Qy. St.* 1905, p. 38. BDB. and Driver on Am. 3⁵ explain *môḳēš* as the *lure* or *bait*, a rendering suggested by Am. 3⁵ מ (where the text, however, is almost certainly at fault*), but impossible in Job 40²¹, 'pierce his nose with *môḳēšîm*,' and in Ps. 64⁵ 'they tell of hiding *môḳēšîm* (a *bait* or *lure* is to be *displayed* not *hidden*), and inappropriate (to say the least) in Ps. 18⁵, where the *môḳēšē mārweṯh* (|| 'nooses of She'ol') are a terror and not an attraction. Since the root *yāḳaš* is evidently connected with *nāḳaš* 'strike,' the two verbs being variant trilaterals of the biliteral שך, it is probable that *môḳēš* denotes some form of trap in which the release of a spring or support caused the *striking* (knocking down or piercing) of the victim.‡

5. *Bochim*. Meaning 'weepers.' Stu. is probably correct in suggesting connexion with the 'Allôn bakhûth, 'oak of weeping,' which is stated in Gen. 35^b E to have been 'below Bethel.'

And they sacrificed, etc. Cf. note on Bethel, v.¹.

* As the text stands in מ, the passage runs—

Shall a bird fall into a *faḥ* upon the ground,
When there is no *môḳēš* for it?
Shall a *faḥ* spring up from the ground,
Without surely capturing?

It is impossible, however, to think that Amos could have written anything so awkward as the repeated *faḥ*; and as a matter of fact the word is omitted by א in the first clause: *εἰ πεσεῖται ὄρνειον ἐπὶ τὴν γῆν ἀνεῖ ἰξευτοῦ*. With this omission there disappears the necessity of explaining *môḳēš* as something in the nature of a lure.

‡ Dr. Driver has privately communicated the following note:—'As to *môḳēš*, the last words of my note in *Am.* p. 158 leave, I fear, an incorrect impression on the reader: but I have corrected it in *Exodus* (*Cambr. Bib.*) on 10⁷. It seems to me to be something like what we should call a *trigger*, with a bait upon it, which, whether touched by the bird, or pulled by the fowler, caused the trap, or net, to close upon the bird (cf. the illustration, *Am.* p. 157). The *môḳēš* certainly was destructive; but it seems certainly to have acted as a lure to entice to disaster (Ex. 10⁷, 23³³, 1 Sam. 18²¹); and it is this double aspect of it which suggests to me that it was the trigger properly, but often spoken of as including the bait upon it as well. Job. 40²¹ suggests that it had a sharp point—possibly it *struck* the bird with this: it was sufficient to be the means of catching a bird, but not to pierce the nostril of the hippopotamus. *nāḳaš* in Aram. is to *strike*; and hence the idea that it was a boomerang: cf. BDB. s.v. שך; but the view in this article seems to me doubtful. I see that BDB. under *môḳēš* do say "prop. a bait or lure"; but "prop." seems to me to be wrong; this is only a secondary idea.'

EXTERNAL EVIDENCE FOR THE USE OF THE TERMS
'CANA'AN' AND 'THE LAND OF THE AMORITE'(cf. *ch.* 1¹ *note*)

For the Egyptians Pe-kanan, *i.e.* 'the Cana'an,' denoted 'the entire west of Syria-Palestine' (Breasted, *AR.* iii. § 87), while the corresponding ethnographical term seems to have been extended beyond the low-lying maritime region to the population of Western Syria as a whole, as in the usage of J. The Egyptian term Amor was applied to the mountainous district of Lebanon.

The early Babylonians, as far back as the time of Sargon of Akkad (about the end of the fourth millennium B.C.: cf. *Introd.* p. lvi, *footnote* §), knew Syria and Palestine generally as Amurru.* In the T.A. Letters (*cir.* B.C. 1400) the term Kinahhî, or Kinaḥna, Kinaḥni (*i.e.* Cana'an), is applied to the Phoenician coast-land, while Amurru (the land of the Amorites) is not applied to Palestine as a whole, but denotes the 'Hinterland' of the northern Phoenicians, *i.e.* the mountainous district of the Lebanons, and also, as now appears from the cuneiform documents recently discovered at Boghaz Keui, the region still farther east, *i.e.* the Syrian desert and its surrounding districts, as far as the border of Babylonia: cf. Winckler in *MDOG.* xxxv., Dec. 1907, pp. 25 f. Possibly these facts may have a bearing on the distinction of usage between J and E; the former embodying the tradition of the south which lay outside the sphere of the Amorites, while the latter presents the tradition of the northern tribes: cf. Winckler, *GI.* i. pp. 52 ff. See further, on the extra-Biblical evidence as to the usage of the two terms, Jastrow in *EB.* 638 ff.; Meyer, *GA.*² i. §§ 354, 396; Böhl, *KH.* pp. 2 ff., 31 ff.; Müller, *AE.* pp. 177, 205 ff., 218 ff., 229 ff.; Weber in *Kn.* pp. 1132 ff.

ŞEDEK AS A DIVINE NAME (cf. *ch.* 1⁵ *note*)

The view that, in אֲדֹנִי שֶׁדֶק Adoni-şedek, מַלְכִּי שֶׁדֶק Malki-şedek, Şedek is the proper name of a Cana'anite deity is commonly held, but the evidence cannot be said to be conclusive. The following occurrences of Şidk or Şedek in compound proper names may be noticed: שִׁדְקִי-מֶלֶךְ Şidki-milk on a Phoenician coin, *cir.* B.C. 449-420, Cooke, *NSI.* p. 349; Sabaean שִׁדְקִי-עֵל Şidki-el, Hommel, *Süd-ar. Chrestom.* quoted by Cooke, *loc. cit.*; Aram. שִׁדְקִי-רַמְמָן Şidki-Rammân, *CIS.* ii. 73

* The name Amurru is commonly represented by the Sumerian MAR.TU, 'west land'; but evidence shows that from the earliest times MAR.TU was read and pronounced as Amurru among the Semitic Babylonians: cf. Böhl, *KH.* pp. 32, 33.

(letters דק not quite certain), cf. *EB*. 'Names,' § 36; Phoenician צדק־דכר Šidki-dakar, quoted by Baethgen, *Beiträge zur Sem. Religionsgesch.* p. 128 (without ref. to source); and the following instances from cuneiform literature quoted by Zimmern in *KAT*.³ p. 474: Šidkâ, king of Ashkelon, a contemporary of Hezekiah, *KB*. ii. 91; Rab-Šidki in T.A. Letters, Knudtzon, no. 170 (given as Ben-Šidki by Winckler, no. 125 in *KB*. v.); Šidki-ilu as the name of an eponym, B.C. 764, cf. Winckler, *KT*. p. 59; Šubi-šidki, Johns, *Deeds*, no. 6, rev. 3. From these we can scarcely separate the Israelite צדקיהו Šidki-Yahu or צדקיה Šidki-Yah.

The conclusion that Šedek is the proper name of a deity is based upon a statement of Philo of Byblos that the Phoenicians had a deity named Συδικ. This writer (quoted by Eusebius, *Præp. Evan.* i. 10), in the course of a lengthy account of the Phoenician Pantheon, based upon information derived professedly from Sanchuniaton, remarks that 'Ἀπὸ τούτων [Ἀμυνος καὶ Μαγος] γενέσθαι Μισωρ καὶ Συδικ, τουτέστιν εὐλυτον καὶ δίκαιον. Οὗτοι τὴν τοῦ ἀλὸς χρῆσιν εἴβρον. Here Συδικ and Μισωρ are shown to correspond to the Heb. words *šedek* 'justice,' and *mêšâr* 'uprightness.' The statement that these deities 'discovered the use of salt'* seems to indicate no very profound acquaintance with their origin and characteristics; and definite information thus failing us, it is natural to suspect the influence of Babylonian thought, in view of the fact that for the later Babylonians *kettu* ‡ 'justice,' and *mêšâru* 'uprightness' appear as the 'sons' of Šamaš the Sun-god (cf. *KAT*.³ pp. 224 *n*¹, 370), a theory which would seem to imply hardly more than that these attributes were characteristic of Šamaš, or at most that they might be venerated in connexion with his worship: cf. the manner in which Hammurabi pictures himself as deriving his legal code, the embodiment of Justice, directly from Šamaš. Not very dissimilar are certain statements in the Psalms with regard to Yahweh: 'Righteousness (*or* Justice, *šedek*) shall walk before him,' 85¹³; 'Righteousness (*šedek*) and Judgment are the foundation of thy throne,' 89¹⁴, cf. 97²; 'Righteousness (*šedek*) and Peace have kissed,' 85¹⁰.

But, granted the existence of a W. Semitic deity Šedek § = Bab. Kettu, the inference by no means follows that, where Šedek occurs

* Possibly we may trace connexion with the ברית מלח 'covenant of salt' (Num. 18¹⁹ P, 2 Chr. 13⁵), in which *šedek* 'righteousness,' and *mêšâr* 'uprightness' would naturally be involved. Cf. La., *ÉRS*.² p. 421. Upon the ceremonial use of salt in covenants, cf. Gray's note on Numbers *loc. cit.*

‡ *Kettu* for *kentu*, √ *kānu* = Heb. כון. *Kettu* is the Bab. equivalent of the W. Semitic *šedek*.

§ צדק, *i.e.* Šedek or Šiddik, occurs as a masc. proper name in Sabæan (cf. *CIS*. iv. no. 287, ll. 2, 11, 15, etc.); and this is perhaps to be explained as contracted from צדקאל, a form which we have noticed above as occurring in

in compound proper names either predicatively or in the genitival relation, it must refer to this deity. 'Justice' or 'Righteousness' cannot have been pictured as the exclusive possession of the son of Šamaš, and it is reasonable to assume that the attribute may have been predicated of other deities. Thus few would dispute that Šidki-Yahu means, not 'Yahu is the god Šedeḫ,' but simply 'Yahu is righteousness' (*i.e.* righteous), the name corresponding in form precisely to Hizki-Yahu, 'Uzzi-Yahu, 'Yahu is strength' (strong). Analogously it may be inferred that Šidki-Rammân denotes 'Rammân is righteousness.' It would seem to follow, therefore, that where Šedeḫ is coupled, not with a proper name, but with an honorific title such as *'adoni, melekḫ,* or *'el,* it is at least as probable that the meaning intended is 'the (unnamed) Lord, King, or God is righteous' as that we are to find reference to (the god) Šedeḫ described as Lord, etc.

THE MEANING OF THE NAME KIRIATH-ARBA'

(cf. *ch.* I ¹⁰ *note*)

The evidence which goes to prove that in Kiriath-arba', *i.e.* 'City of Four,' 'Four' is a divine title is as follows. The name naturally suggests comparison of the Assyrian Arbela between the Upper and the Lower Zab. The name of this city is written in cuneiform (*ālu*) *Arba' ilu*, '(city) Number Four God.' Here it is beyond doubt that the numeral Four is employed as a divine name or title. The inference that Kiriath-arba' is to be explained similarly is strengthened by comparison of the place-name בֵּית אַרְבֵּאל 'Beth-Arbel' of Hos. 10¹¹ (perhaps situated near Pella on the east of Jordan), where we find the name Arba-ilu apparently taken directly from the Assyrian or Babylonian, since the ע of the Hebrew אַרְבַּע is wanting.* Winckler (*GI.* ii. pp. 39 ff.), who adopts this explanation of Kiriath-arba', further explains Be'er-sheba' in like manner as 'Well of Number Seven God.' Thus fresh light is thrown upon the subject. A god *Sibitti*, *i.e.* 'Number Seven,' was known to the Babylonians at the period of the First Dynasty. Thus, for example, we find such names

Sabaeen. It is worthy of observation that, in the inscription cited, the name צֶדֶק stands in close conjunction with מְרֹאֲשֵׁמִים, *i.e.* according to Derenbourg, 'Vir Solis' (Ar. *أمرؤ الشمس Imru-eš-šems*), to be explained as 'vir Solis cultor': cf. discussion in *CIS. loc. cit.*

* Cf. בֵּל, Isa. 46¹, Jer. 50², 51⁴⁴, taken directly from Bab. *bēlu*=*Ararn*.
בְּעֵל, Heb. בַּעַל.

as Warad (ilu) Sibittim, *i.e.* 'servant of (God) Sibitti': Thureau-Dangin, *Lettres et Contrats de l'époque de la première dynastie Babylonienne*, p. 50: cf. further references in Jastrow, *RBA.* i. p. 173.

The meaning of Four and Seven as divine titles is elucidated by the well-known fact that the name of Sin, the Moon-god, is commonly written in cuneiform as '(God) Number Thirty,' thirty days being the conventional length of the lunar month. It is probable that, as Winckler thinks (*op. cit.* p. 48), Four and Seven represent different phases of the Moon-god, the former the four phases of the moon, the latter the seven-day week as a lunar quarter. Evidence that the worship of *Sibitti* extended to the West is to be found in the fact that, in the list of kings of the West whom Tiglath-Pileser IV. mentions as paying tribute, the king of Gebal bears the name Sibittibi'li, *i.e.* 'Number Seven is lord': cf. Rost, *Tiglath-Pileser*, p. 26. The evidence here brought together is based upon the present editor's note in *JTS.* xii. pp. 118 f.

THE CONQUEST OF THE NEGEB (cf. *ch.* 1^{16,17} notes)

The account of the conquest of 'Arad in the Negeb which is given in Judg. 1^{16,17} cannot be considered apart from the very similar account which is found in Num. 21¹⁻³ (J). This latter narrative states that, during the period of Israel's sojourn in the wilderness, the king of 'Arad advanced against them, apparently because they were encroaching upon his territory, fought against them, and took some of them prisoners. Israel thereupon vowed a vow that, if Yahweh would deliver up the Canaanites into their hand, they would place their cities under a ban (*hérem*), and utterly destroy every inhabitant. Success attended their arms; the vow was carried out; and the name of the district was thenceforth known as Hormah, a name in which there is an assumed connexion with *hérem*.

This narrative, which implies a northward advance of Israel from Kadesh-Barnea into the Negeb, is at variance with the preceding narrative (Num. 20¹⁴⁻²¹ JE), which apparently pictures the whole of the Israelites as turning southwards from Kadesh, in order to compass and avoid the land of Edom. It is also difficult to understand why an immediate settlement in the conquered territory was not effected by at least a portion of the Israelites, when the whole of the Canaanites inhabiting it had been put to the sword.

The author of the introduction to Deut., who apparently bases his information upon E, gives, in 1⁴¹⁻⁴⁶, an account of a disorganized attempt made by the Israelites to conquer the Negeb, after the failure of the mission of the spies, and against the express command of Moses. This was repulsed by 'the Amorite who inhabited that hill-country,' Israel being put to the rout, and beaten down 'in Se'ir as far as Hormah.' This narrative corresponds with Num. 14⁴⁰⁻⁴⁵, which apparently combines elements from J as well as from E, and

in which the foe appears not as 'the Amorite,' but as 'the 'Amalekite and the Cana'anite' (*v.* 45¹¹). No mention is made in Deut. of Israel's subsequent success, and their extirpation of the inhabitants of the district; and we are probably correct in inferring that these details were not contained in the E source.

The question is further complicated by the account of the conquest of 'Arad which occurs in Judg. 1^{16,17}. Here it is the tribes of Judah and Sime'on, together with the Kenites, who are related to have effected the conquest, moving southwards from the City of Palms (*i.e.* Jericho) subsequently to the passage of the Jordan under Joshua'. As in the narrative of Num., however, the origin of the name Hormah is explained by the fact that the Cana'anites inhabiting a city (previously named Sephath) were smitten, and the city placed under the ban and utterly destroyed.

The narratives of Num. 21 and Judg. are obviously parallel, and cannot, as they stand, be reconciled. It is easy to supply a reason for the occurrence of the narrative in Judg. as a duplicate to that in Num., viz., the view that the conquest of Cana'an under Joshua' was the first settlement in the land of any of the tribes of Israel: but, if the narrative of Judg. be taken to be correct in its present position, it is not easy to divine why the narrative of Num. should have come in at that particular place.

Adopting, then, the view that the conquest of 'Arad in the Negeb took place through a tribal movement northward from the neighbourhood of Qadesh, the inference becomes plausible that this movement was effected, as related in Judg., by the tribes of Judah and Sime'on in alliance with the Kenites. It is a well-known fact that the tribe of Judah consisted of mixed elements: the genealogy of 1 Chr. 2 includes among the descendants of Judah the North Arabian tribes of the Kenites and Jeraḥme'elites, and the clan of Caleb which was of Kenizzite, *i.e.* of Edomite, origin (*cf.* Gen. 36¹¹). Whether or not these clans originally formed an integral part of the tribe of Judah, it is clear that so early as the days of David they were regarded as standing in a very intimate relation to the tribe. In 1 Sam. 27^{7 ff.}, which relates David's stay as an outlaw with Achish king of Gath, we read that David made pretence to Achish that his occasional raids were directed 'against the Negeb of Judah, and against the Negeb of the Jeraḥme'elites, and against the Negeb of the Kenites'; and Achish remarks to himself with satisfaction, 'He hath made *his people Israel* utterly to abhor him; therefore he shall be my servant for ever.' Again, in 1 Sam. 30^{26,31}, David sends presents 'of the spoil of the enemies of Yahweh' to the Judaeans of the Negeb, including the Jeraḥme'elites and the Kenites.

If, then, clans which originally inhabited the region south of the Negeb are subsequently found occupying the Negeb and forming part of the tribe of Judah, what is more probable than that this change of locality was effected through conquests gained in the

Negeb in a movement directly northwards, as is suggested by the narrative of Num. 21?

We seem, in fact, to be upon the track of a Calibbite tradition, embodied in the Judaeen document J, which originally narrated the way in which this northward movement was effected by the clan of Caleb, and probably other kindred clans. It may be conjectured that this tradition lies at the bottom of the older (JE) narrative of the spies which is combined with the P narrative in Num. 13 and 14.* In this older narrative (in contrast to that of P) it is the Negeb only which is explored; Caleb is the only spy who is mentioned by name; and it is Caleb only who maintains, against the opinion of the other spies, that the conquest of the district is quite a feasible undertaking, in spite of the race of giants—the sons of 'Anak—inhabiting it:—‘We can easily go up and possess it, for we are well able to overcome it’ (Num. 13³⁰).

As a matter of fact, the conquest of these sons or clans of 'Anak and their cities is directly ascribed to Caleb in Josh. 15¹⁴⁻¹⁹ = Judg. 1^{20,10b} (in part).¹¹⁻¹⁵ from the narrative of J. Is it not, then, at least a plausible theory that the original Calibbite story related that Caleb, after first spying out the Negeb, then proceeded to go up and conquer it?

It seems probable that the present form of the combined JE narrative of the spies, which makes the project of conquest fail in spite of Caleb's protests, is due to the theory that the conquest of any part of Canaan did not take place until the country as a whole was invaded by a combined movement from the east made by the whole of the tribes under the leadership of Joshua. This theory, as we have seen, accounts for the present form of Judg. 1^{16,17}, which makes the conquest of the Negeb to have been effected through a movement which took its start from Jericho.

It is the Judaeen document J which embodies the Calibbite tradition in Num. 21: cf. ‘the Canaanite’ in *v.*¹. The Ephraimite E, on the other hand (which is naturally the principal repository of the Joshua-tradition), from which is drawn the narrative which is found in Deut. 1⁴¹⁻⁴⁶ (cf. ‘the Amorite’ in *v.*⁴¹), while mentioning the defeat of the Israelites, knows nothing, or at any rate will have nothing, of the subsequent victory as narrated by J.

Our inference, then, is that clans which went to form the tribe of Judah (including North Arabian clans then or subsequently embodied in the tribe) advanced northward from Qadesh-Barnea; and, in combination with the remnant of the tribe of Simeon (which, after a disastrous attempt to effect a settlement in Central Palestine, appears to have moved southward: cf. *note* on 1³), conquered the territory of 'Arad, and settled down in it, afterwards advancing their conquests

* In Gray's *Numbers* (ICC.), pp. 130ff., the two narratives of the spies are arranged in parallel columns, and will be found each to read nearly continuously.

still farther north, into the country which is known to us later on as the hill-country of Judah.

If this inference be true, it will help to explain to us a very striking fact in the later history, viz. the isolation of Judah and Sime'on from the rest of the tribes. From the Song of Deborah, which celebrates the great victory over the forces of Šišera, it is clear that an organized attempt was made on that occasion to unite the tribes of Israel against the Canaanites. Ten tribes, including the tribes from the eastern side of Jordan, are mentioned, either for praise as having taken part in the contest, or for blame as having held aloof: Judah and Sime'on alone remain unnoticed. We must infer, therefore, that at that period they were so far isolated from the rest of the tribes that they were not even expected to take part in the common interests of Israel, and therefore received no call to arms.

This single instance is in itself so striking, that we need do no more than allude briefly in passing to the fierce rivalry which is pictured as existing between the men of Israel and the men of Judah in the days of David (2 Sam. 19⁴¹⁻⁴³), and to the fact that the superficial union between Judah and the rest of the tribes which was effected under Saul, David, and Solomon, was readily dissolved at the commencement of Rehobo'am's reign.

THE ORIGINAL FORM OF J'S ACCOUNT OF THE SETTLEMENT OF THE TRIBES OF ISRAEL IN CANA'AN

Bu. has displayed great skill and critical insight in reconstructing J's narrative in the form in which it may be supposed originally to have stood: cf. *RS.* pp. 84 ff. The following reconstruction is indebted to him throughout, but exhibits in detail such variations as have been adopted in the notes on the text, with citation of Bu.'s readings in the footnotes.

Judg. 1 ^{1aβb}	And the children of Israel enquired of Yahweh,
1 ²	saying, 'Who shall go up for us first against the
1 ³	Canaanites to fight against them?' And Yahweh
	said, 'Judah shall go up: behold, I have given the
	land into his hand.' And Judah said to Sime'on his
	brother, 'Go up with me into my lot, that we may
	fight with the Canaanites, and I also will go up with
1 ⁵	thee into thy lot.' So Sime'on went with him. And
{ emended after	they came upon Adoni-šedeḡ, ^a the king of Jerusalem,
Josh. 10 ¹	and they fought against him, and smote the Canaan-
1 ⁶	ites and the Perizzites. And Adoni-šedeḡ ^a fled; and
	they pursued after him, and captured him, and cut
1 ⁷	off his thumbs and his great toes. And Adoni-šedeḡ ^a

^a Bu. 'Adoni-bezeḡ.'

said, 'Seventy kings, with their thumbs and their great toes cut off, used to pick up food under my table: as I did, so hath God required me.' And they brought him to Jerusalem, and he died there. And Yahweh was with Judah, and he gained possession of the hill-country; for he was not able to dispossess the inhabitants of the Vale, because they had chariots of iron. But the Jebusites dwelling in Jerusalem the children of Judah could not dispossess; and the Jebusites dwelt with the children of Judah in Jerusalem, unto this day.

I¹⁹

{ I²¹ after
Josh. 15⁶³

{ I^{20,10b8}
|| Josh. 15¹⁴

{ I¹¹ after
Josh. 15¹⁵

{ I¹²
|| Josh. 15¹⁶

{ I¹³
|| Josh. 15¹⁷

{ I¹⁴
|| Josh. 15¹⁸

{ I¹⁵
|| Josh. 15¹⁹

I¹⁶I³⁶I¹⁷I²¹I^{23a}

^b And they gave Hebron to Caleb, as Moses had bidden^b: and he dispossessed from thence the three sons of 'Anak, Sheshai, and Ahiman, and Talmai. And he went up thence against the inhabitants of Debir. (Now the name of Debir formerly was Kiriath-šepher.) And Caleb said, 'He that smiteth Kiriath-šepher, and taketh it, I will give him 'Achšah my daughter as wife.' And 'Othniel, the son of Kenaz, the brother of Caleb, took it: and he gave him 'Achšah his daughter as wife. And when she came, he incited her to ask of her father a field: and she lighted down from off the ass; and Caleb said to her, 'What wouldest thou?' And she said to him, 'Give me a present; for thou hast set me in the land of the Negeb; so give me springs of water.' And Caleb gave her the upper spring and the lower spring.

And Hobab the Kenite, the father-in-law of Moses, went up from the City of Palms with the children of Judah into the wilderness of Judah which is 'in the Negeb of 'Arad'; and he went and dwelt with the Amalekites. And the border of the Edomites was from the ascent of 'Akrabbim,^d from the Crag and upwards.^d

And Judah went with Simeon his brother, and smote the Canaanites who inhabited Šephath, and devoted it to destruction. And the name of the city was called Hormah.

And the house of Joseph also went up to 'Ai: and Joshua^e was with them. . . .^e And the house of Joseph made a reconnaissance at Bethel. (Now the

^{b-b} Bu. 'And to Caleb, the son of Kenaz, there was given an inheritance among the children of Judah, namely Hebron.'

^{c-c} Bu. 'at the descent of 'Arad.'

^{d-d} Bu. 'to Petra and beyond.'

^e Here Bu. is probably right in supposing that the document originally related the conquest of 'Ai, as in Josh. 8.

1²⁴ name of the city formerly was Luz.) And the watchers saw a man coming out of the city,^f and they laid hold on him,^f and said to him, 'Show us, we pray thee, the way to enter the city, and we will deal kindly with thee.' So he showed them the way to enter the city, and they smote the city at the edge of the sword; but the man and all his clan they let go.

1²⁵

1²⁶ And the man went to the land of the Hittites, and built a city, and called its name Luz: that is its name unto this day.

2^{1a} ^g And the Angel of Yahweh went up from Gilgal unto Bethel: and they sacrificed there to Yahweh.^g

2^{5b}

{ 1²⁷ And Manasseh could not dispossess Beth-she'an and its dependencies, and Ta'anach and its dependencies, and the inhabitants of Ible'am and its dependencies, and the inhabitants of Megiddo and its dependencies, ^h and the inhabitants of Dor and its dependencies ^h; but the Canaanites persisted in dwelling in this land.

{ 1²⁸ And when Israel was waxen strong, they impressed the Canaanites for labour-gangs, and did not dispossess them at all.

{ 1²⁹ And Ephraim did not dispossess the Canaanites who dwelt in Gezer: but the Canaanites dwelt in the midst of Ephraim ^j unto this day,^j and became toiling labour-gangs.

{ || Josh. 17^{11,12}

{ || Josh. 17¹³

{ 1²⁹ And Ephraim did not dispossess the Canaanites who dwelt in Gezer: but the Canaanites dwelt in the midst of Ephraim ^j unto this day,^j and became toiling labour-gangs.

{ || Josh. 16¹⁰

Josh. 17¹⁴ ^k And the house of Joseph spake unto Joshua', saying, 'Why hast thou given me but one lot and one territory for an inheritance, seeing that I am

^{f-f} Not adopted by Bu. The passage is supplied from G: cf. *note ad loc.*

^{g-g} This is placed by Bu. at the close of the narrative, after mention of the settlement of the other tribes.

^{h-h} Bu. follows the order of H. For the reasons for the transposition, cf. *note ad loc.*

^{j-j} Omitted by Bu.

^k The fact that Josh. 17¹⁴⁻¹⁸ was originally derived from the J narrative is clearly shown by the phraseology: cf. Bu. *R.S.* p. 32. That the subject in v. 14^a should be 'the house of Joseph' and not 'the children of Joseph' appears from v. 17 and from the singulars יָּ 'to me,' וָּאִנִּי 'and I,' etc., in v. 14^b and elsewhere. It is impossible, however, to derive any consistent sense from the section as it stands in H. The house of Joseph complain that they have only received *one* lot, which is insufficient for their numbers, the extent of this lot being further diminished owing to the fact that part of it falls in the vale, where the Canaanites are too strong to be ousted by them owing to their possession of iron chariots (cf. Judg. 1¹⁹, 4³). Joshua', in acknowledging the justice of their protest, recommends them to 'go up' into the forest and cut down for themselves (v. 15), this forest being further described as הָרִי 'hill-country' in v. 18. That the reference, however, cannot be to any part of the hill-country west of Jordan appears to be clear. The situation presupposed is that the west Jordan

- Josh. 17¹⁶ a great people, forasmuch as hitherto Yahweh hath blessed me? The hill-country doth not suffice for me: and all the Cana'anites that dwell in the land of the vale have chariots of iron, both they that are in Beth-she'an and its dependencies, and they that are in the vale of Jezre'el.' And Joshua' said unto the house of Jo'seph, 'Thou art a great people, and hast great power: thou shalt not have one lot only. For the hill-country of Gile'ad shall be thine: get thee up into the forest and cut down for thyself there; since the hill-country of Ephraim is too narrow for thee.'
- Josh. 17^{18a}
Josh. 17^{18aβb}
- Num. 32³⁹ 'Then Machir the son of Manasseh went to Gile'ad, and took it,¹ and dispossessed the Amorites that were

country has already been allotted among the tribes, and the house of Jo'seph have not found the difficulties of gaining a footing in the portion of hill-country (in contrast to the vale) allotted to them to be insuperable. Thus Bu. suggests, with great plausibility, that the hill-country which Joshua' invites them to conquer is the hill-country of *Gile'ad*, which is appropriately described as יַעַר forest or jungle-land: cf. 2 Sam. 18^{6.8.17}. As the result of Joshua's suggestion there follows the conquest of districts in Gile'ad by different clans of Manasseh, as described in the passages from Num. given above, which may plausibly be taken as the continuation of our narrative. If Bu.'s view of the situation be correct, 'Gile'ad' in Josh. 17^{18a} may be supposed to have been excised by the priestly redactor of this section of Josh., to whom is due the general dislocation of the J passage in question. Marks of his hand are to be seen in the plurals v. 14, 'And the children of Jo'seph spake' (an alteration, noticed above), v. 16a, 'And the children of Jo'seph said' (addition necessitated by the dislocation of v. 15), לָנוּ 'to us' (alteration of לִי 'to me'), in the explanatory 'to Ephraim and to Manasseh,' v. 17, and in the P phrase הִצְאָתָיו 'its goings out,' v. 18a. The main part of this final verse, with its five times repeated כִּי and its apparent ascription of iron chariots to the Cana'anites inhabiting the hill-country, appears in its present form to be due to this editor as a weak summary of *his* view of the situation, viz. that what is contemplated is a further extended conquest west of Jordan. The words of v. 15 בארץ הפרזים והרפאים 'in the land of the Perizzites and the Rephaim,' which are wanting in \mathfrak{C} , are probably merely a corrupt doublet of the following כִּי אֵין לָךְ הָר אֶפְרַיִם 'since the hill-country of Ephraim is too narrow for thee.'

Bu., to whom is due the merit of this reconstruction, varies in the following details. In v. 16a he retains לָנוּ 'to us' of \mathfrak{B} , and reconstructs v. 16b by the help of v. 18b:—'And the Cana'anites which dwell in the vale I cannot dispossess, since they are too strong for me. For they have chariots of iron, both they that are in Beth-she'an,' etc. After v. 15b he adds the words of v. 18a, 'and its goings out shall be thine.'

וַיִּלְכְּדוּ בְנֵי מַכִּיר . . . וַיִּלְכְּדוּ \mathfrak{C} , however, καὶ ἐπορεύθη υἱὸς Μαχὲρ . . . καὶ ἔλαβεν αὐτήν, points to the text adopted above, which is favoured by the singular verb וַיִּנָּחֵם in \mathfrak{B} , and by the parallelism of vv. 41.42.

Num. 32⁴¹ therein. And Ja'ir the son of Manasseh went and took the tent-villages thereof, and called them the tent-villages of Ja'ir. And Nobah went and took Kenath and its dependencies, and called it Nobah after his own name. But the children of Israel^m did not dispossess the Geshurites and the Ma'acathites; but Geshur and Ma'acath dwelt in the midst of Israel, unto this day.

I 30 Zebulun did not dispossess the inhabitants of Kithron, nor the inhabitants of Nahalol; but the Canaanites dwelt in the midst of them, and became labour-gangs.

I 31 Asher did not dispossess the inhabitants of 'Acco, nor the inhabitants of Sidon, nor Mahaleb,^o nor Achzib, nor Aphik, nor Rehob: but the Asherites dwelt in the midst of the Canaanites inhabiting the land; for they did not dispossess them.

I 33 Naphtali did not dispossess the inhabitants of Beth-shemesh, nor the inhabitants of Beth-anath; but they dwelt in the midst of the Canaanites inhabiting the land; and the inhabitants of Beth-shemesh and Beth-anath became labour-gangs for them.

I 34 And the Canaanitesⁿ pressed the children of Dan into the hill-country; for they did not suffer them to come down into the vale. ^q So the border of the children of Dan was too strait for them^q; and the children of Dan went up, and fought with Lesham, and took it, and smote it at the edge of the sword, and took possession of it, and dwelt therein; and they called Lesham, Dan, after the name of Dan their father. But the Canaanites^p persisted in dwelling in Har-heres, in Aijalon, and in Sha'albim:

^m Possibly the original may here have read 'the children of Manasseh.' The reading 'in the midst of Israel' (with reference to the clans of Manasseh) in the latter half of the verse is favoured by the analogy of 6L in Judg. 133 which reads, with reference to Naphtali, καὶ κατοίκησεν Ἰσραηλ, in place of 𐤁 𐤍𐤔𐤁 simply. Cf. RS. p. 39.

ⁿ Here Bu. supposes a lacuna for the account of the settlements of Benjamin and then Issachar.

^o Bu. reads Ahlab, and adds Helbah after Achzib, as in 𐤁.

^p Bu. 'Amorites,' as in 𐤁.

^{q-q} Reading 𐤍𐤔𐤁, in place of 𐤁 𐤍𐤔𐤁, Bu., following 6, reads 𐤍𐤔𐤁 𐤍𐤔𐤁, following 6, reads 𐤍𐤔𐤁 𐤍𐤔𐤁.

𐤍𐤔𐤁 𐤍𐤔𐤁 'so they made the border of their inheritance too strait for them.'

yet the hand of the house of Joseph prevailed,^r and they became labour-gangs.

2^{23a}

3^{2a}

3^{5a}

3⁶

So Yahweh left these nations, not expelling them quickly, only on account of the generations of the children of Israel, to teach them war.^s And the children of Israel dwelt in the midst of the Canaanites; and they took their daughters to themselves for wives, and their own daughters they gave to their sons; and they served their gods.

2. 6-3. 6. *Introduction to the History of the Judges.*

This section forms the introduction to the Book of Judges as it left the hand of the main editor (R^{E2}): cf. *Introd.* p. xxxv. That it is not homogeneous is clear even from a cursory examination; but the analysis is difficult, and scholars are not agreed upon points of detail.

The narrative of the Book of Joshua¹ is resumed in 2⁶⁻⁹ by repetition of Josh. 24²⁸⁻³¹. The two passages are identical except for small verbal variations, and for the different order in which the verse occurs which states that the people (Josh. 'Israel') served Yahweh during the lifetime of Joshua¹ and the elders who survived him (in Josh. 24³¹ after the mention of Joshua's death, in Judg. 2⁷ before it). Critics are agreed in assigning this section to E, with the exception of Judg. 2⁷ = Josh. 24³¹, which is regarded as editorial. That this verse should belong to E is demanded, however, by the E narrative in Josh. 24¹⁶⁻²⁴: cf. especially *v. 18b, 19, 21, 22, 24*. If, according to E, the people, in response to Joshua's last appeal, pledged themselves to serve Yahweh, the narrative of E (upon the assumption that it went on to relate the history of the Judges: cf. *Introd.* p. xxxviii) *must* have stated that this promise was carried out up to a certain point. Such a statement is found in Judg. 2⁷.

The same conclusion as to the origin of this verse appears to be demanded by what follows. Judg. 2¹⁰, which forms the natural continuation of *v. 9* in the E narrative, certainly presupposes *v. 7*: cf. especially *v. 7*, 'who had seen (Josh. 'known') all the great work of Yahweh which he had wrought for Israel,' with *v. 10*, 'who knew not Yahweh nor yet the work which he had wrought for Israel.' To assign *v. 10* as well as *v. 7* to the main editor (whether we call him R^D, or, according to our theory, R^{E2}) seems to be forbidden by the fact that *v. 10* is a necessary link in the introduction to E's narrative of the Judges, which, as appears below, can be traced in the verses which follow, and which may be expected to read continuously, since there is no reason to suppose that R^{E2} felt the need of excising any portion of it. Moreover, if *v. 7* be editorial and *not* part of E, it is not clear

^r Bu. adds 'against the Amorites.'

^s Here Bu. adds the list of nations given in 3³, which we assign to R^D.

how it came to be incorporated both in Josh. and Judg.; for in each case the editor was presumably drawing directly from the pre-Deuteronomic work of R^{JE}.*

The small variations between the two recensions of these verses may be dismissed in a few words. It is clear from the narrative of Josh. 24 that v.²⁸ was originally intended by E to round off and conclude the account of Joshua's last words which precedes; and for this purpose the statement that 'Joshua' dismissed the people every man to his inheritance,' is obviously sufficient. In Judg. 2⁶, however, this sentence, which *concludes* a section of E, is taken by R^{E2} to *introduce* what he has to narrate about the events which followed the settlement. It may be assumed, therefore, that the expanded form of v.^{6b} represents an adaptation due to R^{E2}. The disappearance from v.⁸ of the E phrase, 'and it came to pass after these things,' which occurs in the corresponding v.²⁰ of Josh. 24, is of course due to the fact that the 'things' referred to have no place in Judg. If Judg. 2¹⁰ be rightly regarded as forming part of E, it follows that 2⁷ is in its original position with regard to its context, since the connexion between 2¹⁰ and 2⁹ cannot be broken. The position of Josh. 24³¹ must therefore have been altered by the redactor.†

In the verses which follow, a difference in the point of view is evident. In vv.¹¹⁻¹⁹ Israel's punishment for idolatry is that they are delivered into the hands of the *surrounding* nations; as we find, in fact, to be the case in the narrative of the Judges which follows. In vv.^{20,21}, however, the punishment consists in Yahweh's refusal to interpose any further in order 'to dispossess any from before them of the nations which Joshua' left when he died'; obviously meaning the races still remaining *within* the land after the settlement of the tribes and their merely partial conquest. This aspect, then, of Yahweh's relation to Israel is not strictly apposite to what follows in Judg., in so far as it cannot have been specially framed in order to introduce the events which follow in the book; these events, as we have noticed above, serving rather to illustrate the former point of view.

Moreover, the purpose for which the nations still remaining after Joshua's death are here stated to have been left by Yahweh is not that of 2¹¹⁻¹⁹, where the surrounding nations are employed in order to *punish* idolatrous Israel. It is stated in 2²², 3^{1,4} to be 'in order

* The only solution, upon the assumption of the Deuteronomic origin of the verse, would seem to be that it may have been inserted in Josh. by a later hand in order to make Josh. 24²⁸⁻³¹ square exactly with Judg. 2⁶⁻⁹. The converse process (insertion from Josh. into Judg.) is excluded by the facts noticed above.

The only reason for the assigning of v.⁷ to the editor appears to be the occurrence of the D phrase 'who had prolonged days'; but there is no reason why this phrase should not have been adopted by the D school from E (just as other phrases, e.g. אֱלֹהִים אֲחֵרִים 'other gods,' have been), and in fact it cannot be proved that the similar phrase 'that thy days may prolong themselves' in Ex. 20¹² did not originally belong to E.

† In G^B of Josh. the verse stands in the same position as in Judg.

to prove Israel by them.' The method of 'proof,' however, is explained in two different ways. In 2²², 3⁴ it is a *religious* probation—to test the adhesion of Israel to Yahweh's precepts ('the ways or commands of Yahweh'); but in 3^{1,2} it is explained simply as directed towards keeping the successive generations of the children of Israel exercised in the use of arms, and is therefore, it may be inferred, *devoid of any strictly religious purpose*. These remaining nations, again, which form Yahweh's instrument of probation, appear, as mentioned in 3³, to be (with the exception of 'all the Canaanites') *surrounding* nations, inconsistently with 2²⁰⁻²³, but in accordance with 2¹¹⁻¹⁹, where it is these nations that form Yahweh's instrument of punishment. Once more, 3⁵ harks back to the point of view of 2²⁰⁻²³, and it is the races *within Canaan* with whom the writer is concerned.

Looking once more at 2¹¹⁻¹⁹, the existence in these verses of a duplication of statement can hardly escape notice. Thus 2¹³ repeats 2¹², and 2^{18,19} are in substance the same as 2^{16,17}. If, however, we remove one set of duplicates, viz. 2^{12,18,19}, it will be found that the remainder, with the exception of 2^{14b,15}, is nearly identical in wording with the pragmatic framework of the book as seen in the introductions to the histories of the various judges. The closeness of the parallel may best be seen by a comparison with 3⁷⁻⁹:—

- 2¹¹ And the children of Israel did that which was evil in the sight
 3^{7a} And the children of Israel did that which was evil in the sight
 2¹² of Yahweh, and they forsook Yahweh and served the
 3^{7b} of Yahweh, and they forgot Yahweh their God, and served the
 2^{14a} Ba'als and the 'Ashtarts. And the anger of Yahweh was
 3⁸ Ba'als and the 'Ashtarts. And the anger of Yahweh was
 2^{14a} kindled against Israel, and he delivered them into the hand
 3⁸ kindled against Israel,
 2^{14a} of spoilers and they spoiled them, and he sold them into
 3⁸ and he sold them into
 2^{14a} the hand of their enemies round about.
 3⁸ the hand of Cushan-rish'athaim, king of Aram-naharaim : and
 —
 3⁸ the children of Israel served Cushan-rish'athaim eight years.
 2¹⁶ <And the children of Israel cried unto Yahweh,> and Yahweh
 3⁹ And the children of Israel cried unto Yahweh, and Yahweh
 2¹⁶ raised up judges, and they saved
 3⁹ raised up a saviour for the children of Israel, and he saved
 2¹⁶ them from the hand of their spoilers.
 3⁹ them . . .

This framework is due to the main editor, who appears (as has

been argued in the *Introd.* pp. xli ff.) to have been a representative of the later school of E.

The words in 2^{14a,16}, which find no parallel in 3^{7,9} ('and he delivered them into the hand of the spoilers and they spoiled them'; 'from the hand of their spoilers'), may be by a later hand (D²; cf. 2 Kgs. 17²⁰); but it is more likely that they belong to R^{E2}, who in referring to Israel's enemies generally at the commencement of his history, may be expected to use some emphasis and even repetition (2^{14a}). The clause missing in 30, 'And the children of Israel cried unto Yahweh,' seems necessary to complete the nexus, and has been supplied in accordance with 3^{9,15}, 4³, 6⁶, 10¹⁰.

The verses, however, which appear not to have originally formed part of this writer's scheme, viz. vv. 12, 14b, 15, 18, 19, are just the verses which exhibit very markedly the phraseology of Deuteronomy*; and we can hardly err therefore in regarding them as additions made in later times by a member of the Deuteronomic school (D²).

2²⁰-3⁶ is very difficult to analyse with any certainty. If, as seems probable, E's narrative in 2⁶⁻¹⁰ is continued by v. 13 (notice E's expression 'the Ba'als and the 'Ashtarts'), vv. 20, 21 form the appropriate sequence. Notice the opening phrase, 'So the anger of Yahweh was kindled against Israel,' which has formed the text of the editorial expansion of R^{E2} in vv. 14a, 16, 17.

Of the two methods of probation noticed above, that which consists in religious proving (3⁴) may be regarded as due to E (נִסָּה in this sense is characteristic: cf. CH.^{JE} 192 a). The somewhat awkwardly inserted interpolation 2²², which also refers to this religious probation, is marked by its phraseology as Deuteronomic. The alternative method of probation ('to teach them war,' 3^{2a}) as devoid of religious purpose, may be judged to be older than the other, and is therefore probably to be assigned to J. This seems to connect on to 2^{23a}; which may very well be the sequel to the J narrative in 1¹⁻²⁵, which gives a detailed account of the foreign races within Palestine which the different tribes were unable to expel. Notice the expression 'these nations,' clearly referring to nations just previously mentioned. The immediate sequel to 3^{2a} is 3^{5a,6}, which relates how Israel settled down among the Canaanites, intermarrying with them and adopting their religious practices ('Canaanites,' J's general term for the inhabitants of Palestine: cf. 1³ note. Notice also the J phrase 'dwelt in the midst of'). 2^{23b} (back-reference to 2^{21b}), and 3^{5b} (list of races) exhibit the hand of the redactor of J and E.

The summary of nations 'which Yahweh left to prove Israel by them,' 3^{1a,3}, must be due to D²: cf. the similar Deuteronomic summary in Josh. 13² ff. Finally, the awkwardly placed explanatory glosses in 3^{1b,2b} seem to be due to the latest hand of all (R^v).

* Cf. especially the phrases 'go after other gods,' vv. 12, 19, 'vex Yahweh,' v. 12, 'as Yahweh had spoken and as Yahweh had sworn to them,' v. 15a. Cf. CH.^D 85, 91, 107^b; phrases of R^D in Kings in DB. ii. pp. 860 f., nos. 32, 39.

6. E So Joshua^a dismissed the people, ^{R^{E2}} and the children of Israel went E every man to his inheritance ^{R^{E2}} to possess the land. 7. E And the people served Yahweh all the days of Joshua^a, and all the days of the elders who outlived Joshua^a, who had seen all the great work of Yahweh which he had wrought for Israel. 8. And Joshua^a the son of Nun, the servant of Yahweh, died, aged one hundred and ten years. 9. And they buried him within the boundary of his inheritance, in Timnath-heres^a, in the hill-country of Ephraim, on the north of mount

2. 6. *dismissed the people.* From Shechem; where, according to Josh. 24 ¹⁻²⁸ E, they had been assembled by Joshua^a to receive his final charge.

7. *the elders.* The sheikhs of the various tribal clans who were the representatives of permanent official authority in matters social and religious. They appear from the earliest times, both in J (Ex. 3 ^{16,18}, 12 ²¹) and E (Ex. 17 ^{5,6}, 18 ¹², 19 ⁷, 24 ^{1,9,14}).

outlived. Lit. 'prolonged days after.' Upon the use of the phrase in this passage, cf. *footnote*, p. 53.

who had seen, etc. || Josh. 24 ³¹ 'who had known, etc.' So in our passage Ε ἑγνωνται, Ξ 'noverant.' The expression 'all the great work of Yahweh' probably includes (as Mo. notices) not merely the conquest of Canaan, but also the wonderful events of the Exodus and wilderness-wanderings. Cf. Deut. 11⁷, where the same phrase is employed with regard to these latter.

8. *the servant of Yahweh.* This title, which is only applied to Joshua^a here and in || Josh. 24 ²⁹, is very frequently used with reference to Moses: so in Deut. 34⁵, Josh. 1¹ (both E), Josh. 1 ^{13,15}, 8 ^{31,33}, 11 ¹², 12 ⁶, 13 ⁸, 14 ⁷, 18 ⁷, 22 ^{2,4,5} (all R^D), 2 Kgs. 18 ¹² (R^D), 2 Chr. 1 ³, 24 ⁶ (cf. 'servant of God,' 2 Chr. 24 ⁹, Neh. 10 ²⁹, 1³⁰, Dan. 9 ¹¹). It is applied to David in the headings of Pss. 18 and 36, and to the nation of Israel in Isa. 42 ^{19†}. Similarly, 'my servant' or 'my servants' (in Yahweh's mouth), 'his servants' are employed as a description of the outstanding figures of Israel's history, especially the prophets, and the idealized representative of Israel in Isa. 40 ff.; the idea embodied being that of vocation to a special mission: cf. the editor's *Outlines of O. T. Theology*, pp. 112 ff.

9. *Timnath-heres.* || Josh. 24 ³⁰ and 19 ⁵⁰ Timnath-heres, doubtless an intentional metathesis made by a later scribe: cf. *note* on Har-heres^a, *ch.* 1³⁵. The same alteration appears in a few MSS. of Ψ, and in Ξ, Σ^P in our passage.

The site of this city is uncertain. Christian tradition, as represented by Eusebius and Jerome, identifies it with the Timnah of Gen. 38 ¹² (OS. 261 ³³ Θαμνα), i.e. the modern Tibneh, ten miles north-west of Bethel. About three miles to the east of Tibneh is Kefr Isha^a,

Ga'ash. 10. And also all that generation were gathered unto their fathers; and there arose another generation after them who knew not Yahweh, nor yet the work which he had wrought for Israel.

11. ^{RE2} And the children of Israel did that which was evil in the sight of Yahweh, [] 12. ^{D2} and forsook Yahweh the God of their fathers, who had brought them out of the land of Egypt; and they went after other gods, of the gods of the peoples who were round about them, and bowed themselves down to them; and they vexed Yahweh. 13. ^E And they forsook Yahweh, and

i.e. 'Joshua's village.' Samaritan tradition, however, claims as the site the modern Kefr Hâris, some nine miles south-south-west of Nâblus, which is said to have been the burial-place of both Joshua and Caleb. Cf. Buhl, *Geogr.* p. 170.

mount Ga'ash. The site is unknown. 'The wâdys of Ga'ash' are mentioned in 2 Sam. 23³⁰=1 Chr. 11³²; and these Buhl conjectures to be the valleys close to Tibneh on the west: *Geogr.* p. 101.

10. *were gathered unto their fathers.* Elsewhere the expression used (in every case in P) is 'gathered unto his kindred' (עֲפָיִי); so Gen. 25^{8,17}, 35²⁹, 49³³, Num. 20²⁴, Deut. 32⁵⁰; cf. Num. 27¹³, 31².

11. At the end of the verse, ^ח (with the Versions) adds 'and they served the Ba'als,' a statement which is redundant by the side of *v.* 13, and probably represents an early accidental repetition.

12. *went after . . . round about them.* A reminiscence of Deut. 6¹⁴.

13. *the Ba'als.* Reading plur. לְבָעֲלִים (cf. *v.* 11^b ^ח) in place of the sing. לְבָעַל.* The title Ba'al signifies 'owner' or 'possessor,' and was applied by the Western Semites to a deity as owner of a special sphere of influence, whether in the heavens, *e.g.* Ba'al-zebul, 'owner of the (heavenly) mansion' (cf. 1⁵ *note*), and, among the Phoenicians and Aramaeans, Ba'al-shamêm, 'owner of the heavens'; or of a special locality or city where his worship was practised, *e.g.* Ba'al-Hêrmon, and Phoenician Ba'al-Şidon, Ba'al-Lebanon, etc.; or of a special property, *e.g.* Ba'al-berith, 'owner of a covenant' worshipped at Shechem, *ch.* 8³³, 9⁴; Ba'al-Gad, the name of a locality where the Ba'al was worshipped as the god of fortune, Josh. 11¹⁷, 12⁷, 13⁵. The plur. 'the Ba'als' refers to the different local Ba'als among the Canaanites. Upon the use of the title as applied to Yahweh in early times, cf. the present editor's *Outlines of O. T. Theology*, pp. 27 ff.

* Mo. emends 'served the Ba'als, etc.,' into 'burned incense (וִיקָטְרוּ) to the Ba'als, etc.,' on the ground that 'לְ עֲבָדָא' for עֲבָדָא with accus. is unexampled.' But, as Bu. rightly remarks, even if the occurrence of the verb with this constr. in Jer. 44³ be regarded as a gloss (as by Mo.), the constr. is found twice over in 1 Sam. 4⁹ (probably E): פֶּן תַּעֲבֹדוּ לַעֲבָדִים כַּאֲשֶׁר עֲבָדוּ לָכֶם.

served the Ba'al[s]¹ and the 'Ashtarts. 14. ^{R^E2} So the anger of Yahweh was kindled against Israel, and he gave them into the hand of spoilers, and they spoiled them, and he sold them into the hand of their enemies round about, ^D² and they were not

Ba'al being thus not the proper name of a deity, but a title applied to many local Cana'anite deities, it is impossible to define any special characteristic which may have been common to all. We can only infer from such passages as Hos. 2 ^{5,8,12} (^{7,10,14} ¹⁹) that the Ba'als were commonly regarded as the givers of agricultural fertility, and were therefore worshipped in a round of agricultural festivals: cf. *ch.* 9²⁷. This view is confirmed by the common connexion of the Ba'als with the 'Ashtarts, on which see *note* following.

the 'Ashtarts. The local forms of the goddess 'Ashtart. The vocalization 'Ashtoreth, which meets us everywhere in ¹⁹, is an intentional alteration made by the introduction of the vowels of *bōšeth*, 'shame' or 'shameful thing,' in order to indicate that this word is to be substituted in reading. ¹⁹, however, always renders ἡ Ασταρτη, which doubtless nearly preserves the true pronunciation.* The same substitution of the vowels of *bōšeth* has been made in Molech for Melech, 'king,' the god in whose worship the Israelites made their children to pass through the fire; and the word *bōšeth* is substituted for Ba'al in Hos. 9¹⁰, Jer. 3²⁴, 11¹³, and in the proper names Ishbosheth, Mephibosheth, Jerubbesheth: cf. *note* on Jerubba'al, *ch.* 6³².

There can be no doubt that a principal (if not *the* principal) conception embodied in the Cana'anite 'Ashtart was that of the mother-goddess, to whom was due the fecundity of nature. This may be inferred from the expression '*āšterōth šōnékhā*, i.e. either the 'breeding ewes' or 'the offspring of thy flock,' Deut. 7¹³, 28 ^{4,18,51} +; and also from the special characteristics of the numerous small figurines, apparently of this goddess, which have been unearthed in the excavation of city-sites in Palestine: cf. Driver, *Schweich Lectures*, pp. 56 ff.; Vincent, *Canaan*, *ch.* iii.; *TB.* ii. pp. 81 ff. Whether the *ḫadhešīm* and *ḫadhešōth*, i.e. the temple-prostitutes of both sexes belonging to the Cana'anite religion, were specially devoted to the service of 'Ashtart is not certain. The Bab. Ištar, however, had her female prostitutes, who bore the title *ḫadištu* or *ḫarimtu*: cf. *KAT*,³ p. 423.

Old Testament writers seem to regard 'Ashtart as specially a Phoenician deity: so 1 Kgs. 11 ^{5,33}, 'Ashtart the goddess of the Sidonians': cf. 2 Kgs. 23¹³. Her worship was, however, very widely diffused among the Semites. She is the Bab. Ištar, the one goddess

* An original 'Ashtart may have come to be pronounced 'Ashtárath or 'Ashtérèth. ^{בְּעִשְׁתֵּרָה} Bē'shtērā for ^{בֵּית עִשְׁתֵּרָה} Beth-'Esh'tēra in Josh. 21²⁷ probably preserves one original form of the name.

able any more to stand before their enemies. 15. Whithersoever they went out the hand of Yahweh was against them for evil, as Yahweh had spoken, and as Yahweh had sworn to them; and they were in sore straits. 16. ^{R^{E2}} <And the children of Israel cried unto Yahweh,> and Yahweh raised up judges, and they saved

who holds her position as it were in her own right, and not merely as the somewhat shadowy consort of a god. Different localities in Babylonia were famous for the worship of Ištar, who thus appeared, under various localized forms, as the Ištar of Erech, of Nineveh, of Arbela, etc. The principal aspects under which she was regarded were as the goddess of war (she is spoken of as *bēlit taḥāzi*, 'mistress of battle,' and her chief epithet is *ḫarittu*, 'warrior': see references in Muss Arnolt's *Dict.*, and, for a representation of the goddess under this aspect, *TB.* ii. p. 80) and goddess of love or mother-goddess (cf. Herodotus' statement (i. 131. 199) that the Assyrians called her *Μυλιττα*, i.e. *muallidat*, 'she who causes to bear'). This latter aspect of the Canaanite 'Ashtart we have already noticed: of the existence of the former in Canaan we have no evidence; though it may be noticed that the Philistines, after their victory over Israel and the death of Saul, hung Saul's armour in the temple of 'Ashtart (1 Sam. 31¹⁰).

The plur. *ištarāti* came to be used in Babylonian in the general sense 'goddesses' (a point of resemblance to the Heb. plur. *'Aštārôth*); and even the sing. Ištar is sometimes employed to denote 'goddess,' alongside of *ilu*, 'god,' especially in the penitential psalms: cf. *iššu u ištaršu zenû ittišu*, 'his god and his goddess are angry with him': Muss Arnolt, *s.v. ištaru*.

The same deity is seen in the Sabaean 'Athtar, the Aram. 'Attar, and in the Moabite compound form 'Ashtar-Chemosh. With regard to 'Athtar, Barton (*Semitic Origins*, pp. 123 ff.) has made out a plausible case in proof that the mother-goddess came to be transformed into a male deity; but his argument that the same phenomenon is to be observed in the Moabite deity (only mentioned once in Mesha's inscription, l. 17) is not equally convincing: cf. *op. cit.* pp. 141 ff.

15. *Whithersoever they went out.* *Sc.* to battle. So Le Clerc 'quamcumque expeditionem aggredierentur'; Mo. 'in every campaign,' and similarly Stu., Bach., Bu., La. For **סו** 'go forth' in this military sense, cf. *ch.* 5⁴, 2 Kgs. 18⁷, Deut. 28²⁵.

as Yahweh had spoken, etc. Cf. Deut. 28²⁵; and, generally, the whole tenor of that chapter.

16. *And the children of Israel cried unto Yahweh.* This clause is not found in **ℳ** or Verss., but forms elsewhere a regular element in the pragmatic scheme of ^{R^{E2}}, and can scarcely be dispensed with in the present connexion. Cf. *introd.* to the section.

judges. The two verbs *šāpḥat* 'judge,' and *hōšāa* 'save,' are used interchangeably by ^{R^{E2}} with reference to Israel's deliverers.

them from the hand of their spoilers. 17. But even unto their judges did they not hearken; for they went a whoring after other gods, and bowed themselves down to them: they turned aside quickly from the way wherein their fathers had walked, obeying the commandment of Yahweh: they did not do so. 18. D² And when Yahweh had raised up judges for them, Yahweh would be with the judge, and would save them from the hand of their enemies all the days of the judge: for Yahweh would be moved to pity because of their groaning by reason of them that crushed and oppressed them. 19. But when the judge died they would turn back, and deal more corruptly than their fathers, in going after other gods to serve them and to bow themselves down to them: they did not let fall any of their practices or of their stubborn way. 20. E So the anger of Yahweh was kindled against Israel, and he said, 'Because this nation have transgressed my covenant which I commanded their fathers, and have not hearkened to my voice, 21. I also will no more expel any from before them of the nations which Joshua^a left when he died':

and they saved them. Ε και ἔσωσεν αὐτοὺς Κύριος. Possibly original (so La.); cf. v. 18, where Yahweh is similarly subject of the verb.

17. *went a whoring.* A frequent metaphor for intercourse with other deities and unfaithfulness to Yahweh. So again in *ch.* 8^{27,33}. *they turned aside quickly, etc.* For the phrase, cf. Ex. 32⁸ (E⁷), Deut. 9^{12,16}.

18. *would be with, etc.* The verbal sequence in the Heb., in this and the following verse, describes what happened on repeated occasions.

would be moved to pity. R.V. 'for it repented the Lord' does not adequately express the sense of the verb. Cf. the use of the same verb (נָחַם) in *ch.* 21^{6,15}, Jer. 15⁶, Ps. 90¹³.

20. *have transgressed my covenant.* I.e. the divine constitution given to Israel by Yahweh at Horeb or Sinai, upon the basis of which (i.e. upon condition of the faithful performance by Israel of the ordinances of the constitution) Yahweh undertook to make Israel his peculiar people. The two sides of the covenant are tersely summarized in Deut. 26¹⁷⁻¹⁹.

21. *left when he died.* Lit. 'left and died.' The Heb. constr. is very peculiar. Ε, in place of וְ 'and died,' reads ἐν τῇ γῇ καὶ ἀφῆκεν (in connexion with the verse following τοῦ περιάσαι κ.τ.λ.). Here ἐν τῇ γῇ is most likely only an insertion explanatory of the

22. D² in order to prove Israel by them, whether they would keep the way of Yahweh to walk [therein], as their fathers kept it, or not. 23. J So Yahweh left these nations, not expelling them quickly, R^{JE} and did not give them into the hand of Joshua'.

3. 1. D² Now these are the nations which Yahweh left to prove Israel by them, R^p even all who had not experienced all the wars of Cana'an ; 2. J only on account of [] the generations of the

preceding κατέλιπεν : but καὶ ἀφῆκεν = וַיַּנֵּחַ, i.e. the opening word of v. 23 'and [Yahweh] left,' which must have stood in immediate connexion with v. 21 before D²'s insertion (v. 24) was made. It is possible, therefore, that D² took up this word to introduce his insertion (meaning perhaps to write וַיַּנֵּיחֵם), and explained 'So he left them in order to prove Israel,' etc. This may then be supposed to have become subsequently corrupted into וַיִּמַּח in 𐤁. Such a repetition by an editor of the words of the older source as the text of his expansive comment is seen in R^{E2}: 'So the anger of Yahweh was kindled against Israel'; a statement which introduces v. 14.16.17 prior to the occurrence of the same phrase in v. 20 E.

La. emends וַיַּנֵּחַ for וַיִּמַּח, and connects the verb closely with the preceding sentence : 'que Josué a laissé subsister "en repos"' ; but this is scarcely possible.

22. therein. Reading sing. בָּהֶם with some MSS. and 𐤂, 𐤁, F, S, in place of 𐤁 plur. בָּם.

3, 2. on account of the generations, etc. I.e. the generations successive to the one which had been responsible for gaining the first footing in Cana'an ; as is explained by R^p's gloss, 'such namely as formerly knew nothing thereof.' The text adopted is that of 𐤂, πολλὰν διὰ τὰς γενεὰς νιῶν Ἰσραὴλ κ.τ.λ. So 𐤁. 𐤁 inserts דַּעַת after לְמַעַן, and this can only be rendered with S^p, T, R.V. 'only that the generations of the children of Israel might know' ; what they were to know being left to be understood inferentially from the context, viz., the art of war, as the following sentence states. But the constr. 'that they might know (sc. war) to teach them war' is impossibly harsh, and the fact that דַּעַת 'to know' is omitted by 𐤂 points to its being merely an erroneous dittography of דְּרוֹת 'generations' (so Oort, No., Kit., Ehr.).

Mo. (and so Bu.) would prefer to read דַּעַת instead of דְּרוֹת, and to regard לְלַמְּדֵם as a gloss on the former word, thus obtaining the text וַיַּנֵּחַ בְּנֵי יִשְׂרָאֵל מִלְחָמָה רַק לְמַעַן דַּעַת בְּנֵי יִשְׂרָאֵל 'merely in order that the children of Israel might have experience of war.' This of course

children of Israel, to teach them war, ^R such namely as formerly knew nothing thereof:—3. ^D the five lords of the Philistines, and all the Canaanites, and the Sidonians, and the Hittites¹ dwelling in mount Lebanon, from mount Ba'al-Hermon unto the

simplifies the passage, and says all that is required to convey the writer's meaning; but it may be doubted whether we are justified in so far altering the text against the evidence of ^Q, which gives us a quite comprehensible construction.

knew nothing thereof. Lit. 'had not known them.' The 'them' refers to ^R's previous 'all the wars of Canaan' in *v.*¹; and he uses the plur., regardless of the fact that the sing. 'war' intervenes in the old source (*v.*^{2a}).

3. *the five lords of the Philistines.* The rulers of the five principal Philistine cities are always distinguished by the title *śēren*—a title never used in any other connexion. The word is not, so far as we know, susceptible of a Semitic derivation; the old view (cf. Ges. *Thes.*) that it is the same as the Heb. *śēren*, 'axle' of a wheel (1 Kgs. 7³⁰, and in the cognate languages), and that the princes are so called as being, as it were, the axles or pivots of the state, being both unlikely in itself, and also (presumably) precluded by the fact that we do not find the title used elsewhere among the Hebrews or other Semitic peoples.

This being so, it is likely that the title may be of native Philistine origin. ^S מַרְאָנִי, ^T מַרְנִי render *τύραννοι*, and it is thus a plausible conjecture that *śēren* is simply *τύραννος* reproduced in a Hebraized form. ^Q renders *σατράπαι, σατραπείαι, ἄρχοντες* (most usual in ^Q^B), and *σπαρτηγοί* (once); ^F, *satrapae, reguli, principes*.

Upon the Philistines and their origin, cf. *Introd.* xcii ff.

the Hittites dwelling in mount Lebanon. ^W and all Verss. 'the Hivvites.' In Josh. 11³ we find mention of 'the Hivvites under Hermon in the land of Mišpah.' In this latter passage ^Q^B reads 'Hittites,' making the opposite change (Hivvites for Hittites) in the list of races dwelling in the central hill-country of Palestine which immediately precedes. In other passages in which the Hivvites are mentioned in such a way that they can be more or less definitely localized, they appear as inhabitants of Central Palestine: so in Gen. 34² (^P) the term is used of the Shechemites, and in Josh. 9⁷ (^J) of the Gibeonites. Thus, in both passages where Hivvites are mentioned in ^W as dwelling in the neighbourhood of Lebanon and Hermon,* modern scholars take the view that the true reading should be Hittites (הַחִתִּים may easily have been confused with הַחִוִּי; cf. ^Q^B

* 'The land of Mišpah' in Josh. 11³ seems to be the same as 'the valley (Heb. *biḡ'ā*) of Mišpah' in *v.*⁸; *i.e.* probably the southern portion of the great plain between the two Lebanons now called el-Buḡā' in Ar.: cf. Warren in *DB.* iii. p. 402.

entry of Ḥamath. 4. E And they served to prove Israel by them, to know whether they would hearken to the commandment of Yahweh, which he commanded their fathers by the hand of Moses. 5. J And the children of Israel dwelt in the midst of the Canaanites, ^{R^{JE}} the Hittites, and the Amorites, and the Perizzites, and the Hivvites, and the Jebusites. 6. J And they took their daughters to themselves for wives, and their own daughters they gave to their sons; and they served their gods.

in Josh. 11³). The Hittite principalities extended as far south as Ḥadesh in the neighbourhood of the Anti-Lebanon (cf. *Introd.* p. xcix); and it is likely that Hittite clans may have penetrated into the Lebanon-district, which is ideally reckoned as part of the promised land.

from mount Baal-Hermon . . . Ḥamath. The northern extremity of Israel's inheritance, which still remained unconquered after the campaigns of Joshua, is described in Josh. 13⁵ (R^D) as 'all Lebanon eastward [*sc.* of the land of the Gebalites], from Ba'al-Gad under mount Hermon unto the entry of Ḥamath.' Josh. 11¹⁷, 12⁷ (R^D) mentions Ba'al-Gad as the extreme northern limit of the territory subdued by Joshua. Here Ba'al-Gad is probably the same as Ba'al-Hermon, and this is supposed to be the modern Bānyās (Greek Paneas, *OS.*, 217⁴⁰; in N. T., Caesarea Philippi), a grotto near the sources of the Jordan where the ancient worship of Gad was superseded in later times by the worship of Pan; cf. Rob. *BR.*³ iii. pp. 409 ff. Ḥamath, frequently mentioned in the Assyrian inscriptions as Amattu or Ḥammātu, is the modern Ḥamā, situated on the Orontes about 115 miles north of Damascus. 'The entry of Ḥamath' is mentioned several times as the ideal northern limit of the kingdom of Israel (Num. 13²¹, 34⁸; Josh. 13⁵, 1 Kgs. 8⁶⁵ = 2 Chr. 7⁸, 2 Kgs. 14²⁵, 1 Chr. 13⁵, Am. 6¹⁴, Ezek. 47²⁰, 48¹ †); probably because it represented the actual northern limit of the kingdom as Solomon inherited it after the conquests of David (1 Kgs. 8⁶⁵), and as it was regained in later times through the victories of Jerobo'am II. (2 Kgs. 14²⁵). It is doubtless (as Rob. *BR.*³ iii. p. 568, points out) the *northern* extremity of the pass between the Lebanon and Anti-Lebanon ranges. The descriptions here and in Josh. 13⁵ are obviously intended to cover all the Lebanon-district from south to north. Cf. *Introd.* p. xcix, footnote †.

5. *the Canaanites, etc.* To the term 'Canaanites' used by J as a general designation of the inhabitants of Canaan (cf. 1³ *note*) R^{JE} adds the catalogue of races which, when complete, enumerates the 'seven nations' of Canaan: cf. Deut. 7¹, Josh. 3¹⁰, 24¹¹.* Here the Girgashites are missing. On the races mentioned, cf. references in *Index*.

* Driver, on Deut. 7¹ (*ICC.*), gives a conspectus of all the passages in which the enumeration occurs, noticing the order and omissions.

3. 7-11. 'Othniel.

This narrative exhibits throughout the characteristic phraseology of R^{E2}'s pragmatic scheme. Indeed, R^{E2} appears to have possessed no further information than the names of the oppressor and deliverer, and the length of the periods of oppression and subsequent peace. The name Cushan-rish'athaim, signifying 'Cushan of double wickedness,' or, as we might say, 'the double-dyed barbarian,' excites suspicion; and, if genuine, can scarcely be preserved in its original form. The subjugation of Cana'an by a kingdom so remote as that of Mesopotamia might have been expected to have left further traces than we here possess: and it is strange that the deliverer from this foe from the north-east should have been found in a Kenizzite from the extreme south; a member of a clan whose connexion with the northern and central tribes of Israel appears at this time to have been of the slightest (cf. pp. 44 ff.). Hence many critics have supposed that the editor was altogether without authentic information, and, in order to fill up a blank in his scheme of history, chose the name of 'Othniel, which had the advantage of being well known, and, at the same time, of giving a Judge to Judah. Such an hypothesis does not explain the origin of Cushan-rish'athaim, a name which can scarcely be the product of mere invention.

Of the attempted explanations of this name which have been put forward, the most plausible is that suggested by Ball (*ET.* xxi. Jan. 1910, p. 192), who compares the Kaššite name Kashsha-rishat (cf. Ranke, *Early Babylonian Personal Names*, p. 244, n.⁷). The Kaššites were foreign invaders of Babylonia, probably from Elam and the farther East, who founded the Third Babylonian Dynasty, which lasted from *cir.* B.C. 1760 to *cir.* 1185: cf. *Introd.* p. lxx. Their name appears in cuneiform as *Kāššu*; and there can be little doubt that this is the Heb. כִּשׁ Kîš (Cush) mentioned in Gen. 10⁸ as the 'father' of Nimrod, whom the writer regards as the founder of civilization in Babylonia.* The name Kashsha-rishat happens, in the occurrence cited, to belong to a woman; but both elements in the name are familiar in other names, both masc. and fem. Thus the element Kash is seen in Kash-tiliash, which occurs twice among the king-names of the dynasty. Such a name would have been represented in Heb. as כִּישׁ-תִּלְיָשׁ or כִּישׁ-רִישָׁה, and would thus readily have lent itself to the jesting modification which is found in 3. As Ball remarks, 'on any computation, the period of the

* The passage belongs to J; and it is probable that this writer's Kîš is unconnected with the Hamitic Kîš of P in v.⁶. Cf. Skinner (*Genesis, ICC.*, p. 208), who remarks that 'it is conceivable that in consequence of so prolonged a supremacy, Kaš might have become a name for Babylonia, and that J's knowledge of its history did not extend farther back than the Kaššite dynasty. Since there is no reason to suppose that J regarded Kaš as Hamitic, it is quite possible that the name belonged to his list of Japhetic peoples.'

7. ^{R^{E2}} And the children of Israel did that which was evil in the sight of Yahweh, and forgot Yahweh their God, and served the Ba'als, and the 'Ashtarts'. 8. And the anger of Yahweh was kindle against Israel, and he sold them into the hand of Cushan-rish'athaim, king of Aram-naharaim: and the children of

Judges, that is to say, the period of the settlement of Israel in Canaan, falls within that of the Cassite or "Cushite" domination in Babylonia. Although nothing is known at present of any expedition westward on the part of these Babylonian Cushites, it is quite possible that the story of Cushan-rish'athaim's oppression of Israel may preserve an indistinct memory of such an historical episode.*

The only other suggestion as to Cushan-rish'athaim which needs be noticed is that proposed by Klostermann (*GVl.* p. 119), who, working upon the suggestion of Grä. that Aram should be Edom (confusion of ארם and אדום as in 2 Sam. 8^{12,13}, 2 Chr. 20², 2 Kgs. 16⁶: in this case 'naharaim' must be regarded as a later gloss; notice its omission in v. 10), supposes that there may have been an Edomite king named Cushan,† and that *rish'athaim* may represent an original *rôsh hat-têmānî*, i.e. 'chieftain of the Temanites' (רֹשֶׁתֵּימָנִי from רִשְׁעָתִים). This king, he thinks, may be identical with 'Husham (חִשָּׁם) of the land of the Temanites' mentioned in Gen. 36³⁴. This view is favoured by Marquart, *Fundamente israelitischer und jüdischer Geschichte*, p. 11; Cheyne, *EB.* 969; and (as regards the emendation 'Edom') by La. Granted that the emendations based upon the proper name are highly precarious, it is at any rate possible that an encroachment upon southern Palestine by the Edomites may have occurred at this period; and, if so, the deliverer might naturally be found in a clan (the Kenizzites) which was allied to or incorporated with the tribe of Judah.

3. 7. *the 'Ashtarts.* Reading הַעֲשִׁתָּרוֹת with two MSS. and פ (‘the ‘Ashtarts’ are regularly mentioned elsewhere by E or ^{R^{E2}} in connexion with ‘the Ba’als’: cf. 2¹³, 10⁶, 1 Sam. 7⁴, 12¹⁰) in place of הַאֲשִׁתֹּרוֹת ‘the *Ashērôth.*’ The plur. of ‘Ashera (on which cf. *ch.* 6²⁵ note) is usually ‘Asherim (nineteen occurrences); while ‘Asheroth is only found twice besides: 2 Chr. 19³, 33³.

8. *Cushan-rish'athaim.* See introduction to the section. A similar distortion of the name of an enemy in order to cast ridicule upon him

* In the passage cited by Ball from the T.A. Letters which appears to connect *Kaš* with *Nahrima* (i.e. the Biblical Aram-naharaim), ‘as by rights belonging to the Pharaoh's empire’ (according to Winckler's reading in *KB.* v. 181, l. 35: cf. also *KA T.*³ 195), the mention of *Kaš* cannot be substantiated, since the actual reading is *Ka-pa-si*: cf. Knudtzon, *Die el-Amarna Tafeln*, 288, l. 36.

† Cf. the use of Cushan as a tribal name parallel to ‘the land of Midian’ in Hab. 3⁷.

Israel served Cushan-rish'athaim eight years. 9. And the children of Israel cried unto Yahweh, and Yahweh raised up a saviour for the children of Israel, and he saved them, to wit 'Othniel the son of Kenaz, Caleb's ^R younger ^{R^E2} brother. 10. And the spirit of Yahweh came upon him, and he judged Israel; and he went forth to war, and Yahweh gave into his hand Cushan-rish'athaim, king of Aram; and his hand prevailed against Cushan-rish'athaim. 11. And the land had rest forty years. And 'Othniel the son of Kenaz died.

is probably to be seen in the Aram. name טבאל, Isa. 7⁶, properly Ṭab'ēl, *i.e.* 'El is wise' (cf. Ṭabrimmon, 'Rimmon is wise,' 1 Kgs. 15¹⁸), but vocalized by \mathfrak{M} as Ṭab'al in order to suggest to Jewish readers the Heb. meaning 'good for nothing.' Other instances of a like perversion are perhaps to be seen in Zebaḥ and Ṣalmunna (*ch.* 8⁵ *note*), and Adoni-bezek (*ch.* 1⁵ *note*).

Aram-naharaim. 'Aram of the two rivers,' mentioned elsewhere, Gen. 24¹⁰ (J), Deut. 23⁴ (⁵ \mathfrak{M}), 1 Chr. 19⁶, Ps. 60 title†. The two rivers (if the dual form be correct) are the Euphrates and possibly the Chaboras (Heb. Ḥabor, 2 Kgs. 17⁶, 18¹¹). The land of Naḥrima or Narima is repeatedly mentioned in the T.A. Letters, and the same designation is found in the Egyptian Naharin, which seems to have been used of the district both east of the Euphrates and west as far as the valley of the Orontes: cf. Müller, *AE.* pp. 249 ff. Possibly, as Mo. suggests, the dual form in Heb. may be a later artificiality (cf. יְרִיטָלִים for יְרִיטָלִים), and the original form may have been a plur. *Nḥarīm*, 'Aram of the rivers,' *i.e.* the upper watershed of the Euphrates.* R.V. 'Mesopotamia' (as \mathfrak{C}^{AL} , \mathfrak{F}) is too wide, since this term appears to have been used by the Greeks to cover the whole vast district between the Euphrates and Tigris: cf. references cited by Mo.

9. 'Othniel, etc. Cf. 1¹³ *notes*.

10. *And the spirit of Yahweh came upon him.* The divine incentive to deeds of superhuman valour. The same expression is used of Jephthah in *ch.* 11²⁹, and, with emphatic and pictorial description of the force of the divine access, of Gideon, 6³⁴ (it 'clothed itself in him'), and Samson, 13²⁶ (it 'began to impel or smite him'), 14^{6.19}, 15¹⁴ (it 'rushed upon him': the same verb *šālaḥ* is used of the rapid onslaught of fire in Am. 5⁶).

judged Israel. Avenged and vindicated them, as the verse goes on to relate.

11. *forty years.* *I.e.* for a whole generation: cf. *Introd.* p. liv.

* The reason adduced by Mo. (followed by Cooke), viz. that there is no trace of a dual form in the Egyptian Naharin, is based on the argument of W. M. Müller, *AE.* pp. 251 f. In *EB.* 287, however, the same authority states that the form might equally well be read as Naharēn, *i.e.* a dual form.

3. 12-30. *Ehud*.

An ancient narrative is introduced by R^{E2} in *vv.* 12-15a, in which we find the editor's characteristic phraseology combined with material derived from his source. R^{E2} also closes the narrative in his usual manner in *v.* 30. That the old narrative is not a unity, but combines elements derived from two sources, was first recognized by Winckler (*Alttest. Untersuchungen*, pp. 55 ff.); and this view is also taken by Mo., Bu. (*Comm.*), No. The most striking evidence for this is found in *vv.* 18-20. In *v.* 19b 'Eglon is surrounded by his retinue, and Ehud manages to gain a private interview by stating that he has a secret communication (דבר סתר) to make to the king, thus securing the dismissal of the bystanders. In *v.* 20, however, Ehud comes in unto him (בא אליו), apparently from outside, and finds him sitting alone in his roof-chamber; whereupon he announces that he is the bearer of a divine communication (דבר אלהים). Having noticed this indication of a double narrative, we can scarcely fail to observe that *v.* 19a interrupts the connexion between *v.* 18 and *v.* 19b. Clearly Ehud, after dismissing his own retinue (*v.* 18), at once takes steps to secure a private audience (*v.* 19b). If *v.* 19a were really part of this narrative, we should expect *v.* 19b to be introduced by the statement that he re-entered the king's presence. As the narrative stands, the sequence is somewhat abrupt. The natural sequence to *v.* 19a is *v.* 20. This, when directly connected with *v.* 19a, may have run יבא אל המלך 'And he came in unto the king.'

Other traces of a double source may be seen in *v.* 22b by the side of *v.* 23a, and in *v.* 24 following upon *v.* 27. In *v.* 27 Ehud musters his forces, and we are told that 'they went down with him from the hill-country' into the Jordan valley. In *v.* 28 he invites them to come down, only then explaining the purpose of the muster; and we are again told that 'they went down after him.' Traces of two accounts of Ehud's escape have been supposed to exist in *v.* 26; but these are not so obvious.

Beyond these points, it is difficult to discover further indications which might aid in discrimination of the sources; and phrases peculiarly characteristic of either J or E do not happen to occur in the narrative. Bu. (*RS.*) notices that the verb התמקמה 'tarry' in *v.* 26 is confined to J when it occurs in the Pentateuch (Gen. 19¹⁶, 43¹⁰; Ex. 12³⁰). Rather more significant as a mark of J is the expression in *v.* 28 which relates the holding of the fords of the Jordan against Moab, as compared with *ch.* 12^{5a}:

וילכדו את מעברות הירדן למואב
וילכדו גלעד את מעברות הירדן לאפרים

Cf. also *ch.* 7²⁴ (also J), as emended in our text, ולכדו להם את מעברות הירדן. Here the use of the ל as a kind of *dutivus incommodi*

12. ^{R^{E2}} And the children of Israel again did that which was evil in the sight of Yahweh: and Yahweh strengthened 'Eglon king of Moab against Israel, because they had done that which was evil in the sight of Yahweh. 13. And he gathered unto him the children of 'Ammon and 'Amalek; and went and smote Israel; and took possession of the City of Palms. 14. And the

('against' or 'to the detriment of') is rather striking. It must be acknowledged, however, that criteria upon which to base a detailed analysis are wanting; and nothing can be affirmed with even approximate certainty as to the composition of the narrative beyond the fact of the existence of a few fairly clear indications that two sources have been employed. The old narrative as a whole is therefore marked in the text as JE.

3. 12. *Yahweh strengthened 'Eglon.* The same verb (*hizzēk*) is used in Ezek. 30²⁴ of Yahweh's 'strengthening' the arms of the king of Babylon as an instrument of punishment.

13. *'Amalek.* A marauding Bedawi people dwelling in the south of the Negeb (Num. 13²⁹, 14²⁵ ^{R^{JE}, 43.45} JE), in the neighbourhood of the Kenites (*ch.* 1¹⁶ *note*, 1 Sam. 15⁶) and the tribe of Sime'on (1 Chr. 4⁴³). Israel is related (Ex. 17^{8ff.} E, Deut. 25¹⁷⁻¹⁹) to have first come into conflict with them soon after the Exodus upon arriving at Rephidim, which must have been close to Horeb or Sinai—a fact which tells in favour of the location of the holy mountain somewhere in the neighbourhood of Qadesh-Barnea' in the south of the Negeb: cf. *note* on *ch.* 5⁴. David, whilst dwelling at Šiklag in the Philistine country, made forays against the 'Amalekites (1 Sam. 27⁸), and suffered reprisals in his turn (1 Sam. 30). ³¹ in *ch.* 5¹⁴, 12¹⁵ suggests that 'Amalekites may at one time have been found in Central Palestine; but cf. *note* on the former passage. The 'Amalekites are again mentioned as invading Israelite territory during the period of the Judges in *ch.* 6^{3.33}, 7¹², where they appear in conjunction with the Midianites and 'all the children of the East,' nomadic peoples like themselves with whom it is natural to find them associated. In the present narrative there is no further allusion to 'Ammon or 'Amalek; and it is possible that ^{R^{E2}} may have amplified the account of the invasion by the addition of the names of these peoples. Nöldeke (*EB.* 128) suggests that 'Amalek in this passage may have arisen from an ancient dittograph of 'Ammon (עמון ועמלק).

and took possession of. Reading sing. וַיִּירֶשׁ with *Gr*, *F*, in place of ³¹ (and so *T*) plur. וַיִּירְשׁוּ. ³² has plur. verbs throughout v. ^{13b}, 'they went and smote, etc.'

children of Israel served 'Eglon king of Moab eighteen years. 15. And the children of Israel cried unto Yahweh, and Yahweh raised up for them a saviour, to wit Ehud the son of Gera, the Benjaminite, a left-handed man: JE and the children of Israel

the City of Palms. Jericho, as in ch. 1¹⁶ (cf. *note*). The mention of Jericho in this connexion suggests that the city can scarcely have remained unbuilt and unfortified after its destruction by Joshua until the days of Ahab, as might be inferred from 1 Kgs. 16³⁴ taken in connexion with Joshua's curse in Josh. 6²⁶ (JE); for the allusion to its capture by 'Eglon seems to imply that it was a fortified city, the possession of which was employed as a vantage-ground for the oppression of the surrounding country.

15. *Ehud the son of Gera.* Gera appears as a son (*i.e.* clan) of Benjamin in Gen. 46²¹ (P), and as a grandson in 1 Chr. 8³; while Ehud himself is found in the obscure genealogical lists of 1 Chr. 7¹⁰, 8⁶ (7¹⁰ would make him the great grandson of Benjamin, but here the name is probably due to an erroneous marginal gloss: cf. Curtis, *ICC. ad loc.*). These facts need not be weighed against the historical truth of our narrative, as though Ehud were simply a clan-name of Benjamin round which the narrator had woven his story; since it is much more probable either that the name has been introduced by the Chronicler into his genealogy directly from Judg., or that a clan in subsequent ages traced its descent from the individual Ehud (so Bu. *RS.* p. 100; Mo.). The fact, however, that Ehud is called 'son' of Gera very likely means that he was member of a clan of that name, and not that Gera was actually the name of his father. Similarly, in David's time, Shime'i the Benjaminite was a 'son of Gera,' 2 Sam. 16⁵, 19^{16,18}, 1 Kgs. 2⁸.

left-handed. Lit. 'bound (*i.e.* restricted) as to his right hand.' The adj. 'ittēr,* 'bound,' is used by itself in New Heb. in the sense 'left-handed' or 'lame' (restricted in the use of a foot), and belongs in form to the class of words descriptive of bodily defects, *e.g.* 'iwwēr

* The verbal form אָטַר is not, as stated by Mo., cognate with אָטַם, but rather belongs to a series of triliteral roots from an original DAR, ṬAR, TAR, ŠAR, ŠAR, ZAR, with the sense 'go round,' 'surround,' and hence, in some instances, 'bind' (a form of surrounding). So דָּוָר (Ar. *dāru* and its derivatives, *e.g.* *dār*, 'dwelling,' or properly circle of buildings round a court; Bab. *dāru*, 'wall' as encircling; Heb. *dōr* 'generation' as periodic, *dūr* 'ball' as *being round*), probably דָּר-ר (whence *derôr* 'swallow,' perhaps as flying round in circles), חָדַר, גָּדַר, טוֹר, אָטַר, עָטַר, קָטַר (Ezek. 46²²); בִּיתָר, תוֹר; צוֹר, צָרַר, חָצַר, עָצַר, אָצַר, צָרַר (bind harvest); אָסַר, זוֹר (compress), אָזַר, חָזַר (Aram.). Notice, especially in the ŠAR series, the ascending scale of initial gutturals employed to differentiate the modifications of the original sense of the biliteral root.

sent by his hand tribute to 'Eglon king of Moab. 16. And Ehud made himself a sword with two edges, a cubit long; and he girded it under his raiment on his right thigh. 17. And he presented the tribute to 'Eglon king of Moab: now 'Eglon was a very fat man. 18. And when he had finished presenting the tribute, he sent away the people who were carrying the tribute.

'blind,' *'illēm* 'dumb,' *piššāh* 'lame,' etc.; but that the peculiarity did not involve any defect in skill appears from the reference to the 700 left-handed Benjaminites in *ch.* 20¹⁶. *U* renders ἀμφοτεροδέξιον (—δέξιαι), 'ambidextrous,' in both passages; and similarly *V* here 'qui utraque manu pro dextera utebatur,' but in 20¹⁶ 'sinistra ut dextra proeliantes.' Cf. the description of the Benjaminites in 1 Chr. 12².

tribute. The Heb. *minhā* is used elsewhere in this sense in 2 Sam. 8²⁶, 1 Kgs. 4²¹ (*U* 5¹), 2 Kgs. 17³. In other passages the word has the meaning of a *present* offered voluntarily in order to gain the favour of the recipient: cf. Gen. 32¹³, *U* 14, 2 Kgs. 8⁸, 20¹². In the sacrificial terminology of the Priestly Code *minhā* denotes the *meal-offering*.

16. *two edges.* Lit. 'two mouths': cf. the expression 'a sword of mouths,' Prov. 5⁴, Ps. 149⁶, and the phrase noticed in *ch.* 1⁸.

a cubit long. The Heb. term *gōmedh* (only here in O.T.) is explained by the Jewish interpreters as a short cubit, *i.e.* the length from the elbow to the knuckles of the closed fist: cf. Mo. in *JBL.* xii. p. 104. The measure thus corresponds to the Greek πρυγμή, approximately 13½ inches. *U* renders σπιθαμῆς τὸ μῆκος αὐτῆς, 'a span long'; but, as Mo. (following Stu.) appositely points out, 'the description of 'Eglon's corpulence (*v.* 17) is pertinent only in relation to the fact that a long dirk was buried, hilt and all, in his belly.' *V* offers a curious and obscure paraphrase, intended to explain the character of the sword: 'gladium ancipitem, habentem in medio capulum longitudinis palmae manus,' interpreting *gōmedh* as a hand-breadth and referring it to the hilt. *S* 1 סביו מלח is interesting as reading *gāmadh* (cf. Ar. *ḡamada*, 'cut off'; Aram. *g'madh*, 'contract') in place of *gōmedh*: 'he curtailed its length.' Such a proceeding on the part of Ehud, for the purpose of more effectively concealing the weapon under his raiment, would be perfectly intelligible: still, the consideration noticed above seems to demand a precise mention of the length of the sword, as in *U*.



under his raiment. Heb. *maddim* is the loose outer garment, outside of which the sword was usually worn: cf. 1 Sam. 17³⁹.

18. *he sent away the people, etc.* The tribute was doubtless paid in kind (most probably in farm-produce) and would require a number of bearers. In later times, when Moab was subject to Israel, the tribute consisted in the wool of one hundred thousand rams and one

19. But he himself returned from the graven images which are near Gilgal; and he said, 'I have a secret communication for thee, O king.' And he said, 'Silence!' And there went out from him all who stood by him. 20. And Ehud came in unto him: now he was sitting by himself in his cool roof-chamber.

hundred thousand lambs: 2 Kgs. 3⁴. A representation of a train of envoys of Jehu, king of Israel, bearing tribute to the Assyrian king, is to be seen upon the black obelisk of Shalmaneser III. (cf. Driver, *Schweich Lectures*, p. 17), and in this case the tribute is very costly (consisting largely in vessels of gold: cf. *NHTK*. p. 377), in accordance with the resources of the kingdom of Israel in Jehu's time.

19. *graven images*. This is the meaning which is regularly borne by the Heb. *p'silim* elsewhere (twenty-one occurrences). In itself the term simply denotes 'carved things,' and might refer to figures in low relief carved upon standing stones, possibly some of the stones from which Gilgal derived its name (cf. *note* on *ch.* 2¹). The connexion in which the *p'silim* are mentioned is, however, rather striking: it is when Ehud reaches this point that he dismisses his retinue; and later on (*v.*²⁶) when he has passed it he gets clear away, and so escapes. Both references, especially when taken together, can scarcely fail to suggest a comparison with the sculptured *boundary-stones* which have been found in Babylonia (cf. *OTLAE*. i. p. 11; Jastrow, *RBBA*. pp. 230, 385 f.), and to raise the possibility that the *p'silim* may have marked the limit of the sphere of Moab's influence, beyond which comparative safety was attained. Such a theory could not hold if the narrative were a unity; since, according to *v.*¹³, Jericho, three miles west-north-west of Gilgal, was in the possession of Moab. But, as we have noticed, the story clearly seems to have been derived from two sources, and the source to which the references to the *p'silim* belong may have differed as to this point; or the words 'which are near Gilgal' may be a later and erroneous identification of the site of the *p'silim*.

A.V., R.V. render 'quarries,' apparently following מַחְצְבֵיא. Ἐ ἀπὸ τῶν γλυπτῶν, Ἦ 'ubi erant idola,' support the ordinary meaning of the word. שׁׁ  employs the same word as ח. .

a secret communication. Lit. 'a word of secrecy.'

Silence! The command (Heb. *hās*, onomatopoeitic, like English 'hush!' or 'ssh!') is addressed by 'Eglon to his retinue.

20. *roof-chamber*. The Heb. 'ālīyyā is explained by the same term 'ullīyya, 'illīyya in Ar., in which it denotes a room built on the top of the flat roof of a house, with windows on every side for the free passage of air. Cf. Mo., who quotes authorities for the use of such roof-chambers in the modern east. The purpose of this 'ālīyyā is

And Ehud said, 'I have a communication from God for thee.' And he rose up from his seat. 21. And Ehud put forth his left hand, and took the sword from his right thigh, and thrust it into his belly. 22. And the hilt also went in after the blade, and the fat closed over the blade; for he drew not the sword out of his belly. And he went out into the vestibule. 23. And Ehud

further defined by the term *ham-meḵērā* (חַמ־מֶעָרָא), lit. 'roof-chamber of coolness.' The size and character of the windows in such a chamber is indicated by 2 Kgs. 1², where we are told that king Ahaziah accidentally fell through the lattice-window (רֶשֶׁת־כֶּבֶד) in his 'āliyyā.

a communication from God. Lit. 'a word of God.'

he rose up, etc. The action seems to have been intended as a mark of reverence for the divine oracle.

21. *put forth, etc.* The movement of the left hand to the right side was unlikely to arouse suspicion.

22. *the hilt also went in.* As Mo. remarks, 'the dirk was doubtless without either guard or cross-piece.'

into the vestibule. Heb. *hap-parš'dhônā* only here. The precise rendering 'vestibule' is conjectural, but there is no reason for doubting the originality of the Heb. word. There is an Assy. word *parašdinnu*, the exact meaning of which is similarly unknown; but (according to Delitzsch, *HWB.* p. 546) we have the equivalents *pa-ra-aš-din-nu* = KIRRU.DA in Sumerian, i.e. some form of cavity or opening. *Parš'dhônā* may therefore be assumed to denote a means of exit; though exactly what we cannot say. La., adopting this explanation, assumes that the term denotes the *window*. But the form of the Heb. word (with ה locative) implies that it was something *into* which and not simply *through* which Ehud passed; and, moreover, there seems no reason why the writer should not have used the ordinary word *hallôn*, 'window,' if this had been his meaning.

The rendering which we have adopted is given by A. τὴν προστάδα (from which apparently R.V. marg. 'the ante-chamber'), 'A. παραστάδα, Σ. εἰς τὰ πρόθυρα. We cannot, however, certainly assume that the meaning of the word was familiar to the translators, since it is not unlikely that the rendering may have been dictated by the accidental resemblance of the Greek word to the Heb.*

* This is a consideration which appears not infrequently to have influenced the A. translators. Driver (*NHTS.*² p. 270) notices ἐσχαπλήτην for אֲשַׁפֵּר probably read as אֲשַׁפֵּר 2 Sam. 6¹⁹, δρεπανον for דְּרֶבֶן 1 Sam. 13²¹, τόκος for תֶּן Ps. 72¹⁴ al.; to which we may add τανάσιον for מָוֶן Ex. 28¹⁷ al.; σκηνοῦν for שָׁכַן Judg. 5¹⁷, 6¹¹.

went out into the colonnade, and shut the doors of the roof-chamber upon him, and lock^d them. 24. Now when he had gone out, his servants came; and they looked, and, behold, the

פ, ט* seem to have read or understood *hap-péres* (Ex. 29¹⁴; Lev. 4¹¹, 8¹⁷, 16²⁷; Num. 19⁵, Mal. 2³ †) in place of *hap-par^sdhōnā*: 'and the *faeces* came out' *sc.* from the anus, as is said to be the ordinary consequence of a wound in the abdomen (cf. Mo.). This emendation is adopted by Nöldeke, Mo., Bu., Kent; but the objections advanced against it by No. are valid; ‡ and in any case it can scarcely stand in view of the support given to פ by the Assyr. parallel.

ס^p 'and he went out *hastily*' (ספס חסל) is a bad guess. R.V. 'and it came out behind' depends upon a mere conjecture made by a number of the older commentators (cf. Mo.'s enumeration), and involves a violation of grammar (החרב 'the sword' is fem., and can scarcely be the subject of the masc. ויצא 'and it came out').

23. *into the colonnade.* Or 'portico.' Heb. *ham-mišd rōnā* only here. The meaning of the term is almost as obscure as the meaning of that last discussed, to which it probably corresponds in the parallel narrative. The Heb. root *sādhār* means 'to arrange in order *or* in a rank,' and is so used in New Heb., Assyr., and Aram. We have cognate substantives in all these languages meaning 'arrangement,' 'rank,' or 'row' (in Assyr. 'line of battle'); and it may thus be inferred that *mišd^erōn*, in accordance with its form (substantives with preformative מ commonly denote the *place* of the action implied by the verbal form), may mean 'place of rows' (*sc.* of pillars), *i.e.* 'colonnade.' This is the rendering of S^p *kšūš^rrōn*, *i.e.* ξυστός. Ἐπὶ τοὺς διατεταγμένους recognizes the meaning of the root, but is at a loss for an intelligible rendering. פ 'per posticum' (perhaps an error for 'per porticum'). ט לאכסדרא, *i.e.* ἐξέδρα. R.V. 'into the porch.'

and locked them. The Heb. construction (וַיִּנְעַל) Perfect with Weak *wāw*) is irregular. We should expect וַיִּנְעַל; but it is quite possible that the form intended is the *infinitive absolute* וַיִּנְעַל in continuation

* פ's rendering, however, אכליה שפך 'cibus ejus ejectus,' is merely an illustration of the Rabbinic method of explaining an incomprehensible word by analysis (פָּרִישׁ 'dung' and טָרָה 'to cast out'), as is rightly noticed by Stu., Ber., No. The translator therefore had the same reading before him as that of פ.

‡ 'Schon Holzinger hat darauf aufmerksam gemacht, dass diese Aenderung in הפרש nicht ohne Bedenken ist, insofern הפרש gewöhnlich den Thiermist, nicht aber den Menschenkoth bezeichnet, man würde auch ein מִמְנו oder doch das Suff. am Subj. erwarten; endlich ist es auch nicht leicht zu verstehen, wie unter dem Einfluss von המסדרנה das urspr. הפרש in הפרשרנה verderbt werden konnte.' No. offers no explanation of the difficult word.

doors of the roof-chamber were locked: and they said, 'Surely he is covering his feet in the closet of the cool apartment.' 25. And they waited till they were ashamed; and, behold, he opened not the doors of the roof-chamber: so they took the key and opened them, and, behold, their lord was fallen down on the ground dead. 26. But Ehud had escaped while they tarried, and had passed the graven images, and escaped to Se'irah. 27. And when he arrived, he blew the trumpet in the hill-country of Ephraim, and the children of Israel went down with him from the hill-country, and he before them. 28. And he said unto them, 'Come down¹ after me, for Yahweh hath given

of the preceding imperfect with *wāw* consecutive: lit. 'and locking,' for 'and locked.' For this idiomatic construction, cf. Davidson, *Hebrew Syntax*, § 88; G-K. § 113 z. A precisely similar construction is found in *ch.* 7¹⁹, וַיִּתְּקֵנוּ בַשִּׁפְרוֹת וַנִּפְּוֹן הַפְּדִים, 'and they blew the trumpets and brake (lit. "and breaking") the pitchers.' Adopting this slight change of one vowel-point, there is no reason to suppose, with Mo., that the words 'are, as the false tense proves, the addition of a scribe, who, observing that the doors were locked (*vv.* 24. 25), missed an explicit statement here that Ehud locked them.'

24. *he is covering his feet.* The same euphemism is found in 1 Sam. 24³.

25. *till they were ashamed.* Or, 'to the point of confusion': Heb. עַד-בוֹשׁ. The expression here implies the perplexity and apprehension caused by an occurrence which is inexplicable. As we might say, they were *at their wit's end*. There are two other occurrences:—2 Kgs. 2¹⁷, 'they urged him till he was ashamed' (such was the importunity of the disciples that Elisha^a had no longer the *face* to refuse their request); 2 Kgs. 8¹¹, 'And he steadied his countenance, and set (it on him) till he was ashamed' (Elisha^a looked Hazeal out of countenance).

the key. A flat piece of wood with projecting pins corresponding to holes in the wooden cross-bolt into which the pins of the socket fall when the door is locked. When the key is inserted into a hollow in the bolt and pushed upwards, the pins of the key push up the pins of the socket, and the bolt is released. For a full description and illustrations, cf. *DB.* ii. p. 836.

26. *had passed, etc.* Cf. note on *v.* 19.

Se'irah. The site is unidentified.

28. *come down after me.* Reading רָדְפוּ אַחֲרַי with Ῥ Karάβητε ὁπίσω μου (cf. the following, 'and they came down after him'), in place of רָדְפוּ אַחֲרַי, which can only mean 'pursue after me.'

your enemies, even Moab, into your hand.' So they went down after him, and took the fords of the Jordan against Moab, and suffered no man to pass over. 29. And they smote of Moab at that time about ten thousand men, every stout and every valiant man; and there escaped not a man. 30. ^{R^{E2}} So Moab was subdued that day under the hand of Israel. And the land had rest eighty years.

R.V. renders 'Follow me'; but such a meaning for the verb cannot be paralleled.

took the fords, etc. Cf. *ch.* 7²⁴ (*note*), 12⁵. The *coup* was designed to prevent the escape of the Moabites who occupied Israelite territory west of Jordan (cf. *v.* 13^b), and at the same time to prevent the despatch of assistance to them from the land of Moab.

29. *And they smote, etc.* The statement implies that the army of occupation west of Jordan was cut to pieces, but scarcely (as ^{R^{E2}} seems to imply in *v.* 30) that the land of Moab was invaded and subdued.

30. *eighty years.* A round number representing, approximately, two generations.

3. 31. *Shamgar.*

It is quite clear that this brief notice formed no part of the Book of Judges as it left the hand of ^{R^{E2}}. The story of Ehud must have been directly connected by ^{R^{E2}} with *ch.* 4¹: 'And the children of Israel again did that which was evil in the sight of Yahweh, when Ehud was dead.' We miss, moreover, ^{R^{E2}}'s pragmatic introduction and conclusion, and no hint is given as to the length of the period of oppression or of the subsequent period of tranquillity.

The name of Shamgar the son of 'Anath is, however, certified as historical by its occurrence in the Song of Deborah, which alludes to the desolate condition of the country 'in the days of Shamgar the son of 'Anath' (*ch.* 5⁶); though, for all this passage tells us, Shamgar may have been a foreign oppressor (see below as to his name) and not an Israelite judge. The exploit recorded of Shamgar bears striking resemblance to that of one of David's heroes, Shammah the son of Agee (2 Sam. 23^{11ff.}), and also to Samson's feat with the jaw-bone at Ramath-lehi (*ch.* 15^{14ff.}). In all three cases the success is recorded to have been gained against the Philistines. It should be noticed, also, that the Song of Deborah, though mentioning Shamgar, says nothing about any encroachment of the Philistines, who seem at this point to appear too early in the narrative. It may be added that, since the Song deals with the Canaanite aggressions in N. Palestine, it is the less natural to connect Shamgar with the Philistines in the south.

The name Shamgar is certainly non-Israelite. It bears close resemblance to the Hittite Sangara or Sangar (*KB*. i. pp. 107, 159), which we find as the name of a king of Carchemish in the reigns of Ashurnasirpal and Shalmaneser III. (ninth century B.C.). It is perhaps worth noticing that some codd. of *F* read Sangar; and so *Jos. Ant.*, v. iv. 3 Σαράγας. 'Anath as the name of a goddess has been noticed under *ch.* 1³³. The use of the name as a masc. proper name, without such a prefix as *'ēbhedh* ('servant of 'A.': cf. Baethgen, *Beiträge*, pp. 52, 141), may seem strange to us, but is certainly not unusual (as stated by Mo.), since Anatum occurs several times among the names of the period of the first Babylonian dynasty: three occurrences are cited by Ranke, *Early Babylonian Personal Names*, p. 66, and three (one probably the name of a woman) by Thureau-Dangin, *Lettres et Contrats de l'époque de la première dynastie Babylonienne*, p. 15.* The name also occurs at the close of one of the T.A. Letters; *ana Anati šulma kibi*, 'To Anatu speak salutation' (No. 125 in Winckler's ed., *KB*. v. p. 236; No. 170 in Knudtzon's ed.).

Granted that *ch.* 3³¹ forms no part of R^{E2}'s history, it is a further question whether this allusion to Shamgar as a judge of Israel is due to the same hand as introduced the five 'minor' judges in *ch.* 10¹⁻⁵, 12⁸⁻¹⁵ (R^P: cf. *note* on 10¹⁻⁵). It is noteworthy that, according to R^P's scheme, the number of judges is twelve (the tribal number) without Shamgar; since R^P, who reintroduced the story of Abimelech into the book (pp. 263, 266, 268), clearly intended him to rank as a judge: cf. *ch.* 10¹, 'And there arose after Abimelech to judge Israel, etc.' Moreover, as Mo. remarks, the verse which tells Shamgar's brief story exhibits 'none of the distinctive formulas of the list 10¹⁻⁵, 12⁸⁻¹⁵'; and what is more conclusive, Shamgar is not embraced with them in the final chronological scheme of the book; neither the period in which he wrought deliverance for Israel nor its duration is given.† Thus it seems likely that the verse is an insertion made subsequently to the work of R^P; possibly, as Bu. suggests (*R.S.* p. 166, and *Comm.*), by a scribe who wished to dispense with the reckoning of the wicked Abimelech among the twelve judges. Notice, as a mark of the later hand, the גַּם-הוּא, 'he also saved Israel.' This interpolator probably extracted the name Shamgar the son of 'Anath from the Song of Deborah, upon the supposition that he was an Israelite hero, and may have based his exploit upon the similar

* If the termination *-atum* is really an hypocoristic affix, as is supposed by Ranke (*op. cit.* pp. 14 f.), it is possible that 'Anath, Anatum, used as a personal name, may be not really the name of the goddess, but an hypocoristic abbreviation of a personal name compounded with the name of the god Anu, e.g. Anum-malik, 'Anu counsels,' Anum-gamil, 'Anu spares,' etc. Cf. Sinatum, Sinnatum (Ranke, *op. cit.* pp. 153, 162), by the side of Sin-malik, Sin-gamil, etc.

† *Jos.* (*Ant.*, v. iv. 3) states that he died within a year of his election as judge, an assertion which is clearly intended to explain the absence of the usual chronological note.

1. G1 And after him came Shamgar, son of 'Anath, who smote of the Philistines six hundred men with an ox-goad. And he also saved Israel.

exploit of Shammah the son of Agee which we have already noticed.

Mo. (*Journal of the American Oriental Society*, 1898, p. 159) notices that certain recensions of G (codd. 44, 54, 56, 59, 75, 76, 82, 106, 134 HP.; *sub obel.* 121), together with S^h, Arm., Slav., have the account of Shamgar's exploit a second time after 16³¹. Here it appears with the introductory formula *καὶ ἀνέστη μετὰ τὸν Σαμψων Σεμεγάρ υἱὸς Ἐναν*, which corresponds closely to the formula of *ch.* 10¹, 'And there arose after Abimelech to save Israel,' etc. Comparing this with 'the awkward and unparalleled' *וַיְהִי אַחֲרָיו* (G *ἀνέστη*) of 3³¹, Mo. infers that the position and form of the reference to Shamgar, as it stands in 16³¹ in the authorities cited, is the more original:—'There is thus good reason to think that the verse at first stood after the story of Samson, and was subsequently, for some reason, removed to a place between Ehud and Barak.' More probably the notice, as it stands in 3³¹ W (depending, as we have seen, upon the allusion in 5⁶), was subsequently moved to a position after 16³¹ because it seemed to refer to the period of the Philistine domination; and the introductory formula was at the same time squared with that which is found in 10^{1,3}.

Nestle (*JTS.* xiii. pp. 424 f.) cites a chronicle (published by Lagarde, *Septuaginta Studien*, ii. pp. 21 ff.) which originated in the Vandalian Church of Africa in A.D. 463, as stating both that Shamgar of 3³¹ was an oppressor of Israel, and that Shamgar the Judge succeeded Samson.* These statements are (according to Nestle) of much greater antiquity than A.D. 463, that which places the judge Shamgar after Samson being at least as old as Julius Africanus (*cir.* 140 A.D.).

ox-goad. Heb. *milmadh hab-bāḳār*. The word *malmēdh* (assumed Absolute form) occurs only here, and must be supposed to denote literally 'instrument of instruction or training.' In Hos. 10¹¹ the verb from which it is derived, *limmēdh*, is used of *training* a heifer to the yoke. Elsewhere the word for 'goad' is *dorbhān*, 1 Sam. 13²¹ (also used in New Heb.), *dorbhōnā*, Eccles. 12¹¹. The modern Palestinian ox-goad is a wooden pole eight or nine feet long, shod at one end with a metal point and at the other with a metal blade for cleaning the ploughshare. Cf., for figures, *EB.* p. 78; *DB.* i. 49.

G^{AL}, ἐκτὸς μούσχων (τῶν) βοῶν, S^h, L, read מְלִמְדָּה for בְּמִלְמָד.

* After allusion to Ehud, the chronicle states, 'deinde servierunt regi Semegar annis xx. hic occidit ex alienigenis in aratro boum octingentos viros et defendit filios Israel.' The reference to Samson is followed by a second allusion to Shamgar, this time as Judge:—'Deinde Sampson filius Manoe . . . qui plus occidit in morte sua quam quod in vita sua. deinde Samera iudicavit eos anno uno hic percussit ex Allophylis sescentos viros praeter iumenta et saluum fecit et ipse Israel. deinde pacem habuerunt annis xxx.'

4. 1-5. 31. *Deborah and Barak.*

Besides the Commentaries, etc., quoted throughout the book, cf. Cooke, *The History and Song of Deborah*, 1892; Driver, in *Expositor*, 1912, pp. 24 ff., 120 ff.

R^{E2}'s hand is seen in the introduction, 4¹⁻⁴, which contains certain facts derived from the old narrative, and in the conclusion, 4^{23.24} 5^{31b}.

In the material employed by R^{E2} we are fortunate in possessing not merely a prose-narrative of presumably the same date as the other lengthy narratives relating to the exploits of the Judges (*ch.* 4), but also a poetical description which is generally accepted as a contemporary document (*ch.* 5),* and which must therefore be regarded as a peculiarly valuable picture of the condition of affairs during the period which followed the settlement in Canaan.

In both accounts the main facts are the same. Each opens with reference to a drastic oppression of Israel on the part of the Canaanites. Deborah, the 'mother in Israel' of the poem, is clearly the instigator of the effort to shake off the foreign yoke, just as Deborah the 'prophetess' is in the prose-narrative. In both Barak is leader of the Israelite troops against Sisera the leader of the Canaanites. In both, again, the battle and the rout of the Canaanites takes place in the plain of Megiddo, Sisera subsequently meets his death at the hand of a woman named Ja'el, and a period of pastoral prosperity follows upon Israel's victory.

There exist, however, a certain number of somewhat remarkable discrepancies between the two narratives, which we must proceed to notice. According to the prose-narrative, the principal oppressor of Israel was Jabin, king of Hazor in North Palestine, a city probably situated near the lake Huleh (doubtfully identified with the waters of Merom), and about three and a half miles south-south-west of Kedesh of Naphtali. This narrative states that the captain of Jabin's army was Sisera 'who dwelt at Harosheth of the nations,' i.e. probably el-Hârîyyeh on the right bank of the lower Kishon, and north-west of Megiddo. The fact is remarkable, however, that no mention of Jabin occurs in the poem, in which Sisera only is named. It is clear, too, that Sisera is there regarded not merely as the captain of the Canaanite army and the viceregent of a higher power, but as himself of kingly rank. His mother, when she is pictured as anxiously

* Cf. Wellh. *Comp.* 3 p. 213, n.: 'In proof that the Song is a contemporary composition, we may cite in the first place 5⁸, where the whole number of the fighting men of Israel is given as 40,000 (in the Pentateuch 600,000), and also the fierceness of the passion 5^{25.27}, and the exultation over the disappointed expectation of the mother, 5^{28ff.} "Only some one actually concerned, who had experienced the effrontery of an insolent oppressor directed against himself, could express himself with this glowing hatred over a dead foe; not a poet living some centuries later" (Studer, p. 166).' Such arguments as have been advanced against the contemporary character of the poem are insignificant: cf. Mo. pp. 129 f.; La. p. 114.

awaiting his return after the battle, is attended by princesses (5²⁹); and, if the emendation which is adopted in the last clause of *v.* 30 may be regarded as correct, it is stated that he will bring back with him 'two dyed embroideries for the neck of *the queen*,' i.e. for his mother or wife. Kings of Canaan are represented as taking part in the battle (*v.* 19); but they only receive brief mention, and are obviously subordinate to Šisera, whose fate occupies nearly a third of the whole poem.

There is also a striking difference in the two narratives as to the tribal connexions of Deborah and Barak. According to the prose-narrative, Deborah dwells between Ramah and Bethel in the hill-country of Ephraim, far to the south of the scene of action; while Barak belongs to Kedesh of Naphtali, west-north-west of lake Hûleh and not far from Haşor. In the poem, however, *v.* 15, though admittedly somewhat obscure, at any rate seems to indicate that both Deborah and Barak belonged to the tribe of Issachar, which, as occupying a region which extended southward from the plain of Megiddo (Josh. 19¹⁷⁻²³), was naturally a principal sufferer from the aggressions of the Canaanites.

Again, there is a difference as to the Israelite tribes which are said to have taken part in the battle. According to the prose-narrative, Barak is enjoined to take with him 10,000 men of the tribes of Naphtali and Zebulun only (*v.* 6); but from the poem we gather that a grand muster of all the tribes was attempted, with the exception of Judah and Siméon in the south, which were probably at this time remote from the interests of the other tribes (cf. p. 47). Those which responded to the summons, and bore their part in the combat, were the tribes surrounding the great plain, viz. Ephraim with Benjamin, Machir (i.e. West Manasseh), Zebulun, Issachar, and Naphtali (5^{14,15,18}).

It is also supposed by some scholars that there is a slight difference as to the scene of the battle. In the prose-account Barak sweeps down from Mount Tabor to the north of the plain, and the battle takes place on the right bank of the Kishon (*v.* 14-15). According to the poem, the scene is 'at Ta'anach by the waters of Megiddo' (*v.* 19), i.e., if regarded as a precise definition, on the left bank. This, however, if really a discrepancy, is a very minor point, and need not be taken seriously into account.

Lastly, a point which Wellh. (*Comp.*³ p. 217) regards as 'die Haupt-differenz' between the two narratives, and which has been made much of by a large number of scholars, is probably no discrepancy at all. According to the prose-narrative, when Šisera after his flight arrives at the tent of Heber the Kenite, Ja'el, Heber's wife, welcomes him with protestations of friendship, his request for a drink of water is met by the offer of curdled milk, and Ja'el allows him to lie down and sleep in the tent, undertaking herself to stand at the tent-door and put any chance pursuer off the track of the fugitive. As soon,

however, as Šisera is fast asleep, Ja'el takes a tent-peg and mallet, and going softly to him so as not to wake him, hammers the peg through his temples so forcibly as to pin his head to the ground. Most modern critics think that we have in the poem a different description of the death of Šisera. Here it is supposed that Ja'el is pictured as approaching him from behind as he is eagerly drinking, felling him with a blow from a mallet, and then beating his head to pieces. This view is based principally upon the line rendered in R.V. 'at her feet he bowed, he fell, he lay,' where the three verbs would accurately describe Šisera's coming down on his knees under the blow, falling forward on his face, and lying prone. It necessitates, however, a very forced explanation of the peg, יֵתֶר (a point rightly emphasized by Kue., La., and Kit., *GVI.*² ii. 79 *n*¹), making it to denote the wooden handle of 'the workman's mallet' (if that be the meaning of the Heb. expression). The statement 'She smote Šisera, crushed his head, shattered and struck through his temples' (זל.²⁶; see *note*) agrees well with the prose-account as describing the effects of driving a wooden peg through her victim's temples; whilst, had Šisera been struck down from behind, he would naturally have fallen on his face, in which case the smashing and piercing of his temples is not so easily explained. It may be added that the Heb. בֵּין רַגְלֶיהָ scarcely admits of the rendering 'at her feet.' It properly means 'between her feet' (*or* 'legs': cf. the only other sense in which the expression is used, Deut. 28⁵⁷), and rather describes Ja'el's straddling over Šisera's recumbent body in order to deliver the fatal blow than the idea that he fell prone 'at (*i.e.* before) her feet.' Probably the expression is intended to emphasize the indignity of his death. Thus it appears that it is unnecessary to find variation between the prose and poetical accounts as regards this event, beyond that which may naturally be referred to the licence of poetry.

Looking now at the prose-narrative alone, we cannot fail to notice that it contains serious internal discrepancies. Šisera, the captain of the host of Jabin, lives at a great distance from him (assuming that Ḥarosheth and Ḥaṣor are rightly identified), thirty-four miles in a direct line without taking account of the detours which are necessary in traversing a rugged and difficult country. Deborah, living between Ramah and Bethel (the former five miles, the latter ten miles, north of Jerusalem), sends to Barak at Kēdesh of Naphtali, more than ninety miles to the north. Barak musters his troops at Kēdesh in the heart of the enemy's country, and must have marched them unmolested close past the gates of Ḥaṣor in order to reach Mount Tabor, thirty miles to the south. After the rout of the Canaanites, Barak pursued the fugitives up to (עַר) Ḥarosheth, twelve miles or more west-north-west. Šisera meanwhile flees north-north-east towards Ḥaṣor, thirty miles distant; but instead of seeking safety in

the fortified city of his sovereign Jabin, he prefers to find it in the tent of a stranger, although this is quite close to Kēdesh (v. 11), and he must therefore have passed by Ḥaṣor in his flight. Here he meets his death; and Barak, in spite of the delay which his pursuit of Siṣera's army in a different direction might have been expected to cause, seems all the time to have been close on his heels; for the narrative apparently pictures him as arriving at Ja'el's tent shortly after the murder.

These difficulties for the most part disappear with recognition of the fact that Jabin king of Ḥaṣor has really no place in our narrative, but belongs to quite a different narrative which has been erroneously interwoven with it. The shadowy figure of Jabin plays no real part in the story. His position was plainly something of a puzzle to R^{E2}; for whereas the old narrative makes him 'king of Ḥaṣor' according to the theory of R^{E2} he was 'the king of Cana'an, who reigned in Ḥaṣor' (v. 2), *i.e.*, apparently, a kind of superior monarch who was overlord of the many petty kings of the Cana'anite cities. Yet we never hear elsewhere of Cana'an as a political unit. Kings of separate cities such as Jerusalem, Jericho, 'Ai, etc., are constantly mentioned, but never a king of Cana'an.

We meet with Jabin king of Ḥaṣor in Josh. 11¹⁻⁹, where he appears as head of a coalition of Cana'anite kings in North Palestine which was defeated by Joshua' near the waters of Merom. This narrative is derived in the main from JE (whether J or E is doubtful), but has been amplified by R^D in his usual manner (vv. 2 and 8^b), in order to intensify the magnitude of the coalition and the thoroughness of Joshua's conquest. It seems probable that the references to Jabin in Judg. 4 are reminiscent of the victory recorded in Josh. 11. Possibly the original form of this narrative may have made Zebulun and Naphtali the chief actors in the defeat of Jabin, *i.e.* it may have related a separate tribal movement akin to those which are recorded in the J document in Judg. 1, and possibly originally forming part of it. If this is so, a parallel may be found in the account of the conquest of Adoni-ṣedek in Josh. 10^{1ff.} as compared with that of Judg. 1^{5ff.} (cf. *note* on v. 5).

We have already noticed the discrepancy between the prose and poetical narratives as to the homes of Deborah and Barak. It is not unlikely that in *ch.* 4⁵ we may have a gloss introduced by a late hand confusing Deborah with another Deborah, Rebeḳah's nurse, who is recorded in Gen. 35⁸ to have been buried under an oak below Bethel. There was a city named Dābērath belonging to Issachar, Josh. 21²⁸, 1 Chr. 6⁷² (*¶* v. 57), one of the boundary-points between Issachar and Zebulun, Josh. 19¹², and this is identified with the modern Debūriyyeh at the west foot of mount Tabor. Possibly there may have been a connexion between the name of this city and the name of the prophetess. The fact that the name Kēdesh ('sanctuary') was applied to several different places has led some scholars to suppose that,

while Barak's city is rightly named Kedes̄h, an error has arisen as to the particular Kedes̄h in question. Thus Wellh., Reuss, Cooke think that the reference is properly to Kedes̄h of Issachar (Josh. 12²², 1 Chr. 6⁷², *ℳ* 2.⁵⁷), *i.e.* the modern Tell Abû Kudis, two and a half miles south-east of Tell el-Mutesellim (Megiddo), and about the same distance north of Ta'anach. Smith's objection (*HG.* p. 396 *n.*) that this Kedes̄h 'was too near the battle and too much under the hills of Manasseh for Šisera to flee there' is not very weighty; but a consideration which appears to be fatal to this theory is the strong improbability that Barak could have ventured with impunity to muster a large force of poorly armed Israelites (*ch.* 5^{sb}) within so short a distance of Ta'anach and Megiddo, two of the most important of the Canaanite fortified cities (*ch.* 1²⁷; cf. *ch.* 5¹⁹), and could then have marched his army across the open plain to Tabor thirteen miles to the north-east; this too at a time when travel was beset with the utmost danger and difficulty even for the peaceful and inoffensive wayfarer (*ch.* 5⁶). Conder (*Tent Work*, p. 69), mainly on the ground of a highly precarious identification of Baš'annim with the modern Beşşûm (cf. *note* on *ch.* 4¹¹), suggests that 'the Kedes̄h of the narrative where Barak assembled his troops' is the modern Kadiš* 'on the shore of the sea of Galilee, only twelve miles from Tabor'; and this view is favourably regarded by Smith (*loc. cit.*). But, taking into consideration the proximity of Kedes̄h of Naphtali to Haşor, the conclusion which most commends itself is that Kedes̄h properly belongs to the history of the Jabin-campaign which took place in the farther north (cf. Josh. 11^{1ff.}), and is therefore unconnected with our narrative. Indeed, the character of Barak's force of mountaineers, and the fact that they 'deployed' upon mount Tabor (cf. *note* on *ch.* 4⁶), make the supposition probable that this mountain (or possibly Daberath at its foot) was their first mustering place, and that they arrived at it in their tribal detachments, and (as mountaineers would naturally do) in open skirmishing order under cover of the night.

Supposing the view taken above to be the true explanation of the discrepancies between the prose and poetical narratives, the course of events appears to become reasonably clear. As Driver remarks, 'this view of the relation of Judg. 4 to Josh. 11 does not materially modify the picture which we form from Judg. 4 and 5 respecting Deborah and Barak, and their victory over Šisera: it leaves the general representation untouched, and merely bids us disregard a few elements in *ch.* 4 which have properly no connexion with Šisera.' There is no essential difference between the two accounts. The scene of action is laid in and about the plain of Megiddo. The Canaanites with their strong cities in and bordering on the plain (*ch.* 1²⁷) oppress the surrounding Israelite tribes. A deliverer is

* خربة قدیش (*sic*); cf. *SWP. Name Lists*, p. 128.

found in the tribe which, owing to its situation, had been the greatest sufferer. Possibly Barak had at one time been a captive in the hands of the Canaanites (cf. *ch.* 5^{12b} *note*), and therefore his call to action and readiness to obey the summons are the more easily to be understood.

As to the source from which the prose-narrative was derived—the indications of phraseology, so far as they go, seem to point to E. Thus we may notice *v.*⁴ אִשָּׁה נְבִיאָה, lit. 'a woman, a prophetess'; cf. אִישׁ נְבִיא 'a man, a prophet' in *ch.* 6⁸: *v.*⁹, 'for into the hand of a woman shall Yahweh sell Šisera' (the phrase is generally characteristic of R^{E2}, but is found in 1 Sam. 12⁹ E² with which R^{E2}'s connexion is very close: cf. *Introd.* xli ff.): וַיִּהְיֶה 'and Yahweh discomfited'; cf. 1 Sam. 7¹⁰, Ex. 14²⁴, Josh. 10¹⁰ (all E), Ex. 23²⁷ (JE or E), Deut. 2¹⁵. Cf. also the phrase, 'and all the people that were with him' with the same phrase in *ch.* 7^{13a} (apparently characteristic of the E narrator; cf. also 7^{2a.19}, 8⁴). It should further be noticed that 1 Sam. 12 (E²) presupposes a narrative of the oppression of Šisera (*v.*⁹), and also probably alludes to the deliverance effected by Barak (if we follow *Gr*, *S*¹ in reading Barak in *v.*¹¹ in place of the unknown Bedan). In *v.*¹¹ the allusion to Hobab (J's name) is doubtless a gloss derived from *ch.* 1¹⁰.

The fragments of the Jabin-narrative may be derived from J (as noticed above); but it is at least as probable that the combination of reminiscences of this campaign with the account of the victory of Deborah and Barak was effected when the story was still in the oral stage—in which case the narrative as a whole must be assigned to E.* We may notice that in 1 Sam. 12⁹ (E²) Šisera is already described as 'captain of the host of Haṣor'; but the assumption is open that these words may be a later gloss. Ps. 83⁹ combines Jabin with Šisera, but is probably not earlier than the post-exilic period.†

The poetical narrative, which was probably at first preserved in written form in a collection of poems compiled in the northern kingdom, may be reasonably supposed to have been subsequently incorporated in E.

4. 1. R^{E2} And the children of Israel again did that which was evil in the sight of Yahweh, when Ehud was dead. 2. And

4, 1. *when Ehud was dead.* R^{E2}'s narrative connects immediately on to the end of the story of Ehud, 3³⁰. Cf. *note* on 3³¹.

* An attempt at analysis has been made by Bruston, 'Les deux Jéhovistes,' *Revue de Théol. et Philos.* 1886, pp. 35 ff., but has not met with acceptance: cf. Bu. *RS.* 70, n².

† Similarly 'Oreb and Ze'eb are combined with Zebah and Šalmunna in *v.*¹¹, as in the present form of the Gideon-narrative. The Psalm is plausibly regarded by Cheyne as referring to the events narrated in 1 Macc. 5: cf. *Origin of the Psalter*, pp. 97 f.

Yahweh sold them into the hand of Jabin the king of Canaan, who ruled in Haşor; and the captain of his host was Šişera, and he dwelt in Harosheth of the nations. 3. And the children of

2. *Jabin the king of Canaan, etc.* R¹² states his view that Jabin was not simply 'king of Haşor,' as might be inferred from *v.*¹⁷ (cf. Josh. 11^{1ff.}), but 'king of Canaan,' i.e. overlord of the various city-kings of northern Canaan, whose royal city was Haşor. This statement is intended to explain the perplexing relationship of Jabin to Šişera: cf. *introd.* to the narrative, p. 81.

Haşor. This city is named in Josh. 19³⁶ among the cities assigned to Naphtali, and immediately precedes Kadesh in the list. The name is very possibly preserved in the modern name of the valley Merg ('meadow') el-Haḍireh, south-south-west of Kadesh on the northern side of the Wādy 'Auba which runs into the lake of Hūleh, and in Ġebel ('hill') Haḍireh immediately to the east of the 'meadow.' There are no traces of an ancient city upon this hill, and it is therefore supposed that Haşor may have been one of the ruined sites upon the hills still further east: cf. Buhl, *Geogr.* p. 236.

and the captain of his host, etc. The statement gives the narrator's view of the relationship of 'Šişera' of the one narrative to 'Jabin' of the other.

Šişera. The name has the appearance of being Hittite in origin. Cf., with the same termination, Sangara (noticed under *ch.* 3³¹), and Tarhulara, the name of a king of Gurgum in northern Syria who was a contemporary of Tiglath-pileser IV.: Rost, *Tiglath-pileser*, p. 13, *al.*; *KB.* ii. p. 21.* The resemblance of the name to Bab. *saseru*, *sisseru*, 'child or youth,' is rather striking (Delitzsch, *Prolegomena*, p. 199, *Rem.* 3), but may be merely accidental. The name Šişera occurs again in Ezr. 2⁵³ = Neh. 7⁵⁵ in a list of Nēthinīm (foreign Temple-slaves) who returned to the land of Judah after the Exile.

Harosheth of the nations. Probably el-Hārīḡiyeh, a large double mound on the northern bank of the Kishon, commanding the narrow passage between Carmel to the south and the hills of Galilee to the north, which connects the plain of Esdraelon with the plain of Acre: cf. Thomson, *LB.* pp. 436 f. Buhl's objection to this identification (*Geogr.* p. 214), on the ground that according to 4¹³ the city cannot have been situated near the Kishon, hardly seems to carry weight; and the circumstances of Šişera's rout as depicted in 5²¹ are entirely in favour of such a site: cf. *note ad loc.* The name Harosheth is probably connected with Heb. *hōreš* (1 Sam. 23^{15,16,18,19}, 2 Chr. 27⁴), Assy.

* We cannot follow Mo. and Cooke in adding the Hittite names cited by Müller (*AE.* 332) from Egyptian sources which appear to end in *-sira*, H-tā-si-ra, May-ra-si-ra, etc., since we now know from the cuneiform tablets discovered at Boghaz Keui (cf. *MDOG.* Dec. 1907) that the name which appears in Egyptian as H-tā-si-ra is really Hattušili, and May-ra-si-ra Muršili.

Israel cried unto Yahweh: for he had nine hundred chariots of iron; and he oppressed the children of Israel with rigour twenty years.

4. And Deborah a prophetess, the wife of Lappidoth—she was

ḥuršu or *ḥursu*, 'wooded (?) mountain-ridge' (cf. Delitzsch, *Prolegomena*, p. 180)—an appropriate description of the wooded hills of Galilee below which el-Ḥārīṭīyyeh is situated.*

The city was doubtless called *Ḥarosheth of the nations*, as a Canaanite city which formed, as it were, the gateway into the maritime plain which remained in the possession of the Phoenicians (*ch.* 1^{31.32}). Cf. the name 'district of the nations' noticed in *note* on *ch.* 1³³.

3. *chariots of iron.* Cf. *ch.* 1¹⁹ *note*.

twenty years. Approximately half a generation.

4. *Deborah.* The name means 'bee.' Mo. compares the Greek name *Μελισσα*, which was applied to the priestesses of Delphi, and to those of Demeter, Artemis, and Cybele: cf. references in Liddell and Scott *s.v.* On the possible connexion of Deborah with the city of Daberath, cf. *introd.* to section, p. 81.

the wife of Lappidoth. The fact that Lappidoth means 'torches,' or possibly 'lightning-flashes' (cf. Ex. 20¹⁸), while Barak is the ordinary term for 'lightning,' led Hilliger (*Das Deborah-lied*, Giessen, 1867) to make the precarious suggestion that Lappidoth and Barak are one and the same man, and that in the original form of the tradition Barak was the husband of Deborah. This view is favoured by Wellh. (*Comp.*³ p. 218), Bu. (*RS.* p. 69), Cooke.

she was judging. The verb *šāphaṭ* is here used (as commonly elsewhere in Heb.) in the sense in which we normally speak of 'judging,' *i.e.* (as explained in *v.* 5) of deciding cases between man and man. Since, however, R^{E2} regularly uses the verb in the sense 'vindicate,' or 'save' from a foreign oppressor (cf. *notes* on 2¹⁶, 3¹⁰), Mo. believes that this must have been the original sense in this passage; and since the participle *שֹׁפֵט* (expressing continued action—'was judging') would be inappropriate in this sense, he proposes to vocalize as a perfect, *שִׁפְטָהּ*—'it was she that judged (*i.e.* saved)

Israel at that time.' But if this sense had been intended, R^{E2}, who does not unnecessarily vary his phraseology, might naturally have

* The modern name Ḥārīṭīyyeh appears to mean 'ploughed or cultivated land,' the Heb. and Assyr. word noticed above being apparently unknown in Arabic. This fact, however, is no obstacle to the explanation of the Heb. name which is given in the *note*, or to the identification with el-Ḥārīṭīyyeh; since the substitution of a similarly sounding name for an old name of unknown meaning may very easily occur: cf. *note* on 'the rills of Megiddo,' *ch.* 5¹⁹.

judging Israel at that time. 5. Gl. And she used to sit under the palm tree of Deborah between Ramah and Bethel in the hill-country of Ephraim, and the children of Israel came up unto

been expected to have written יָרָקָם ו' יִשְׁפָּטָה, 'And Yahweh raised up a judge': cf. *ch.* 2¹⁶, 3^{9.15}.

5. *she used to sit.* The verb *yāšabh* is used in the sense of presiding as judge. Cf. 1 Kgs. 21⁸, 'who presided (lit. *sat*) with Naboth' (so *v.* 11); Isa. 28⁶, 'for him that presides (*sits*) over the judgment'; Ps. 9⁷ (*39 v.* 8), 'Yahweh *sitteth* for ever' (cf. the parallel clause, 'He hath prepared his seat for the judgment'); Am. 6³, 'the *seat* of violence' (*i.e.* of unjust judgment). R.V.'s rendering, '*she dwelt* under the palm-tree' is therefore inadequate and misleading. The tree was doubtless a sacred tree under which the oracle of Yahweh might be expected to be ascertained. Such a tree is seen in the *ēlôn mōré*, 'terebinth of the oracle(*tōrā*)-giver' near Shechem, Gen. 12⁶J, which is perhaps the same as the *ēlôn mō'ôn nām*, 'terebinth of the soothsayers' mentioned in Judg. 9³⁷.

the palm-tree of Deborah. Deborah, Rebekah's nurse, is stated in Gen. 35⁸E to have been buried under an oak (Heb. *'allôn*) below Bethel; and hence the tree became known in later times as *'allôn bakhūth*, 'the oak of weeping' (cf. 2⁶ *note*). This tree, as Ewald points out (*HL*. iii. p. 21, *n*⁴), appears to be alluded to again in 1 Sam. 10³ as 'the terebinth (Heb. *'ēlôn*) of Tabor'; since it can scarcely be doubted that 'Tabor' (תָּבוֹר) is an error for 'Deborah' (דְּבוֹרָה). The context shows that the tree was on the way to Bethel and not far from Ramah; whereas Tabor lies more than fifty miles to the north. The difference between *'allôn* and *'ēlôn* is one of vowel-points merely.

We have already noticed that the allusion in our passage to 'the palm-tree of Deborah between Ramah and Bethel' seems to be based upon a late confusion between the two Deborahs (cf. *introd.* to section). Whether the palm-tree (Heb. *tōmer*) of Deborah can be the same as the famous tree of the two other passages is somewhat more doubtful. Evidence seems to show that, throughout the O.T., the words *'allôn*, *'allā* are generally used to denote the oak (of various species), and *'ēlôn*, *'ēlā*, the terebinth (cf. *EB*. 4975); but it is not impossible that these terms may have been used at times to describe other kinds of tall and conspicuous trees. In favour of such a possibility it may be noticed (1.) that the Aram. *'ilānā* (the equivalent of Heb. *'ēlôn*) denotes 'tree' in general; and (2.) that the name *'ēlīm* (the plur. of *'ēlā*), which occurs as a place-name in the narrative of the wilderness-wanderings (Ex. 15²⁷), is apparently so-called because there were seventy *palm-trees* there. Cf. Wellh., *Prolegomena*, p. 234 *n*.

Ramah. The modern er-Rām, five miles due north of Jerusalem.

Bethel. Cf. *note* on *ch.* 1²³.

her for judgment. 6. E And she sent and called Barak the son of Abino'am from Kedesh of Naphtali, and said unto him, 'Hath not Yahweh the God of Israel commanded, "Go, and open out upon mount Tabor, and take with thee ten thousand men of the

6. *Barak*. Cf. *note* on Lappidoth, v.⁴. The Punic Barcas, the surname of Hamilcar, has been compared; and also the Sabaeen ברקם and Palmyrene ברק. Cf. references in BDB. p. 140.

Kedesh of Naphtali. The modern Kadis, four miles west-north-west of the lake of Hûleh, and about three miles north-east of Merg' el-Haḍîreh (cf. *note* on Haṣor, v.²).

open out. The Hebrew verb *māšak* means to *draw out* or *extend*, and is used both intransitively and transitively. The passages in which the verb is intransitive are Job 21³³, R.V., 'and all men shall draw after him,' where the idea seems to be that of a long-extended or never-ending line (cf. Shakespeare, *Macbeth*, iv. 1, 'What! will the line stretch out till the crack of doom?'); and the present passage and *ch.* 20³⁷, where the expression is used in a military sense. In the latter passage the meaning can scarcely be mistaken, for here the verb is used of the manner in which the ambush advanced against the city of Gibé'ah in order to capture it. *Extension into column* would be out of place as a fighting formation; therefore *extension* or *opening out into line* must be what is intended; *i.e.* into loose skirmishing order such as would be best adapted for the attack of light-armed mountain troops. The modern military term is *deploy*, from the French *déployer*=Latin *displicare*. The verb *māšak* in this sense has been conjecturally restored in *ch.* 5^{14a}.

The same verb is used in its transitive sense in v.⁷, 'And *I will draw out* unto thee, etc.' Here the sense may be 'cause to advance in a similar extended order,' or, more probably, 'draw forth' or 'attract.'

upon Mount Tabor. The rendering 'open out *upon*, etc.' preserves the ambiguity of the preposition ב in the Hebrew; the sense being either 'advance in open order (so as to come) upon mount Tabor' (prep. of rest after verb of motion), *i.e.* mount Tabor is the objective of the movement described by the verb: or 'when upon mount Tabor, open out'; *i.e.* mount Tabor is the point from which this strategic movement preparatory to advancing into the vale is to commence.

Mount Tabor is doubtless the modern Ġebel eṭ-Ṭôr ('mountain') on the north-east side of the plain of Esdraelon. Its altitude is only 1843 feet, and it rises 1312 feet above the plain; but it forms a very conspicuous object owing to its isolation and its peculiar domed shape which is noted by Jerome (*O.S.*, 156³³); 'est autem mons in medio Galilaeae campo mira rotunditate.' As Smith remarks *HG.* p. 394), 'It is not necessary to suppose that Barak arranged his

sons of Naphtali and of the sons of Zebulun? 7. And I will draw out unto thee unto the wâdy Kishon Šisera, the captain of Jabin's host, with his chariots and his multitude, and I will give him unto thine hand." 8. And Barak said unto her, 'If thou

men high up Tabor; though Tabor, an immemorial fortress, was there to fall back upon in case of defeat. The headquarters of the muster were probably in the glen, at Tabor's foot, in the village Debûriyyeh.²

of the sons of Naphtali, etc. The poem, *ch.* 5, differs in describing a general muster of the tribes. Cf. *introd.* to the present narrative, p. 79.

7. *the wâdy Kishon.* The Hebrew term which is here represented by the Ar. *wâdy* is *nâḥal*. Both the Arabic and Hebrew terms denote a winter-stream or torrent (ἢ χεῖμαρρος), or the valley-bed of such a stream, which may vary from an insignificant depression to a precipitous ravine (such as is seen, *e.g.*, in the wâdy Kelt), which marks the action of water at a period when the rainfall of Palestine was much heavier than it is at present.

It is only the larger streams of this character (*e.g.* the Yarmuk, Jabbok, and Arnon) which constantly contain an abundant flow of water. Many of them fail in the summer-months, leaving the valley-bed dry, or nearly so; but in winter they may possess considerable volume, and are liable after storms or lengthy rains to swell suddenly to the dimensions of swift and dangerous torrents. Many wâdys, again (*e.g.* the Kïdron), though of considerable depth, are now quite dry, or only occasionally contain a little water. A.V., R.V., render *nâḥal* variously by 'brook,' 'stream,' 'river,' 'flood,' 'valley.' The Ar. term *wâdy* is here adopted as preserving the same ambiguity as is possessed by the Hebrew term. Cf. further, *Addenda*, p. xiii.

The character of the wâdy Kishon is described by Thomson (*LB.* p. 435). Its higher reaches are fed by the winter-streams which descend from the hill-country to the south of the great plain; but the most important source is the perennial spring of Genin ('En-Gannim), which, however, is insufficient to provide a constant flow during summer and autumn. 'I have crossed,' says Thomson, 'the bed of the Kishon (even after it enters the plain of Acre) in the early part of April, when it was quite dry. The truth is, that the strictly permanent Kishon is one of the shortest rivers in the world. You will find the source in the vast fountains called Sa'adiyah, not more than three miles east of Haifa. They flow out from the very roots of Carmel, almost on a level with the sea, and the water is brackish. They form a deep, broad stream at once, which creeps sluggishly through an impracticable marsh to the sea; and it is *this* stream which the traveller crosses on the shore. Of course, it is largely swollen during the great rains of winter by the longer river from the interior.'

wilt go with me, I will go ; but if thou wilt not go with me, I will not go.' 9. And she said, 'I *will* go with thee : howbeit, glory shall not accrue to thee upon the course which thou art taking ; for into the hand of a woman shall Yahweh sell Šisera.' So Deborah arose, and went with Barak to Kēdesh. 10. And Barak summoned Zebulun and Naphtali to Kēdesh ; and there went up after him ten thousand men : and Deborah went up with

8. '*If thou wilt go, etc.*' 'The presence of the prophetess will not only ensure to him divine guidance (2. 14), but give confidence to him and his followers' (Mo.). E makes Barak add a reason for his demand : *ὅτι οὐκ οἶδα τὴν ἡμέραν ἐν ᾗ εὐοδοῖ τὸν ἄγγελον Κύριος μετ' ἐμοῦ.*

The fact that this sentence is clearly an incorrect * translation of *אֲנִי יְהוָה מֵאֲנִי הַצֶּלֶת מִלְאָךְ* 'for I know not the day whereon the Angel of Yahweh shall prosper me,' proves that the translator must have had a Hebrew original before him ; but Bu., Mo. (SBOT), No. are probably right in regarding this as an early gloss, intended to obviate an unfavourable interpretation of Barak's demand. E's paraphrase of 2. 14a^β is very similar : *הֲלֹא מִלֵּאכֶנָּה דִּיהוָה נִפְקָא לְאַעְלָחָא קֳדָמְךָ* 'Hath not the angel of Yahweh gone forth to make [thy way] prosperous before thee?' The phrase, 'the Angel of Yahweh' (a J phrase) is somewhat unexpected, if the narrative is rightly assigned to E ; and seems, moreover, to presuppose 5 23a, where metrical reasons compel us to regard it as due to textual alteration. The passage is accepted by Houbigant, Grätz, Stu., Franken-berg, La.

9. *howbeit, glory, etc.* In spite of Mo.'s contention that the context betrays no sign of disapproval, it is difficult to escape the common impression that the unpalatable information is produced by the prophetess at this juncture in consequence of Barak's want of alacrity in accepting the divine mandate. As La. paraphrases, 'You wish for a woman's help, and it is a woman (though a different one) who shall have the honour.'

to Kēdesh. Upon the view that the Kēdesh here referred to is not Kēdesh of Naphtali, but another Kēdesh nearer to the scene of the battle, cf. *introd.* to chapter, p. 82.

10. *after him.* Lit. 'at his feet,' *i.e.*, as we might say, 'at his heel.' So 5 15, 8 5, *al.*

* The translator reads *מִלְאָךְ* (*St. Absol.*) and treats it as object of the verb, making *יהוָה* the subject ; while regarding *אֲנִי* (accus. 'me') as the prep. 'with me.'

him. 11. Now Heber the Kenite had separated himself from Kain, Gl. from the sons of Hobab, Moses' father-in-law, E and had pitched his tent as far away as the terebinth of Baʿannim¹ which is near Kedesh. 12. And they told Sisera that Barak the son of Abino'am had gone up to Mount Tabor. 13. And Sisera summoned all his chariots, even nine hundred chariots of iron, and all the people who were with him, from Harosheth of the nations unto the wādy Kishon. 14. And Deborah said unto Barak, 'Arise; for this is the day whereon Yahweh hath given Sisera into thine hand: hath not Yahweh gone forth before

11. *had separated himself from Kain.* The statement explains how a member of a clan which normally inhabited the Negeb (cf. 1¹⁶) came to be found in northern Canaan.

Hobab, Moses' father-in-law. R.V. text 'brother-in-law,' quite unwarrantably: cf. note on 1¹⁶.

the terebinth of Baʿannim. Vocalizing אֵלֹן בְּצַעְנַיִם, in place of אֵלֹן בְּצַעְנַיִם (cf. Josh. 19³³), R.V. 'the oak (*marg.* terebinth) in Za'ananim,' where ב is regarded as the preposition. If this had been intended, however, we should have expected אֵלֹן הָאֵלֹן (with the article) 'the (well-known) terebinth';* not simply אֵלֹן, which can only mean 'a terebinth.' The locality (otherwise unknown) is described in Josh. 19³³ as on the border of Naphtali; a fact which suggests, as Mo. remarks, that Heber the Kenite belonged originally to the story of Jabin.

Conder (*SHP. Mem.* i. pp. 365 f.; *Tent Work*, p. 69) identifies Baʿannim with the modern Beṣṣûm, four miles west of the Kadiš which is south-west of the sea of Galilee. There is not, however, any philological connexion between the names; and the proposed identification depends partly upon the view with regard to Kedesh which we have noticed in the *introd.* to the chapter (viz. that it is not Kedesh in Naphtali, but another Kedesh nearer to the scene of the battle), and partly upon the fact that A.V. renders 'êlôn 'terebinth' erroneously as 'plain,' and there is a plain (Ar. *sahel*) called el-Aḥmâ close to the south of Beṣṣûm.†

14. *hath not Yahweh gone forth before thee?* The scene gains

* Mo. compares הָאֵשֶׁל בְּרָמָה 'the tamarisk in Ramah,' 1 Sam. 22⁶, 31¹³, הָאֵלֹה אֲשֶׁר בְּעַפְרָה 'the terebinth which is in Ophrah,' ch. 6¹¹, etc.

† Driver (*Expositor*, Jan. 1912, p. 32, n²) exposes the manner in which the extraordinary error which identifies 'the plain (!) of Zaanaim' with the plain called Sabel el-Aḥmâ has penetrated into several modern maps.

thée?' So Barak went down from mount Tabor, and ten thousand men after him. 15. And Yahweh discomfited Sisera, and all his chariots, and all his army, at the edge of the sword before Barak; and Sisera alighted from his chariot, and fled away on foot. 16. And Barak pursued after the chariots and after the army as far as Harosheth of the nations: and all Sisera's

much in vividness if we may suppose (with Thomson, *L.B.* p. 436) that Deborah, as she speaks, points to the gathering storm, which appears to have burst in the face of the foe at the commencement of the battle: cf. *ch.* 5 ^{4,5,20,21} (*notes*); *Jos. Ant.* v. v. 4. Yahweh's connexion with the phenomena of the storm, especially when He goes forth to battle before His people, is well marked in the O.T.: cf. *Josh.* 10¹¹, 1 *Sam.* 7¹⁰, *Ps.* 18^{9 ff.}, etc., and the present editor's discussion in *JTS.* ix. p. 326.

15. *at the edge of the sword.* The phrase לפי חרב (on which cf. *note* on 1⁸) may possibly here be a corrupt dittography of the following לפני ברק, 'before Barak'; but Mo. goes too far when he states that it 'appears incongruous with the verb' (ויהם, 'discomfited').*

16. *And Barak pursued, etc.* The circumstances of the rout appear to have been as described by Thomson (*L.B.* p. 436):—'The army of Sisera naturally sought to regain the strongly fortified Harosheth of the Gentiles, from which they had marched up to their camping-ground a short time before. This place is at the lower end of the narrow vale through which the Kishon passes out of Esdraelon into the plain of Acre, and this was their only practicable line of retreat. The victorious enemy was behind them; on their left were the hills of Samaria, in the hand of their enemies; on their right was the swollen river and the marshes of Thora; they had no alternative but to make for the narrow pass which led to Harosheth. The space, however, becomes more and more narrow, until within the *pass* it is only a few rods wide. There, horses, chariots, and men become mixed in horrible confusion, jostling and treading down one another; and the river, here swifter and deeper than above, runs zigzag from side to side of the vale, until, just before it reaches the castle of Harosheth, it dashes sheer up against the perpendicular base of

* In the other occurrences of the phrase, it is used with the following verbs:—הכה 'smite,' *Num.* 21²⁴; *Deut.* 13^{16a}, 20¹³; *Josh.* 8^{24b}, 10^{28,30,32,35,37,39}, 11^{11,12,14}, 19⁴⁷; *Judg.* 1^{8,25}, 18²⁷, 20^{37,48}, 21¹⁰; 1 *Sam.* 22¹⁹; 2 *Sam.* 15¹⁴; 2 *Kings.* 10²⁵; *Jer.* 21⁷; *Job* 1^{15,17}; הרג 'slay,' *Gen.* 34²⁶; החליט (?) חליט 'render prostrate,' *Ex.* 17¹³; החרים 'ban' or 'utterly destroy,' *Deut.* 13^{16b}; *Josh.* 6²¹; 1 *Sam.* 15⁸; נפל 'fall,' *Josh.* 8^{24a}, *Judg.* 4¹⁶⁺. It therefore appears not inappropriate after יהם 'discomfit.'

army fell at the edge of the sword; there was not left so much as one. 17. But Šišera fled away on foot unto the tent of Ja'el, the wife of Heber the Kēnite: for there was peace between Jabin king of Ḥaṣor and the house of Heber the Kēnite. 18. And Ja'el came out to meet Šišera, and said unto him, 'Turn in, my lord, turn in unto me; fear not.' So he turned in unto her into

Carmel. There is no longer any possibility of avoiding it. Rank upon rank of the flying host plunge madly in, those behind crushing those before deeper and deeper into the tenacious mud. They stick fast, are overwhelmed, are swept away by thousands. Such are the conditions of this battle and battle-field that we can follow it out to the dire catastrophe.' Doubtless the storm (cf. *note* on *v.*¹⁴) was responsible for the sudden swelling of the Kishon, and the reduction of the plain surrounding it to a quagmire, in a manner which has frequently been observed by travellers. Cf. also Smith *HG.* p. 395; Ewing in *DB.* iii. p. 5*a*.

17. *unto the tent of Ja'el.* Šišera's refuge cannot have been greatly remote from the scene of the battle; especially since *v.*²² represents Barak as not far behind in pursuit, though having previously accomplished the rout of the Canaanite army before Ḥarosheth. Cf. the discussion in *introd.* to the chapter, pp. 80 f.

18. *Turn in.* Or, perhaps, more correctly, 'Turn aside.' Ja'el persuades Šišera to desist in his flight, and take shelter in the tent, without his previously having asked admission.

a fly-net. The Heb. word, *sēmikhā*, is a ἀπαξ λεγόμενον, and the meaning adopted is based upon philological considerations, and accords with the context.* A net to keep off the flies would be more essential for the rest and comfort of a hot and weary man than anything of the nature of a rug or coverlet. Ἑ^B ἐπιβολαίφ, Ἑ^{AL} ἐν τῇ δέρρει αὐτῆς 'with her leathern covering' (a rendering commonly used elsewhere to translate יריעה 'tent-curtain'; so 𐤁𐤍𐤔𐤁𐤀, 𐤁𐤍𐤔𐤁𐤀, 𐤁𐤍𐤔𐤁𐤀 'in pelle sua,' 𐤁𐤍𐤔𐤁𐤀 'pallio,' 𐤁𐤍𐤔𐤁𐤀 'with the coverlet,' 𐤁𐤍𐤔𐤁𐤀, *id.*, Ar. بالمطیفة *id.*; A.V. 'mantle,' *marg.* 'rug or blanket,' R.V. 'rug.' All these appear to be guesses guided by the context. Grä.'s emendation 𐤁𐤍𐤔𐤁𐤀, 'with a coverlet,' is unnecessary.

* An original biliteral שך, שך 'interweave,' 'intertwine,' appears both as the י"ע form שוך, שוך, and as the ע doubled שכך, שכך. There can be no doubt that the ש"ך, whence ש"כך 'net-work' (as interwoven) represents the same root internally triliteralized by the labial כ which is akin to ו; cf. ש"ך and ש"ך, both meaning 'skirts,' from an original biliteral ש"ך, ש"ך, from ש"ך, may exhibit the same root ש"ך internally triliteralized by כ, which is also close akin to ו; cf., for the same internal triliteralization, Bab. *namāru* by the side of Heb. נור, both meaning 'shine.'

the tent, and she covered him with a fly-net. 19. And he said unto her, 'Give me, I pray thee, a little water, for I am thirsty'; and she opened her bottle of milk, and gave him to drink, and covered him. 20. And he said unto her, 'Stand¹ at the door of the tent, and it shall be, if any man come and ask thee, and say, "Is there any man here?" that thou shalt say, "No."' 21. Then Ja'el the wife of Heber took a tent-peg, and took a hammer in her hand, and approached him softly, and struck the peg into his temple, and it went down into the ground; for he was fast asleep¹ and exhausted¹: so he died. 22. And, behold,

19. *a bottle of milk.* The beverage is described in 5²³, in one clause as milk, in the other as *ḥen'ā* 'curds,' i.e. the *leben* which is the choicest drink of the modern Bedawin, and is said to be most delicious and refreshing, but to possess a strongly soporific effect: cf. Conder, *Tent Work*, pp. 69 f.

20. *Stand.* Reading fem. עֹמֵד in place of masc. עֹמֵד. Ehr.'s proposal to point as Infin. Absol. עֹמֵד, used, as occasionally elsewhere, in place of the Imperative, is possible: cf. Davidson, § 88 *b*; G-K. § 113 *bb*.

21. *Then Ja'el, etc.* On this account of the death of Šišera, as compared with that which is given in the poem, 5^{26,27}, cf. the discussion in *introd.* to chapter, pp. 79 f.

a tent-peg. The peg would be made of wood, and the hammer would be a heavy mallet, also of wood, as at the present day. 'Among the Bedawin, pitching the tent is woman's business, and so no doubt it was in ancient times; the mallet and pin were accustomed implements, and ready to hand' (Mo.).

for he was fast asleep. In place of this E^{AL} renders $\kappa\alpha\iota\ \alpha\upsilon\tau\omicron\varsigma\ \acute{\alpha}\pi\epsilon\sigma\kappa\acute{\alpha}\mu\iota\sigma\epsilon\nu$ ('made a convulsive movement') $\alpha\upsilon\tau\omicron\ \mu\acute{\epsilon}\sigma\sigma\omicron\nu\ \tau\omicron\omega\nu\ \gamma\omicron\nu\acute{\alpha}\tau\omega\nu$ (E^{L} $\pi\omicron\delta\delta\omega\nu$) $\alpha\upsilon\tau\eta\varsigma$. This seems to represent a paraphrastic attempt at interpretation of the somewhat uncommon נרדם (E^{B} $\acute{\epsilon}\xi\epsilon\sigma\tau\acute{\omega}\varsigma$) in the light of *ch.* 5²⁷.

and exhausted Vocalizing וְיָעֵף with Mo., Bu., No., in place of וְיָעֵף or וְיָעֵף, which, in spite of the prevalent accentuation*

* According to Kit., *BH.*, 4 MSS. place the pause upon נרדם and connect וְיָעֵף with וְיָמַת. A.V. renders the sentence 'for he was fast asleep and weary. So he died,' and similarly R.V. *margin*. (with the variation 'in a deep sleep'): but it must be emphasized that, as וְיָעֵף is pointed in וְיָעֵף, it cannot denote a state existing coincidentally with that which is described by the participle נרדם 'fast asleep'; but only some further resultant state, the וְ *consec.* having the force 'and so.'

as Barak was pursuing Sisera, Ja'el came out to meet him, and said to him, 'Come, and I will show thee the man whom thou art seeking.' And he came in unto her; and, behold, Sisera was fallen down dead, and the peg was in his temple. 23. ^{RE2} So God subdued on that day Jabin the king of Canaan before the children of Israel. 24. And the hand of the children of Israel bore more and more severely upon Jabin the king of Canaan, until they had destroyed Jabin the king of Canaan.

(connecting with the preceding והוא נרדם rather than with the following וימת), can only be understood (as by R.V. *text*) in connexion with what follows: 'so he swooned and died.' But to speak of a man whose head had been practically shattered by the tent-peg as swooning before death ensued, appears almost ludicrous.

23. *So God subdued, etc.* The concluding formula of R^{D2}. In this passage only we get the active verb with subject God (*ʿēlōhīm* a mark of the E school; but variants exist in G: cf. Kit., BH.) in place of the passive, 'was (were) subdued,' *ch.* 3³⁰, 8²⁸, 11³³.

24. *until they had destroyed, etc.* It can scarcely be doubted that R^{E2} (like R^D in Josh.) tends to exaggerate the far-reaching effects of the victory. So far as the old narrative is concerned, it does not even mention the capture of the city of Harosheth.

5. 1-31. *Deborah and Barak: the triumph-song.*

Besides the Commentaries, etc., quoted throughout the book, and the authorities cited at the head of the *introd.* to 4¹⁻⁵³¹, cf.* C. F. Schnurrer, *Dissertatio inauguralis philologica in Canticum Deborahae*, 1775; republished in *Dissertationes philologico-criticae*, 1790, pp. 36-96 (his discussions are marked by learning and good sense): J. B. Köhler in Eichhorn's *Repertorium für Biblische und Morgenländische Litteratur*, vi. 1780, pp. 163-172 (a criticism of Schnurrer. Translation and very brief notes): J. G. von Herder, *Briefe das Studium der Theologie betreffend* (1780), 4^e Ausg. 1816, i. pp. 65-75 (a literary appreciation); *Vom Geist der ebräischen Poesie* (1783), 3^e Ausg. von K. W. Justi, 1825, pp. 237-243 (translation with scanty notes): G. H. Hollmann, *Commentarius*

* The compilation of a list of nineteenth-century authorities upon the Song necessarily goes back to Schnurrer at the end of the eighteenth century; since this scholar's work is very outstanding, and has had considerable influence upon his successors. For earlier writers, cf. Justi, as noticed above, and Bachmann, pp. 298 f. Reuss, in his *Geschichte der heil. Schrift. A. T.*, names a considerable number of additional nineteenth-century writers on the Song; but the present editor has not been able to find their works, either in the Bodleian Library, or in Dr. Pusey's library, which Dr. Darwell Stone, Principal of Pusey House, has kindly made accessible to him. The fact, however, that these writers are either not cited at all, or only very occasionally cited, by subsequent scholars, may perhaps justify the assumption that their contributions to the study of the Song are of no special importance.

philologico-criticus in Carmen Deborah, 1818 (very scholarly and thorough): K. W. Justi, *National-Gesänge der Hebräer*, ii., 1820, pp. 210-312 (he gives, pp. 117-225, a full list of earlier writers on the subject from the commencement of the eighteenth century; and his commentary offers a serviceable conspectus of their opinions): H. Ewald, *Die Dichter des Alten Bundes* (1839), neue Ausarb. 1866, pp. 178-190 (his translation often happily reproduces the original rhythm. Very brief notes): G. Boettger, *Commentarius exegetico-criticus in Deborah canticum*, in Käufer's *Biblische Studien*, i. pp. 116-128, ii. pp. 81-100, iii. pp. 122-148 (down to v. ²³), 1842-4 (he adds little or nothing to the work of earlier scholars); J. von Gumpach, *Alttestamentliche Studien*, 1852, pp. 1-138 (lengthy, but not very discriminating): J. G. Donaldson, *Jashar*, 1854, pp. 237-240, 261-289 (comments of no special value): E. Meier, *Uebersetzung und Erklärung des Debora-Liedes*, 1859 (his comments are often suggestive): G. Hilliger, *Das Deborah-Lied übersetzt und erklärt*, 1867 (he makes no special contribution of his own): A. Müller, *Das Lied der Deborah; eine philologische Studie*, in *Königsberger Studien*, 1887, pp. 1-21 (a protest against the attempt to extract a rendering from a corrupt text at all costs—having mainly in view the second edition of Bertheau's commentary on Judges, which appeared in 1883); M. Vernes, *Le cantique de Débora*, in *REJ.* xxiv. 1892, pp. 52-67, 225-255 (he regards the Song as a very late production—not earlier than the fourth or third century B.C.—based upon the prose-narrative in *ch.* 4): C. Niebuhr, *Versuch einer Reconstellation des Deborahliedes*, 1894 (highly fanciful*): H. Winckler, *AF.* i. (1893-97), pp. 192 f., 291 f.; *GL.* ii., 1900, pp. 127-135 (many original, but not very convincing, emendations); P. Ruben, *JQR.* x. (1898), pp. 541-558 (emendations based on very rash philologizing): K. L. Stephan, *Das Debora-Lied*, 1900 (his original suggestions are not happy): A. Segond, *Le cantique de Débora*, 1900 (painstaking, but fails at crucial points): V. Zapletal, *Das Deborahlied*, 1905 (he deals somewhat arbitrarily with the text in order to produce a uniform scheme of three-beat stichoi; and his Hebrew forms and constructions are often very curious): Ed. Meyer, *IN.* pp. 487-498.

On the metrical form of the poem, cf. J. Ley, *Die metrischen Formen der hebräischen Poesie systematisch dargelegt*, 1866, pp. 160-171; *Grundzüge des Rhythmus, des Vers- und Strophenbaues in der hebräischen Poesie*, 1875, pp. 214-219; G. Bickell, *Carmina Veteris Testamenti metrice*, 1882, pp. 195-197; *Dichtungen der Hebräer*, i., 1882, pp. 27-31; C. J. Ball, *The formal element in the Hebrew Lyric*, 1887; H. Grimme, *Abriss der biblisch-hebräischen Metrik*, in *ZDMG.* 1896, pp. 572-578; J. Marquart, *Fundamente israelitischer und jüdischer Geschichte*, 1896, pp. 1-10; D. H. Müller, *Der Aufbau des Debora-Liedes*, in *Actes du XI^e Congrès Internat. d'Orientalistes*, 1897 (1898), iv. pp. 261-272; E. Sievers, *Studien zur hebräischen Metrik* (part i. of the writer's *Metrische Studien*, 1901), pp. 418 ff.; J. W. Rothstein, *Zur Kritik des Deborahliedes und die ursprüngliche rhythmische Form desselben*, in *ZDMG.*, 1902, pp. 175-208;

* The poem, in its original form, is thrown back by Niebuhr into the fourteenth century B.C. Sisera becomes a king of Egypt—Sesu-ra, the (supposed) last representative of the Eighteenth Dynasty; who revived Aḥnaton's cult of the Solar-disk, which had been abandoned for the old religion of Egypt under Sesu-Ra's predecessors, Amen-tut-anḥ and Ay; and whose accession was signalized by a combined attempt of the kings of Canaan to throw off the Egyptian yoke ('<Sisera, king of Egypt>, chose new gods; then was there war at the gates <of Egypt>'). Sesu-Ra is supposed to have quelled the Canaanite opposition; but subsequently to have suffered defeat at the hands of the Hebrew tribes under Barak. It goes without saying that the text of the poem has to undergo somewhat violent treatment before this view of affairs can be extracted from it.

437-485; 697-728; 1903, pp. 81-106; 344-370; N. Schlögl, *Le chapitre V du livre des Juges*, in *RB.*, 1903, pp. 387-394 (a common-sense criticism of Rothstein); E. G. King, *Early Religious Poetry of the Hebrews*, 1911, pp. 8-14; G. A. Smith, *The early Poetry of Israel* (*Schweich Lectures*, 1910), 1912, pp. 80-90.

The historical circumstances presupposed by the Song, as compared with the prose-narrative of *ch.* 4, have already been discussed in the general *introd.* to 4¹⁻⁵³¹. It remains to say something about the metrical form of the poem. As a preliminary, we may notice that, while *v.*¹ and *v.*^{31b} are obviously the work of editors, the former being due, in all probability, to R^{JE}, and the latter to R^{E2}, *v.*² also, which is usually regarded as the opening couplet of the poem, is more probably an ancient introduction, extracted, together with the poem itself, from the old song-book in which it was contained (cf. *note ad loc.*). The poem thus possesses two introductions of a different date in *v.*¹ and *v.*², and its true commencement is found in *v.*³.

The fact may now be regarded as well established that Hebrew poetry, besides such long-recognized characteristics as parallelism in thought, etc., possesses a definitely marked metrical or (perhaps more accurately) rhythmical system. Attempts which have been made to discover a strict form of scansion by feet may be said to have resulted in failure: investigation has rather proved that ancient Hebrew possessed no regularly quantitative system of metre, but rather a system in which so many *ictūs* or rhythmical beats occur in each stichos, while the number of intervening unstressed syllables is governed merely by the possibilities of pronunciation.*

The existence of such a system in the poetry of an ancient Semitic

* This system is exactly illustrated in English by Coleridge's *Christabel*, on the rhythm of which the poet writes:—'I have only to add that the metre of *Christabel* is not, properly speaking, irregular, though it may seem so from its being founded on a new principle: namely, that of counting in each line the accents, and not the syllables. Though the latter may vary from seven to twelve, yet in each line the accents will be found to be only four. Nevertheless, this occasional variation in number of syllables is not introduced wantonly, or for the mere ends of convenience, but in correspondence with some transition, in the nature of the imagery or passion.' In illustration of this system, as worked out in the poem, we may quote

'They crossed the moat, and *Christabel*
Took the key that fitted well;
A little door she opened straight,
All in the middle of the gate;
The gate that was ironed within and without,
Where an army in battle array had passed out.
The lady sank, belike through pain,
And *Christabel* with might and main
Lifted her up, a weary weight,
Over the threshold of the gate:
Then the lady rose again,
And moved, as she were not in pain.

language is well illustrated by the Babylonian epic poems, where the regular rhythmical form appears to consist in four beats to the line.* Thus, e.g., we may cite (*Gilgameš-epic*, xi. 9. 10):

luptéka Gílgameš amát nišírti
u pírista ša iláni káša luḫbika

'I will unfold to thee, Gílgameš, a word of secrecy,
 And a decision of the gods will I tell thee—e'en thee.'

Or, with a fewer number of syllables to the line (*id.* xi. 21. 22):

kíkkiš kíkkiš ígar ígar
kíkkišu šiméma ígaru ḫissás

'Reéd-hut, reéd-hut ! wáll, wáll !
 Reéd-hut, listen ! wáll, attend !'

This four-beat measure is well recognizable in Hebrew, and is prominent in the Song of Deborah, about three-eighths of the poem being so composed. The rhythm, as it appears in the original, may be illustrated from *v.*⁶:

hārím nāz^elú mipp^ené Yahwéh
mipp^ené Yahwéh^e lōhé Yisrā'él

The measure appears to be especially characteristic of such examples of Hebrew poetry as may be supposed (upon other grounds) to be among the most ancient; and the influence of the Babylonian pattern may here be conjectured to have been operative, or even a more remote tradition common to both peoples. As illustrations from other early poems we may cite Ex. 15^{1b}: ‡

'āsīrā l^e Yahwéh kī gā'ō gā'ā
šús w^e rōkl^e bhó rāmá bhayyām

'I will sing to Yahwéh, for he hath triumphed, hath triumphed;
 The horse and his rider hath he whelmed in the sea';

* Cf. Zimmern, *Ein vorläufiges Wort über babylonische Metrik*, in *ZA.* 1893, pp. 121-124; *Weiteres zur babylonischen Metrik*, in *ZA.* 1895, pp. 1-20. In the latter article, the author publishes a neo-Babylonian text in which the stichoi are divided by three vertical lines into four parts. This division can, in his opinion, serve no other purpose than to indicate the four verse-members (feet); and thus we have an actual proof that the Babylonians consciously reckoned lines of four beats in a species of their poetry.

‡ The major part of this poem is so composed. Sievers (*op. cit.* pp. 408 f.) contrives to fit nearly the whole of it to this measure.

and 2 Sam. i²² from David's lament over Saul and Jonathan, which is mainly composed in this measure:

middám h^alālim meḥēlebh gibbōrīm
ḵēšeth Y^ehōnāthān lō nāsōgh 'āhōr
w^eḥerebh Šā'ūl lō th^ašūbh rēkām

'From the blood of the slain, from the fat of the strong
 The bow of Jonathan turned not back,
 And the sword of Saul returned not void.'

Together with the four-beat measure we also find, in the Song of Deborah, a three-beat measure into which about five-eighths of the poem is cast. We may instance v.⁴:

Yahwéh b^ešēth^ekā missē'ir
b^ešādh^ekhā miss^edhē'^Edhóm

This is the most frequent form of Hebrew measure, the Book of Job and a great number of the Psalms being written in it. Couplets of this form may account for the term 'hexameter' as used by Josephus.*

The three-beat measure appears, like the four-beat measure, to be of considerable antiquity. We find it, for instance (combined with an opening line of four beats), in the ancient 'Song of the Sword' which is ascribed to Lamech in Gen. 4^{2ff.}, and evidently celebrates the invention or acquisition of weapons of bronze and iron by a people in the nomadic stage:

* Jos. applies the term (*Ant.* iv. viii. 44) to the 'Song' (Deut. 32) and 'Blessing' (Deut. 33) of Moses, in both of which the three-beat measure is well marked. He also states (*Ant.* ii. xvi. 4) that Ex. 15 is composed 'in hexameter verse,' a statement which is true only of a very minor portion of the poem (cf. vv. 2, 8bc, 16cd), the greater part being composed, as we have already noticed, in the four-beat measure. David is said (*Ant.* vii. xii. 3) to have composed 'songs and hymns to God of several sorts of metre: some of those which he made were trimeters, and some were pentameters.' Here the trimeter of course is the three-beat measure considered as a stichos and not as a couplet (hexameter); while the pentameter is the so-called *Ḳ'innā* (elegiac) measure which is well exemplified, e.g. by Ps. 42-43; cf. v.²:

'Thirsteth my soul for Gód,
 For the Gód of my life,
 Whén shall I come and behold
 The face of Gód.'

The former measure is reckoned either as trimeter or hexameter because each three-beat stichos is complete in itself, and the two lines of the couplet are usually parallel in sense; whereas in the pentameter (3+2) the second line completes the sense of the first.

‘Adhā w^e Šillā šmā’an kôlī
w^ešē Lémekh ha^azēnnā ‘imrāthī
kī ‘iš hārāghtī l’phišī
w^eyēledh l’hābbūrāthī
kī šibhāthāyim yúḵḵam Ḳāyin
w^eLémekh šibhīm w^ešibhā

‘‘Ada and Šilla, heár my voice;
 Wives of Lámech, give éár to my wórd:
 For a mán have I sláin for my wóund,
 And a bóy for the sáke of my bruise:
 If séven times Cáin be avénged,
 Then Lámech full séventy and séven.’

Occasionally we find couplets in the Song of Deborah composed of a four-beat line followed by a three-beat line (4 + 3); cf. *vv.* 4b.15b-18.26b.27a. Instances of the reverse order (3 + 4) occur in *vv.* 6a.9. Combination of these two forms of measure is found similarly in Ex. 15. Other metrical forms employed in Hebrew poetry do not come under consideration in the present connexion.

The fact that Hebrew vocalization, as known to us from *℣*, represents a somewhat artificial system of pronunciation which is due to the method of cantillation practised in the Synagogue from early times, does not invalidate the conclusions above illustrated as to the metrical form of Hebrew poetry; since there is no reason to suppose that the number and position of the accentual beats were essentially altered to suit the pronunciation of *℣*. We are not altogether without evidence as to the pronunciation of Hebrew as a spoken language, but can draw well-founded inferences, partly from comparative philology, and partly from evidence derived from the transliterations of Amorite and Hebrew words which are found in Babylonian and Assyrian inscriptions (Amorite proper names on Babylonian First Dynasty Tablets; ‘Canaanite glosses’ on the T.A. Tablets; Biblical names in Assyrian Annals), and of proper names and place-names in *℣*. Such evidence indicates that the main difference between the original and the traditional pronunciations consisted in the occurrence of short vowels in positions in which we now find either tone-long vowels or else vocal *sheva*. Such a couplet as that quoted above from the Song of Deborah, *v.* 5, was probably pronounced in some such form as

harrīm nazalū mippānáy Yāhwáh
mippānáy Yāhwáh ‘elāháy Yisra’él

This, however, does not, for our purposes, vary essentially from the pronunciation of *℣*. Cf. further, *Additional note*, p. 158.

The theory of Hebrew rhythm here exemplified is substantially that which has been expounded in detail by Sievers (*op. cit.*), and which is now very generally adapted by scholars.* Sievers gives (pp. 418 ff.) his view of the rhythmical form of the Song of Deborah, which agrees throughout with that which has been arrived at by the present writer (prior to consultation of Sievers' version), except in a few minor particulars which depend upon individual views as to the original form of certain passages. The translation which follows aims at reproducing the rhythm of the original, in so far as this can be done consistently with a strictly accurate translation. Here and there a faithful reproduction of the rhythm (which might have been

* Ball's rendering of the Song (published nearly thirty years ago) proceeds upon the assumption of a more strictly metrical method, his lines falling into regular iambic feet, with an occasional anapaest or trochee. Such a theory must now give way in favour of that which is adopted above; yet the writer's method deserves notice, if only as a tribute to his exceptional command of English style in his reproduction of what he conceives to be the metrical form of the original. We may cite, by way of illustration, *vv.* 25 ff., the account of Šišera's murder:—

Maim shá'al, háláb náthaná;
Basífl 'addírim híqribá hem'áh:
Yadáh [saniól] layyáthed tíshlehénn
Wimínah lálmut' ámilím;
Waháláma Sís'ra máhaqá roshó,
Umáhaqá waháláfa ráqqathó.

Bein ráglaihá kará', nafál, shakáb;
Bein ráglaihá kará', nafál:
Bāshér kará', shám'mah' nafál shadúd.

'He asked but water, milk she gave;
In lordly platter she presented curds.
Her left hand to the tent-pin soft she lays,
And to the workmen's maul her right;
Then smote she Sisera and brake his head;
She struck, and pierced withal his temples through.

'Betwixt her feet he bowed, he fell, he lay;
Betwixt her feet he bowed, he fell;
E'en where he bowed, he fell, slain violently.'

A similar system of syllable-reckoning is found in the Syriac metres, the invention of which is ascribed by tradition to Bardesanes (born 154 A.D.).

Bickell counts syllables in the same way as Ball; but his feet (in contrast) are trochaic, and he takes great liberties with the Hebrew forms in order to fit them into his system. Thus *vv.* 24 ff. run, according to this system, as follows:—

Téborákh minnášim Já'el,
Minnášim b'ohl t'bórah!
Májm saúl, chaláb natána;
B'sófl -ddir híqr'ba chém'a.
Jádah, l'játéd tíšlachánna;
Wimínah lehálmutf' amélim.

obtained through a paraphrase) has to give way in favour of a faithful rendering into English.

That the poem was intended to exhibit a kind of strophic arrangement is very probable. On examination of its contents, it appears to fall into the following divisions:—

- (1) vv. 3-5. Introduction—Praise of Yahweh, who is pictured as setting forth from His earthly seat to the help of His people (9 stichoi).
- (2) vv. 6-8. Israel's oppression by the Canaanites prior to the rising of the tribes (11 stichoi).
- (3) vv. 12, 9-11. Summons to a retrospect of Yahweh's 'righteous acts' in giving victory to His people (11 stichoi).
- (4) vv. 13-15a. Muster of the clans—The patriotic tribes (9 stichoi).
- (5) vv. 15b-18. Reproach of the recreant tribes, who are contrasted with Zebulon and Naphtali, whose bravery was most conspicuous (10 stichoi).
- (6) vv. 19-21. The battle (9 stichoi).
- (7) vv. 22, 23. Flight of the foe (6 stichoi).
- (8) vv. 24-27. Ja'el's deed extolled—The fate of Sisera (11 stichoi).
- (9) vv. 28-30. The poet gloats over the anxiety and vain expectation of Sisera's mother (11 stichoi).
- v. 31a. A concluding couplet (supposed by some to have been added to the poem in later times).

V'hál'ma Sís'ra', mách'qa róšo,
 V'mách'ça v'chál'fa ráqq'to.
 Bén ragláha kára', náfal,
 V'šákháb ládref,
 Bén ragláha kára', náfal;
 Báašér kará', šam náfal šádud.

This typically German rhythm lends itself admirably to his translation:—

'Jahel sei von Frau'n gepriesen,
 Von den Frau'n im Zelte!
 Statt des Wassers gab sie Milch ihm,
 Rahm in mächt'ge Schale.
 Ihre Hand griff nach dem Pflöcke,
 Und den Hammer fasste ihre Rechte.
 'Und sein Haupt zerschlug sie hämmernd,
 Quetschte seine Schläfe.
 Sisara fiel, stürzte nieder,
 Lag zu ihren Füßen,
 So vor ihr dahingestreckt,
 Blieb er, wo er fiel, zerschnettet liegen.'

Marquart's system likewise takes such liberties with the position of the *ictus* as would be capable (by the aid of emendation, where deemed necessary) of producing almost any desired result from any Hebrew poem to which it might be applied.

Here we notice that, out of the nine divisions or strophes into which the poem falls, four, viz. Nos. 2, 3, 8, and 9, are of exactly the same length, viz. eleven stichoi. Every strophe, except Nos. 5 and 7, contains a single line; and in Nos. 4, 6, 8, and 9 these single lines correspond with a break in subject, rounding off the strophe. Such a measure of uniformity suggests that, in its original form, the poem may have been more completely uniform. Thus, *e.g.*, it seems probable that *v.*¹² in strophe 3 originally stood before *vv.*⁹⁻¹¹—an arrangement which brings the single stichos *v.*^{11c} to the end of the strophe. This gives a very natural order:—Deborah, Barak, the military commanders, 'the people' or rank and file of the fighting men, and then typical representatives of the community in time of peace—the sheikhs, the wayfarers, and the village-maidens. We must not, however, lay too great stress upon such an arrangement, since it seems fairly clear that it was not hard and fast throughout the poem. Few would doubt that strophe 1 stands substantially in its original form. In this case the strophe may be said to fall into two parts, 1a (*v.*³) and 1b (*vv.*⁴⁻⁶); and it is 1a, and not 1b, that the poet has rounded off with the single stichos.

The variation in length of strophes 1, 4-7, and more especially the very marked comparative brevity of No. 7, suggests that the poem has undergone a certain amount of mutilation in transmission—a conclusion which is also rendered highly probable by the very corrupt condition of the text in the middle part of the poem (*vv.*⁸⁻¹⁶), which has been the despair of a multitude of commentators.

It is perhaps needless to remark that the emendations adopted in the translation are not claimed as offering more than a reasonably possible solution of textual difficulties which are in some cases so considerable that they may well be regarded as beyond the reach of remedy.* When confronted by difficulties of such a character there are three courses which are open to the translator. He may endeavour to force a meaning out of *ftl* as it stands, in defiance of the ordinary rules which govern Hebrew philology; he may abandon the passage as hopeless, and leave a lacuna in his translation; or he may seek, by aid of the ancient Versions, or (in default of such aid) by means of reasonable conjecture, so to emend the text that it may satisfy at once the demands of the Hebrew language and the requirements of the context. The third course has been adopted as most appropriate to a commentary of which the aim is the elucidation of the Biblical text by all the aids which modern research has placed within our reach.

* The very corrupt condition of portions of the poem may be taken as an indication that it was derived by E, not from *oral* tradition, but from an ancient *written* source which may already have been partially illegible when it was drawn upon by the historian. Cf. the similar phenomenon in David's lament over Saul and Jonathan, 2 Sam. 1^{17ff.}, and Solomon's words at the dedication of the Temple, 1 Kgs. 8¹²⁻¹³—poems which we know to have been extracted from an ancient song-book, viz. the Book of Jashar.

5. 1. ^{RJ^B} Then sang Deborah and Barak the son of Abino'am
on that day, saying,
2. ^E (When long locks of hair were worn loose in Israel ; when
the people volunteered.)

Bless ye Yahweh !

3. Attend, ye kings ; give ear, ye rulers :
I — to Yahweh I will sing,
Will make melody to Yahweh, the God of Israel
4. Yahweh, in thy progress from Sé'ir,
In thy march from the field of Edom,
Earth quaked, yea, heaven 'rocked',
Yea, the clouds dropped water.
5. The mountains 'shook' before Yahweh,
[] Before Yahweh, the God of Israel.
6. 'From' the days of Shamgar ben-'Anath,
[From] the days of 'old, caravans' ceased.
And they that went along the ways used to walk [] by
crooked paths.
7. Villag^{es} ceased in Israel ;
. ceased ;
Till thou didst arise, Deborah,
Didst arise as a mother in Israel.
8. 'Armourers had they none ;'
'Armed men failed from the city :'
Was there seen a shield or a lance
Among forty thousand in Israel ?
12. Awake, awake, Deborah !
Awake, awake, sing paeon !
Rise up, Barak, and lead captive
Thy capt^{ors}, O son of Abino'am !
9. 'Come, ye' commanders of Israel !
Ye that volunteered among the people, bless ye Yahweh !
10. 'Let' the riders on tawny she-asses [<review it,>]
And let the wayfarers [<'recall it to mind !']>]
11. [] Hark to 'the maidens laughing' at the wells !
There they recount the righteous acts of Yahweh,
The righteous acts of his 'arm' in Israel.[]

13. Then down ¹to the gates gat¹ the nobles ;
Yahweh's folk ¹gat them¹ down mid the heroes.
14. From Ephraim ¹they spread out on the vale¹ ;
'After thee, Benjamin !' mid thy clansmen.
From Machir came down the commanders,
And from Zebulun men wielding the truncheon [].
15. And ¹thy¹ princes, Issachar, were with Deborah ;
And ¹Naphtali¹ was leal <to> Barak :
To the vale he was loosed at his heel.

<Utterly reft> ¹into¹ factions was Re'uben ;
Great were ¹his searchings¹ of heart.

16. Why sat'st thou still amid the folds,
To hear the pastoral pipings ? []
17. Gile'ad beyond the Jordan dwelt,
And Dan [] abideth by the ships.
Asher sat still by the shore of the seas,
Dwelling beside his creeks.
18. Zebulun is the folk that scorned its life to the death.
And Naphtali on the heights of the field.
19. On came the kings, they fought ;
Then fought the kings of Cana'an ;
In Ta'anach, by the rills of Megiddo ;
The gain of money they took not.
20. From heaven fought the stars ;
From their highways they fought with Šišera.
21. The torrent Kishon swept them off ;
[¹It faced them¹, the torrent Kishon.
¹Bless thou¹, my soul, the might <of Yahweh !>
22. Then loud beat the hoofs of the horse^fs¹ ;
¹Off¹ gallop^fed¹, ¹off¹ gallop^fed¹ his chargers.
23. Curse ye, ¹curse ye¹ Meroz ! []
Curse ye, curse ye her towns-folk !
For they came not to the help of Yahweh,
To the help of Yahweh mid the heroes.

24. Most blessed of women be Ja'el, [
Of tent-dwelling women most blessed !
25. Water he asked ; milk she gave ;
In a lordly dish she proffered curds.
26. Her hand to the peg she put forth,
And her right to the maul of the workmen ;
And she smote Šišera---destroyed his head,
Shattered and pierced through his temples.
27. 'Twixt her feet he bowed, he fell down, he lay prone ;
'Twixt her feet he bowed, he fell down.
Where he bowed, there he fell down undone.
28. Out through the window she leaned and exclaimed,
The mother of Šišera out through the lattice :
'Wherefore delayeth his car to come ?
Wherefore tarrieth the clatter of his chariots ?'
29. Her wisest princesses mak[e] answer,
Vea, she returneth her reply : [
30. 'Are they not finding---dividing the spoil ?
A damsel---two damsels for every man :
A spoil of dyed stuffs for Šišera,
A spoil of dyed stuffs embroidered ;
Two dyed embroideries for the neck of 'the queen.''
31. So perish all thy foes, Yahweh :
But be 'thy' friends like the sun going forth in his might.
- R²² And the land had rest forty years.

5, 1. *Then sang Deborah.* That the poem was actually composed by Deborah does not appear to be probable : cf. *note* on v.^{7b}.

2. *When, etc.* The view which is taken in the translation given above is that this statement forms no part of the poem, but simply states the *occasion* on which it was composed, viz. when the Israelites consecrated themselves with unshorn locks (see below) to fight the battle of Yahweh, and made spontaneous offering of their service. The *form* of the sentence (Infinitive Construct with **כ** in a temporal clause) is exactly like that which is employed in stating the supposed occasions of several of the Psalms in the 'David' collection. So Ps. 3, 'When he fled from Absalom his son' (בְּבִרְחוֹ וְג'); Ps. 34, 'When he changed his conduct before Abimelech, etc.' (בִּישְׁנוֹתָו וְג') : Ps. 51, 'When Nathan

the prophet came unto him, etc.' (בְּבוֹא וְנָ); cf. also Pss. 52, 54, 57, 59, 60, 63.*

Bar^ekhû Yahweh, 'Bless ye Yahweh!' may then be regarded as the title of the poem, indicating that it is a *song of thanksgiving*; just as in certain Psalms we find a prefixed *Hal'êlû Yāh*, 'Praise ye Yah!' which is not strictly part of the Psalm itself, but indicates its contents, viz. a *song of praise*: cf. Pss. 106, 111, 112, *al.* Title and note of occasion appear to have been taken over by the E writer from the old song-book (perhaps 'the Book of the wars of Yahweh,' Num. 21¹⁴) in which the poem was contained. The ordinary view, which makes this verse the opening couplet of the poem, is opposed by its somewhat abrupt character, in contrast to v.³ which forms a natural opening (cf. Ex. 15^{1b}, 'I will sing to Yahweh, etc.'): and also (and especially) by the difficulty of finding a suitable rendering which does justice to the Hebrew construction. It is very doubtful whether the rendering of R.V., 'For that, etc., bless ye Yahweh' (*i.e.* Thank Yahweh that such spontaneous service was rendered) can be justified, no parallel to the use of the Infinitive Construct with ב in such a sense seeming to exist.‡ The only natural rendering of בִּפְרַע וְנָ is that which makes it a temporal clause: 'When, etc., bless ye Yahweh'; *i.e.* when Israel offers spontaneous service, bless *Yahweh* as the true source of the noble impulse, just as He is the true giver of victory; and (implicitly) do not ascribe the movement to human merit (cf. *ch.* 7²). The impulse described by the verb *hithnaddēbh*, *i.e.* voluntary service in Yahweh's

* Since writing the above note, the present editor has discovered that a similar view was put forward by William Green, Fellow of Clare Hall, Cambridge, in 1753 (*The Song of Deborah, reduced to metre*). Green treats v.² as a statement of the occasion of the poem, and renders vv. 1, 2,

'Then sang Deborah and Barak
The son of Abinoam, on that day,
When they set Israel free, (and)
The people willingly offered themselves,
saying, Bless ye Jehovah.'

His note on the passage runs as follows:—'The second Period contains the title and occasion of the Song, as may be seen by comparing it with the titles of the Psalms, many of which run as this does. See titles of the 3rd, 34th, 51st, and other Psalms. The Song plainly begins at Period the third.'

‡ We should expect עַל with the Infin. Constr. (cf. Ex. 17⁷ עַל-נִסּוֹתֵם אֶת-יְיָ 'on account of their trying Yahweh,' Am. 1³ עַל-דִּוְשָׁם 'on account of their threshing'), or עַל-אִשֶּׁר, or אִשֶּׁר alone, with the finite verb (cf. Ex. 32³⁵ אִשֶּׁר בָּנִינוּ בְּנִיִּים 'because they had made,' Ps. 144¹² עַל-אִשֶּׁר עָשָׂה 'For that our sons are like young plants'). Bu. asserts (against Mo.) that it is permissible to render ב 'on the ground that' after בָּרַךְ; but he quotes no illustration of such a usage

cause, is ascribed to the influence of Yahweh in 1 Chr. 29¹⁴. It would be precarious, however, to argue from so late a passage to the passage with which we are dealing; and, in any case, such an explanation involves reading more into our verse than perhaps it may reasonably be supposed to contain. Mo. suggests that the pref. **וְ** might here be rendered 'with':—'with long streaming locks in Israel, with free gifts of the people, praise ye Yahweh'—a rendering which, even if it be possible, does not commend itself as at all probable.

When long locks of hair were worn loose. Heb. *biphroa' p̄rā'ôth*. The construction is literally that of an impersonal active verb: 'When one let loose long locks, etc.'

Much discussion has taken place over the meaning of substantive and cognate verb. The grounds upon which the rendering given above is adopted are as follows. In Bab. *pirtu* (plur. *pîrêtu*, *pîrîtu*) means 'long hair' (of the head): cf. *Gilgames-epic* I. col. ii. 36, where it is said of the wild man Engidu that 'his long hair is arranged like a woman's' (*uṣṣuṣ pîrîtu kîma sinniṣti*; lit. 'he is arranged as to the long hair, etc.'). The same subs. is seen in the Ar. *far'* 'long hair' of a woman, 'full or abundant hair' (Lane). In Heb. *p̄rā'* occurs in Num. 6⁵ with reference to the Nazirite: R.V. 'All the days of his vow of separation no razor shall come upon his head: until the days be fulfilled in which he separateth himself to the Lord, he shall be holy, he shall let the locks (*p̄rā'*) of the hair of his head grow long. Similarly, Ezek. 44²⁰: R.V. 'Neither shall they (the priests the sons of Šadoq) shave their heads, nor suffer their locks (*p̄rā'*) to grow long; they shall only poll their heads.' In all these cases (Bab., Ar., and Heb.) the meaning of the substantives is undisputed.

A plur. form *par'ôth*, Construct State of *p̄rā'ôth* in our passage with fem. termination (cf. Bab. *pirtu*, plur. *pîrêtu*), is found in Deut. 32⁴²; and the meaning has been held to be equally ambiguous in Deut. and Judg. In the passage of Deut. (where Yahweh is the speaker) Driver renders as follows:—

'I will make mine arrows drunk with blood,
And my sword shall devour flesh,
With the blood of the slain and of the captives,
From the long-haired heads of the foe.'

The Heb. phrase in the last line is *rôš par'ôth*, lit. 'head of long locks.'

There is no dispute that the verb *p̄ārā'* has the meaning *let loose*, *unbind long hair* in other passages: cf. Lev. 10⁶, 21¹⁰, 13⁴⁶, Num. 5¹⁸. It is also used metaphorically in the sense of *letting loose* people by removing restraint from them, in Ex. 32²⁶ (twice). Syr. *p̄rā'* means 'to sprout,' and late Ar. *farā'a* is quoted in this sense* (cf. references in BDB. s.v. פָּרַע II.).

* The roots פָּרַע and פָּרַח 'sprout' may be ultimately connected.

This is the case for the rendering which has been adopted in the text with some confidence. As Black remarks (after W. Robertson Smith), 'The expression . . . refers to the ancient and widespread practice of vowing to keep the head unshorn until certain conditions had been fulfilled (cf. Acts 18¹⁸). The priests [cf. the passage from Ezek. already cited] were prohibited from making such vows because they might interfere with the regular discharge of the priestly functions; but with warriors in primitive times the unshorn head was a usual mark of their consecration to the work which they had undertaken, and their locks remained untouched till they had achieved their enterprise or perished in the attempt (cf. Ps. 68²¹). War among most primitive peoples is a sacred function, and this was specially the case in Israel where Jehovah was the God of Hosts.'

This interpretation, which was probably intended by Σ. ἐν τῷ ἀνακαλύψασθαι κεφαλᾶς (cf. Ὁ^B Ἀπεκαλύφθη ἀποκάλυμμα), is also adopted by Cassel, Wellh. (*Isr. u. Jüd. Gesch.* p. 97), Vernes, No., La., Cooke (*Comm.*), Gress., and, on Deut. 32⁴² (according to Driver), by Schultens, Knobel, Keil, and by R.V. *marg.* 2.

The principal rival interpretation is 'For that (or when) the leaders led.' This appears in Ὁ^{AL}, Θ., ἐν τῷ ἄρξασθαι ἀρχηγούς, and is adopted by R.V., Schnurrer, Herder (1780), Hollmann, Ges., Ros., Donaldson, Meier, Ewald, Hilliger, Bach., Reuss, Ber., Oet., Bu., Stephan, Kit., Zapletal, Kent, Smith, and apparently given the preference by Mo. on Judg.; and in Deut. by R.V. ('From the head of the leaders of the enemy'), Schultz, Kamphausen, Dillmann, Oet., Steuernagel. It depends upon the fact that in Ar. the verb *farā'a* has the sense *over-top* or *surpass in height*, and then *become superior in eminence, nobility*, etc.; and hence is derived the subs. *far'*, *noble* or *man of eminence* (Lane).*

If this rendering is correct, it is at any rate remarkable that, where so many occasions for mentioning *leaders* or *chieftains* occur in the O.T., both in poetry and prose, this particular term should be found only in the two passages specified, and should in both of them be open to a considerable measure of ambiguity.

Other explanations may be dismissed in a few words. Kimchi, and several older modern commentators (Köhler, Herder (1825), etc.),

* There can be little doubt that this root is the same as that from which the subs. 'long hair' is derived, the common idea being that of *luxuriant growth*.

Cooke makes a mistake in attempting (with some of the older commentators) to connect the Aram. פִּוּרְעָנִים, which is used in π^O Deut. 16¹⁸ to translate the Heb. שִׁטְרִים 'officers' (in subordinate position); since the sense here intended is *vindices* (from פָּרַע 'to avenge'), alongside of Heb. שִׁפְטִים, Aram. דִּינָן 'judges.' Cooke adds a reference to Ex. 20⁵ in π^J; but this is quite off the point, פִּוּרְעָן here having the sense 'vindictive,' in the phrase, 'a jealous and vindictive God.'

following the rendering of S^p , 'For the vengeance wherewith Israel was avenged,' explain 'For the vengeance (lit. vengeance) which was taken in Israel,' *i.e.* the avenging of their wrongs. Similarly, in Deut. 32⁴² R.V. *marg.* offers the rendering, 'From the beginning of revenges upon the enemy.' But this sense of the verb פָּרַע, though common in Aram., cannot be paralleled in Heb., in which *nāḳam* is the regular term for 'avenge.' Lastly, Le Clerc, Michaelis, Justi, Stu., von Gumpach, assuming the meaning of the root to be *to loosen* in a general sense, would render 'For the freedom (freedoms) which was wrought in Israel.' Such a sense, however, cannot be supported.

volunteered. The Heb. *hithnaddēbh*, which is used, as here, in 2 Chr. 17¹⁶, Neh. 11², in the sense of offering one's self willingly to perform certain services, occurs in 1 Chr. 29 (*passim*), Ezr. 1⁶, 2⁶⁸, 3⁵† with the meaning *offer freewill offerings* (*n'dhābhōth*) for the Temple. Cf. also, in Bib. Aram., Ezr. 7^{13.15.16}†.

3. *ye rulers.* Heb. *rōzēnim*, which is connected with an Ar. root meaning 'to be weighty, grave, firm in judgment,' is only employed in the O.T. in poetical or elevated diction. It is parallel to 'kings' (as here) in Hab. 1¹⁰, Ps. 2², Prov. 8¹⁵, 31⁴, and to 'judges of the earth' in Isa. 40²³†. Cf. Bab. *urzunū* (*ruzzunū*?), *ruṣṣunū*, 'mighty, dignified,' cited by Dyneley Prince, *JBL*, 1897, pp. 175 ff.; Langdon, *AJSL*, 1912, pp. 144 f.

I—unto Yahweh I will sing. The first 'I' is a *nominativus pendens*. R.V., 'I, even I will sing, etc.,' is incorrect.

will make melody. Heb. *zimmēr* is used of playing an instrument (cf. Ps. 33^{2b}, 144^{9b}, 147^{7b}, *al.*), as well as of singing. Hence the rendering adopted is preferable to the more specific rendering of R.V., 'I will sing praise.'

4. *Yahweh, when, etc.* Yahweh is pictured as marching to the assistance of Israel from His ancient seat in the south (as rightly observed by Hollmann), which is placed by the poet in 'Se'ir' or 'the field of Edom.' That this seat can be no other than Sinai (of J and P) or Horeb (of E and D), as is assumed by the author of the ancient gloss 'This is Sinai' in *v.*^{5b}, cannot be doubted. The old poem called 'the Blessing of Moses,' Deut. 33, is very explicit. It opens with the quatrain—

'Yahweh came from Sinai,
And beamed forth unto them from Se'ir;
He shone forth from mount Paran,
And came from 'Meribath-Ḳadesh.'

Here Sinai is grouped with Se'ir, *i.e.* the mountain-range of Edom which runs north and south, from the Dead Sea to the Gulf of 'Aḳaba; with a mountain (or mountain-range) belonging to Paran—perhaps Ġebel Fārân, among the mountains to the south-east of

Ḳadesh ; and with Meribah of Ḳadesh,* *i.e.* Ḳadesh-Barnea, which was close to the border of Edom : cf. Num. 20^{16b}, and *note* on 'from the Crag,' Judg. 1³⁶.

The evidence of the 'prayer' of Habākkuḵ is similar. This opens with the statement—

‘God came from Teman,
And the holy one from mount Paran.’

Teman, which etymologically means 'the right hand side,' or South country, from the standpoint of Cana'an, is the name applied to a district of Edom, as appears from Ezek. 25¹³, Ob. 9.

If the site of Mount Ṣinai is to be sought among the mountains of Edom, not far from Ḳadesh—possibly in the Ġebel el-Maḳrah group to the south-east of 'Ain Ḳudēs (cf. *Map* V.), this is consonant with several other statements contained in the O.T. For instance, Moses comes to Mount Ḥoreb when feeding the flock of his father-in-law, the priest of Midian (Ex. 3¹ E); and Midian appears to have been situated north-east of the Gulf of 'Aḳaba, in the neighbourhood of the hill-country of Se'ir.† Israel's first conflict with the 'Amaleḳites is at Rephidim close to Ṣinai (Ex. 17^{8ff.} E); and the 'Amaleḳites are mentioned elsewhere as inhabiting the region immediately south of the Negeb, in the neighbourhood of the Ḳenites and Sime'onites : cf. *note* on 'Amaleḳ' *ch.* 3¹². The story of Moses striking the rock at Ḳadesh is given as the origin of the name Meribah in Num. 20¹⁻¹³ (JEP), and is closely parallel to the story of his striking the rock at Rephidim close to Ṣinai, Ex. 17^{1b-7} (JE), where the name Meribah is similarly given ; and it is impossible to think otherwise than that the two narratives are duplicates of the same tradition. Cf. further Sayce, pp. *HCM.* 262-272.

The traditional site of Ṣinai is Ġebel Mûsâ in the south of the peninsula of Ṣinai, more than 150 miles south of Ḳadesh ('Ain Ḳudēs), and considerably over 100 miles from the southernmost district of Edom, and from the land of Midian. The only evidence

* מִרְבַּת קֹדֶשׁ reads מִרְבַּת קֹדֶשׁ, *i.e.* 'from ten thousands of holiness,' which is paraphrased by R.V., 'from the ten thousands of holy ones.' G, however, renders σὺν μυριάσιν ἁγίων *Kadēs*, and it is clear that a place-name is required by the parallelism with the three preceding stichoi. This can be scarcely other than מִרְבַּת קֹדֶשׁ : cf. Deut. 32⁵¹, Ezek. 47¹⁹, 48²⁸; Ps. 106³².

† The statement of Ex. 3¹ that Moses 'led his flock to the back of the wilderness' implies that the mountain of God lay to the west of Midian. The *Μοδιαρα* or *Μαδιαρα* of Ptolemy (vi. 7), *i.e.* the Madyan of the Arabic geographers, lies east of the gulf of 'Aḳaba and south of the mountain-range of Se'ir; but the land of Midian may in all probability have extended further northwards along the eastern side of Se'ir. Thus a mountain west of Midian might be situated in Se'ir to the east of the 'Arabah : but the tradition which associates Ṣinai with Ḳadesh and Paran, seems rather to favour the district of Edom which lay to the west of the 'Arabah.

in the O.T. which may be said to tell in its favour, in so far as it is incompatible with the evidence given above associating Sinai with Ẕadesh, is the statement of Deut. 1² that 'it is eleven days from Horeb by way of the hill-country of Se'ir to Ẕadesh-Barnea'. It may be noticed also that P in Num. 33¹⁶⁻³⁶ places twenty stations between Sinai and Ẕadesh; but this is discounted by the fact that the old narrative JE knows nothing of these stations, and only mentions Tab'erah (Num. 11³), Ẕibroth-hatta'avah (Num. 11³⁴), and Ḥašeroth (Num. 11³⁵), as intervening.*

The tradition which connects Sinai with Ġebel Mûsâ cannot be traced beyond the monastic period. It seems to have been in the fourth century A.D. that Christian communities began to settle in the Sinai peninsula, and monasteries were established in the neighbourhood of Ġebel Mûsâ, and also of Ġebel Serbâl in the west of the peninsula, which, in the opinion of many authorities, possesses the earlier claim to have been considered the traditional Sinai. Upon this question, cf. Driver, *Exodus* (*Camb. Bib.*), pp. 186 ff. ‡

the field of Edom. The phrase שֵׂרָה אֶדוֹם (parallel to 'Seir,' a mountain-district: cf. preceding *note*) suggests an original connexion between Heb. *sādhē*, ordinarily rendered 'field,' and Bab. *šadû*, 'mountain.' § Cf. also *v.*¹⁸, 'on the heights of *the field*'; Num. 23¹⁴, 'unto *the field* of the watchmen' (Šophim), further explained by 'unto the top of Pišgah,' mentioned as a point of view; Deut. 32¹³, 'produce

* Ẕadesh is not mentioned at the end of Num. 12 or the beginning of 13. Num. 12¹⁶ says that 'the people journeyed from Ḥašeroth and pitched in the wilderness of Paran,' and *ch.* 13 then at once commences to relate the mission of the spies. But that it was Ẕadesh from which, according to the old narrative, the spies were sent forth is clear from 13²⁶, where they return to Ẕadesh, and from 32⁸, where they are definitely stated to have been sent forth from Ẕadesh-Barnea'.

‡ An expansion in Ɔ's paraphrase of *v.*⁵ shows that the translator must have supposed Sinai to be a very small mountain, and therefore could not have known the tradition identifying it with Ġebel Mûsâ or Ġebel Serbâl. The passage runs, 'Mount Tabor, Mount Ḥermon, and Mount Carmel were in a fury one with another, and were saying one to another, the one of them, "Upon *me* shall His *Shēkhînā* dwell; and *me* it becometh"; and another, "Upon *me* shall His *Shēkhînā* dwell; and *me* it becometh." He caused His *Shēkhînā* to dwell on Mount Sinai, which is weaker and smaller than all the mountains.'

§ Heb. שֵׁ = Bab. š is seen also in שָׂבַע = šēbā 'be sated', שֵׂה = šū'u 'sheep', שׂוֹט = šātu 'rebel', שֵׁיב = šēbu 'hoary', שִׁיחַ 'plant' = šīḡtu 'shoot' from šāḡu 'grow', שְׂמָאל = šumēlu 'left side', שֵׁצֶר 'hair' = šārtu 'hairy skin', שֵׁק = šakku 'sack', שָׂרַף = šarāpu 'burn', שֵׁר 'prince' = šarru 'king', and in other cases in which the connexion is not so obvious. Cf. the way in which loan-words in Hebrew from Assyrian represent š by ש; e.g. סַרְגִּין for šargānu, etc.; cf. the present editor's note in *J.T.S.* xi. p. 440.

of *the field*,' parallel to 'the heights of the earth'; 2 Sam. 1^{21a}, where we should perhaps read '*ye fields* of [death], (שָׂרֵי מָוֶת), parallel to 'ye mountains of Gilboa'; Jer. 18¹⁴, 'Shall the snow of Lebanon fail from the rock of *the field*?' In all these cases the more original meaning 'mountain' appears to be prominent. Cf. Barth, *Etymologische Studien*, pp. 65 f.; Winckler, *AF.* i. p. 192; Peters, *JBL.*, 1893, pp. 54 ff. The reason why *sādhē* came to denote more generally 'field,' i.e. *open country*, usually uncultivated pasture or hunting-ground, probably was that the usage sprang up in Palestine where this type of country is found in the hills as opposed to the vale (*ēmekē*), which doubtless was then, as it is now, appropriated for arable purposes. A parallel may be found in the fact that, for the Babylonians, the same Sumerian ideogram KUR stands both for *šadū*, 'mountain,' and *mātu* (Aram. *māthā*), 'country'; a fact which points the inference that for the original users of the ideogram their 'country' was a mountain-country.

Earth quaked. The reference is not to Yahweh's manifestation in storm and earthquake at the giving of the Law on Sinai or Horeb (Ex. 19^{16ff.}, Deut. 4^{11,12}, 5^{22ff.}), as has been supposed by many scholars—a fact which would have no special significance in the present connexion, but to his appearance in these natural phenomena upon the occasion with which the poem deals. As we have already noticed (4¹⁴ note), the fact that a thunder-storm burst in the face of the foes, and materially assisted in their discomfiture, may be inferred both from the poetical and prose-narratives. The statement that 'the earth quaked' need not be taken more literally than the companion-statement that 'the heaven rocked'; and may well be a poetical description of the apparent effect produced by the rolling peals of thunder.

rocked. Reading נִמְוָה with Ἐ^{Na}l ἐταράχθη (cf. Ἐ^A ἐξεστάθη), 𐤍 'turbatum est,' Bu., Mo., Oort, No., in place of 𐤍 נָפַח which means 'dropped' or 'dripped,' and is the word used in the following stichos—a fact which doubtless accounts for its erroneous occurrence in our passage. The Heb. root *mūgh*, suggested by the Versions above cited, is the same as the Ar. *māḡa*, which, as applied to the sea, means 'be in a state of commotion,' 'be agitated with waves,' 'be very tumultuous' (Lane). Marquart, Ehr. read נִמְוָה 'were shaken.'

5. *shook.* Vocalizing נָזַל (as in Isa. 63¹⁹, 64²) with Ἐ ἐσαλεύθησαν, 𐤍 𐤏𐤍, 𐤍 'commoti sunt,' 𐤍 𐤏𐤍, 𐤍, Ar. تزعزعت, and most moderns, in place of 𐤍 𐤏𐤍 'flowed down,' which has the support of 𐤍 'fluxerunt.'*

* It is possible that נָזַל as vocalized by 𐤍 may be intended as a weakened form of נָזַל; cf. 𐤍 𐤏𐤍 for 𐤍 𐤏𐤍, 𐤍 𐤏𐤍 in Gen. 11^{6,7}; G-K. § 67 *dd.*

to *Before Yahweh, etc.* **U** opens the clause with the words **וְהָ סִינִי**, id. if part of the original, 'Yon Sinai before Yahweh, etc.' The use of the pronoun **וְהָ** *deiktikōs* can be paralleled (cf. BDB. s.v. **וְהָ** 2); it, as Mo. remarks, 'would only be natural if Sinai were in sight.' The chief objection, however, to the originality of the words is the fact that they are metrically superfluous, since they make the stichos contain five beats;* whereas, with their omission, the verse is perfectly balanced. It can hardly be doubted that **וְהָ סִינִי** is simply the scribe's marginal note which has crept into the text, and which is to be understood predicatively, 'This is Sinai' (cf. **Σ. τούτέστι τὸ Σιναι**). *be.* 'This refers to Sinai,' viz. the mention of the mountains in the first stichos of *v.*⁵. The inclusion of this gloss in the text must have happened fairly early, since it appears in the same position in all the Versions, and also in Ps. 68⁸, which is copied from our passage.† This view is adopted by von Gumpach, Donaldson, Ball, Mo., Bu., Oort, No., La., Kit., Cooke, Gress. Winckler and Marquart read **רָנָה סִינִי** 'Sinai trembled,' and modify Yahweh's title in order otherwise to shorten the stichos (Winck. 'before Yahweh'—tautologous with parallel stichos; Marq. 'before him'—three beats only in the stichos). Kit., *Bri.* proposes (after Grä.) to read **וַעַ** for **וְהָ**—'Sinai quivered,' and to delete **וְהָ**.

6. *In the days of Shamgar, etc.* Cf. note on 3³¹, where the fact is remarked that the name Shamgar is non-Israelite, and may very likely be Hittite in origin. We have also noticed (4² note) that Šišera may very possibly be a Hittite name; and these two inferences, taken together, lend colour to the theory, propounded by Marquart, and afterwards worked out by Mo. (*JAOS.*, 1898, pp. 159 f.), that Shamgar may have been a foreign oppressor, and Šišera his immediate successor, if not his son: both being members of a Hittite dynasty ruling in Canaan, to which the Canaanite city-kings, at least in the vicinity of the great plain, were vassals.

From the days of old. **U** reads 'In the days of Ja'el'; but this can scarcely represent the original text. As Mo. appositely remarks, 'it is singular that the name of this Bedawi woman should be coupled with that of Shamgar. And how can the period before the rise of Deborah be called *the days of Ja'el*, when the deed which made her famous was only the last act in the deliverance which Deborah had already achieved? The best that can be said is that, although Shamgar and Ja'el, both of whom in different ways wrought deliverance for their people, were living, they did nothing to free Israel from the tyranny of the Canaanites until Deborah

* **וְהָ סִינִי** would count as one beat only.

† Ps. 68 is probably not earlier than the Maccabæan period. Ball has made out a strong case for finding its occasion in the events narrated in 1 Macc. 5^{9 ff.}, *cir.* B.C. 165; cf. *JTS.* xi. (1910) pp. 415 ff.

appeared.' The difficulty is enhanced if Shamgar was not re Israelite Judge, as supposed by the author of the gloss in 3 (as is suggested by his name: cf. *note*) a foreign oppressor. commentators would escape the difficulty by excising the 'in the days of Ja'el' as a gloss suggested by *vv.* 21^{ff}. Here ever, we find ourselves upon the horns of a dilemma. If we no more than these words, with Geddes, Bickell, Cooke, Mar. Bu., Mo. (*Comm.*, but not *SBOT.*), No., we then have a stichosisting of two beats only, חָדְלוּ אֲרָחוֹת 'caravans ceased'—which scarcely possible. If, on the other hand, we also excise 'the son 'Anath' from stichos *a* (with Kit.), and then read *a b* as a stichos, 'In the days of Shamgar caravans ceased' (rhythmic correct), we are unable to point to the source whence 'the son 'Anath' was derived by the late author of 3³¹.

Assuming the correctness of the suggestion noticed above, that Shamgar was a foreign oppressor preceding Šišera, it is feasible to regard the ' of עֵל as due to dittography of the final letter of בִּימֵי, and to find in עֵל the first two letters of עֵלָם 'old time' (so Ball, privately). Then, reading in both stichoi מִימֵי for בִּימֵי (confusion of מ and ב is frequent; cf. examples cited by Driver, *NHTS.*² p. lxxvii.) we obtain the text adopted above. It may be objected to this that עֵלָם מִימֵי suggests too remote an antiquity. Yet cf. the expression חֲרוֹבוֹת עוֹלָם 'the desolations of old time,' Isa. 58¹², 61⁴, an expression covering a period of not more than fifty to seventy years. It would be natural for the poet, after the great victory, somewhat to exaggerate the duration of the oppression.

Suggested substitutions of another proper name for the name Ja'el (e.g. 'Ja'ir,' Ewald, *HI.* ii. p. 365; 'Othniel,' Grä.) do not call for comment.

caravans. Vocalizing אֲרָחוֹת with most moderns, in place of אֲרָחוֹת 'ways' or 'paths' of אֲרָחָה* 'Ōrḥā (cf. Gen. 37²⁵, Isa. 21¹³) is the active participle fem. sing. of 'ārah 'to journey,' and is used collectively to denote a travelling company. The aggressions of the Canaanites put a stop to commercial intercourse in Israelite territory. חָדְלוּ אֲרָחוֹת of אֲרָחָה, i.e. 'the ways ceased,' is interpreted by R.V. 'the highways were unoccupied'; † but to make 'ceased' to mean 'ceased

* The same change has to be made in Job 6¹⁹, where אֲרָחוֹת תִּמְנָה should be 'אֲרָחוֹת ת'. Similarly, in Job 31³² we must read לְאֲרָחָה 'for the wayfarer' (|| נֵר 'a sojourner') in place of לְאֲרָחָה אֲנִי, which can only mean 'for the way.'

† R.V. *marg.* offers the rendering 'the caravans ceased'; but it should be noted that this involves a tacit adoption of our emendation, and cannot be got out of אֲרָחָה as it stands.

to be used' is a forced expedient which cannot be justified. Such an idea would have been more naturally expressed by a different verb : cf. Isa. 33^b, 'The highways lie desolate (נִשְׁמּוּ מַסְלֹת), the wayfaring man ceaseth.'

They that went, etc. Even the private wayfarer could only find safety by taking 'crooked,' *i.e.* devious and roundabout, paths.

crooked paths. Lit. 'crooked ones,' 'paths' being naturally inferred from the context. So in Ps. 125⁵ עֲקֻלְקֻלָּהֶם 'their crooked (ways)'. \mathfrak{H} inserts אֲרָחוֹת 'paths' before עֲקֻלְקֻלָּהֶם, but this spoils the rhythm by introducing a fifth beat into the stichos. The omission is favoured by Mo. (who quotes Briggs, Ley, Grimme), Bu., No., La., Cooke.

7. *Villages.* Reading פְּרוֹנוֹת with four MSS. of \mathfrak{M} , \mathfrak{S}^P פְּרוֹנוֹת 'open (*i.e.* unwallled) places,' קְרוֹי פְּצוּחִיא 'village-towns,' and many moderns. *Perāzōth* (cf. Ezek. 38¹¹, Zech. 2⁴ (\mathfrak{H}^8), Est. 9¹⁹ †) are the unwallled hamlets which the Israelites dwelling round about the plain of Esdraelon were compelled to inhabit owing to their failure to capture the fortified cities of the Canaanites : cf. *ch.* 1²⁷ ff. Such hamlets, being unprotected, were speedily swept out of existence by the foe ; and we are left to infer that, as happened during other periods of oppression (cf. *ch.* 6², 1 Sam. 13⁶), the Israelite inhabitants must have been driven to take refuge in the caves and fastnesses of the hills.

\mathfrak{H} פְּרוֹנוֹת, which occurs again in the suffix-form פְּרוֹנוֹנִי in *v.* 11, has been explained as a collective 'peasantry,' 'rural population' (hence R.V. *marg.* 'villages'); but the coupling of the plur. verb חָדְלוּ, 'ceased' with the sing. collective subject is extraordinarily harsh, and can scarcely be justified.* Bu., who retains פְּרוֹנוֹת, feels constrained to alter the verb into the sing. חָדַל (cf. \mathfrak{E}^{AL} ἐξέλιπε φραζων). צִדְקָת פְּרוֹנוֹנִי in *v.* 11 is likewise only susceptible of a very forced explanation : — 'the righteous acts of (*i.e.* pertaining to) his peasantry,' *i.e.* 'his righteous acts towards the peasantry.' The rendering of \mathfrak{E}^B δυνατοί *v.* 7, \mathfrak{F} 'fortes' *vv.* 7, 11, Ber., La., and several of the older commentators, ‡ R.V. *text*, 'rulers' (or 'judges') *v.* 7, 'his rule' *v.* 11, may be

* A parallel may perhaps be found in 1 Kgs. 5³ (\mathfrak{H}^{17}) הַמִּלְחָמָה אֲשֶׁר סָבְבָהּ 'the state of warfare (sing.) which surrounded (plur.) him.' which can only be explained upon the supposition that the writer, in speaking of *warfare*, had implicitly in his mind the *foes* (plur.) who were its cause, and so lapsed into the plur. verb. Cf. *NHTK. ad loc.*

‡ This interpretation is given by Rabbi Isaiah (in Buxtorf, *Rabbinic Bible*): וַיֵּשׁ לְפִתְחוֹ לִשְׁנוֹ מִמִּשְׁלָה שֶׁחָדְלוּ מֵהִיּוֹת לָהֶם מִמִּשְׁלָה 'and it is possible to interpret it in the sense of "rule," viz. that they ceased to have rule.'

compared with פְּרָנִין in Hab. 3¹⁴, where the meaning 'his chief men,' 'rulers,' or 'warriors' is given by פ, F, S^p, T, and is agreeable to the context. Such an explanation is not without philological support* (as stated by Mo.); yet if the root פָּרַן was really employed in Heb. in the sense 'decide' or 'judge,' it is somewhat strange that no clear occurrences of it are to be found.

. . . *ceased*. As H stands, the word is connected with the preceding stichos: 'Villages ceased in Israel, they ceased'; and the Versions all presuppose the same text. Since in v.^{7b}, however, we have a perfectly balanced distich, it seems obvious that v.^{7a} must originally have formed a similar distich, the first stichos beginning, and the second ending, with הָרְלוּ 'ceased' (cf. the similar structural arrangement in the distichs vv.^{21a, 21}); though what the subject of the second הָרְלוּ was we have no means of conjecturing.

Till thou didst arise. קָמְתִי is doubtless intended by H for 1st pers. sing., as rendered by S^p, T, A.V., R.V., 'until I arose.' The objection that, inasmuch as the poet addresses Deborah in v.¹², it is scarcely possible that she can here be the speaker, is sufficiently answered in the words of Herder, who, writing of v.¹², remarks, 'Just as Pindar so often arouses himself, his *φίλον ἥτορ*, just as David so often summons heart and soul, when both are preparing themselves for the highest flights of their song; so Deborah wakes herself as she now commences the actual description of the battle, and as it were endeavours once more to fight the valiant fight.' A real objection to taking קָמְתִי as the 1st pers. has, however, been advanced by Houb., viz. that, if this had been intended, we should have expected the 1st pers. pronoun, אֲנִי דְבוּרָה, instead of דְבוּרָה simply (cf. Dan. 10⁷, 12⁵): and it is perhaps preferable, therefore, to take the verb as the older form of the 2nd pers. fem. sing. (for קָמְתִי cf. Jer. 2²⁰, where יִצְבֶּרְתִּי, יִתְקַתִּי must be regarded as 2nd fem. sing.; Mic. 4¹³, וְהִתְרַמְתִּי: G-K. § 44 *h*), as is done by most moderns. Ἐως οὗ ἀνέστη (B, according to Swete, ἀναστῆ), L 'donec surrexit,' F 'donec surgeret,' presuppose קָמָה, or possibly קָמַת. If this is original, we must suppose that it was altered into קָמְתִי (intended as the 1st pers. sing.) in H under the influence of the heading in v.¹, 'Then sang Deborah and Barak' (so Wellh.).

* Ar. *faraza* means to *separate, divide*, and then, apparently, *decide*: cf. Lane s.v. 2.8. Bab. *parāsu* (with which cf. Heb. *pāraś*, 'divide') means to *decree, judge, give decision*; and *piristu*=*decision*. Sum. GAR.ZA, MAR.ZA=Bab. *paršu*, i.e. a divine decree or institute in Temple-worship: cf. Br. 5647, 5836; Muss-Arnolt, *Dict.* p. 836b. We thus have evidence that the sense *divide*, and thence *decide*, runs through the differently modified Semitic root *prs* (*prś*), *prš*, *prz*.

8. *Armourers, etc.* Reading

חָסְרוּ לָהֶם חַיִּים

אֲזָלוּ חֲמִשִּׁים מֵעִיר

The text of **ח** here offers perhaps the greatest crux in the poem. As it stands, it can only be rendered, 'One chooses (*or* shall choose) new gods (*or* God chooses new things); then battling (??) of gates.' The rendering of A.V., R.V., 'They chose new gods; then was war in the gates,' proceeds upon the assumption that the verb **בחר** is an impersonal Imperfect used pictorially of a past event, and that **לחם** is employed in place of the ordinary **מִלְחָמָה** in the sense 'war'; 'war of gates' being interpreted as 'war in the gates.' If **לָהֶם** or **לָהֶם*** is really intended to convey this sense, it is best to regard the form as an Infinitive Piel, used in place of a substantive, in accordance with the explanation of Schnurrer, 'tunc factum est τὸ oppugnare urbes (Israëliticas).' The meaning then is that apostasy from Yahweh to the service of strange gods was punished by the siege of Israel's cities by the Canaanites; a thought which is akin to the pragmatism of R¹². It is true that the 'new gods' may be paralleled by Deut. 32¹⁷, 'They sacrificed . . . to gods whom they knew not, to new ones that came up recently'; and the idea of *choice* of gods other than Yahweh is found in *ch.* 10¹⁴ (E²).† But, apart from the difficulty of construing the Hebrew in this sense, the stage depicted as 'war in the gates' hardly suits the condition of abject submission already described in *vv.* 9, 7, or the statement as to the absence of weapons among the Israelites in *v.* 8^b. Still less probable is the explanation of Ewald (and so Meier), who regards **אֱלֹהִים** as referring to *judges*, so called as God's representatives § ('heilige Richter'), and somewhat prosaic-

* The common reading is **לָהֶם**; but thirty-six MSS. read **לָהֶם** or **לָהֶם** (Kit., BH.). We should expect the Infin. Piel to be **לָהֶם**; but no other instance of the Piel of this verb exists.

† Possibly a scribe may have endeavoured to restore an illegible text under the influence of these two passages (Cooke, Mo.).

§ Cf. the present writer's *Outlines of O.T. Theology*, pp. 15 f. The use of 'Ēlōhīm in the passages quoted from Ex. 21⁶, 22^{8,9} ('The Book of the Covenant'), is susceptible, however, of a different and probably preferable explanation, viz. the household-gods (Teraphim), which were possibly connected with the practice of ancestor-worship, and whose cultus appears to have existed among the Israelites in early times apart from any conception that the allegiance due to the national God Yahweh was thereby contravened. Laying these passages aside, the only *certain* instance of the employment of 'Ēlōhīm to denote judges is Ps. 82⁶.

ally makes the passage state that the outbreak of hostilities was co-incident with the appointment of new judges (Deborah and Barak).

The evidence of the Versions is somewhat conflicting. \mathfrak{C}^B , \mathfrak{T} support substantially the text of \mathfrak{H} , and the interpretation of it given by A.V., R.V. \mathfrak{C}^B renders ἐξελέξαντο θεοὺς καινοὺς, ὅτε ἐπολέμησαν πόλεις ἀρχόντων. Here ὅτε is probably a corruption of τότε (as in HP. 58), and πόλεις a corruption of πύλας. πύλας ἀρχόντων is most likely to be the result of a doublet (שַׁעְרִים 'gates'; נָצִירִים 'princes'); the second rendering coming into the text from the margin as ἄρχοντας, and then being altered to the genitive to make sense.* ἐπολέμησαν may be a rendering of חָמַל of \mathfrak{H} , regarded as Infin. Constr. Piel; or it may represent an original לַחֲמֵי (or לַחֲמֵי regarded as an abbreviated plural); unless it be considered as a corruption of ἐπολέμησεν, as is suggested by \mathfrak{T} , 'et portas hostium ipse [Dominus] subvertit,' where the translator had before him a text identical with \mathfrak{H} , but treated לַחֲמֵי as the Perfect חָמַל. The lengthy paraphrase of \mathfrak{T} appears to have behind it a text in no way different from \mathfrak{H} :—'When the house of Israel desired to serve new errors [*i.e.* idols], which had lately been made, with which their fathers had not concerned themselves, the peoples came against them and drave them from their cities, etc.' Here the description of the idols clearly points to the fact that the paraphraser had Deut. 32¹⁷ in his mind. The same text and interpretation are offered in stichos *a* by \mathfrak{C}^{AL} ἡρέτισαν θεοὺς καινοὺς. The rendering of this stichos which makes 'God' the subject of the verb is offered by \mathfrak{S}^P בָּחַל אֱלֹהִים בְּלִי, 'God chooses a new thing,' \mathfrak{T} 'Nova bella elegit Dominus'; and has been adopted by a few of the earlier commentators, who understand חֲדָשִׁים 'new ones,' either as 'new judges,' or 'new things' (properly חֲדָשִׁוֹת; cf. Isa. 42⁹, 48⁶; sing. Isa. 43¹⁹, Jer. 31²¹)—*i.e.* a new mode of action, viz. deliverance through the agency of a woman.† This rendering, however, is opposed by the fact that 'Yahweh,' and not 'God,' is employed elsewhere throughout the poem with reference to the God of Israel.

Another interpretation of the stichos *b* is offered by \mathfrak{C}^{AL} *al.* ὡς ἄρτον κριθινόν, \mathfrak{H} 'velut panem hordeaceum' (so \mathfrak{S}^B); \mathfrak{S}^P סוּסְבַּע לֶחֶם בָּרְכִי; *i.e.* the last two words of \mathfrak{H} are vocalized as לַחֲמֵי שַׁעְרִים 'barley-bread.' This has led Bu. to propose the emendation אֶזְלַל לַחֲמֵי שַׁעְרִים

* HP. cite four Codd. Arm. as reading ἄρχοντες πόλεων.

† Kemink (as quoted by Donaldson) seeks to find the clue to the passage in this conception; but emends חֲדָשִׁים into הַנְּשִׁים—'God makes choice of women' (Deborah and Ja'el).

'The barley-bread was spent,' upon the view that the ל of אֶל has been omitted through haplography. The verb אָזַל is employed in this sense in 1 Sam. 9⁷; and barley-bread is typical of the Israelite peasantry in the Midianite's dream, *ch.* 7¹³, doubtless as forming their staple sustenance. In harmony with this suggestion, Bu. conjectures that stichos *a* may have run וְבָהִי אֱלֹהִים חָרְלוֹ 'The sacrifices of God ceased,' *i.e.* through lack of the wherewithal to provide them. Apart, however, from the objection to the use of 'God' instead of 'Yahweh,' which we have already noticed, such a distich, though not at variance with what follows in the next distich, yet stands in no necessary connexion with it. Such a connexion has been sought by Lambert (*RÉJ.* xxx. p. 115) in his emendation of stichos *b* אֶן לַחֲמִשׁ עָרִים; according to which the sentence would run on into the following distich:—'Then unto five cities was there seen a shield, etc.' But such an overrunning between distich and distich is contrary to analogy. La., Schlögl, Kent, in following Lambert, reject stichos *a* altogether; and combine stichos *b* with the following distich in such a way as to form a single distich of the whole:—

'Then there was not seen a shield for five cities,
Or a lance among forty thousand in Israel.'

The emendation adopted above has been made at the suggestion of Dr. Ball, who observes that the only guide which we possess as to the original sense of the distich is found in the succeeding distich, 'Was there seen a shield, etc.' This immediately recalls the similar account of the drastic disarmament effected by the Philistines at the commencement of Saul's reign, as recorded in 1 Sam. 13¹⁹⁻²², which relates that 'no armourer (*or* smith, חָרָשׁ) was found throughout all the land of Israel: for the Philistines said, Lest the Hebrews make them swords or spears'; but all the Israelites were obliged to go down to the Philistines in order to sharpen their agricultural implements. 'So it came to pass in the day of battle that there was neither sword nor spear found in the hand of any of the people that were with Saul and Jonathan: but with Saul and with Jonathan his son there was found.' The resemblance between חָרָשִׁים 'new things' and חָרָשִׁים 'armourers' is patent; יָבָחַר may have arisen through transposition of the letters of חָסְרוּ, and אֱלֹהִים from לָהֶם or אֱלֹהֶם. As a parallel clause we have the statement that 'Armed men failed from the city'—a natural result of the absence of armourers and the vigorous oppression exercised by the Canaanites. חָמִישִׁים is the term employed of the armed warriors in the Midianite camp, *ch.* 7¹¹. Possibly אֶזְלוֹ חָמִישִׁים may have been written in abbreviated

form *אֹל חַמִּשׁ* (cf. *footnote*, p. 124); while the letters of *מַעִיר* may be supposed to have suffered transposition *עִירִמ*.

Marquart already has our *חַרְשֵׁים*;* but rearranges *זז. 7a-8a* in a manner which scarcely commends itself. Supposing *ז. 7b* to be a later gloss, he follows *ז. 7a* (as in *U*) by the first two words of stichos *a* of *ז. 8a* in the form *יִכְרְחוּ אֶת־לֵים*: 'Village-life ceased in Israel; They fled into tents . . .' His next distich then runs, 'The barley-bread was spent; Armourers ceased in the land' (*חֲדָלוּ חַרְשֵׁים <בַּאֲרִיז>*). Here the first word is from *ז. 7a*, the second from *ז. 8a*, and the third supplied by conjecture. Other suggested emendations need not here be noticed.

Was there seen, etc. The Imperfect *יִרְאֶה* is frequentative—whenever and wherever one might look, this condition of affairs existed. The curious reading of *Ⲭ^L* (occurring with variations in other recensions of *Ⲭ*), *σκέπη νεανίδων ἂν ὀφθῇ καὶ σιρομάστης*, has undoubtedly arisen from an original text *σκέπη ἐν ἰδῶ καὶ σιρομάστην*, reading *אִם יִרְאֶה* 'Do I see,' for *אִם יִרְאֶה*, which may be original (so Marquart, Gress.).

In its present form *Ⲭ^L* seems to have undergone the following process. A scribe noted the variant *ἂν ὀφθῇ* (the reading of *Ⲭ^B*) upon the margin of his MS. This was subsequently copied into the text; and since *ἐν ἰδῶ* was superfluous by the side of *ἂν ὀφθῇ*, *σκέπη ἐν ἰδῶ* was corrupted into *σκέπη νεανίδων*, thus supplying a nominative to *ὀφθῇ*; and, in accordance with this, *σιρομάστην* became *σιρομάστης*.

Among forty thousand. Hollmann comments upon the contrast between the number of able-bodied men in Israel as here given, and the large numbers of the Pentateuchal narrative: Ex. 12^{37b}, Num. 11²¹ (J) 600,000; Num. 1⁴⁶ (P) 603,550. The modest assessment of our passage is, as he remarks, a strong argument for the contemporaneity of the poem with the events which it celebrates. So Wellh. as already quoted (p. 78, *footnote*).

12. This verse is placed before *זז. 9-11* for the reasons noted on p. 102.

Awake, awake, Deborah! On the supposed incompatibility of this address with Deborah's reputed authorship of the Song, cf. *note* on *ז. 7*, 'Till thou didst arise.' The variation of accent—here *úrí úrí*, but in the next stichos *úrí úrí*—is a rhythmical device: cf. G-K. § 72 s.

Thy captors. Vocalizing *שְׂבִיךְ*, with *S^L*, Michaelis, Wellh., Stade, Black, Bu., Kit., No., Marquart, Segond, La., Ehr., Smith, Cooke (*Comm.*), Gress.: cf. Isa. 14² *לְשִׁבְיָהֶם וְהָיוּ שְׂבִיךְ* 'and they shall be captors to their captors.' *שְׂבִיךְ*, i.e. 'thy band of captives' rather than 'thy

* The same emendation was offered by von Gumpach in 1852.

captivity' (R.V.), offers a sense which is perfectly legitimate, and can be paralleled elsewhere (cf. Num. 21¹, 2 Chr. 28¹⁷, Ps. 68¹⁸, **U**¹⁹); but misses the fine paradox which is gained by the easy emendation. It is by no means improbable that Barak, like Gide'on (cf. *ch.* 8^{1st}), may have had his own private wrongs to avenge as well as those of his people.

A number of interesting variants are offered in this verse by **U**^{AL} al., **S**^h. Taking **U**^{AL} as typical, it runs ἐξεγείρου, ἐξεγείρου, Δεββωρα, Ἀξεγείρου (^L ἐξέγειρον) μυριάδας μετὰ λαοῦ, ἐξεγείρου, ἐξεγείρου (^A adds λάλει) μετ' ὧδῆς ἐνισχύων Ἀξανίστασο Βαραχ (^L ἐξανιστὰς ὁ Β.) καὶ Ἀένισχυσον (^L κατίσχυσον) Δεββωρα τὸν Βαραχ, καὶ αἰχμαλώτιζε αἰχμαλωσίαν σου, υἱὸς Αβινεεμ. Other noteworthy variants are the addition of σου after μετὰ λαοῦ, and ἐν ισχύϊ in place of ἐνισχύων. Here we must eliminate the doublet of stichos *b*, ἐξεγείρου, ἐξεγείρου, λάλει μετ' ὧδῆς, which represents insertion of the **U** tradition (cf. **U**^B); and, since La. is probably right in regarding ἐνισχύων, with variant ἐν ισχύϊ, and Ἀένισχυσον as doublets of an original ἐν ισχύϊ σου in stichos *c*, we can scarcely err in also excising καὶ Ἀένισχυσον . . . Βαραχ, the addition of Δεββωρα τὸν Βαραχ being an attempt to explain the corrupt Ἀένισχυσον. Thus, the original Heb. which lies behind this recension of **U** may have run as follows:—

עֲרִי עֲרִי דְבוֹרָה
הָעֲרִי רַבָּבוֹת בָּעָם
בְּעֹד קוֹם בָּרַק
יִשְׁבֵּה שְׁבִיךְ בֶּן־אֲבִינֹעַם

‘Awake, awake, Deborah !
Arouse myriads among the people !
In thy strength arise, Barak !
Lead captive thy captive-band, son of Abino'am !

So La., with the addition of בָּשִׁיר, μετ' ὧδῆς, at the end of stichos *a*. Mo. (*SBOT*.) reads עָם (? עֲמֹךְ) for בָּעָם, and חֲזַק ‘Take courage’ in place of בְּעֹד.

It is a moot point whether such a text is superior to **U**, as Mo., No., La., Zapletal, Cooke (*Comm.*) think. Mo. rests his argument mainly upon the fact that ‘Here Deborah is not summoned to sing a song—whether of battle or of victory—but to arouse the myriads of her countrymen, which certainly agrees better with the words addressed to Barak.’ This is true, if we suppose that the poet pictures himself as addressing the chief actors *prior to the battle*; but the obvious inference to be drawn from **U**, as it stands, is that he is

rather addressing them as he voices his song, i.e. *subsequently to the victory*, calling upon Deborah to recount the main facts in poetic strain, and upon Barak to fight his battles o'er again. Nor is it any objection to this view that in such a case the verse should stand at the commencement of the poem (where it is placed by Niebuhr): cf. the words of Herder already cited under *v.*⁷ note on 'Till thou didst arise.' A point which should not escape notice is that it is somewhat strange if the poet here alludes to 'myriads among the people,' even in hyperbole, when previously (*v.*⁸) he has placed the whole available fighting strength of Israel at the moderate assessment of forty thousand. רבבות may quite easily have arisen as a corruption of רבורה or of רכרי, and נעם (among the people) come in later in explanation of the 'myriads.' It thus appears that there is no sound ground for abandoning the lucid text of *℣*.

9. *Come, ye commanders.* Reading לכו מְחַקְקֵי, as privately suggested by Ball. *℣* לְבִי לְחַקְקֵי 'My heart is to the commanders,' i.e. (presumably) it *turns* or *goes out* towards them: cf. *℣* 'Cor meum diligit principes Israel.' The ellipse of the verb is illustrated by Schnurrer from Ps. 141⁸ אֵלַי יְהוָה עֵינֵי 'Unto Thee, Yahweh, (are) mine eyes.' Such a use of 'heart,' as denoting sympathetic attraction, is perhaps not quite without parallel in Hebrew (cf. 2 Kgs. 10¹⁶), though 'soul' (*néphes*) is more usual in such a sense (cf. 1 Sam. 18¹, Gen. 34^{3,8}, *al.*): but the invitation, 'Bless ye Yahweh!' of stichos *b* favours the supposition that the commanders *are addressed* in stichos *a*; and the imperative לכו forms a natural and appropriate opening to the invitation to thanksgiving.

commanders. מְחַקְקֵי are the imposers of חֻקֵּי, 'statutes' or 'enactments.'

that volunteered. Cf. *v.*² note. *℣*^{AL} οἱ θυνάσται reads הַנְּדָבִים.

10. *Let the riders, etc.* Reading

רָכְבִּי אֶתְנוֹת צְהָרוֹת יִשְׂרָאֵל
וְהֹלְכֵי עַל-דָּרָךְ יִשְׁבּוּ עַל-לֵב

As the verse stands in *℣*, it offends against parallelism and rhythm. The imperative שִׁירָה (rendered by R.V. 'Tell of it') comes at the end of stichos *c* of a tristich referring to three classes of people previously mentioned; and the rhythmical form of the tristich is 3 + 2 + 3 beats. Moreover, stichos *b*, יִשְׁבּוּ עַל-מִדִּין, which affords the only instance of a two-beat stichos in the poem, cannot, as it stands, be explained with any approach to probability. The substantive *madh*, to which the plur. *middin* must be referred, is derived from a verb *mādhadh*, 'to measure,' and denotes 'measure' (Jer. 13²⁵, *lit.* 'the portion of *thy*

measures'), or more usually 'garment,' as in *ch.* 3¹⁶, so-called as *lengthy* or *wide* (cf. Ar. *madda*, 'to extend or stretch'). R.V. 'rich carpets,' however, has no more basis than the mere supposition that a word which usually means a spreading garment may also denote any spreading piece of woven material, and that such a rendering is suitable to the context. But even the appropriateness of this assumption may be questioned. The two other classes mentioned are travellers along the roads, which, in contrast to their former condition (*v.* 6), may now be used with impunity. These classes appear to cover all the population—the wealthy magnate who rides, and the plain man who walks. Is it appropriate that between these two classes there should be interposed reference to a third class of persons who are vaguely defined as those who sit (presumably indoors) upon carpets? It is true that some have explained *middin* as 'saddle-cloths' or 'housings,' thus making the clause a further description of the riders; but this is excluded by the fact that the verb *yāšabh*, 'sit,' is never used in Hebrew of riding an animal.

The Versions afford no help towards elucidation. Gr^{BL} καθήμενοι ἐπὶ κριτηρίου (so S^{h}), V 'et sedetis in iudicio,' T ומתחברין למתב על דינא, 'and are associated in order to preside over judgment,' read מָדוֹן, which may mean 'strife,' but scarcely 'judicial procedure.' Gr^{A} represents מָדוֹן by λαμπηγῶν, 'covered chariots,' L 'in lecticis,' apparently a guess influenced by the context; * S^{P} سَادَقَ بَقَا 'and ye who sit at home'—a guess.

The emendation offered above proceeds upon the assumption that the strophe *vv.* 12.9-11 contains an invitation to a *retrospect* of the past deliverance; as is evident from *vv.* 11, 12. If, then, the word שִׁיחוּ at the end of *v.* 10 means 'review' *sc.* the past deliverance, whether in thought or in speech (see *note* below); and having regard to the fact that so much of the remainder of the verse as can be translated contains reference to two classes of persons which, as we have noticed, appear to include the whole population; it is reasonable to assume that the complete verse was originally a *distich*, in which the two classes are mentioned in parallel stichoi, and summoned to take part in the retrospect. In other words, we may expect to find in the obscure יִשְׁבוּ עַל-לֵב a parallel to שִׁיחוּ 'review.' The resemblance to the phrase יִשְׁבוּ עַל-לֵב, 'let them recall it to mind,' is obvious; the only real difference—that between לֵב and מָדוֹן—being accounted for by the fact that the resemblance between ב and ד is very close in the old character, and that between ל and מ not remote. לֵב read as מֵד may

* Or possibly reading צַבִּים; cf. Isa. 66²⁰, Num. 7³. ἐν λαμπήγαις is the Gr rendering of this word in the Isa. passage.

have been taken for 'מד', an abbreviated form of the plural (cf. *foot-note* § below).

If we have in יִשְׁבוּ a jussive, 'let them recall,' etc., it is probable that in place of the imperative שִׁיחוּ we should likewise have a jussive form יִשְׁיחוּ 'let them review.' But if יִשְׁבוּ עַל לֵב belongs to stichos *a* and יִשְׁיחוּ to stichos *b*, the former contains five beats and the latter three beats. We may assume therefore that an erroneous transposition has taken place, the rectification of which gives us four beats in each stichos. That such errors of transposition have often occurred in copying MSS. cannot be doubted. The explanation is that a scribe erroneously copied the latter part of stichos *b* in place of the corresponding part of stichos *a*; and then, in order to avoid spoiling the appearance of his MS., transposed the omitted part of stichos *a* to stichos *b*. Such an erroneous transposition has clearly taken place in Ps. 35^{5,6}, where *v.*^{5a}, 'Let them be as the chaff before the wind,' should be followed by *v.*^{6b}, 'And the Angel of Yahweh pursuing them'; and *v.*^{6a}, 'Let their way be dark and slippery,' by *v.*^{5b}, 'And the Angel of Yahweh pushing them down.*' Similarly, in *v.*⁷ of the same Psalm, 'a pit' has been transposed from stichos *b*, where 'digged' now has no object, to stichos *a*, where 'they have hid' already has its proper object 'their net.' Cf. also the transposition which is rectified in Judg. 7⁶, with *note ad loc.*

tawny she-asses. A.V., R.V., 'white asses.' The adjective *ḥôrôth* occurs only here in Heb., but comparison of the Ar. shows that it denotes light reddish-grey, or white flea-speckled with red (*ṣuḥra* the colour, *ṣaḥûr* a she-ass so coloured). ‡ Asses of this colour are rare and highly prized at the present day in the East; and their mention in this passage implies that their owners are persons of rank and means, travelling at their ease in a time of peace. The she-ass is preferred for riding purposes as more tractable than the entire male. §

* דחה always means to *push* or *thrust* for the purpose of casting down: cf. BDB. *s.v.* R.V.'s rendering, 'driving them on,' is intended to give a suitable meaning, as the half-verse now stands (clearly 'chaff before the wind' cannot be 'pushed down'); but is quite unwarranted by the usage of the verb elsewhere.

‡ Lette (quoted by Hollmann) cites Firuzabadi: صاكور ابل واتان فيديا 'ṣaḥûr is used of a camel or she-ass in which there is white and red.'

§ The reading of *Ἐπὶ ὄνυ θηλέας μεσημβρίας* is interesting as seeming to prove that אֲתַנּוֹת צְהָרֹת must have stood in the Heb. MS. used by the translator in the abbreviated form אֲתַנְ צְהָרְ, which was read as אֲתַנְ צְהָרְ and then interpreted as אֲתַנְ צְהָרִים. Similar abbreviations of plural terminations are presupposed in *v.*^{8aβ} (אֲזַלְ חַמִּישׁ), *v.*¹⁰ (אֲזַלְ לֵב misread as מַד, and then treated as shortened plur. מַדְ), *v.*¹¹ (מַצְחֵק), *v.*^{22b} (דַּהֲרַ דַּהֲרַ). On the use of abbreviation in Heb. MSS., cf. Ginsburg, *Introd. to Mass.-Crit. Bible*, ch. v.

review it. The verb יָחַד may mean *to talk* about anything or to any one, as in Ps. 69¹² (¹³ יָחַד), 'They that sit in the gate *talk* about me'; Job 12⁸, '*Speak* to the earth, and it shall instruct thee'; or *to muse* or *meditate* upon some topic, as in Ps. 77⁶ (⁷ יָחַד), 'I will *muse* with my heart'; Ps. 119⁷⁸, 'I will *muse* upon thy precepts'; *al.* Hence in our passage the verb may mean 'think about it' ($\text{ס}^{\text{p}} \text{אָד}$) or 'talk about it' ($\text{G}^{\text{B}} \text{διηγεῖσθε}, \text{A}^{\text{A}} \text{φθέγγασθαι}, \text{L}^{\text{L}} \text{ἐφθέγγασθε}, \text{F}^{\text{F}} \text{'loquimini,' } \text{ט} \text{ומשתעין}$), and the rendering 'review it' is adopted as applicable either to thought or speech, and therefore equally ambiguous.

The Heb. leaves the *object* of the verb to be understood from the context, both here and in the corresponding expression in the parallel stichos; but English idiom obliges us to supply it as 'it.' Obviously it is the recent deliverance, which is defined in ז^{L} ¹¹ under the term 'the righteous acts of Yahweh.' There is not the slightest ground for doubting the originality of the verb יָחַד , as has been done by some scholars.

recall it to mind. *Lit.* 'bring it back to (or upon) heart,' the *heart* being regarded by the Hebrews as the seat of the intellectual or reflective faculty. The same expression, with עַל 'upon,' as here, occurs in Isa. 46⁸; but is more frequent with אֵל 'unto':* cf. Deut. 4³⁹ 30¹, 1 Kgs. 8⁴⁷, Isa. 44¹⁹, Lam. 3²¹.

11. *Hark . . . wells!* Reading

קוֹל מִצְחָקוֹת בֵּין מִשְׁאֲבִים

As יָחַד stands, $\text{מִקּוֹל מִצְחָקִים}$ can only be explained upon the most improbable assumptions. The difficulty is twofold. In the first place, it seems impossible to assign a satisfactory sense to בֵּין . The suggestions which have been put forward may be grouped as follows: מִן has been explained as denoting (1) *Separation*; 'Away from or Far from' (cf. for this usage, BDB. *s.v.* 1 b); (2) *Substitution*; 'Instead of' (as though for מִהֵיחָת : this is an explanation which is of very doubtful justification, תַּחַת being commonly used in such a sense); (3) *Comparison*; 'More than' (BDB. 6); (4) *Origin*; 'By reason of' (BDB. 2 e); (5) *Partition*; 'Something of' (BDB. 3).

Secondly, we have no clue to the meaning of מִצְחָקִים , which can only be conjectured.† The rendering of A.V., R.V., 'archers,' is that which is adopted by Kimchi and Levi ben-Gershon, and by Luther,

* The prepositions עַל and אֵל are frequently used interchangeably after a verb of motion. Cf. cases cited in *NHTK.* p. 10.

† Several of the modern explanations of the word were already debated by the mediæval Jewish commentators. Cf. Tanchum, as cited by Ges., *Thes.* p. 511.

Ges., Justi, Ke., Ber., Oet., Cooke, etc. It appears to go back to the interpretation of ט, מַחֲצִי יָרִיִן, 'those who shoot arrows,' which, though occurring in ז.⁸ (or as a gloss to ז.⁸; cf. note to Praetorius' edit.), is doubtless based upon our passage, and interprets מַחֲצִיִּים as a denominative from חֵן 'arrow.' Adopting this explanation, the rendering least open to objection is that of R.V., 'Far from the noise of the archers.' Justi renders somewhat similarly, 'Instead of the noise of the archers'; and, in favour of this, Hollmann cites Gen. 49^{22,23}—a passage which seems similarly to refer to the disturbance of pastoral peace by the attacks of hostile archers (there described as בְּעֵלֵי חֲצִים, lit. 'owners of arrows'). Hollmann rightly objects, however, to the use of מִן in place of תַּחַת.

Other interpretations of מַחֲצִיִּים base themselves upon the root-sense of the verb חָצַן, which is that of *dividing*. Among these, the most widely adopted is 'those who divide the spoil' (Schnurrer, Köhler, Hollmann, Hilliger, Stu., von Gumpach, Bach., Bickell, Kent). All that can be said in favour of this interpretation has been said by Hollmann, who compares the Ar. verb *ḥaṣṣa*, which means in Conj. III., 'share a portion with some one else, give to some one else'; Conj. IV., 'give (to some one else) one's portion'; and the substantive *ḥiṣṣah*, 'portion.' As parallels for such a sense, Hollmann cites Isa. 9³, י² ('as men exult when they divide spoil'; already cited by Ges.), Isa. 33^{23,24}, Ps. 68¹², י¹³; and giving מִן a comparative meaning, he renders 'prae júbilo sortientium . . . ibidem canant laudes Dei.' An obvious objection (noted by Meier) is that the crucial word שָׁלַל 'spoil' has to be supplied by conjecture, and that the ordinary term for 'dividing' spoil (occurring with object שָׁלַל in all the passages cited by Hollmann, and also in ז.³⁰ of the Song) is חָלַק.

Some commentators, again (Menaḥem quoted by Rashi, Boettger, La.), have been attracted by the use of the verb in Prov. 30²⁷—R.V. 'The locusts have no king, yet go they forth all of them *by bands*' (חֲצִי, lit. 'dividing [themselves] into companies or swarms,' BDB.). Thus מַחֲצִיִּים is thought to mean 'those who range themselves' in battle-array, or 'divide' the army into companies. Whatever sense, however, is attached to מִן in this connexion, it remains an enigma why these military operations should be carried out at the places of drawing water.

From this point of view, the explanation of Ros., 'those who divide (the flocks) at the watering places,' is more comprehensible. Vernes, who also adopts this explanation, paraphrases the verse, "Chantez par-dessus la voix des distributeurs aux auges," c'est-à-dire : chantez

de tous vos poumons, plus fort encore que ne crient ceux qui distribuent et font ranger les troupeaux près des auges où ils vont s'abreuver à la tombée du jour.' Having thus expressed his idea of the meaning of the passage, Vernes refers to the rivalry existing between shepherds in watering their flocks, which leads to frequent disputes. But such a comparison of the singing of the praise of Yahweh with the angry shouts of rival shepherds is altogether grotesque.

Herder thinks that מַחְצִיִּים may have the sense, 'those who apportion,' *sc.* water to their flocks; and having rendered שִׁירוֹ in the preceding verse 'denkt auf ein Lied,' he gives to מֵן a partitive sense, and makes the clause resumptive of שִׁירוֹ:—'Ein Lied zum Gesange der Hirten die zwischen den Schöpfefbrunnen Wasser den Heerden theilen aus.' A similar connexion with שִׁירוֹ (already suggested by C^B διηγείσθε ἀπὸ φωνῆς κ.τ.λ., C^L ἐφθέγγασθε φωνήν κ.τ.λ., S^P , Ar. as noticed below) is sought by Meier, who quotes, as a parallel to such a partitive usage of מֵן, Ps. 137³, 'Sing us *one of the songs* (מְשִׁיר) of Zion.*' Such an overrunning from the one distich to the other is, however, in the highest degree improbable: and, moreover, since the words, 'There they recount, etc.,' in stichos 2 *cf.* v. 11 can only refer to what goes on at the places of drawing water, the gist of the passage (according to this interpretation) is that the classes of people mentioned in v. 10 are summoned to relate (שִׁירוֹ) how another class of people are relating (יִתְּנוּ), etc.—a very awkward and unpoetical conception.

Lastly, as probably based on the idea of *division* inherent in the verb הִצִּין, we may notice the rendering of C , ἀνακρονομένων, *i.e.*, apparently, 'singers' or 'players' (*cf.* the use of the verb elsewhere in C : 2 Sam. 6^{14,16}, 1 Chr. 25^{3,5}, Ezek. 23⁴²)—an interpretation which suggests that הִצִּין may have had the sense of *marking the intervals* of the musical scale: *cf.* the use of the Lat. *dividere* by Horace, *Odes* I. xv. 15, 'Imbelli cithara carmina divides'; and the 'septem discrimina vocum' of Virgil, *Aen.* vi. 646, *i.e.* probably the seven notes of the scale. So also Shakespeare, *I. Henry the Fourth*, iii. 1:

'ditties highly penn'd,
Sung by a fair queen in a summer's bower,
With ravishing division, to her lute.'

Romeo and Juliet, iii. 5:

'Some say the lark makes sweet division;
This doth not so, for she divideth us.'

Ewald, who adopts the rendering 'singers' upon the authority of

* Meier does not, however, agree with Herder as to the meaning of מַחְצִיִּים; but he revocalizes the form as מַחְצִיִּים (a supposed derivative of מִחֵץ), and renders 'Feindezerschmettrer'!

Ⲭ, offers a very improbable explanation of the ground-sense of the verb, *those who keep time or order*, and hence *rhythm*; quoting in support of his view ⲛⲓⲥⲓⲛ of Prov. 30²⁷, which has already been noticed above: cf. *HL*. ii. p. 355 *n*¹; *DAB*. i. p. 180.

The other Versions were evidently very puzzled by the stichos. Ⲑ's rendering, 'ubi collisi sunt currus, et hostium suffocatus est exercitus,' is obscure. Ⲥ^p (connecting with ⲥⲓⲁⲓⲟ) renders ⲛⲓⲥⲓⲛ ⲛⲓⲥⲓⲛ ⲛⲓⲥⲓⲛ, 'Meditate upon the words of the researchers, who are among the learned'; and this appears in Ar. as 'Consider some of the words of those who investigate the books of the learned.' Here the idea of *dividing* which is proper to ⲛⲓⲥⲓⲛ appears to be understood as referring to *investigation* (as in Heb. ⲃⲓⲛⲁⲣ); and 'the places of drawing water' seem to be metaphorically explained as the founts of knowledge. The paraphrase of Ⲭ clearly understands the verse to mean that the scenes of former hostile outrages are now consecrated to the praises of Yahweh; but the rendering is too vague and diffuse to admit of detailed elucidation.*

This survey of the interpretation of the stichos may serve to show that every artifice has been employed by scholars, ancient and modern, to extract a suitable meaning from ⲛⲓⲥⲓⲛ, and that the best suggestions possess only the slightest of claims to serious consideration. It is probable, therefore, that the text has suffered corruption. The emendation offered above is based upon the acute suggestion of Bu. (adopted by Marquart) ⲕⲟⲗ ⲙⲥⲁⲕⲓⲙ 'Hark! the merry-makers.' Here the change in the verbal form is but slight; and the rejection before ⲕⲟⲗ has the support of Ⲭ^A ⲡⲉⲃⲉⲓⲛⲁⲣⲥⲁⲥⲥⲉ (Ⲭ^L ⲉⲡⲉⲃⲉⲓⲛⲁⲣⲥⲁⲥⲥⲉ) ⲡⲱⲛⲓⲛ, *i.e.* apparently ⲥⲓⲁⲓⲟ. ⲕⲟⲗ, properly 'a sound of . . .!' is then employed as in Gen. 4¹⁰, Isa. 13⁴, 40^{3,6}, 52⁸; Jer. 4¹⁵, 10²², 25³⁶, 50²⁸; Cant. 2⁸, 5²: cf. G-K. § 146 *b*.

The reason why we have adopted the fem. form ⲙⲥⲁⲕⲓⲙ, 'laughing maidens,' in preference to the masc., is because it appears more natural to find the *girls* of the village (*haš-šō'abbōth*, 'the maidens who draw water'; cf. Gen. 24^{11,13}) at the *maš'abbīm*, 'places of drawing water,' than representatives of the male portion of the community (unless it be supposed that the ⲙⲥⲁⲕⲓⲙ are the shepherds,

* It has not been deemed necessary to discuss the Rabbinic interpretation of ⲙⲥⲁⲕⲓⲙ advocated by Schultens (as quoted by Ros., etc.), which, regarding the word as a denominative from ⲛⲓⲥⲓⲛ, explains it as meaning 'those who cast lots with arrows'; nor the suggestion (also current in Rabbinic circles) which surmises a connexion with ⲛⲓⲥⲓⲛ 'gravel,' in the sense 'gravel-treaders.'

watering their flocks). A fem. form is as likely as a masc., if it may be supposed that the plur. was written in abbreviated form צִהָקְ (cf. *footnote* §, p. 124); and the fact that the masc. plur. verbal form יָתְנוּ, 'they recount,' follows in the next clause, does not militate against such a supposition, since there are many cases in which the masc. form of the 3rd plur. Imperfect is employed in preference to the fem. with reference to a fem. subject preceding (cf. the cases collected in G-K. § 145 *u*). Other suggested emendations need not be noticed.

at the wells. Lit. 'between *or* among the places of drawing water.' The subs. *mašabbīm* is a *μαῖξ λεγόμενον*, but there is no ground for doubting its genuineness; since it is a regularly formed derivative from the verb *šābāh*, 'draw water,' which is of frequent occurrence. For בֵּין, usually 'between,' in the more general sense 'among,' cf. Hos. 13¹⁵, Ezek. 19², 31³, Cant. 2²³.

they recount. The verb *tinnā*, which occurs again in a similar sense in *ch.* 11⁴⁰ ('to *commemorate* the daughter of Jephthah') is doubtless the same as the Syr. *tannī*, which corresponds to the Ar. *tanna*, 'celebrate'; the root-idea being 'do a second time.' The normal Heb. equivalent of the Syr. and Ar. should be *šinnā*; and a Heb. *šānā* (the *Kal* or simple stem-form) does occur several times in the sense 'repeat,' as the regular equivalent of the Ar. and Aram. verb. The form *tinnā* must therefore be regarded as a pronounced Aramäism; but is not on that account necessarily to be condemned, since it is reasonable to suppose that the North Israelite dialect was to some extent tinged by Aramaic influence. Cf. further *Additional note*, p. 171.

ἔτι δώσουσιν, דָּבֹנְתִי 'dabunt,' דָּבֹנְתִי, vocalize the form as יָתְנוּ, which is adopted by Marquart; but this is very improbable. יְבִי נַרְרֶנְתִּי 'ibi narrentur justitiae Domini,' takes the form as a passive, and makes יְבִי נַרְרֶנְתִּי the subject. יִירָדָן עַל זִכְרוֹתָי, supports יְבִי נַרְרֶנְתִּי.

the righteous acts of Yahweh. The acts by which Yahweh manifests His covenant-faithfulness—in this case by vindicating His people against the national foe. The meaning of the expression is best illustrated by its occurrence in 1 Sam. 12⁷, with the description of Yahweh's dealings with Israel which follows, in substance corresponding with the pragmatism of R^{E2}. Cf. also the use of the same phrase in Mic. 6⁵.

his arm. Reading וְזִרְעוֹ as suggested privately by Ball, in place of וְזִרְעוֹ, the difficulties of which have already been noticed under *v.* 7 *note* on 'Villages.' The phrase *the arm of Yahweh*, as descriptive of His might exhibited in the deliverance of His people, is familiar in the O.T. Cf. Ex. 15¹⁶, 'By the greatness of thine arm they [Israel's

foes] are as still as a stone'; the characteristic phrase of Deut., 'with a mighty hand and with a stretched out arm'; Isa. 51⁹, 'Awake, awake, put on strength, O arm of Yahweh'; *al.*

At the end of the verse אֵן adds an additional stichos, אֵן יִרְדּוּ לַשָּׁעֲרִים עַם-יְהוָה 'Then down to the gates gat the people of Yahweh.' This clearly belongs to the description of the tribal muster, which commences with *v.*¹³; and the similarity of the stichos to stichos *a* of that verse, which, as it stands, is obviously somewhat corrupt, proves it to be a marginal variation which has been subsequently copied into the text. We observe similar variants of a single stichos in *v.*^{15b, 16b}.

12. For the notes on this verse, cf. pp. 120 f.

13. *Then down . . . heroes.* Reading

אֵן יִרְדּוּ לַשָּׁעֲרִים אֲדִירִים
עַם-יְהוָה יִרְדּוּ-לוֹ בַּנְּבוֹרִים

It is not clear what אֵן intends by the vocalization of the twice repeated יִרְדּוּ. Jewish interpreters explain the form as apocopated Imperfect Pi'el of רָדָה 'to have dominion' (from full form יִרְדָּה), the Pi'el, which does not occur elsewhere in Heb., being employed causatively, 'cause to have dominion.'* That this was intended by אֵן seems very probable, since we may thus explain the awkward and ungrammatical connexion of עַם with אֲדִירִים, as due to the necessity of making יְהוָה the subject of the verb in stichos *b*, just as He must have been assumed to be in stichos *a* :—

'Then may He cause a remnant to have dominion over the
nobles—the people ;
'May Yahweh cause me to have dominion over the heroes.'

Or possibly it may have been supposed that the apocopated form has the sense of a full Imperfect : 'Then He shall cause, etc.'

The awkwardness and improbability of this need not be laboured. It may suffice to remark that, since *v.*^{14, 15} describe the advance of the tribes in ordinary narrative-form, employing Perfect tenses, we naturally expect to find the same method adopted in the present passage. This is a consideration which sufficiently refutes the alternative explanation of יִרְדּוּ as Imperative Kāl of יִרְדּוּ 'go down'

* We should expect יִרְדּוּ (apocopated Imperf. Hiph'il) in such a sense (cf. Isa. 41²)—a form which is here adopted by von Gumpach.

(in place of the normal Imperative יֵרֶד), as adopted, *e.g.* by Hollmann, who regards the verse as the words of Deborah prior to the battle :— ‘Tunc ego : “Descendite residui nobilium populi, Jehova descende mihi cum heroibus.”’ A further difficulty is found in the use of the word יִשְׁרִיר ‘remnant,’ a term ordinarily applied to a survivor (or survivors) after a defeat in battle ; but here, it must be supposed, employed to denote Israel’s exiguous forces, implicitly contrasted with what they might have been but for the long-continued aggressions of the Canaanites.

It need not be doubted that the true text of the verse is indicated by *v.*^{11c}, which we have already noted as a marginal variation to *v.*¹³. This variation appears, in fact, to represent the combination of two originally separate marginal notes ; *viz.* אֶן יֵרֶד לְשַׁעְרִים as a variant of אֶן יֵרֶד יִשְׁרִיר, and עַם יְהוָה ‘the people of Yahweh,’ a variant of the separated עַם יְהוָה which is found in 20 MSS. of *ℳ*. *℣*^B, though agreeing with *ℳ* in reading יִשְׁרִיר, supports the vocalization of יֵרֶד as a Perfect, and the view that עַם goes with יְהוָה and forms the subject of stichos *b* ; and further reads לוֹ (*i.e.* the ‘ethical’ dative, referring to the subject of the verb—cf. BDB. *s.* ל. *ה*—rather than ‘for Him, *i.e.* Yahweh) in place of לוֹ in stichos *b*—a correction which is obviously to be adopted :—

τότε κατέβη κατάλημμα τοῖς ἰσχυροῖς·

λαὸς Κυρίου κατέβη αὐτῷ ἐν τοῖς κραταιοῖς.

The restoration of the verse as given above is, as regards stichos *b*, generally adopted by moderns, and is scarcely open to doubt. Stichos *a* may perhaps be held to be open to criticism as regards the sense which it yields. Since the verb יֵרֶד ‘went down,’ as employed in *v.*¹⁴, refers to Israel’s downward onset from mount Tabor (cf. *ch.* 4^{14b}), the meaning must be the same in the present passage ; and ‘to the gates’ can therefore only refer to the gates of the foe—it was down to the very gates of such Canaanite cities as Ta’anach and Megiddo (cf. *v.*¹⁹) that the Israelites advanced in their first spirited onslaught. If this interpretation be held to be improbable, it is difficult to see how the text can otherwise be explained.

Other conjectural emendations of stichos *a* have been made. Thus Mo. (followed by Bu., No., Gress.) thinks that שְׁרִיר represents an original יִשְׁרָאֵל, and, supplying כ before אֲדִירִים, he obtains the sense, ‘Then Israel went down like the noble.’ Kit., in *BH*, offers the

suggestion אָן יִרְדֵּי שָׂרִיד לְדִיהֶם 'Then let a remnant dominate those who dominated them.'

14. *From Ephraim . . . vale.* Reading

מִנִּי אֶפְרַיִם מִשְׁכְּנוֹ בְּעַמְלֵק

𐤌𐤏, as it stands, is incredibly concise. The literal rendering is 'From Ephraim their root in 'Amalek'; which is explained, by inferring the necessary verb from *v.*¹³, 'From Ephraim *came down those* whose root *is* in 'Amalek.' The explanation of 'their root in 'Amalek' is also a grave stumbling-block. The Bedawi people called 'Amalek in the O.T. appear elsewhere as inhabiting the desert-region south of the Negeb (cf. *note* on *ch.* 3¹³); and it is to this region that Saul marches in order to carry out his commission to destroy 'Amalek, as recorded in 1 Sam. 15. In the present passage we seem to be told that the 'root' of the tribe of Ephraim (or a portion of it), which inhabited central Palestine, was 'in 'Amalek,' *i.e.* we must infer that they dwelt in the midst of the 'Amalekites. Yet elsewhere, in enumerations of the foreign races inhabiting Canaan, we find no allusion to the 'Amalekites; though, in view of the bitter hostility which existed between Israel and them (cf. Ex. 17^{15,16} E; 1 Sam. 15^{2,3}), it is scarcely possible that they should have been unmentioned if they had inhabited Canaan in any considerable numbers. It is true that they are pictured in *ch.* 6^{3,33}, 7¹² as invading the land together with the Midianites and 'children of the East'; but here they appear in their normal character as roving nomads, making periodical forays at the time when the Israelites' crops were ready for reaping, and bringing their camels and tents with them, as Bedawi tribes would naturally do. The only passage which can be adduced as possibly supporting the allusion to 'Amalek in our passage, is the reference in *ch.* 12¹⁵ to Pir'athon (probably the modern Far'atâ) as situated 'in the land of Ephraim, in the hill of the 'Amalekite.' How this locality obtained its name is unknown to us. It may have been so named as the scene of an encounter with Amalekite clans which had entered Canaan upon such a foray as is described in the story of Gide'on. But even on the supposition that it was so named as the settled abode of 'Amalekites, the very nature of the reference compels us to regard it as a very limited district in comparison with the whole territory occupied by Ephraim; and though, upon this view, it might be possible to speak of 'Amalek as having his root in Ephraim, the converse statement, as we find it in 𐤌, seems to be out of the question.

In face of this difficulty, we may obtain help from 𐤂^{AL}, 𐤀, which, in place of שָׂרִיד בְּעַמְלֵק 'their root in 'Amalek,' read ἐτιμωρήσατο (𐤂^L ἐτιμωρήσαντο) αὐτοὺς ἐν κοιλάδι, *i.e.* שָׂרִיד בְּעַמְלֵק, ἐτιμωρήσατο

αὐτοὺς being doubtless a somewhat free rendering of the verbal form 'rooted them out,'* which is rendered more literally by Ἐξέριζωσεν αὐτοὺς. Here בַּעֲמֶק 'in the vale,' affords excellent sense (cf. vi. 15); and though we can scarcely accept יִשְׂרָשֵׁם, it can hardly be doubted that the translator is right in assuming that a verbal form is here needed.† שִׂרְשֵׁם may easily have arisen as a corruption of מִשְׁכּוֹ 'they spread out or deployed,' the verb which is actually used of the skirmishing advance of the Israelite tribes upon this occasion in ch. 4⁶ (cf. note). Winckler (followed by Marquart, Bu., No., Kit., Zapletal) proposes שָׁרו 'they travelled or passed along,' from the root שָׁר, which is well known in Assy. as *šaru* and in Ar. as *sāru*, but only occurs once in Heb., viz. Isa. 57⁹, and there very doubtfully.‡ La.'s suggestion נְשִׁיטִים 'captains'—'From Ephraim (there were) captains in the vale'—is opposed by the facts that it fails to supply the desiderated verb; and that נְשִׁיטִים, so far as can be judged by the occurrences of the term, appear to have been a class of officers connected with chariots (cf. NHTK. p. 139), of which the Israelites possessed none at this period.

'After thee, Benjamin!' The words אַחֲרֶיךָ בְּנִימִן are viewed with suspicion by many recent commentators; but, as it seems, without just cause. They occur again in Hos. 5⁸, where the prophet is describing the hasty preparations for battle, in face of the Assyrian invasion:—

'Blow the horn in Gibe'ah,
The trumpet in Ramah;
Raise the battle-cry, Beth-aven,
"After thee, Benjamin!"'

Here the sense which we attach to the verb הֲרִיעוּ 'Raise the battle-cry,' is that which it possesses in Josh. 6^{5,10,16,20}, 1 Sam. 17^{20,52}, Isa. 42¹³, 2 Chr. 13¹⁵; cf. Judg. 15¹⁴; and the natural inference is that the words 'After thee, Benjamin!' which immediately follow, represent the old Benjaminite battle-cry; both in Hosea, and also,

* It can scarcely represent שִׁבְלֵם (*sic* for שִׁבְלֵם), as La. supposes.

† שִׂרְשֵׁם is similarly treated as a verbal form by H, 'delevit eos in Amalec'; and apparently by the paraphrase of ש, 'From the house of Ephraim arose Joshua' the son of Nun at the first—he made war with the house of 'Amalek; after him arose king Saul of the house of Benjamin—he destroyed the house of 'Amalek.'

§ Cheyne, Marti, Box emend וַתִּשָּׁחֵי 'And thou didst anoint thyself to (the god) Melek with oil,' in place of וַתִּשָּׁרֵי 'And thou didst journey.'

by inference, in the Song of Deborah. So G. A. Smith, *The Twelve Prophets*, on Hos. 5⁸. If this be so, the meaning may be, 'Benjamin (the tribe) takes the lead; let others follow!' or, 'After thee, Benjamin (the eponymous ancestor), we (the tribesmen) follow!' For אַחֲרַי 'after' used of following a leader in battle, cf. *ch.* 4¹⁴, 1 Sam. 11⁷. As the battle-cry stands in the Song, the precise sense may be '(The cry) "After thee, Benjamin!" (was) among thy clansmen'; or, 'Those from Ephraim spread themselves in the vale "after thee, Benjamin,"' i.e. the Benjaminites headed the Ephraimites, as their war-cry would have them do.

Many scholars (Hollmann, Köhler, Justi, Ros., Stu., Kit., Ber.) explain אַחֲרַיך 'After thee (Ephraim) came Benjamin'; but, apart from the improbability that the same expression should occur here and in Hosea in different senses, it is unlikely that the poet should address the tribe mentioned in the previous stichos (and there alluded to in the 3rd pers.), and not the tribe with which the present stichos deals.

In place of אַחֲרַיך, ^{AL} offer the reading ἀδελφοῦ σου (connected with κοιλᾶδι in the preceding line), i.e. אֶחָיך 'Thy brother, Benjamin, among thy (Ephraim's) clansmen.' This is adopted by Bu., No., La., Kent, Cooke (*Comm.*), but is in no way preferable to ^U.*

thy clansmen. עֲמֻמֶּיךָ. The plur. form regularly denotes 'kinsmen'; as e.g. in the phrase 'he was gathered to his kinsmen' (עֲמִיּוֹ), Gen. 25⁸, *al.* Upon the view that עֲמֻמֶּיךָ (for עֲמִיךָ) is a mark of Aram. influence, cf. *Additional note*, pp. 171 ff.

Machir. Mentioned in Josh. 17^{1b.2} R^p as the first-born son of Manasseh, and in Num. 26²⁰ P as the only son—a description which implies that Machir was the predominant clan of the tribe of Manasseh. Both passages associate Machir with the land of Gile'ad east of Jordan; in Josh. he is 'the father of Gile'ad' (הַגִּלְעָד i.e. clearly *the district*, and not a person), and is termed 'a man of war,' possessing 'the Gile'ad and the Bashan'; in Num. the fact that Machir inhabited this region is expressed by the statement that he 'begat Gile'ad.' In the same passage of Num. (נזי.³⁰ ff.) six grandsons (sons of Gile'ad) are assigned to Machir, of whom at any rate Shechem † and Íezer, i.e. Abi'ezer (cf. Josh. 17² R^p) pertained to the territory of the *western* division of Manasseh. In Josh. 17^{1b.2} we find that the

* Bu. supposes that אַחֲרַי came to be altered into אַחֲרִיךְ owing to the influence of Hos. 5⁸. Winckler and Marquart reject אַחֲרִיךְ altogether (as a gloss from Hos.), much to the detriment of the poetry.

† Vocalized שִׁכֶּם, whereas the city is always שִׁכֶּם; but the identity of the two cannot be doubted.

six *grandsons* of Machir, according to P in Num., are set down as his younger *brothers*.

Supposing that this late evidence were all the information which we possessed with regard to Machir, we should naturally infer that this predominant section of Manasseh settled first in Gilé'ad, and that it was only subsequently that some of its clans made their way into central Cana'an west of Jordan. If, however, the reconstruction of the original J narrative of the tribal settlement in Cana'an, which we have adopted from Bu., is substantially correct, and Num. 32^{39,41,42} forms the sequel of Josh. 17^{16ff.}, which certainly belongs to this narrative; then Manasseh first of all effected a settlement in the hill-country *west* of Jordan, and it was only subsequently to this that the clan of Machir, together with Ja'ir and Nobah, finding their west Jordanic territory too exiguous, pushed their way to the east of Jordan and made settlements there (cf. *Additional note*, pp. 49 ff.).

In our passage in the Song, it can hardly be doubted that Machir refers to *west* Manasseh. If this is not the case, there is no other allusion to this part of Manasseh; and supposing that a tribe so intimately associated with the scene of battle had refused its aid, it would certainly have been bitterly censured in the Song. On the other hand, Gilé'ad east of Jordan *is* mentioned, independently of Machir, and is censured for holding aloof (*v. 17*); the reference probably being to the tribe of Gad, which inhabited the southern portion of Gilé'ad. We seem therefore to have choice of two hypotheses: either the term 'Machir' is used in the Song, by poetic licence, of Manasseh as a whole, and here refers to west Manasseh to the exclusion of Machir in Gilé'ad; *or*, the Manassite settlements at this period were *west of Jordan only*; and the migration of Manassite clans (Machir, Ja'ir, Nobah) to the east of Jordan, which the J document already referred to supposes to have been carried out under the direction of Joshua', really only took place *later than the victory of Deborah*. This latter hypothesis seems to be preferable; since we have already noticed (p. 45) that the J document, as we know it, adopts the view that the whole tribal settlement of the Israelites took place under the direction of Joshua'.

Ultimately Machir was closely, and probably exclusively, associated with the east of Jordan. According to the genealogy of I Chr. 7¹⁴⁻¹⁶,* Machir is the son of Manasseh by an Aramaean concubine; and Machir's son Gilé'ad takes a wife named Ma'acah, *i.e.* the Aramaean clan of the Ma'acathites, which, together with the Geshurites, the children of Israel were unable to expel from Gilé'ad (Josh. 13¹³ J). This means, without a doubt, that ultimately the Machir-section of Manasseh became closely fused by intermarriage with the Aramaeans

* The text of this passage, as it stands in 𐤀, is somewhat confused and corrupt; but the solution is fairly transparent: cf. Curtis, *ICC. ad. loc.*

who remained dwelling in the territory east of Jordan ; cf. the way in which the genealogy of 1 Chr. 2 includes North Arabian clans, such as Jerahme'el, among the descendants of Judah.

the commanders. Heb. *m^hôḥēḱîm*, as in *v.*⁹ (*note*).

men wielding. The Heb. verb *môš'khîm* is here satisfactorily explained from Ar. *masaka*, 'to grasp and hold,' which is in like manner construed with the prep. **ב**, cf. Ges., *Thes. s.v.* 2. The explanation favoured by Mo., La., Smith, '*drawing* the truncheon' (cf. for constr. with **ב**, 1 Kgs. 22³⁴ **וַאִישׁ מִטָּךְ בִּקֶּשֶׁת** 'and a man drew a bow') is hardly so natural ; and still less so the interpretation of Ges. (doubtfully), Cooke, No., Kit., '*marching along with* the truncheon,' in supposed accordance with the use of *māšak* noticed under *ch.* 4⁶.

the truncheon. Vocalizing **בַּשֵּׁבֶט** and omitting **סֶפֶר**. Heb. *šēbhēṭ* here denotes the wand of office—a term which, in two other poetical passages (Gen. 49¹⁰, Num. 21¹⁸), has for its parallel *m^hôḥēḱ* (the word which, in the plur., is rendered 'commanders' in the parallel stichos), in the sense *commander's staff*.

After *šēbhēṭ* **וְ** adds *sôphēr*—'*the truncheon of the muster-master*' (lit. *enumerator*)—an addition which is correct as regards sense, but spoils the rhythm by the introduction of one beat too many ; and must therefore be regarded as a gloss.

15. *And thy princes, Issachar.* Reading **וְיִשָּׁרִיךְ יִשׂ** : cf. **יְ** 'Principales tui, Issachar.' Such a direct address to the tribe imparts vigour and life to the description of the muster ; cf. *v.*^{14a, 16a}. **וְ** **יִשָּׁרִי בְיִשָּׁרִי** 'And my princes in Issachar,' is an awkward expression, and can scarcely be original. The force of '*my* princes' is obscure ; since it is unlikely that the poet, who elsewhere sinks his individuality, intends thus to identify himself specially with the tribe of Issachar. Ew., Ros., in defence of **וְ**, treat Deborah as speaking ; but in this case the words 'with Deborah' which follow are superfluous ; since it is impossible that the prophetess should, in one breath, allude to herself both in the first and third persons. Ges. and Hollmann follow Kimchi in taking **יִשָּׁרִי** as a poetical plur. form for the ordinary **יִשָּׁרִים** ; but the existence of such forms is more than doubtful, the cases cited being otherwise explicable (cf. G-K. § 87 *g*). **καὶ ἀρχηγὸς ἐν Ἰσασαχαρ**, seems to presuppose the vocalization **יִשָּׁרִי בְיִשָּׁרִי**, a variant which is found in some Heb. MSS. *teste* Ginsburg. Such a use of the Construct State before the prep. **ב** may be illustrated by **הָרִי בְגִלְבֹּעַ** 'Ye mountains in Gilboa,' 2 Sam. 1²¹ ; **שִׂמְחַת בְּקָצִיר** 'joy in harvest,' Isa. 9² : cf. G-K. § 130 *a*. This reading, which is favoured by Rabbi Tanchum, has been adopted by the majority of

moderns (Schnurrer, Justi, Stu., Ber., Müller, Cooke, Oet., No., La., Kit., etc.).

F 'duces Issachar,' פ' וְיִשָּׁכָר וְיִשָּׁכָר seem to have read וְיִשָּׁרִי simply, and this is adopted by Michaelis and Mo.; but it is hardly likely that so simple and obvious a reading should, if genuine, have suffered the alteration which we find in H. Bu. connects וְיִשָּׁרִי with סָפַר from the preceding stichos; and thus obtains the reading 'סָפַר וְיִשָּׁרִי בִישׁ', 'Count the princes of Issachar' (*sc.* if you can!). This emendation (followed by Marquart) of course necessitates the taking of the words עַם דְּבִרָה into the next stichos (see *note* following). Such an emphasis upon the innumerable princes or leaders of Issachar (not to speak of their followers) is scarcely, however, in accord with the poet's moderate assessment of the whole fighting force of Israel in *v.*⁸. Winckler's emendation of וְיִשָּׁרִי into וְיָסְרוּ 'and they journey' is altogether improbable; cf. *note* on the supposed occurrence of this verb in *v.*¹⁴, 'From Ephraim . . . vale.'

with Deborah. Bu. reads עַם in place of עַם of H—'the people (*i.e.* clansmen) of Deborah,' comparing the use of עַם in *v.*^{18a}. So Marquart.

and Naphtali was leal to Barak. Reading וְנַפְתָּלִי בֶן לְבָרַק. Naphtali is here conjecturally restored in place of Issachar. That Naphtali, 'le nom le plus essentiel de cette histoire' (Reuss: cf. *v.*¹⁸), should be altogether unmentioned in the strophe which describes the heroic response of the patriotic tribes, appears highly improbable; and it is equally unlikely that the poet should have been guilty of the prosaic inelegancy which is occasioned by the repeated mention of Issachar in the parallel stichoi. If the statement of the prose-narrative that Barak belonged to Kedesh of Naphtali is part of the original story, and not due merely to the combination of the Jabin-tradition (cf. p. 82), the mention of Naphtali in connexion with Barak is what we should expect. The substitution of Naphtali for Issachar is also favoured by Stu., A. Müller, Mo. (*SBOT*), D. H. Müller, No., Driver, Kent, Cooke (*Comm.*), Gress.

בֶּן in the sense 'steadfast,' and so 'reliable' or 'honest,' is found several times in Heb.: cf. especially Gen. 42^{11.19.31.33.34}, where Joseph's brethren say בָּנִים אֲנַחְנוּ 'we be *honest*'; Prov. 15⁷, 'The heart of a fool is *not reliable*' (לֹא-בֶן) || 'The lips of the wise disperse knowledge'; and the expression דְּבָרִים אֲשֶׁר לֹא-בֶן 'things which were *not right*,' 2 Kgs. 17⁹. The adj. *kēnu* is also very frequent in Assy. in the sense 'reliable' or 'faithful,' and in Syr. *kīn* has the

meaning 'steadfast,' 'just.' On this interpretation of בָּן we obtain, with no more serious alteration of the text than the addition of ל before בָּרַק, the sense 'leal to Barak' as an excellent parallel to 'with Deborah' in stichos *a*.

The view that בָּן is the substantive which elsewhere in the O.T. has the meaning 'base' or 'pedestal,' here used metaphorically in the sense 'support' or 'reliance,' is as old as the Jewish commentators *; and has been adopted by many of the earlier modern commentators (Köhler, Herder, Hollmann, Justi, Stu., etc.). Schnurrer likewise regards בָּן as a substantive; but connects it with the Ar. verb *kanna*, 'to cover or protect' (cf. Heb. *gānan*), and so explains in the sense 'bodyguard' or 'escort.' This root, however, is not otherwise known in Heb. (Ps. 80¹⁶ is scarcely an instance).

The explanation of בָּן as the adverb 'so' or 'thus' appears to be impossible, as אֵל now stands. R.V. renders 'As was Issachar, so was Barak'; but this meaning cannot be extracted from the Heb. without the addition of כִּי before יִשְׁשַׁכָּר; and even so it is, as Mo. remarks, 'difficult to imagine a worse anticlimax.' Scarcely less feeble is the sense which is gained by No. through the insertion of עַם before בָּרַק: 'and Naphtali was similarly with Barak.' אֵל^b omits יִשְׁשַׁכָּר; and connecting כֵּן בָּרַק with the following stichos, offers the rendering οὕτως Βαράκ ἐν κοιλάσιν ἀπέστειλεν ἐν ποσὶν αὐτοῦ. Following this suggestion, von Gumpach, Grä., Grimme combine the stichoi and read בֵּן בָּרַק בְּעֶמֶק שִׁלָּה בְּרִגְלָיו. Since, however, it is difficult to believe that בְּרִגְלָיו has here any other meaning than 'at his heel' (cf. 4¹⁰ note), we may in this consideration find evidence for the view that the expression refers back to the mention of Barak in the *preceding* stichos, as in אֵל.

אֵל^L, S^b, omitting all traces of stichos *b*, represent stichos *c* by ἐξαπέστειλε πεζοὺς αὐτοῦ εἰς τὴν κοιλάδα, i.e. בְּעֶמֶק שִׁלָּה רִגְלָיו. On the supposition that this is original, the active verb and the suffix of the object demand a subject, which might be found in בֵּן בָּרַק of אֵל (so La., but reading וּבָרַק). Or it is conceivable that the letters כִּנְבָּרַק might conceal an original וְנִפְתָּלִי; and stichos *b* would then run, 'And Naphtali despatched his footmen to the vale.' Such a

* Cf. the statement of R. Tanchum (*apud* Schnurrer); 'Some think that כֵּן signifies those upon whom Barak *relied*, and whom he had as his followers; from that meaning of the word כֵּן which is found in Ex. 30¹⁸ וְכֵן 'כִּיּוֹר וְכֵן' ['a laver and its base'].

stichos, however, does not offer so good a parallel to stichos *a* as that which we have adopted with but little alteration of **ח**; and we may reasonably doubt a reconstruction which involves the annihilation of the single stichos at the close of the strophe which appears elsewhere to be characteristic of the poem (cf. p. 102).

he was loosed. The subject of the verb is the tribe mentioned in the preceding stichos, which we have assumed to be Naphtali, Barak's own contingent. The verb שָׁלַח (used similarly in the active, of releasing a bird, Gen. 8^{7,8}, Deut. 22⁷, or beast, Ex. 22⁴, Lev. 16²²; or pent up waters, Job 12¹⁵) vividly describes the sudden onrush of the tribe at the moment when Barak's word of command unleashed it, as it were, from restraint.

at his heel. Lit. 'at his feet': cf. 4¹⁰ *note*.

Utterly reft into factions, etc. Reading

נִפְרָד נִפְרָד לְפִלְגּוֹת רְאוּבֵן
נְדוּלִים חֲקָרֵי לְבֹ

ח offers an isolated four-beat stichos, which may be rendered 'In the clans (or districts) of Re'uben great were the resolves of heart.' As this stands, Heb. *p^elaggôth*, lit. 'sections,' may be compared with the use of *p^eluggôth* in 2 Chr. 35⁶ of the 'divisions' of the priestly families for the purpose of Temple-service. So **ט** renders בִּזְרְעִית 'in the family.' The cognate Bab. *pulug*[*g*]*u* and *pulukku* denote a 'division' or 'district' of a country; Phoenician פִּלַּג *id.* This seems to be the meaning intended by **ע**^B in *v.*¹⁵ εἰς τὰς μερίδας (*v.*¹⁶ εἰς διαρέσεις, 'A. *id.*, **ע**^L *v.*¹⁵ ἐν ταῖς διαρέσεσιν are ambiguous), **ס**^P חֲחִימֵי, Ar. *القسم*. R.V.'s rendering of *p^elaggôth* by 'water-courses' depends on the use of the term in Job. 20¹⁷, and the meaning of the cognate *p^elāghîm*, 'canals' (lit. 'cuttings'), which is found in Isa. 30²⁵, Ps. 1³, *al.* This meaning, however, is not so likely in the present connexion as that given above. חֲחִי (which occurs again in this uncontracted form in Isa. 10¹; cf. עֲמִידָה for עֲמִיד *v.*¹⁴), from an assumed sing. חֶק (Ar. *ḥakḥ* = the normal חֶק 'statute,' i.e. 'action prescribed,' must here be taken to mean *actions prescribed for oneself*, i.e. *resolves* (so BDB.). Such a usage of the term is, however, unparalleled elsewhere. The stichos recurs in *v.*^{16c}, where it is clearly a marginal note offering two variations, which has crept into the text. One of these variations is חֲחִיר 'searchings' or 'questionings,' in place of חֲחִי; and this is probably correct, and has been

adopted above. 'Searchings of heart' must be taken to mean, not (as we might use the phrase) anxious self-questionings, but the ascertaining of the views of others, or, as we should express it, *interchanges of opinion*. The trait of indecision and ineffectuality is noted as characteristic of Re'uben in Gen. 49^{4a}. The other variation לפלגות appears, as the text stands, to be less natural than בפלגות, though it is possible to explain ל in the sense 'at'; cf. לחוף ימים, 'at the shore of the seas,' in *v.* 17^{ba}.

It may be regarded as certain that this single stichos cannot originally have stood by itself without a parallel, at the commencement of the strophe which deals with the tribes which failed to respond to the summons to arms: and if it was composed, as we now find it, as a four-beat stichos, we must suppose that a similar corresponding stichos, which originally preceded it, has wholly disappeared from the poem. The possibility that the stichos represents the remains of *two parallel stichoi* cannot, however, be overlooked: and since the characteristic rhythm of the other couplets of the strophe is clearly 4 + 3 beats, it may be inferred that this measure was also employed in the opening couplet. לב חקרי לב (or חקקי לב) forms a single beat; but, if we add a suffix to לב, we obtain two beats—*hikrê libbô*, lit. 'the searchings of his heart,' i.e. 'his searchings of heart.' Thus it is reasonable to suppose that לבו חקרי גדולים may represent the three-beat stichos *b*; and, if this is so, we have the last two beats of stichos *a* in לפלגות ראובן. Now, 'Great were his questionings of heart' suggests, as a parallel, *divisions* of counsel in regard to the summons to arms on the part of the clansmen of Re'uben; and this is just the sense which may properly be attached to לפלגות 'into divisions,' i.e. into divergent opinions, or into parties giving opposed counsels, or, as we should say, *factions* (so *V* renders 'diviso contra se Ruben'): cf. Syr. *pulǧǧ* 'division,' which may mean *hesitation*, and also σχίσμα.

What is desiderated, therefore, to supply the first part of the stichos is some verb meaning *was divided* or *was rent asunder*; and this may very likely have been נפַרַר, which may well have been emphasized by a preceding Infinitive Absolute נַפְרֹר. The emphatic נַפְרֹר נַפְרֹר supplies a suitable parallel to נְדוּלִים in stichos *b*; both statements laying stress upon the *extent* of Re'uben's fruitless discussions and differences of opinion. The use of the prep. ל 'into' after a verb expressing *division* can be abundantly illustrated (cf. חָצָה ל 'divide into,' Gen. 32⁸; נָתַח ל 'cut up into,' Judg. 19²⁹; קָרַע ל 'rend into,' 2 Kgs. 2¹²; הִכָּה ל 'smite into,' Isa. 11¹⁵). לפלגות may therefore be regarded as the more original reading; and בפלגות may

be thought to be a correction—as more naturally expressing the sense ‘in’ or ‘among,’ which seems to be required by *ל*.

16. *the folds*. Heb. *mišpetháyim*. The meaning assigned to the word is purely conjectural. It suits the context here (cf. the stichos following), and in the one other occurrence, Gen. 49¹⁴, where the tribe of Issachar is compared to ‘an ass of strength (lit. bone) lying down amid the *mišpetháyim*. And he saw rest that it was good, and the land that it was pleasant, etc.’ In Ps. 68¹¹ (apparently based upon our passage) a cognate term is used:—‘Will ye lie (*or* When ye lie) among the *šephattáyim*?’ Both forms are duals, and may refer to some kind of double pen, with an inner and outer enclosure: Roediger in Ges., *Thes.* 1471, compares *G̃dhērôtháyim*, used as a proper name in Josh. 15³⁰, and meaning ‘two fences,’ or ‘double fence.’ *G̃dhērôth* is a term employed of sheep-folds (cf. Num. 32^{16, 36}, 1 Sam. 24¹, *al.*) constructed for permanent use out of solid material (cf. Num. 32¹⁶, ‘We will *build* sheep-folds’); and it is possible, as Roediger suggests, that *mišpetháyim* may have been the name applied to temporary folds made of hurdles. This explanation of the term, which is as old as David Kimchi, is adopted by the majority of moderns.

The rival interpretation is ‘ash-heaps,’ such as are found in close proximity to modern Palestinian villages. This is based on the fact that there is a subs. *’ašpôth*, meaning ‘ash-heap,’ or ‘refuse-heap,’ occurring in 1 Sam. 2⁸, Ps. 113⁷, Lam. 4⁵, *al.*, which is supposed to be cognate. The advocates of this interpretation do not seem, however, to have explained the connexion of the village ash-heap with pastoral amenity and the tending of flocks; nor the use of the dual, which appears, upon this view, to be quite anomalous. Were there, regularly, *two* ash-heaps to each village or encampment?

The Versions were puzzled by *mišpetháyim*, and seem to have guessed at its meaning. *Gr*^B τῆς διγομίας; *Gr*^L transliterates τῶν μωσφαθαυμ (^Aμωσφαυθαυμ); ^A. τῶν κλήρων (so *Gr* in Gen. 49¹⁴, Ps. 68¹¹; *Fr* in the latter passage ‘inter medios cleros’); *S*. τῶν μεταχμίων; *Fr* ‘inter duos terminos’; *S*^P *חבלי מפתח* ‘between the foot-paths’ (so in Gen.); *Ar*. *بين الطرق* *id.*; *Ch* *בין תחומין* ‘between the boundaries’ (similarly in Gen.).

the pastoral pipings. Heb. *šerîkôth ’ădhārîm*, lit. ‘the hissings *or* whistlings of (*i.e.* for) the flocks.’ In Latin *sibila*, ‘hissings’ or ‘whistlings’ is used similarly of *piping* to flocks upon a mouth-organ of reeds: so Ovid, *Met.* xiii. 784 *f.*:

‘Sumptaque arundinibus compacta est fistula centum;
Senserunt toti pastoria sibila montes.’

Cf. also ‘sibila cannae,’ Statius, *Thebais* vi. 338. The Latin term is

also employed by Columella, *De Re Rust.*, ii. *cap.* 3, of *whistling* to oxen to induce them to drink more freely after work :—‘Quem [cibum] cum absumpserint, ad aquam duci oportet, sibiloque allectari, quo libentius bibant.’ Cf. the way in which whistling or music will cause cows which are difficult milkers to yield their milk more freely (a fact noted *e.g.* by Hardy, *Tess of the D'Urbervilles*, *ch.* 17).

These parallels suggest that Heb. *šrîkôth* here refers to playing to flocks upon a mouth-organ or pipe—probably the ‘*ūghābh*, which is explained by *ⲧ* ‘*abbūbhā*, *Ⲭ* ‘*organon*,’ as a reed-pipe—the purpose being to conduce, in one way or another, to their physical well-being by the *charm* of the shrill music (‘*ūghābh*’ probably gains its name from its *sensuous* effect : cf. the meaning of the root in Heb. and Ar.). Thus the indolent Re’ubenite is pictured as charmed into inaction by the music of the shepherd’s pipe.

The Heb. root does not occur elsewhere in connexion with flocks ; but the verb *šîrak* is used in Isa. 5²⁶, 7¹⁸, Zech. 10⁸, of the employment of hissing or whistling, as a *signal*. Hence some have thought that the reference in our passage is to whistling (*not* piping) in order to call the flocks together. But why should the sound of such shepherd’s calls be represented as keeping Re’uben at home ?

Heb. *šrîkôth* bears striking resemblance to the Greek *σῆρυγξ*, which has been supposed by Lagarde and Lewy (cf. references in BDB.) to be derived from the same Semitic root *šrk* ; but it is more likely that both words are independently onomatopoeitic from the sound which they describe. Cf. the English word *shrick*.

17. *Gil’ad*. The reference appears to be to the tribe of Gad, and *not* to East Manasseh (cf. *note* on ‘*Machir*,’ *v.* 14). The history of Jephthah (10¹⁷⁻¹²⁷) shows us Gil’adites, who presumably were Gadites, inhabiting the southern portion of Gil’ad, in proximity to the land of ‘Ammon. On the use of the term ‘*Gil’ad*,’ cf. *ch.* 10¹⁷ *note*. Gad is read in place of Gil’ad by *S^p*, Arm., Goth., and a few codd. of *Ⲭ* ; while Ar. interprets Gil’ad as referring to Re’uben.

And Dan abideth by the ships. Omitting *לְפָנֶיךָ* before the verb with two Heb. MSS., *Ⲉ*, *ⲧ*, Ar., and with *S^p* as it now stands.* *Ⲭ*, which has the support of *Ⲭ*, offers a fine and vigorous line with its rhetorical query, ‘And Dan—wherefore abideth he by the ships?’ But elsewhere throughout the strophe the scheme of rhythm in the couplets appears to be 4 + 3 beats ; and, if we adopt the reading of *Ⲭ*, we have here, exceptionally, a stichos *b* containing *four* beats instead of three, which is improbable.

* *S^p* reads *לְפָנֶיךָ לְדָן וְלָאֵלֶּיךָ* ‘And Dan to the harbour draws ships’ ; but the resemblance of *לְפָנֶיךָ* ‘to the harbour’ to *לְפָנֶיךָ* ‘wherefore?’ suggests that this latter may have been the original reading, and that the alteration may have been induced by the context.

The reference to Dan in connexion with *ships* may be taken to indicate that clans of this tribe had already made their migration to the extreme north of Canaan, as related in *ch.* 18, Josh. 19¹⁷ J; since, if the tribe was still dwelling only in the south, it is difficult to understand how they can have become seafarers (cf. *note* on *ch.* 1³⁴). Even the supposition that the Danites carried on trading by sea from their northern home (though supported, as Mo. notes, by the following couplet with regard to Asher) is not without its difficulties; since *ch.* 18^{7,28}, informs us that Laish, which they conquered, was isolated, not merely from Aram on the east, but from Sidon on the west; though it is true that 18⁷ at the same time compares the habit of life of the people of Laish with that of the Sidonians. It is reasonable, however, to suppose that the Danites, living on friendly terms with the Phoenicians, may shortly after their settlement have entered into close relationship with them, and taken service on board their ships (so Stu.). It was probably the protection extended by the Phoenicians to the tribes of Asher and Dan (in return, we may infer, for service rendered) which made these tribes unconcerned to throw in their lot with the central Israelite tribes, and respond to the summons to battle. Bu., who formerly (*RS.* p. 16) proposed to emend אֲנִיִּים 'ships' into נְאוֹתָיו 'his pastures,' now (*Comm.*) adopts the view which we have advocated, and retains the reading of 18.

Asher sat still, etc. Cf. *note* on *ch.* 1³², 'the Asherites dwelt, etc.'

his creeks. Heb. *mīphrāsāw*, which only occurs here in Heb., is elucidated by its philological connexion with Ar. *furḍah*, 'a gap or breach in the bank of a river, by which ships or boats ascend'; *firād*, 'the mouth of a river' (Lane). The verb *faraḍa* means 'to make a notch or incision.' It is possible to explain the possessive suffix of *mīphrāsāw* as 'its creeks,' referring to 'the shore of the seas' in the preceding stichos (so Mo.).

18. *that scorned its life, etc.* The expression is unique, and must be regarded with suspicion. The verb *hērēph* elsewhere properly denotes *verbal* taunting or reproach (cf. BDB.: properly, 'to say sharp things about'; connected with Aram. *harrēph*, 'sharpen'); though it is true that there are passages in which it is used metaphorically of *insulting* God by injustice to the poor (Prov. 14³¹, 17⁵), or idolatry (Isa. 65⁷). This latter usage, however, hardly supports the conception implied in 'insulting' one's own life by exposing it to risk of death. The Ar. parallels cited by Ros. are not very apposite ('We count our lives of light value (*lanurḥīsu*) in the day of battle,' *Hamasa*, p. 47, ed. Freytag; *tahāwana nafsahu*, 'he held his life of light worth'); since the expressions there used, so far from appearing forced and strange, are familiar all the world over.

Phrases used elsewhere in O.T. of risking one's life are 'he cast his life in front' (וַיִּשְׁלַךְ אֶת-נַפְשׁוֹ מִנֶּגֶד) *ch.* 9¹⁷; 'I placed my life in

my hand' (וַאֲשִׁימָה נַפְשִׁי בְּכַפִּי) *ch.* 12³, cf. 1 Sam. 19⁶, 28²¹; 'he poured out his life unto death' (הֵעֵרָה לְמוֹת נַפְשׁוֹ) Isa. 53¹². It is conceivable that this latter phrase (הֵעֵרָה נַפְשׁוֹ לְמוֹת) may have been the original reading in our passage; cf. the use of the Pi'el of the same verb in Ps. 141⁸, 'Pour not out my life' (אַל־תֵּעַר נַפְשִׁי), *i.e.* 'Give me not over unto death.' So Ball, who, as an alternative, suggests the emendation הַחַרִּים for חָרַף—'*devoted* his life to death' (on *heḥērim* 'devote' to a deity, usually by destruction, cf. *note* on *ch.* 1¹⁷)—a striking and vigorous expression which may very well have been employed, though no close parallel can be cited. Cf., however, the words of St. Paul in Rom. 9³: ἡὐχόμεν γὰρ ἀνάθεμα εἶναι αὐτὸς ἐγὼ ἀπὸ τοῦ Χριστοῦ ὑπὲρ τῶν ἀδελφῶν μου, κτλ. 'Ανάθεμα is the regular rendering of אֵר for Heb. *ḥērem* 'devoted thing,' and ἀναθεματίζειν for the verb *heḥērim*.

to the death. Lit. '(so as) to die.'

on the heights of the field. Cf. *note* on 'the field of Edom,' *v.* 4. The use of the expression here is somewhat enigmatical, in view of the fact that the scene of the battle was the low-lying plain of Esdraelon (called 'ēmek, 'vale,' lit. 'depression,' in *vv.* 14, 15). It can hardly mean (Cooke, *Comm.*) that 'the two tribes came fearlessly down from their mountain-homes prepared to sacrifice all for the cause,' because it was not *on the heights* of their mountain-homes that they risked their lives. Mo. thinks that the phrase 'may perhaps be employed here of the mounds and hillocks in the plain, which, however inconsiderable, were positions of advantage in the battle, especially as rallying points for the hard pressed Canaanites before the rout became complete. These elevations, where the enemy fought with the ferocity of desperation, Zebulun and Naphtali with reckless hardihood stormed and carried.' It may be doubted whether any part of the plain itself would have been described as *sādhē* (*v.* 4 *note*): yet it is quite likely that the battle may have raged round about the cities of Ta'anach and Megiddo on the edge of the hill-country; or that many of the Canaanites, finding their escape to Harosheth barred by the flooded Kishon (cf. *note* on 4¹⁶), may have been driven into the hills of Galilee, which come down to the right bank of the river, and there made their last desperate stand.

19. *the kings of Canaan.* *I.e.* the petty chieftains of the fortified Canaanite cities such as Ta'anach and Megiddo, who appear as a rule to have been mutually independent (cf. the condition of affairs in earlier times as gathered from the T.A. Letters; *Introd.* pp. lxx ff.); but are here united for action under the leadership of Sisera, who was, presumably, the king of Harosheth. Cf. the alliance among the Amorite city-kings of the south against Joshua, as related in Josh. 10.

The use of the term 'king of Canaan' as applied to Jabin in *ch.* 4² by R^{E2} is different; in that it pictures him as overlord of northern Canaan as a whole—a conception which gains no support from the older narrative. Cf. *note ad loc.*

In Ta'anach, etc. On the sites of these cities cf. *ch.* 1²⁷ *note.*

the rills of Megiddo. Lit. 'the waters of M.' The reference doubtless is to the numerous small tributaries of the Kishon which flow down from the hills to the south-east of Megiddo. The modern Ar. name for the Kishon is Nahr el-Muḡatta', *i.e.* 'River of the forlorn or shallow.' While there is no philological connexion between Megiddo and Muḡatta', we are probably right in inferring that the modern name was bestowed owing to its assonance with the old city-name of unknown meaning. So Smith, *HG.* p. 387, *n*¹. A similar phenomenon is noted as regards the Heb. name Hārōsheth compared with the modern Ar. el-Hārīṭīyyeh (*ch.* 4² *note*).

The gain of money they took not. Most commentators interpret this statement as meaning that they were balked in their expectation of spoil. So Mo.: 'it was a most unprofitable campaign for them; a sarcastic meiosis. The gains of war were in the ancient world one of the principal causes of war; cf. Ex. 15⁹.' This explanation is described by La., not unjustly, as 'pensée très banale et qui devance le cours des événements'; and it may be added that, if the reference is to hoped-for *spoil*, the description of this spoil as 'money' or 'silver' simply is not very natural: contrast *v.*³⁰. La. himself adopts the explanation offered by Rashi and Levi ben-Gershon, that the kings did not fight for payment like mercenaries, but with the wholeheartedness of men who are protecting their own interests. This is more probably correct. A third explanation, which is not impossible, is given by Kimchi, *viz.* that they did not accept money as ransom from the Israelites who fell into their hands, but slew them without quarter—the statement thus emphasizing the fierceness of the combat. Cf. the way in which Trojan combatants, when vanquished, are pictured as offering the Greeks a price for the sparing of their lives. Thus, in *Iliad*, vi. 46 ff., Adrestus addresses Menelaus:—

ζῶγρει, Ἀτρείος νιέ, σὺ δ' ἄξια δέξαι ἄποινα.
πολλὰ δ' ἐν ἄφνειοῦ πατρὸς κειμήλια κείτω,
χαλκός τε χρυσός τε πολύκμητός τε σίδηρος·
τῶν κέν τοι χαρίσαιο πατὴρ ἀπερείσι' ἄποινα,
εἴ κεν ἐμὲ ζῶν πεπύθοιτ' ἐπὶ νηυσὶν Ἀχαιῶν.

Il. x. 378 ff., xi. 131 ff. are similar.

Several commentators follow Tanchum in understanding *bēṣa'* in the sense 'fragment,' or, as we should say, 'bit' of money (cf. Ar. *baḏ'a*, Aram. *biṣṣa'*); primitive money taking the form of uncoined ingots, the value of which was tested by weight. Since, however,

there is no parallel for such a meaning elsewhere in the Heb. of the O.T., in which *béša'* occurs with frequency in the sense 'gain made by violence, unjust gain, profit' (BDB.), it seems preferable to acquiesce in the ordinary meaning, which is quite suitable to the context.

20. *From heaven fought the stars, etc.* The break between the stichoi is obviously to be placed upon הַכּוֹכְבִּים, which gives 3+3 beats to the distich; and not, as by פא , on נִלְחָמוּ (so R.V., 'They fought from heaven, The stars in their courses fought, etc.'): since this offends against rhythm by offering 2+4 beats.

From their highways. Winckler proposes to emend מִמִּסְלָתָם into מִמְּוִלָּתָם 'from their stations.' The term proposed, *mazzālôth* (cf. 2 Kgs. 23⁵), is elucidated from Bab., in which *manzazu* denotes a 'place of standing,' from *nazāzu* 'to stand'; and a fem. form *manzaltu* (= *manzastu*) is found, e.g. in iii. R. 59, 35a: 'The gods in heaven in *their mansions* (*manzaltišunu*) set me.' These heavenly *mansions* or *stations* are identified by Delitzsch (*Prolegomena*, p. 54) with the zodiacal stations; while Jensen (*Kosmologie*, pp. 347 f.) thinks that they denoted rather the stations of certain fixed stars and planets, lists of which are found in the Bab. inscriptions. In Ar. *manzil* denotes a 'lodging place' or 'mansion'; and the plur. *al-manāzil* is used of the twenty-eight *mansions* of the moon. Thus the occurrence of מִמִּסְלָתָם in our passage would be appropriate to the context; and it is possible that the reading of פא may represent the easy substitution of a common term for the more unusual word: but since מִמִּסְלָתָם of פא yields a good sense, the alteration is unnecessary.

21. *The torrent Kishon, etc.* Cf. Thomson's description of the probable circumstances of the rout, as cited under *ch.* 4¹⁶. A description of the Kishon is given under *ch.* 4⁷.

swept them off. The Heb. verb *gāraph* does not occur elsewhere; but the meaning which it bears is elucidated by the usage of the Ar.

verb *garafa*. Thus Ar. says جَرَفَتْهُ السُّيُولُ 'the torrents *swept it away*'; جَرَفَ النَّاسَ كَجَرَفِ السَّيْلِ 'it *swept away* men like the *sweeping away* of a torrent' (Lane). The sense attached to Aram. *g^raph* (here employed by ס) is similar. ס^{B} ἐξέσυρεν αὐτούς, ס^{A1} ἐξέβαλεν αὐτούς, פ 'traxit cadavera eorum,' render with approximate accuracy. ט , more freely, תברנן 'shattered them.'

It faced them, the torrent Kishon. Reading קִישׁוֹן נֶחַל קִדְמָם. As **U** stands, נֶחַל קִדְמָם is a source of great difficulty. The root *kdm* in Semitic has the meaning 'to be in front or before.' Hence, in Heb., the subst. *kédhem* means, locatively, *what is in front* (opposed to *āhôr*, *that which is behind*), Ps. 139⁵, Job 23⁸; and, especially, the *East*, this being the region which (possibly as the direction from which the sun rises) was regarded as *in front* in reckoning the quarters of the compass*; or, temporally, *what is before*, i.e. 'ancient or former time' (Bab. *kudmu* is employed in both these senses). From *kédhem* comes the denominative verb *kiddēm*, which means *to be in front* and also *to confront* in a hostile sense (cf. the Ar. *aḡdama*, 'cause to advance against the enemy').

The substantival form *k^hdhûmîm* only occurs in our passage; and, in accordance with the sense of the root, the main explanations of *nahal k^hdhûmîm* are two: (1) '*torrent of antiquity*' (lit. *of ancient times*) is adopted by **E**¹¹ χειμάρρους ἀρχαίων (perhaps 'men of old time'), **T** ('the torrent at which signs and mighty acts were wrought for Israel from ancient times'), Kimchi ('the torrent that was there from ancient times'), R.V. ('that ancient river'), Michaelis, Justi, Boettger, Bach., Reuss, Oet., Vernes, etc.; (2) '*torrent of (hostile) encounters*,' suggested by Abulwalid, and adopted by Schnurrer, Köhler, Hollmann, Ros., von Gumpach, Donaldson, Ber., Kit., etc.

Why the Kishon, rather than any other stream, should be spoken of as an *ancient* torrent is not clear. The only obvious explanation is that in the mind of the poet it had a *long history* behind it; and this explanation is also demanded by the rival rendering '*torrent of encounters*,' which would seem to imply that many historical battles had taken place in the neighbourhood of the Kishon. At the present day such a title as '*torrent of battles*' would be appropriate to the Kishon; since we know that, as a matter of fact, the vale of Esdraelon is the historical battle-field of Palestine: cf. Smith, *HG.* pp. 391 ff. But the inference that the Hebrew poet knew of traditions of ancient battles in this locality, such as that of Thutmose III. against the prince of Kadesh and his allies (cf. *Introd.* p. lxvii), appears somewhat precarious.

Other explanations of *nahal k^hdhûmîm* have been offered. Thus Meier, Cooke, Grimme, Driver render '*the onrushing torrent*,' and, similarly, Smith, Segond, 'the torrent of spates.' It is doubtful, however, whether such a sense can be maintained. The verb *kadama* in Ar. may mean 'to advance,' and 'to be bold in attack'; but always with the implied idea of *going in front of* (leading), or *coming in front of* (meeting), *some one else*; and the transference of this idea to an onrushing stream is somewhat remote. Still less probable is the

* Similarly, *mē'āhôr*, 'behind' = 'on the west,' Isa. 9¹², **U**¹¹; *yāmîn*, 'the right' = 'the south,' Ps. 89¹², **U**¹³, *al.*

sense, '*winding* (i.e. *self-confronting*) *torrent*,' adopted by Herder. The fact (noted by Mo.) is, however, worthy of observation that in Ar. *ḫadūm* (identical with our form) means a man who is *first in attacking the foe*, and so, *brave, courageous*. Thus the Heb. phrase would mean '*the torrent of heroes*,' if, as might be the case, the word was employed in Heb. in the Ar. sense.*

The Versions not already noticed are not helpful: 𐤅 'Cadumim'; 𐤌𐤕𐤌 (with 𐤌 erroneously for 𐤎), Ar. *id.*; 𐤀, Θ. *καδησεμ*; 𐤀𐤌𐤕𐤌 *καδημειμ*; Ἀ. *καυσώνων* (connecting with קרים 'east wind').

The emendation adopted above follows the private suggestion of Ball; and has been independently adopted, as regards קדמם, by Ehr.‡ It assumes that it is natural to find in the stichos a verbal parallel to נרפם of stichos α; and that the first occurrence of נחל is an erroneous insertion, made to explain the substantive קדומים, when this latter had taken the place of the verbal form קדמם. The form of the distich, with its identical term and inverted order in the parallel stichoi, may be compared with *v.*²¹.

It is true that the sense obtained through the emendation involves something of a hysteron-proteron; since, strictly speaking, the torrent 'came in front of' the Canaanites in their flight before it 'swept them away' in their attempt to cross it: yet we have no right to demand an accurately logical sequence from the poet; and it is legitimate to explain the second verb as to some extent explanatory of the first—the torrent swept them away *because* it confronted them in their flight.

The numerous other emendations which have been offered need not be noticed.

Bless thou, my soul, the might of Yahweh! Reading תברכי נפשי תהוה תדרכי is barely intelligible. The Imperfect תדרכי has been taken as a pictorial description of past events (R.V. *marg.* 'thou hast trodden down'; properly, 'thou treadest down': cf. the use of the Imperf. in Ex. 15⁵ תהמות יבסימו 'The deeps cover them')!—where the tense, in describing a past event, emphasizes 'the process introducing it and preliminary to its complete execution': Driver, *Tenses*, § 27a); or as a Jussive in place of the Imperative (so R.V. *text* 'March on'). עז is taken either as the direct

* On nouns of this form used in Heb. in an active sense, cf. G-K. § 84^a *m*. It is worth while to remark that, in *miphraṣ v.*¹⁷, *gārāph v.*²¹, we have instances of words of which the meaning would be obscure, were it not for the clear elucidation offered by Ar.

‡ So also (since the writing of the above note) Gressmann in *Die Anfänge Israels*, p. 186. Rothstein adopts the same verbal form in the plur.; but emends the remainder of the line beyond recognition—קדמו מים מרפבתם 'The waters confronted their chariots.'

accusative (R.V. *marg.*), and explained as abstract 'strength' for concrete 'the strong' (so *Ἔ* 'Conculca anima mea robustos'); or as an adverbial accusative 'with strength' (R.V. *text*, *ע* בתקוף: cf. G-K. § 118*q*). Upon either interpretation we have, if not 'simple bathos' (Mo.), at any rate a very weak conclusion to the strophe; and, as Mo. rightly remarks, 'most inappropriate as the conclusion of *vv.*^{20,21}, which tell how heaven and earth conspired to destroy Sisera.' On the other hand, the sense offered by the stichos as restored above, viz. an ejaculation of thanksgiving to *Yahweh* as the controller of the powers of nature which assisted Israel, is very suitable to the context; and may be compared with Ex. 15⁶, where, after allusion to the overwhelming of the Egyptian hosts by the Red Sea (as the Cana'anites were overwhelmed by the *Kishon*), the poet exclaims—

'Thy right hand, O *Yahweh*, is glorious in power;
Thy right hand, O *Yahweh*, dasheth in pieces the enemy.'

The use of the *Jussive* (תברכי) in place of the Imperative is scarcely to be termed 'rare' (Mo., referring to תברכי): cf. *ch.* 7^{17a}, Hos. 14², *וְיָ*³ (תשא Juss. coupled with the Imperat. קח); Ps. 51^{8,9}, *וְיָ*^{9,10} (Juss. three times, alongside of the Imperat. four times in the two following verses); Ps. 71^{2a} (Juss. twice; parallel to Imperat. twice in *v.*^{2b}); 71^{20,21}. It is possible, however, that the Imperative may have been originally written: cf. *בְּרַכִּי נַפְשִׁי* in Ps. 103^{1,2}.

The corruption of תברכי into תררכי is likely; ב and ד being very similar in the old character. *עו* יהוה may have been written *עו* ^י, and the ^י subsequently omitted through accident. That יהוה was sometimes thus abbreviated into ^י is proved by Jer. 6¹¹, where חמת יהוה of *וְיָ* is read as חמתי by *ש*; and by Judg. 19¹⁸, where בית יהוה is clearly an error for ביתי. Cf. Driver, *NHTS.*² p. lxi. n².

Mo.'s suggestion, combining part of the preceding stichos, *עו* נַפְשִׁי *נָחַל* קְרוֹמִים דָּרָה (similarly La.) is condemned, if by nothing else, by the monstrosity *נַפְשִׁי*.* The emendation of Ruben (adopted by Cheyne, *JQR.* x. p. 566; *EB.* 2652) is an example of how not to use the Assyrian dictionary.

22. *loud beat.* Lit. 'hammered' (*sc.* the ground). Cf. the English expressions, 'the hammer of countless hoofs'; 'to hammer along the road,' used of pushing a horse to a fast pace on the hard road. R.V. and most moderns render 'did stamp.' The Versions treat הִלְמָו ¹⁷ either as passive (*Ἐ*^B ἐνεποδίσθησαν, ^{AL} ἀνεκόπησαν, Θ. ἀνεκόπησαν, *ש* אשתלפא 'were drawn off,' *i.e.* possibly pulled *or* broken off) or

* The fem. subst. נַפֶּשׁ occurs some forty-nine times in the O.T. in the plural with the fem. termination, and never with the masc. termination; the form נַפְשִׁים in Ezek. 13²⁰ being clearly an error for חַפְשִׁים 'free.'

intransitive (𐤔 'cecidērunt,' 𐤍𐤕𐤌, Ar. سَطَ—all meaning 'fell,' or, as we should say 'stumbled'; cf. the rendering of 𐤔^B). Similarly, Kimchi explains that the form is 'a stative; as though he said, the horses' hoofs were battered (נִהְלְמוּ) through excessive galloping in the battle.' The same view is taken by other Jewish interpreters, and is adopted by A.V., 'Then were the horsehoofs broken, etc.' Mo., who favours this interpretation, vocalizes the verb as a passive הִלְמוּ (Pu'al not elsewhere found). Against it, we may remark that horses' *hoofs* are not very likely to be injured by excessive galloping,* more especially on a plain which must have been largely in the condition of a swamp owing to the heavy rain-storm (cf. *ch.* 4¹¹ *note*); and further, if the poet meant that they were *broken* or *bruised*, he would scarcely have expressed this by stating that they were *hammered* through themselves striking the ground.

Probably a passive sense is given to הִלְמוּ by the Versions and early interpreters owing to the prep. מִן 'from' or 'through' of the succeeding stichos as it stands in 𐤍, which seems to denote the *source* of the action denoted by הִלְמוּ. Cf., however, the *note* following.

Smith, who adopts the vocalization as a *passive* הִלְמוּ, renders as an *active* 'thudded'; but this term, which commonly denotes the dull, dead fall of a heavy body, is not very happy.

the horses. Reading plur. סוּסִים with Bu., Kit. *BH.*, Gress., by taking over the מ from the commencement of the following stichos. Cf. 𐤔^L, 𐤍^B.

off galloped, off galloped. Reading דָּהָרוּ דָּהָרוּ, as suggested by Kit., *BH.* Cf. 𐤔^B σπουδῇ ἔσπευσαν. The verb דָּהָר occurs again of a galloping horse in Nah. 3². 𐤍 reads מִדְּהָרוֹת דָּהָרוֹת 'through the galloping, galloping' (Suspended Construct State: cf. Gen. 14¹⁰). It seems likely, however, that the מ belonging to סוּסִים at the end of the preceding stichos came erroneously to be prefixed to דָּהָרוּ דָּהָרוּ, and this was then treated as מִדְּהָרוּ דָּהָרוּ, *i.e.* as an abbreviated plur. substantive (on the use of such abbreviations, cf. *footnote* §, p. 124). Adopting our emendation, the couplet offers two stichoi *parallel in sense*, and it may be noticed that such parallelism (either synonymous or climactic: cf. *Additional note*, p. 169) is characteristic of the poem:

* The modern Syrian horse has particularly good legs and feet, and is usually shod with plates; but in ancient times horses appear to have gone unshod. Isa. 5²⁸ refers to the hardness of the hoofs of the Assyrian horses ('like flint'), as a proof of their power to resist wear and tear; but whether this implies that trouble was common with the feet of ordinary horses is doubtful.

whereas the synthetic form of parallelism, which is offered by ה in this distich, is comparatively rare (cf. *vv.* ^{5b, 10a, 19b}).

The repeated *daharû daharû* is intended to represent the three-fold beat of a horse's gallop; and does so most accurately with the main *ictus* on the third beat; as in the final movement of the overture to Rossini's *Guillaume Tell*. Virgil represents the gallop by the familiar dactylic line, *Aen.* viii. 596,

‘Quadrupedante putrem sonitu quatit ungula campum’;

and this dactylic rhythm is adopted by Charles Kingsley in *My Hunting Song*:

‘Hark to them, ride to them, beauties! as on they go,
Leaping and sweeping away in the vale below’;

but the dactylic measure is not quite so true as the anapaestic. In Ps. 68¹¹ ה ¹² we find the measure $\simeq \text{—} \simeq$; *yiddôdhûn yiddôdhûn*, ‘Kings of hosts *are running, are running*,’ which is again intended to represent the sound of a cavalcade galloping away in the distance. This reminds us of the rhythm of Browning's *How they brought the Good News from Ghent to Aix*:

‘I sprang to the stirrup, and Joris, and he;
I galloped, Dirck galloped, we galloped all three.’

his chargers. Heb. ‘*abbîrâw*, lit. ‘his strong ones.’ The term is used elsewhere of horses in Jer. 8¹⁶, 47³, 50¹¹. Horses at this period were employed in chariots, and not (so far as we know) for riding purposes; but since the functions of chariotry in warfare were akin to those of cavalry in later times, the rendering ‘chargers’ may be held to be justified.

23. *Curse ye, curse ye Meroz!* Reading $\text{אָרוּר מֵרֹז אָרוּר}$, in place of ה $\text{יְהוָה מְלָאךְ אָמַר מֵרֹז אָרוּר}$ “‘Curse ye Meroz!’ said the Angel of Yahweh,” which is plainly unrhythmical (five beats). Such an allusion to the Angel of Yahweh in this ancient poem is also somewhat unexpected (cf. *ch.* 2¹ *note, end*). Probably אָרוּר became corrupted into אָמַר ‘he said’; and the natural query ‘Who said?’ was answered by supplying a subject—‘the Angel of Yahweh.’

Meroz is only mentioned here, and the site is unidentified. The modern Muraşşas, four miles north of Bêsân, which is doubtfully advocated by Buhl (*Geogr.* p. 217) after Guérin, is not philologically connected with the Heb. name; and conjectures that Meroz is the corruption of some better known name (cf. the suggestions cited by Mo. *SBOT*.) are necessarily futile, since we have no guide as to the

locality of the city. It is highly probable that the curse took practical effect, and the city with its inhabitants was destroyed by the Israelites, and never subsequently rebuilt. Cf. the fate of Penuel (*ch.* 8^{8,9,17}) and Jabesh of Gile'ad (*ch.* 21⁸⁻¹²) in similar circumstances.

For they came not to the help of Yahweh. Possibly Meroz was situated somewhere upon the line of the enemy's flight; and, like Succoth and Penuel on the occasion of Gide'on's rout of the Midianites closed its gates when it might have aided by cutting off the fugitives, or by supplying the pursuers with much needed refreshment.

mid the heroes. Heb. *bag-gibbôrîm* as in *v.*¹³. So R.V. *marg.* 'among the mighty.' R.V. *text* 'against the mighty' is less probable.

24. *Most blessed of women be Ja'el.* H's addition of 'the wife of Heber the Kenite,' which spoils the balance of the couplet, is a prosaic gloss derived from *ch.* 4¹⁷.

tent-dwelling women. Lit. 'women in the tent.' Cf. the phrase 'the tent-dwellers' applied to the Bedawin on the farther east of Jordan in *ch.* 8¹¹. Mo. compares the Ar. expression '*ahlu-lwabar*, 'the people of the hair-cloth tents.'

25. *a lordly dish.* Lit. 'a dish of (*i.e.* fit for) nobles.' Heb. *šéphel* occurs once again in *ch.* 6³⁸ to denote the dish or basin into which Gide'on wrung the dew from the fleece. The word is used in the cognate languages in a similar sense. Cheyne's emendation (*EB.* 2313) 'a bowl of bronze' (אֶרֶב deduced from Bab. *urudû*) is uncalled-for.

curds. Cf. *ch.* 4¹⁹ *note*.

26. *Her hand to the peg, etc.* Against the view that this description of Šišera's death is essentially different from that of *ch.* 4^{21 ff.}, cf. pp. 79 f. Cooke's contention (*Comm.*) that 'according to the parallelism of Hebrew poetry *her hand* and *her right hand* mean the same thing; and so should *nail* and *workmen's hammer*,' cannot be substantiated. Cf. Prov. 3¹⁶:

'Length of days is in her right hand;
In her left hand are riches and honour.'

So also Cant. 2⁶, 8³. The only difference in our passage is that the poet has chosen to use *yādhāh* 'her hand' instead of *s'mōlah* 'her left hand.' א^{BA}, L, F, Ar. explain correctly as 'her left hand.'

she stretched forth. Heb. תִּשְׁלַחנָה, apparently a plur. form, but probably intended for a sing.*

* The view that in this and a few other cases we have the remains of an emphatic form of the Imperfect, akin to the Ar. *modus energicus* 1, *yaktulanna*

the maul of the workmen. Heb. *halmûth 'āmēlim*. The expression has caused difficulty. The term *halmûth*, from *hālam* 'to hammer,' should represent the implement described under the term *maḳḳēbheth* in *ch.* 4²¹, i.e. a hammer or heavy wooden mallet; but elsewhere in Heb. substantives ending in *-ûth* are secondary formations denoting abstract qualities*; cf. G-K. § 86 *k*. The real existence of a concrete derivative from *hālam* is, however, a reasonable assumption; and possibly the true form of the subst. should be *halmath*. The Heb. verb *'āmal*, from which *'āmēlim* is derived, commonly means *to toil* (i.e. *to labour*, with the accessory idea of *weariness* or *painful endeavour*); and all its occurrences are, with possibly one exception (see below), very late. The subst. *'āmāl*, which occurs both in early and late literature, usually denotes, in its earlier occurrences, *trouble*; and the sense *toil* or *labour* is only found in the later literature, especially Ecclesiastes. The subst. *'āmēl* (of which our form is the plur.) means a *labourer* in Prov. 16²⁶, and is coupled with the cognate verb:—'The appetite of the labourer laboreth for him.' This passage occurs in the central section of Prov., which many scholars regard as pre-exilic; though a considerable body of opinion views the whole book as the product of post-exilic times. The word occurs twice in Job in the sense *sufferer*; and, in an adjectival sense, *toiling*, five times in Ecclesiastes†. Hence the occurrence of *'āmēlim* in our passage is commonly regarded with grave suspicion. Mo. remarks, עמלים does not mean *artisans* (smiths, carpenters), but men who are worn out, or wear themselves out, with toil and hardships; "hammer of hard-working (or weary) men" is a singular metonymy for a heavy hammer!'

Such a statement overlooks the fact that the cognate languages prove that the root can be used in the general sense of *work*, apart from the connotations noticed above. Thus Ar. *'amila* means 'to

for the ordinary *yaḳtulu*, is rejected by G-K. § 47 *k*; yet seems, at least in our passage, to be by no means improbable. Cf. the Phoenician form יעמסן, occurring in the inscription on the sarcophagus of Eshmun'azar king of Sidon (*CIS.* I. i. no. 3, ll. 5 f.):—'ואל יעמסן במשכב ז עלת משכב שני'—'and let him not superimpose upon this resting-place the chamber of a second resting-place.' יעמסן, which recurs in ll. 7.21, may be compared with the Ar. *modus energicus* II. *yaḳtulan*. Cooke (*NSI.* pp. 34 f.) treats יעמסן as a suffix-form 'carry me'; an explanation which involves a highly forced and unnatural treatment of the context.

If תשלחנה be not an energetic form, the alternative is to vocalize it as a suffix-form תִּשְׁלַחְנָה, and to treat יָדָהּ as an *accusativus pendens*:—'her hand, to the peg she stretched it forth.'

* The forms are mostly late. A complete list of them is given by König, *Lehrgebäude der hebräischen Sprache*, II. 1, pp. 205 f.

work *or* make,' 'amal 'work *or* occupation,' 'amil 'artisan'; Aram. 'amal 'to labour'; Bab. *nimelu** 'the produce of work,' *i.e.* 'gain *or* possession.' There is no difficulty, therefore, in supposing that 'āmēlīm may denote 'workmen' generally, *without* the connotation of toil *or* weariness.

The meaning of the phrase is correctly elucidated by שׁוֹן לְנֹסֶלֶת ^{5P} 'to the carpenter's mallet,' Ar. *id.*, ט לְאַרְזַחְתָּא דְנַפְחִין 'to the mallet of the smiths,' F 'ad fabrorum malleos' (treating הַלְמוֹת as a plur.). G^B, 'A. εἰς σφῆραν κοπιῶντων interpret עֲמָלִים in accordance with customary Heb. usage. G^{AL} εἰς ἀποτομὰς κατακοπῶν (^L κατακοπῶν) misunderstands.

she smote. Lit. 'hammered.'

destroyed. Heb. *māh^aḱā*, which only occurs here in the O.T., is explained from New Heb. and Aram. 'wipe out *or* erase,' Ar. *māḥaḱa* 'utterly destroy, annihilate.'

pierced through. The Heb. verb *hālaph* commonly means to *pass on*, *or pass away*; but is here used transitively 'passed (*i.e.* *pierced*) through.' This usage is substantiated by Job 20²¹, 'The bow of bronze pierces him through' (*taḥl^ephēhū*), where 'bow' is used metonymically for the arrow which is shot from it. Mo. explains 'demolishes,' lit. 'causes to pass away,' quoting Isa. 24⁵ חָלַף חֹק in support of the causative usage. This, however, probably means 'they have *passed by* (*i.e.* overstepped) the ordinance' (cf. || עָבְרוּ תוֹרוֹת 'they have transgressed the laws') and not 'they have abolished' it.

27. 'Twixt her feet, etc. The passage is discussed on p. 80.

undone. Driver's rendering. Heb. *šādhūdh* means lit. 'treated with violence.'

28. *and exclaimed.* Heb. וַיִּבְבֵּב. The verb *yibbēbh*, which only occurs here in O.T., is explained from Aram., in which *yabbēbh* means 'blow the trumpet,' and also 'raise a shout'; being used in this latter sense by S^P to translate Heb. יִרְעֶה in *ch.* 7²¹, 1 Sam. 4⁶, 17²⁰; Ps. 47², 66¹, *al.* In New Heb. the verb means 'to lament' over a corpse. Thus F renders 'et ululabat,' S^P סִבַּח, Ar. جلبت. G^{AL}, however, renders καὶ κατεμάνθανεν, S^B מִבְּלִי וּסְלִי, ומדיקא ט.

* With *nimelu* with preformative *n* from עֲמָלָא, cf. *nimeḱu* from עֲמָק, *nimedu* from עֲמָד.

‘and looked attentively’; *i.e.*, apparently, **וַתִּתְבּוֹנֶן** or **וַתִּתְבַּט**. This latter verb is adopted by Klostermann, Marquart, No., La., Zapletal, and is favoured by Bu. and Cooke (*Comm.*).

the lattice. Heb. *hā-’ešnābh*. The precise meaning of the term is uncertain. It occurs again in Prov. 7⁶ (**חַלּוֹן** ‘window,’ as in our passage); and in Ecclus. 42¹¹ †, where it is mentioned as a means of gazing on the street. The conventional rendering, which we have adopted, is that which is given by **Γ^{AL}**, **Θ.**, **διὰ τῆς διακτωτῆς** (so, in Prov., **Υ** ‘cancellos’). **טענתא**, apparently ‘wood-work,’ perhaps has the same meaning. **Γ^B**, however, renders **ἐκτὸς τοῦ τοξικοῦ** ‘through the loop-hole’; while **Υ** ‘de coenaculo,’ **ס^P** **סממא סממא סממא** think of an upper chamber or colonnade (**ξυστός**).

tarrieth. On the Heb. form **אָחַרָהּ** (for **אָחַרָהּ** or **אָחַרָהּ**), cf. G-K. § 64 *h*.

the clatter. Heb. *pa‘amê*, lit. ‘strokes,’ here no doubt refers to the *hoof-beats* of the chariot-horses.

29. *Her wisest princesses.* As Mo. remarks, ‘there is a fine irony in the allusion to the wisdom of these ladies, whose prognostications were so wide of the truth.’

make answer. Reading plur. **תַּעֲנֶינָהּ**, in place of **תַּעֲנֶנָּה** ‘answereth her’ (sing. with suffix), which is impossible after the plur. **חֲכָמוֹת שָׂרוּתֶיהָ**. An equally possible alternative is to emend **חֲכָמָה** for **חֲכָמוֹת**—‘The wisest one of her princesses answereth her.’ So **Υ** ‘Una sapientior ceteris uxoribus ejus’; **ס^P** **בַּחֲכָמָה**
חֲכָמָה; Ar. *id.*

Yea, she returneth her reply. She tries to quiet her anxiety by making herself the most reassuring answer. **וְ** adds **לָהּ** ‘to herself,’ which destroys the balance of the couplet by adding a fourth beat to the stichos.

30. *A damsel, two damsels.* Heb. *rāham* (which elsewhere in O.T. means ‘womb’) occurs in plur. with the meaning ‘girl-slaves’ in the inscription of the Moabite stone, l. 17.

for every man. Lit. ‘for the head of a man’; *i.e.*, as we might say, ‘per head.’

of dyed stuffs embroidered. Lit. ‘of dyed stuffs, embroidery,’ the two substantives being in apposition.

Two dyed embroideries. Lit. ‘a dyed piece of two embroideries.’ This may be understood as the dual of what would be in the sing. ‘a

dyed piece of embroidery' (צָבַע רֶקְמָה), the dual termination of the second (genitival) subst. sufficing to throw the whole compound expression into the dual. Cf. sing. בֵּית אָב 'a father's house or family,' plur. בֵּית אָבוֹת 'families': G-K. § 124 *z*. R.V.'s rendering, 'of divers colours of embroidery on both sides' (the explanation of Kimchi and Levi ben-Gershon), can hardly be correct.

The manner in which the terms meaning 'dyed stuff' and 'embroidery' are repeated and combined in the three final stichoi of the strophe is somewhat strange; and various alterations and omissions have been proposed. We need only notice the reconstruction suggested by Bu., which reduces the three stichoi to two, each containing three beats:—

שָׁלַל צָבַע צְבָעִים לְסִסְרָא
שָׁלַל רֶקְמָה רֶקְמָתִים לְצִנְאָרִי

'Spoil of a piece or two of dyed stuff for Sisera;
Spoil of a piece or two of embroidery for my neck.'

Here 'צב' 'צב' and 'רק' 'רק' are brought into exact analogy with רַחַם רַחֲמַיִם 'a damsel or two.' It may be questioned, however, whether this rearrangement is not too precise and formal to represent the original. It, as it stands, is susceptible of the rendering which we have given in the text; and in its repetition, which may be paralleled by *v.* 27, it exhibits affinity to the climactic parallelism which is so marked elsewhere in the Song (cf. *Additional note*, pp. 169 f.). It may be intended to represent the way in which the women's thoughts run on in prospect of the spoil. Cf. the passage from Virgil, *Aen.* xi. 782, cited by Ros. and others:—

'Femineo praedae et spoliolum ardebat amore.'

for the neck of the queen. Reading שָׁנָל 'queen' (cf. Ps. 45⁹, *שָׁנָל*¹⁰, Neh. 2⁶), after the suggestion of Ewald, in place of שָׁלַל 'spoil.' So Ber., Wellh., Stade, Oet., Oort, Schlögl, Kit., Driver, etc. The reading of שָׁלַל can only mean 'for the neck of the spoil,' which fails to yield sense; since it is impossible to follow Michaelis, Schnurrer, Ros., and several of the older commentators in explaining 'the spoil' as referring to the beasts of burden captured from the foe, which are to be led in triumph decked with the dyed raiment, etc.; nor is it likely that Justi is right in suggesting (after Mendelssohn) that 'the spoil' refers to the captured damsels previously mentioned. Levi ben Gershon explains as בְּעֵלֵי שָׁלַל 'owners of spoil'; and similarly Hollmann supposes an ellipse of אִישׁ before שָׁלַל—'man of spoil'

(cf. A.V. 'meet for the necks of *them that take* the spoil'): but such an ellipse is impossible. It would be easier to follow W. Green (1753) in vocalizing as an active participle שָׁלַל 'spoiler'; as is suggested by the rendering שָׁלַל בְּצוֹן הַשָּׁבוֹת (Ar. *id.*). Kimchi explains 'for the necks of the spoil' as equivalent to 'on the head of the spoil,' the sense intended being that 'the garments are placed on the head of the spoil to give them to the captain of the host.' He thus seems to regard 'the spoil' as referring to the *captives* generally; an explanation which is without analogy. R.V., 'on the necks of the spoil,' apparently assumes that the passage means that the garments are on the necks of the spoil (captive or slain?) before they become a booty; but the explanation of ל as 'on' ('belonging to') is very harsh and improbable.

Ⲭ^B τῷ τραχήλῳ αὐτοῦ (^A περὶ τράχηλον αὐτοῦ) σκῦλα; 𐤋 'circa cervices ejus spolia'; 𐤇 בֹּזֶת צִיּוּרִי צִבְעִינָן עַל צוּרִיהָ 𐤇 *i.e.* שָׁלַל (לְצִנְאָרִיו) לְצִנְאָרִיו 'for his (*i.e.* Šisera's) neck as a spoil'; and this is adopted by Meier, Hilliger, Stu. Ⲭ^L περὶ τὸν τράχηλον αὐτοῦ, *i.e.* לְצִנְאָרִיו, omitting שָׁלַל: so No., La., Kent. The original of 𐤇, 'supellex varia ad ornanda colla congeritur,' is not clear.

Further, Donaldson, Reuss, Grä., Smith, etc., read שָׁלַל לְצִנְאָרִי 'a spoil for my neck'; while Bu., Cooke adopt the reading לְצִנְאָרִי 'for my neck' simply.

31. *So perish, etc.* The couplet is regarded by Meier, Winter (ZATW. ix. 223 ff.), Bu., etc., as an addition, in the style of the Psalms, made to the poem in later times. It cannot be doubted, however, that it forms a most effective conclusion. As Mo. remarks, the single word '*So*' brings the whole course of events before our eyes again, culminating in Šisera's 'death by a woman's hand, disgrace worse than death; the anguish and dismay of those who loved him,' which the poet, with consummate art, leaves to the imagination of the reader. It is true that the idea embodied in the phrase 'thy friends' (lit. 'those that love thee') first comes into *prominence* at a later age (Ex. 20⁶, the explanatory extension of the Second Commandment, probably E²; Hosea, and Deuteronomy); but it by no means follows that it was wholly unthought of in much earlier times.

thy friends. Reading אֶהְבֵּיךָ with 𐤇, Ⲭ^P, in place of אֶהְבִּיּוּ 'his friends.'

An echo of the couplet is probably to be found in the first three verses of Ps. 68, which later on (vv. 7.8.13) shows traces of the influence of the poem.

A DETAILED EXAMINATION OF THE RHYTHM OF THE SONG OF DEBORAH.

A more detailed presentation of the rhythmical scheme of the Song of Deborah, and the extent to which this scheme is reproduced in our English rendering, may be of interest, as illustrating the method of early Hebrew poetical composition. As we have already remarked (p. 96), ancient Hebrew poetry, like English poetry, possesses no regularly quantitative system of metre; but is characterized by the occurrence of so many *ictūs* or rhythmical beats to the line, the intervening unstressed syllables being governed by the possibilities of pronunciation rather than by any strict rule. It is feasible, however, both in Hebrew and English, to divide the stichoi into 'feet,' with a view to a more accurate observation of the correspondence which may be obtained between the original and its translation; and an attempt has been made to do this in the comparison which is offered below.

Such a division of the Hebrew original into 'feet' also serves to illustrate the position of the *ictus* and its relationship to the accompanying unstressed syllables. It may be noticed that the Song contains, in all, 298 'feet.' Of these, by far the most frequent concatenation of stressed and unstressed syllables is $\asymp\asymp\angle$, *i.e.* the anapaest,* this 'foot' occurring 115 times. Closely similar to this is the 'foot' which contains an additional syllable as a weak (unstressed) ending, *i.e.* $\asymp\asymp\angle\asymp$; and this is found 13 times. Further, we find, with an additional unstressed syllable before the *ictus*, $\asymp\asymp\asymp\angle$, 31 times; and, with a weak ending, $\asymp\asymp\asymp\angle\asymp$, twice. Rarely, four unstressed syllables precede the *ictus*; $\asymp\asymp\asymp\asymp\angle$, 4 times; but there is no instance of such a 'foot' with an additional syllable as a weak ending. Next to the 'anapaest,' the most frequent 'foot' is the 'iambus,' $\asymp\angle$, this occurring 77 times; and, corresponding to this with a weak ending, $\asymp\angle\asymp$, 25 times. Not infrequently, a word of a single syllable may bear the *ictus*, unaccompanied by any unstressed syllable; \angle , 12 times. Such an *ictus* may be followed by a weak ending, $\angle\asymp$, 19 times.†

It thus appears that, out of the 298 'feet' in the poem, 192, or nearly two-thirds, are either $\asymp\asymp\angle$ or $\asymp\angle$ in form; and it will be found that this proportionate relationship of stressed to unstressed

* The term 'anapaest' is used loosely to denote two unstressed syllables followed by the stress, and not necessarily two *short* syllables followed by a *long*; since it is possible in Hebrew for an unstressed syllable to be long by nature.

† In this analysis, *Furtive Pathah* is not reckoned as a weak ending. Thus *maddû*⁴ is reckoned as $\asymp\angle$, not as $\asymp\angle\asymp$.

syllables is (speaking generally) characteristic of other examples of Hebrew poetry. The reason why an anapaestic or iambic 'foot,' with such variations as we have noted, is characteristic of Hebrew rhythm, depends upon the fact that the Hebrew tonic syllable is always either the ultimate or penultimate syllable (of a word, the accented ultimate being by far the most frequent (in the Song 239 instances, as against 59 instances of the accented penultimate); while the throwing of the accent farther back than the penultimate syllable is wholly unknown. It is thus impossible to find a dactylic 'foot,' $\angle \cup \cup$; while the trochaic 'foot,' $\angle \cup$, is, as we have seen, comparatively uncommon. In English, on the contrary, the accented penultimate or antepenultimate syllable greatly prevails over the accented ultimate; and a dactylic or trochaic measure is therefore natural, and indeed, at times, unavoidable. The comparative prevalence of dactylic or trochaic 'feet' in our English rendering of the Song will be found to be the feature which most markedly militates against close approximation to the Hebrew original. Fortunately, however, the English language is rich in weighty monosyllables; and the use of these enables us largely to reproduce the effect of the Hebrew rhythm by bringing the *ictus* down to the final syllable of the 'foot.'*

The fact is familiar to students that the system of Hebrew vocalization, as known to us from fH , represents the artificial product of the synagogue-system of cantillation; and only preserves the original pronunciation of living Hebrew in a very modified form. We are able, however, partly by the help of comparative philology, and partly by the aids to which reference has been made on p. 99, to infer with a fair approximation to certainty what the spoken pronunciation of the language must have been like; and an attempt has been made to reproduce this pronunciation in the transliteration of the Hebrew original. It should be remarked that this transliteration only claims substantial accuracy in so far as it substitutes full short vowels in open syllables for the tone-long vowels and vocal *she'wa* of fH : but the evidence at our disposal is not sufficient to enable us to dogmatize as to the *precise vocalization* of many word-forms at the period represented by the Song; and many of the forms which are

* The conclusions here adopted assume that the practice of spoken Hebrew, as regards the position of the tone, is substantially preserved in fH . We must not, however, overlook the possibility that the synagogue-system of cantillation may to some extent have affected the *position* of the tone-syllable, tending to throw it forward to the end of the word; and it is conceivable that, when Hebrew was a spoken language, the practice with regard to the tone conformed to that of Arabic, viz. that the accent was thrown forward till it met a long syllable, and if no long syllable occurred in the word, the accent rested on the first syllable. Such a system would to some extent modify our conclusions as to the different types of 'feet' represented in the Song; and, leading as it would to a multiplication of 'feet' of the form $\angle \cup$ and even $\angle \cup \cup$, would result in a closer approximation of the Hebrew rhythm to the English rendering.

given must be regarded as only approximately accurate (cf. the philological remarks which are added at the close of this note).

It is, however, the relationship of the unstressed syllables to the *ictus*-bearing syllable, and not the precise quality of the vowels of such syllables, which is of importance to us in our presentation of the rhythmical form of the Song; the latter question, though of supreme importance to philology, being only of subordinate interest as regards our present subject.

Lastly, it may be observed that the short vowels which take the place of tone-long vowels and vocal *shewa* in our transliteration, though represented as full vowels, may very likely have been pronounced in some cases with extreme brevity (as in Arabic), and in others very possibly slurred together in utterance. The effect of such a slurring would be to diminish the number of unstressed syllables (making e.g. $\underline{\text{u}}\underline{\text{u}}\underline{\text{u}}\underline{\text{u}}$ sound as $\underline{\text{u}}\underline{\text{u}}\underline{\text{u}}$), but would in no way essentially alter the character of the rhythm.

It will be noticed that, in the four-beat stichoi, we have placed a double line of division, halving the stichos. This indicates the caesura, which is characteristic of this form of rhythm; and which ordinarily marks a break in sense, sometimes considerable, as in *v. 3a. 4ba*, where the first half of the stichos is parallel to the second; but at other times very slight, and amounting to little more than the taking of breath at the half-way point. Stichoi also occur occasionally in which the caesura is purely formal, *sense* requiring a connexion rather than a break. So in *v. 10a* (caesura between subst. and adj.), *v. 17aa. 31b* (between Constr. St. and its following genitive).

Lest it should be thought that the fact that the caesura is purely formal in *v. 10a*, where we have re-arranged the text, is an argument against the arrangement, it may be remarked that the occurrence of such formal caesuras can be substantiated elsewhere. Thus we have Ps. 45^{2b}:

לשוני עט | סופר מהיר

‘My tóngue is the pén | of a ready writer.’

3. *šumú'ú* | *malakhím* || *hā'zīnu* | *rōzīntm*
'anōkhī | *l'Yahwáh* || *'anōkhī* | *'āštra*
'azammér | *l'Yahwáh* || *'elāháy* | *Yisra'él*
4. *Yahwáh* | *bašēthikhá* | *misSe'ír*
bašādikhá | *missadhē* | *'Adhôm*
'áraṣ | *ra'dša* || *gam-šamēm* | *namōghū*
gam-'abhīm | *naṭaphū* | *máyim*
5. *harrīm* | *nazalū* || *mippanáy* | *Yahwáh*
mippanáy | *Yahwáh* || *'elāháy* | *Yisra'él*

Ps. 89^{16b}:

יהוה באור | פניך יהלכון

‘Yahweh, in the light | of thy countenance shall they walk.’

Ps. 10^{13a}:

על-מה נאין | רשע אלהים

‘Wherefore contemneth | the wicked, Gód?’

Similarly, Babylonian, which ordinarily marks the caesura very clearly, offers occasional instances of a formal kind merely. Thus, *Gilgamesh-epic* xi. 121:

ki ákbi ina púhur | iláni limútta

‘When I decreéd in the assémbly | of the góds an evil thing.’

Id. xi. 182:

átta abkál | iláni kurádu

‘Thóu, O ságe | of the góds, thou wárrior.’

Creation-epic iv. 11:

zananútum íršat | parák iláni-ma

‘Abúndance is the desíre | of the sanctuary of the góds.’

Id. iv. 31:

alík-ma ša Tiámat | napšátuš purúma

‘Gó, and of Tiámat | her life cut off.’

It may be noted that, in the English rendering, the ordinary English accentuation of proper names has been adopted, rather than that of the Hebrew, in cases in which the latter would appear scarcely tolerable in the conventionalized forms to which the English reader is accustomed. In other cases, in which this difficulty is less acute or non-existent, the Hebrew accentuation has been retained.

3. Atténd, | ye kíns ; || give eár, | ye rúlers :
Í — | to Yahwéh || Í | will síng,
Will make mélogy | to Yahwéh, || the Gód | of Ísrael.
4. Yahwéh, | in thy prógress | from Se'ír,
In thy márch | from the fiéld | of Edóm,
Eárrh | quáked, || yea, héaven | rócked,
Yea, the clóuds | drópped | wáter.
5. The móúntains | shoók || befóre | Yahwéh,
Befóre | Yahwéh, || the Gód | of Ísrael.

6. *miyyamáy | Šamgár | ben-‘Anúth*
miyyamáy | ‘ólám || ħadhalú | ‘ōrahóth
whōlikháy | nathibhóth || yēlakhú | ‘aḵalḵallóth
7. *ħadhalú | parazóth | b Yisra’él*
ħadhalú
‘ádḥ | šaḵḵámti | Dabhōrá
šaḵḵámti | ‘ém | b Yisra’él
8. *ħasarú | lahúm | ħarraštīm*
‘azalú | ħamuštīm | me’ṭr
maghén | ‘im-yirra’é | warúmaḥ
ḏarbu’īm | ‘álah | b Yisra’él
12. *‘úrī | ‘úrī | Dabhōrá*
‘úrī | ‘úrī | dabbari-štr
ḵím | Baráḵ | wašabhé
šobháyka | bēn | ‘Abhinú’am
9. *lakhú | muḥōḵaḵáy | Yisra’él*
hammithnaddabhim | ba’am || barrakhú | Yahwáh
10. *rōkhibháy | ‘athōnóth || šahōróth | yašihū*
whōlikháy | ‘al-dírah || yašibhu | ‘al-lébh
11. *ḵól | mušaliḵaḵóth || bēyn | mašabbīm*
šám | yutannú || šadhakóth | Yahwáh
šadhakóth | zuro’ó | b Yisra’él
13. *‘az-yaradhú | laša’arīm | ‘addirīm*
‘am-Yahwáh | yaradh-ló | baggabbōrīm
14. *minni-‘Ephrēm | mašakhú | ba’émek*
‘aḥaráyka | Binyamín | ba’amamáyka
minni-Makhír | yaradhú | muḥōḵaḵīm
umizZabhúlán | mošikhīm | bašébbheṭ
15. *wasaráyka | Yissakhár | ‘im-Dabhōrá*
waNaphṭáli | kén | laBharáḵ
ba’émek | šulláh | baraghláw
- naphródh | naphrádh || lapḥalaggóth | Re’ubhén*
gadhōlīm | ḥeḵeráy | libbó
16. *lámma | yašábhtu || bēyn | hammašpatēm*
lašamó‘ | sarīḵóth | ‘adharīm
17. *Gal’ádh | ba’ébher || hayYardén | šakhín*
waDhán | yaḡhúr | ‘oniyyóth
‘Ašér | yašábh || laḥóph | yammīm
wa’ál | maphrasáw | yaškún
18. *Zabhúlán | ‘am-ħarráph || naphšó | lamúth*
waNaphṭalí | ‘al-marōmáy | sadhé

6. From the dáy's | of Shamgár | ben-'Anáth,
 From the dáy's | of óld, || cáravans | ceásed
 And they that wént | along the wáys || used to wálk | by
 crooked páths.
7. Vállages | ceásed | in Ísrael ;
 ceásed ;
 Till thou | didst aríse | Deboráh,
 Didst aríse | as a móther | in Ísrael.
8. Ármourers | hád they | nóne ;
 Ármed men | fáiled from the | cíty :
 Was there seén | a shiéld | or a lánce
 Amóng | forty thousánd | in Ísrael ?
12. Awáke, | awáke, | Deboráh !
 Awáke, | awáke, | sing paéan !
 Ríse | Barák, | and lead cáptive
 Thy cáptors, | O són | of Abinó'am !
9. Cóme, | ye commánders | of Ísrael !
 Ye that volunteéred | among the péople, || bléss ye | Yahwéh !
10. Let the ríders | on táwny || she-áesses | revíew it,
 And lét | the wayfárers || recáll it | to mínd !
11. Hárk | to the maídens || laúghing at | the wélls !
 Thére | they recoúnt || the righteous ácts | of Yahwéh,
 The righteous ácts | of his árm | in Ísrael.
13. Then dówn | to the gátes | gat the nóbles ;
 Yahweh's fólk | gat them dówn | mid the héroes.
14. From Ephráím | they spread out | on the vále ;
 'After theé, | Benjamín !' | mid thy clánsmen.
 From Machír | came dówn | the commánders,
 And from Zebulún | men wiélding | the trúncheon.
15. And thy prínces, | Issachár, | were with Deboráh ;
 And Naphtáli | was leál | to Barák :
 To the vále | he was loósed | at his heél.
- Útterly | réft into || fáctions was | Re'úben ;
 Greát were | his seárchings | of heárt.
16. Why sá't'st | thou stíll || amíd | the fólds,
 To heár | the pástoral | pípings ?
7. Gilé'ád | beyónd || the Jórdan | dwélt,
 And Dán | abídeth | by the shíps.
 Ashér | sat stíll || by the shóre | of the séas,
 Dwélling | besíde | his créeks.
18. Zebulún | is the fólk || that scorned its lífe | to the deáth,
 And Naphtalí | on the héights | of the fiéld.

19. *bā'ū* | *malakhīm* | *nalhāmū*
'az-nalhamū | *malakháy* | *Kanā'an*
baTa'nákh | *'al-máy* | *Magiddō*
báša | *kášaph* | *lo-laḳáḥū*
20. *min-šamēm* | *nalhamū* | *hakkōkhabhīm*
mimmasillōthám | *nalhamū* | *'im-Šisará*
21. *náhal* | *Ḳīšōn* | *garaphīm*
ḳaddamám | *náhal* | *Ḳīšōn*
Tubarrakhi | *naphšē* || *'óz* | *Yahwáh*
22. *'az-halamū* | *'aḳibháy* | *susīm*
daharū | *daharē* | *'abbirāw*
23. *'úrrū* | *Merōz* | *'arōr*
'úrrū | *'arōr* | *yōšibháyha*
ki-lō-bā'u | *la'ezráth* | *Yahwáh*
la'ezráth | *Yahwáh* | *baggabbōrīm*
24. *tuburrákh* | *minnašīm* | *Ya'él*
minnašīm | *bā'úhul* | *tuburrákh*
25. *máyim* | *šā'al* || *ḥalábh* | *nathāna*
baséphel | *'addīrīm* || *haḳrībha* | *hem'í*
26. *yadháh* | *layathídh* | *tašlahánna*
wyamīnáh | *lthalmáth* | *'amīlīm*
wḥalamá | *Šisará* || *maḥaḳá* | *rōšō*
umaḥašá | *waḥalaphá* | *raḳḳathō*
27. *beyn-raghláyha* | *kará* || *naphúl* | *šakhábh*
beyn-raghláyha | *kará* | *naphúl*
bā'sér | *kará* || *šam-naphúl* | *šadhúdh*
28. *bā'ádh* | *haḥallōn* || *našḳaphá* | *wattuyabbábh*
'ém | *Šisará* || *bā'ádh* | *ha'ešnábh*
*maddit** | *bōšéš* || *rakhabhō* | *labhō*
*maddit** | *'aḥḥarú* || *pá'amáy* | *marḳabhōtháw*
29. *ḥakhāmōth* | *sarrōtháyha* | *tā'náyna*
'aph-hí | *tašēbh* | *'amaráyha*
30. *halō* | *yamšū'ú* || *yuhallakū* | *šalál*
rāham | *raḥmathēm* || *larōš* | *gábar**
šalál | *šabha'tm* | *laŠisará*
šalál | *šabha'tm* | *riḳmá*
šába' | *riḳmathēm* || *lašawwaráy* | *šeghál*
31. *kén* | *yobhadhū* || *kol-'oyabhúyka* | *Yahwáh*
wōhabhúyka | *kašēth* || *haššámaš* | *baggabūrathō*

* Possibly this couplet should be regarded as consisting of trimeters rather than tetrameters:—

halō-yamšū'ú | *yuhallakū* | *šalál*
rāham | *raḥmathēm* | *larōš-gábar.*

19. Ón came | the kíngs, | they fough̃t ;
Then fough̃t | the kíngs | of Caná'an ;
In Tá'anach, | by the rills | of Megíddo ;
The gaín | of móney | they toók not.
20. From heáven | fough̃t | the stárs ;
From their h́ghways | they fough̃t | with Sísera.
21. The tórrent | Kishón | swept them óff ;
It fáced them, | the tórrent | Kishón.
Bléss thou, | my sóul, || the míght | of Yahwéh !
22. Then loúd beat | the hoófs | of the hórses ;
Off gálloped, | off gálloped | his chárgers.
23. Cúrse ye, | cúrse ye | Meróz !
Cúrse ye, | cúrse ye | her tówns-folk !
For they cáme not | to the hélp | of Yahwéh,
To the hélp | of Yahwéh | mid the héroes.
24. Most bléssed | of wómen | be Já'el,
Of tént-dwelling | wómen | most bléssed !
25. Wáter | he ásked ; || mílk | she gáve ;
In a lórdly | dísh || she próffered | cúrds.
26. Her hánd | to the pég | she put fórth,
And her ríght | to the mául | of the wórkmén ;
And she smóte | Sísera || —destróyed | his heáð
Sháttered | and píerced | through his témples.
27. 'Twixt her feét | he bówed, || he fell dówn, | he lay próne ;
'Twixt her feét | he bówed, | he fell dówn.
Whére | he bówed, || there he fell dówn | undóne.
28. Oút | through the wíndow || she leáned | and excláimed,
The móther | of Sísera || óút | through the láttice :
'Whérefore | deláyeth || his cár | to cóme ?
Whérefore | tárrieth || the clátter | of his cháriots' ?
29. Her wísest | princésses | make ánswer,
Yea, shé | retúrñeth | her replý :
30. 'Áre they not | fínding || —divíding | the spoíl ?
A dámsel— | two dámsels || for évery | mán :
A spoíl | of dýed stuffs | for Sísera,
A spoíl | of dýed stuffs | embroídered ;
Twó dyed | embroíderies || for the néck | of the queén.'
31. So pérish | áll || thy foés | Yahwéh :
But be thy fríends | like the sún || going fórth | in his stréngth.

The following notes are offered in explanation of the Heb. forms adopted in the transliteration.

3. *šumū'ā*, for *šim'ā*. Comparative philology points to such a form: cf. Bab. *kuṭulū*; and Ar. *uḫtulū*, where the need for the prosthetic vowel was the direct result of the slurring away of the first short *u* vowel. That Heb. *ḫēṭōl* was once pronounced *kuṭul* may also be inferred from Origen's translit. of *לָחֵץ*, Ps. 35¹ by *λοομ* (*o* in translit. answering to *ū*).

malakhīm, with two *ā*'s in open syllables, for *m'lākhīm*. So throughout the poem, *parazōth*, *ḥakhamōth*, etc.

ha'zīnū; or possibly *ha'zanū*. The origin of the *ī* of the Hiph'il is obscure.

rōzinīm. The *ō* of the Act. Particip. (from an original *ā*; cf. Ar. *ḫātil*) was of early development in Heb.: cf. the T.A. 'glosses' **šūkkini* = *סִכְכִּין*, *ūbil* = *אֲבִיל*, where the *ū* is the nearest approach to the representation of *ō* in cuneiform script.

'anōkhī; perhaps originally accented *'anōkhi*. Cf. *אֲנִי* of the Moabite stone and Phoenician inscriptions.

6. *lYahwāh*. It is here assumed that, before the weak letter *'*, the short vowel of the preposition is merged by crasis with the following short vowel. Cf. T.A. *badiu* = *בִּירִי* (gloss on Bab. *ina ḫātīšu*). A similar crasis is assumed before the weak *h* in *whōlikāy*, etc. Whether such a crasis took place before *ʿ* is perhaps more doubtful. A possible instance is to be seen in the Precative Particle *בִּי*, if this really stands for *בִּעִי* 'supplication'; and, similarly, the name *רִיח* is usually regarded as a contraction of *רִיעַח* (cf. Syr.

* The so-called 'Cana'anite glosses' in the T.A. Letters (which might preferably be termed 'Amorite,' as relics of the language of Amurru: cf. *Introd.* pp. lx f.) are words and phrases in the language which is the prototype of Hebrew, occurring in the letters which were written in the cuneiform script and in the Babylonian language by the petty kings and governors of Canaanite cities to their suzerain, the king of Egypt. We may infer that the scribes who were responsible for the writing of these letters were themselves Canaanites, to whom the Babylonian was a foreign language, acquired (as evidence shows) not always very perfectly. Thus, they often employ a Canaanite word as an explanation or gloss of the equivalent term in Babylonian which precedes it in the letter; or even occasionally substitute a Canaanite term for the Babylonian, for which they were probably at a loss. These 'glosses' are of great value, not only as forming the earliest relics of the Hebrew language which are known to us, but also because (inasmuch as they are written syllabically in the cuneiform script) they embody the vocalization as well as the consonants of the forms. A complete list of the T.A. glosses will be found in Böhl, *Die Sprache der Amarna-briefe*, pp. 80 ff.; cf. also *KAT*.³, pp. 651 ff.

לֹאִי). The crasis is of regular occurrence in Bab., where *e.g.* *bêlu* stands for the West Semitic *bê'el*, *bê'al*.

'azammér. The last vowel probably *ē* or *ā*. The *ē* of the Pi'el in **פא** is a late and artificial development. So late as the time of Origen this vowel is regularly represented in translit. by *ε* and not by *η* (contrast the Act. Particip. *Ḳal*, where *η* always appears: *e.g.* *Νωσηρ*).

'elâháy, for **פא** *'elôhê*. For *ā* in place of *ō*, cf. Ar. *ilâh*, Syr. *'elâhâ*. That *ē* was originally the diphthong *ay* is clear from comparative philology.

4. *bašêthikâ*, *baša'dikhâ*. The connective vowel before the suffix is given as *i*, the Genitive case-ending after the preposition, as in Bab. and Ar.

missadhê. That **שָׁדַח** was originally **שָׁדַי** might be conjectured from the sporadic occurrence of the latter form in **פא** as a poetical archaism. The early existence of the more familiar form is, however, witnessed by the T.A. *šatê* = **שָׁדַח** as a gloss to the Bab. *ugari*.

'Adhom. For the initial short vowel, cf. Bab. *Adumu*.

'âraš, for **פא** *'éreš*. It must be regarded as an open question whether the segholate nouns were pronounced at this period with a helping vowel after the second consonant (as in **פא**, and in the form which we have adopted), or in the monosyllabic form (*e.g.* *'ârš*) which is assumed to be the original (cf. Ar. *'ard*, the philological equivalent of **אֶרֶץ**). Origen uniformly represents this type of noun as monosyllabic: *e.g.* *aps* = **אֶרֶץ**, *δερχ* = **דֶּרֶךְ**, etc.; the only exceptions being formed by words which have a guttural as second or third radical; *e.g.* *uaad* = **יָחַד**, *πεγε* = **רִנֵּעַ**, etc. On the other hand, the much earlier evidence of **א** exhibits a uniform representation of the helping vowel; *e.g.* *Iaφεθ* = **יָפֶת**, *Δαμεχ* = **לָמַךְ**, etc. Among the T.A. glosses we find *batnu* = **בָּטָן**, *su'ru* = **צָהַר**, *šahri* = **שָׁעַר**, segholate forms with case-ending, just like Ar. *'arḏum*. Taking, however, a Hebrew proper name of the classical period such as **חֲזַקְיָהוּ** (meaning, apparently, 'Yahu is strength, or my strength'), where the first element *hizkî* must be assumed to be a segholate noun of the form *hēzekî* (for the normal *hōzekî*; cf. fem. *hezḳā* by the side of *hozḳā*), we find that the helping vowel after the *z* which appears in the **א** translit. *Eḫekias* is confirmed by the Assy. translit. in Sennacherib's inscription,* where the name is spelt out as *Ha-za-ki-ia-u* or *Ha-za-ki-a-u*. In face of this conflict of evidence, it appears preferable to retain the helping vowel in

* The Taylor Cylinder, col. ii. l. 71; col. iii. ll. 11, 29; cf. *KB*. ii. pp. 92, 94.

segholate forms,* vocalizing, as \mathfrak{C} suggests, form 1 as in 'áraṣ; form 2 as in śéphel, v. ²⁵; form 3 as in 'úhul, v. ²⁴ (cf. \mathfrak{C} forms Bapað, Eξερ, Ζογορ).

ra'áša. The pausal form is retained, here and elsewhere (*nalhāmú, laḳāhú, v. ¹⁹; nathāna, v. ²⁵*), as probably characteristic of the original pronunciation. Origen recognizes such pausal forms in his transliterations; e.g. *δαββηρον* = יִבְרָה. The existence of the pausal accent in Bab., as indicated by the doubling of the succeeding consonant, also seems to be clear; cf. Delitzsch, *Assyr. Gramm.* § 53 c. In Ar. the pause introduces certain formal modifications.

šamēm, in place of \mathfrak{H} šāmāyim. For the dual termination -ēm, cf. Phoenician שִׁמֻם.

naṭaphú, in place of \mathfrak{H} nāṭ'phú, as in Ar.; and so in similar verbal forms throughout the song. Possibly such a form may sometimes have been pronounced *naṭphú*: cf. T.A. gloss *maḥṣu* for *maḥaṣu* (מחצו). The Bab. Permansive form is similar.

māyim; or possibly mēm: cf. T.A. gloss *mīma, mēma* (spelt out *mī-ma* and *mī-e-ma*). Moabitic, however, represents the ' in מִין, a fact which perhaps indicates a pronunciation such as we have adopted (i.e. the pronunciation of \mathfrak{H}).

5. *harrīm*, for \mathfrak{H} hārīm. Similarly, ṛ is doubled in *yirra'é, v. ⁸, barrakhú, v. ⁹*, etc. It cannot be doubted that ancient Heb. found no more difficulty about the pronunciation of double ṛ than does Bab. and Ar. Cf. the T.A. gloss *ḥarri* = חֲרִי with Genitive case-ending; and the \mathfrak{C} transliterations 'Αμoppαῖος = אֲמֹרִי pronounced 'Amurri (native of the land of Amurru); *Xappav* = חָרַן, cf. Bab. *Ḥarrānu*.

7. 'ēm; or possibly 'imm (Origen, εμ). Similarly, *maghén, v. ⁸*, may have been pronounced *maghinn*, 'óζ, v. ²¹, 'uzz (Origen, οζ), etc.

9 ff. *muḥōḳaḳáy, muṣahḥaḳóth, yutannú*. The short preformative vowel of the Pi'el is represented by *u*, as in Ar. Cf. the T.A. gloss *yukabid* = יִכְבֵּד.

11. *zurō'ó*. For vowel of first syllable, cf. T.A. gloss *zurúh*.

13. *baggabborīm*; or possibly *baggabbarīm* as in Ar.: but it is probable that original *á* had already in most, if not in all, cases become *ó*; as it certainly had in the case of the Act. Particip. *Ḳal*: cf. note on *rōziním, v. ³*. The original *a* of the sharpened first syllable of the subst. was probably not yet thinned to *i*, as in \mathfrak{H} .

* It is, as a matter of fact, difficult to conceive that a form like 'arṣ can ever have been pronounced without a helping vowel under the *r*, supposing this *r* to have been trilled; and, in the same way, *šiphel* cannot be pronounced as a true monosyllable, but naturally becomes *šíphel*.

Many instances may be drawn from *Gr* showing that the thinning of an original *a* in a toneless closed syllable into *i* is a late development : cf. *Mapiaμ* = מִרְיָם, *Maxμαs* = מַכְמָשׁ, *Γαλααδ* = גַּלְעָד, etc.

15. *naphrôdh naphrâdh*. On the analogy of the fact noticed in the preceding note with regard to substantives, it may be assumed that the original *a* of the preformative of Niph'al was unthinned to *i* (so *nalhamû*, *v.* 19; *našḥaphâ*, *v.* 28; cf. the T.A. glosses *naḥṣapu*, [na]aḥṣapṭi); and the same inference may be drawn with regard to the preformative vowel of the Perf. Hiph'il (*hakrîbha*, *v.* 25), and the sharpened first syllable of the Perf. Pi'el (*ḥarraph*, *v.* 18; *ḥaddamûm*, *v.* 21; *'aḥḥarû*, *v.* 28). In the case of the preformative vowel of the Imperf. Kal we have evidence from the T.A. glosses that the original *a* of the preformative was, at that period, preserved as in Ar., *yazkur* standing for יִזְכֹּר. Hence, in *v.* 17 we vocalize *yaškûn* for יִשְׁכֹּן of *Gr*, and in *v.* 30 *yamšû'û* for יִמְצְאוּ.

26. *tašlahanna*, vocalized upon the analogy of the Ar. *modus energicus I*. Cf. footnote, p. 152.

rôšô. That an original *ra's* (as presupposed by the Ar. *ra's*) had already developed into *rôš* in Heb. is proved by the T.A. gloss *rušunu* 'our head,' where the *u* of the syllable *ru* represents *ô*.

THE CLIMACTIC PARALLELISM OF THE SONG OF DEBORAH.

The purpose of this note is to call attention to a characteristic of the Song which is somewhat infrequent in Hebrew poetry, viz. the recurrence of a form of parallelism which has been not inaptly termed *Climactic*. In this form, stichos *b* of a distich does not offer a more or less complete echo of stichos *a* in different words (Synonymous parallelism); nor, on the other hand, is it merely formally parallel to stichos *a*, while in matter it offers an advance in thought (Synthetic parallelism). Instances of such forms of parallelism are to be found in the Song; but do not call for special comment.* In Climactic parallelism, however, stichos *b* is partially parallel to stichos *a*, but adds something further which completes the sense of the distich, thus forming, as it were, a climax. In the following examples this principle is carried out to a varying extent, in a manner which adds to the vigour and movement of the poetry. In order that the method may be the more clearly observed, the stichoi are divided into sections upon the basis of parallel and non-parallel parts; and the

* On the various forms of Hebrew parallelism, cf. Driver *LOT*.⁹ pp. 362 ff.

parallel parts are placed one beneath the other, while the non-parallel sections stand separately. It may thus be observed that the non-parallel portion of stichos *b* is intended to round off and complete the whole distich.

5. The mountains shook | before Yahweh,
Before Yahweh, | the God of Israel.
6. From the days of Shamgar ben-'Anath
From the days of old, | caravans ceased.
- 7*b*. Till thou didst arise, | Deborah,
Didst arise | as a mother in Israel.
9. Come, | ye commanders of Israel,
Ye that volunteered among the people, | bless ye Y.
11. There they recount | the righteous acts of Y.,
The righteous acts of his arm | in Israel.
- 12*a*. Awake, awake, | Deborah ;
Awake, awake, | sing paeon !
- 12*b*. Rise up, Barak, | and lead captive
O son of Abino'am, | thy captors !
18. Z. is the folk | that scorned its life to the death,
And N. | on the heights of
the field.
- 19*a*. On came the kings, | they fought
the kings | Then fought | of Cana'an.
20. From heaven fought | the stars
From their highways they fought | with Šišera.
23. For they came not | to the help of Y.
To the help of Y. | mid the heroes.
28. Out through the window | leaned and exclaimed
out through the lattice | the mother
of Š.
30. A spoil of dyed stuffs | for Šišera,
A spoil of dyed stuffs | embroidery,
Dyed stuff | for the neck of the queen | two embroi-
deries.

Cf. also *v.*²⁷, where the single word שָׁדָד 'undone' in stichos *c* forms the climax to the description of Šišera's death and humiliation.

Driver (*LOT*.⁹ p. 363) remarks that 'this kind of rhythm is all but peculiar to the most elevated poetry'; and quotes, as instances occurring elsewhere, Ps. 29⁶, 92⁹ *U*¹⁰, 93³, 94³, 96¹³, 113¹. 'There is

something analogous to it, though much less forcible and distinct, in some of the "Songs of Ascents" (Ps. 121-134), where a somewhat emphatic word is repeated from one verse (or line) in the next, as Ps. 121^{1b,2} (help); *v.* 3^{b,4}; *v.* 4^{b,6a}; *v.* 7^{,8a}; 122^{2b,3a}, etc.⁷

Observation of this structural device cannot fail to suggest that the emendations and excisions proposed by some scholars, *merely for the sake of removing repetitions*, should be received with the utmost caution. Thus, *e.g.* when Rothstein emends נִלְחָמוּ in *v.* 10^{aa} into וְ[ו]עָרְבוּ '[and] they set the battle in array,' on the ground that 'das natürliche rhythmische Empfinden sträubt sich dagegen, in beiden Halbversen das gleiche Verbum zu lesen,' he is proceeding upon an assumption which belies the most salient characteristic in the parallelism of the Song.

THE LANGUAGE OF THE SONG OF DEBORAH.

In considering the language of the Song, one broad general principle has first to be laid down; viz. that, since Hebrew literature, as known to us from the O.T., is extremely exiguous, the Hebrew vocabulary which we possess doubtless represents only a somewhat limited part of the vocabulary which must have been in regular, if not in common, use in the written and spoken language. This is a consideration which is substantiated by the large number of ἀπαξ λεγόμενα which occur throughout the O.T.; and its importance is enhanced when it is applied to one of the very few monuments of the earliest period of the literature which happen to have survived. In discussing the text of the Song, we have noticed a number of words, the meaning of which can only be elucidated by recourse to the evidence supplied by the cognate languages. Thus, מִשָּׁךְ *v.* 14, מַפְרָעִים *v.* 17, נָרַף *v.* 21, מַחֵק *v.* 26, and possibly קְדוּמִים *v.* 21, are explained from the Arabic; פִּלְגוֹת *v.* 16 possibly from Babylonian and Phoenician usage, but more probably from Aramaic; עֲמָלִים *v.* 26 in a sense common to Arabic, Aramaic, and Babylonian, but *not* to early Hebrew as otherwise known to us; יָבֵב *v.* 23 from Aramaic and New Hebrew; and רָחַם *v.* 30 from Moabitic. מִשְׁאֲכִים *v.* 11 is elucidated only by our knowledge of the meaning of the verb in Hebrew; while the signification of מִשְׁפָּתִים *v.* 16 can only be vaguely guessed. These facts do not, of course, imply that *e.g.* the list of words which are explained from the Arabic are to be regarded as Arabisms, *i.e.* that their use in the Song is *due to the influence of Arabic*; but simply that Hebrew and Arabic being from a common stock, and our knowledge of the Arabic vocabulary being much more extensive than our knowledge of the Hebrew, Arabic helps us to explain some of the otherwise unknown Hebrew words, which may have been, and very likely were, in common daily use at the early period represented by the Song.

Further, the fact urged by Vernes, in his argument for the late date of the Song, that a number of the words employed in it occur elsewhere, mainly or exclusively, in the third division of the Hebrew Canon—the *K^ethûbbîm*, is really destitute of significance as bearing upon the date. Hebrew poetry, like the poetry of other languages, has its choice words and expressions which are not commonly employed in prose; the great bulk of the Hebrew poetry known to us in the O.T. is contained in the *K^ethûbbîm* (Pss., Job, Cant., Lam.); and at least two-thirds of the words cited by Vernes in proof of his thesis are cited because they occur in these poetical books.*

There are, however, a few forms in the Song which are to be regarded as dialectical. Of those which have frequently been cited by scholars in time past, the termination מִין in מִיִּן *v.*¹⁰, and the supposed Absol. plur. termination י in שָׁרִי *v.*¹⁶, have disappeared under our criticism of the text; but there remain the Relative שׁ *v.*⁷ for the ordinary אֲשֶׁר; קָמַתִּי *v.*⁷, if rightly regarded as 2nd fem. sing., for the normal קָמַת; the form עָמַמִּיךְ *v.*¹⁴ (cf. Neh. 9.^{22,24}) with dissimilated מ, for עָמִיךְ; and, most remarkable of all, יִתְנוּ *v.*¹¹, where comparison of the cognate forms in Arabic and Aramaic, and the actual occurrence of the normal form in Hebrew (שָׁנָה 'to do a second time'), lead us to expect יִשְׁנֹו. It should be observed that the Song is not the only example of pre-exilic literature in which these forms occur. The Relative שׁ is found again in *ch.* 6.¹⁷, 7.¹², 8.²⁶, in 2 Kgs. 6.¹¹ (if the text is sound), and throughout Cant. (which, however, may be post-exilic). Instances of forms resembling קָמַתִּי for קָמַת have been quoted in *note ad loc.* from Mic. 4.¹³, Jer. 2.²⁰. Forms from verbs *v* doubled exhibiting dissimilation, like עָמַמִּיךְ, are seen in חָקְקִי Isa. 10.¹ (as in the variant for חָקְרִי in the Song, *v.*¹⁶); הָרַרִי Num. 23.⁷, JE, *al.*, הָרַרִי Jer. 17.³, הָרַרִיךְ Deut. 8.⁹; צִלְלִי Jer. 6.⁴. יִתְנוּ is substantiated by לִתְנוֹת in *ch.* 11.⁴⁰ (if original; cf. *note*).

The claim that these forms are proofs of the late date of the

* Most of the remainder occur in the prophets, who also naturally at times employ terms which would not be used in plain prose. In citation of his references to various books, Vernes frequently does not state all the facts, or states them incorrectly. Thus רָעִשׁ, which is assigned to Pss. and Ezek., occurs also in the pre-exilic prophets Am. 9.¹, Nah. 1.⁵, Jer. 4.²⁴, 8.¹⁶, 10.¹⁰, 50.⁴⁶, 51.²⁹; מָנַן, assigned to Pss., Prov., Chron., is, needless to say, very frequent also in the earliest literature; סָפַל, assigned to Chron., Neh., Pss. (where it does *not* occur), is only found again in Judg. 6.³⁸ E; and so on.

Song (Vernes), and the assertion that they are late alterations of the text, (Rothstein), are, therefore, equally unwarranted; and scholars generally recognize the fact that the Hebrew of northern Canaan must have exhibited certain dialectical peculiarities—as indeed is seen to be the case in the lengthy narratives in Kings which must have emanated from the prophetic schools of the Northern Kingdom: cf. *NHTK*. pp. 208 f.

Many scholars, however, while admitting the existence of such dialectical forms, express their doubts as to the possibility of so marked an Aramaism as יִתְנֶה in an early poem, and are inclined to regard it as a textual corruption; and it is somewhat surprising to find so learned and judicious a scholar as Mo. asserting roundly that 'as equivalent of Heb. שָׁנָה the word is not conceivable in old Hebrew.'

Such a statement appears to imply a preconceived conclusion as to the sharp differentiation between early Hebrew and early Aramaic which, in default of evidence, we are scarcely justified in drawing. Indeed, it may be claimed that such evidence as we *do* possess as to the relationship between the two languages at a later period (and therefore, *a fortiori*, at this period) tends all in the other direction; *i.e.* it is more likely that, if we possessed ample evidence as to the character of the Hebrew or Canaanite,* and the Aramaic, which were spoken at this period, we should find that both languages existed in dialectical forms exhibiting so many common characteristics that we should (at any rate in some examples) find it difficult, if not impossible, to draw a distinction between the two, and to say, 'This is Hebrew (Canaanite), and this Aramaic.'

The discoveries of recent years have given us some insight into the character of the language spoken, at about the eighth century B.C., by some of the small Aramaean states which lay to the north of Israel. Thus, we have the Hadad-inscription of Panammu, king of Ya'di in northern Syria, dating from about the middle of the eighth century B.C., and the two inscriptions of his son Bar-rekub (towards the end of the same century), who seems to have been king of Sam'al as well as of Ya'di (unless the two places are to be regarded as identical). These were discovered near Zengirly in the years 1889-91.‡ Next, an inscription of Zakir, king of Hamath and La'ash, *cir.* 800 B.C. or a little earlier, was discovered in 1903 by Pognon, and published by him in 1907.§ And, most recently, an

* The fact is well recognized that Hebrew is 'the language of Canaan' (cf. Isa. 19¹⁸); and that Phoenician, Moabitic, etc., are examples of the same language, with dialectical variations.

‡ Cf. E. Sachau in *Ausgrabungen in Sendschirli*, 1893, D. H. Müller, *Die altsemitischen Inschriften von Sendschirli*, 1893; Cooke, *NSI*. pp. 159-185.

§ Pognon, *Inscriptions Sémitiques de la Syrie, de la Mésopotamie, et de la région de Mossoul*, 1907, pp. 156-178; cf. also Driver in *Expositor*, June 1908, pp. 481-490; Lidsbarski, *Ephemeris*, iii. pp. 1-11.

inscription of Kalumu, an earlier king of Ya'di of the latter half of the ninth century B.C., has also been discovered in the neighbourhood of Zengîrly.*

The language of the inscriptions of Panammu and Bar-rekub, kings of Ya'di during the eighth century B.C., is clearly Aramaic of a kind, though distinguished by certain marked characteristics which connect it with Hebrew (Cana'anite) rather than with later Aramaic. Into these characteristics we cannot here enter in detail; but it may be noticed that, in the three ordinary equations, Ar. 𐤀 = Aram.

𐤁 = Heb. ַ; Ar. 𐤂 = Aram. 𐤃 = Heb. ָ; Ar. 𐤄 = Aram. 𐤅 = Heb. ֿ, it is to Hebrew and not to Aramaic that the Zengîrly dialect conforms. The use of 𐤂 where Aramaic ordinarily employs 𐤃 (e.g. 𐤂𐤕𐤁 for 𐤕𐤁, 𐤂𐤕𐤁 for 𐤕𐤁) is, we may observe, the converse of the employment of the form 𐤕𐤁 in the Hebrew of the Song, where we should expect 𐤕𐤁. †

Turning, however, to the inscription of Kalumu, who may have preceded Panammu as king of Ya'di by nearly a century,§ we find that his language is Canaanite throughout, closely resembling Phœnician as known to us from inscriptions of the fourth century B.C. and later, though marked by a few Aramaisms such as the use of 𐤍 'son' in place of 𐤌.

The language of Zakir's inscription associates itself most closely with Aramaic, though offering points of contact with Canaanite similar to those which are found in the inscriptions of Panammu and Bar-rekub; and in addition so remarkable a Hebraism as the use of the Imperfect with 𐤏 *consecutive*, a construction which is elsewhere only found in Biblical Hebrew and in the inscription of Mesha', king of Moab.

These facts—and more especially the remarkable alteration in the

* First edited by F. von Luschan in *Ausgrabungen in Zendschirli*, 1911; cf. also E. Littmann, 'Die Inschriften des Königs Kalumu,' in *Sitzungsberichte der Königl. Preuss. Akad. der Wiss.*, 1911, pp. 976-985; M. Lidsbarski, 'Eine phönizische Inschrift aus Zendschirli,' in *Ephemeris für Semit. Epigraphik*, iii. pp. 218-238 (he gives a list of other writers on the inscription, p. 220 n.). Kalumu is mentioned in the shorter inscription of Bar-rekub, in a passage which, prior to the discovery of his inscription, was not unnaturally unintelligible to editors. Bar-rekub says (ll. 15 ff.), 'And a good house my fathers, the kings of Sam'al, did not possess; they had only the house of Kalumu, and it was their winter-house and their summer-house: so I built this house.'

† Cf. further on the dialect of these inscriptions, Cooke, *NSI*. pp. 184 f.

§ Kalumu's father, Hayân the son of Gabar, paid tribute to Shalmaneser III. in B.C. 854 (cf. *KB*. i. pp. 170 f.); and seems to have been succeeded by his son Sha'il, before the accession of Kalumu. Bar-rekub states that his father Panammu, as well as himself, was a contemporary of Tiglath-Pileser, who reigned from 745-727 B.C.

language used by the kings of Ya'di in the course of a century or so—are sufficient to make us surmise that, if the characteristics of so-called Aramaic in the 8th and 9th centuries B.C. were such as we have noticed; in the 12th century B.C. (*i.e.* at about the period of the Song of Deborah) Aramaic may scarcely as yet have been differentiated from Hebrew as a separate language, but the two may have appeared as somewhat closely related dialectical forms of the one language which was known to the Assyrians as 'the tongue of Amurru.'

Before, therefore, we pass an opinion as to the possibility or impossibility of 'Aramaïisms' in the Song of Deborah, we have to take account of the following facts:—

- (1) Evidence shows that even so much as three hundred years later than the date of the Song, the 'Aramaic' spoken by states in northern Syria was more nearly related to Canaanite or Hebrew than was the Aramaic of later times.
- (2) The northern, or, more accurately, central, Palestinian Hebrew of some three hundred years later, albeit that we know it as the literary language of the prophetic schools (1 Kgs. 17—2 Kgs. 10), offers certain dialectical peculiarities akin to Aramaic.
- (3) The Song is probably the only existing instance of a piece of literature belonging to this early period which emanates from the extreme north of Palestine, and was perhaps composed by a member of a tribe (Issachar?) which may have been in Canaan without a break from its earliest settlement in the west; and had not, like the Joseph-tribes, undergone the segregation from external Semitic influences involved in the sojourn in Egypt (*cf. Introd.* pp. cvi ff.).
- (4) In any case, the northern tribes of Israel dwelt in close association (*cf. ch. i* ^{30ff.}) with the Canaanites of the north, who may have been considerably influenced linguistically by their Aramaean neighbours, just as these latter were doubtless influenced by them.
- (5) There were Aramaean clans closely contiguous to Israel not only on the north, but east of Jordan—the Geshurites and Ma'acathites—clans which ultimately became united to East Manasseh by intermarriage (*cf. note* on 'Machir' 5¹⁴ at *end*). Some of these clans may already have used the later Aram. 𐤌 for Heb. שׁ in cases in which the Ar. equivalent is ܫ, and may have passed on some of their terms as loan-words to the Israelites.
- (6) Judg. 12⁶ is actual proof that there existed dialectical peculiarities among the Israelites in regard to the pronunciation of the sibilant שׁ (*sibbóleth* for *shibbóleth*).

Bearing these facts in mind, we may recognize the existence of 'Aramaisms' in the Song as a natural phenomenon, and may well pause before we condemn a form such as יִתְּנִי as impossible in a very early example of northern Israelite literature.

6. 1-8. 28. *Gid'ôn.*

Besides the Commentaries, etc., quoted throughout the book, cf. W. Böhme, *Die älteste Darstellung in Richt. 6¹¹⁻²⁴ und 13²⁴, und ihre Verwandtschaft mit der Jahveurkunde des Pentateuch*, ZATW. v. (1885) pp. 251-274; H. Winckler, *Die Quellenzusammensetzung der Gideonserzählungen*, AF. i. (1893) pp. 42-59.

The narrative of the oppression of Midian and the deliverance effected by Gid'ôn is highly composite throughout. In no other section of Judges is the existence of two documents bearing the characteristics of J and E more clearly evident, and the criteria for determining the main lines of analysis are fairly decisive; though in details there remains considerable scope for difference of opinion.

6¹⁻⁶. Here R^{E2}, whose regular introductory formulae occur in *vv.*^{1.6b}, opens the narrative with a statement of facts derived from his old sources. We notice certain similarities to the narrative of J in 1 Sam. 13^{6,6}, to which *cf.* 7¹² J ('like the sand which is upon the sea-shore for multitude') is also related. The fact, however, that there is some duplication of statement (*cf.* *v.*³ 'there would come up Midian' with *v.*⁵, 'For they and their cattle used to come up'; *v.*⁴, 'And they encamped against them, and destroyed the produce of the land' with *v.*⁵, 'with their tents, . . . and they came into the land to destroy it'), and the somewhat curious combination of tenses in the Heb.,* suggest that elements from more than one source have been combined; and these it is useless to attempt to unravel.†

* After וַיִּהְיוּ . . . וְעָלָה . . . וְעָלָה in *v.*³ we should expect וַיִּהְיוּ . . . וְעָלָה . . . וְעָלָה in *v.*^{4a}, more especially as these statements are continued by וַיִּשְׁאֲרוּ in *v.*^{4b}. The frequentative construction continues the narrative in *v.*^{5a} וַיִּבְּאוּ . . . וְעָלָה, and this is followed in *v.*^{5b} by an imperfect with 1 *consecutive* וַיִּבְּאוּ 'and they came into the land, etc.', which, as summarizing in brief the result of these repeated raids, might stand in the same narrative in continuation of preceding frequentatives; but at the same time is just as likely to have been taken from another narrative which spoke of a single invasion, or viewed the repeated invasions as a single fact (*cf.* וַיִּשְׁחִיתוּ . . . וַיִּבְּאוּ, *v.*⁴).

‡ It is possible (*cf.* Bu. RS. p. 107) that the narrative may contain later glosses. Thus וְאֵת הַמְּעֵרוֹת וְאֵת הַמְּנוֹהָרוֹת 'and the caves' may be explanatory of אֵת הַמְּנוֹהָרוֹת 'the crevices,' or erroneous dittography of it. In *v.*^{3b} it is not unlikely that the text originally ran וְעָלָה מִדְיָן עָלֵינוּ 'then would come up Midian against them' simply, and that later insertion of וְעָמַלְק וּבְנֵי קֵדָם necessitated the

67-10. The retrospect of Israel's past history and the polemic against their idolatry are in the style of the later strata of E which closely approximates to the style of R^{E2}, and, indeed, appears to have formed its model (cf. *Introd.* pp. xli ff.). We may compare generally Josh. 24, 1 Sam. 10¹⁷⁻¹⁹, 12. Cf. especially the phraseology of vv. 8^{ba}, 9^a with 1 Sam. 10¹⁸. The phrases 'bring up or bring out from Egypt,' 'from the house of bondmen,' 'oppressors,' 'Yahweh your God,' 'Amorite' used as a general designation of the inhabitants of Canaan, are characteristic of the school of Hosea; cf. *Introd.* p. xlv. Possibly v. 7 may be due to R^{E2}; cf. v. 7^a with v. 6^b: still, the phrase, 'cried unto Yahweh,' is originally due to E²; cf. 1 Sam. 12¹⁰, Josh. 24⁷. Moreover, the expression עַל אֲדָוָת 'on account of' in v. 7^b is characteristic of E: cf. CH.^E 111.*

61-24. This section clearly stands in no original relationship to the foregoing. Contrast, in v. 13, Gide'on's unconsciousness of any apparent cause for Israel's misfortunes, with the unnamed prophet's denunciation of Israel's idolatry as the crying cause of these misfortunes. The narrative generally has close affinities with ch. 13 and Gen. 18¹ ff., which belong to J. Special J phrases are 'the Angel of Yahweh,' vv. 11, 12, 21, 22 ('the Angel of God' in v. 20 is probably an accidental variation: cf. *note ad loc.*); 'If now I have found grace in thy sight,' v. 17; 'Oh, my lord' (בִּי אֲדֹנָי), v. 15: cf. CH.^J 4, 31a, 56b.

It is probable (as supposed by Bu., Mo., etc.) that this narrative may have undergone some later modifications and additions, the main purpose of which was to imply that the divine character of Gide'on's visitor was evident from the first, and was at once recognized by Gide'on: cf. *notes* on the text. The precise extent of these secondary additions being highly debatable, no attempt has been made to indicate them in the text. Winckler's theory that two distinct narratives are here combined throughout does not commend itself.

625-32 is clearly distinct in source from the foregoing. In 624 Gide'on builds an altar to Yahweh, which is still, when the narrator writes, to be seen in 'Ophrah of the Abiezrites, and was, we may certainly infer, the only altar to Yahweh there. In v. 26, however, he

awkward resumption וַעֲלֶה. Adoption of this conclusion does not, however, oblige us to suppose that the similar detailed description of the foe in v. 33^a, 7^{12a} is likewise due to later interpolation; though it is possible that this may be so.

* Stade (*GVI.* i. p. 182) remarks that the introduction of *anonymous* persons, such as the prophet of this section, into the narrative, is always a mark of late date. This consideration has weight as regards the lateness of the narrative in comparison with the earlier parts of E; but by no means compels us to regard the section as later than E², in face of the evidence connecting it with E² which is noticed above.

is commanded to build an altar to Yahweh in place of the Ba'al-altar, as though no other Yahweh-altar existed in the place, though (if *vv.* 25 ff. are really the sequel of 6¹¹⁻²⁴) he had only just previously built such an altar to Yahweh. Since 6¹¹⁻²⁴ belongs to J, we may infer, therefore, that 6²⁵⁻³² comes from E; and with this agrees the polemic against Ba'al-worship which characterizes it, and which perhaps justifies us in regarding the section as belonging to the same stratum of E as 6⁷⁻¹¹, i.e. E². In addition to the phrase 'Yahweh thy God' in *v.* 26 (cf. *v.* 10), Bu. notes as an E phrase, 'rose up early in the morning' (וַיִּשְׁכְּמוּ בַבֶּקֶר), *v.* 28. The name Jerubba'al, which first appears here, seems to belong to E: notice 7¹, 8²⁹, 9^{1.2.5.16.19.24.67}, 1 Sam. 12¹¹. R^{E2} combines Jerubba'al Gide'on 8^{35a}: cf. R^{JE2}'s gloss, 'that is, Gide'on' in 7^{1a}.

6³³, describing the incursion of Midian, etc., as in *v.* 3b (cf. *footnote*), 7^{12a}, belongs in all probability to E: cf. *note* on 7¹. J's narrative, in 6¹¹⁻²⁴, presupposes that the Midianites are already on the spot, and ravaging the country, at the time of Gide'on's commission.

6³⁴, describing Gide'on's muster of his small force from the clan of Abi'ezer only, is to be assigned to J; while

6³⁵, which pictures the muster of a large force from all Manasseh, Asher, Zebulun, and Naphtali, presupposes the narrative of 7²⁻⁷ (on which see below), and must therefore, in its present form, be assigned to E². It seems likely, however, that the verse is composite (cf. the repeated וַיִּמְלֵאכֵם 'and he sent messengers'); and that the first half, which speaks of a muster from the tribe of Manasseh, belongs to the original narrative of E, which may have been closely akin to J in assuming that Gide'on drew his force from purely local sources. The וְגַם-הוּא 'it also' (the tribe of Manasseh) is R^{JE2}'s link with the preceding *v.* 34.

6³⁶⁻⁴⁰, which gives an account of a request by Gide'on for a sign of God's favour, can scarcely belong to the narrative 6¹¹⁻²⁴ which contains the account of the Theophany. This latter also narrates the request for and the granting of a sign (*vv.* 17 ff.); and in face of this the second sign appears less marvellous and also superfluous. Probably it belongs to a narrative in which the call of Gide'on was related as taking place in a different manner, perhaps through the medium of a vision. Since 6¹¹⁻²⁴ belongs to J, we shall scarcely err in assigning 6³⁶⁻⁴⁰ to E, especially in view of the fact that throughout it uses 'God' (*hā-'ēlōhîm* *vv.* 36, 39, *'ēlōhîm* *v.* 40) and not 'Yahweh.' It may be observed, however, that Gide'on's words in *v.* 39a bear close resemblance to the words of Abraham in Gen. 18^{30.32}, usually assigned to J.*

* According to Bu. (*RS.* p. 111) the words are probably a gloss derived from this passage. La. remarks that the words 'and I will speak only this once' are more appropriate to the Genesis-passage where the conversation is prolonged.

7¹ appears to belong to E. Notice the connexion with 6³³. The invaders arrive and make their encampment as specified; Gide'on then musters his force, and they make *their* encampment: it then remains to notice the relative positions of the two camps. 'The vale' of 7^{1b} is 'the vale of Jezre'el' of 6^{33b}.

7²⁻⁷. Looking at the account of the muster (6³⁵), and the methods employed to reduce the large force from 32,000 to 10,000, and finally to 300, and reading it in the light of the narrative which follows, we can scarcely fail to trace indications of discrepancy. Thus, in 7²³ we are informed that, on the flight of the Midianites, 'the men of Israel were called to arms from Naphtali, and from Asher, and from all Manasseh,' and joined in the pursuit. Yet these are the very tribes which, according to 6³⁵, had already been mustered by Gide'on, and the great bulk of whose representatives must, according to 7²⁻⁷, have been dismissed, and scarcely have had time even to reach their homes. It should be noticed, again, that in 8², where Gide'on contrasts the achievement of his own small force with that of the Ephraimites, he speaks of his force as 'Abi'ezer.' It is of course possible that under this title he may be simply referring to himself as representative of the clan; yet the allusion can scarcely fail to convey the impression that his army as a whole was composed largely if not solely of Abi'ezrites. Reading this in connexion with 6³⁴ which narrates the muster of the clan, the theory becomes plausible that the original narrative may have made Gide'on draw his force from his own clan only; and that this may account for the smallness of its numbers, until reinforced, when the pursuit was taking place, by accessions from the other clans of Manasseh, as well as from the other tribes mentioned (cf., however, *note* on 7²³). Thus, the passages which narrate the first muster from Manasseh, Asher, Zebulun, and Naphtali (6³⁵), and the reduction of the large force to a very small one, must, upon this view, be supposed to belong to another and a later narrative.

We have assigned 6³⁵ partly to the original E (the muster of Manasseh), and partly to E² (the muster of the other tribes mentioned). The latter half of this verse, as narrating the muster of a large force from several tribes, is obviously intended to pave the way for the narrative of 7²⁻⁷, which is to be assigned in like manner to E². That the narrative of E² has been fitted into, and is to some extent dependent upon, the older E, may be inferred from the echo of the phrase of *v.*¹, 'all the people that were with him,' in *v.*², 'the people that are with thee.'

7⁸. The first part of this verse (down to 'their trumpets') is obviously intended to explain how Gide'on came to have so many trumpets and pitchers (if the emendation adopted in the text be accepted) as are presupposed by 7¹⁶; and since, in the narrative of the night-attack, there is good reason to believe that the trumpets

belong to one account and the pitchers to the other, this portion of 7⁸ must be regarded as due to the redactor of the two main narratives, *i.e.* R^{JE}. The rest of the verse is to be assigned to E²; the latter half being resumptive of the narrative of the older E which was broken at 7^{1b} by insertion of the later intervening narrative.

7⁹⁻¹⁴. The older narrative of E, resumed, as we have noticed, in 7^{8b}, is here continued. The relative positions of the two camps having been defined, the Midianite camp as *below* that of Gide'on *in the vale*, the way is paved for the narration of Yahweh's command, 'Go down into the camp, etc.'* Cf. 6²⁵ for the introductory formula of v.⁹, 'And it came to pass the same night, etc.'

7¹⁵⁻²². The account of the night-attack is very involved, and it is impossible to regard it as a unity. Bu. remarks, 'To carry a burning torch in a pitcher turned upside down over it requires two hands; thus there is no hand left for the trumpet, or *vice-versâ*. In the same way, it is impossible at once to blow a horn and to raise the battle-cry' (*Comm.* p. 60). These objections to the integrity of the narrative are to some extent answered by La.; ‡ yet the fact remains that throughout the narrative there occur repetitions which can only be accounted for by the supposition that two parallel accounts have been closely interwoven. Thus v.^{17a} is repeated by v.^{17bβ}; vv.^{19ba-20aa} by v.^{22aa}; v.^{21b} gives an account of the effects of the night-alarm which differs from that which is given by v.^{22aβ}; and v.^{22b} can scarcely be anything else than the combination of two variant accounts of the line of flight. Probably, therefore, the view is correct which regards the pitchers and torches as belonging to one account, and the trumpets to the other. The ruse connected with the pitchers and torches has about it an air of originality and verisimilitude, and Gide'on's small force (according to J's account) would be more likely to find pitchers or

* The obvious transition from 7^{1b}, as noticed above, seems to be the only safe argument upon which this section is assigned to E. Bu. (*Comm.*), who takes the same view as to the source of the narrative, adduces as evidence the night-scene, the dream, and its interpretation; though rightly remarking (against Winckler) that the use of *ha-'ēlōhīm* 'God' (not Yahweh) in the mouth of a Midianite in v.¹⁴ is destitute of significance as a criterion. Such evidence, however, is not very weighty. A night-scene from J immediately follows in one of the narratives of the night-attack; and though it is true that E in the Hexateuch seems to display a fondness for the narration of revelations vouchsafed in nightly visions, this fact by no means renders improbable the occurrence of a like incident in J. The section is assigned to J by Mo., though the majority of scholars appear to be of the opinion of Bu.

‡ La. suggests that, if the pitcher had a hole in it, the torch could be passed through the hole and held by the hand underneath the pitcher; and moreover, even if both hands were needed for this operation, the trumpet might at the same time be suspended from a bandolier. When the pitcher is broken, one hand is surely sufficient to carry the torch, and it is then that the trumpet is blown. Further, it goes without saying that it is possible to desist from blowing the trumpet in order to raise the battle-cry (p. 136).

jars ready to their hand than a sufficient supply of trumpets (the statement of *v.*⁸ must be regarded as the work of R^{JE}): hence we shall probably be right in assigning the pitchers and torches to J, and the trumpets (perhaps under the influence of Josh. 6^{12ff.}) to the later narrative of E. We may then make the following allocation. To J belong *v.*¹⁶ with the exception of 'trumpets and' inserted by R^{JE} in joining the two narratives (notice as a J phrase 'three bands,' lit. 'heads' ראשים, as in *ch.* 9^{34.37}, 1 Sam. 11¹¹, 13^{17f.}, all probably J) *v.*^{17a}, *v.*²⁰ (from 'and they brake,' etc.) with the modification which is due to the insight of Bu. (substituting בַּחֶרֶב for לְתַקוֹעַ, and omitting הָרֶבֶץ after וַיִּקְרְאוּ; cf. *v.*^{18bβ}), 'and in their right hand the sword; and they cried, "For Yahweh and for Gide'on!"' This is directly continued by *v.*²¹; and, possibly with some small intervening omission, by *v.*^{22bβ} which recounts the direction of the enemy's flight. To E must be assigned *v.*¹⁵ (continuing the previous E narrative), *v.*^{17b}, which is continued by *v.*¹⁸ down to 'all the camp,' *v.*¹⁹ down to 'the trumpets,' and *v.*²² down to 'Beth-shittah,' which relates in due sequence how all the three hundred took up the trumpet-call of Gide'on's band (read וַיִּתְקְעוּ שְׁלֹשׁ הַמֵּאוֹת בַּשּׁוֹפָרוֹת), and the effect which the demonstration had upon the foe. All that remains over appears to be the work of R^{JE} in joining and harmonizing the two narratives. Thus, mention of the trumpets had to be inserted in *v.*¹⁶ and in *v.*²⁰ ('the trumpets to blow,' leading to the alteration of J's account above noticed); and mention of the battle-cry and the breaking of the pitchers from J needed to come into *vv.*^{18.19}, which are otherwise derived from E; just as mention of the trumpet-blowing by the three bands had to be duplicated from E's account in *v.*^{22a}, and inserted at the beginning of *v.*²⁰, which is derived from J. If this scheme be adopted, it will be found that the two accounts run parallel, and are each nearly continuous, as may be seen from the connected narrative of each which is given in the *notes ad loc.* This view of the combination of J and E assumes, as we have already noticed, that the statement of *v.*⁸, which (if the emendation adopted in the text be correct) mentions both pitchers and trumpets, is the work of R^{JE}.

7²³. This mention of the call to arms of the neighbouring Israelite tribes is inconsistent with E's narrative in 6³⁵, 7²⁻⁷; since according to this narrative these are the tribes whose representatives had been summoned in the first place, and then, for the most part, dismissed (cf. under 7²⁻⁷). This objection does not hold against assigning the verse to J; though, as a matter of historical fact, it may be doubted whether Gide'on, who seems to have planned his attack in the first instance with the aid of his own clan of Abi'ezer only, would have been able, in the course of a hurried pursuit towards the south-east,

to have summoned the tribes of Naphtali and Asher who dwelt to the north of the scene of action. Possibly, therefore, the verse may be a later gloss, or may have originally mentioned only 'all Manasseh.'

7²⁴-8³. The difficulty noticed under the preceding verse does not apply to the summoning of Ephraim which is here narrated; since the position occupied by this tribe would enable them to intercept the fugitives in time, as is related. The source of the narrative seems to be indicated by Gide'on's allusion in 8² to his achievement as 'the vintage of Abi'ezer,' from which we are justified in assuming that we have the sequel of the account which pictures the rout of Midian as, in its inception, the unaided work of the clan of Abi'ezer; *i.e.* the account of J.* It is clear, however, that 7²⁵ is, in part at least, the work of R^{JE}; the statement that the heads of 'Oreb and Ze'eb were brought to Gide'on *beyond the Jordan* being obviously an attempt to harmonize the narrative with 8^{4ff.} which comes from a different source. Probably the statement 'and they pursued Midian' is also due to the same hand, with allusion to 8^{4ff.} According to J's narrative, the task of Ephraim seems to have been simply to hold the fords; and there is no indication that the pursuit was pushed across the Jordan. On the other hand, *v.*^{25ba}, 'and the heads of 'Oreb and Ze'eb they brought unto Gide'on,' appears to belong to J; more especially if the opening of 8¹, 'said *unto him*' (with back-reference to Gide'on's name in 7^{25b}) is in its original form.

8⁴⁻²¹. The impression which 8¹⁻³ leaves upon us is that the rout of Midian is completed and pursuit at an end. The capture and execution of 'Oreb and Ze'eb may be said to constitute the chief honours of the victory. A lull in the proceedings of victorious Israel affords occasion for the recriminations of the Ephraimites. Yet in 8^{4ff.} we find Gide'on crossing Jordan, and in hot pursuit of two Midianite kings, Zebaḥ and Šalmunna', previously unnamed. And not only so, but his chance of success appears so remote to the men of Succoth and Penuel, upon whom he calls for refreshment for his weary force, that they meet his request with a taunting refusal (*v.*⁶). The conclusion is irresistible that the narrative of 8⁴⁻²¹ belongs to a different account from that of 7²⁴-8³, and that Zebaḥ and Šalmunna in the one account take the place of 'Oreb and Ze'eb in the other. If 7²⁴-8³ is rightly assigned to J, the assumption is that 8⁴⁻²¹ belongs to E; and in favour of this conclusion there may be cited the incredibly large numbers in *v.*¹⁰, which accord with the narrative of 7²⁻⁷ where Gide'on's large force is reduced to 300 in order that his victory may partake of a miraculous character. ‡ As a mark of E's

* La. recognizes that this section belongs to J, but other scholars very strangely assign it to E.

‡ It is not unlikely that the older narrative of E has been amplified by E² in this section also, though evidence decisive of such amplification is lacking. Cf., however, the E section *vv.*²²⁻²⁷ which follows.

narrative we may notice the phrasing of *v.*¹, 'And the three hundred men that were with him,' compared with 7^{1a} 2a.19. The mention in *v.*²¹ of 'the crescents that were upon the necks of their camels' is a point of connexion with *v.*²¹, which belongs to a section which undoubtedly comes from E.

As we read this section, we can scarcely fail to notice that it presupposes the prior narration of incidents which have disappeared altogether from the Gide'on-narrative as known to us. Gide'on's inquiry of the Midianite kings as to the fate of his brethren (*v.*¹⁸) demands that some account of their murder must originally have existed in this narrative, and supplies a new motive for Gide'on's taking action against the Midianites, viz. the prosecution of the blood-feud which naturally devolved upon him. Such a motive, however, is by no means inconsistent with his rôle as the divinely appointed deliverer of Israel. Similar personal considerations enter into the actions of Samson which are ascribed to him as 'Judge' or vindicator of Israel; and may possibly have also influenced Barak, if, as seems likely, he was at one time a captive in the hands of the Canaanites (cf. 5¹², *note*). We have already noticed (cf. under 6³⁶⁻⁴⁰) that in E the account of Gide'on's call is missing, that which is derived from J (6¹¹⁻²⁴) having taken its place. Probably E's account of the call was closely combined with the account of the personal outrage which is presupposed by 8¹⁸ ff. This is a further point which connects our narrative with E rather than J; since, if it belonged to the latter, we might reasonably expect to find some reference to the family-feud in J's account of Gide'on's call in 6¹¹⁻²⁴; and Gide'on would scarcely have professed to regard himself as the man least suited for the task entrusted to him (*v.*¹⁶). It may be added that the obviously sincere description of Gide'on's kingly bearing given by the Midianite kings in 8¹⁸ is hardly consonant with his position as we gather it from J's narrative in 6¹¹⁻²⁴.

8²²⁻²⁷. This section seems clearly to exhibit the hand of E² in *vv.* 22, 23, 27aβb. In *v.*²², the fact that 'the men of Israel' (i.e. the tribes as a whole; cf. *note ad loc.*) join in requesting Gide'on to become their king, invests his victory with a wider importance than it seems to have possessed in either of the older accounts. Cf., as a mark of E², the use of the verb הוֹשַׁעְתָּנוּ 'thou hast saved us.' In *v.*²³, the idea that the appointment of a human ruler is inconsistent with the true conception of the Theocracy, is characteristic: cf. 1 Sam. 8^{6,7,*}

* The view put forward in this passage, that Israel's request for a king amounts to a definite rejection of Yahweh's kingship—'They have not rejected thee, but they have rejected me, that I should not be king over them'—stands in striking contrast to the standpoint of the parallel and older narrative from J, where Yahweh Himself grants a king as a mark of favour and pity: cf. 9¹⁶, where Samuel is instructed with regard to Saul, 'Thou shalt anoint him to be leader over my people Israel, and he shall save my people out of the hand of the Philistines: for I have looked upon my people, because their cry is come unto me.'

10¹⁹, 12¹⁷ (all E²); and passages in Hosea^a in which the appointment of a king appears to be regarded as a wilful act, closely bound up with Israel's defection from Yahweh—Hos. 8^{4,10}, * 10³, 13^{10f}. As a matter of fact, Gide'on's sons *do* seem to have become hereditary sheikhs of Shechem, by virtue of the office transmitted by their father: cf. *ch.* 9², where the verb *māšal*, 'rule,' is the same as is employed in 8²³, 'I will not rule over you, etc.' The polemic against the Ephod in *v.* 27, with the special term employed to describe defection from Yahweh, וַיִּזְנוּ 'and they went a whoring,' is also characteristic of E²: cf. *Introd.* p. xlv.

There is no reason, however, to doubt that the main part of *vv.* 22-27 belongs to an older narrative: and since the verses which we assign to E² are *based upon* this older narrative, the inference is clear that the latter must be assigned to the older stratum of E. The connexion between *v.* 26^b and *v.* 21^{bβ} has already been remarked.

8²³. The concluding summary of R^{E2}, couched in his usual style and phraseology.

6. 1. R^{E2} (JE) And the children of Israel did that which was evil in the sight of Yahweh: and Yahweh gave them into the hand of Midian seven years. 2. And the hand of Midian pre-

6. 1. *Midian*. On the situation of the land of Midian, as lying to the east or north-east of the gulf of 'Aqaba, in the northern part of the modern Ḥigāz, cf. *footnote*, p. 110. The nomadic Arabian clans of Midian were regarded by the Israelites as related to themselves, though somewhat remotely. Midian is reckoned in Gen. 25¹⁻⁶ J as one of the sons of Abraham by his second wife, or concubine (*v.* 6, 1 Chr. 1³²), Keturah; just as Ishma'el is also Abraham's son by the concubine Hagar. The Midianites of our narrative are classed as Ishma'elites in *ch.* 8²⁴; and similarly, in the story of Joseph and his brethren, Gen. 37^{25ff}, while the J narrative relates that Joseph was sold, at Judah's suggestion, to Ishma'elite traders, the E narrative makes him to have been kidnapped by passing Midianites. It thus appears that some amount of vagueness existed in the minds of Israelite historians in their definition of these Arab tribes: and with this inference agrees the fact that, whereas the land of Midian which formed the home of Moses during his exile from Egypt lay far to the south of Canaan (cf. also 1 Kgs. 11¹⁸), Gen. 25⁶ describes Abraham as sending away the sons of the concubines (including Midian) 'eastward, into the land of the east'; and similarly, one of the Bala'am-

* Hos. 8¹⁰ should almost certainly be emended (after ט) וַיִּחְדְּלוּ מִמָּעַט 'that they may cease for a little from anointing a king, and princes.'

vailed against Israel: because of Midian the children of Israel made themselves the crevices which are in the mountains, and the caves, and the strongholds. 3. Now it used to be that, when Israel had sown, there would come up Midian, and 'Amalek, and the children of the East; they would come up against them. 4. And they encamped against them, and destroyed the produce of the land as far as Gaza; and they would leave no means of sustenance in Israel, neither sheep, nor ox, nor ass. 5. For they

narratives embodied in Num. 22-24 (JE) pictures 'elders of Midian' as forming the retinue of Balak, king of Moab (22^{4,7}; cf. also the late narrative of P in Num. 31¹⁻¹²). See further, on this point, Skinner, *Genesis* (ICC.), p. 349.

2. *because of Midian, etc.* The limestone-hills of Palestine are full of caves of various shapes and sizes, which are partly natural and partly artificial. The writer of our narrative traces the origin of these caves to the Israelite refugees, for whom they formed welcome hiding-places. Cf. 1 Sam. 13⁶ J.

crevices. Heb. *minhārôth*, a ἄπαξ λεγόμενον, is explained from the Ar. *minhara* or *minhar*, lit. a place hollowed out by water.

3. *Now it used to be, etc.* The Heb. tenses employed in vv. 3-5 for the most part denote recurrence; but there are some exceptions which probably point to a combination of two originally separate narratives. Cf. footnote * p. 176.

there would come up Midian, etc. The Arab tribes from the east of Jordan commit similar depredations upon the peasant-proprietors west of Jordan at the present day, pitching their tents in the Wâdy of Jezre'el and the Wâdy Šerrâr a little further north, as is described in our narrative, 7^{1,12}. Cf. Thomson, *LB.* pp. 447 f.

and 'Amalek, and the children of the East. Possibly a later insertion in the narrative: cf. footnote ‡ p. 176. On 'Amalek, cf. ch. 3¹² note. The expression 'children of the East' is used again in 1 Kgs. 4³⁰ 5¹⁰ (cited for their proverbial wisdom), Isa. 11¹⁴, Jer. 49²³ (|| Kedar), Ezek. 25^{4,10}, Job 1³, as a general description of the Arab tribes to the east of Jordan, extending as far as the Euphrates; but in Gen. 29¹ E 'the land of the children of the East' is applied to the district of N. Mesopotamia in which Haran was situated.

4. *as far as Gaza.* I.e., as far as the south-western extremity of the Philistine territory. According to this statement, the Midianite incursions must have extended over the greater part of Palestine. The remainder of the narrative, however, appears to confine them to central Palestine; and Gide'on's exertions rid the country of them at one blow. Possibly, therefore, the reference may be due to a later editor, who was thinking of incursions of Arab tribes from the south ('Amalekites?); and it may have been this hand which was responsible

and their cattle used to come up, with their tents, [and] would come in like locusts for multitude; and both they and their camels were without number: and they came into the land to destroy it. 6. And Israel was brought very low by reason of Midian; and the children of Israel cried unto Yahweh.

7. E² And when the children of Israel cried unto Yahweh by reason of Midian, 8. Yahweh sent a prophet unto the children of Israel: and he said to them, 'Thus saith Yahweh, the God of Israel, "I brought you up from Egypt, and I brought you forth from the house of bondmen, 9. and I rescued you from the hand of Egypt, and from the hand of all your oppressors; and I drave them out from before you, and gave you their land. 10. And I said to you, 'I am Yahweh your God; ye shall not fear the gods of the Amorites in whose land ye are dwelling': but ye have not hearkened to my voice.'"

11. J And the Angel of Yahweh came, and sat under the for the allusion to 'Amalek and the children of the East,' in addition to Midian, in the earlier part of the verse.

5. *with their tents.* Lit. 'and their tents.' In the verbal form which follows, 'and would come in,' we adopt the reading of *K^{er}* וַיָּבִיאוּ אֹתָם וְאֶת אֹהֳלֵיהֶם, *Gr^{AL}*, *S^h*, *Θ.*, *L* presuppose וַיָּבִיאוּ, which would govern וְאֶת אֹהֳלֵיהֶם 'and their tents they would bring in, etc.' Since this reading, however, seems to make the following 'like locusts for multitude' refer to the tents and not to the Midianites (as in 7¹²), it must be regarded as inferior to that which is adopted above. It is possible, however, that *K^t*. may indicate the *Kal* וַיָּבִיאוּ 'they used to come in,' the *asyndeton* being due to careless piecing together of the parallel narratives.

8. *a prophet.* Lit. 'a man, a prophet' or 'a prophet-man.' Cf. 'a prophetess-woman,' *ch.* 4⁴.

I brought you up, etc. It is characteristic of E² to base admonition and rebuke upon a retrospect of God's mercies as vouchsafed to Israel in their past history. Cf. Josh. 24^{2ff}, Judg. 10^{11f}, 1 Sam. 2^{27.28}, * 10^{17ff}, 12^{7ff}. This method is further developed in Deuteronomy; probably owing to the influence of the school of thought represented by E². Cf. *Introd.* p. xlv.

11. *the Angel of Yahweh.* Upon the conception involved in this title, and its alternation with 'Yahweh' simply in *vv.* 14, 16, 23, cf. *note* on *ch.* 2¹.

* 1 Sam. 2²⁷⁻³⁶ is commonly regarded as later than E², though without adequate reason.

terebinth which was in 'Ophrah, which belonged to Joash the Abi'ezrite; and Gide'on his son was beating out wheat in the wine-press, to save it from Midian. 12. And the Angel of Yahweh appeared unto him, and said unto him, 'Yahweh is with thee, thou mighty man of valour.' 13. And Gide'on said unto him, 'Oh, my lord, if Yahweh *is* with us, why, then, hath

the terebinth. Heb. *hā'êlā*; possibly 'the (sacred) tree,' without specification of its species: cf. *note* on 'the palm-tree of Deborah,' *ch.* 4⁵. The terebinth or turpentine-tree (*Pistacia terebinthus*, L.) is frequent in Palestine, where it often grows to a large size; and, since it usually stands in isolation, it forms a prominent landmark. Many of these trees are regarded as objects of veneration at the present day. Cf. Tristram, *Nat. Hist.* pp. 400 f.

'*Ophrah.* The site is unknown. It may be inferred from *ch.* 9^{1,2} that it was not far from Shechem. Neither Far'atâ, six miles west-south-west of Shechem (*SWP. Mem.* ii. p. 162), nor Far'ah as preserved in the name of the wâdy to the east of Shechem (Bu.), are philologically probable; the former name accurately corresponding to the Biblical Pir'athon. The designation 'Ophrah of the Abi'ezrites' (*v.* 2¹, 8³²) is perhaps intended to distinguish the city from the Benjaminite 'Ophrah mentioned in Josh. 18²³ P (so Kimchi).

which belonged, etc. The reference is to the terebinth, and not to the city of 'Ophrah.

the Abi'ezrite. Abi'ezer is named in Josh. 17² as a clan of Manasseh—a fact which also appears from *v.* 16 of our narrative. The clan is referred to the Machir-division of Manasseh in Num. 26³⁰ P, 1 Chr. 7¹⁸: cf. *note* on 'Machir,' *ch.* 5¹⁴.

was beating, etc. The Heb. *hābhāṭ* 'beat out' (with a stick) is similarly used of threshing grain in a small quantity in Ru. 2¹⁷. The ancient wine-press (Heb. *gath*) was a trough hewn out of the solid rock, in which the grapes were trodden by the foot; the expressed juice flowing down a channel into another trough at a slightly lower level, the wine-vat (Heb. *yēkebēh*). The use of a wine-press in a sheltered situation for the beating out of wheat was less likely to attract the attention of marauding Midianites than the ordinary process of threshing with a wain drawn by oxen (or an ox and an ass), upon a threshing-floor in an exposed situation open to the wind.

13. *If Yahweh is with us.* Heb. *וַיֵּשׁ יְיָ עִמָּנוּ*. The use of *וַיֵּשׁ* before *יְיָ*—lit. 'And is Y. with us'—imparts a touch of sarcasm to Gide'on's response which it is difficult adequately to reproduce in English. Cf. 1 Kgs. 2²², 'Why, *pray*, askest thou Abishag the Shunammite for Adonijah?' (*וְלֵמָּה*, lit. 'And why'); 2 Kgs. 7¹⁹, 'Pray, if Yahweh were to make windows in heaven, could this thing

all this happened to us? and where are all his wondrous works which our fathers recounted to us, saying, "Did not Yahweh bring us up from Egypt?" But now Yahweh hath cast us off, and given us into the hand of Midian.' 14. And Yahweh turned unto him, and said, 'Go in this thy strength, and save Israel from the hand of Midian: have not I sent thee?' 15. And he said unto him, 'Oh, my ^llord, whereby can I save Israel?

come to pass?' (וְהָיָה, lit. 'And lo'). Other instances are cited in *NHTK*. p. 20.

which our fathers recounted to us. Cf., for the phrase, Ps. 44¹ (32²), 78³. The injunction is laid upon Israelite fathers to recount to their children the facts of the deliverance from Egypt in Ex. 12^{26,27}, 13^{8,14,15} (R^{JE}?), Deut. 6^{20ff}. It is possible that Gide'on's speech, as it stood originally in J, may have been expanded by a later hand in *v.* 13^b.

14. *Yahweh.* Ε^{BAL} ὁ ἄγγελος Κυρίου. Cf. *v.* 16 *note*.

have not I sent thee? Since these words embody a direct commission from Yahweh, it is supposed by many scholars that Gide'on must at once have recognized that he was being addressed by Yahweh or His Angel; and that the passage is therefore inconsistent with *v.* 22, where it is stated that it was only *after the miracle of v.* 21 that Gide'on recognized who his visitor was. The whole section, *vv.* 11-24, having clearly undergone some amount of re-editing (cf. *notes* following), it is quite likely that this passage may be due to the later hand; as also the words 'I will be with thee' in *v.* 16, which recall Ex. 3¹² E. While, however, the narrative assumes that Yahweh, in order to appear visibly to Gide'on, clothes Himself in human form, it does not necessarily follow from this that He should dissemble His presence by couching His commission in the form in which it would be delivered by an intermediary, such as a prophet ('Hath not Yahweh sent thee?'). On the other hand, even though Yahweh should give His commission *directly*, as He is represented as doing, here and in *v.* 16, by the narrative as it now stands, it would obviously require something more surprising than this direct commission (viz. the portent of *v.* 21) to convince Gide'on that he was actually the spectator of a Theophany.

While, therefore, we may *suspect* conflation of the narrative in the passages under discussion, it is a mistake to speak dogmatically and to say that they *cannot* originally have stood alongside of *v.* 22.

15. *my lord.* Vocalizing אֲדֹנָי, in place of אֲדֹנִי of *פ*, i.e. 'my (divine) Lord.' The vocalization of *פ* is intended to indicate that Gide'on by this time recognized that his visitor was Yahweh Himself; but it is clear from *v.* 22 that this was not the case until the occurrence of the events narrated in *v.* 21. The form which we have adopted is

behold my family is the weakest in Manasseh, and I am the least in my father's house.' 16. And Yahweh said unto him, 'I will be with thee, and thou shalt smite Midian as one man.'

the ordinary title of respect (like our 'sir'), and is so vocalized by פֹּה in *v.*¹³.

behold, my family, etc. Mo. compares 1 Sam. 9²¹; and remarks that 'the protestation is, no more than that of Saul, to be taken too literally. Both the following narratives imply that the hero's family was one of rank and influence in the clan.' The word rendered 'family' properly means 'thousand' (Heb. *'elep*h); and occurs in connexion with tribal organization in 1 Sam. 10¹⁰ ('by your tribes and by your thousands'), the following *עַלְפִּי*^{20,21} showing it to be synonymous with *mišpāḥā*, the ordinary term for a *clan* or *family* within the tribe. Cf. also the use of the word in Mic. 5² ('the thousands of Judah,' among which Bethleḥem is a small 'thousand' or 'clan').

the weakest. Heb. *הַלָּוִי*, which R.V. renders 'the poorest.' The adj., however, suggests not merely poverty, but also paucity of numbers and lack of influence in the affairs of the tribe as a whole.

16. *And Yahweh . . . 'I will be with thee.'* Ε^{PA} καὶ εἶπεν πρὸς αὐτὸν ὁ ἄγγελος Κυρίου, Κύριος ἔσται μετὰ σοῦ. If this had originally stood in the Heb. text, it is very unlikely that it would have been altered into the reading of פֹּה ; and we should rather regard the readings of Ε , here and in *v.*¹⁴, as due to the harmonizing tendency which is elsewhere frequently manifested in this Version. Ε^{b} S^{b} agree with פֹּה in the present passage. As we have already remarked (*ch.* 2¹ *note*), it is not unlikely that the original narrative spoke throughout of Yahweh Himself as appearing to Gide'on and holding intercourse with him; and that the introduction of 'the Angel' represents an early attempt to modify the text which has not been thoroughly carried out in פֹּה .

'I will be with thee.' Cf. *note* on 'have not I sent thee?' *v.*¹⁴. The precise words *כִּי אֶהְיֶה עִמָּךְ* are found in Ex. 3¹², E's narrative of the Theophany to Moses at Mount Horeb: cf. also Josh. 1⁵ R^D. In each of these passages, the writers, in using the verbal form *'ehyeh* 'I will be,' probably have in view the significance of the name Yahweh as denoting *progressive revelation*, as is explained in Ex. 3¹⁴ in the formula *'ehyeh 'āšer 'ehyeh* 'I will be (or become) what I will be.' While, however, the latter formula refers to the revelation *as a whole*, as it is to be unfolded throughout the history of the chosen people, and the course of this revelation is intentionally left undefined,* in the former expression we have a particular phase of the

* Cf. the similar phrase 'I will have mercy upon whom I will have mercy,' Ex. 33¹⁶ J, which implies that God refuses to define beforehand a course of action which will be determined by his sovereign will. Similarly, *'ehyeh 'āšer*

17. And he said unto him, 'Prithee, if I have found grace in thy sight, make me a sign that thou art speaking with me.
18. Depart not hence, prithee, until I come unto thee, and

revelation clearly stated—Yahweh promises that He *will be with* each of three chosen servants, Moses, Joshua, and Gide'on.

R.V. renders 'Surely I will be with thee' (so in Ex. 3¹², 'Certainly, etc'); but it is preferable to regard the ׀ as simply introducing the direct narration, like *orū recitativum* in Greek. Such a use of ׀ is frequent: cf. examples collected in *NHTK*. p. 6; BDB. s.v. 1b.

as one man. For the expression, cf. *ch.* 20^{1.8.11}, Num. 14¹⁵, 1 Sam. 11⁷, 2 Sam. 19¹⁴, *III*¹⁵, Ezr. 3¹, Neh. 8¹†.

17. *Prithee, if I have found, etc.* Here 'prithee' represents the Heb. precativè particle *nā*, which comes in the protasis of the sentence after the conjunction 'if,' and is rendered 'now' by A.V., R.V.—'If now I have found grace, etc.' Such a rendering, however, can scarcely be held adequately to represent the precativè force of the particle*; and the rendering 'prithee' has therefore been adopted, the fuller 'I pray thee,' sometimes employed as a rendering by A.V., R.V., (cf. *v.* 39, 8⁵, *al.* †) being less suitable as making too much of the monosyllabic particle. It is obvious that, so far as the particle expresses *entreaty*, it properly refers to the request which is formulated in the apodosis; but its use at the commencement of the protasis is probably intended to place the speaker in the attitude of a suppliant from the moment that he opens his mouth.

make me a sign that thou, etc. As the narrative stands, the request seems to indicate Gide'on's dawning consciousness that his visitor is a supernatural being, and his inability (owing to his uncertainty) to

'*ehyeh* implies that God is absolutely self-determined, and that what He *will be* is to be revealed at His own good pleasure. Cf. the present editor's criticism of Dr. Davidson's interpretation of the two phrases (*Theology of the O.T.*, p. 56), in *JTS*. vi. p. 466.

* For the use of 'now' in the rendering of A.V., R.V., cf. the illustrations collected in the *Oxford New Eng. Dict.*, vi. s.v. 11. 9, where the adverb is used 'In sentences expressing a command or request, with the purely temporal sense weakened or effaced': e.g. Shakespeare, *Love's Labour's Lost*, 11. i. 124, 'Now faire befall your maske'; *Tempest*, 111. i. 15, 'Alas, now pray you worke not so hard . . . pray now rest yourselfe.' The usage is similar in modern colloquial speech, in such a form of request as 'Now, don't forget!'

† In *v.* 39 A.V., R.V. the rendering 'I pray thee' stands side by side with the rendering 'now'—'Let me prove, *I pray thee*, but this once with the fleece; let it *now* be dry only upon the fleece.' In 7⁸ A.V., R.V. *nā* is rendered 'Go to,' as in Isa. 5⁵, Jer. 18¹¹ (on the use of this obsolete expression, cf. *DB*. ii. 194a); apparently because the rendering 'I pray thee' was felt to be unsuitable in the mouth of Yahweh. There is no reason, however, why 'prithee' should not be employed in these passages also as the *conventional* introduction of a request (or a command couched as such), which is what *nā* amounts to in Heb.

bring my present, and set it before thee.' And he said, 'I will abide until thou returnest.' 19. And Gide'on went in, and made ready a kid of the goats, and unleavened cakes of an ephah of

express himself clearly through fear of giving offence. He desires confirmation of his surmise, but does not quite know how to phrase his request, or what kind of sign to expect, because he is not yet clear as to the character of the stranger.

In what follows, however, in *v.*¹⁸ there is no reference to a *sign*, the sign of *v.*²¹ being clearly unexpected by Gide'on; and the act of grace which is asked of the stranger is to stay while a meal is prepared for him, the conversion of which into a sacrifice does not seem to be *anticipated*. It is likely, therefore, that, as Mo., Bu., etc., think, *v.*^{17b} may be an editorial addition,* and that originally *v.*^{17a} was directly connected with *v.*^{18a}—an arrangement which would make the passage closely parallel to Gen. 18³ J, 'Prithee, if I have found grace in thy sight, prithee pass not away from thy servant.'

18. *my present*. The Heb. *minhā* frequently denotes a gift voluntarily offered (cf. *note* on 'tribute,' *ch.* 3¹⁵); but it is somewhat strange to find it applied to hospitality offered in the form of a meal. It is possible, therefore, that the term is intended to denote (*sacrificial offering* (so *Ἡ τὴν θυσίαν*, *Ἦ* 'sacrificium'), and that its employment is due to editorial alteration in view of the fact that the meal actually *did* become a sacrifice: cf. *note* preceding. Bu. conjectures that, in place of 'and bring my *minhā*,' the original narrative may have used the words 'and bring unto thee a morsel of bread': cf. Gen. 18⁶.

19. *made ready, etc.* If we regard this description as referring to the preparation of an ordinary meal, we must suppose that the cakes are unleavened as necessarily prepared in haste; and that the broth is probably the liquid in which the meat was boiled (Kimchi), which, as containing much of its nutritiousness, would not be wasted. Böhme, however, finds in the ingredients of the meal the three forms of sacrificial offering—flesh-offering, meal-offering, and drink-offering,—and therefore regards *v.*^{19aβ} ('the flesh . . . pot') and *v.*²⁰ as a later addition to the narrative, inserted for the purpose of giving to the meal the character of a religious offering. This view is also favoured by Bu. Against it, Mo. remarks, 'if the object was to convert Gide'on's hospitality into a sacrifice, it would have been done unmistakably. In no ritual that we know was meat presented in a basket (as unleavened cakes were) or a libation made of broth. It is conceivable that such rites existed in this early time; but not that such a description proceeds from a later edition. I find in the words, how-

* The unusual relative particle *ψ*, as in 8²⁶, is thought to mark the passage as a gloss.

meal: the flesh he put in a basket, and the broth he put in a pot; and he brought it out unto him under the terebinth, and presented it. 20. And the Angel of God said unto him, 'Take the flesh and the unleavened cakes, and set them on yonder crag, and pour out the broth': and he did so. 21. And the Angel of Yahweh stretched forth the end of the staff which was in his hand, and touched the flesh and the unleavened cakes; and fire went up from the rock, and devoured the flesh and the
 ever, no certain evidence of a sacrificial intention; even וַיִּזְכֹּק ['and presented it'] is properly used of bringing food to one, putting it within his reach (Gen. 27²⁵). The question must be held to be doubtful; cf. *note* following.

an ephah. A dry measure, corresponding to the liquid measure called *bath*, each containing the tenth part of a *hómer*: cf. Ezek. 45¹¹. Its content was probably about a bushel. Such a quantity of flour—weighing some 45 lb., and sufficient to make about twenty-three of our ordinary loaves—is hugely in excess of the needs of the occasion; and possibly this consideration should be held to weigh in favour of the opinion that the writer has in view a religious offering rather than an ordinary meal prepared for a single individual.

20. *The Angel of God.* The expression is that which is commonly employed by E (cf. *ch.* 2¹ *note*); J's phrase, which is elsewhere employed throughout this narrative, being 'the Angel of Yahweh' (so here \mathfrak{G}^{AL} , \mathfrak{S}^{h} , \mathfrak{L}^{L}). Probably the present variation is merely due to transcriptional accident (Mo.), and does not indicate a difference of source.

'Take the flesh, etc.' This ritual as here prescribed can scarcely fail to suggest to us the ancient rock-altar with cup-marks on its surface for receiving libations, such as have been discovered in the excavations of various ancient sites in Palestine: cf. Driver, *Schweich Lectures*, pp. 66 f.; Vincent, *Canaan*, pp. 94 ff.; *TB.* ii. pp. 2 f. Possibly, therefore, the origin of the legend should be traced to the fact that such a rock-altar existed at 'Ophrah in later times, and that its consecration as such was popularly ascribed to the occasion here related. If this is so, however, why are we told in *v.* 24 that Gide'on subsequently *built* an altar to Yahweh on the site? Perhaps we should find in these facts (as Wellh. thinks) an indication of the composite character of the narrative.

21. *stretched forth . . . in his hand.* We may note the verbal similarity to 1 Sam. 14²⁷—also J.

and fire went up, etc. The supernatural fire is a token of the Divine acceptance of the offering as well as of the power of the Deity: cf. 1 Kgs. 18^{22ff.}, Lev. 9²⁴, 2 Chr. 7¹. In the similar narrative of *ch.* 13^{19,20} it seems that Manoah kindles his sacrifice in the ordinary way.

unleavened cakes : and the Angel of Yahweh departed from his sight. 22. And Gide'on perceived that he was the Angel of Yahweh ; and Gide'on said, 'Alas, Lord Yahweh ! forasmuch as I have seen the Angel of Yahweh face to face.' 23. And Yahweh said to him, 'Peace be to thee ; fear not. Thou shalt not die.' 24. So Gide'on built there an altar to Yahweh, and called it *Yahweh shālôm*. Unto this day it is still in 'Ophrah of the Abiezrites.

from the rock. The fact that 'the crag' (*haš-sēla'*) of *v.*²⁰ is here called 'the rock' (*haš-sūr*) is noted by several commentators ; but it scarcely seems necessary to infer diversity of source from this small variation.

and the Angel of Yahweh departed, etc. Cf. *ch.* 13²⁰, where the Angel ascends in the flame from the altar, and disappears.

22. *And Gide'on perceived, etc.* Here we have a clear indication that it is only after the portent related in *v.*²¹ that Gide'on recognizes the supernatural character of his guest. Cf. *note* on 'my lord,' *v.*¹⁵.

'Alas, etc.' For the idea that no human being can see God and survive, unless through an exceptional manifestation of the Divine favour, cf. *ch.* 13^{22f}, Gen. 16¹³ J,* 32³⁰ ~~31~~³¹ J, Ex. 24⁹⁻¹¹ J, 33¹⁸⁻²³ J. E in Ex. 20¹⁹ extends the danger of death to the hearing of the voice of God : cf. Deut. 4³³, 5^{25,26}. We may notice also the words of Isa'iah in Isa. 6⁶. On the other hand, Ex. 33¹¹ E states that 'Yahweh used to speak unto Moses face to face (פָּנִים אֶל-פָּנִים), as in our passage), as a man speaketh unto his friend.'

23. *And Yahweh said, etc.* It is rather strange to find Yahweh again speaking after the departure of His visible representative (*v.*^{21bβ}) ; and there is no indication that the voice is to be understood as coming from heaven, as inferred by Kimchi and Levi ben-Gershon. It seems likely, therefore, that *vv.*²²⁻²⁴ may be due to a later hand, in explanation of the name of the altar, *Yahweh shālôm*. Cf. the inference already drawn, in the *note* on 'Take the flesh, etc.' *v.*³⁰, as to *vv.*^{20,21} in relation to *v.*²²⁻²⁴.

24. *Yahweh shālôm.* The meaning is 'Yahweh is peace,' *i.e.* 'is peaceful' or 'well-disposed.' For this use of *šālôm* (substantive in place of adjective), cf. Ps. 120⁷,

'I am peace ; but when I speak,
They are for war.'

* In this passage we ought probably to follow Wellh. in emending Hagar's words, הֲנִם אֱלֹהִים רָאִיתִי וְאַחֲרַי אָחָרִי רָאִיתִי 'Have I actually seen God and lived after my vision?'

25. E² And it came to pass the same night, that Yahweh said to him, 'Take [ten men of thy servants], and a bull [] of seven

25. *And it came to pass the same night.* Cf., for the exact phrase, *ch.* 7⁹, 2 Sam. 7⁴, 2 Kgs. 19³⁵. 'The same night,' if the expression is an integral part of the source (E²; cf. the same phrase in *vv.* 40 E), probably refers to the night following the day on which the unnamed prophet uttered his denunciation (*vv.* 7-10). It is possible, however, that the phrase may be the redactional formula of R^{JE}, and may refer to the Theophany which immediately precedes in the narrative as it at present stands.

'Ten men . . . years old.' The text of **ח** is here incomprehensible, and can only be naturally rendered 'the bull of the ox which belongeth to thy father, and the second bull of seven years old.' Only one bull, however, is mentioned in *vv.* 26, 28; and apart from the difficulty involved in the expression 'the bull of the ox,'* it is impossible to divine why Gide'on should be ordered to take this first mentioned animal, seeing that it is not utilized in any way in the narrative which follows. R.V. (in agreement with Ew., Stu., Ke., etc.) explains the conjunction ו 'and' in the sense 'even,' thus making the reference to be to one animal only; but it is more than doubtful whether such a rendering is legitimate.†

Clearly the text of **ח** must have suffered corruption; but the Versions seem to have had practically the same text before them, and thus afford us little or no help.

Γ^B, τὸν μόσχον τὸν ταῦρον ὅς ἐστιν τῷ πατρὶ σου καὶ μόσχον δεύτερον ἐπταετῆ, agrees in all respects with **ח**. The only important variations offered by **Γ**^{AL} are τὸν μόσχον τὸν σιτευτὸν in place of τὸν μόσχον τὸν ταῦρον, and the omission of καὶ before the second μόσχον. This at any rate yields an intelligible sense; 'the second bull of seven years old' being taken as a further definition of 'thy father's fattened bull,' and the reference thus being to one animal only; though why the

* A somewhat similar collocation is seen in Ps. 69³¹, **ח**³², מְשֹׁר פָּר 'more than an ox-bull.' Here, however, parallelism and rhythm compel us to divide the stichoi at מְשֹׁר, and, probably, to read מְפָר in place of פָּר:—

'And it shall please Yahweh more than an ox;
<More than> a bull that bath horns and parted hoofs.'

‡ A few cases can be cited in which the conjunction ו appears to have such an explicative force; but they are rare, and in most cases the text is open to suspicion. Cf. 1 Sam. 17⁴⁰, 'and he put them into the shepherd's bag which he had, *even* into the scrip' (וּבִלְקִיט); 1 Sam. 28³, 'and they buried him in Ramah, *even* in his city' (וּבְעִירוֹ). See further BDB, s.v. ו, I b; G-K, § 154, n^{1b}.

years old, and pull down the altar of Ba'al which belongeth to thy father, and cut down the Ashera which is by it. 26. And

animal in question should be described as 'the second,' with assumed reference to an unnamed 'first' bull, remains obscure. It should be noticed, however, that τὸν μύσχαον τὸν στυγερόν simply represents the rendering of \mathfrak{G}^{AL} in *v.*²⁸, *i.e.* הַפָּר הַשֵּׁנִי 'the second bull' read as הַפָּר הַשָּׂמֵן 'the fattened bull.' It seems obvious, therefore, that the text of \mathfrak{G}^{AL} has suffered correction after *v.*²⁸, and that we have no real elucidation of \mathfrak{H} 's פֶּרֶר-הַשֹּׁר 'the bull of the ox.' Some MSS.

of \mathfrak{G} represent וּפֶר הַשֵּׁנִי וג' by καὶ μύσχαον ἑπταετηῇ with omission of δεύτερον; and this word is marked with an asterisk in \mathfrak{S}^h .

\mathfrak{F} 'taurum patris tui,' \mathfrak{S}^p בֶּן־אֲבִיךָ 'the bull of thy father,' omitting either פֶּר or הַשֹּׁר; or possibly rendering the difficult compound expression by a single term, just as is done by R.V., 'thy father's bullock,' cutting the difficulty. \mathfrak{T} simply represents the text of \mathfrak{H} .

In face of this difficulty, the most satisfactory course seems to be to follow Kue. (in Doorn., p. 70 *n.*) and to restore the text after *v.*^{27aa}, קַח עֵשֶׂרָה אֲנָשִׁים מִעַבְדֶּיךָ וּפֶר שְׁבַע שָׁנִים, omitting הַשֵּׁנִי 'the second' as an insertion made subsequently to the textual corruption which introduced apparent mention of *two* bulls: cf. for this latter point, the evidence from the Versions above cited. Gid'e'on is commanded to take ten men of his servants, and in *v.*²⁷ it is stated, with no more than the necessary variation in wording, that he took them. Such detailed repetition is characteristic of Heb. story-telling, as of Babylonian; and is a feature which, so far from appearing tautologous, adds a certain vivid picturesqueness to the narrative. It will be sufficient here to compare *ch.* 7^{10b.11b}: "Go down, thou and Purah thy lad, unto the camp" . . . So he went down, he and Purah his lad, etc.'

Kue.'s emendation is favoured by Bu., Oort, Mo. (*Comm.*), Kit., Gress.; but Mo. (*SBOT.*), La. prefer to read simply הַפָּר הַשָּׂמֵן 'Take the fattened bull.'

the Ashera. The 'āshērā (plur. usually 'āshērīm; in two late passages, 2 Chr. 19³, 33³ 'āshērōth; Judg. 3⁷ probably a textual error for 'āshērōth; cf. *note ad loc.*) was an idolatrous object, the precise character of which is very doubtful. The most lucid reference is Deut. 16²¹, where it is enjoined, 'Thou shalt not plant an Ashera—any kind of tree (*or* wood) beside the altar of Yahweh.' We thus gather that the Ashera was a wooden object (cf. *v.*²⁶ of the present context), possibly a tree-trunk or pole, which was 'planted,' or, as 2 Chr. 33¹⁹ has it, 'set on end' in the ground beside an altar (cf. the present passage). This inference is borne out by the various

verbs which are employed to describe the destruction of the Ashera, e.g. it might be 'cut down' (v.²⁵, 2 Kgs. 18¹, 23¹¹), 'chopped down' (Deut. 7⁵, 2 Chr. 14³, ³¹, 31¹), 'plucked up' (Mic. 5¹¹, ¹³, 13¹³), 'pulled down' (2 Chr. 34⁷), or 'burnt' (Deut. 12³, 2 Kgs. 23¹⁵). It is commonly supposed, upon this evidence, that the Ashera was a symbol of, or substitute for, the sacred tree which was regarded by the early Semites as the abode of a deity; much as the *maṣṣēbhā* or standing stone preserved the idea that the deity was accustomed to inhabit stones or rocks. Upon the unsatisfactory character of this inference, cf. Mo. in *EB*. 331.

There are passages in the O.T. in which Ashera seems to be used as the name of a Canaanite goddess. Thus, in 2 Kgs. 21⁷ mention is made of 'the graven image of the Ashera' placed by Manasseh in the Temple. 2 Kgs. 23⁷ perhaps speaks of women weaving 'shrines' (*bāttim*, lit. 'houses') for the Ashera; and the Ba'al and the Ashera are coupled together as the objects of idolatrous worship: 1 Kgs. 18¹⁹, 2 Kgs. 23¹.

We find the name Aširtu or Ašratu in Babylonian as the name of a goddess, who was doubtless of Amorite origin. In an inscription dedicated to Ašratum on behalf of Hammurabi, in which this king is specially designated as king of Amurru (the west land), the goddess appears as 'bride of the king of heaven' (*kallat šar šamē*), and as 'mistress of sexual vigour and rejoicing' (*bēlit kuzbi u ulsi*): cf. Hommel, *Aufsätze und Abhandlungen*, ii. p. 211. The name Abd-Aširta = 'servant of Ashera' is borne by the chieftain of Amurru who figures prominently in the T.A. Letters (cf. *Introd.* p. lxxii ff.); and the name (ilu) Ašratum-ummi = '(the goddess) Ašratum is my mother' is found three times as a feminine name on contract-tablets of the First Babylonian dynasty: cf. Thureau-Dangin, *Lettres et Contrats de l'époque de la première dynastie Babylonienne*, p. 16. Special interest attaches to a passage in one of the Bab. tablets discovered at Ta'anach, which runs, 'If the finger (= omen) of Aširat point, then let one mark and follow': cf. Rogers, *CP*. p. 282; *TB*. i. p. 128. The S. Arabian goddess Aširat is doubtless the same as Ashera, and appears, according to Hommel, to have been consort of the moon-god (cf. *op. cit.* pp. 207 ff.). In an Aram. inscription from the N. Arabian Têma her name is Ašīra (Cooke, *NSI*. pp. 195 ff.; La., *ÉRS.*² pp. 122, 502 f.).

The relation of the Ashera-cult to Yahweh-worship, and the connexion of the Ashera as a wooden symbol (pole or tree-trunk) with the goddess of this name are very obscure questions; but the following theory may be advanced. Evidence goes to prove that the God Yahweh was known and worshipped by the 'Amorite' immigrants into W. Syria (Amurru), whose original home was probably S. Arabia, and who founded the First Dynasty at Babylon (cf. *Additional note*, p. 243). The presumption is at any rate very strong that Yahweh was

identified with the moon-god Sin, whose predominance at this period is attested by the preponderance of proper names compounded with Sin in the First Dynasty tablets (cf. *Additional note*, p. 249). But, as we have just observed, Aṭirat seems to have been the consort of the moon-god in S. Arabia; and the same conclusion may be drawn as to Ašratum from her title 'bride of the king of heaven' in the inscription of Hammurabi above quoted. Quite possibly, therefore, Ashera may have been worshipped among the Amorites inhabiting Cana'an as the consort of Yahweh; and this fact would account both for the setting up of her symbol beside the altar of Yahweh, and also for the bitter hostility with which her cult was regarded by the prophets as exponents of the true (Mosaic) Yahwism.

The use of the normal expression הָאֲשֵׁרָה 'the Ashera' in O.T. is strange as applied to a goddess; but the explanation probably is that it was employed to designate the *symbol* of the goddess (the pole or tree-trunk), which was perhaps not usually carved to represent her features; though this may occasionally have been the case (cf. 'the graven image of the Ashera,' 2 Kgs. 21⁷, noticed above), as with the stone pillars of Ḥathor at Serabit (cf. Petrie, *Researches in Sinai*, plates 95, 101, 102, 103, 111), and the totem-poles of certain savage tribes at the present day.* Possibly the 'horrible object (Heb. *niph-lēseth*) for an Ashera' erected by the queen-mother in the reign of Aśa (1 Kgs. 15¹³) was a pole carved with certain features which were more than usually revolting to the exponents of the purer form of Yahwism.

Whether the Amorite אֲשֵׁרָה 'Ashera stood in any connexion with the originally Babylonian עֲשֵׁתָרַת 'Ashtart (Ištar), or was quite distinct from her, is a question which cannot at present be settled. The two names are unconnected.† The name Ashera probably designates the goddess as the giver of *good fortune*: cf. the sense attaching to the root אִשַּׁר in Heb. In this connexion it is worth while to recall the passage above cited from the Ta'anach tablet, where the finger of Ashera points the way to the *right* or *prosperous* course.

There can be little doubt that, as has often been remarked, the tribal name Asher was originally connected with the deity of good fortune (a masc. form of Ashera?), just as the name Gad is derived from a similar deity. Indeed, it seems highly probable that, just as the latter name is explained by בָּנֵי 'with (the help of) Gad!' in Gen. 30¹¹ J, so the somewhat strange expression בְּאִשְׁרִי 'in my good luck!' (*i.e.* by somewhat forced inference, 'I am in luck!'), Gen. 30¹³ J,

* The reason why no example of an Ashera has been unearthed in excavation, whereas the occurrence of *masṣēbhōth*, or standing stones, has proved very frequent, doubtless is that the former was always made of wood, which necessarily perishes in the damp climate of Palestine.

† Haupt's attempt to connect the two names (*JAOS.* xxviii. pp. 112 ff.) does not commend itself. Cf. the criticisms of Barton (*JAOS.* xxxi. pp. 355 ff.).

build an altar to Yahweh thy God upon the top of this stronghold in due form, and take the bull [], and offer it up as a burnt offering with the wood of the Ashera which thou shalt cut down.' 27. So Gide'on took ten men of his servants, and did as Yahweh had spoken unto him; and, because he feared his father's household and the men of the city, so that he could not do it by day, he did it by night. 28. And the men of the city rose up early in the morning, and, behold, the altar of Ba'al was broken down, and the Ashera which was by it was cut down, and the bull [] was offered up upon the altar which had been built. 29. And they said one to another, 'Who hath done this thing?' And when they had enquired and searched, they said, 'Gide'on the

is an intentional alteration of an original בַּאֲשֵׁרָה 'with (the help of) Ashera!': cf. Ball *ad loc.*, *SBOT*. p. 84. This passage, then, would suggest that part of the 'good fortune' brought by Ashera was connected with success in child-bearing; a characteristic which connects the goddess, at least in *function*, with Ištar under the aspect of Mylitta, *i.e.* *muallidat*: cf. p. 59 *note*. ‡

26. *this stronghold*. The Heb. *mā'ôz* (from the root 'ûz 'to take or seek refuge') seems here to denote a natural fastness, *i.e.* an inaccessible crag, rather than a fortification. Cf. *šâr mā'ôz*, 'rock of fastness,' Isa. 17¹⁰, Ps. 31², 73³.

in due form. Heb. *bam-mā'arikhā*, *i.e.*, apparently, lit. 'in the (proper) arrangement.' The verb 'ārakh, from which the substantive is derived, when used in a sacrificial connexion, may mean *to arrange* the logs of wood upon an altar (Gen. 22⁹), or the portions of the sacrificial victim upon the wood (Lev. 1^{8.12} 6⁵). The altar-pyre thus

* Or possibly בַּאֲשֵׁר 'With (the help of) Asher!' *i.e.* the masc. form of Ashera. Hommel (*op. cit.* p. 209) is inclined to think that traces may be found in O.T. of Asher as a surname of Yahweh in several old poetical passages, especially in Deut. 33²⁹, which he renders,

'[Yahweh] is the shield of thine help,
And Asher the sword of thine excellency.'

Such an explanation certainly relieves the difficulty of בַּאֲשֵׁרָה הָרֶבֶץ, where בַּאֲשֵׁרָה, as vocalized in 𐤁𐤏, is taken for the relative pronoun; R.V. 'And that is the sword, etc.'—a very awkward and unpoetical construction.

‡ The view that the name Ashera is connected with Bab. *aširtu* 'temple,' perhaps so called as a 'place of favour,' and that the Ashera was simply a pole which marked the precincts of such a sanctuary, does not seem to be probable. If this was the only significance which the Ashera possessed, why should it have excited so much animosity upon the part of the adherents of the purer form of Yahwism?

son of Joash hath done this thing.' 30. And the men of the city said unto Joash, 'Bring forth thy son, that he may die; because he hath broken down the altar of Ba'al, and because he hath cut down the Ashera which was by it.' 31. And Joash

arranged is termed *ma'arākhū* in Ecclus. 50^{12ff.}, where, in speaking of Simon the son of Onias, the writer says:

'When he received the pieces from the hand of his brethren,
While himself standing *by the pyres*;
Round about him a crown of sons,
Like cedar-plants in Lebanon;
And they encompassed him like poplars of the wādy,
All the sons of Aaron in their glory,
With the fire-offerings of Yahweh in their hand,
Before all the assembly of Israel;
Until he finished serving the altar,
And setting in order the pyres of the Most High.

Here the first phrase italicized is על מערכות, and the second ולסדר מערכות עליו.

In Num. 23⁴, 'The seven altars *have I arranged*,' the verb may be used as in the cases noticed above, of setting in order the altar-pyres; but it is possible that it refers to the arranging of the stones of the altars, *i.e.* to the building of them.

In our passage, the context forbids us to interpret *ma'arākhū* of the altar or pyre as duly arranged; but it is natural and legitimate to understand the word as denoting the *act of arrangement* (whether of the altar-stones or the pyre), as prescribed by custom.

The explanation of *bam-ma'arākhū* here adopted is that which is offered by L 'in ordinatione,' S^p בסדרה, T בסדרה 'in order'; and is probably intended by G εν τη παρατάξει. Y paraphrases 'super quem ante sacrificium posuisti'—a rendering which seems to accord with the view put forward by Kimchi, who, having explained the *mā'ōz* as the crag upon which Gide'on offered the flesh and the unleavened cakes, then goes on to interpret *ma'arākhū* as the level place on the top of the crag upon which it was possible to arrange the stones of the altar. Levi ben-Gershon explains similarly.

take the bull. Omitting השני 'the second'; here and in v.²⁸, as a later gloss. Cf. note preceding.

30. 'Bring forth, etc.' The voluntary surrender of Gide'on by his father would have obviated the blood-feud which must have been entailed if the townsmen had slain him without such consent (Mo., Cooke). Mo. quotes a parallel from the life of Mohammed:—'So the Qoreish at Mecca tried to persuade Mohammed's uncle, Abū Tālib, to withdraw from him his protection, that they might kill the

said to all who stood by him, 'Will ye contend for Ba'al? or will ye save him? Whosoever will contend for him shall be put to death at morning: if he be a god, let him contend for himself, because he hath broken down his altar.' 32. So they called him

pestilent agitator without incurring the vengeance of his family' (Ibn Hishām, ed. Wüstenfeld, pp. 167-169).

31. '*Will ye, etc.*' The pronoun is very emphatic in the original, the contrast being between the assumed power of the god as contrasted with his would-be avengers. Mo. appositely cites '*deorum injuriae dis curae*,' Tacitus, *Annals* i. 73.

Whosoever . . . at morning. These words interrupt the connexion between the first and last parts of the verse (cf. *note* preceding); and are probably, as Bu. thinks, the insertion of a zealot for Yahweh who, not satisfied with so mild a method of procedure as is suggested by Joash (the leaving of the god to take care of himself if he can), puts into his mouth the statement that the service of a false god deserves the death-penalty (cf. Deut. 13).

at morning. *I.e.*, we may infer, the morning of the next day. The outrage perpetrated upon Ba'al's altar was discovered in the early morning (v. 28), but the investigations implied by v. 29 must have taken some time; and it was possibly not until the evening that the deed was brought home to Gid'e'on.

The phrase עַד-הַבֹּקֶר commonly means 'until the morning' (*ch.* 19²⁵, Ex. 16^{23,24}, 29³⁴, *al.*); but since this sense is here unsuitable, we must take the force of the pref. עַד to be *at* (lit. *up to*) the time indicated—much as we speak of arriving *up to time* in the sense *at* the fixed time. Cf., in a spatial connexion, the use of the prep. אֵל 'unto' where we should expect 'at'; 1 Kgs. 6¹⁸, 2 Kgs. 10¹⁴, Ezek. 31⁷, 47⁷ (cf. *note* in *NHTK.* on 1 Kgs. 6¹⁸). This explanation of עַד seems more probable than the view that it should be taken in the sense '*while* the morning (lasts)'; cf. עַד הַתְּמָהֳמָה 'whilst they delayed,' *ch.* 3²⁶.

If, however, such passages as *ch.* 16² עַד-אֹר הַבֹּקֶר, 1 Sam. 1²² עַד-יָנֹמֶל הַנֶּעַר, really imply an ellipse of some such word as 'wait,' and should be rendered 'Till the morning dawns!' 'Till the lad be weaned!' (cf. *note* on the former passage); it would be possible in the present passage to treat עַד הַבֹּקֶר similarly as an independent sentence, placing a break on יוֹמָה preceding:—'Whosoever will contend for him shall be put to death. (Wait) till the morning! If he be a god, etc': *i.e.* if Ba'al is really a god, he will at any rate have taken action to avenge himself by the next morning; therefore it is reasonable to ask for a suspense of judgment until that time.

Jerubba'al on that day, saying, 'Let Ba'al contend with him, because he hath broken down his altar.'

32. *Jerubba'al*. The meaning, as explained by the narrator, is 'Let Ba'al contend,' an Imperf. יָרִיב (Jussive יָרִיב)* being employed for the normal יָרִיב (Jussive יָרִיב), which would yield the form יִרְבַּעַל Jeribba'al. Why, in face of the explicit statement of v. 32^b, Mo. should say that 'by an ingenious etymology the name is made to signify, Adversary of Ba'al,' is not clear.

It is probable that, while the meaning of the name may really be 'Let Ba'al contend,' or 'Ba'al contends,' Ba'al is here, as often elsewhere (see below), a title of *Yahweh*; and the original purpose of the name was to place the bearer of it under the guardianship of the Deity: -- 'Let Ba'al contend,' *sc.* for the bearer of the name, *i.e.* be his advocate. Such a meaning appears to attach to the name Merib-ba'al (1 Chr. 8³⁴, 9⁴⁰), which is compounded with the participial form of the verb:--'Ba'al is an advocate,' *sc.* of his nominee; and, similarly, we have the name Jeho-yarib, *i.e.* 'Yahweh contendeth,' 1 Chr. 9¹⁰, *al.* Cf. passages in which the verb *ribh* is used of Yahweh's *taking sides* on behalf of His servants, or *pleading their cause*: so in 1 Sam. 25³⁹, David, on hearing of the death of Nabal, says, 'Blessed be Yahweh, who hath pleaded the cause of my reproach (אֲשֶׁר רָב אֶת־יָרִיב הַרְפָּתִי) from the hand of Nabal'; Mic. 7⁹, 'Till He (Yahweh) shall plead my cause' (יָרִיב רִיבִי); Jer. 50³⁴, 'Their Avenger is strong; Yahweh Šebha'oth is His name; He shall surely plead their cause' (רִיב יָרִיב אֶת־יָרִיבֵם).

Wellh. (*TBS.* p. 31) suggests that the name should properly be יְרֻבְעַל Jerûba'al, which is supposed to mean 'Founded by Ba'al,' or 'Foundation of Ba'al' (the first element from the root ירה: for form, cf. פְּנוּאֵל Penuel, 'Face of God'); and with this he compares יְרוּאֵל Jeruel, 2 Chr. 20¹⁶; יְרִיאֵל Jeriel, 1 Chr. 7². This suggestion has been favoured by several scholars (Mo., Bu., No., etc), but is in no way superior to the explanation adopted above.‡

That the title *Ba'al*, *i.e.* 'Master' or 'Owner,' was actually applied to Yahweh in early times cannot be doubted. Thus we have the name Esh-ba'al or Ish-ba'al, *i.e.* 'man of Ba'al,' a son of Saul, who always appears as a loyal worshipper of Yahweh (1 Chr. 8³³, 9³⁹); Merib-ba'al, son of Jonathan, noticed above; Ba'al-yadha', *i.e.* 'Ba'al knows *or* takes notice' (*sc.* of the bearer of the name; 1 Chr. 14⁷), a

* Cf., for this form, Prov. 3³⁰ אִל, and Infin. Constr. רוּב Judg. 22²² אִל.

‡ As a matter of fact, the sense to be attached to the element *yerû* in *Yerû'el* is highly uncertain.

33. E And all Midian and 'Amalek and the children of the East assembled themselves together; and they passed over, and encamped in the vale of Jezre'el. 34. J And the spirit of Yahweh

name borne by one of David's heroes; Ba'al-ḥanan, *i.e.* 'Ba'al is gracious' (1 Chr. 27²⁸), one of David's officers; and—most striking instance of all—Ba'al-ya, *i.e.* 'Ya or Yahweh is Ba'al' (1 Chr. 12⁶, **¶**⁶), one of David's heroes. These names, where they occur in Sam., have been disguised by a later hand in order to remove the reference to Ba'al which was (wrongly) taken to refer to a false god. Thus we find, in Ish-bósheth for Esh-ba'al, Mephibósheth for Meribba'al, the substitution of *bósheth*='shame' or 'shameful thing'; cf. Hos. 9¹⁰, Jer. 3²¹, 11¹³, where allusions to the Ba'al have been similarly disguised. Ba'al-yadha' appears in 2 Sam. 5¹⁶ as El-yadha', *i.e.* 'God takes notice.' Hos. 2^{16,17}, **¶**^{18,19}, is a passage which witnesses to such an application of the title Ba'al to Yahweh; and also to a dislike of it on the part of the prophets of the higher form of Yahwism, which was doubtless ultimately instrumental in bringing about a discontinuance of the usage:—'And it shall be in that day, saith Yahweh, that thou shalt call me 'îšî (my husband); and shalt call me no more ba'alî (my Ba'al or Master). For I will take away the names of the Ba'als out of her mouth, and they shall no more be mentioned by their name.'

The reason why the name Jerubba'al was not similarly disguised by later scribes doubtless was because it is essential to the point of the narrative, which is polemical to idolatry. In 2 Sam. 11²¹, however, we find the altered form Jerub-bésheth. Cf. further the present editor's *Outlines of O.T. Theology*, pp. 27 ff.

33. *And all Midian, etc.* Cf. v. 3 note.

passed over. *I.e.* crossed the Jordan.

the vale of Jezre'el. The name of Jezre'el is preserved in the modern Zer'in, situated upon an outlying spur of the Gilboa'-range overlooking the plain (for the termination -în for -ēl, cf. *footnote* p. 21). According to Macalister, however, the modern site cannot actually represent the ancient city, since the strata do not exhibit an antiquity so remote as O.T. times (cf. *PEF. Qy. St.* 1909, p. 175).

'The vale ('ēmek) of Jezre'el' here denotes (as is clear from *ch.* 7^{1,8b,12}) the part of the great plain immediately to the north of Gilboa', where it begins to narrow down before its descent into the Jordan valley. There are two other occurrences of the term in O.T.: Josh. 17¹⁶ J, where the children of Joseph state that the Canaanites inhabiting the vale of Jezre'el are too strong for them, owing to their possession of iron chariots; and Hos. 1⁵, where the vale is mentioned as a battle-field: 'I will break the bow of Israel in the vale of Jezre'el.' In these passages 'the vale of Jezre'el' seems to mean the whole extent of the modern Merǧ ibn 'Āmir, just as 'the great plain

clothed itself in Gide'on, and he blew a trumpet; and Abi'ezer was called to arms after him. 35. E And he sent messengers

of Esdraelon,* does in Judith 1⁸; cf. also 3⁹, 4⁶, 7³. 'The valley of Megiddo' (*biḳ'ath M'giddo*) is a different designation for the same plain in 2 Chr. 35²², Zech. 12¹¹. ‡

34. *clothed itself in Gide'on*. The same striking phrase occurs in 1 Chr. 12¹⁸, 19¹⁹, 2 Chr. 24²⁰. The meaning seems to be that the divine spirit took complete possession of Gide'on, so that he became, as it were, its incarnation, and was thus employed as its instrument. For the different terms used in this book to describe the access of the spirit of Yahweh upon a 'Judge,' cf. *ch.* 3¹⁰ *note*.

and Abi'ezer. Gide'on's own clan, 'the weakest in Manasseh (*v.* 15), musters the three hundred who form his sole force, according to the earlier and more authentic tradition preserved in J: cf. p. 179.

was called to arms. Heb. קָרָא. The passive (Niph'al) form of the verb קָרָא or קָרָא, meaning 'to cry out *or* call,' always denotes a summons to battle or armed resistance; the original reference of the verb probably being to the loud, excited shout of a messenger who has little time to spare. R.V.'s rendering, 'was gathered together,' is weak and inexpressive.

35. *And he sent messengers, etc.* On the summoning of the tribes here mentioned, cf. pp. 178 f.

* Esdraelon, the Graecized form of Jezre'el, is written Εσδραηλων, Εσδρηλων, Εσρηλων, with other variants which are doubtless due to textual corruption. Cf. the full list in *EB*. 1391, *n*¹.

‡ Smith (*HG*. pp. 384 ff.) would restrict the O.T. usage of 'the vale of Jezre'el' to the south-eastern portion of the plain denoted in our passage (see above); while supposing that the whole wide open plain was properly termed *biḳ'ā*, as in the phrase *biḳ'ath M'giddo*. This view is based upon the assumption that, while *biḳ'ā* (which he renders 'Plain or Opening') may denote a broad open valley surrounded by hills, 'ēmeḳ (rendered 'Vale or Deepening') is 'never applied to any extensive plain away from hills, but always to wide avenues running up into a mountainous country like the Vale of Elah, the Vale of Hebron, and the Vale of Aijalon.' Such a conclusion as regards 'ēmeḳ (though quoted with approval by many scholars, *e.g.* Cooke here; Gray on Num. 14²⁵, *ICC.*; Driver in *DB*. iv. 846a) can scarcely be maintained. In *ch.* 1¹⁹ (cf. *note*) 'ēmeḳ denotes the whole of the maritime plain to the west of the hill-country of Judah; and the usage in 1³⁴ is similar, and can scarcely be restricted to the vale of Soreḳ or the vale of Aijalon. In the Song of Deborah, *ch.* 5^{15c} (and *v.* 14^a as emended), 'ēmeḳ denotes the widest and most open part of the great plain, through which the Kishon flows. The words of the servants of the king of Aram, 1 Kgs. 20²³, 'Their gods are gods of hills; therefore were they stronger than we: but let us fight against them in the plain (Heb. *bam-miśôr*, lit. 'upon the level ground'); surely we shall be stronger than they' (cf. also *v.* 25), are paraphrased by the man of God (*v.* 28), 'Because the Aramaeans said "A god of hills is Yahweh, and not a god of vales"' (*āmāḳim*). Here it would be absurd to say that the reference is to the valleys running up into the hills, and not to the low-lying and level country generally. Similarly, the 'ēmeḳ in which the horses are pictured as

throughout all Manasseh, and they ^{RJ^E} also ^E were called to arms after him ; ^{E²} and he sent messengers throughout Asher and Zebulun and Naphtali, and they came up to meet them.

36. ^E And Gide'on said unto God, 'If thou *art* about to save Israel by my hand, as thou hast spoken, 37. behold, I am setting a fleece of wool on the threshing-floor: if there be dew upon the fleece alone, and it be dry upon all the ground, then I shall know that thou wilt save Israel by my hand, as thou hast spoken.'

38. And it was so: he rose up on the morrow, and wrung the fleece, and squeezed the dew out of the fleece, a bowlful of water.

39. And Gide'on said unto God, 'Let not thine anger be kindled against me, and I will speak only this once: let me make proof, prithee, but this once with the fleece; let it, prithee, be dry upon the fleece alone, and upon all the ground let there be dew.'

40. And God did so that night: for it was dry upon the fleece alone, and upon all the ground there was dew.

36. '*If thou art about to save, etc.*' The emphasis on the '*art*' (i.e. '*really art*, etc.') is expressed in Heb. by the use of the substantival form יִשָּׁךְ with the Participle used as a 'Futurum instans.' Cf.

Gen. 24⁴² אִם-יִשָּׁךְ-נָא מַעֲלִית דְּרַבִּי 'Prithee, if thou art indeed about to prosper my way, etc.' Where such emphasis is absent, the Participle alone suffices: cf. ch. 11⁹, אִם מְשִׁיבִים אַתֶּם אוֹתִי וּג' 'If ye are going to bring me back.'

37. *a fleece of wool.* Heb. *gizzath haṣ-šemer* denotes a *shorn* fleece; therefore Cooke's suggestion that it was 'perhaps his sheepskin cloak with the wool on it' is excluded.

39. '*Let not thine anger, etc.*' On the resemblance of this passage to Gen. 18^{30,32} J, cf. p. 178 *footnote*.

let me make proof, etc. The threshing-floor, in all probability a flat rocky hill-top or prominence, would not collect much dew, and what little there was would soon evaporate; whereas the fleece would naturally collect and hold the moisture. It thus occurs to Gide'on (*after* his first test) that the phenomenon may after all be nothing in the nature of a portent. The reversed condition of things—a dry fleece upon the wet rock—will be much more unexpected; and therefore more reliable as a sign of supernatural intervention.

pawing the ground, as they stand drawn up in line of battle (Job 39²¹) is clearly to be regarded as an open plain, like the great Merg' ibn 'Amir.

While, therefore, it may be true that *emek* (lit. 'depression') 'is a highlander's word for a valley as he looks down upon it,' the further conclusion that the term is 'never applied to any extensive plain away from hills, but always to wide avenues running up into a mountainous country,' is, as the facts quoted above go to show, entirely unwarranted.

7. 1. And Jerubba'al (^{RJk} that is, Gide'on), ^L and all the people who were with him, rose up early in the morning, and encamped beside the spring of Harod: and the camp of Midian was to the north of him, <beneath> the hill of the Oracle-giver in the vale.

7. 1. *Jerubba'al (that is, Gide'on).* The original narrative, E, here employs the name Jerubba'al; while the insertion of the hero's other name is due to the redactor of J and E. Cf. p. 178.

the spring of Harod. Assuming that the description of the position of the two forces is from the same source as 6³³ E, which describes the encampment of Midian in the vale of Jezre'el (or that, if 7^{1aβb} is from J, both narratives describe the same scene of action), then we must look for the spring of Harod upon the southern edge of the vale, and somewhat above it. These conditions are satisfied by the 'Ain Gâlûd, which Rob. (*BR.*³ ii. p. 323) describes as 'a very large fountain, flowing out from under a sort of cavern in the wall of conglomerate rock, which here forms the base of Gilboa'. The water is excellent; and issuing from crevices in the rocks, it spreads out at once into a fine limpid pool, forty or fifty feet in diameter. . . . From the reservoir, a stream sufficient to turn a mill flows off eastwards down the valley.' Smith states that the spring 'bursts some fifteen feet broad and two deep from the very foot of Gilboa', and mainly out of it, but fed also by the other two springs, flows [in] a stream considerable enough to work six or seven mills. The deep bed and soft banks of this stream constitute a formidable ditch in front of the position on Gilboa', and render it possible for the defenders of the latter to hold the spring at their feet in face of an enemy on the plain' (*HG.* pp. 397 f.). The name *Harôdh* is susceptible of the interpretation 'trembling'; and there is thus no doubt a play upon the meaning in the narrative which follows: cf. *v.*³, 'Whosoever is fearful and trembling (*hārôdh*).'

was to the north . . . in the vale. Reading הִיָּה-לוֹ מַצָּפוֹן מִתַּחַת לְנִבְעַת הַמּוֹרָה בְּעֵמֶק. The text of *℣* cannot be original, it being impossible to attach any sense to מִנְבֵּעַת הַמּוֹרָה. R.V. text, 'by the hill of Moreh' is an unjustifiable perversion of the sense of מִן 'from'; nor does the gratuitous addition of 'onwards' by R.V. marg.—'from the hill of Moreh *onwards* in the valley'—commend itself as at all probable. The emendation adopted supposes simply that מִנְבֵּעַת is a scribe's error for לְנִבְעַת; and the reason for its adoption is connected with the probable site of 'the hill of the Oracle-giver,' on which see below.

Bu. emends הִיָּה-לוֹ מִתַּחַת מַצָּפוֹן לְנִבְעַת הַמּוֹרָה בְּעֵמֶק 'was beneath him, north of the hill of the oracle-giver in the vale' (so Kit., No.). Mo., who supposes that combination with *v.*^{6b} is responsible for the

wrought deliverance for me." 3. Now, therefore, prithee proclaim in the ears of the people, saying, "Whosoever is fearful and trembling, let him return, and decamp from mount [Galud]."

worthy of note that the introductory narrative of J presupposes (6¹¹) that marauding Midianites were in very close proximity to 'Ophrah (to which, all the same, they may have come up from their main encampment in the vale of Jezre'el); and that in *ch.* 7²³ two different accounts of the line of flight appear to be combined, one of which *may* have been down the Wâdy Far'ah from the neighbourhood of Shechem—though, in our ignorance of the localities mentioned, this cannot be affirmed. Cf. *note ad loc.*

3. 'Whosoever is fearful, etc.' For the terms of the proclamation, cf. Deut. 20⁸.

and decamp from mount Galud. Reading מֵהָר הַגָּלֹד. The difficulty connected with מֵהָר הַגָּלֹד is twofold.

In the first place, if מֵהָר הַגָּלֹד is original, it stands alone in Heb. as used in the present connexion; and scholars have exhausted their ingenuity in attempting to assign the verb a suitable meaning under some one of the different roots צַפַּר which are known in Semitic. R.V. *text*, 'and depart,' seems to be guided by the rendering of Ἐ καὶ ἐκχωρεῖτω. R.V. *marg.* 'go round about' follows the explanation of Abulwalid, Tanchum, Kimchi (second alternative), etc., who connect the verb with the subst. צִפְרָה 'chaplet' or 'fillet' (Isa. 28⁸), upon the incorrect * assumption that this is so-called as *going round* the head. A.V., 'depart early,' goes back to Rashi, Kimchi (first alternative), and Levi ben-Gershon, who, connecting with the Aram. ṣaphrā 'morning,' explain the verb as meaning 'to depart in the early morning.' The only really philological explanation is that offered by Siegfried and Stade (*Hebr. Wörterbuch, s.v.*), who make the verb the equivalent of the Ar. ḍafara, which may mean 'to go quickly, spring, leap in running'† (Lane). This is plausible, and has been adopted in our rendering 'decamp'; since the context seems to offer scope for an unusual word—perhaps a colloquialism which was calculated to cast ridicule upon the cowards (like our 'cut and run'). Failing this explanation, it is possible that מֵהָר הַגָּלֹד may be a corruption of מֵעֵבֶר 'and pass on' (Grä.): cf. Ἐ καὶ ἐκχωρεῖτω, Ἐ 'et recesserunt.'

Secondly, the reference to 'mount Gile'ad' as the spot upon which Gide'on's army was stationed is quite inexplicable. The name הַגָּלֹד 'the Gile'ad' is elsewhere confined to the well-known district east of

* The root-meaning of צִפְרָה is seen in the Ar. ḍafara = 'to plait or braid.'

† ضفر is given as a synonym of عدا and سعى by the Arabic lexicographers.

And there returned of the people twenty and two thousand, and ten thousand were left.

4. And Yahweh said unto Gide'on, 'The people are still

Jordan; and though it is perhaps too bold to say that the same name *could* not have been applied to a mountain on the western side of the river, yet such a coincidence in nomenclature is at any rate highly improbable. Le Clerc suggests the substitution of מִהַר הַגִּלְבֹּעַ 'from mount Gilboa'; but against this Stu. (who quotes Dathe) and Mo. argue with some reason that, since Gide'on's army was actually encamped upon Gilboa, the naming of the mountain by Gide'on in his command to depart would be extremely superfluous. Michaelis, by vocalizing מִהַר 'quickly' (cf. *ch.* 2^{17.23}) instead of מִהַר, and understanding הַנִּלְעָד as an accusative of direction, seeks to obtain the meaning of 'flee quickly to Gile'ad,' *i.e.* escape across the Jordan: but this is directly opposed by *vv.* 7.⁸ (Mo.), where it is stated that the people were sent back to their own homes.

In face of these difficulties, Mo. proposes to conclude Gide'on's proclamation with יָשָׁב, and to emend the words under discussion וַיִּצְרֶם נִדְעוֹן. The passage thus runs "Whosoever is fearful and trembling, let him return." *So Gide'on tested them.* In support of וַיִּצְרֶם Mo. compares *v.* 4^b, 'Bring them down unto the water, *that I may test them* (וַאֲצִרְפֶּנּוּ) for thee there.'* This suggestion is adopted by Bu. (*Comm.*), No., La., Kit., Kent, Gress. Ingenious and attractive as it is, however, it can hardly be accepted as satisfactory. For, firstly, if the name of Gide'on had originally stood in the sentence, it is incredible that it should have become so illegible as to be mistaken for 'Mount Gile'ad'; and, secondly, though the verb צִרַף 'test' is appropriate to the method adopted in *vv.* 4^{ff}, where the men are selected and segregated in accordance with their different methods of drinking, the effect produced by Gide'on's proclamation can scarcely be termed a 'testing' in the same sense, and it is very doubtful whether the verb צִרַף could be applied to it.

The close resemblance between תְּנִלְעָד 'the Gile'ad' and the modern Ar. name of the spring of Ḥarod, 'Ain Ḡâlûd, together with the stream which is fed by it—the Nahr Ḡâlûd—can scarcely escape

* It may be noticed that Rabbi Isaiah states that וַיִּצְכֹּר is a metathesis of וַיִּצְרַף (*i.e.* apparently, the Niph'al וַיִּצְרַף 'and so be tested'), just as we get the alternative forms כָּשַׁב, כָּשַׁב. The view that the verb is a metathesis appears to explain the rendering of ט, יתבחר.

many: bring them down unto the water, that I may test them for thee there: and it shall be, of whomsoever I shall say unto thee, "This one shall go with thee," the same shall go with thee, and all of whom I shall say unto thee, "This one shall not go with thee," the same shall not go.' 5. So he brought the people down to the water: and Yahweh said unto Gide'on, 'Everyone who lappeth of the water with his tongue, as the dog lappeth, thou shalt set him apart; and everyone who bendeth down upon

notice; and suggests that *Ġālūd* may be an ancient name, and may have been applied, not only to the spring and stream, but also to the mountain-spur from which the spring issues. If this is so, however, it is natural to inquire into the etymology of the name. According to Smith (*HG.* pp. 397 f. *n*²), Boha-ed-Din (*It. Salad.* ch. xxiv.) gives the name as 'Ain el-Ġālūt or 'well of Goliath,' with whose slaughter by David the *Jerusalem Itinerary* connects Jezre'el. This is obviously mere guess-work, and cannot be regarded as a serious explanation.

Now it is worthy of notice that in Bab. the verb *galūdu* means 'to be afraid';* and, in default of other explanation of the Ar. *Ġālūd*, it is by no means improbable that this preserves an old Heb. or Amorite name, the root-meaning of which was identical with the Babylonian. Thus 'Ain *Ġālūd* may have some such meaning as 'the Coward's Spring'; and 'the Spring of Harod or Trembling' may have been a variant name with similar meaning. It is not too bold to assume that the mountain-spur from which the spring issues may also have borne the name הַר הַנִּלְוֹד 'the Coward's Mount,' and that the story may have been woven round this name; an archaic and possibly obsolete root being explained by the learned writer in the sentence מִיִּירָא וְחָרָר 'Whoso is fearful and afraid.' If this is so, it supplies adequate reason for the mention of the name of the mountain, viz. the play upon the meaning of *Galud* in the terms of the proclamation.

4. *that I may test them.* Heb. וַאֲצַרְפָּנִי may be rendered as by Mo., 'and let me separate them.' The verb *šāraph* is used of the *smelting* process which separates the fine metals from the dross.

5. At the end of the verse, תָּצִיג אוֹתוֹ לְבָר 'thou shalt set him apart,' is supplied upon the authority of Gr^{AL}, *Sh*^h μεταστήσεις αὐτὸν κατ' αὐτόν. So *S*^p. Cf. also the rendering of *V*, 'qui autem curvatis genibus biberint, in altera parte erunt.' The words are necessary to complete the sense of the final sentence, the 'likewise' of R.V., inserted before

* The cognate *galātu* has a similar meaning.

his knees to drink <thou shalt set him apart>.’ 6. And the number of those that lapped [] was three hundred men; but all the rest of the people bent down upon their knees to drink water, <putting their hand to their mouth>.

‘every one that boweth down, etc.,’ being unwarranted by the Heb. text.

6. *And the number of those that lapped, etc.* **U** makes ‘putting their hand to their mouth’ to refer to ‘those that lapped’; but since the lapping is stated in the previous verse to have been ‘as the dog lappeth,’ it is clear that the words are out of place, since the dog laps by putting his tongue to the stream. The words are not found in **Gr^{AL}**, **S^h**, **L**, which read instead בִּלְשׁוֹנָם, ‘with their tongue’; and this may be original: cf. *v.* ⁵. Bu. (*RS.* p. 112, *n*³) was the first to point out that the words ‘putting their hand, etc.,’ are out of place in **U**, and should properly apply to those ‘who bowed down upon their knees to drink.’ He referred them to the end of *v.* ⁵; but Mo. is more probably right in placing them at the end of *v.* ⁶. Very possibly the statement was not part of the original narrative, but a later gloss, written upon the margin of a MS., which crept into **U** in the wrong place.

Stade illustrates the posture adopted by those who lapped water from the spring by a quotation from K. v. d. Steinen: *Unter den Naturvölkern Zentral-Brasiliens*, p. 73. Here the writer remarks, ‘It was a comic sight to see how the rising generation and their sisters drank from the Kulisehu: their mouth in the water; supported upon both hands; one leg in the air; not unlike young monkeys’ (*ZATW.*, 1896, p. 186). On the other hand, the description given by Moody Stuart (*PEF. Qy. St.*, 1895, p. 345) of the man whom he observed drinking in Madeira, though he terms the method ‘lapping’ (misled by the misplacement in *v.* ⁶ which has just been noticed), really illustrates the method of those who knelt down and scooped up the water in the palm of the hand:—‘One afternoon, in riding leisurely out of Funchal, there came toward the town a man in the light garb of a courier from the mountains running at the top of his speed; as he approached me he stopped to quench his thirst at a fountain, in a way that at once suggested the lapping of Gideon’s men, and I drew up my pony to observe his action more exactly, but he was already away as on the wings of the wind, leaving me to wonder and admire. With one knee bent before him, and the other limb stretched out in the same attitude as he ran, and with his face upward toward heaven, he threw the water apparently with his fingers in a continuous stream through his open lips, without bringing his hand nearer his mouth than perhaps a foot and a half, and so satisfied his thirst in a few moments.’ Cf. further, *Addenda*, pp. xiv ff.

7. And Yahweh said unto Gide'on, 'By the three hundred men who lapped I will deliver you, and will give Midian into thy hand; but let all the people go, every man unto his place.'

7. *By the three hundred . . . I will deliver you.* The grounds upon which the three hundred were retained and the great bulk of the host rejected, have formed a puzzle for interpreters since the time of Josephus. It would be a fruitless task to tabulate the different suggestions which have been offered; but, speaking generally, it may be said that the majority of explanations are vitiated (*a*) by the misplacement in *v.* 6 **U**, which has led to a misapprehension of the two forms of drinking; and (*b*) by the presupposition that those chosen must have adopted a method which marked them out as more ready and alert, and therefore more suitable for Gide'on's undertaking.*

Granted, however, that the two forms of drinking are correctly explained in the preceding *note*, it is obvious that (in so far as the test was a test of *attitude*) the main part of the army who knelt to drink, and raised the water in their hands, were the better suited for the enterprise, as adopting a method in the practice of which they were the less likely to be taken by surprise by a lurking foe than

* A striking exception, as regards this latter point, is offered by Josephus, who explains that those who were chosen were marked out by their conduct as the greatest cowards, whom it would have been natural to reject: 'And so, in order that they might learn that the matter was one for His assistance, He advised him to bring his army about noon, in the violence of the heat, to the river, and to esteem those who bent down on their knees, and so drank, to be men of courage, but to esteem all those who drank hastily and tumultuously to be cowards and in dread of the enemy. And when Gide'on had done as God suggested to him, there were found three hundred men who took water in their hands with fear in an agitated manner; and God bade him take these men and attack the enemy' (*Ant.* V. vi. 3). This explanation, in so far as it assumes that God made what was, from the human point of view, an unexpected choice, is in harmony with the explanation which is offered above.

The way in which the two factors (*a* and *b*) noted above have operated in concert in leading an interpreter astray is illustrated by the explanation offered by Smith (*HG.* pp. 398 f.): 'Those Israelites therefore who *bowed themselves down on their knees*, drinking headlong, did not appreciate their position or the foe; whereas those who merely crouched, lapping up the water with one hand, while they held their weapons in the other and kept their face to the enemy, were aware of their danger, and had hearts ready against all surprise. The test in fact was a test of attitude, which, after all, both in physical and moral warfare, has proved of greater value than strength or skill—attitude towards the foe and appreciation of his presence. In this case it was particularly suitable. What Gide'on had in view was a night march and the sudden surprise of a great host. . . . Soldiers who behaved at the water as did the three hundred, showed just the common sense and vigilance to render such tactics successful.' It will be obvious at once that this explanation exactly reverses the methods employed by the three hundred and the main body of the army, as stated in the narrative. Those 'who bowed themselves down on their knees' were not 'drinking headlong'; whereas 'those who merely crouched' obviously could not lap 'as the dog lappeth.'

8. R^{JE} And they took 'the pitchers' of the people in their hand, and their trumpets; E² and all the men of Israel he sent every man to his home, but the three hundred men he retained. And the camp of Midian was beneath him in the vale.

those who rested on their hands or lay prone upon the ground so as to lap like a dog by placing their mouths to the water. But if we take into account the fact that the whole narrative is obviously intended to emphasize the lesson that victory results from Divine assistance and not from the numbers or tactics of the human instruments employed (cf. *v.*²), it seems likely that the lapping method, which, from the purely human point of view, might seem to amount to criminal carelessness in presence of the enemy, may have been taken by the narrator as exhibiting trust in the protection and assistance of Yahweh, as opposed to the anxious alertness of those who believed that their hope of success depended upon themselves. If this is so, a commentary on the narrative may be found in 1 Sam. 16⁷: man looks at the outward appearance of fitness; but God looks at the heart.

8. *And they took the pitchers of the people.* Reading וַיִּקְחוּ אֶת־כַּדָּי הָעָם after Mo. וַיִּקְחוּ אֶת־צִידָה הָעָם וְג. is rendered by R.V., 'So the people took victuals.' If this meaning were intended, however, we should expect וַיִּקְחוּ הָעָם צִידָה * א, א offer the rendering 'And they took the victuals of the people' (*i.e.* אֶת־צִידַת הָעָם or אֶת־צִיד הָעָם); *i.e.* the three hundred took the victuals of the nine thousand, seven hundred, who were returning home. It is obvious, however, that Gide'on's little force, which was bent upon a hasty night-attack upon the Midianite camp, would not encumber itself with so large a quantity of useless provisions; and it need not be doubted that Mo.'s suggestion, כַּדָּי 'pitchers' for צִידָה, is correct. The statement is due to R^{JE}, who explains how Gide'on's army came to have a sufficient number of pitchers (J) and trumpets (E) for the ruse which is to be described in *vv.*^{10ff.} Bu. suggests the further emendations וַיִּקַּח 'And he (Gide'on) took' for וַיִּקְחוּ, in agreement with the sing. שָׁלַח 'he sent' which follows; and מִיָּדָם 'from their hand' in place of בְּיָדָם.

to his home. Lit. 'to his tents.' Cf. *ch.* 19⁹ note.

and the camp of Midian, etc. Resumptive of *v.*^{1b}, after the insertion of the narrative relating the reduction of Gide'on's army. Cf. p. 180.

* The order *verb, object, subject*, though rare, is occasionally found: cf. cases cited by Driver, *Tenses*, § 208, (4). אֵת צִידָה, however (אֵת before the indefinite object), cannot be original.

9. E And it came to^f Midian.' 16. J And he divided the unto him, 'Arise, go do^{hree bands}; and the cam^l in the hand of it into thine hand. 10. nd Jem^r, if thou feare^{and torches inside} go down, thou and Purah thy lad, unto the cut, some portic hear what they say; and afterward thine hands sh^{out} it is re^{ngthened}, and thou shalt go down against the camp.' ted, appe^{ent} down, he and Purah his lad, unto the outskirts of the ^ued men who were in the camp. 12. And Midian and 'Amalek and all the children of the East were lying along in the vale like locusts for multitude; and their camels were without number, like the sand which is upon the sea-shore for multitude. 13. And when Gide'on came, behold a man was recounting a dream to his comrade: and he said, 'Behold, I dreamed a dream, and, behold, a cake of barley-bread was rolling into the camp of Midian; and when it came to a tent, it smote it so that it fell, and it

10. *But, if thou fearest, etc.* Ros. appositely compares the passage from *Iliad* x. 220 ff. in which Diomedes, in offering to go down to the enemy's camp, says that he will do so with more confidence and boldness if he can have a companion:—

Νέστορ, ἔμ' ὀτρύνει κραδίη καὶ θυμὸς ἀγήνωρ
ἀνδρῶν δυσμενέων δῦναι στρατὸν ἐγγὺς ἑόντα,
Τρώων· ἀλλ' εἴ τις μοι ἀνὴρ ἄμ' ἔποιτο καὶ ἄλλος,
μᾶλλον θαλπωρὴ καὶ θαρσαλέωτερον ἔσται.

11. *thine hands shall be strengthened.* I.e. 'thou shalt gain courage and confidence': cf. 2 Sam. 2⁷, 16²¹, *al.*

the armed men. Heb. *ha-ḥāmūšīm* occurs again in Ex. 13¹⁸ E, Josh. 1¹⁴, 4¹², R^D (Num. 32¹⁷ ט, פ), and has been restored in *ch.* 5⁸. The root-meaning of the word is obscure; but Ar. *ḥamīs* 'army' is possibly connected: cf. BDB. *s.v.* Whether the term *ḥāmūšīm* refers to the Midianite warriors as a whole, or only to a special class among them, is not clear. Mo. thinks it 'natural to imagine that in such a raid a part of the invaders, better armed and perhaps better disciplined than the rest, lay along the front of the camp to cover it from attack.'

13. *a cake.* The Heb. term, *šēlāl Kt.*, or *šēlāl K'erē*, only occurs here, and the precise meaning is uncertain; but the context demands a flat circular cake or round loaf.

was rolling. The Participle *mithhappēkh* describes the action as the speaker sees it going on.

when it came to a tent. Heb. idiom says 'the tent,' i.e. the particular tent which actually appeared to be knocked down, and so is

8. R^{JE} And they too¹ . . . pitchers¹ of th¹ comrade answered and and their trumpets: ng else all the men ien of Israel: God hath g¹ to his home, bid Midian and a¹re : camp.’

15-mp of Midian¹idē on heard the tēning of the dream, and its elucidat¹ed himself down; and he returned unto the camp of rested on d said, ‘Arise! for Yahweh hath given into
 \dog’

vividly marked by the Definite Article. On this idiomatic usage, cf. *NHTK.* on 1 Kgs. 13¹⁴; G-K. § 126 r; Davidson, *Syntax*, § 21 e.

it smote it . . . upside down. At the end of the verse \mathfrak{M} adds וַנִּפֹּל הָאֹהֶל, ‘and the tent fell’ (R.V. ‘and the tent lay along’), which is redundant after the preceding ‘so that (*lit.* and) it fell, etc.’ and is marked as a gloss by the false tense (Perfect with *weak* 1). The words are omitted by some MSS. of \mathfrak{C} (cf. Mo., Kit., *BH.*), and apparently by \mathfrak{F} , which renders the whole sentence ‘percussit illud, atque subvertit (וַיִּפֹּל), et terrae funditus coaequavit.’ So Mo., Bu., No., Kit., Gress. וַיִּפֹּל ‘and it fell’ might also be dispensed with before וַיִּפְּכוּ לְמַעַלָּה ‘and it turned it upside down,’ which is all that sense requires. It is omitted by \mathfrak{C}^L , Mo., Bu., La., No., Cooke. \mathfrak{S}^P omits וַיִּפְּכוּ as well as וַיִּפֹּל.

14. *the men of Israel.* \mathfrak{M} , ‘the sword of Gide’ on the son of Joash, a man of Israel’; and so all the Versions. It is unlikely, however, that the original narrator would picture the Midianite as knowing the name of the Israelite leader (Mo.); and elsewhere the expression אִישׁ יִשְׂרָאֵל is regularly used in a collective sense, and not of a particular Israelite. The cake of barley-bread clearly represents the Israelite peasantry as a whole, just as the tent denotes the Midianites collectively. הָרֶבֶךְ ‘the sword of’ may have been introduced from *v.*²⁰.

15. *its elucidation.* Heb. *šibhrô*, only here. We may compare Bab. *šabrû*, fem. *šabrātu*, ‘seer’ or ‘interpreter,’ which seems to be formed from *šubrû* ‘to cause to see,’ the Shaph’el (Causative) modification of *barû* ‘to see,’ whence *bârû* ‘seer.’* So Haupt, *SBOT. ad loc.* Cf. further, *Addenda*, p. xvi.

16-22. The reasons for the detailed analysis of these verses, which divides the narrative between J, E, and R^{JE}, have been fully set forth in the *introd.* pp. 180 f. We here give the narratives of J and E in parallel columns, in order that it may be seen how far each narrative forms an independent whole. Naturally, in the piecing together of

* Kimchi explains טָבַר from the ordinary Heb. verb טָבַר ‘break’ as, literally, ‘its breaking.’—‘for the dream is like a thing which is sealed and closed up, and the interpretation breaks it and reveals it.’ This explanation is adopted by several modern commentators who are unaware of the Bab. parallel.

your hand the camp of Midian.' 16. J And he divided the three hundred men into three bands; and placed in the hand of all of them ^{RJE} trumpets and J empty pitchers, and torches inside

two narratives which are nearly parallel throughout, some portions of each may be expected to have been omitted; but it is remarkable how very nearly each narrative, as reconstructed, appears to run continuously, without a break of any importance.

J

16 And he divided the three hundred men into three bands; and placed in the hand of all of them empty pitchers, and torches inside the pitchers. 17^a And he said unto them, 'Ye shall see what I do, and shall do likewise.

...

20 And they brake the pitchers, and held fast the torches in their left hand, and in their right hand the sword; and they cried, 'For Yahweh, and for Gide'on!' 21 And they stood every man in his place round about the camp: and all the camp awoke, and gave a shout, and fled 22^b toward Şeredah, as far as the edge of Abel-meholah, by Ṭabbath.

16. *trumpets*. Heb. *šôphārôth*, properly 'horns.' The *šôphār* seems to have been the curved horn of a cow or ram; while the *h^ašôš^erâ* was a long straight trumpet made of metal. Cf. illustrations of both in Driver, *Amos* (*Camb. Bib.*), p. 145.

R^{JE} has already indicated his view in v. 8^a as to the source of so large a number of trumpets and pitchers.

pitchers. Heb. *kaddim*, earthenware-jars used as water-pitchers (Gen. 24 14^{ff}, 1 Kgs. 18 34, Eccles. 12 6), and also for containing meal

E

17^b And behold, when I come into the extremity of the camp, it shall be that, as I do, so shall ye do. 18 When I blow the trumpet, even I and all that are with me, then shall ye also blow the trumpets round about all the camp.' 19^a And Gide'on and the hundred men that were with him came into the outskirts of the camp at the beginning of the middle watch; they had only just stationed the guards; 19^{ba} and they blew the trumpets.

22 And the three hundred blew the trumpets; and Yahweh set every man's sword against his comrade throughout all the camp; and the host fled as far as Beth-shiṭṭah.

the pitchers. 17. And he said unto them, 'Ye shall see what I do, and shall do likewise: E and behold, when I come into the outskirts of the camp, it shall be that, as I do, so shall ye do. 18. When I blow the trumpet, even I and all that are with me, then shall ye also blow the trumpets round about all the camp; R^{JE} and ye shall say, "For Yahweh and for Gide'on!"'

19. E And Gide'on and the hundred men that were with him came into the outskirts of the camp at the beginning of the middle watch: they had only just stationed the guards; and

(1 Kgs. 17^{12ff.}). It is possible that each man may have had his jar with him as a receptacle for provisions.

torches inside the pitchers. The pitcher would serve to hide the glowing end of the torch from observation, and at the same time to preserve it from the wind. Lane (*Modern Egyptians*, p. 120) quotes a practice which was in vogue among the police at Cairo about the time at which he wrote (5th edit. 1860), which throws remarkable light on our passage:—"The Zābiṭ, or Āghā of the police, used frequently to go about the metropolis at night, often accompanied by the executioner and the "shealegee," or bearer of a kind of torch called "shealeh," which is still in use. This torch burns, soon after it is lighted, without a flame, except when it is waved through the air, when it suddenly blazes forth: it therefore answers the same purpose as our dark lantern. The burning end is sometimes concealed in a small pot or jar, or covered with something else, when not required to give light.'

17. *Ye shall see what I do.* Lit. 'Ye shall see from me,' i.e., as we might say, 'Ye shall take your time from me.'

18. '*For Yahweh and for Gide'on!*' Nine Codd. (de Rossi) of \mathfrak{H} , some MSS. of \mathfrak{E} (cf. Kit., *BH.*), \mathfrak{S}^p , \mathfrak{T} read 'A sword for Yahweh, etc.'—doubtless a harmonistic addition in agreement with *v.*²⁰ as it stands in \mathfrak{H} .

19. *the outskirts of the camp.* He reserves for himself and his own contingent the most hazardous task of working across the open plain to the far side of the Midianite encampment (under Neby Daḥy? cf. *note* on *v.*¹). The object of the whole stratagem was, of course, to make the Midianites believe that their camp was surrounded on all sides by an overwhelming hostile force.

the middle watch. The passage implies that the night was commonly divided into three watches. These watches were probably each of about four hours' duration, throughout the dark hours; and the middle watch would therefore have commenced about 10 P.M. 'The morning-watch' is mentioned in Ex. 14²¹ J, 1 Sam. 11¹¹. In Roman times the Jews seem to have adopted the Roman system of

they blew the trumpets, R^{JE} and dashed in pieces the pitchers that were in their hand. 20. And the three bands blew the trumpets; J and they brake the pitchers; and they held fast the torches in their left hand, and in their right hand R^{JE} the trumpets to blow; J and they cried R^{JE} 'A sword J for Yahweh and for Gide'on!' 21. And they stood every man in his place round about the camp: and all the camp 'awoke', and gave a

four watches; cf. Matt. 14²⁵ = Mark 6⁴⁸, 'In the fourth watch of the night he came unto them, walking upon the sea.' This fourfold division is referred to by our Lord in Mark 13³⁵—ὁψέ, μεσονυκτίου, ἀλεκτροφωνίας, πρωῒ. The Talmud (*Berachoth* 3b) discusses the question whether the night should properly be divided into three watches, on the authority of our passage, or into four.

20. *and in their right hand, etc.* The passage has clearly been adapted by R^{JE} in his endeavour to combine the pitchers of J with the trumpets of E. If, according to J, the men held the pitchers in their left hand, it was natural for R^{JE} (on the assumption that the two narratives are complementary) to assign the trumpets to the right hand. This he has done without regard to the fact that idiom requires הַשִּׁפְרוֹת after וַיִּחַזְקוּ (cf. בַּלְפִּירִים), and not the accusative הַשִּׁפְרוֹת. But granted the inference that the trumpets do not belong to J's account at all, and taking note of the fact that the battle-cry of v.^{18b} is simply 'For Yahweh, etc.', and not 'A sword for Yahweh, etc.', as in the present verse, Bu.'s suggestion seems very plausible that the word הָרֶב 'a sword' really gives us the clue to the true form of J's original narrative, which may have read בַּהֶרֶב in place of הַשִּׁפְרוֹת לְחֻקֹּעַ—'and in their right hand *the sword*.' This emendation could not be adopted in our text without essentially modifying the composite narrative of R^{JE}; but has been embodied in the narrative of J as given above in parallelism to that of E (p. 215).

'A sword for Yahweh, etc.' Originally, 'For Yahweh and for Gide'on!' as in v.¹⁸. The present form of the battle-cry in this verse results from R^{JE}'s attempt to combine the narratives of J and E. Cf. the preceding *note*.

21. *all the camp awoke.* Reading וַיִּיקֶן, as suggested by Mo., in place of וַיָּרֶן 'all the camp *ran*.' The verb וַיָּרֶן is not elsewhere used in the sense 'run away'; and is in any case superfluous beside וַיָּנוּסוּ 'and fled' (the regular verb in such a connexion) at the end of the verse. The *order* of וַיָּרֶן—ran, shouted, fled—is very strange, and can barely be explained by the supposition that 'ran' means 'rushed

shout, and fled. 22. E And 'the' three hundred blew 't'he trumpets; and Yahweh set every man's sword against his comrade [] throughout all the camp; and the host fled as far as

hither and thither'—for which there is no justification. On the other hand, if we adopt Mo.'s emendation, the description of the awakening, followed by a wild cry of alarm and precipitate flight, is very effective. So No., La., Cooke.

and gave a shout and fled. The shout is rightly explained by Kimchi as a cry of panic. $\text{עַל, } \kappa\alpha\iota \text{ } \epsilon\sigma\eta\mu\alpha\nu\alpha\nu$ appears to understand וַיִּרְעֻעַ in the sense 'gave the signal,' or, as we should say, 'sounded the retreat.' So Rashi תרועת מסע וניסה 'an alarm (outcry) for breaking camp and flight.' In rendering 'and fled,' we follow וַיִּנְסוּ . Adopting K^t . וַיִּנְסוּ (Hiph'il), we should have to understand this verb and the preceding in the sense 'and they [the Israelites] raised the battle-cry, and put [them] to flight.' Cf. R.V. The Hiph'il of נוֹס , without expression of object, as here, is used in *ch.* 6¹¹ in a different sense ('to save [it] from Midian'); but in the present passage omission of the object is not very natural. For וַיִּרְעֻעַ in the sense 'raised the battle-cry' cf. *note* on 'After thee, Benjamin,' *ch.* 5¹⁴.

22. *And the three hundred blew the trumpets.* Reading וַיִּתְקְעוּ בְּשׁוֹפְרוֹת שְׁלֹש־הַמֵּאוֹת , with F, 'Et nihilominus insistebant trecenti viri buccinis personantes.' וַיִּתְקְעוּ שְׁלֹש־הַמֵּאוֹת הַשׁוֹפְרוֹת , can only mean 'And they blew the three hundred trumpets'—though here again (cf. *v.* 20 *note*) we note the use of the Accusative after תִּקַּע , in place of the customary ב : cf. *vv.* 19b, 20a. This ב is supplied in the rendering of ע^B , $\kappa\alpha\iota \text{ } \epsilon\sigma\alpha\lambda\pi\iota\sigma\alpha\nu \text{ } \epsilon\nu \text{ } \tau\alpha\iota\varsigma \text{ } \tau\rho\iota\alpha\kappa\omicron\sigma\iota\alpha\iota\varsigma \text{ } \kappa\epsilon\alpha\rho\iota\nu\alpha\iota\varsigma$, which would seem to suggest $\text{וַיִּתְקְעוּ בְּשִׁלְשׁ וַיִּנְסוּ}$; but may very possibly point to a text $\text{וַיִּתְקְעוּ בְּשׁוֹפְרוֹת שְׁלֹש־הַמֵּאוֹת}$, in which שִׁלְש־הַמֵּאוֹת was really intended as the subject of the verb, in accordance with our emendation.

and Yahweh set, etc. This verse, as contrasted with *v.* 21^b, offers perhaps the most obvious mark of divergency between the two narratives. The camp having fled in a panic (*v.* 21^b), it is clear that *the same narrative* cannot have gone on to state that the Midianites began to fight friend in mistake for foe 'throughout all the camp'; and we are not justified in explaining (with Cooke) that they 'tried to fly,' and then, 'believing themselves to be completely surrounded,' turned their arms against one another prior to the flight becoming general.

throughout all the camp. Reading בְּכָל־הַמַּחֲנֶה , with omission of the conjunction ו , as in ע^B , L^1 , S^1 . The ו is probably to be explained

Beth-shiṭṭah J toward Šerē^f d'lah, as far as the edge of Abel-meḥolah,

(with Mo.) as due to dittography of the last letter of the preceding word ברעהו. A.V. renders ובכל המהנה 'even throughout all the host'; but such an explicative use of ו is highly questionable: cf. ch. 6²⁶ footnote †. R.V. 'and against all the host' requires no refutation.

The Heb. term *maḥ^{ne}* (from the verb *ḥānā* 'encamp') is used both to denote the camp of an armed host, and also the same body of soldiers in action, which we should designate a *host* or *army*. Thus it is impossible to employ a single uniform rendering for the term; 'camp' being in some connexions the more suitable rendering, and in others 'host.' Cf. the similar usage of the Greek στρατόπεδον.

as far as Beth-shiṭṭah, etc. None of the places mentioned can be identified with any certainty. Rob. (*BR.*³ ii. p. 356, *n*³) was the first to suggest identification of Beth-shiṭṭah with the modern Šaṭṭā, which lies on the north side of the Nahr Ġālūd in the line of flight towards the fords of the Jordan. An objection to this, however, may be found in the fact that (supposing the Midianites to have been encamped south of ed-Dahy in the neighbourhood of Shunem) Šaṭṭā is barely seven miles south-east of Shunem, and the nearest fords of the Jordan (east of Bêsân), for which the Midianites may have been making, are some eight miles further east-south-east: whereas the preposition ער can scarcely denote 'in the direction of Beth-shiṭṭah' (which would suit Šaṭṭā), but must rather mean 'up to,' i.e. (as rendered above) 'as far as,' as though Beth-shiṭṭah were in some degree the *destination* of the Midianite host—as it might be considered if it were at or near a ford of the Jordan; or as far as the fugitives got before they were intercepted by the Ephraimites (*v.*²¹). The name Beth-shiṭṭah means 'Place of Acacias'; and since the acacia is common in the Jordan valley (cf. the name Shiṭṭim 'Acacias' east of Jordan opposite Jericho, Josh. 2¹, *al.*, and the modern Ġôr es-Sēsabân 'Vale of the Acacias' in the same locality), there are many sites, east or west of Jordan, to which such a name may have been applied in ancient times.

We read צררתה with 20 MSS. of B, in place of the common reading צררתה 'toward Šerērah.' This further description of the line of flight 'toward Šerēdah, as far as etc.,' can scarcely have originally stood beside 'as far as Beth-shiṭṭah'; and is probably to be assigned to the other source. Šerēdah, which is mentioned in 2 Chr. 4¹⁷ in connexion with Succoth east of Jordan (i.e. probably opposite to it on the western side of the river), is the same as Šarēthan in the parallel passage, 1 Kgs. 7⁴⁶. A Šarēthan is named in 1 Kgs. 4¹², which speaks of 'all Beth-she'an which is in proximity to Šarēthan, beneath Jezré'el'—a position which would suit the line of flight of the Midianite host down the Nahr Ġālūd, as we gather it from our narrative. In Josh. 3¹⁶, however, the city of Adam, the name of which is probably preserved in the modern ford ed-Dâmiy-

yeh, is said to be 'beside Šarēthan'; and ed-Dâmiyyeh is some twenty-seven miles to the south of Beth-she'an—a position which suits the allusion to Šerēdah, 2 Chr. 4¹⁷=Šarēthan, 1 Kgs. 7⁴⁶, since evidence seems to indicate that Šuccoth must have been close to the Jabbok, perhaps a little to the south of it in the Jordan valley: cf. Driver, *Jacob's Route from Haran to Shechem*, in *Expos. Times*, xiii. pp. 457-460; more briefly in *Genesis, Westm. Comm.*, pp. 300-302. Indeed, it is likely, as Mo. suggests, that 1 Kgs. 7⁴⁶ originally mentioned the ford ed-Dâmiyyeh; the obscure בְּמַעְבַּת הָאֲדָמָה (R.V. 'in the clay ground') being probably a corruption of בְּמַעְבַּת אֲדָמָה 'at the crossing of Adamah.'

It is questionable whether the Šerēdah of 1 Kgs. 11²⁶, which was the native city of the Ephraimite Jerobo'am, can be the same as the site above discussed. *U* states in 1 Kgs. 11⁴³, 12^{24b} (according to the numeration of Swete's edition), that Jerobo'am's city was *ἐν τῷ ὄρει Εφραιμ*; whereas the Šerēdah-Šarēthan of the other passages must certainly have been in or near the Jordan valley. Van de Velde's proposed identification of Šarēthan with Ḳarn Šarṭabeh (the כְּרִטְבָּה of the Mishna)—on a spur of the hill-country which runs into the Jordan valley south of the Wādy Far'ah and due west of ed-Dâmiyyeh, forming a prominent landmark—though unsuitable so far as identification of the ancient and modern names is concerned, yet suits geographically all allusions to Šerēdah-Šarēthan, except that in 1 Kgs. 4¹²: cf. Cheyne in *EB*. 5383.

Abel-meḥolah (the native city of Elisha', 1 Kgs. 19¹⁶) is mentioned in 1 Kgs. 4¹² as marking one limit of an overseer's district, the other limit being Beth-she'an. It was evidently south of Beth-she'an; and is identified by Eusebius (*OS*. 227³⁵) with *Βηθμαιελα*, ten miles from Scythopolis (Beth-she'an). This is conjectured by Conder (*SWP. Mem.* ii. p. 231) to be the modern 'Ain el-Ḥelweh in the Wādy el-Māliḥ, which is about that distance south of Bêsân.

There is, needless to say, no philological connexion between Ḥelweh and Meḥolah (as Conder seems to suppose*); the 'Ain el-Ḥelweh, 'spring of sweet water,' being so called in contrast to the generality of the springs in the Wādy el-Māliḥ, 'wādy of the salt water,' which are salt or brackish.† The only argument which can really be advanced in favour of this site is the very slender one that it suits the distance from Beth-she'an as given by Eusebius. But here the resemblance between *-μαιελα* and Māliḥ creates a suspicion that Eusebius may have fallen into error; and that the only ground for his identification was the supposition that some site called Bêth-Māliḥ in his day, in the Wādy el-Māliḥ, preserved the old name Meḥolah.

No theory as to the site of Abel-meḥolah deserves consideration unless it does justice to the striking expression 'the edge' (lit. 'lip,'

* His words are, 'Ain Helweh, the name of which contains the proper radicals [of Abel Meḥolah].'

† Cf. Conder, *Tent Work*, p. 227.

נֶפֶשׁ) of Abel-meḥolah,' which is employed in our passage.* This expression is used elsewhere geographically of the *shore* (lip) of the sea, the *bank* (lip) of a river, and the *edge* (lip) of a wādy. It is this latter usage which here concerns us. It occurs in Deut. 2³⁶, 4⁴⁸; Josh. 12², 13^{9,16}; Ezek. 47^{6,7}. All these occurrences, except those in Ezek., refer to the site of 'Aro'er, which is upon the edge (lip) of the wādy Arnon,' i.e. the modern 'Arâ'ir, which is described by Tristram (*Moab*, p. 129) as a desolate heap of ruins, on the northern edge of the precipitous ravine.† Such a 'lip,' overhanging a wādy, appears then to be what our writer has in mind in speaking of 'the lip of Abel-meḥolah.' Conder, in advocating the site 'Ain el-Ḥelweh, makes no mention of any such *lip* or *edge* in its vicinity; and this question, which does not seem to have entered into his consideration, should form a subject for future topographical investigation, if this site is to be maintained.

Another theory as to the site of Abel-meḥolah may be put forward as not unworthy of consideration. We have observed above that 1 Kgs. 4¹² mentions both Ṣarēthan (Ṣerēdah) and Abel-meḥolah; and we have also seen that the statement in this passage that Beth-she'an was 'in proximity to Ṣarēthan' causes great difficulty; since other allusions to Ṣerēdah-Ṣarēthan seem to place it much further south, in the vicinity of the ford ed-Dâmiyyeh. The supposition that the words 'which is in proximity to Ṣarēthan' (אֲשֶׁר אֵצֶל צָרְתָנָה) have been accidentally transposed, and should properly follow 'Abel-meḥolah,' § has the double merit of dissociating Ṣarēthan from

* The importance of the investigation of this expression was first pointed out to the present writer by Dr. Driver, who, however, advanced no theory as to the site of Abel-meḥolah.

† The ravine and its northern edge (in contrast to the southern) are thus described by Tristram. 'The ravine of the Arnon does not show till we are close upon it. . . . The rolling slopes come close down to the precipitous descent, the plain being perfectly level on either side, breaking away in limestone precipices to a great depth. No idea of the rift can be formed till the very edge is reached. As far as we could calculate, the width is about three miles from crest to crest; the depth by our barometers 2150 feet from the south side, which runs for some distance nearly 200 feet higher than the northern edge. . . . We were much struck by the contrast between the two sides, and this impression was confirmed when, next day, we viewed the southern from the northern edge. The protrusion of the basaltic dyke has been subsequent to the formation of the wady, and the continued detaching of its fragments has made the slope less precipitous, giving a variety to the colouring and the vegetation, wanting on the other side. The northern bank, on the contrary, looked an almost unbroken precipice of marly limestone, faintly tinged with the green hue of a very sparse vegetation, and occasionally protruding cliffs and needles, shining pink in the sunbeams' (*op. cit.* pp. 125 f.).

§ Notice that Beth-she'an is already defined as 'beneath Jezre'el.' It is reasonable, therefore, to suppose that the words 'in proximity to Ṣarēthan,' instead of being a second definition of the position of Beth-she'an, should refer to Abel-meḥolah, the position of which is otherwise unspecified.

Beth-she'an, and bringing it into connexion with Abel-meholah, as in Judg. 7²². The verse then runs, 'Ba'ana the son of Aḥilud : Ta'anach and Megiddo, and all Beth-she'an beneath Jezre'el ; from Beth-she'an to Abel-meholah which is in proximity to Šarēthan ; as far as the other side of Joḳme'am.'

Now we have already noticed, in speaking of the site of Šerēdah-Šarēthan, that identification with the modern Ḳarn-Šarṭabeh would suit all Biblical allusions except that of 1 Kgs. 4¹² as ~~it~~ now stands, where it is brought into connexion with Beth-she'an. This difficulty, as we have seen, is removed, if by our transposition we bring it into connexion with Abel-meholah, as in Judg. 7²².

Rob. (*BR*³. iii. p. 317), in speaking of the view of the northern Ġôr (Jordan valley) from a point east of Jordan near Kefr Abil, above the Wādy Yābis, mentions the opening of the Wādy Far'ah between the ridge of Ḳarn-Šarṭabeh to the south, and 'the opposite lower bluff el-Makhrūd' to the north. This el-Makhrūd is the el-Maḥrûḳ of the *SWP. Great Map and Name List*: cf. Map III. in this commentary. The term *bluff* seems exactly to answer to what the O.T. writers mean by a *lip* or *edge* above a wādy.

Looking again at 1 Kgs. 4, which describes the respective spheres of Solomon's twelve commissariat officers, we notice that, in *v.*⁸, the hill-country of Ephraim is assigned to Ben-Ḥur. All immediately north of this, bounded on the south by the line along which the territory of Manasseh marched with that of Ephraim, seems to have fallen within the sphere of Ba'ana the son of Aḥilud, whose sphere of action (*v.*¹²) immediately concerns us.

Now P's account of the boundary between Ephraim and Manasseh in Josh. 16, 17 is admittedly obscure : but at any rate it seems clear that the eastern part* of this boundary was practically marked by the great Wādy Far'ah, which forms an important dividing factor (notice the allusions in 16⁶ to Ta'anath-Shiloh and Janoah—perhaps the modern Ta'na and Yānûn ; and the mention in 17⁷ of 'Michmethath which is in front of Shechem'). Ba'ana's district, then, seems to have embraced the hill-country bounded on the north by the plain of Esdraelon (Ta'anach and Megiddo : cf. *ch.* 1²⁷ *note*), eastward to and including Beth-she'an where the vale falls to the Jordan valley 'below Jezre'el' ; and then southward to Abel-meholah, the 'lip' of which, if it corresponded to the south-eastern limit of Manasseh, must have been the 'bluff' of el-Maḥrûḳ.

If then, the 'lip' of Abel-meholah is el-Maḥrûḳ (the city itself perhaps lying above this 'lip' to the north, on some part of the headland Rās 'Umm el-Ḥarrûbeh), while Šerēdah-Šarēthan is Ḳarn-Šarṭabeh—the northern and southern ramparts of the Wādy Far'ah, where it opens out into the Jordan valley ; we then perceive why the

* On the western part of the boundary between the two tribes, cf. *notes* on 'Manasseh' and 'Ephraim,' *ch.* 1²⁷, ²⁹.

edge of Abel-meḥolah should be mentioned together with Šerēdah in the narrative of the flight of the Midianites: and also why (if our transposition is correct) Abel-meḥolah should be described as 'in proximity to' (בְּצִדָּה 'beside') Šarēthan in 1 Kgs. 4¹².

The site of Ṭabbath cannot be conjectured.

It now remains to inquire whether any inference can be drawn from this verse as to the line of flight which is presupposed. It is clear that the Biblical indications noticed above as to the positions of the places mentioned may furnish some guide upon this point, even though the actual sites defy identification.

We have seen that, according to E, the field of action is laid in the vale of Jezre'el; with Gide'on's army upon a spur of Mount Gilboa' to the south, and the Midianites encamped in the vale—probably below Neby Daḥy (cf. 6³³, 7¹ *notes*). As regards J this is not so clear; the conjecture being open that this narrative may have laid the scene of the night-attack near 'Ophrah (close to Shechem), and pictured the flight as taking place down the Wādy Far'ah towards the ford ed-Dāmiyyeh (cf. the last paragraph to *note* on v.¹, 'was to the north . . . in the vale'). Laying aside the allusions to Beth-Shiṭṭah and Ṭabbath (about which we know nothing), we have such information as we have gleaned with regard to Šerēdah and Abel-meḥolah to guide our inquiry.

The allusion to Šerēdah-Šarēthan in 1 Kgs. 4¹², as *℥* stands, suits the vale of Jezre'el and excludes the Wādy Far'ah. On the other hand, 2 Chr. 4¹⁷ = 1 Kgs. 7⁴⁶, Josh. 3¹⁶, and 1 Kgs. 4¹² according to our re-arrangement, imply proximity to ed-Dāmiyyeh, and so may seem to favour the Wādy Far'ah as the scene of flight. That ed-Dāmiyyeh was, as a matter of fact, used as a crossing by Midian (at least according to J) is almost necessarily to be inferred from *ch.* 7^{24f.}, where the Ephraimites are invited by Gide'on to hold the fords of the Jordan against Midian: since it is clear that Ephraim could scarcely have been summoned to hold a position north of this point; and, had the Midianites been making for the fords due east of Beth-she'an, such a summons would be out of the question, since the foe would have gained and crossed them before Gide'on's messenger had even reached the Ephraimite territory.

There remains, however, the possibility that E, like J, may have represented the Midianites as making for the ford ed-Dāmiyyeh; *i.e.* as turning southwards down the Jordan valley from the Nahr Ġālūd, and so leaving the fords east of Beth-she'an unattempted, either through their haste or through ignorance of them. It is significant that E in *ch.* 8^{4ff.} seems to picture Gide'on as arriving at Succoth and Penuel * directly he has crossed the Jordan; and the inference there-

* Reference has been made earlier in this *note* to the site of Succoth. With regard to Penuel, Driver's conclusion is:—'A site, S. of the Jabbok near where

fore is that he crossed at ed-Dâmiyyeh, after which he struck eastward 'in the direction of the track of the tent-dwellers,' east of Jogbehah (Aġbêhât)—a further fact which lends colour to the same conclusion.

The question then is—supposing the sites of Şerêdah and the 'lip' of Abel-meĥolah to have been as we have conjectured (the former at Ķarn-Şarṭabeh, and the latter at el-Maĥrûḵ), does the form in which these sites are referred to give us any clue as to whether the line of flight was down the Wâdy Far'ah from 'Ophrah, or down the Jordan valley from the Nahr Ġâlûd—in either case with the ford ed-Dâmiyyeh as the goal?

It is probably significant that ה *locale* is used with Şerêdah, while the preposition ער is employed in the reference to the 'lip' of Abel-meĥolah; *i.e.* while the line of flight was *in the direction of* Şerêdah, it was actually *up to or as far as* the 'lip' of Abel-meĥolah that the fugitives reached.* Here is a point which seems to favour the view that this narrative pictures the flight as down the Jordan valley from the Nahr Ġâlûd; since this would involve taking the direction of Ķarn-Şarṭabeh, but at the same time turning off some miles short of it *at* el-Maĥrûḵ in order to make for the ford ed-Dâmiyyeh.† On the other hand, had the course of the fugitives been down the Wâdy Far'ah, it is difficult to see why the distinction should be drawn in the form of reference to the two localities.

Evidence is insufficient to guide us to a decision as to whether the description which we have been considering belongs to J or E. In any case, however, we are probably justified in concluding that the

the Ghôr route crosses the route from es-Salt to the ford ed-Dâmiyyeh, though it can only be assigned conjecturally, would satisfy the conditions of the Biblical narrative.' Cf. references cited, and *Genesis* (*Westm. Comm.*), p. 296.

* The same distinction in usage between ה *locale* and the prep. ער is to be observed in Gen. 10¹⁹ J, where it is stated that 'the border of the Canaanite was from Şidon as thou goest *in the direction of* Gerar (גֵּרָר), *as far as* Ġaza (עֵזְרָה); as thou goest *in the direction of* Şodom and Ġomorrhah and Admah and Seboiim (סְדֹמָה וְגִמְרֵי), *as far as* Leshah' (עֵשְׂרֵן).' Gerar is some distance south-east of Ġaza; so if Ġaza marks the south-west point of the Canaanite territory, the distinction indicated by the use of ה *locale* with Gerar—further on beyond the boundary—is perfectly correct. The whole definition is, however, somewhat strange; and, as Skinner remarks (*ICC. ad loc.* p. 217), 'would only be intelligible if Gerar were a better known locality than Ġaza.' Hence some scholars think that עֵשְׂרֵן is a later gloss. With regard to the places which are named on the south-east we can draw no conclusions, since we are ignorant of their precise positions.

‡ It is actually *at* el-Maĥrûḵ that the road down the Jordan valley from the north intersects the road which, coming from the hill-country to the west, enters the Wâdy Far'ah and runs down to the ford ed-Dâmiyyeh: cf. *Map* III.; *SWP. Great Map*, sheet xv.; Smith, *HG.* Plate v. The name el-Maĥrûḵ signifies 'the perforated,' *i.e.* a rock-cutting through which a road passes.

by Tabbath. 23. And the men of Israel were called to arms ^{GI?} from Naphtali and from Asher, and J from all Manasseh, and they pursued after Midian. 24. And Gide'on sent messengers throughout all the hill-country of Ephraim, saying, 'Come down to meet Midian, and take [the fords] of the Jordan against them': so all the men of Ephraim were called to arms, and took [the fords] of the Jordan. 25. And they took the two princes of Midian, 'Oreb and Ze'eb; and they slew 'Oreb at

variation between the two narratives, as regards topography, was by no means so great as some scholars have assumed.

23. *were called to arms.* Cf. ch. 6³¹ note.

from Naphtali and Asher. Upon the summoning of these tribes, cf. p. 181.

24. *the fords of the Jordan.* Reading אֶת-מַעְבְּרוֹת הַיַּרְדֵּן, as in ch. 3²⁸, 12^{5,6}, in place of אֶת-הַמַּיִם עַד בֵּית בָּרָה וְאֶת-הַיַּרְדֵּן 'the waters as far as Beth-barah, and the Jordan,' the meaning of which has proved a puzzle to commentators. No such site as Beth-barah is known; and Mo.'s suggestion that 'the waters' are the perennial stream of the Wâdy Far'ah, between which and the Jordan 'the Midianites would be in a *cul de sac*,' is vitiated by the fact that the lower part of the Wâdy Far'ah, which is known as the Wâdy eḡ-Ġôzeleh, flows into the Jordan some five miles south of the ford ed-Dâmiyyeh; and therefore, if the Midianites were aiming at ed-Dâmiyyeh, they would not need to cross the Wâdy Far'ah stream at all. Even apart, however, from the difficulty of identifying Beth-barah, the whole description is curiously vague and unintelligible. Why are 'waters' mentioned instead of *nahal*, wâdy (if any particular wâdy is meant); and what is the force of עַד 'unto' or 'as far as,' which suggests that the Ephraimites are expected to line 'the waters' for an indefinite distance, as far as the locality specified? Is it, again, possible that 'and the Jordan' can be original, without reference to any particular ford or fords?

Our emendation supposes that the letters הממערבתברהואת are simply corrupt dittography of מַעְבְּרוֹת, which can be recognized once in letters 3 to 7 with transposition of ב and ר and corruption of the latter letter to ר (מַעְרַבְתָּר). Letters 2, 8, 9, 13 preserve genuine letters of the doublet; this time with בַּר in the right order.

25. *'Oreb and Ze'eb.* The names mean 'Raven' and 'Wolf.' It has been thought that the use of such animal-names presupposes a primitive totemistic stage of society; and evidence quoted from Arabian sources is somewhat striking: cf. Robertson Smith, *Animal worship and animal tribes among the Arabs and in the Old Testa-*

the rock of 'Oreb, and Ze'eb they slew at the wine-vat of Ze'eb; R^{JE} and they pursued ¹ Midian; J and the head[s] of 'Oreb and Ze'eb they brought unto Gide'on R^{JE} beyond the Jordan.

8. 1. J And the men of Ephraim said unto him, 'What is this thing that thou hast done unto us, not to call us when thou didst go to fight with Midian?' and they chode with him

ment; Journal of Philology, ix. pp. 75 ff. Among examples of tribal animal-names collected from Suyûṭī's dictionary of gentile names, we find Zib, 'wolf,' son of 'Amr, a sub-tribe of the Azd; and Ġurâb, 'raven,' a sub-tribe of the Fazâra: cf. *op. cit.* p. 79. On animal-names in the O.T., cf. Gray, *Hebrew Proper Names*, pp. 86 ff.

the rock of 'Oreb . . . the wine-vat of Ze'eb. Conder (*SWP. Mem.* iii. p. 177) tentatively suggests as possible sites the modern 'Uṣṣ el-Ġurâb, 'the nest of the raven,' a sharp conical peak some 2½ miles north of the modern Jericho (Eriḥa); and Tuwêl ez-Ziyâb, 'the ridge of the wolves' (apparently a clan bearing the name ez-Ziyâb), nearly 5 miles north-west of the same point. These sites are probably much too far south of the scene of action; and in any case we cannot attach importance to designations embodying animal-names which (at any rate in the case of Zib, plur. Ziyâb) appear to be elsewhere in frequent use.*

they pursued Midian. Reading מִתְּמִי in place of מִלְּמִי, 𐤌.

the heads. Reading רִאשֵׁי in place of the sing. רִאשׁ, 𐤓.

beyond the Jordan. On the manner in which this verse has been glossed by R^{JE} in order to make it fit in with the narrative of 8⁴⁴, cf. p. 182.

8. 1. *And the men of Ephraim said, etc.* The conduct of the Ephraimites towards Jephthah, ch. 12^{1ff}, is very similar; and the grounds alleged for the quarrel, viz. failure to summon them to the battle in the first instance, are the same. There is no reason, however, to assume, with some scholars, that one of the narratives is therefore secondary to the other. Cf. Mo. *ad loc.*, who remarks that in the two stories 'the sequel is as different as can be imagined, and in each is in entire conformity with the situation.'

* Other instances of the name 'wolf' in place-names in or near the Jordan valley, as noted in the *SIVP. Great Map*, are:—a second Tuwêl ez-Ziyâb, 5½ miles due north of Râs 'Umm el-Ḥarrûbeh (sheet xii.); Metil ez-Zib, 'the peak of the wolf,' in the Jordan valley, 3½ miles south-west from ed-Dâmiyyeh (sheet xv.); Wâdy Unḵûr ez-Zib, 'wâdy of the water-holes of the wolf,' running from the hill-country into the Jordan valley about 8 miles south-west of ed-Dâmiyyeh; and Wâdy Mekûr ez-Zib (with the same meaning), 3 miles further south (sheet xv.).

violently. 2. And he said unto them, 'What have I done now in comparison with you? Is not the gleanings of Ephraim better than the vintage of Abi'ezer? 3. Into your hand hath 'Yahweh' given the princes of Midian, even 'Oreb and Ze'eb: and what was I able to do in comparison with you?' Then was their anger against him abated, when he had spoken this word.

4. E And Gide'on came to the Jordan, 'and he' passed over,

2. *Is not the gleanings, etc.* The Heb. term 'ôlêlôth is confined to the gleanings of grapes (Mic. 7¹, Jer. 49⁹, Ob. 5, Isa. 24¹³) and olives (Isa. 17⁶), and is never used of the gleanings of grain, for which another term, *lêket*, is employed. The point of Gide'on's words is that, though not called to lend their aid until the rout of Midian was an accomplished fact, yet the Ephraimites might be said actually to have secured the greater honour, through the capture of the two princes of the enemy. The fact has already been noted (p. 182) that Gide'on's allusion to his own small force as 'Abi'ezer' seems to indicate that this narrative (J) pictured the muster as consisting of Abi'ezrites only (*ch.* 6³⁴), and knew nothing of the gathering and subsequent dispersion of a very large force from several tribes (E²).

3. *Yahweh.* So E, F, T, in place of H 'God.'

their anger. Lit. 'spirit,' or, as we might say, 'temper.' For this use of Heb. *rûah*, cf. Prov. 16³², 25²⁸, Job 15¹³, Zech. 6⁸, Eccles. 10⁴.

4. *and he passed over.* Reading וַיַּעֲבֹר, which seems to be presupposed by E, F, S^P, with Grä., Bu., Oort, No., La., Cooke; in place of the Participle עֹבֵר in H. The use of this latter, though grouped by Driver (*Tenses*, § 161, (2)) under clauses 'with a participial determination of the subject as the secondary predicate,' is difficult to justify syntactically; the Participle here expressing not an action *concomitant with* the action expressed by the main verb (וַיָּבֵא 'And he came'), but resulting from it.* The Imperfect with ו consecutive is the regular construction to express such a sense.

* Thus such an instance as Jer. 17²⁵ וַיָּבֹאוּ . . . רֹכְבִים 'shall enter *riding*' is evidently different, since here the participle describes the *manner of entry*; and Judg. 17, Isa. 36²², Jer. 27, *al.*, are similar to this. Perhaps the case most like our passage is Num. 16²⁷ וַיָּצְאוּ נֹצְבִים 'they came forth *stationed* (or 'so as to be stationed,') where וַיָּצְאוּ expresses the *result* of וַיָּבֹאוּ; but, in order to make our passage really parallel to this, we should have to alter the 'Athnah from הַיַּרְדֵּן to עֹבֵר—'came to the Jordan, *crossing over*' (*i.e.* 'so as to cross over'); and then what is to happen to the latter half of the verse which also exhibits its

he and the three hundred men who were with him, exhausted and [famished]. 5. And he said to the men of Succoth, 'Prithee, give loaves of bread to the men who are following me, for they are exhausted; and I am pursuing after Zebah and Salmunna',

exhausted and famished. Reading וְרַעֲבִים with \mathfrak{G}^{AL} , \mathfrak{S}^{h} , \mathfrak{L}^{L} . So Houb., Bu., Grä., Frankenberg, Kit., Oort, No., La. This correction seems almost to be postulated by ν .⁵, where the request for bread is made of the men of Succoth. In order to justify the reading of \mathfrak{L} , we have to treat the conjunction ו as adversative, as is done by A.V., R.V., 'faint *yet* pursuing.' Possibly the alteration of רַעֲבִים into רָדְפִים may have been due to the fact that in ν .⁵ בִּי־עֵיפִים הֵם, 'for they are exhausted,' is followed by וְאֲנִי רֹדֵף, 'and I am pursuing.'

5. *Succoth.* The actual sites of Succoth and Penuel have not been discovered; but evidence goes to show that they must have been not far south of the Jabboḳ: cf. *note* on 'as far as Beth-shittah, etc.,' *ch.* 7²².

loaves of bread. Heb. *kikkêrôth léhem* means lit. 'rounds' or 'circles of bread,' i.e. probably, round, flat cakes.

who are following me. Lit. 'who are at my feet.' Cf. 4¹⁰ *note*.

Zebah and Salmunna. The names זֶבַח and שַׁלְמוֹנָע mean respectively 'sacrifice' ('sacrificial victim') and 'shelter withheld.'* It is obvious that these forms cannot be original, but must be later

participial determination of the subject, 'עֵיפִים וְ' 'exhausted, etc.'? We should have to treat it as a circumstantial clause: 'He and the three hundred, etc., were exhausted, etc.' As the verse is accented, however (with break on הִירְדְנָה), we can only render, 'he and the three hundred men that were with him *were crossing over*, exhausted and famished'; the use of the Participle עֹבֵר being apparently intended to indicate that, *at the time when they were crossing*, they were in the condition described by 'עֵיפִים וְ'. This, however, is very unnatural. Mo. suggests that עָבַר, the Perfect, 'he crossed over,' was originally a marginal gloss, which, when transferred to the text, was forced into construction by pronouncing עֹבֵר.

* For שַׁלְמוֹנָע זֶל 'shadow' occurs in the sense 'shelter' in Jer. 48⁴⁵, Num. 14⁹, Ps. 91¹, *al.* For the vocalization זֶל, cf. בְּצִלָּאֵל Bēṣal'el, 'In the shelter of God.' On the Pural Participle מְנַע, with dropping of preformative מ, cf. G-K. § 52 s.

the kings of Midian.' 6. And the officers of Succoth said ׀, 'Are the hands of Zebaḥ and Šalmunna' now in thine hand, that we should give bread to thy host?' 7. And Gide'on said, 'Well then, when Yahweh hath given Zebaḥ and Šalmunna' into mine hand, I will thresh your flesh together with thorns of the desert and

modifications in jesting allusion to the fate of the kings as related in *vv.* 18 ff. Cf., for similar perversions, *notes* on Adoni-bezek, *ch.* 1⁶, and Cushan-rish'athaim, *ch.* 3⁸. The original forms of the names can hardly be conjectured. It is likely, however, that the first three consonants of Šalmunna, שַלְמ, embody the name of the god Šalm, who is known to us through inscriptions from Têma in North Arabia: cf. Nöldeke, *Berichte d. Berl. Akad.*, 1884, pp. 813 ff.; Baethgen, *Beiträge*, pp. 80 f.; *KAT.*³ pp. 475 f.; Cooke, *NSI.* pp. 195 ff.; La., *ÉRS.*² pp. 502 f.

6. *And the officers of Succoth said.* We must, of course, read plur. וְיֹאמְרוּ instead of the sing. וְיֹאמֵר in 𐤁.

7. *Well then.* Lit. 'Therefore'; i.e. 'Since you choose to adopt such an attitude.'

I will thresh your flesh together with, etc. The Heb. verb *dûš*, which is here used, means *to tread in threshing*; the operation of threshing being performed either by the feet of cattle, or by the threshing-drag (*môrāgh*) shod beneath with stone or basalt (cf. Isa. 41¹⁵, Am. 1³), which was weighted and dragged round the threshing-floor by oxen (cf. 2 Sam. 24²², Hos. 10¹¹), thus separating the grain and grinding the straw into chaff.* The equivalent Ar. verb *dûsa* is used generally in the sense *to trample* with the foot (e.g. of horses trampling on the slain), and also specifically of *threshing* grain, either by the feet of beasts, or by repeatedly drawing over it the *midwas* or threshing-drag (Lane). Bab. *dûšu* means *to tread down* or *crush*.

The preposition rendered 'together with' is אִתּ, which is always used of *accompaniment*, and never of the instrument. So 𐤁 renders correctly 'cum spinis tribulisque deserti'; שׁ ׀ חֲבֹן ׀ מִדְבָּר׀ 'upon thorns of the desert and upon briars'; ׀ על כובי מדברא ונ' *id.*

Thus Gide'on threatens that he will lay the men of Succoth 'naked upon a bed of thorns' (Mo.), and treat them as corn is treated in threshing, either by trampling them down or by drawing threshing-wains over them (cf. Am. 1³).

R.V. *text*, in rendering 'I will tear your flesh with the thorns, etc.,' commits the double error of giving to *dûš* a sense which (so far

* For illustration and description of the threshing-board as used at the present day in Syria and Palestine, cf. Driver, *Joel and Amos* (*Camb. Bib.*), pp. 227 f.

thistles.' 8. And he went up thence to Penuel, and spake unto them on this wise; and the men of Penuel answered him as the men of Succoth had answered. 9. And he spake also unto the men of Penuel, saying, 'When I return in safety, I will break down this tower.'

10. Now Zebaḥ and Šalmunna' were in ẖarkor, and their host was with them, about fifteen thousand men, even all that were left out of all the host of the children of the East: for they that had fallen were an hundred and twenty thousand men who drew sword. 11. And Gide'on went up 'towards' the track of

as we know) it never possesses, either in Heb. or in the cognate languages; and of rendering **אִתּוֹ** 'with' in an instrumental sense, as is done by **Ἐν ταῖς ἀκάνθαις κ.τ.λ.** In *v.* 16, which relates the carrying out of Gideon's threat, the words used are **וַיִּרְשׁ בָּהֶם** (on the emended verb, cf. *note ad loc.*); and here the **ב** might have an instrumental sense (**Ἐν αὐτοῖς**) if it were possible to explain the verb **דָּוֶשׁ** 'thresh' in the sense 'thrash' or 'flog,' the briars and thorns being used in place of a stick or flail. As we have seen, however, this form of threshing is never denoted by **דָּוֶשׁ**; the verb which denotes the *beating out* of corn with a stick being **חָבַא**: cf. *ch.* 6¹¹ *note*. We must explain **ב**, therefore, as meaning (like **אִתּוֹ**) 'together with,' a sense which this prep. possesses: cf. BDB. *sv.* **ב**, III. 1. *a*.

thistles. The precise meaning of Heb. *barḳānīm* is unknown; but the close connexion with *ḵôšê ham-midhbār*, 'thorns of the desert,' demands that the word should denote some kind of prickly plant. The explanation advocated by J. D. Michaelis, *Ges.*, *Thes.*, etc., threshing-sledges shod with *fire*-stones, is simple guess-work, depending upon a supposed connexion of the word with *bārāḳ*, 'lightning.'

10. *ẖarkor.* The site is unknown. Eusebius (*OS.* 272⁶²) identifies with *Karkaria*, one day's journey distant from Petra; but this seems too far to the south. On the other hand, the ẖarkar at which Shalmanešer III. met and defeated Bir-idri of Damascus and his allies (*KB.* i. pp. 172 f.; Rogers, *CP.* pp. 295 f.) must have been in the neighbourhood of Ḥamath, and would thus be much too far to the north.

they that had fallen, etc. The huge number is clearly the exaggeration of a late writer. The expression *šôlaph ḥérebh*, 'that drew sword,' is a favourite one in the part of the narrative of *ch.* 20 which is due to R^p, and where similar high figures are given: cf. *sv.* 2. 13, 17, 35, 46. Possibly, as Mo. suggests, the latter part of the verse may have been added by a redactor to harmonize 8^{10a} with 7^{23ff}.

11. *towards the track of the tent-dwellers.* Reading **דָּרְכָה יִשְׁכְּנֵי בְּאֵהָלִים**, with Bu., in place of **דָּרְכָה הַיִּשְׁכְּנֵי בְּאֵהָלִים**, which offers

the tent-dwellers¹, east of Nobah and Jogbehah : and he smote the host, whilst the host was careless. 12. And Zebah and Šalmunna² fled ; and he pursued after them, and captured the two kings of Midian, even Zebah and Šalmunna², but all the host he devoted to destruction¹. 13. And Gide'on the son of Joash

the grammatical solecisms of the Article with the Construct State, and the Passive Participle of the Stative verb which is elsewhere unknown. The track of the tent-dwellers was doubtless the beaten track running north and south by which the nomads were accustomed to travel—much like the modern *ḥaǧǧ*-route which runs from Damascus to Mecca. Gide'on, guessing that the fugitives would make for this track in order to escape southward, struck south-eastward from the Jordan valley until he reached it.

Nobah. According to Num. 32¹² J (cf. p. 51), Nobah, a clan of Manasseh, conquered Kēnāth and its dependencies, and called its name Nobah. Eusebius (*O.S.* 269¹⁵) says of Kēnāth that it is *εἰς ἔτι Καναθα λεγομένη*, . . . *κείται δὲ καὶ ἔτι καὶ νῦν ἐν Τραχώνι πλησίον Βοστρων*. He refers to the modern el-Ḳanawāt in the Ḥaurān ; but this seems much too remote to be the site intended in our passage : cf. *note* following.

Jogbehah. The name is preserved in the modern Ağbêhât, twenty miles east-south-east from the ford ed-Dâmiyyeh at which Gide'on seems to have crossed the Jordan.

careless. Heb. *bēṭah*, lit. 'confidence,' and so 'confident' of safety, the substantive being used, as often, in place of an adjective. Cf. *note* on *Yahweh shālôm*, *ch.* 6²⁴.

12. *he devoted to destruction*. Reading הִחָרִים, as conjectured by Scharfenberg (*apud* Mo., Ewald, etc., for הִחָרִיר, which can only mean (as rendered by R.V. *marg.*), 'he terrified,' and in illustration of which 2 Sam. 17², Ezek. 30⁹, are cited by Stu., and Zech. 2⁴ by Mo. This, however, is a very weak conclusion to the campaign. The mere throwing into a panic of Israel's mortal foes (for the *second* time in the course of the rout : cf. 7^{21.22}) cannot have been intended by the narrator : contrast the late narrative of Num. 31⁷ P, where every male of Midian is put to the sword. The corruption of הִ is an ancient one, being found in the Versions : \mathfrak{C}^B ἐξέστησεν, \mathfrak{F} 'turbato omni exercitu eorum,' \mathfrak{S}^P וָלַן, וָזַע. \mathfrak{C}^A ἐξέτριψεν, \mathfrak{C}^1 ἐξέστρεψεν, and similarly \mathfrak{S}^h וָסַפַּךְ, seem to be corrections of the reading of \mathfrak{C}^B in order to produce a sense more consonant with the context. Jos., however (*Ant.* v. vi. 5), must have read or understood the passage in accordance with our emendation ; for his paraphrase is ἀπαντας διέφθειρε τοὺς πολεμίους.

The correctness of הִחָרִים (rather than הִכָּחִיר, Ex. 23²³, Ps. 83⁵,

returned from the battle, [] 14. and captured a lad of the men of Succoth, and questioned him ; and he wrote down for him the officers of Succoth and the elders thereof, even seventy-seven men. 15. And he came unto the men of Succoth, and said, 'Behold Zebaḥ and Šalmunna', concerning whom ye did taunt me, saying, "Are the hands of Zebaḥ and Šalmunna' now in thy hand, that we should give bread to thy men that are exhausted?" 16. And he took the elders of the city, and thorns of the desert

as suggested by Mo., 'if an emendation is necessary') is attested by the doublet which is noted in *v.*¹³.

13. *returned from the battle.* H adds מִלְמַעְלָה הֶהָרִם, R.V. 'from the ascent of Heres.' These words have formed a puzzle to interpreters in all ages. The Versions treat the allusion either as topographical (E, S^v), or as a note of time, understanding חרם as the rare word for 'sun' (F, 'ante solis ortu' ; T, עַד לֹא מַעַל שֶׁמֶשׁ, 'before the sun had set'). Modern commentators suppose that the passage is intended to indicate that Gid'eon returned from battle by a different route ; and thus (it is assumed) took the town of Succoth by surprise.

It is astonishing that no one should have perceived that the words are simply a variant of *v.*^{12bβ}, which has come into the text from the margin. This may at once be seen if we write them below the original form of *v.*^{12bβ} :

וּכְלָהּ מַחֲנֵה הָחֵרֶם
מִלְמַעְלָה הֶהָרִם

It will be noticed that the last four letters of the doublet, הָחֵרֶם, tend to confirm the emendation הֶהָרִם which is adopted in *v.*^{12bβ}.

14. *he wrote down for him, etc.* A boy or youth captured by chance, and therefore (we may infer) without any exceptional qualifications as a scholar, writes down the names of the elders of Succoth ; probably scratching them with a sharp-pointed implement such as a pin or knife, in the alphabetic (so-called Phoenician) script, upon a fragment of shale or similar material. This may seem to us to be surprising, but need not be regarded as incredible. Cf. further *Additional note*, p. 253. The rendering of R.V. *text*, 'he described for him,' which seems to be intended to obviate the conclusion that the names were *written*, is absolutely unwarranted.

the officers of Succoth, and the elders thereof. The distinction between the officers, *sārīm* (mentioned alone in *v.*⁶), and the elders *š'kēnīm* (mentioned alone in *v.*¹⁶) is somewhat obscure. The *š'kēnīm* were the heads of families in whose authority the government of the city was vested. In distinction from these, the *sārīm* were probably concerned, not with civil government, but with military organization.

and thistles; and 'threshed' therewith the men of Succoth.
17. And the tower of Penuel he brake down, and slew the men

16. *and threshed therewith.* Reading וִירֶשׁ בָּהֶם, in place of וִירֶע בָּהֶם 'and taught therewith,' a somewhat strange expression in Heb.* The emendation is supported by the parallelism of *v.*⁷ וִירֶשֶׁתִּי 'I will thresh'; and by *Gr*^b καὶ ἡλόησεν (*v.*⁷ ἀλόησω), *Gr*^a καὶ κατέξανεν, 'and he carded' (*v.*⁷ καταξάνω). *Et* contrivit cum eis, atque comminuit' (*v.*⁷ 'conteram') may also have read וִירֶשׁ; but the double rendering of the verb suggests the possibility of a paraphrastic explanation of the curious וִירֶע of *℣*. In the same way, *S*^p סִפֵּן חֶסֶס 'and he tortured therewith' (but *v.*⁷ וִירֶשֶׁתִּי 'I will thresh'); וַתִּכַּר עֲלֵיהֶם 'and upon them he broke' (*var. lect.* וַנִּכַּר עֲלֵיהֶם 'and upon them he dragged') the men, etc. (but *v.*⁷ וִירֶשֶׁתִּי 'I will thresh'), may perhaps be paraphrases of *℣*.

We cannot, however, be sure that by this simple emendation we have arrived at the original form of the verse. *Gr* offers evidence of another original considerably different from *℣*. Thus the verse runs in *Gr*^L, καὶ ἔλαβε [τοὺς ἄρχοντας καὶ] τοὺς πρεσβυτέρους τῆς πόλεως καὶ κατεδίωξεν αὐτοὺς ἐν ταῖς ἀκάνθαις τῆς ἐρήμου καὶ ταῖς βαρκτηνεῖαι, [καὶ κατεδίωξαν ἐν αὐτοῖς ἄνδρας σοκχωθ]. So *Gr*^a, with κατέξανεν in place of κατεδίωξεν. *S*^b, *℣*^L are similar. Here we have bracketed τοὺς ἄρχοντας καὶ as a harmonistic addition (cf. *v.*¹⁴), and the last six words as a doublet embodying the *℣* tradition. The remainder seems to represent a Heb. original

וַיִּקַּח אֶת־יִזְקִי הָעִיר וַיִּרְשֶׁם אֶת־קוֹצֵי הַפְּדִדָּר וְאֶת־הַבְּרִקָּנִים

'And he took the elders of the city, and threshed them together with thorns of the desert and thistles.' This has strong claims to consideration as the original text. *℣*, 'And he took the elders of the city, and thorns,' etc., is certainly suspicious; and it is possible that the verb וִירֶשֶׁם may have fallen out before וְאֶת קוֹצֵי וְנ', and that *v.*^{16b} may have been added subsequently as an explanatory gloss.

17. *the tower of Penuel.* It may be inferred that the city was unwall'd, and the tower was intended as a refuge in case of danger. Cf. *ch.* 9^{46ff. 51ff.}

* Perhaps the nearest parallel to the usage of the verb וִירֶע in *℣* is 1 Sam. 14¹², where the Philistines, on spying Jonathan and his armour-bearer, say, 'Come up unto us, that we may teach you a thing' (וְנוֹרִיעָה אִתְּכֶם דָּבָר); if it is legitimate to explain this somewhat obscure expression as used with a touch of irony, 'give you a lesson,' or 'give you something to think about.' Here, however, we have the addition of the object דָּבָר; whereas a similar object is lacking in our passage.

of the city. 18. Then he said unto Zebaḥ and unto Šalmunna, 'Where are the men whom ye slew at Tabor?' And they said, 'As thou art so were they: 'e^lach resembled the children of a king.' 19. And he said, 'They were my brethren, my mother's sons: as Yahweh liveth, if ye had kept them alive, I would not have slain you.' 20. And he said to Jether his first-born, 'Arise, slay them!' But the lad drew not his sword, for he was afraid, because he was still a lad. 21. And Zebaḥ and Šalmunna said, 'Arise *thou* and fall upon us, for a man hath a man's strength.'

18. '*Where are the men, etc.*' Gide'on knows that the Midianite kings are responsible for his brothers' death; and he thus challenges them to produce them alive in order to save their own lives (cf. *v.* 19: so Bu.). The Midianites are aware that they are doomed, and, with the true savage instinct, glory in acknowledging the murders. Question and answer thus do not formally correspond; but *℣*, *℟*^p, R.V. 'What manner of men, etc.,' is both impossible as a rendering of אִיפֹה הָאֲנָשִׁים; and also very much weaker than the legitimate rendering. This latter consideration also tells against the emendation adopted by Mo. (*SBOT.*), La. מִי יִפְּאוּ הָאֲנָשִׁים 'Who, then, were the men, etc.?'

in Tabor. Mount Tabor, north of the plain of Esdraelon, is some thirty miles or more to the north of Shechem; near which, as we have seen (cf. *note* on 'Ophrah,' *ch.* 6⁸), the clan of Abi'ezer must have been situated. Bu. suggests an original תֵּבֶשׁ Tebeš: cf. *ch.* 9⁶⁰.

each. Reading לְאָחֵר for אָחֵר. Cf. Ex. 22²², Num. 15¹².

20. *he said to Jether, etc.* Robertson Smith (*Religion of the Semites*,² p. 417, *n*³) cites Nilus as stating that the Saracens charged lads with the execution of their captives.

but the lad drew not his sword, etc. It does not necessarily follow that Jether had taken part in the battle; for it is very probable that the captives were taken back in triumph to 'Ophrah before their execution. The arming of the lad with a sword may have been simply in view of the task assigned to him, which he had not the heart to perform when called upon to act.

21. *Arise thou.* The pronoun is emphatic; and the request of the Midianites, like their answer in *v.* 18, is a tribute to Gide'on's prowess and noble bearing.

a man has a man's strength. The rendering of Mo.; lit. 'as the man, (so) his strength.' כֵּן 'so,' or כֵּן, is exceptionally omitted. There is no doubt that Gide'on will slay them at a blow; whereas a mere lad might make a bungling attempt. *℣*^b reads ὅτι ὡς ἀνδρὸς ἡ

So Gide'on arose and slew Zebah and Šalmunna'. And he took the crescents which were upon the necks of their camels.

22. E² And the men of Israel said unto Gide'on, 'Rule over us, both thou, and thy son, and thy son's son; for thou hast saved us out of the hand of Midian.' 23. And Gide'on said unto them, 'I will not rule over you, neither shall my son rule over you; Yahweh shall rule over you.' 24. E And Gide'on said unto them, 'Let me make a request of you: give me every man the ear-rings of his spoil.' For they had golden ear-rings, because

δύναμις σου, *i.e.* בְּיָדְךָ כֹּחַ, which may possibly be original. Bu. emends בְּיָדְךָ אֶתָּה 'for thou art a mighty man.' This, though involving no great change of *℣*, hardly seems necessary.

crescents. Heb. *šah'rônîm* occurs once besides (Isa. 3¹) in a list of feminine ornaments. On the form, cf. G-K. § 86*g*. In Ar. *šahr* denotes the *new moon*; and Aram. *ših'rā*, Syr. *šahrā* mean *moon*. The crescents were doubtless threaded on necklaces, and worn as amulets. Similar strings of amulets are placed upon Bedawi camels and horses at the present day.

22. *the men of Israel.* The reference is to the tribes of Israel as a whole—or at least the central and northern west-Jordanic tribes, most of whom, according to the later narrative (E²), had borne a share in the campaign, and were benefited by its outcome. This, however, as we have seen, is not the conception of the old narrative J, which pictures Gide'on's *coup de main* as carried out with the assistance of his own clan merely, and invests its outcome with a local, rather than a general, importance. It is difficult to picture the haughty Ephraimites of J, *ch.* 8¹⁻³, who turn upon the victor in the hour of his triumph, and whose aggressive indignation has to be calmed by a diplomatic rejoinder, as taking part in a request to Gide'on to become their king because he had 'saved' them out of the hand of Midian. The older narrative of E seems to have agreed with J in making Gide'on's influence local rather than general. Cf. *introd.* to the story of Abimelech, p. 267.

23. '*I will not rule over you, etc.*' The conception of Theocracy here put forward belongs to the later eighth century stage of prophetic thought. Cf. the discussion on pp. 183 f.

24. *ear-rings.* Heb. *nīẓem* may denote an ear-ring (Gen. 35⁴ E, Ex. 32^{2,3} E, Prov. 25¹²), or a nose-ring (Gen. 24⁴⁷ J, Isa. 3²¹, Ezek. 16¹²). Here, as worn by men, the former is the more probable meaning, since (as Mo. notices) nose-rings appear in the O.T. only as the ornaments of women. Pliny (*Hist. Nat.* xi. 50) refers to the wearing of ear-rings by men in the East. The custom does not exist

they were Ishma'elites. 25. And they said, 'We will surely give them.' And they spread out a mantle, and cast therein every man the ear-rings of his spoil. 26. And the weight of the golden ear-rings which he requested was one thousand and seven hundred shekels of gold; beside the crescents, and the pendants, and the purple garments which were upon the kings of Midian, and beside the necklaces which were upon the necks of their camels. 27. And Gide'on used it for an Ephod, and

generally among the Bedawin at the present day; though Mackie states that, 'in the case of an only son, the ear-ring is sometimes worn as an amulet in the form of a large silver ring suspended round the outer ear, with discs or balls attached to the lower half of the ring, hanging visible below the lobe of the ear': *DB.* i. p. 633*b*.

they were Ishma'elites. Upon the interchange between the terms 'Midianite' and 'Ishma'elite,' cf. *note* on 'Midian,' *ch.* 6¹.

25. *they spread out.* ע, ש, 'he spread out.' So Kit., No., La., Gress.

26. *one thousand and seven hundred shekels of gold.* Taking the weight of the heavy shekel at 252.5 grs. troy (cf. G. F. Hill in *EB.* 4444), the total weight of the golden ear-rings would be nearly 75 lbs. If reckoned by the light shekel, it would be about half as much.

beside the crescents, etc. Mo. regards the whole of this half-verse as an editorial addition, on the ground that 'this catalogue of things which were not used in making the *ēphōd* is quite superfluous, and only interrupts the narrative.' A similar view is taken by Wellh. and Sta., who, taking *v*^{21*b*} as part of the original narrative, find in it the origin of the later addition *v*^{26*b*}. On the other hand, Bu. takes the last quarter of the verse, 'beside the necklaces, etc.,' to be genuine, supposing it to be the origin of *v*^{21*b*}, which he regards as a later gloss.

It is unsafe to express a definite opinion on such a point. The narrative of E in *vv.* 22-27 has, as we have seen, been worked over by E²; but it is difficult to divine any *purpose* in such an editorial addition as this (whether by E² or some later hand), beyond the desire to glorify Gide'on's exploit, which may equally have been present in the mind of the original narrator. The half-verse may seem to *us* to interrupt the proper sequence between *v*^{26*a*} and *v*²⁷; but would this fact have counted for much in the mind of a narrator who was fascinated by the richness and variety of the spoil, as reported by tradition?

27. *an Ephod.* As regards the nature of the Ephod, evidence is extremely vague; and it is even doubtful whether it was everywhere and at all times the same thing. The Ephod of the Priestly Code (*i.e.* of post-exilic, though probably also of earlier, times) is described (Ex. 28 P) as a decorated vestment, apparently of the nature of an

apron,* fastened partly by a band at the top round the body (חֵטֶב אֶפְדּוֹתוֹ אֵיטָר עָלָיו) 'the band of its attachment which is above it,' † v.⁸), and partly by two shoulder-straps (כְּתֻפּוֹת, v.⁷). These latter were probably intended to keep the band of the Ephod in a position round the wearer's middle well above the loins, and thus to obviate the possibility of its becoming contaminated with sweat. § The shoulder-straps appear to have been joined to the apron at its two upper corners; || and their upper ends may have been fastened to the shoulders of the *m'it* (see below) by the two onyx-stones in filigree settings (v.⁹⁻¹²), which very likely served the purpose of brooches. It is possible, however, that the stones were merely ornamental and symbolical; and, if so, the shoulder-pieces may have

* The older view regarded the Ephod of P as a kind of waistcoat; but this seems to be excluded by the position of the band of its attachment עָלָיו 'above it' (v.⁸), rather than 'upon it'; and likewise by the position of the pouch *above* (עַל) the band (v.²⁸)—scarcely *upon* it. The position of the rings which fastened the pouch to the Ephod—the two upper ones attached to the shoulder-straps, and the two lower ones above the band of the Ephod—favours the same conclusion.

The view that the Ephod was of the nature of an *apron* rather than a *kilt*, i.e. that it covered the front of the trunk below the waist and did not extend round the body and join at the back, depends upon the emendation noticed in *footnote* ||.

‡ This rendering assumes the view that *hēsebh* is a metathesis of *hēbheš* from *hābhaš* 'to bind on'; so, 'band.' Cf. Driver's *note ad loc.* in *Camb. Bib.* The sense 'attachment' given to 'āphuidā makes the term a secondary derivative from the denominative verb 'āphaāh 'to attach the Ephod,' which is used in Ex. 29⁵, Lev. 8⁷ (|| *hāghar* 'gird on').

§ The very curiously phrased injunction in Ezek. 44^{18b} לֹא יִחְבְּרוּ בִיזוּעַ, i.e., apparently, 'they shall not gird themselves with (or in) sweat,' which is understood by R.V. to mean 'with *that which causeth* sweat' (i.e. with woollen materials in distinction from linen), was understood by the Jewish interpreters to mean that they were prohibited from girding themselves as high as the arm-pits or as low as the loins—either position being conducive to sweating—but were to adopt an intermediate position. So Rashi and Kimchi. This interpretation is as old as T^J, which paraphrases the passage וְלֹא יִרְוּנוּ עַל חֲרִיצִיהֶן אֱלֵהֵן 'and they shall not gird themselves about their loins, but shall bind themselves about their hearts.' It may well be doubted whether the passage (the genuineness of which is open to suspicion) is capable of such an explanation; yet it is quite likely that the interpretation depends upon a true tradition as to the ritual position of girding, and the reason by which it was dictated.

|| In Ex. 28⁷ we should read plural verbs יִחְבְּרוּ, יִהְיוּ, referring to the two shoulder-straps, in place of the singulars יִחְבֵּר, יִהְיֶה of B. Cf. ὁ δύο ἐπωμίδες συνελχόνσαι ἔσονται αὐτῶ ἐτέρᾳ τῇ ἐτέρᾳ, ἐπὶ τοῖς δυνσὶ μέρεσιν ἐξηκτισμέναι. On the use of the masc. form of the 3rd plur. Imperfect, in place of the fem., with reference to a fem. subject preceding, cf. G-K. § 145 u.

been joined together at the back of the neck so as to form a yoke ; or else they may have joined the band of the Ephod at the back, and held it up like braces.

The Ephod is mentioned in connexion with the pouch (חֶשֶׁן, A.V., R.V. 'breast-plate,' *צִי*¹⁵), which contained the objects known as Urim and Tummim. This latter was fastened by rings at its four corners, the two upper rings to the shoulder-straps (*צִי*²³⁻²⁵), and the two lower to the band of the Ephod (*צִי*²⁶⁻²⁸). The dimensions of the pouch were a span, *i.e.* about nine inches, square (*צִי*¹⁶) ; and when the Ephod was in place, the Urim and Tummim within the pouch lay upon the heart of the high priest (*צִי*³⁰)—a fact which makes it clear that the band of the Ephod must have been well above the loins, as has already been indicated.

The material of Ephod, band, and pouch alike, and doubtless also of the shoulder-straps, was of 'blue, and purple, and scarlet, and fine twined linen,' interwoven with gold thread or wire (פְּתִילִים), which was cut from a plate of beaten gold (*ch.* 39³). The pouch was further adorned by twelve precious stones, set in gold (*צִי*¹⁷⁻²¹). The Ephod was girded on over the *mē'il*, a long garment with sleeves, of blue material (*צִי*^{31 ff.}).

Probably similar to this Ephod in form, though doubtless of simpler workmanship, and (so far as we know) unconnected with any special means of obtaining an oracle,* was the *'ēphôdh badh* 'Ephod of linen,' ‡ with which the child Samuel was 'girt' (הִגִּיר) when he ministered as a temple-servant (1 Sam. 2¹⁸) ; and with which King David was similarly 'girt,' when he danced ceremonially before the Ark, whilst it was being brought up from the house of 'Obed-edom to the sanctuary at Jerusalem (2 Sam. 6¹⁴). On this occasion David excited the outspoken contempt of his wife Michal, for exposing his

* There must, no doubt, have been some ultimate connexion between the *'ēphôdh badh* and the oracular Ephod noticed above in the next paragraph ; and it is possible that the former may have been a kind of 'dummy' Ephod, typical of the relationship in which those who exercised priestly service stood towards the Deity, though actually unequipped with the means of casting lots (Urim and Tummim). Foote recalls the fact that the oracular lots in the temple of Fortuna at Praeneste were mingled and drawn by a child ('quid igitur in his [sortibus] potest esse certi, quae Fortunae monitu pueri manu miscentur atque ducuntur' ; Cicero, *De Divinatione*, ii. 41, 86 : a similar practice is observed in the modern State-lotteries of Italy and France), and thinks that the child Samuel may have been entrusted with a similar office. There is, however, absolutely no evidence of any such practice among the Israelites.

‡ The derivation of *badh* is unknown ; but the view that it denotes the *material* of which the Ephod was made, and that this was some form of *linen*, is probably correct. Foote's theory that *badh* means 'member,' and so *membrum virile*, which the Ephod (the primitive loin-cloth) was designed to cover, is sufficiently refuted by Lev. 16⁴, where the word is applied to the various parts of the priestly attire, turban included, and evidently describes their *material*.

person 'like one of the lewd fellows'; and the inference is that he wore nothing but the Ephod, and that this was of scanty dimensions *—perhaps not unlike the apron which the Egyptian priest Pe-nhēsi is represented as wearing, when performing an act of ceremonial worship; cf. Perrot et Chipiez, *Histoire de l'Art dans l'Antiquité*, i. p. 253.† Sellin and Mo. (*EB*. 1306) suppose that the assumption of this scanty attire may have been a return to a primitive costume rendered sacred by its antiquity; much as Mohammedan pilgrims, so soon as they approach Mecca, are obliged to adopt the simple loin-cloth which was the primitive dress of the Arabs. §

More doubt has been expressed as to the precise nature of the Ephod which, in the days of 'Eli, Saul, and David, was regularly employed in the cultus of Yahweh. The priest is never said to *wear* or to *be girt* with this, but always to *bear* it (נָשָׂא; 1 Sam. 2²⁸, 14³, 22¹⁸ ||). Abiathar, when he escapes from the slaughter of the priests at Nob, comes down to David with an Ephod 'in his hand' (1 Sam. 23⁶). ¶ Here 'in his hand' refers to the carrying of the Ephod when not in use; but the verb 'bear' is clearly used ceremonially, and is most naturally to be explained from the use of the same verb in Ex. 28¹², where it is said that Aaron 'shall bear' (נָשָׂא) the names of the children of Israel before Yahweh engraved upon the stones of the two shoulder-straps of the Ephod; and similarly (v. 29) that he 'shall bear' their names upon the pouch. We learn from 1 Sam. 23⁶ that the Ephod was used in consulting the oracle, or 'enquiring of Yahweh'; and from 1 Sam. 14 it seems, as in later times, to have been employed in connexion with Urim and Tummim (in v. 18 אֲבִי־אֵל preserves the true reading 'Ephod' in place of

* The Chronicler (who was evidently somewhat scandalized by the narrative as it stands in 2 Sam.) clothes David in a *m^ul būṣ* 'robe of byssus,' in addition to the Ephod of linen, and omits all allusion to the episode in which Michal plays a part (1 Chr. 15²⁷).

‡ It is worthy of note that Pe-nhēsi's apron is loosely girt well above the loins, being apparently supported in that position by a band from the shoulders.

§ In the description given by the Roman lawyer Gaius (iii. 192-193) of the house-search for stolen articles—'furtum licio et lance conceptum'—the leather apron, 'licium' ('consuevit genus quo necessariae partes tegerentur') is explained by Ihering as a relic of antiquity—the usual dress of the ancient Aryans—preserved in a ceremonial institution dating from hoary antiquity. Cf. *The Evolution of the Aryan*, pp. 2 ff.

|| This last passage, as it stands in 19, speaks of 'bearing the Ephod of linen'; but it is not improbable that the word *badh*, which is omitted by 20^B, is an erroneous insertion.

¶ The passage is in some slight disorder. As it stands in 19, אֶפֶד יָרַד בְּיָדוֹ seems to mean 'an Ephod came down in his hand.' 20^B, however, after the words 'unto David,' presupposes a text יָרַד וְאֶפֶד בְּיָדוֹ 'he went down with David to Kē'ilah, having an Ephod in his hand.' This is very possibly the original text: cf. Driver, *NHTS*,² *ad loc.*

אֲרֹן 'Ark of God'). When asked to consult the oracle, the priest is told to *bring it near* (הֵנִי־יָטָה, 14¹⁸, 23⁹, 30⁷); and, when ordered to desist, the command is 'withdraw thine hand' (אַפֶּסֶף יָדְךָ, 14¹⁹), which seems to presuppose some form of manipulation in connexion with the sacred lot. The *locus classicus* for the use of this latter (Urim and Tummim) is 1 Sam. 14⁴¹ עַל, which has already been noticed under *ch.* 1¹ *note* on 'enquired of Yahweh.' Thus, if we are to explain the Ephod of 1 Sam. by the Ephod of P, it may have been the receptacle in which the sacred lot was preserved—possibly a pouch and apron or girdle combined—the prototype of the later priestly vestment.

The character of Gide'on's Ephod has formed subject for much discussion. It is commonly supposed that the description of *v.* 27 can only be satisfied by the supposition that here the Ephod denotes some kind of *idol*, and not simply a vestment and pouch employed in consulting the oracle. In favour of this view the following points have been alleged.

If the words וַיַּעַשׂ אוֹתוֹ גִּדְעוֹן לְאֶפֶד mean that Gide'on *made* the 1700 shekels of gold *into* an Ephod, it seems to follow that the Ephod must have been something of the character of an idol, or possibly an non-eikonic symbol (ξόανον) of considerable size; since so great a weight of metal cannot have been employed in the manufacture of a mere belt and apron, with pouch attached, even if we suppose these to have been heavily overlaid with gold. The verb וַיַּצַּב, again, rendered 'and he set it up,' suggests an idol rather than an instrument of divination which, when in use, was girt on to the body of the priest. Further, the strong terms of reprobation employed by the writer—'and all Israel went a whoring after it, etc.'—though appropriate in application to the worship of an idol, seem rather strange if they are to be understood of an object which is mentioned, without a word of blame, as commonly employed in ascertaining the oracle of Yahweh in the days of Samuel and David, and the continued use of which in post-exilic times is specifically provided for in the ritual enactments of the Priestly Code.

Added to the arguments based upon the reference to Gide'on's Ephod, there are other references which have been thought to point in the same direction. The story of Micah and his private sanctuary, Judg. 17.18, is clearly composite in origin; and the Ephod and Teraphim of the one narrative are parallel to the graven image and molten image of the other—or rather to the graven image only, the molten image being a later addition. In 1 Sam. 21¹⁰ the sword of Goliath is preserved in the sanctuary of Nob 'wrapped in a cloth behind the Ephod'—a reference which may be taken to mean that the Ephod stood by itself, clear of the wall, as an image would do. Lastly, the obscure phrase of Isa. 30²² (probably a late passage), אֶפְסַת מִסַּכַּת זָהָב, R.V. 'the plating of thy molten images of gold,

is parallel to כְּפָדָה 'עֲפֹדֹתֶיךָ כְּפָדָה' 'the overlaying of thy graven images of silver'; the term 'āphuddā (cognate to 'ēphōd) being interpreted by R.V. as 'plating' owing to its parallelism with šippūy 'overlaying' (for which cf. Ex. 38^{17,19}, Num. 17^{3,4}). If, then, 'āphuddā means the 'plating' of an idol, it is inferred that 'ēphōd denotes such a plated idol, *i.e.* a wooden idol overlaid with metal.

Taking these points in order—it should be observed that, while the phrase עָשָׂה ל may be used in the sense 'he made into' (cf. especially Isa. 44¹⁷ וַיִּשְׁאַרְתוּ לְאֵל עֲשָׂה 'and the remnant thereof he made into a god'; so v. 19; cf. also Deut. 9¹⁴, Ezek. 4⁹), it may equally well have the sense 'he used for.' This is the sense of the phrase in 1 Sam. 8¹⁶, 'Your servants, etc., shall he take and use them for his work'; Ex. 38²⁴, 'All the gold that was used for the work'; Ezek. 15⁶, 'It (the wood of the vine) cannot be used for work.' Similarly, in Hos. 2⁸ (וְ¹⁰), עֲשֹׂה לְבַעַל זָהָב is more naturally to be rendered 'the gold which they used for the Ba'al' (*i.e.* in his service) than 'the gold which they made into the Ba'al'; הַבַּעַל by itself being nowhere else used of the *image* of the false god. Thus, the rendering of the phrase which is adopted in our translation is at any rate quite legitimate; the statement being understood to mean that Gid'eon used the gold not merely in the manufacture of the Ephod, but also in the provision of such accessories as were necessary for its proper maintenance as a cultus-object, *i.e.* a sanctuary and priestly caretaker, etc.

The verb וַיִּצַּב, whether rendered 'he set it up,' or, as above, 'he established it' (cf. Am. 5¹⁵ וַיִּצַּב בִּשְׁעָרֵי מִשְׁפָּט 'establish judgment in the gate'), need not imply that the Ephod was an image; since, upon the alternative assumption that it was, here as elsewhere, a vestment employed in ascertaining the will of the oracle, it is not clear what other verb could have been more suitably employed to describe the fact that it was kept and used in divination at 'Ophrah. What the writer wishes to express is that it was there that the Ephod-cult was 'established'; and any alternative expression, such as 'he placed' or 'kept it at 'Ophrah,' would scarcely have been possible.

The strong reprobation of the Ephod-cult is explained by the fact that the passage comes from E²; whereas the passages in 1 Sam. which seem to regard the Ephod as the natural and appropriate means of ascertaining the will of Yahweh, belong to the much older narrative of J. The difference in point of view is no greater here than in the two accounts of the institution of the kingship; where, while J regards the granting of a king as a mark of Yahweh's favour to Israel (1 Sam. 9^{15,16}), E², on the other hand, stigmatizes Israel's

demand for a king as a definite act of rejection of Yahweh (1 Sam. 8⁷). It is at least probable, if not certain, that the prophetic school represented by E² grouped the Ephod with other conventional forms of divination, and regarded it with disfavour; and Hosea, whose influence is to be traced in E² (cf. *Introd.* p. xlv), makes disparaging reference to Ephod together with Teraphim (Hos. 3⁴). It is generally acknowledged that in 1 Sam. 14¹⁸ the original form of the passage is preserved in \mathfrak{C} :—καὶ εἶπεν Σαουλ τῷ Αχεία Προσάγαγε τὸ εφουδ' ὅτι αὐτὸς ἤρην τὸ εφουδ ἐν τῇ ἡμέρᾳ ἐκείνῃ ἐνώπιον Ἰσραηλ. In \mathfrak{H} , however, אֲרֹן הָאֱלֹהִים, 'the Ark of God' has taken the place of 'the Ephod'—

an alteration which must have been purposely made, and that most probably in order to avoid reference to the consultation of the will of Yahweh by a form of divination which the corrector of the text regarded with some disfavour. The fact that, in post-exilic times, the Priestly Code lays down detailed regulations for the manufacture and use of the Ephod is not an argument to prove that in late pre-exilic times the school of E² could not have disapproved of its use. Rather, we may argue that, if P had supposed that the term Ephod had at any time been used of a definitely idolatrous symbol, such a term would not have been perpetuated by the Code in reference to a legitimate instrument of divination. The evidence of the Priestly Code, therefore, tells in favour of the inference that the codifiers of this body of legislation were unaware that the term 'Ephod' had been applied in early times to an idol.

The fact that, in Judg. 17.18, one narrative equips Micah's sanctuary with Ephod and Teraphim, while the parallel narrative speaks of a graven image merely, is no argument to prove that the graven image was the same as the Ephod. Nor would the case really be strengthened if the second narrative had originally mentioned (as it does now) both graven image and molten image; since there is no reason whatever for supposing that the two traditions were so absolutely at one that graven image and molten image must denote *the same things* as Ephod and Teraphim. As Mo. has shown, however, the molten image is a late addition to the narrative.

In 1 Sam. 21¹⁰ the statement that the sword of Goliath at the sanctuary of Nob was 'wrapped in a cloth behind the Ephod' may very well mean that both sword and Ephod were hanging on a large peg fixed in the wall (Lotz, Foote, Sellin), the Ephod, as being constantly in use, hanging outermost.

Lastly, the interpretation of אֲפֻדַּת מִסְכָּה זָהָב in Isa. 30²² is very obscure: but on any interpretation the phrase can scarcely carry much weight in proof that the term Ephod was ever applied to an idol. Foote argues that מִסְכָּה never means 'molten image' where, as here, it is a genitive. It means a 'casting'; and as a genitive it means that the *nomen regens* is not carved, nor beaten, but cast.

established it in his city, even in 'Ophrah; ^{E2} and all Israel went a whoring after it there, and it became a snare to Gide'on and to his house. 28. ^{RE2} So Midian was subdued before the sons of Israel, and they lifted up their head no more. And the land had rest forty years in the days of Gide'on.

This conclusion is supported by such phrases as עֲנֵל מִסְכָּה, lit. 'bull of casting,' i.e. 'cast or molten bull'; אֱלֹהֵי מִסְכָּה 'gods of casting,' i.e. 'molten gods.' Thus, אֶפְדֹת מִסְכַת זָהָב might mean 'thy cast band of gold,' lit. 'the band (attachment) of the casting of thy gold.' It may be considered doubtful whether the parallelism of כְּסִפֵי כֶסֶף 'thy graven images of silver,' does not tell against Foote's conclusion, and compel us to explain זָהָב מִסְכַת as 'thy molten image of gold.' But even so, it is likely that אֶפְדֹת has the same meaning here as in Ex. 28⁸, viz. 'attachment' or 'band,' and thus refers to the priestly band or vestment which was in this case worn by the idol, and not to an actual part of the idol, such as a metal sheathing—a sense which is purely hypothetical.

We conclude then that, while the reference to Gide'on's Ephod is involved in considerable difficulty, there is nothing in the statement, nor in other statements which we have noticed, to compel us to believe that it was an idol, or anything else but the ordinary priestly vestment which was employed in obtaining an oracle.

The explanation of the Ephod here adopted follows, in the main, the lines laid down by Lotz, *Realencyklopädie für protestantische Theologie und Kirche*, 1898, v. pp. 402-406; Foote, *JBL.*, 1902, pp. 1-47; Sellin, *Das israelitische Ephod* (*Orient. Studien T. Nöldeke gewidmet*, 1906, pp. 699-717): cf. also the brief summary given by Benzinger, *Hebräische Archäologie*,² pp. 347 f.

went a whoring. Cf. ch. 2¹⁷ note.

a snare. Heb. *môkēš*. Cf. ch. 2³ note.

28. On the characteristic phraseology of ^{RE2}, cf. *Introd.* p. xlviii.

YAHWEH OR YAHU ORIGINALLY AN AMORITE DEITY

(Cf. note on 'the Ashera,' ch. 6²⁵.)

Sayce was the first to call attention (*ET.* ix. p. 522) to the existence of the name *Ya-u-um-ilu* on a Babylonian text of the First Dynasty period (published in *CT.* iv. 27). This can scarcely mean anything else than 'Ya-u is god'; and is thus identical in form and meaning

with the Hebrew יוֹאֵל Jo'el. Sayce's conclusion was accepted by Hommel, who further cited the name *Ha-li-pi-um*, i.e., probably, *Ha-li-ya-um*,* 'Ya-u is maternal uncle' (Ar. *hāl*), as occurring in a document of the same period (*ET*. x. p. 42: the list in which *Ha-li-ya-um* occurs is published in *CT*. iv. 27). *Ya-u-um-ilu* was subsequently cited by Delitzsch, together with the two forms *Ya-a'-we-ilu*, *Ya-we-ilu* (which he explained as meaning 'Yahweh is God') in proof of the recognition and worship of the God Yahweh in Babylonia in early times (*Babel und Bibel*, pp. 46 f.). Upon this evidence Delitzsch based much too far-reaching assumptions as to the derivation of Hebrew monotheism from Babylonian sources; and his conclusions excited a keen and voluminous controversy.† In particular, his reading of the names *Ya'-a-we-ilu*, *Ya-we-ilu* was hotly disputed, upon the ground that the syllable which he read as WE might be interpreted as PI, and that the first element of the names *Ya'-a-pi* or *Ya-pi* was probably a verbal form. Early Babylonian usage favours the reading WE or WA for the disputed syllable rather than PI; yet, even so, it is by no means certain that the element *Ya'-a-we*, *Ya-we* in the names in question is a divine name and not a verbal form. Thus Ranke, who transcribes *Ya'-ah-wi-ilu*, takes the meaning to be '(The) god lives' (assuming an Amorite verb חיה = Heb. חָיָה 'to live'); while Hilprecht, reading *Ya'-wi-ilu*, understands as 'God has spoken' (Bab. *awû* or *amû* 'to speak'; but in this case the normal Babylonian form would be *êwi*, *êmi*, not *ya'wi*).§ More recently, the publication by Thureau-Dangin of the First Dynasty tablets preserved in the Louvre|| reveals the existence of the name *Ya-wi* (*we*, *wa*, *pi*?)-(ilu)-*Dagan*¶; and association with the name of the deity Dagan greatly strengthens the case for regarding the disputed form as a verb—the only alternative being to suppose that the name identifies a deity *Ya-wi* with the deity *Dagan*: cf. the compounds Hadad-Rimmon, Zech. 12¹¹, and the Moabite 'Ashtar-Chemosh (*Moabite Stone*, l. 17). It is thus evident that the names *Ya'-a-we-ilu*, *Ya-we-ilu* cannot be cited with any probability as instances of compounds containing the divine name Yahweh.

Clay's publication of *Personal Names of the Cassite Period* (1912), i.e. the period subsequent to the First Dynasty period, ranging from *cir.* B.C. 1760 to 1185, throws further light upon the use of the divine

* The cuneiform sign-group, which has the syllabic value PI in Assyrian documents of a later period, is commonly used with the value WE, WA, and YA in Babylonian documents of the First Dynasty period, and later still into the period of the T. A. Letters (*cir.* B.C. 1400). For *Ha-li-ya-um* with the common sign for YA, cf. p. 245 (from Thureau-Dangin, *op. cit. infra*, p. 22).

† For the literature of this controversy, cf. Rogers, *Relig. Bab. and Assy.* p. 92.

§ Cf. Ranke, *Early Bab. Personal Names of the Hammurabi Dynasty*, 1905.

|| *Lettres et contrats de l'époque de la Première Dynastie Babylonienne*, 1910.

¶ *Op. cit.* p. 23. The occurrence of this name and its bearing on the controversy were first brought to the notice of the present writer by Dr. R. W. Rogers.

name *Ya-u* in Babylonia. He chronicles the forms *Ya-a-u*, *Ya-u-ba-ni*, *Ya-u-gu*, and the apparently feminine forms *Ya-(a-)u-tum*, *Ya-a-i-tum*. *Ya-u-ba-ni* can only mean 'Ya-u is creator,' the form being precisely analogous to *Ilu-ba-ni*, 'The god is creator,' *Ellil-ba-ni*, 'Ellil is creator,' etc. The form *Ya-u-ba-ni* recalls the familiar name of the king of Hamath who was contemporary with Sargon (B.C. 721-705), (*ilu*) *Ya-u-bi²-di* (Winckler, *Sargon*, pp. 102, 178), *Ya-u-bi²-di* (*id.* p. 170), which alternates with *I-lu-bi²-di* (*id.* p. 6), just as in Hebrew we find both יהוה and אלהים. Here *Ya-u* is marked by the determinative prefix *ilu*, 'god,' which proves beyond a doubt that it is a divine name. The element *Ya-u*, as the first element of a proper name, appears in *Ya-u-ha-si*, the Assyrian equivalent of the Heb. Jeho'ahaz, i.e. the Judæan king 'Aḥaz, in an inscription of Tiglath-pileser IV. (cf. Rost, *Tiglath-pileser*, p. 72). Cf. The form *Ya-u-a* which occurs as the representation of the name of the Israelite king Jehu, in the inscriptions of Shalmaneser III. (cf. *AB.* i. pp. 140, n¹, 150). The shortening of *Ya-u* into *Ya* as the first element of a proper name is seen in *Ya-ma-e-ra-aḥ*, i.e. 'Ya indeed is the moon,' *CT.* viii. 17.

In face of this evidence, it is impossible to doubt that *Ya-u* or *Ya-um* (with mîmation) is a divine name, and corresponds to the Heb. —יה or —י, the shorter form of the divine name Yahweh, which regularly occurs as the first element in Israelite proper names. On the form *Ya-u-tum*, cf. p. 248.

We find, moreover, a large class of proper names occurring in Babylonian documents of the First Dynasty and Kassite periods in which the *second element* of the name is *Ya*, *Ya-u-a* (once), *Ya-tum*, *Ya-u-tum*, *Ya-u-ti*; the names themselves being precisely parallel in form to other names in which the second element is indisputably the name or title of a deity.

Thus, where the relation is that of a genitive following a Construct State, we may notice *A-pil-ya*, *A-pil-ya-tum*, apparently 'son of Ya or Yatum,' like *A-pil-i-li-šu*, 'son of his god.'

Ardi-ya, *Ardi-ya-um*, apparently 'servant of Ya or Ya-um,' like *Ardi-ilâni*, 'servant of the gods'; *Ardi-(ilu)-Marduk*, 'servant of (god) Marduk'; *Ardi-Šamaš*, 'servant of Šamaš,' etc.

Nûr-ya-u-ti, apparently 'light of Ya-u-tu,' like *Nûr-Ellil*, 'light of Ellil'; *Nûr-Ištar*, *Nûr-Marduk*, etc.

Cases in which the relation to a preceding substantive is predicative, the copula being understood, are:—

A-bi-ya, *A-bi-ya-tum*, *A-bi-ya-u-ti*, apparently 'Ya or Ya-tum or Ya-u-tu is father,' like *A-bi-ilu*, '(the) god is father'; *A-bi-i-li*, 'my god is father'; *A-bi-i-li-šu*, 'his god is father'; *A-bi-e-ra-aḥ*, 'the moon is father,' etc.

Ha-li-ya-um, *Ha-li-ya-tum*, apparently 'Ya-um or Ya-tum is maternal uncle.'

Be-li-ya, *Be-li-ya-tum*, *Be-li-ya-u-tum*, apparently 'Ya or Ya-tum or Ya-u-tum is lord,' like *Be-li-a-bi*, 'my father is lord.'

Šili-ya, *Šili-ya-u-tum*, apparently 'Ya or Ya-u-tum is my protection' (lit. 'shadow'; cf. Heb. בְּצֵלֵי יְהוָה, 'In the shadow of God'), like *Šili-Addu*, 'Addu is my protection'; *Šili-(ilu)-Amurru*, *Šili-(ilu)-Dagan*, *Šili-Marduk*, *Šili-Šamaš*, *Šili-Ištar*, etc.

Tukulti-ya-u-ti, apparently 'Ya-u-tu is my help,' like *Tukulti-Ellil*, 'Ellil is my help,' etc.

It is doubtful whether *A-ḫi-ya*, *A-ḫi-ya-u-a*, *Aḫ-i-ya-tum*, *A-ḫi-ya-u-ti*, like *A-ḫi-ilu* (or *-ili*), should fall into the first or second of these classes. *A-ḫi-ya* might mean 'Ya is brother,' or 'brother of Ya,' just as *A-ḫi-ilu* might mean '(the) god is brother,' or (taking the ideogram for 'god' as the genitive *ili*), 'brother of (the) god.' In favour of the latter supposition we may cite the fem. name *A-ḫa-ti-ya*, presumably 'sister of Ya'; scarcely 'Ya is sister.' Cf. masc. *E-ri-ši-ya*, 'bridegroom of Ya,' beside the fem. names *E-ri-iš-ti-(ilu)-A-a*, 'bride of (god) A-a'; *E-ri-iš-ti-Addu*, 'bride of Addu'; and Phoenician חמלך 'brother of Milk,' אחמלך 'sister of Milk,' חמלקרת 'sister of Melkart.'

A third class, in which the first element of the name is a verbal form, is represented by *I-din-ya*, *I-din-ya-tum*, apparently 'Ya or Ya-tum has given,' like *I-din-ili-šu*, 'his god has given'; *I-din-Marduk*, 'Marduk has given'; *I-din-(ilu)-Amurru*, *I-din-Sin*, etc.

It must be admitted that the explanation of *-ya*, *-ya-tum*, etc., as divine names is not generally accepted, some scholars (e.g. Ranke and Clay) explaining them as hypocoristic terminations in substitution for some fuller and more definite form (*Ardi-ya* thus conceivably implying *Ardi-(ilu)-Marduk*, or *-(ilu)-Sin*, etc.). Against this view, and in favour of that which is here advocated, the following points may be made:—

(1) In cases in which *Ya-u*, *Ya-u-um* occur as the *first element* in a proper name (as in *Ya-u-ba-ni*, (*ilu*) *Ya-u-bi'-di*, *Ya-u-um-ilu* above cited), the hypocoristic explanation breaks down; it being impossible to explain *Ya-u* as anything else than a divine name or title. If, then, as has been shown, names ending in *-ya*, etc., are identical in formation with names containing as their second element the name of a god such as Marduk, Sin, Šamaš, etc., it is reasonable to infer that *-ya* as the second element of these names denotes the same deity as *Ya-u* when occurring as the first element in other names. In fact, as we have seen, the full form *A-ḫi-ya-u-a* occurs side by side with *A-ḫi-ya*. That *Ya-u*, when occurring as the second element in a proper name, should normally be shortened to *-ya* is precisely analogous to the usage of Hebrew proper names containing the divine name יְהוָה— (as well as יְהוֹה)— as the second element, answering to יְהוֹה־, יְהוֹה־ as the first element. And further, an

instance of such shortening when *Ya* is the *first* element is seen in *Ya-ma-e-ra-ah*, assuming this to mean 'Ya indeed is the moon.'

(2) The forms *A-bi-ya*, *A-ḥi-ya*, *Be-li-ya* are identical in all respects with the Hebrew אֲבִיָּה, אֲחִיָּה, בַּעֲלִיָּה. אֲבִיָּה, אֲחִיָּה are variations of the fuller forms אֲבִיָּהוּ, אֲחִיָּהוּ; and the fact that in these Hebrew names the element *Ya* or *Yahu* is a divine name corresponding to the fuller form *Yahweh* is generally admitted.* It is difficult, therefore, to believe that the identity in form of the Babylonian names is accidental, and does not involve identity of meaning.

(3) The name *A-ḥi-ya-mi* occurs in a Babylonian letter from Ta'anach of *cir.* B.C. 1450 (cf. Rogers, *CP.* p. 282; *TB.* i. p. 129), borne by the Amorite writer of the letter. Here the element *-mi* is probably not to be understood as equivalent to *-wi*, as has been supposed. *Ya-wi* thus answering to *Yahweh*; but more probably *-mi* is the Babylonian enclitic particle which is regularly employed in letters of this period from Canaan in place of the normal enclitic *-ma*. The purpose of the enclitic, thus used, is to predicate a fact with some emphasis. Thus *A-ḥi-ya-mi* would denote 'Ya indeed is brother,' or 'brother of *Ya* (emphatic)'; cf. *Ya-ma-e-ra-ah*, 'Ya indeed is the moon' above noticed. *Ilu-ma-ilu*, '(The) god indeed is god'; *I-li-ma-a-bu-um*, 'My god indeed is father'; *I-li-ma-a-ḥi*, 'My god indeed is my brother', and the S. Arabian אֲבִימַאל 'Abi-ma-el (Gen. 10²⁸, 1 Chr. 1²²), 'God is father indeed,' side by side with the normal אֲבִיאל 'Abi-el, 'God is father.' But, if emphasis is thus thrown upon *Ya*, it seems clear that the sense intended is '*Ya and no one else*'; and it is out of the question that *Ya* thus emphasized should be simply a hypocoristic termination, and not a genuine divine name or title.

A further important fact (noticed by the present writer in *JTS.* ix. p. 341) is that a Babylonian syllabary (*CT.* xii. 4) which gives a large number of equivalents of the star-ideogram which is the ordinary symbol for *ilu*, 'god,' offers as the first of these equivalents the word *Ya-u*, a form which would appear in Hebrew as יָהוּ *Yāhū*, the light breathing in Bab. here answering to the Heb. הָ. The second equivalent on the list is *Ya-a-ti*, which recalls *Ya-tum* in the names which we have been examining; but which Sayce is perhaps right in regarding as an etymology offered by the Babylonian scribe for the (to him) unintelligible *Ya-u*, viz. Bab. *yāti*, 'myself' (*ET.* xviii. p. 27; xix. p. 525).

The relationship of the apparently fem. forms *Ya-tum*, *Ya-u-tum* to *Ya-u* or *Ya-u* is obscure. The following attractive explanation

* Cf., however, Jastrow, *JBL.* xiii. (1899), pp. 110 ff., who takes *-ya*, *-yahu* as affirmatives.

has been offered by Sayce:—‘By the side of the masculine Yaû we have the feminine Yaûtum, corresponding with a Hebrew יְהוָה. And just as יְהוָה is used in Hebrew for the masculine, so we find Yaûtum used not only as a feminine but also as a masculine name. That is to say, the absorption of the feminine Yaûtum, יְהוָה, by the masculine יְהוָה, יְהוָה, יְהוָה, which is fully carried out in Hebrew, is in process of being carried out in the Babylonian of the Cassite age. How the goddess, who in so many cases possessed after all only a grammatical existence, came to be identified with the god, I have explained in my Lectures on the Religion of the Babylonians; a well-known example of the fact is the Ashtar-Chemosh of the Moabite Stone. While the Latin races, like the natives of Asia Minor, seemed to have craved for a female divinity, the Semites resembled the Teutonic populations in their tendency to believe only in a male deity’ (*ET*. xviii. p. 27). The transformation of an originally female deity into a male deity in the case of the Sabaeen ‘Athtar has already been noticed in *note* on ‘the ‘Ashtarts,’ p. 59.*

Babylonian evidence for the worship of the deity *Ya-u*, *Ya-u-tum* (*Ya*, *Ya-tum*) appears, then, to be abundant during the First Dynasty period, and onward into the Kaššite period, though not earlier †; and this fact lends high probability to the view of Sayce and Hommel that this deity was first introduced into Babylonia by the ‘Amorite’ immigrants, to whom the foundation of the First Dynasty seems to have been due: cf. *Introd.* pp. lvii ff. §

* Identification of *Ya-u-tum*, *Ya-tum* at one time with a female deity (Istar) and at another with a male deity (Sin) is perhaps to be seen in *Ištar-ya-ut-tum* (Clay, *op. cit.*), *Sin-ya-tum* (Ranke and Thureau-Dangin, *opp. cit.*).

‡ The view put forward by the present writer in *JTS*. ix. p. 342, that the divine name *Ya-um* is to be found so far back as *cir.* B.C. 3000 in *Lipuš-l-a-um* (or *E-a-um*), the name of the daughter of Narâm-Sin, a priestess of Sin, now appears to him to be too doubtful to be cited as evidence: cf. Rogers, *Religion of Babylonia and Assyria*, p. 94 n¹. On Ball’s plausible explanation of *Ya-u amêlu* in *Gilgameš-Epic*, Tab. x. Col. iv. l. 17, as ‘god-man,’ cf. *JTS*. ix. pp. 341 f.

§ It is difficult to escape the impression that the reluctance of some scholars—especially Jewish scholars—to recognize the existence of the divine name Yahu or Yahweh in Babylonian documents of an early period is due to the feeling that such a fact, if true, must tend to derogate from the uniqueness of Israel’s privilege as the sole recipient of the revelation implied by the name which has always been regarded as peculiarly the *proper name* of the God of Israel. In view of this tendency, and to guard against the misunderstanding of his own position, the present writer hastens to affirm that the views which he puts forward in this *Addit. note* as regards the use of the name in very early times among the people of Amurru, from whom Israel sprang, and in the following *Addit. note* as to the early identification of Yahweh with the moon-god Sin, do not, in his opinion, derogate in any respect from the *uniquely new significance* in which the name is related in Ex. 3 to have been revealed to Moses at Horeb. That revelation, with its new exposition of the name Yahweh as ‘He who will become’ (*i.e.* the God of progressive Revelation—‘I will become what I will become’; cf. *note* on *ch.* 6¹⁶, ‘I will be with thee’), no less than the fulness of moral and spiritual meaning which Israel’s prophets and psalmists were inspired to draw from the name in later ages, stands unparalleled in the history of Semitic religions; and is

EARLY IDENTIFICATION OF YAHWEH WITH THE MOON-GOD

(Cf. *note* on 'the Ashera,' *ch.* 6 ²⁵.)

We have seen, in the preceding *note*, how the name Yahu, Yahweh (*Ya-u* or *I'a'-u*, *Ya-u-tum*) comes into prominence at the period of the First Babylonian Dynasty; and evidence appeared to indicate that the knowledge and worship of this deity in Babylonia was due to the 'Amorite' immigrants, who may be supposed to have been the founders of the First Dynasty. It is a noteworthy fact that, while proper names compounded with the names of various Babylonian deities such as Šamaš, Marduk, Ištar, etc., are frequent at this period, by far the largest number of such theophoric names are framed in honour of the Moon-god Sin. Among these, we have already noticed *Sin-ya-tum*, which appears to equate or identify Sin with Yatum or Yahweh. The occurrence has also been cited of the name *Ya-ma-e-ra-ah*, 'Ya indeed is the moon,' *i.e.* the moon-god Sin.

Now the fact is significant that Gen. 14 makes Abraham, the traditional ancestor of Israel, a contemporary of Ḥammurabi ('Amraphel), the most celebrated king of the First Babylonian Dynasty. Biblical records, again, associate Abraham with Ur, the southern seat of the worship of Sin; and depict him as moving thence to Ḥarran, the northern seat of the worship of the same deity, before his migration westward to the land of Canaan. Abraham's movements are represented in the O.T. as dictated by the influence of a higher form of religion than was current at the time in Babylonia. His immediate ancestors are stated to have been polytheists, the worshippers of deities other than Yahweh (Josh. 24 ² E).

Ḥarran* (Bab. *Ḥarrānu*, 'way or road') appears to have been so named as the *road* from east to west, the gateway by which Babylonian trade and culture penetrated into and permeated the coast-land of Syria, including Canaan. It possessed a celebrated temple of Sin, called E. ḤUL. ḤUL, the antiquity of which is vouched for by Nabonidus, when he tells us that 'since ancient days Sin, the great lord, had dwelt therein as the abode of his heart's delight.' ‡ Included wholly unaffected by the fact that the name itself appears to have been known and used in earlier times, and among a wider circle of peoples. Cf. on this point, Rogers, *Relig. of Bab. and Assy.*, p. 97; Driver, *Genesis (Westm. Comm.)*, p. 409, *Exodus (Camb. Bib.)*, p. li. The document J (as distinct from E) regards the use of the name Yahweh as primeval; since it states, in Gen. 4 ²⁶, that in the days of Enosh, the grandson of Adam, 'men began to call with the name of Yahweh,' *i.e.* to use the name in invocations. Yet J by no means implies that the name was used in these early times with anything like the fullness of meaning which it attained when it became the covenant-name of Israel's God.

* The Hebrew vocalization *Ḥārān* is due to the objection which was felt, at the time of the creation of the Massoretic vowel-system, to the doubling of ר; but the *Ḥ* form *Xappan* makes it certain that, at the time when Hebrew was a spoken language, the Hebrew and Babylonian forms of the name were identical. Cf. *note* on *harrīm*, p. 168.

‡ Cf. *KB.* iii. 2, p. 96; Ball, *Light from the East*, p. 208.

in the pantheon of Harran were Šarratu ('the Queen'), wife of the moon-god Sin, and Malkatu ('the Princess'), a title of the goddess Ištar. The names Šarratu and Malkatu are identical in form with the Hebrew Sarah and Milcah, who are related to have been respectively the wife and sister-in-law of Abraham, and to have joined in the migration from Ur to Harran (Gen. 11²⁷ ff.). *

The two forms Abram, Abraham, point to Babylonian originals, the former to *Abu-rāmu*, the latter to *Abu-ra'imū* (the Bab. 𒀭- being represented in Heb. by א; cf. *Ya'-u*=אֵל). But *rāmu*, *ra'imū* are variant participial forms of the verb *rāmu* (Heb. *rāham*), 'to love or show pity.' Abram, Abraham may therefore mean 'loving (merciful) father,' or 'the father is loving (merciful).' ‡ It is at least very probable that the father here originally intended was the moon-god Sin. The attribute of *love* or *mercy* (denoted by this verb) is very characteristic of Sin. We may notice such proper names as *Sin-ra-im-u-ri*, 'Sin loves Ur(?)'; *Sin-ra-im-Uruk* (KI), 'Sin loves (the city) Uruk'; *Sin-ra'-im-zêr*, 'Sin loves the seed (offspring)'; (*ilu*) *Sin-ri-me-ni*, '(the god) Sin, is merciful.' The title 'Father' was especially appropriate to Sin. He was regarded as the father of the gods, the 'merciful, gracious father (*a-bu rām-nu-u ta-a-a-ru*), in whose hand the life of the whole world rests.' §

Thus, without asserting that the origin of the figure of Israel's great ancestor is to be found in a personification of the Moon-god (which indeed it would be rash to do, in view of the fact that the name was known as a personal name at the period to which Abraham is assigned by the Biblical narrative; cf. footnote ‡), it may at least be maintained with some reason that the narrative of the movement which brought the ancestors of the Hebrews from Ur to Harran and finally to Canaan, appears to be bound up with the worship of Sin; just as it is manifestly bound up with definite adhesion to the worship of Yahweh, involving the repudiation of the 'other gods' which the ancestors of Abraham are traditionally recorded to have worshipped.

* Cf. Jensen, *ZA.* xi. pp. 299 f.; Zimmern, *KAT.* 3 p. 364.

‡ This solution of the meaning of the two forms Abram, Abraham was first suggested to the present writer many years ago by Dr. Ball. More recently Ungnad has discovered the name *Aba-rāma*, *Abam-rāma* in Bab. contract-tablets from Dilbat of the reign of Ammizaduga (cf. *Beiträge zur Assyriologie* vi. 5, 1909, p. 60); and here, since the first element is an Accusative, it is probable that the meaning is 'he loves the father,' the name belonging to a series of Bab. names thus formed; cf. Ranke quoted by Gressmann, *ZATW.* xxx. (1910) pp. 2 f. Thus Ball's conclusion as to the pure Bab. origin of the name Abram, Abraham, and his connexion of the second element with the verb *rāmu*, are confirmed; but the possibility (though not the necessity) is opened that the Heb. name may be precisely equivalent to the Bab., and should be so interpreted. Langdon has also noted (on the basis of Ungnad's discovery) that the variants *-rām*, *-rāhām* are explicable through the Bab. variants *rāmu*, *ra'imū*: cf. *ET.* xxi. (1909), p. 90.

§ Cf. the hymn to Sin in iv. 2 R 9, translated by Jastrow, *RBA.* i. pp. 436 f.; Ungnad, *TB.* i. pp. 80 f.; Jensen, *AB.* vi. 2, pp. 90 ff. Rogers, *CP.* pp. 141 ff.

The fact which next calls for notice is the close connexion of Abraham with Be'er-sheba' (Gen. 21²²⁻³¹ E, 21³² J, 22¹⁹ E), a connexion which is continued in the narrative of Isaac, where it is related that Yahweh appeared to Isaac on the night of his arrival at Be'er-sheba', revealing Himself as 'the God of Abraham thy father,' and re-affirming the promises made to Abraham (Gen. 26^{23ff.} J). It is from Be'er-sheba' that Jacob sets out when he leaves his parents in order to go to Paddan-Aram (Gen. 28¹⁰ J); and when, in much later life, he reaches Be'er-sheba' on his way to Egypt, he offers sacrifice there 'unto the God of his father Isaac,' and is the recipient of a Theophany in which God once more repeats His covenant promises made to Abraham and Isaac (Gen. 46¹⁻⁵ E).

The name Be'er-sheba' means 'Well of number Seven,' שֶׁבַע, 'Seven,' being here identical with the Babylonian (*ilu*) *Sibitti* '(god) number Seven,' who seems to have represented one aspect of the moon-god, the seven-day week as a lunar quarter: cf. *Addit. note* pp. 43 f. The connexion which might naturally be inferred from these facts alone between שֶׁבַע Sheba', 'God Seven,' and Yahweh, is confirmed by the existence of the Israelite proper names אֱלִישֶׁבַע, Elisheba', 'God is number Seven,' and especially יְהוֹשֶׁבַע, Jehosheba', 'Yahu or Yahweh is number Seven.' We may recall, in this connexion, how Sabbath (the lunar quarter) and New Moon were observed in later times in connexion with the worship of Yahweh.

Coming now to Moses, we observe that the mountain at which God revealed Himself to him under the name of Yahweh, which is called Sīnai in the narratives of J and P, must have been so called on account of an ancient connexion with the moon-god Sin, who gives His name to the whole district in which the mountain is situated ('the wilderness of Sīn'). According to the account of the Theophany preserved by E, Horeb (as the mountain is called in E and D) is already, prior to the revelation made to Moses, known as 'the mount of God' (Ex. 3¹), *i.e.* it was invested with sacred associations owing to its connexion with the worship of a particular deity—doubtless the god Sin. Jethro, Moses' father-in-law, who was a Kēnite, is styled 'the priest of Midian,' *i.e.* the supreme interpreter of the religion of his tribe; and there can be little doubt that the God whom he worshipped was the God Yahweh, and that the central seat of this worship was Mount Sīnai. No doubt the sacred associations of the place, and very possibly the conversation which Moses may have had with his father-in-law anent the character and worship of the tribal God, in a great measure prepared Moses' mind for the revelation which he was to receive.* It is interesting in this connexion to

* The view here put forward that Moses' mind may thus have been prepared, to some extent, for the Theophany, does not, of course, diminish the extraordinary and providential character of that Theophany, any more than does the fact that St. Paul was doubtless reflecting upon the argument of St. Stephen's speech, and

recall the account of the meeting of Moses with Jethro after the deliverance of the Israelites from Egypt. Moses gave Jethro an account of the course of events, laying stress upon the fact that it was Yahweh who had brought about this great deliverance; and it is recorded that 'Jethro rejoiced for all the goodness which Yahweh had done to Israel, in that he had delivered them out of the hand of the Egyptians. And Jethro said, Blessed be Yahweh, who hath delivered you out of the hand of the Egyptians, and out of the hand of Pharaoh. . . . Now know I that Yahweh is greater than all gods.' Jethro then proceeded to take 'a burnt offering and sacrifices for God: and Aaron came, and all the elders of Israel, to eat bread with Moses' father-in-law before God' (Ex. 18^{8ff.} JE). Here no doubt we have a sacrificial meal, in token of communion of Israel and the Kenite in the worship of Yahweh, the God of Sinai (Sin's mountain).

These conclusions, with regard to the religion of the Kenites, are strengthened by consideration of the name of the North Arabian tribe Jeraḥme'el, which was closely associated with the Kenites, as, subsequently, with the tribe of Judah: cf. *Addit. note*, p. 45. We may infer from 1 Sam. 30²⁶⁻³¹ that the Jeraḥme'elites were worshippers of Yahweh. David is recorded to have sent presents 'of the spoil of the enemies of Yahweh' to the elders of Judah, including 'those who were in the cities of the Jeraḥme'elites and those who were in the cities of the Kenites.' 1 Chr. 2, which makes Jeraḥme'el a descendant of Judah, *i.e.* an integral part of the tribe, gives, in *vv.* 25-33, the genealogy of the descendants of Jeraḥme'el, and includes among them Ahijah and Jonathan, two names which assert allegiance to Yahweh. The name Jeraḥme'el most probably = *Yerah-ma'el*, 'the moon indeed is god.*' Cf. for the formation of the name, '*Abi-ma'el*' (noticed p. 247). Thus this tribe of Yahweh-worshippers bore a name which proclaimed their allegiance to the moon-god.

The description of the Theophany on Mount Sinai, after the ratification of the Book of the Covenant (Ex. 24⁹⁻¹¹ J) is undoubtedly very ancient, and primitive in conception. It tells us that 'Then went up Moses, and Aaron, Nadab, and Abihu, and seventy of the elders of Israel; and they saw the God of Israel; and there was under his feet as it were a pavement of sapphire, and as the heaven itself for clearness. And upon the nobles of the children of Israel he put not forth his hand: and they beheld God, and did eat and drink.' It is difficult to escape the impression that the imagery is here suggested by the spectacle of the moon, riding at its full in the deep sapphire sky; and it can scarcely be objected that such an explanation involves a more crude and unspiritual conception than that which

the circumstances of the martyr's death, when he received the revelation upon the Damascus road, affect the character of that revelation as an interposition of Divine Providence. Each case illustrates the fact that God works through human agents in order to prepare the way for His signal manifestations in history.

* Cf. Hommel, *Grundriss*, i. p. 95, *n*².

seems to be the only possible alternative, viz. that the writer pictured a revelation in human form.

It would be possible to make kindred speculations as to the ultimate meaning of other primitive descriptions of Theophanies—e.g. Jacob's ladder (Gen. 28¹² E), the pillar of fire (Ex. 13^{21f.} J, 14²¹ J), and the revelation to Moses on Šinai (Ex. 33¹⁷-34⁷ J). Such speculations, however, would be at the best highly precarious, and are not needed in order to strengthen this argument for the primitive association of Yahweh with the Moon-god. It is sufficient to observe, in conclusion, that the opening words in which Yahweh proclaims His character to Moses in Ex. 34⁶, יהוה יהוה אל רחום וחנון, 'Yahweh, Yahweh, a merciful and gracious God,' are identical in conception with the 'Merciful gracious Father' in the hymn to Sin already quoted (p. 250).

THE USE OF WRITING AMONG THE ISRAELITES AT THE TIME OF THE JUDGES.

(Cf. *ch.* 8¹⁴ *note.*)

The earliest written documents from Cana'an of which we have knowledge are the T.A. Letters written *cir.* 1400 B.C. by the petty rulers of Cana'anite and North Syrian cities to their Egyptian suzerain Amenhotp III., and, subsequently, to his son and successor Amenhotp IV. or Aḥnaton (cf. *Introd.* p. lxix). These are written in cuneiform Babylonian upon clay tablets. Similar letters, belonging to the same period, have been unearthed at Lachish and Ta'anach. The earliest known documents written in the West Semitic language (using this term broadly to embrace Cana'anite or Phoenician, Hebrew, Moabitic, and also early Aramaic) are very much later. From Southern Syria we have the Moabite stone, *cir.* B.C. 850; the Gezer agricultural calendar, probably not later than the eighth century B.C.; the Siloam inscription, *cir.* B.C. 700.* To these we may now add the ostraka from Samaria of the time of 'Omri and Aḥab, *i.e.* the earlier part of the ninth century B.C., facsimiles of which have not yet (1918) been published;† and a limited number of inscribed seals and jar-handles, the most important of which is the seal from Megiddo

* These inscriptions may conveniently be consulted in *NHTS.*² pp. vii. ff. where further references are given.

† Cf. Driver in *PEF. Qy. St.*, 1911, pp. 79 ff.; and, for a summary account of the excavations at Samaria, based upon the reports in the *Harvard Theol. Journ.*, 1908-1911, Handcock, *The latest light on Bible Lands*, pp. 245 ff.

inscribed 'Belonging to Shama', the servant of Jerobo'am,' *i.e.* very possibly Jerobo'am II., B.C. 783-743.* To Central Syria belongs the Phoenician inscription on fragments of a bronze bowl from the Lebanon, probably of the eighth century B.C.† Northern Syria offers the inscriptions of Kalumu (latter half of ninth century B.C.), Panammu, and Bar-rekub (latter half of eighth century B.C.), kings of Sam'al and Ya'di, and an inscription of Zakir, king of Hamath and La'ash, *cir.* B.C. 800.§ These are written in the alphabetic script which was the prototype of the later West Semitic (Hebrew, Samaritan, and Syriac) and Central Semitic (Arabic) alphabets, as also of the alphabet of the Greeks.

It thus appears that we possess no direct evidence for the use of the alphabetic script in Syria earlier than the commencement of the ninth century B.C.; though its wide diffusion throughout Syria in the ninth and eighth centuries (as proved by the examples above cited) is a clear indication that its first employment must go back to a very considerably earlier date.

The fact that, in the fourteenth century B.C., the cuneiform script was regularly employed in Canaan in official correspondence with the kings of Egypt, and even (as exemplified by the Ta'anach Tablets ||) in private correspondence between Canaanite governors, is not in itself a proof that the alphabetic script was unknown and unused even at this early period. The Canaanite practice in this respect may very well have been parallel to that which existed among the Hittites at about the same periods (as shown by Winckler's discoveries at Boghaz Keui); these latter employing the cuneiform script and Babylonian language together with their own hieroglyphic writing.

The reason why cuneiform Babylonian documents have survived from this early period, whereas no alphabetic West Semitic documents belonging to the same period are known to exist, may possibly be explained by the following facts. The cuneiform method of writing is the direct result of the material employed for written documents by the Babylonians and their imitators—this being normally the clay tablet, upon which, when in a damp condition, the characters were impressed with some form of angular stylus, before the document was baked or sun-dried. Thus, characters which were originally pictographs came to assume the form of conventional combinations of wedges or arrow-heads, the intractability of the writing material being unfavourable to the preservation of the linear

* For the seals generally, cf. *NHTS*.² p. iv.; *TB*. ii. pp. 103 ff.; and for the Megiddo seal, *Tell el-Mutesellim: Bericht über die . . . Ausgrabungen*, i., 1908, p. 99; Driver, *Schweich Lectures*, p. 91. For the jar-handles, cf. Driver, *op. cit.* pp. 74 f., with references there cited.

† Cf. *CIS*. I. i. 1, pp. 22 ff.; Ball, *Light from the East*, p. 238; Cooke, *NSI*. pp. 52 ff.

§ On these North Syrian inscriptions, cf. further pp. 173 f.

|| Cf. Rogers, *CP*. pp. 281 ff.; *TB*. i. pp. 128 f.

pictograph.* On the other hand, the West Semitic alphabetic script, also without doubt originally pictographic, has preserved its linear form because (though capable of being carved, like cuneiform, upon stone) it was never, apparently, written upon clay tablets, † but with a pen and ink upon skin or papyrus. But skin and papyrus necessarily perish in the course of ages when exposed to the damp climate of Syria; therefore, it is well within the range of possibility that such documents, written in the West Semitic script, may have existed at this early period and subsequently perished, while the cuneiform tablets survived. Indeed, the striking paucity of written documents from ancient Palestine may perhaps be explained by the hypothesis that skin or papyrus were commonly employed for writing purposes; and, if this was so, we may be sure that the script employed was the West Semitic alphabet, and not cuneiform. §

* The present editor has made experiments in the writing of cuneiform upon soft putty with a wooden penholder cut to a triangular shape, with one very sharp angle, the end of the 'stylus' being cut off flat. This is held through the full of the hand, as the bearded Assyrian scribe is holding his stylus in the bas-relief figured in Plate 1. (from Layard, *Monuments of Nineveh*, ii. Pl. 26). These experiments have proved to him that the wedges can only be formed successfully *by impression without drawing*, the variation in form being affected by differentiating the slope at which the stylus is applied to the putty—the short broad wedges being formed mainly by the end of the stylus, while the longer and narrower ones result from impressing the sharp edge of the stylus into the putty at an angle of approximately forty-five degrees, a still more acute angle (flatter application of the stylus) being necessary for the production of a very long wedge. Initial attempts to produce the latter by *drawing* with the stylus resulted in failure, as the surface of the putty tended to crumble, and the characteristic clear-cut impression was lost. The same difficulty would obviously stand in the way of drawing linear pictographs or West Semitic alphabetic characters upon this kind of material.

† The only known exceptions are the Aramaic dockets on cuneiform contract-tablets of the late Assyrian, Neo-Babylonian, and Achaemenian periods, written, for the most part, upon the edges of the tablets, so that their contents might be seen at a glance when they were stacked upon a shelf. These have generally a rough appearance, and must have been difficult to draw upon the damp clay. Their existence certainly does not prove that it was *usual* to write the Aramaic script upon clay, but simply that it was *convenient*, in the later stages of the use of cuneiform writing, to have *cuneiform* documents so docketed. For these Aramaic dockets, cf. *CIS.* II. i. Nos. 15 ff.; J. H. Stevenson, *Assyrian and Babylonian Contracts with Aramaic Reference Notes* (*Vanderbilt Oriental Series*, 1902); A. T. Clay, *Babylonian Expedition of the University of Pennsylvania*, Vol. X. (1904), 'Business Documents of Murashû sons of Nippur dated in the reign of Darius II,' pp. 5 ff.; Vol. VIII. (1908), 'Legal and Commercial Transactions dated in the Assyrian, Neo-Babylonian, and Persian Periods,' pp. 14 ff.; A. T. Clay, 'Aramaic Endorsements, etc.,' in *Old Testament and Semitic Studies in Memory of William Rainey Harper* (1908), Vol. I. pp. 286 ff.; *University of Pennsylvania Museum, Publications of the Babylonian Section*, Vol. II. No. 1, 'Business Documents, etc.,' by A. T. Clay (1912), Plates 116-123.

§ This latter is very ill-suited for writing with a pen and ink. Layard, *Monuments of Nineveh*, 2nd Series, Plate 54, represents a fragment of coloured

The scribes who wrote the T.A. Letters which came from Cana'an were obviously more at home in using the West Semitic language than in using Babylonian. This fact is proved by their employment of Cana'anite 'glosses' on Babylonian terms, or substitution of Canaanite words when at a loss for the Babylonian equivalent (cf. p. 166). If, however, they were familiarized with the idea of writing through their official correspondence in Babylonian, and could write their own West Semitic language in Babylonian cuneiform syllables, as is proved by the 'glosses,' and were accustomed to express themselves in West Semitic rather than in Babylonian, why has no discovery been made of documents in the West Semitic language, but written in cuneiform upon clay tablets? A reasonable inference is that no such documents existed; the West Semitic tongue, if written at all at this period, being written upon perishable materials such as skin or papyrus, in the alphabetic script.

There is a fact in connexion with the T.A. correspondence which may very possibly indicate that the West Semitic alphabet *was* actually known to, and normally used by, the Cana'anite scribes of this period. It is probable that the secretary at the Egyptian court, whose business it was to read and interpret the Cana'anite correspondence to the king of Egypt, was himself not a native Babylonian, or a specially trained Egyptian, but a Western Semite like those with whose correspondence it was his duty to deal. He was possibly a personal friend of ARAD-Ḥiba of Jerusalem, who regularly concludes his letters to the king with a postscript addressed to the secretary, begging him to impress upon the king's mind the main points with which his letters are concerned. Thus, in one of his letters he writes to him, 'Bring thou in plain words unto the King, my Lord. The King my Lord's entire territory is lost' (Knudtzon, 286). The phrase here rendered 'is lost,' in Babylonian *ḫal-ka-at*, occurs, in the same connexion, in another of ARAD-Ḥiba's letters (Knudtzon, 288, l. 52), and is glossed, for the sake of emphasis, by the Cana'anite *a-bu-da-at* (Heb. אֲבֹדָה). We can scarcely err in interpreting this emphasis as

pottery on which are a few cuneiform characters painted with a brush; but apart from this no instance is known to the present editor of the writing of the script otherwise than with a stylus upon clay or stone. In the bas-relief mentioned in an earlier footnote (cf. Plate 1.), which is part of a scene representing a bearded Assyrian scribe taking a memorandum of the spoils of war in cuneiform writing upon a tablet, this figure is accompanied by another who is writing with a pen upon a piece of curling material which obviously represents a scroll of leather or papyrus. The fact that this latter man is beardless marks him as a foreigner (possibly a eunuch); and it may be inferred therefore that he is writing in a non-cuneiform script—very possibly in the alphabetic Aramaic script. The two scribes are thus making a double entry in Assyrian and Aramaic respectively. The relief in question, which is of the seventh century B.C., is to be found in the British Museum, Kouyunjik Gallery, West Wall, Nos. 4-8. Nos. 15-17 in the same gallery evidently contain a continuation of the same series, and here too we have two similar scribes engaged in the same employment.

carrying the implication, 'Do not let there be any mistake: when I say *ḥalkat*, I mean *abadat*'; and hence the inference is fair that the Egyptian king's secretary, like his correspondent, was more familiar with West Semitic than with Babylonian.

Now among the T.A. correspondence there were found certain fragments of Babylonian legends which had apparently been written as exercises in the writing of the cuneiform script by the secretary of whom we have been speaking, or by some one else holding the same position. These exercises are written in the simplest possible form, ideograms and compound syllables (*i.e.* syllables both beginning and ending with a consonant) being avoided, and the words built up entirely with simple syllables (*i.e.* vocalic syllables or syllables containing one consonant only). In illustration we may quote the first few lines of the story of Nerigal and Ereškigal, which, apart from its occurrence among the T.A. Letters, would be unknown to us:—

i-nu-ma i-lu iš-ku-nu ki-e-ri-e-ta
a-na a-ḥa-ti-šu-nu e-ri-eš-ki-i-ga-a-al
iš-ḫu-u-ru ma-a-ar ši-i-ḫ-ri
ni-i-nu u-lu nu-ur-ra-da-ak-ki
u at-ti ul ti-li-in-na-a-ši
šū-u-up-ri-im-ma li-il-gu ku-ru-um-ma-at-ki.

'When the gods prepared a feast,
 To their sister Ereškigal
 They sent a messenger;
 "Even if we should descend to thee,
 Thou wouldst not come up to us;
 Therefore send and take thy portion."

A native Babylonian scribe, writing in normal fashion, would have expressed this as follows:—

e-nu-ma DINGIR.MEŠ iš-ku-nu ki-ri-ta
a-na a-ḥa-ti-šu-nu (DINGIR) e-riš-ki-gal
iš-ḫu-ru TUR šip-ri
ni-nu u-lu nu-ur-ra-da-ak-ki
u at-ti ul ti-li-in-na-ši
šup-rim-ma lil-ḫu ku-rum-mat-ki.

Here we give the ideograms DINGIR.MEŠ = Bab. *ilāni*, TUR = Bab. *mār*, in Sumerian form in order more clearly to illustrate the normal Babylonian method of using ideograms.

The use of simple, as distinct from compound, syllables suggests that the scribe was accustomed to an *alphabet* rather than to a syllabary, the simple syllables being for him the equivalents of his own alphabetic signs. We say *the equivalents*, because it is obvious that the West Semitic *alphabet*, which has no signs to denote vowels, and which we are accustomed to regard as wholly consonantal, must really have been regarded—at any rate by its framers and earliest

users—as a *simple syllabary*, in which each consonantal sign carried the vowel which was appropriate to the word in which it was used.* In certain cases, *e.g.* in *ga-a-al* for *gal*, *ši-i-ip* for *šip*, the T.A. scribe uses the opportunity afforded him by the Babylonian syllabary of expressing the *vowel* even in a closed syllable in which the vowel is short. He does this because the language is unfamiliar to him, and it is convenient to be able to employ a *phonetic complement*; and, in so doing, he anticipates the history of the development of the written vocalic system in Hebrew, which was simply the invention of a series of phonetic complements when the fact that Hebrew had become comparatively unfamiliar to the Jews necessitated such a course.

Be this as it may, we have definite evidence to prove that by the twelfth century B.C., *i.e.* during the early part of the period covered by the Book of Judges, papyrus was employed in Palestine as a writing material; and therefore, we must infer a form of writing other than cuneiform was known and used. The Egyptian envoy Wenamon (*cir.* B.C. 1114; cf. *Introd.* pp. xcvi ff.) mentions, among the presents shipped from Egypt in payment to Zakar-ba'al, king of Gebal, for timber from the Lebanon, five hundred rolls of papyrus.† It is evident, therefore, that this Phoenician king knew and valued a material which could only be employed for writing with pen and ink; and there is no reason to doubt that this writing was the 'Phoenician' alphabetic script. It is interesting to observe that, in the earliest known examples of this script to which we have already referred—the ostraka from Samaria belonging to the early ninth century B.C., the writing is not scratched or otherwise incised upon the sherds, but written in ink with a reed pen, in a free and flowing style. §

The evidence afforded by philological examination of the terms employed in Bib. Heb. in connexion with *writing* is as follows.

The ordinary Heb. verb which means 'to write' is *kāthabh*, the ground-significance of which is uncertain. This verb may be used of engraving upon stone (*e.g.* the two tablets of the ten commandments), or of writing with ink in a book. Other verbs which denote 'to engrave' are *hāraš*, *hārath*, *hāḥak*; but the latter verb, as used in Isa. 30⁸ ('inscribe it in a book'), may have come to be applied to writing in ink. It is worthy of note that the ordinary Bab. and Assy. verb 'to write,' *šafāru*, is not so used in Heb.; though the

* Thus, if a Western Semite read דבר, he did not—like modern learners of Hebrew—think of it as a mere series of consonants *d-b-r*, to which the addition of the vowels was a matter of guess-work aided by the context; but he thought of it as *da-ba-rium* if it happened to be the substantive meaning 'word,' or otherwise as the context dictated, the decision as to the precise vowel which the written sign carried being instinctive to a born user of the language, just as the decision as to a cuneiform sign-group, which, *e.g.*, might have the different values *dan*, *kal*, or *rib*, was instinctive from its context to the practised reader of Babylonian.

† Cf. Breasted, *AR.* iv. § 582.

§ Cf. Handcock, *The Latest Light on Bible Lands*, p. 255.

participial form *šof^erîm*, which is applied to a class of minor officials who had to do with the civil and military organization of the people, perhaps originally denoted 'scribes' or 'secretaries.'

Heb. *šēpher*, 'missive, document, book,' is probably an ancient loan-word from Bab. *šipru*, 'missive, message,' which is derived from *šapāru*, 'to send'; and this very probably points to the Babylonian origin of the use of written documents among the Western Semites. Bab. *šipru*, however, never seems itself to denote the document or clay tablet on which the message was inscribed; the regular term for this being *duppu*. That the Heb. *šēpher* came, at a relatively early date, to denote a leather or papyrus document written in ink, and therefore in the alphabetic script, is clear from such a passage as Ex. 32³² (prob. J) where Moses is pictured as petitioning God, 'Wipe me, prithee, out of thy book which thou hast written' (מִחֲנִי נָא מִסְפָּרְךָ אֲשֶׁר כָּתַבְתָּ), the verb *māḥā* implying the wiping of something written in ink off a roll of papyrus or leather, and not the erasure of cuneiform characters from a clay tablet.

The Heb. *mēgillā*, 'roll,' from *gālal*, 'to roll' (sometimes coupled with *šēpher* in the phrase 'the roll of a book') can, of course, only have been a document of papyrus or leather, written in ink. The term is earliest used of Jeremiah's roll (Jer. 36^{2 ff.}), written in the reign of Jehoiakim, *cir.* B.C. 600. This was divided into *dēlāthōth* (lit. 'doors'), *i.e.* perhaps rectangular 'columns,' or, less probably, 'leaves' (*v.* 23), and the writing is stated to have been in 'ink' (*d'yō*, *v.* 18). Ezekiel's 'roll of a book,' 'written on the face and on the back' (Ezek. 2¹⁰) is of nearly the same date. It is probably merely accidental that the term *mēgillā* does not occur at an earlier period.

The regular Heb. term for a *tablet* for writing is *lūah*, which is most commonly applied to the two tablets of stone on which the ten commandments were inscribed. The term is used besides in Isa. 30⁸—'Now go, write it on a tablet in their presence, and inscribe it in a book, that it may be for a future day, [for a testimony]* for ever'; and in Prov. 3³, 7³, Jer. 17¹, in the figurative expression, 'the tablets of the heart.' In all these passages the reference is to the making of a permanent memorial: and the inference is that tablets, probably of stone, were used for such a purpose. No mention of the use of *clay* as a writing material occurs in the O.T.

Heb. *ḥeret*, 'stylus,' Isa. 8¹, must have been, in the first instance, a graving tool for cutting incised characters upon stone or metal: cf. the use of the same substantive to describe the tool with which Aaron 'fashioned' (וַיַּצַּר) the molten bull, Ex. 32⁴ E; and the Aram. verb *ḥ^araṭ*, 'to cut or scratch.' The term may, however, have come to denote a pen for writing with ink. The *gillāyôn* upon which the writing is to be done in Isa. 8¹ may have been a polished metal

* Vocalizing לְעֶר, in place of לְעֶר 'for eternity.'

tablet (cf. R.V.), if (as is doubtful) the plur. form *gilyônîm* in Isa. 3²³ denotes tablets of polished metal used as mirrors (from verb *gālā* in the sense 'display, reveal'); but comparison of the Talmudic *gilyôn*, which denotes the *empty margin* of a page or roll (from verb *gālā* in the sense 'be uncovered, and so, bare'; cf. Ar. *ġala*) suggests that Isaiah may have been thinking of the blank page of a book: cf. Θ^A $\tau\acute{o}\mu\omicron\nu\ \chi\alpha\rho\tau\acute{o}\upsilon\ \kappa\alpha\iota\rho\acute{o}\upsilon$.* Heb. 'ēṭ, 'pen' or 'stylus,' was probably usually a reed-pen for writing in ink. Jeremiah, who himself, as we have seen, used a 'roll' for the writing of his prophecies, refers to 'the lying pen ('ēṭ) of the scribes'; and we may infer that his own pen (or rather, that of Baruch) would have been described as 'ēṭ. 'The pen of a rapid writer,' Ps. 45¹, פֶּן ², would naturally be a reed. The 'ēṭ, however, might also be an iron stylus for incising characters upon stone or metal. Jeremiah, in speaking of the ineradicable character of Israel's sin, says that it 'is written with a pen of iron with diamond point' (Jer. 17¹): cf. also Job 19²⁴.†

So far, then, as Biblical evidence is concerned, we gather that written records in pre-exilic times were in special cases engraved on stone; but more commonly written in ink upon a roll or book of papyrus or leather. The earliest definite reference to the employment in a 'book' of writing which could be wiped off, and was therefore presumably in ink, is Ex. 32³² (Moses' prayer), which, of course, does not *prove* anything more than that the J writer (if the passage is rightly assigned to him) in the ninth century B.C. supposed that Moses would think of a book written in ink. It is likely, however, that J may be embodying an oral tradition emanating from an indefinitely earlier period. On the other hand, we find no reference whatever to the use of *clay* tablets by the Israelites, and no hint that it is in any way reminiscent of the use of the cuneiform script in early times.

If, as we have seen from the allusion in the story of Wenamon, papyrus was used for writing in Palestine in the twelfth century B.C., it is at any rate very possible that the use of the alphabetic script may

* In either case, the terms are most probably used metaphorically, as is not obscurely hinted by the expression 'stylus of a man,' i.e. 'human stylus,' and by *v.*³ which refers the symbolism to the begetting of a son who is to be named Maher-shalal-hash-baz. The *gillāyôn* of *v.*¹ is a metaphor, then, for 'the prophetess' of *v.*³, who, if described as a blank page, may very possibly have been Isaiah's second wife, and not the mother of She'ar-yashub of *ch.* 7³. On this explanation, the want of apparent connexion between the symbolism of *v.*¹ and that of *v.*³ disappears; and there is no occasion to suppose that the *gillāyôn* was a metal tablet to be set up in some public place, or that the expression *hēreṭ 'ēnōš*, 'stylus of a man,' means an *ordinary stylus* which would write 'common characters, intelligible to all' (as strangely explained by BDB. p. 355).

† Heb. 'ēṭ is probably connected with Bab. *haṭṭu*, which usually means 'sceptre,' but also, no doubt, 'stylus' (the ideogram which expresses it may also denote 'scribe'). The cognate verb *haṭāṭu* means 'to cut into.'

have been well diffused throughout the country at the time of the Judges. How far the art of writing was generally understood and practised, or had only been mastered by a class of specially trained scribes, we cannot say. In the Gezer-calendar, however, in which the months of the year are distinguished by the agricultural operations with which they were associated ('The month of ingathering, the month of sowing, etc.'), it is generally recognized that we have the work of a peasant-farmer who was able to write in a fair and legible hand; and if such an accomplishment was possible for a peasant in the eighth century B.C. there is no valid reason for supposing that it would have been impossible for the boy captured by Gide'on some three or four centuries earlier.

The conclusion that the use of the alphabetic script may quite possibly have been well-diffused in Cana'an at the time of the Judges is as much as this note is concerned to argue. The question how far back the script is to be traced is a much wider one, and is bound up with the problem of its origin—a problem which has been much debated, and upon which the paucity of evidence does not at present permit us to speak with any certainty. It can hardly, however, be disputed that there exist a few traces of the use of the West Semitic alphabet at a period far earlier than the earliest of the documents mentioned on pp. 253 f. The alphabetic letters discovered by Schumacher at Megiddo (cf. *Tell el-Mutesellim*, p. 109) are dated by Kit. (*GVI*.² i. p. 120) between the sixteenth and thirteenth centuries B.C. Some of the signs on fragments of pottery discovered by Bliss at Tell el-Hasi (Lachish) bear a remarkable resemblance to West Semitic letters (cf. *A Mound of Many Cities*, chap. ii.); and it is at least highly doubtful whether they can be dismissed as 'owners' marks' merely. These pot-sherds were, with but one exception, found exclusively in the earliest strata of the mound, dated by Bliss not later than *cir.* 1600 B.C.*

As for the origin of the West Semitic script, few if any scholars at the present day would maintain de Rouge's theory which attempted

* The inscription on an Egyptian statute of Hathor, discovered by Petrie at Serabit in the Sinai-peninsula (cf. *Researches in Sinai*, pp. 129 ff.), and dated by him *cir.* 1500 B.C., was discussed by Ball in *PSBA.*, 1908, pp. 243 f., who took the writing as an early form of Phoenician, and read the first four characters as עתחר, 'Athtar. The publication by Gardiner of further inscriptions from the same locality now shows that the characters are badly written Egyptian hieroglyphics: cf. *Journal of Egyptian Archaeology*, iii. (1916), pp. 1-21. Gardiner attempts to prove that these signs are the prototypes of an early Semitic alphabet of Egyptian origin, basing his argument upon the supposed occurrence of בעלת, *Ba'alath*, 'Mistress'—the title of the goddess—which recurs in several of the inscriptions (reading from left to right, or from top to bottom); but his theory, though supported by Cowley and Sayce, depends too much upon assumption to carry weight as a plausible solution of the problem of the origin of the alphabet.

to trace it to the Egyptian hieratic character. The theory of an origin from the Babylonian, or rather Sumerio-Akkadian, linear script which was the prototype of the cuneiform syllabary has been maintained by Ball, Hommel, Winckler, and others. In favour of this theory many attractive arguments have been adduced,* though in the present state of our knowledge these cannot be claimed

* Cf. especially Ball, *The Origin of the Phœnician Alphabet*, PSBA., 1893, pp. 392-408; reproduced in revised and abridged form in *Light from the East*, pp. 232-238. Perhaps the most striking instances of close resemblance in *form* and *sound* between the linear Babylonian and West Semitic characters are the following. The Sumerian sign ZI, ZIDA, ZIDE, Bab. *Zītu* (cf. Heb. *Šādē*, Greek *Ζῆτα*) probably represents a flowering reed. There being no consistent differentiation between *z* and *š* in old Babylonian, the difference between the West Semitic sounds seems to have been effected by taking the upper part (flower) of the reed for **𐤆**, and the lower part (a leaf) for **𐤇**. The Sumerian sign GAM (meaning, according to Babylonian lexicographers *kaḍādu* 'to bow down,' and representing some bowed or bent object, conceivably a broken reed) is practically identical in form with the West Semitic *Gimel*. *Gimel* corresponds to the Greek *Γάμμα*, a form of the name which is not to be regarded as a modification of an original *Γάλλα* (as suggested by Bevan, *EB.* 5360), but rather represents a more primitive form of the name: cf. Ar. *Ġim*. But the Sumerian GAM may also have been pronounced GAMMA: cf. DUG, DUGGA; IL, ILLA; etc. The Heb. name *Gimel* 'camel' may then be taken to be a later modification of the name GAM, due at once to the similarity in sound and to the fancied resemblance of the sign to the head and neck of a camel. If the names *Ζῆτα*, *Γάμμα* really find their origin not in West Semitic but in Sumerio-Akkadian, the linear Babylonian theory of the alphabet may well be regarded to be as good as proved.

We can, of course, argue nothing from such names of the alphabet as happen to be Semitic words of known meaning; since these may conceivably have been bestowed at a relatively late date in the history of the alphabet (we have already argued that the name *Gimel* is probably later than GAM or GAMMA). Thus the fact that **𐤆** bears the name *Rēš* 'head,' and not the Canaanite or Hebrew name *Rōš*, while it suggests the Bab. *rēšu*, is more probably to be explained from the Aram. *rēšā*; the fact being well established that it was the Aramaean development of the alphabet which was the parent of the Hebrew square character—the *ketābh 'aššūri* 'Assyrian (*i.e.* Mesopotamian) script'—rather than the Phœnician development which resulted in the Samaritan script. 'Pō, the Greek form of *Rēš*, may be compared with Ar. *Rā*, and with Sumerian RU, the name of the triangular character which is practically identical with the early West Semitic **𐤆** *Rēš*. But the Sumerian sign for RU may also bear the value DA, just as **𐤆** *Rēš* and **𐤇** *Dāleth* are nearly identical in form in early West Semitic—a fact which suggests that **𐤆** and **𐤇** may have had a common origin, and also that DA (for DAL? cf. Ar. *Dāl*) may have been the original name for the latter letter, this being later on semiticized into the word of known meaning *Dāleth* 'door.'

A point in favour of the linear Babylonian theory which should not be overlooked is the fact that we have actual evidence, in the old Persian cuneiform writing, of the utilization of the cuneiform script for alphabetic purposes. On the manner in which the syllabary may have been gradually adopted so as to form an alphabet, cf. Ball, *op. cit.*, and also the facts which we have noticed above (p. 257) as to the simplification of the syllabary by a Canaanite scribe *cir*.
1400 B.C.

actually to amount to a demonstration. Most recently Sir Arthur Evans has attempted to prove (*Scripta Minoa*, vol. i. 1909) that the Minoan script discovered by him in his excavations at Knossos in Crete is closely connected with the West Semitic alphabet; and this writer therefore argues for a Mediterranean origin for the alphabet, holding it to have been introduced into Canaan by the Philistines and other kindred sea-peoples who invaded and settled in Palestine at the end of the thirteenth and beginning of the twelfth centuries B.C. This theory assumes the doubtful position that there is no trace of the use of the alphabetic script in Canaan prior to the thirteenth century B.C.; and, while ignoring the striking parallels, both in *form* and *sound*, between the linear Babylonian and certain of the West Semitic letters, draws similar parallels between the Minoan and West Semitic scripts based on *form* only, the value of the Minoan characters being at present undetermined.* Evans also fails to take account of the possibility that such resemblances as may be traced between the Mediterranean and West Semitic scripts may conceivably be due to a common dependence, whether direct or indirect, upon linear Babylonian. ‡

8. 29-32. *R^P's introduction to the story of Abimelech.*

This short section forms a necessary introduction to the story of Abimelech contained in *ch.* 9. As is noticed elsewhere (cf. p. 268), *ch.* 9, though derived from the old composite narrative and forming part of R^{JE}'s history of the Judges, must have been cut out of the book by R^{E2}, who substituted the short summary 8³³⁻³⁵ in place of it. We infer therefore that the story of Abimelech, together with *chs.* 16-21, was re-inserted into the book by the final editor R^P; and if this is so, this editor must have been responsible for 8²⁹⁻³² introducing *ch.* 9, apart from which the information which these verses contain is superfluous to the narrative. The phraseology of 8²⁹⁻³² points to the influence of P: cf. יֵצְאֵי יֶרְכּוֹ 'that came out of his loins,' an expression elsewhere (Gen. 46²⁶, Ex. 1⁵ †) peculiar to P; בְּשִׁיבָה טוֹבָה 'in a good old age,' Gen. 15¹⁵ (late editorial interpolation), Gen. 25⁸ P, 1 Chr. 29²⁸ †.

* This criticism applies equally to Petrie's recently published theory of the evolution of the alphabet, by survival, out of a large and widely diffused signary which had, according to him, its origin in prehistoric Egypt, and drew accretions from the whole of the nearer East (*The Formation of the Alphabet*, 1912, published as Vol. III. of *The British School of Archaeology in Egypt Study Series*). The theory really shows how deceptive arguments from *form* are when divorced from *value*.

‡ Thus, to take one illustration only, the coincidence (if such it be) is at any rate very remarkable that the Cypriote sign PA, noted by Evans (*op. cit.* p. 1, n³; p. 71, no. 4) and compared by him with the same sign in Minoan, is absolutely identical in form and bears the value PA in Sumerio-Akkadian.

29. R^p (E) And Jerubba'al the son of Joash went and dwelt in his house. 30. And Gide'on had seventy sons, that came out of

Naturally R^p must have been dependent for his *facts* upon the original narrative introductory to the story of Abimelech. This probably belonged, like the main narrative of *ch.* 9, to E; notice the name Jerubba'al in *v.* 29, as in *ch.* 9^{1.2.5a.5b.16.19.24.57}.

8. 29. *went and dwelt, etc.* Logically, we should have expected this fact to have been narrated before the account of the making of the Ephod in *vv.* 24^{ff}. There is a reason, however, for the order of events. The Israelites (*v.* 22) ask Gide'on to become their king. He refuses this (*v.* 23), but at the same time takes the opportunity (*v.* 21) of asking for the ear-rings of their spoil; and it is natural that this should immediately be followed by the account of the use to which the gold was put, and the abuse which the Ephod became. It is not until these facts have been narrated that the writer gets the opportunity of stating that (instead of accepting the offer of the kingship) the hero retired into private life, which is what the statement of *v.* 29 'he went and dwelt in his home' (or, as suggested by Bu., וַיָּשָׁב לְבֵיתוֹ, 'and returned to his home') amounts to; and this reference is a natural introduction to the account of his becoming the founder of a large family (*vv.* 30, 31). To conclude, therefore, that *v.* 29 'stands singularly out of place' (Mo.), and 'originally closed the narrative in *vv.* 1-3, or that in *vv.* 4-21' (Cooke) entirely misses the point. The verse *might* immediately have followed *v.* 23, but *could not* have preceded it.

30. *seventy sons.* The same number is given for the sons of Ahab, 2 Kgs. 10¹. The sons and the grandsons of the Judge 'Abdon are said to have been seventy in all, Judg. 12¹⁴. In the inscription on the monument erected by Bar-rekub, king of Ya'di, in honour of his father Panammu (cf. p. 173) it is stated that seventy brethren (or kinsmen) of Panammu's father Bar-šur perished in an insurrection. Adoni-šedeḳ boasted that he had seventy captive kings picking up crumbs under his table, Judg. 1⁷. We can only conclude that in all these cases *seventy* represents a large round number.

that came out of his loins. Heb. *yārēkh* (properly 'hip' or 'thigh') is here used of the seat of procreative power: so also (in addition to the other occurrences of the same phrase, cited above) in the phrase (preparatory to the calling for a specially solemn oath) 'Put thy hand under my *yārēkh*,' Gen. 24^{2.9} J, 47²⁰ J †, where the reference is probably 'to an oath by the genital organs, as emblems of the life-giving power of the deity—a survival of primitive religion': Skinner, *Genesis* (ICC), p. 341. The force of the expression as used in our passage is that these sons belonged to Gide'on's clan *by male descent*, in contrast to Abimelech, mentioned in the next verse, who belonged

his loins : for he had many wives. 31. And his concubine who was in Shechem, she also bare him a son ; and he made his name Abimelech. 32. And Gide'on the son of Joash died in a good old age, and was buried in the sepulchre of Joash his father, in 'Ophrah¹ of¹ the Abiezrites.

by birth *to the clan of his mother* : cf. *note ad loc.* Robertson Smith remarks that the term *ṣahid* 'thigh' denotes a *clan* in the Palmyrene inscriptions and elsewhere in Arabic literature, and contrasts it with *ḥaṭn* 'belly' or 'womb' which is similarly used ; arguing that 'the "thigh" or clan of male descent, stands over against the "belly" or clan of mother's blood' : cf. *Kinship and Marriage in early Arabia*,² p. 38.

31. *his concubine, etc.* The connexion was not, according to the custom of the time, an irregular one. It seems to have been a marriage of a type well known among the early Arabians, in which the wife does not become the chattel or property of her husband, but is known as his *ṣadiqa** or 'female friend,' and remains with her own clan, being visited by her husband from time to time. Samson's marriage with his Philistine wife (*ch.* 14) was very possibly of the same character. In such cases, the children of the marriage belong to the wife's clan—a fact which has an important bearing on the events related in *ch.* 9 : cf. *note on v.*² 'your bone, etc.' On *ṣadiqa*-marriage, cf. Robertson Smith, *op. cit. supra*, pp. 93 ff.

he made his name. Heb. **וַיִּשֶׂם אֶת-שְׁמוֹ**, lit. 'he set or appointed his name.' This somewhat peculiar usage (in place of the normal **וַיִּקְרָא** 'he called') is seen again in 2 Kgs. 17²¹, Neh. 9⁷ ; cf. Dan. 1⁷.

Abimelech. The name, which probably means 'the (divine) king is father' (*sc.* of the bearer of the name) is borne by the king of Gerar in Gen. 20^{2 ff.} E, 26^{1 ff.} J. Abi-milki (which is identical) is the name of the governor of Tyre who figures in the T.A. Letters *cir.* 1400 B.C., and of a prince of Arvad who was tributary to Ashurbanipal : *KB.* ii. pp. 172 f. On the use of the element *Mélekh* or *Milk* in proper names, cf. *KAT.*³ pp. 469 ff. ; Baethgen, *Beiträge*, pp. 37 ff. ; Gray, *Hebrew Proper Names*, pp. 115 ff. ; La., *ÉRS.*² pp. 101 ff.

32. *in 'Ophrah, etc.* Reading **בְּעֶפְרָה** in place of the Absolute form **וּבְעֶפְרָה** **וְ**. It is possible, however, that the original narrative may have read 'in 'Ophrah' simply, and that the definition 'of the Abiezrites' was added subsequently as a gloss from *v.*²¹, without altering **בְּעֶפְרָה** into the Construct State.

* The form *ṣadāka* given by Cooke is unknown in this sense. He seems to be making a cor fusion with *ṣadāq*, which denotes a gift given by the husband to the wife on the occasion of marriage.

33. ^{R^{E2}} And, when Gide'on was dead, the children of Israel turned back, and went a whoring after the Ba'als, and made Ba'al-berith their god. 34. And the children of Israel did not remember Yahweh their god, who had delivered them out of the hand of all their enemies round about. 35. And they did not show kindness to the house of Jerubba'al (Gide'on), according to all the goodness which he had shown to Israel.

8. 33-35. *R^{E2}'s summary in place of the story of Abimelech.*

These verses, which are clearly marked by their phraseology as due to ^{R^{E2}}, give a summary account of Israel's apostasy based upon *ch.* 9 (cf. *vv.* 33b, 36a), and evidently intended to take its place; since, if *ch.* 9 had stood in ^{R^{E2}}'s book, such a summary would have been superfluous. Cf. further *Introd.* to *ch.* 9.

8. 33. *when Gide'on was dead.* Cf. 2⁶⁻¹⁰ E, 2¹⁹, 4¹ ^{R^{E2}}. According to the main editor's philosophy of history, apostasy regularly follows after the death of a judge.

went a whoring. Cf. 2¹⁷ note.

the Ba'als. Cf. 2¹³ note.

Ba'al-berith. Cf. 9⁴. The title means 'Lord *or* owner of the covenant.' In 9⁴⁶ El-berith, 'God of the covenant,' is used. Whether this deity was thought to preside over a league of Canaanite cities, or whether the 'covenant' was between him and his worshippers, cannot be determined. Cf. Cheyne, *EB.* 404 for different views.

Ba'al-bērith, according to *ch.* 9, was the local Ba'al of the Canaanites at Shechem. This narrative, whence ^{R^{E2}} derives his information, says nothing about a general defection of the *Israelites* after the Ba'al; the fact being quite clear that the inhabitants of Shechem were *Canaanites*, and that Abimelech obtained and held sway over them in virtue of his *Canaanite* descent. Cf. p. 267

35. *did not show kindness, etc.* A summary reference to the facts narrated in 9¹⁻²¹. Here again ^{R^{E2}} misses the point of the narrative, and assumes that the execution of Jerubba'al's seventy sons and the appointment of Abimelech as king were due to the Israelites. m

Jerubba'al (Gide'on). ^{R^{E2}} (or possibly some later hand) adds the name Gide'on in order to make the fact clear that the two names refer to one and the same man. Cf. the similar insertion in 7¹. y

9. 1-57. *The story of Abimelech.*

Besides the Commentaries, etc., quoted throughout the book, cf. H. Winckler, *AF.* i. (1893) pp. 59-62.

This ancient narrative is of the highest interest on account of the light which it throws upon the circumstances of the early stages of Israel's occupation of Canaan. After the death of Gide'on or Jerubba'al, the hegemony which he had exercised over his own clan at 'Ophrah and (as we gather from this narrative) over the neighbouring

THE BOOK OF JUDGES

Cana'anite city of Shechem, passed in natural course. Thus we see Israelite and Canaanite living in a state of mutual toleration if not of friendship, and suffering from the incursions of the Midianites when a deliverer such as Jerubba'al arises from his family, willing to recognize his right to exercise leadership by side in a relation of government. Distinctions of race and place. Both races alike are obliterated, as subsequent events show. Canaanites from without; and by birth, is wholly Canaanite. In these cases, both races thereafter are merged. He uses his racial connexion to secure some form of chieftainship over the clan at Shechem in his own place are, however, by no means (with one exception) all proved. Abimelech, half-Canaanite, was an Israelite, and secured his position by tribal custom: cf. *note* on *v. 2*. The neighbouring divisions conspire to incite the members of his mother's prince 'over Israel' in his favour; and by their aid he wipes out Israel at this time: the other sons of Jerubba'al who by birth were Israelites, that the authority secures a short-lived kingship over Shechem and local. The fact is correct. The statement (*v. 22*) that Abimelech was under Abimelech seems to belong to the point of view which regards but it is clear already forming an organic unity, and supposes fails to pay exercised by the Judges was general, and not simply Canaanite, that Israelites as well as Canaanites were included his local king's sway is, as Mo. notices, to be inferred from *v. 65*;

Evidence that the framer of the narrative misses, or at least noticed in regard to, the fact that Abimelech was essentially a growth who used his Canaanite connexions in order to secure tracedanship.*

spirit of the employment of more than one source may be these in the middle part of the narrative. As Mo. points out, the ever, hostilities between Abimelech and the men of Shechem is Ga'a two distinct causes. According to *v. 23*, God sends an evil between Abimelech and the citizens of Shechem, which causes them to deal treacherously with their ruler. In *v. 26-29*, however, a new situation is created by the arrival on the scene of one and his family. These new-comers stir up the racial pride of blue-blooded Shechemites against the half-breed Abimelech, and so foster a revolt. Clearly this second cause is distinct from, and cumulative upon, the first. In *v. 26b* it is stated that Abimelech was informed of the treacherous aggressions of the Shechemites; and the expectation is created that he will immediately take action. Instead of this, however, the narrative of Ga'al intervenes, and is continued down to *v. 41*; at which point, after Ga'al's defeat by Abimelech and subsequent expulsion from Shechem, he disappears from the narrative, which is now concerned (*v. 42 ff.*) with the reprisals taken by Abimelech upon the Shechemites as a whole.

* Cooke misapprehends this point when he states (p. 98) that 'at Shechem the native Canaanites were in the ascendant, and yet there was a sufficiently strong Israelite element in the place to raise Abimelech to the position of ruler.' Yet he rightly recognizes (p. 97) that, in the *ṣadiḡa* marriage, 'the children remained with their mother and belonged to her tribe,' and that 'the narrative seems to imply that the woman was a Canaanite' (p. 97).

THE BOOK OF JUDGES

that *v.*^{42b}, 'and they told Abimelech,' repeats *v.*^{25b}, 'Abimelech,' with but trifling variation. We may see that the main narrative, interrupted after *v.*^{25b}, is probably *v.*^{42a}, 'And, on the morrow, the people of Ga'al went out to the field,' represents the redactor's attempt to continue the Ga'al-narrative. It is plausible to infer that the narrative came forth from the city,—an event which resumed by R^{JE} in *v.*^{42b}. The rest of the narrative anticipates *v.*^{43b}, 'the people came out to the field,' which clearly took place *after* the ambush as recorded in *v.*^{43a}. The rest of the narrative for a few later additions has been derived, as Mo.

We conclude, then, with Mo., that the *vv.*²⁶⁻⁴¹ is derived from a distinct source. It appears to be homogeneous; and, except for a few notes on *vv.*¹⁶⁻²⁰, *v.*²², may well have been derived from a single ancient source.*

The source of the main narrative appears to be E: cf. the use of the name Jerubba'al, which elsewhere belongs to E (cf. p. 178); 'Ēlōhīm 'God,' and not 'Yahweh,' *vv.*^{7.23.56.57}; 'with its due integrity' (*בְּאֵמֶת וּבְתִמְיֹם*) *vv.*^{16.19}, a phrase which only occurs elsewhere in the Bible; 'serveth' (lit. 'as thy hand shall find,' *כַּאֲשֶׁר תִּמְצָא יָדְךָ*) which belongs to E; and 'then do as occasion serveth' (lit. 'then do as occasion serveth') which belongs to J. The source of the main narrative appears to be E: cf. the use of the name Jerubba'al, which elsewhere belongs to E (cf. p. 178); 'Ēlōhīm 'God,' and not 'Yahweh,' *vv.*^{7.23.56.57}; 'with its due integrity' (*בְּאֵמֶת וּבְתִמְיֹם*) *vv.*^{16.19}, a phrase which only occurs elsewhere in the Bible; 'serveth' (lit. 'as thy hand shall find,' *כַּאֲשֶׁר תִּמְצָא יָדְךָ*) which belongs to E; and 'then do as occasion serveth' (lit. 'then do as occasion serveth') which belongs to J.

Ch. 9, like *chs.* 16-21, exhibits no trace of the hand of R¹ who clearly did not enter into his pragmatic scheme, as outlined in *ch.* 2⁶⁻³⁶, and worked out in the histories of the 'major' Judges. R^{E2} had the story before him in the earlier composite narrative which he employed (the work of R^{JE}) is proved, however, by the fact that he knew it, and composed a short summary (*ch.* 8³³⁻³⁵) which was intended to take its place. For R^{E2} Abimelech was very far from being a divinely appointed Judge. The narrative relating his reign had no interest in connexion with R^{E2}'s religious philosophy of history, except as illustrating (from his point of view) a period of apostasy which could fitly be summarized in a few sentences. The re-insertion of the story into the Book of Judges must have been due to the last editor (R^N; cf. *note* introductory to 8²⁹⁻³²), who seems to have reckoned Abimelech among the Judges: cf. the reference in the introduction to the first of the 'minor' Judges, 10^{1a}, whose insertion in the book appears to have been due to this editor (cf. *note ad loc.*)

* The attempts which have been made by Winckler, Bu., and No. to present a more detailed analysis are not convincing; any more than is the argument that the whole narrative is derived from a single source.

9. 1. E And Abimelech the son of Jerubba'al went to Shechem unto his mother's brethren, and spake unto them and unto all the clan of the house of his mother's father, saying,

9. 1. *Shechem*. The Roman Flavia Neapolis, and the modern Nâblus,* situated thirty miles north of Jerusalem in the fertile valley which runs east and west between Mt. 'Ebal on the north and Mt. Gerizim on the south, forming an easy pass between the maritime plain and the Jordan valley. Placed at a point at which many important roads converge, the city must always have exercised considerable importance: cf. Smith, *HG.* pp. 332 ff. The name Shechem, denoting *shoulder*, probably refers to the position of the city on the watershed, 1870 feet above the Mediterranean.

The early history of the relations between Israelites and Cana'anites at Shechem is involved in great obscurity. The city was occupied, prior to the arrival of the ancestors of Israel west of Jordan, by the Cana'anite clan of the B'nê-Ḥamor. The natural advantages which it enjoyed rendered it the principal city of Central Palestine, and the earliest Israelite clans (the Patriarchs) gravitated thither on their arrival in Cana'an, and lived on terms of friendship and alliance with the B'nê-Ḥamor (Gen. 12^{6,7} J, 33¹⁸ P, 33^{19,20} E). These relations were broken by the treacherous aggressions of the Sime'on and Levi clans (Gen. 34[†]), which seem to have provoked such retaliation on the part of the Cana'anites of the district as decimated and dispersed these Israelite clans, the remnant of them seeking refuge in other parts of the land (Gen. 49⁵⁻⁷ J). On the arrival of the Joseph-clans in Cana'an and their settlement under Joshua', Shechem lay within the district which they overspread. North Israelite tradition recorded that the bones of Joseph were brought up from Egypt and buried in a plot of ground at Shechem acquired by purchase from the B'nê-Ḥamor (Gen. 33¹⁹ E, 50²⁴⁻²⁶ E, Ex. 13¹⁹ E, Josh. 24³² E); and according to a later tradition (Josh. 24¹ E²) Shechem appears as the rallying-place of 'all the tribes of Israel' on the occasion of Joshua's farewell charge. Thus we are probably justified in assuming that the early relations between the Joseph-tribes and the B'nê-Ḥamor were of a friendly character. We find, however, that, in the time of the Judges, Shechem is still in possession of the Benê-Ḥamor, the burghers or free-born 'owners of Shechem' (בְּעָלֵי שִׁכְמָה) clearly belonging to this Cana'anite clan: cf. 9²⁵ *note*. The services rendered

* With Nâblus as the Arabized form of Neapolis, cf. Yerablus for Hierapolis.

† This narrative is clearly a thinly-veiled description of tribal relations between Israelites and Cana'anites, at first friendly, then hostile. The two sources employed in the chapter bear respectively the characteristics of J and P; but there are difficulties in the way of correlating the J narrative with the main document J: cf. Skinner, *Genesis* (ICC.), pp. 417 f.

2. 'Prithee speak in the ears of all the citizens of Shechem, "Which is better for you, that seventy men should rule over you, even all the sons of Jerubba'al, or that one man should rule over you? Remember also that I am your bone and your

by Jerubba'al in ridding the country of the Midianite pest benefited Israelite and Cana'anite alike, and the Bⁿê-Ḥamor at Shechem were thereafter willing to acquiesce in Israelite predominance in the district as represented by Jerubba'al and his sons. Abimelech's rise to power was achieved through the stirring up of racial antipathies between Cana'anite and Israelite; but the pure-blooded Bⁿê-Ḥamor were not able for long to acquiesce in the domination of the half-bred upstart ruler, and the friction which ensued resulted in the destruction of Shechem, as related in our narrative.

When next we hear of Shechem, it is an Israelite town in possession of the Joseph-tribes, and still holds the position of importance which was the natural outcome of its physical advantages; so that it appears in 1 Kgs. 12¹ as the city to which 'all Israel' resorts in order to anoint a successor to Solomon. The tradition in Gen. 48²² E—where the aged Israel on his death-bed bequeaths to Joseph one *shoulder* (Heb. Shechem) above his brethren, which he claims to have captured from the hand of the Amorite with his sword and with his bow—may have arisen no earlier than the time of David or Solomon, as a northern Israelite explanation of the way in which the most favoured spot in Canaan came into the possession of the Joseph-tribes—a special gift made by the common father of the Israelite clans to his most favoured son. The contrast, however, with the other E tradition noticed above—which speaks of rights at Shechem acquired by purchase from the Bⁿê-Ḥamor—is very striking—and indeed inexplicable. Cf. further *Introd.* p cxi.

The fact that Shechem was not easily defensible against an outside foe rendered it unsuitable as the capital of the organized kingdom of Northern Israel; and it was for this reason that 'Omri built Samaria on a site five miles to the north-west which his military eye selected as peculiarly adapted for a fortified capital city.

2. *the citizens of Shechem.* Heb. בְּעָלֵי שֵׁ, lit. the *owners* of Shechem. The same term is used of the citizens of Jericho (Josh. 24¹¹ E), of the high places of Arnon (Num. 21²⁸ E*), of Gibé'ah (Judg. 20⁶), of Ké'ilah (1 Sam. 23^{11,12}), and of Jabesh of Gile'ad (2 Sam. 21¹²).

your bone and your flesh. The same expression is used in Gen. 29¹⁴ J, 2 Sam. 5¹, 19^{12,13} (ḡ 13.11); cf. Gen. 2²³ J. As belonging to

* Here, however, ḡ is almost certainly corrupt. We need a verb in place of בְּעָלֵי—possibly בָּרָה 'It (the fire) hath consumed the high places, etc.' ḡ καὶ κατέπιεν seems to have read בָּלָע or וַתִּבְלָע.

flesh.”’ 3. So his mother’s brethren spoke concerning him in the ears of all the citizens of Shechem all these words: and their heart inclined after Abimelech, for they said, ‘He is our brother.’ 4. And they gave him seventy shekels of silver from the temple of Ba’al-berith; and Abimelech hired therewith worthless and reckless men, and they followed him. 5. And he came unto his father’s house at ‘Ophrah, and slew his brethren the sons of Jerubba’al, even seventy men, upon one stone: but Jotham the youngest son of Jerubba’al was left, because he hid himself.

6. And all the citizens of Shechem and all Beth-millo

his mother’s clan and not to his father’s (cf. 8³¹ *note* on ‘his concubine, etc.’), Abimelech could claim that he was of one race with the Shechemites (the B’nê-Hamor; cf. v. 28), in contrast to Jerubba’al’s other seventy sons who were of Israelite descent (cf. 8³⁰ *note* on ‘that came out of his loins’).

4. *from the temple, etc.* The temple, like that at Jerusalem (cf. 1 Kgs. 7⁵¹, 14²⁶, 15¹⁸, *al.*), contained a treasury in which were accumulated the gifts and fees of worshippers. Possibly also it may have been the repository of public treasure: cf. the *θησαυροδομος* of the Parthenon at Athens, and the *aerarium* of the Temple of Saturn at Rome (cited by Stu.).

Ba’al-berith. Cf. 8³³ *note*.

worthless. Heb. *rêkîm*, lit. ‘empty.’ Cf. *ch.* 11³ *note*.

reckless. Heb. *pôh^azîm*, a participial form, occurs once again in Zeph. 3⁴; a cognate subs. *paḥ^azûth* is found in Jer. 23³²†; and subs. *pâḥaz* in Gen. 49⁴†. In the latter passage it is said of Re’uben that he is ‘*pâḥaz* (“wantonness,” *i.e.* “wanton” or “unbridled”) like water.’ The cognate root in Ar. means ‘to be insolent,’ and in Aram. ‘to be lascivious’—facts which suggest that the original idea may have been *to overpass bounds, be uncontrolled* (cf. the comparison with *water*). Cf. Hiph’il *hiphḥîz* in Ecclus. 8², 19².

5. *upon one stone.* The statement (repeated in v. 18) is striking. Possibly the stone may have been the official place of execution. The great stone used by Saul for the slaughter of cattle in conformity with sacrificial rule (1 Sam. 14³³ f.) is compared by Mo., who thinks that ‘the very conformity to the precautions taken in slaughtering animals in the open field shows that the motive was to dispose of the blood, in which was the life of his victims, in such a way that they should give him no further trouble. It is an instructive instance of the power of animistic superstitions.’

6. *Beth-millo.* Cf. v. 20. A place of this name in the kingdom of Judah is mentioned in 2 Kgs. 12²⁰, 21²¹. The Millo at Jerusalem

assembled themselves together, and went and made Abimelech king by the terebinth of 'the standing-stone' which was in Shechem. 7. And men told Jotham, and he went and stood on the top of Mount Gerizim, and lifted up his voice, and cried, and said to them,

‘Hearken unto me, Shechem’s citizens,
That so God may hearken unto you.

formed part of the fortifications of the City of David ; and if the word is rightly explained as from the causative stem of the verb *mālē* ‘to be filled,’ it must be understood as meaning something which *fills* or *banks up*, and so possibly an *earthwork* : cf. Talmudic *mûlîthā*, ‘filled-up ground’ ; Bab. *mulû*, ‘earthwork.’ Probability, however, favours the view that the Jerusalem Millo was more than a simple earthwork—rather, perhaps, a massive fortification on the northern side of the city where such protection was specially needed. If, in our passage, Beth-millo has some such sense as ‘House (place) of the fortress,’ it may have been identical with ‘the Tower of Shechem’ (apparently distinct from the city of Shechem) mentioned in *z.*⁴⁶.

the standing stone. Reading *הַמַּצֵּבָה* with most moderns, in place of *מִצֵּב* which only occurs again in Isa. 29³ in the sense of a *balisade* or *entrenchment*. Possibly the *maṣṣēbhā* may have been the stone which tradition stated to have been set up by Joshua’ (Josh. 24²⁶ E).

7. *stood on the top, etc.* Not actually on the summit, which is nearly 1000 feet above Shechem ; but on one of the lofty precipices overhanging the city (cf. Thomson, *LB.* p. 473) from which he was able to make himself heard from below, and at the same time to beat a safe retreat after speaking.

8-15. The parable is intended to contrast the position of Jerubba’al and his sons with that of the mere adventurer Abimelech, and to predict that nothing but misfortune can result from the course which has been taken by the Shechemites. The olive, the fig-tree, and the vine, which are invited in succession to accept the kingship, represent men who, like Jerubba’al, possess a status which has been won by service for the public good. These have business more important than the acceptance and exercise of the office of kingship. On the other hand, the buckthorn, a low-growing and worthless shrub, is unequal to the task of affording shelter to the trees ; but only too likely to be the cause of a forest-fire which may end in the destruction of all.

The parable is cast into a rhythmical form which is very well marked. After the summons to attend (*z.*^{7b}), which forms a couplet of 3-beat stichoi, there follow four strophes, corresponding to the

8. Time was when the trees set out
To anoint o'er themselves a king;
And they said to the olive, "Reign thou over us."
9. But the olive said to them,
"Shall I leave my fatness
 「whereby¹ men honour God [],
And go to wave over the trees?"

applications to the four different trees. The first of these contains six stichoi; the second and third, five stichoi; and the fourth, seven stichoi. Most of the stichoi contain 3 beats; but stichos 3 of strophe 1 contains 4 beats, and in each strophe the response of the tree is given in a long stichos which exhibits 5, or 2 + 3 beats (in strophe 4 perhaps 6, or 3 + 3, beats). The English rendering is intended, as nearly as possible, to reproduce the rhythm of the original.*

8. *Time was . . . set out.* The Heb. says literally 'Going they went,' i.e. the action is introduced with some emphasis, much as we might say, 'Once upon a time the trees went.'

the olive. The olive, the fig, and the vine are the staple products of Palestine, upon which its agricultural wealth and prosperity mainly depend. Cf. G. A. Smith, *Jerusalem*, i. pp. 299 ff.

9. *Shall I leave.* Lit. 'Am I to have left,' the Perfect tense being idiomatically used in Heb. 'to express astonishment at what appears to the speaker in the highest degree improbable': cf. Driver, *Tenses*, § 19.†

whereby, etc. Reading בּוֹ in place of בִּי with עַל הָיָה, וְ 'quâ, מֵמֵנִי 'from which,' and omitting וְאֲנִשִּׁים. This latter, which spoils the rhythm by causing one beat too many, has obviously been introduced from וְאֲנִשִּׁים, 'which rejoiceth God and men.' The Imperfect כִּבְרוּ is impersonal; and is therefore rendered 'men honour.'

men honour God. The reference is to the use of oil in sacrifice and worship.

to wave. The Heb. נָדָה denotes the *swaying* motion of the

* The scheme adopted above agrees in nearly every detail with that offered by Sievers (*Metrische Studien*, i. pp. 388 f.), though worked out independently. The only difference is that Sievers makes the response of the trees in each case a 6-beat line; in v. 13a by accepting בִּי as it stands, and in vv. 11aβ, 13aβ by inserting אֲנִי after הַחֲרָלְתִּי. Cf. also Rothstein, *ZA.* xxvi (1914), pp. 22 ff.

† The form הַחֲרָלְתִּי is very anomalous. The most probable explanation of it is that חֲרָלְתִּי is the Perfect Ḳal, and that the Ḳāmeṣ of the first syllable, falling between the tone and the countertone, is weakened into ḥāteph Ḳāmeṣ through loss of emphasis: so G-K. § 63 k. The view that the form should be vocalized as a Hiph'il or Hoph'al is less probable.

10. Then said the trees to the fig-tree,
"Come *thou*, reign over us."
11. But the fig-tree said to them,
"Shall I leave my sweetness,
and my goodly produce,
And go to wave over the trees?"
12. Then said the trees to the vine,
"Come *thou*, reign over us."
13. But the vine said to them,
"Shall I leave my must,
which rejoiceth God and men,
And go to wave over the trees?"

branches in the wind ; cf. Isa. 7². This is 'represented as a gesture of authority' (Mo.).

13. *must*. Heb. *tîrôš*, which is frequently coupled with *dāghān*, 'corn,' and *yîshûr*, 'fresh oil,' as a natural product of the land, seems commonly to denote the grape-juice when first trodden out from the grapes. In Joel 2²⁴, Prov. 3¹⁰ it is mentioned as filling the *vats*; and the term *yékebîh*, 'vat,' denotes the trough into which the juice flowed after being trodden out in the *gath* or 'wine-press'; cf. *ch.* 6¹¹ *note*. The connexion in which *tîrôš* is used in the present passage ('which rejoiceth, etc.') implies that it is regarded as an *exhilarating* beverage; and this suggests that the term may have been used of wine in some degree *fermented*, as it certainly is in Hos. 4¹¹, where it is coupled with 'whoredom' and 'wine' (*yáyîn*) as something which 'taketh away the heart' (i.e. the *intellect*). The fact is well known that the ancients were in the habit of making a light wine by checking the process of fermentation at an early stage; and it may be assumed that *tîrôš* may denote such a light wine, as well as the unfermented juice when first pressed out from the grapes.

The view that *tîrôš* denotes the *vine-fruit* and not a liquid is sufficiently refuted by the passages from Joel and Prov. already quoted. The grapes in their natural state were placed in the *gath*, and it was the *juice only* which flowed into the *yékebîh*, the purpose of which was to separate the liquid from the solid matter. Cf. further Driver in *Amos* (*Camb. Bib.*), pp. 79 f.

God and men. Or possibly 'gods and men.' The allusion is to the use of wine in libations at sacrificial feasts, when the god, as well as his worshippers, was thought to be cheered by the beverage.

14. Then said all the trees to the buckthorn,
 "Come *thou*, reign over us."
15. And the buckthorn said to the trees,
 "If in truth ye wish to anoint
 me as a king over you,
 Come ye, take refuge in my shadow :
 But if not, then come fire from the buckthorn,
 And devour the cedars of Lebanon."

16. Now, therefore, if ye have dealt in truth and in integrity, in that ye have made Abimelech king,^{RJE?} and if ye have dealt well with Jerubba'al and with his house, and if ye have done to him according to his deserts; 17. (in that my father fought for

15. *the buckthorn.* A variety of *Rhamnus* (so \mathfrak{E} , \mathfrak{F}), probably *Rhamnus palaestina*, a low and straggling bush which is common in the hill-country of Palestine.

Come ye, take refuge, etc. The irony of the parable culminates in the absurdity of the invitation, which the buckthorn issues in all seriousness.

16-20. The application fits somewhat loosely on to the parable; but such lack of strictly logical connexion as exists is a common characteristic of Oriental reasoning. The main point of the parable is that the Shechemites had chosen a king who could not command confidence and respect; but who, if treated otherwise than in good faith (בְּאֵמֶת $\nu.15$), was capable of compassing their ruin. The application takes up the theme of the good faith of the Shechemites (בְּאֵמֶת $\nu.16$), and points out that this has been markedly absent in their dealings with Jerubba'al, a man who was, in the highest degree, worthy of their confidence and gratitude. *A fortiori*, therefore, it was most unlikely that good relations between them and Abimelech would last for long; and, once they failed, the ruin of both parties was bound quickly to ensue. This moral is emphasized in the narrative which follows: $\nu\nu.$ ^{23.24.36.37.}

Doorn., Bu., Mo., and others improve the connexion between parable and application by marking $\nu\nu.$ ^{16b-19a} as a later addition. The reference of בְּאֵמֶת 'in truth' or 'in good faith,' in $\nu.16$ is then the same as in $\nu.15$, *i.e.* it refers to their good faith *towards Abimelech*: 'If ye have made Abimelech king, intending to act towards him in good faith, I congratulate you; but if not, the parable teaches you what to expect.'

16. *according to his deserts.* Lit. 'according to the dealing of his hands.'

you, and risked his life, and delivered you from the hand of Midian; 18. and ye have risen up against my father's house this day, and have slain his sons, even seventy men, upon one stone, and have made Abimelech, the son of his bond-maid, king over the citizens of Shechem, because he is your brother); 19. if ye have acted in truth and in integrity with Jerubba'al and with his house this day,^E rejoice in Abimelech and let him also rejoice in you. 20. But if not, let fire come forth from Abimelech, and devour the citizens of Shechem and Beth-millo; and let fire come forth from the citizens of Shechem and Beth-millo, and devour Abimelech.' 21. And Jotham ran away and fled, and went to Be'er, and dwelt there, on account of Abimelech his brother.

22. And Abimelech was prince^{RJE} over Israel^E three years. 23. And God sent an evil spirit between Abimelech and the

17. *risked his life.* Lit. 'cast his life *in front*' or '(so as to be) *at a distance*' (cf. the use of מִנְּקָר in Deut. 32⁶², 2 Kgs. 2¹⁵, *al.*); *i.e.* exposed it to the utmost risk, without a thought of personal safety.

19. *his bond-maid.* The Heb. 'āmā implies a slave-concubine, such as were Hagar to Abraham, and Zilpah and Bilhah to Ja'cob. As we have seen, however, *ch.* 8³¹ implies that Abimelech's mother was a free-woman, dwelling with her clan at Shechem. The misconception involved in the present passage is a point in favour of its later date.

20. *let fire come forth from the citizens, etc.* That the buckthorn, in destroying the other trees, would itself perish, is implied though not stated in the parable.

21. *Be'er.* The place intended may have been el-Bireh, twenty-two miles south of Shechem and eight miles north of Jerusalem, which has been supposed to be the site of Be'ereth of Josh. 9¹⁷, *al.* The name, which means 'well,' was, however, doubtless of frequent occurrence in ancient times; just as its modern Ar. equivalent is at the present day.

22. *was prince over Israel.* On this statement, as implying a later conception than that of the original narrative, cf. *Introd.* to chapter, p. 267. The early narrative pictures Abimelech as possessing the authority of a local sheikh over Shechem and the neighbouring district.

23. *God sent an evil spirit.* Cf. the evil spirit sent by God upon Saul, 1 Sam. 16¹¹, 18¹⁰; and the spirit divinely commissioned to deceive Ahab, in order that he might go up and fall at Ramoth-Gilead, 1 Kgs. 22^{19 ff.} The view that God, from motives of displeasure,

citizens of Shechem; and the citizens of Shechem dealt treacherously with Abimelech. 24. 'To bring¹ the violence done to the seventy sons of Jerubba'al, and to lay their blood upon Abimelech their brother, who slew them, and upon the citizens of Shechem, who encouraged him to slay his brethren. 25. And the citizens of Shechem set men in ambush upon the hilltops to his hurt, and they robbed all that passed by them on the way: and it was told Abimelech.

may incite men to their own ruin, is frequent in the O.T. Thus He hardens Pharaoh's heart (*hikbīdh*, lit. 'made heavy,' Ex. 10¹ J; *hizzēkh*, lit. 'made strong,' Ex. 4²¹, 10^{20,27} E or R^{JE}; 9¹², 11¹⁰, 14^{4,8,17} P; *hikšā*, lit. 'made hard or rigid,' Ex. 7³ P), and similarly He prompts Sihon, king of the Amorites, to resist Israel in order that He may give him into their hands, Deut. 2³⁰. So too, in 2 Sam. 24¹, He is pictured as inciting David to a pernicious action; in Isa. 19^{2,14} He is said to stir up civil strife in Egypt, and to mingle a spirit of perverseness in the midst of her; and in Ezek. 14⁹ He deceives the false prophet to his own destruction.

24. *to bring*. Reading לְהָבִיא after Ἐ τοῦ ἐπαγαγεῖν, with Grä., Oet., La., in order to avoid the very awkward change of subject in וַיָּבִיאוּ and the following לָשׁוֹם—'that the violence . . . might come, and to lay their blood, etc.' The alternative is to follow Mo., Bu., No., Oort in retaining וַיָּבִיאוּ and deleting לָשׁוֹם as the introduction of a scribe who missed the verb governing דָּמָם—'That the violence done to the seventy sons of Jerubba'al and their blood might come, etc.'

encouraged him. Lit. 'strengthened his hands.'

25. *set men in ambush, etc.* The Shechemites began to set armed bands in the mountains to rob the passing caravans, thus enriching themselves at the cost of Abimelech either by injuring his trade or by interfering with the dues which he was accustomed to exact for the safe conduct of merchandise through his territory. The force of the *Dativus incommodi* לוֹ 'to his hurt' is very idiomatic, and may be compared with the use of the preposition in ch. 3²³, 7²⁴, 12⁵, 'take the fords of the Jordan to the detriment of' (so, against) a foe. R.V. renders 'set liers in wait for him' (cf. ch. 16² וַיִּצָּבְרוּ לוֹ); and this is explained by Cooke, 'They hoped to catch Abimelech, who apparently was non-resident, and failing him, they plundered his friends.' This is very improbable.

and it was told Abimelech. The sequel to this statement follows in v.⁴³, after its repetition with slight variation in v.^{42b}, as already

26. J And Ga'al the son of [ʿObed] came with his brethren, and they went over into Shechem; and the citizens of Shechem put their trust in him. 27. And they went forth into the field, and cut their vintage, and did the treading, and held a praise-festival,

explained (pp. 267 f.). Otherwise, if we assume the narrative of *vz.*^{26 ff.} to be of a part with *v.*²⁵, the information conveyed to Abimelech seems to have produced no result.

26. *Ga'al*. Wellh. vocalizes as גֹּאֵל Go'al, comparing Ar. *ḡu'al* 'dung-beetle': *Isr. u. Jüd. Gesch.*², p. 44. Mo. (*SBOT.*) notes that (according to Lane) *ḡu'al* in Ar. is 'also applied to a black and ugly and small man, or to a contentious one.' This vocalization is favoured by Jos. Γυάλης (*Ant.* v. vii. 3 f.).

'Obed. Vocalizing עֹבֵד with ʾ, in place of עֲבָד. The same form is suggested by 𐤂𐤓𐤁𐤀 Iωβηλ, which, as Mo. points out, is probably an uncial error IΩBHA for ΩBHA.* The form Ωβηδ occurs in HP. 30, Ωβιδ HP. 56. 𐤂𐤓𐤁𐤀 Aβεδ supports 𐤂𐤓𐤁𐤀. The participial form 'Obed, 'server,' i.e. 'worshipper' of a deity, is well known as a proper name; whereas the substantive 'Ebed, 'servant,' though used in composition in 'Abdi, 'servant of Yah,' 'Abdiel, 'servant of God,' does not occur elsewhere by itself, and is unlikely to have been so used. A less probable view has been put forward by Kue. (*Ond.* § 19⁵) and others, who regard Iωβηλ as pointing to an original יֹבְעֵל 'Yahweh is Ba'al'—a name which was offensive to later thought, and was therefore altered in contempt into 'Ebed, 'servant.' With this view is involved the supposition that Ga'al, as the son of a worshipper of Yahweh, must have been an *Israelite*, whose object was to stir up the Israelite population of Shechem against the rule of the Canaanite Abimelech. This, however, is plainly refuted by the fact that the men whose ear Ga'al succeeds in gaining are 'the citizens of Shechem' ('בְּעָלֵי שֵׁ', *v.*²⁶), i.e. the same people who, according to *vz.*²⁶, made Abimelech king on the ground that he was their own kinsman ('your bone and your flesh,' *v.*²).

27. *cut their vintage*. Here the plural of *kérem*, 'vineyard,' is used by metonymy of the *produce* of the vineyard, as is indicated by the fact that it is coupled with the verb *bāšar*, which is the regular term for *cutting grapes*: cf. Deut. 24²¹.

a praise-festival. If rightly connected with *hillēl*, 'to praise,' Heb. *hillûlîm* here seems to denote a festival of thanksgiving to the deity. The term occurs only once besides, in Lev. 19²⁴ H, in the phrase

* The form Iωβηδ, for עֲבָד Ωβηδ, occurs in 𐤂𐤓 in 1 Chr. 2 12(twice), 27, 38, 11 47 (𐤂𐤓 Iωβηθ), 26 7, 2 Chr. 23 1.

and went into the house of their god, and did eat and drink, and cursed Abimelech. 28. And Ga'al the son of 'Obed¹ said, 'Who is Abimelech, and who is Shechem, that we should serve him? 'should¹ not the son of Jerubba'al and Zebul his officer 'serve¹ the men of Hamor, the father of Shechem? but why

kōdeš hillūlīm, 'a holy thing of praise'; * the reference here being to the produce of fruit-trees in the fourth year, when it was consecrated to Yahweh in token of thanksgiving. In Aram. *hillūlā* denotes a *marriage-song* (cf. the use of the Hoph'al *hullālū* in Ps. 78⁶³). Ar. *tahlīl* is used of a *shout of praise* (ordinarily applied to the pronouncing of the formula, 'There is no god but God'). This term, however, is connected by Wellh. with *hilāl* 'the new moon,' and is supposed by him to have been associated originally with the festival in honour of the new moon: cf. *Reste arab. Heidenthums*, p. 108.

28. *Who is Abimelech, etc.* Reading Imperfect עֲבָדוּ in place of Imperative עֲבְדוּ.

As the text stands in \mathfrak{H} , Ga'al's speech can only be rendered as in R.V.: 'Who is Abimelech and who is Shechem, that we should serve him? is not he the son of Jerubba'al? and Zebul his officer? serve ye the men of Hamor the father of Shechem: but why should we serve him?' Here 'Shechem' seems to stand as the rhetorical equivalent of 'Abimelech': cf. 1 Sam. 25¹⁰, 'Who is David, and who is the son of Jesse?' This is clearly the view adopted by \mathfrak{C} , which renders *καὶ τίς ἐστὶν υἱὸς Συχεμ* for וְמִי יַעֲבֹד. We can hardly assume, however, that a reading בְּנֵי-יַעֲבֹד lies behind the \mathfrak{C} rendering; since, as Robertson Smith (quoted by Mo.) has rightly pointed out, this expression is never used in the sense *Shechemite*: and that 'Shechem' by itself should be employed as a synonym of 'Abimelech' is incredible. The alternative explanation is to take 'Shechem' as an antithesis to 'Abimelech'—'we Shechemites'; but, as the text stands, this is excluded by the fact that there is no similar antithesis in the answer which Ga'al supplies to his own question (we should expect, 'is he not the son of J., etc., while we are, etc.'). Further, the Imperative עֲבְדוּ 'serve ye' should naturally be followed by the 2nd person plur., 'but why should ye serve him'; and the occurrence of the 1st person, 'but why should we, etc.,' is at least very awkward. And again, in וְלֵמָּה נַעֲבֹדוּ אֲנַחְנוּ the emphasis on the *subject* of the verb, as indicated by the personal pronoun, is very great—'but why should *we* serve him?' i.e. *we* in implied contrast to some other

● Probably we ought to place the *'athnah* upon *kōdeš*, and render, 'And in the fourth year all its fruit shall be holy (lit. a holy thing), a praise-offering to Yahweh.'

should *we* serve him? 29. Oh, would that this people were under my hand! then would I remove Abimelech, ¹and would say¹ to Abimelech, "increase thine army, and come out."

person or persons; whereas, if the earlier part of the sentence is correct as it stands in **ח**, we should expect the emphasis to be thrown upon the *object* of the verb—"but why should we serve *him*?" (in contrast to 'the men of H̄amor, etc.').

Adopting our simple emendation, the following explanation is plausible. The speech contrasts the antecedents of Abimelech and Shechem (*i.e.* the *citizens* of Shechem, or free-born Bⁿê-H̄amor)—'What is there in Abimelech's antecedents as compared with ours, that we (pure-blooded Bⁿê-H̄amor) should serve him (the half-breed)? Ought not the relations to be reversed, and Abimelech and his place-man Zebul to serve the hereditary owners of Shechem?' This is substantially the explanation of Mo., which has been adopted by Bu., La., etc.; except that these scholars read the Perfect עָבְדוּ in place of **ח** עָבְדוּ—'Did not the son of J. and Z. his officer serve the men of H̄., etc.?' *i.e.* 'he himself was formerly a subject of the old H̄amorite nobility of Shechem.' It may be urged, however, against this reading that it implies that, prior to the election of Abimelech as king, the ruling class in Shechem had been the Bⁿê-H̄amor; whereas, as a matter of fact, *vv.*^{1,2} represent the Bⁿê-H̄amor as acquiescing in time past in the rule of the Israelite Jerubba'al and his sons.

Upon the various other explanations and emendations of the passage which have been offered, cf. Mo. *Comm.*, and especially the same writer's very full note in *SBOT.* pp. 46 f. For the most part they depend upon the mistaken assumption that Ga'al was an Israelite, and that the rebellion which he was fomenting was an upheaval of the Israelites against the rule of the Shechemite Abimelech. Upon this theory, cf. *note* on "Obed," *v.*²⁶.

29. *under my hand.* Lit. 'in my hand,' *i.e.* subject to my authority. *and would say.* Reading וַאֲמַר with **Ἐ** καὶ ἐπὶ and most moderns in place of **ח** וַאֲמַר 'And he said to Abimelech.' It is clear from what follows that Ga'al's words are merely a boast which was not carried into execution until his hand was forced, as related in *v.*²⁹.

Bu., however, thinks that, if the words 'and would say to A. "Increase thine army, etc.,"' really formed part of Ga'al's boast, the *challenge* which they contain would have preceded and not followed its *result* as embodied in the words 'then would I remove A.' He therefore suggests that the words 'Increase thine army, etc.,' originally formed part of Zebul's message to Abimelech, as related in *vv.*^{32 f.}, and were later on erroneously inserted in their present position, with the introduction 'and he said to A.' This objection can hardly

30. And when Zebul, the governor of the city, heard the words of Ga'al the son of [Obed], his anger was kindled. 31. And he sent messengers to Abimelech at [Arumah], saying, 'Behold,

be maintained. It is obvious that Ga'al may first have stated the main fact, viz. that he would soon get rid of Abimelech if he had the chance, and then have gone on to boast *how* he would attain this end—by challenging him to pitched battle.

30. *Zebul the governor of the city.* It is clear from the narrative that Abimelech did not *reside* at Shechem, but at the neighbouring city of Arumah: cf. vv. 31. 41, with *note* on the former verse. Zebul appears to have been his representative at Shechem. Whether he was a Canaanite or an Israelite cannot be determined.

31. *at Arumah.* Reading בְּאַרְוִמָּה (or בְּאַרְוָמָה; cf. v. 41) in place of בְּתִרְוִמָּה. R.V.'s rendering of this latter, 'craftily,' is the interpretation of שׁוֹטְטִים. It presupposes that a *ἀπ. λεγ. tormā*,* from the root *rāmā*, 'to deceive,' is used in place of the normal *mirmā* or *tarmīth* in the sense 'deceit.' A.V., 'privily,' follows the majority of the versions: Ἐ ἐν κρυφῇ, Ἑ 'clam,' ט ברז, Ar. سراً. This rendering likewise presupposes derivation from the root *rāmā*, upon the view that an expression properly meaning 'in deceit' is used in the sense 'in secret.' Thus A.V. adds marg. 'Heb. craftily.' So Rashi, Kimchi (first explanation), and the older commentators generally. Granted, however, that *b^e-tormā* is the equivalent of *b^e-mirmā*, such a sense as 'privily' is illegitimate; the only possible meaning of the statement being 'that Zebul sent to Abimelech a *deceptive*, and therefore an *erroneous* message' (Stu.). But this is excluded by the context, which makes it clear that the message embodied a true statement of affairs.

Kimchi (second explanation) and Levi ben-Gershon rightly divined that what we should expect is the name of the place at which Abimelech was residing; and observing that Arumah is named as his residence in v. 41, supposed that Tormah and Arumah are variant names of the same city. We may follow most moderns in concluding that תְּרִמָּה represents a simple corruption of the latter name. Ἐ^{AL}, Σ^h μετὰ δώρων, i.e. בְּתִרְוִמָּה, suggests that the Greek translator may have used a text in which the ו was written as in בארומה, v. 41.

* The form תְּרִמָּה is strange if derived from רָמָה. König (*Lehrgebäude* I. ii. p. 193) groups it with תִּצְנָה from אָנָה Judg. 14⁴ תִּצְנָה from יָנָה Prov. 10¹, 14¹³, 17²¹, Ps. 119²⁸.

Ga'al the son of 'Obed' and his brethren are come to Shechem, and, behold, 'they are stirring up' the city against thee. 32. Now, therefore, arise by night, thou and the people who are with thee, and lie in wait in the field. 33. And in the morning, when the sun is up, thou shalt rise early and make an onset against the city: and, behold, he and the people who are with him will come forth unto thee, and thou shalt do to him as occasion serveth.'

34. And Abimelech arose, and all the people who were with him, by night, and they lay in ambush against Shechem in four bands. 35. And Ga'al the son of 'Obed' went out, and stood in the entry of the gate of the city; and Abimelech rose up, and

The site of Arumah is unidentified. The modern el-'Ormeh (written with ע and not א *) about five miles south-east of Shechem has been suggested.

are stirring up. Reading מְעִירִים with Frankenberg, Bu., Mo. (SBOT.), No., in place of צָרִים , which can only mean 'are besieging,' and is so rendered by the Versions. As Mo. points out, however, the Heb. construction is irregular,† and the sense 'are inciting to hostility,' which has been adopted by many commentators, is illegitimate.

33. *make an onset.* The Heb. verb pāšat , which occurs again in our narrative in *v.*⁴⁴ (twice), expresses (as appears from the context in these and other occurrences) the making of a sudden and unexpected raid or attack. The connexion with Heb. pāšat 'strip off' (one's garment) is obscure. The explanation offered by BDB—'*put off* (one's shelter), i.e. *make a dash* (from a sheltered place)'—is very precarious.‡

as occasion serveth. Lit. 'as thy hand shall find.'

34. *four bands.* Lit. 'four heads': cf. p. 181. So *v.*^{37b}. The expression, though most frequent in J, is used in the parallel narrative E in *vv.*^{43f}.

* Substitution of ע for א is seen in the modern 'Askalân for ancient 'Ashkelon, and in 'Ānâ for 'Ono. The converse change is seen in 'Endûr for 'En-dor.

‡ We should expect צָרִים עַל הָעִיר , not צָרִים אֶת הָעִיר . The only other occurrence of צֹר followed by אֶת of the city is 1 Chr. 20¹ $\text{וַיִּצַר אֶת רֵבֶה}$, where || 2 Sam. 11¹¹ has the normal עַל .

§ New Heb. pāšat , Aram. pāšat , mean 'to extend,' and also 'to make plain'; while Bab. pāšātu has the sense 'expunge, obliterate,' *sc.*, *writing* by smearing or covering it with clay. The bond of connexion (if such exists) between the various senses of the root requires investigation.

the people who were with him, from the ambushade. 36. And when Ga'al saw the people, he said unto Zebul, 'Behold, people are coming down from the tops of the hills.' And Zebul said unto him, 'The shadow of the hills thou seest like men.' 37. And Ga'al spoke yet again and said, 'Behold, people are coming down from the navel of the land, and one band is coming by way of the soothsayers' terebinth.' 38. And Zebul said unto

36. *The shadow, etc.* A taunt suggesting that 'his fears make him imagine enemies where there are none' (Mo.). Zebul's policy was to force Ga'al's hand by insinuating that he dared not be as good as his word : cf. v. 38.

37. *the navel of the land.* The meaning of Heb. *ṭabbūr* is elucidated by new Heb. *ṭabbūr*, *ṭibbūr*, and Aram. *ṭibbūrā*, 'navel.' So Ξ ὀμφαλός, Ψ 'umbilicus.' The other versions paraphrase : Σ נִּפְתָּלִית 'stronghold,' ס^p סִּבְבִּי (meaning dubious), Ar.

أقصى 'furthest part.' Rashi and Kimchi explain as a hill or elevation forming a stronghold, and R. Isaiah as a central position from which roads diverged. In Ezek. 38¹², the only other occurrence of the term in O.T., it is also used topographically, the inhabitants of the hill-country of Judah being described as 'those dwelling upon the navel of the earth,' i.e. (from the Israelite point of view) the most prominent and central part of the Universe (cf. Ezek. 5⁵). In the present passage the expression is obviously a closer definition of 'the tops of the mountains,' v. 36, and probably describes some neighbouring height (or even heights ; for v. 37^b seems to indicate that the bands are coming from different directions) which was regarded as the central part of the main mountain-range of Canaan.

the soothsayers' terebinth. Heb. *'ēlôn m'ōn'ânîm*, some well-known tree which was the seat of the practice of divination. Gen. 12^{6J} speaks of a tree called *'ēlôn mōré*, 'terebinth of the oracle-giver' (cf. for *mōré*, footnote p. 206), which was also in the near neighbourhood of Shechem, and may have been identical with the tree mentioned in the present passage.

The form of soothsaying practised by the *m'ōn'ân* is uncertain. If the Heb. root *'ānan* is connected with Ar. *ḡanna*, 'to omit a hoarse nasal sound,' *m'ōn'ân* may denote the *murmurer* or *hoarsely humming one*. So Robertson Smith (*Journal of Philology*, xiv. pp. 119 ff.), who states that 'the characteristic utterance of the Arabic soothsayer is the monotonous rhythmical croon called *saḡ*,' properly the cooing of a dove.' According to Wellh., however (*Reste arab. Heidenthums*², p. 204), the term is to be explained, from Ar. *'anna*, 'to appear,' as meaning *dealer in phenomena*.

him, 'Where is now thy boast, in that thou saidst, "Who is Abimelech, that we should serve him?" Are not these the people whom thou didst despise? Pray, go forth now, and fight with them.' 39. So Ga'al went forth before the citizens of Shechem, and fought with Abimelech. 40. And Abimelech pursued him, and he fled before him : and there fell down many slain up to the entry of the gate. 41. And Abimelech dwelt in Arumah : and Zebul drove out Ga'al and his brethren, so that they should not dwell in Shechem.

42. ^{R^{JE}} And on the morrow, the people went out into the field : and men told Abimelech. 43. ^E And he took the people and divided them into three bands, and lay in ambush in the

38. *thy boast.* Lit. 'thy *mouth*.' The Heb. *phé*, 'mouth,' is used similarly in Ps. 49¹³ (³⁹14), 'This is the way of them that have self-confidence, and of those who following them approve their speech (*mouth*).' Bab. *phû* 'mouth' frequently has the meaning 'speech.'

Are not these the people, etc. The situation is aptly summed up by Mo. : 'Zebul, by reminding Ga'al, doubtless in the presence of many bystanders in that public place, of his former boasts, goads him into fighting. He had indeed no choice ; if he declined the challenge, his prestige and influence in Shechem were gone.'

41. *And Abimelech dwelt, etc.* Abimelech returned to the city in which he was dwelling (possibly the narrative may originally have run 'וַיָּשָׁב א' וַיֵּשֶׁב בָּא' 'And A. returned, and dwelt in A.'), and did not trouble to follow up his victory, feeling no doubt that Zebul was capable of dealing with the situation. Ga'al's incompetence as a leader having been sufficiently demonstrated by his shameful defeat, Zebul had no difficulty in expelling him from Shechem, together with the other members of his family or clan. Thus the disaffection in the city, of which Ga'al was the author, comes (at least temporarily) to an end. 'The citizens of Shechem,' who had been persuaded by the impostor to adopt him as their leader, were no longer concerned to support him ; and Zebul could scarcely have expelled him from the city without their aid, or, at any rate, without their acquiescence. The continuation of the narrative in vv. 42 ff., which represents 'the people,' *i.e.* the same citizens of Shechem, as still at active hostilities with Abimelech 'on the morrow,' is thus not of a piece with the Ga'al narrative. As we have seen (cf. *note* on v. 25b), vv. 43 ff. are clearly the proper continuation of the main narrative, which is broken off at v. 25, and resumed by the Redactor in v. 42.

42. *And on the morrow . . . field.* On this statement, as representing an attempt on the part of R^{JE} to harmonize his two narratives, cf. p. 268.

field ; and he looked, and, behold, the people were coming out from the city ; and he rose up against them, and smote them. 44. And Abimelech, and 'the band' that was with him, made an onset, and stood in the entry of the gate of the city : and the two bands made an onset upon all who were in the field, and smote them. 45. And Abimelech fought against the city all that day ; and he captured the city, and the people who were in it he slew : and he broke down the city, and sowed it with salt.

43. *the people were coming out, etc.* Coming out upon one of the predatory excursions described in *v.*²⁵.

44. *the band.* Reading sing. הָרֵאִיט with F and some MSS. of C, in place of H plur. הָרֵאִיטִים 'the bands.' According to *v.*^{43a}, Abimelech had divided his available forces into *three* bands, and according to *v.*^{44b} *two* bands attacked the Shechemites in the field while Abimelech was seizing the gate of the city with his own contingent.

made an onset. Cf. *v.*³³ *note*.

45. *sowed it with salt.* A symbolic action, apparently intended to indicate that nothing thereafter was to live and flourish there. The turning of a fruitful land into a salt desert as the result of a curse is mentioned in Deut. 29²³, Ps. 107³⁴ ; cf. Jer. 17⁶, and the story of the destruction of the cities of the plain in Gen. 19 J. Ros. and commentators after him refer to Pliny, *Hist. Nat.* xxxi. *ch.* 7 ; Virgil, *Georg.* ii. 238, as mentioning the well-known fact of the infertility of a salt soil. More to the point, in connexion with our passage, is Tiglath-pileser I.'s account of his destruction of the city of Hunusa (*Annals*, col. vi. 14) : 'The three great walls of their city, which with burnt brick were strongly built, and the whole of the city I laid waste, I destroyed, I turned into heaps and ruins ; and salt (?) thereon I sowed' ; * cf. Budge and King, *Annals of the Kings of Assyria*, i. p. 79 ; *KB.* i. pp. 36 f. Scheiden, *Das Salz*, p. 95 (quoted in *EB.* 4250) cites the tradition that Padua was sown with salt by Attila, and Milan by Barbarossa.

Robertson Smith (*Religion of the Semites*², p. 454, *n*¹) adopts a

* The word rendered 'salt' is (*abnu*) ŠI.PA ; and unfortunately we cannot be sure of the meaning of ŠI.PA (or ŠI.ĤAD), which is most likely the ideographic form in which an otherwise unknown Assyrian word is written ; though the rendering above adopted appears to be the most probable. The Determinative Prefix *abnu*, 'stone,' marks the substance as a *mineral* ; and there is a variant reading plur. *abnē*, 'stones' (lumps of salt ?). The Assy. *azrû*, 'I sowed (it),' is the same verb as is used in our passage by the Heb., *way-yizra'êhâ*. The reference in the *Annals* of Ašurbanipal (col. vi. 79 ; cf. *KB.* ii. pp. 206 f.) cited in *EB.* 4250 from Gunkel, *Genesis*², p. 187, which is supposed by Gunkel to refer to the same ceremony, is of too doubtful significance to be quoted.

46. And when all the citizens of the tower of Shechem heard it, they entered into the crypt of the temple of El-berith. 47. And it was told Abimelech that all the citizens of the tower of Shechem had gathered themselves together. 48. And Abimelech went up to Mount Šalmon, he and all the people who were

different explanation, supposing that the salt was used as a symbol that the city was *consecrated* to the deity as a devoted thing (*hérem*; cf. *note* on *ch.* 1¹⁷), since the sprinkling with salt has a religious meaning, as a symbol of consecration, in Ezek. 43²⁴. This parallel, which refers to the sprinkling of a whole burnt-offering with salt, must be deemed of doubtful validity.

46. *the tower of Shechem.* This stood, apparently, apart from the city of Shechem, and was probably (like the tower of Penuel, *ch.* 8^{9.17}) the stronghold of an unwall'd hamlet.

crypt. Heb. *šerîah*. The meaning of the term is somewhat obscure. In its only other occurrence in the O.T., 1 Sam. 13⁶, it seems to denote an *underground chamber*, natural or artificial; * and this sense is borne out by the use of *šerîhā* in the Nabataean inscriptions to denote a tomb hewn out of the rock: cf. Euting, *Nabatäische Inschriften*, 15³⁴. In Ar. the cognate word *darîh* denotes 'a trench' or *oblong excavation in the middle of a grave*, in distinction from *lahd* (an excavation in the *side*); or it may denote *the grave altogether*, as in the benediction 'May God illumine his grave!' (*darîhahu*): cf. Lane *s.v.*

How such a rock-hewn crypt could have been set on fire is not evident. Possibly the door may have been in the side of a rock, with steps descending into the interior; and, the faggots being piled *against* this door, the fire burnt it through and suffocated the refugees. Or, if we explain (as we legitimately may do) that the faggots were placed *upon* (לע) the crypt, we may picture a flat trap-door on the top of which the fire was laid, so that the mass of burning material eventually fell upon the people in the crypt beneath.

A.V., R.V., in giving the more general rendering 'hold,' seem to depend upon Gr^{AL}. ὀχύρωμα, Έ (v.⁴⁹) 'praesidium.' Abulwalid compared the Ar. *šarh*, 'a lofty building or chamber *standing apart*' (from *šaraḥa* 'to be unmixed, clear,' here used in the sense 'to *stand clear*'); and hence the sense 'citadel' or 'tower' was adopted by many of the mediæval and earlier modern commentators. Most recent scholars adopt the explanation which is given above.

48. *Mount Šalmon.* The name Šalmon seems to mean 'the shady'

* In this passage *šerîhîm* are coupled with *ḥôrôth*, 'cisterns,' i.e. rock-hewn receptacles for water which, in a disused state, might form effectual hiding-places.

with him; and Abimelech took an axe [†] in his hand, and cut a bundle of brushwood, and took it up and placed it on his shoulder; and he said unto the people who were with him, 'What ye have seen me do, make haste, do likewise.' 49. And all the people also cut each his bundle [†]: and they went after Abimelech, and placed them against the crypt, and set the crypt on fire over them: so all the men of the tower of Shechem died also, about one thousand men and women.

50. And Abimelech went unto Tebeš, and encamped against Tebeš, and captured it. 51. Now there was a strong tower in the midst of the city, and thither fled all the men and women,

—probably a reference to the woods which (as the context shows) clothed its sides.*

an axe. Reading sing. הַקֶּרֶם with \mathfrak{E}^{AL} , \mathfrak{S}^{h} , \mathfrak{F} , \mathfrak{S}^{p} , in place of \mathfrak{H} plur. הַקֶּרֶמוֹת 'axes.' The Heb. idiom says 'the axe,' the Definite Article being so used with familiar objects which are understood elements in the situation: cf. Davidson, *Syntax*, § 21 d; G-K. § 126 s; *NHTK*. p. 1. The idiom may be illustrated in English by the way in which we speak of 'boiling *the* kettle'—never 'boiling *a* kettle.' The emendation קֶרֶמוֹן 'his axe,' adopted by Mo., Bu., No., Kent, Cooke, is much less idiomatic; apart from the fact that 'his' is not pre-supposed by any of the versions above cited.

49. *his bundle.* Reading fem. שׁוֹכָתוֹ (cf. *v.* ⁴⁸) in place of שׁוֹכָה, which, as vocalized, is intended to convey the same sense, being regarded as a masc. form שׁוֹךְ with suffix of the 3rd masc. sing. (on the suffix-form; cf. G-K. §§ 7c, 91e). Probably \mathfrak{H} should be vocalized שׁוֹכָה 'a bundle,' which may be the original text.

against the crypt. Or possibly, 'upon the crypt'; cf. *note* on *v.* ⁴⁶.

50. *Tebeš.* The modern Tûbâs, twelve miles N.E. of Shechem, has been identified by Rob. (*BR.* ³ ii. p. 317) as the site which Eusebius gives as the ancient Tēbēs; which is described by him as thirteen Roman miles from Neapolis (Shechem) in the direction of Scythopolis

* That the meaning 'to be dark or shady' belongs to the root צָלַם is clear from the subst. צִלְמוֹת (for \mathfrak{H} צִלְמוֹת) 'deep shade,' and the Bab. root *šalāmu*, 'to be dark or black.' Probably Heb. צֶלֶם 'image' properly means 'shadow' (so-called as being *black* in a land of strong lights and shades), since an image is the *shadow* or *replica* of that which it represents. Cf. Delitzsch, *Prolegomena*, p. 141; *KAT.* ³ p. 475, n⁶. BDB.'s explanation of צֶלֶם as 'something cut out,' based on Ar. *šalama*, 'to cut off' (properly 'to extirpate by amputation') is very far-fetched.

even all the citizens of the city, and shut themselves in, and went up on to the roof of the tower. 52. And Abimelech came unto the tower, and fought against it, and he drew near to the door of the tower to burn it with fire. 53. And a certain woman cast an upper millstone upon the head of Abimelech, and brake his skull. 54. And he called quickly unto the lad who bore his armour, and said to him, 'Draw thy sword and despatch me, lest they say of me, "A woman slew him."' So his lad thrust him through, and he died. 55. And when the men of Israel saw that Abimelech was dead, they went every man to his place.

(Bethshe'an), *OS.* 262⁴⁴. This identification is accepted by some modern writers (so, most recently, Cooke); but must, on philological grounds, be deemed highly precarious.*

53. *an upper millstone.* Heb. *pēlah rēkhebh*, lit. 'cleft (stone) of riding,' so-called as *riding* upon the lower stone (*pēlah tahtīth*, Job 41²⁴, *Is.* 10). The complete mill is termed *rēhāyim*. The hand-mill still used in Palestine is formed of two flat stones: a peg in the centre of the lower one corresponds to a hole in the upper, which is thus kept in place; and the upper being turned by a wooden handle, the corn which is placed between the two stones is ground. The diameter of the mill is usually about eighteen inches, the upper stone being of smaller diameter than the lower and two or three inches thick. These mills are usually turned by women, the performance of such work by men being regarded as a badge of degradation: Judg. 16²¹, Lam. 5¹³, Jer. 52¹¹ (Ⓔ). Cf. Kennedy in *EB.* 3091 ff.

54. *Draw thy sword, etc.* Similarly, Saul commands his armour-bearer to slay him when he perceives that otherwise he must fall into the hands of the Philistines: 1 Sam. 31⁴.

despatch me. Heb. *mōthēth*, the causative and *intensive* form of *mūth*, 'to die,' always has the sense 'to kill outright.' Cf. especially 1 Sam. 14¹³, where it is stated that the Philistines 'fell before Jonathan, and his armour-bearer despatched them (*m'mōthēth*) after him.'

55. *the men of Israel.* Abimelech, in succeeding to the power and influence exercised by Jerubba'al and his seventy Israelite sons, may be supposed to have ruled over Canaanites and Israelites alike in the district about Shechem. The feelings of the Israelites against the B'nê-Ḥamor of Shechem and the Canaanites of the neighbouring

* There is correspondence of one consonant only between Tēbēs and Tūbās; and the *t* in the latter name ought naturally to represent *ṭ* in Heb. The modern Ar. form would accurately correspond to a Heb. טֹבֵשׁ, rather than תִּבְיָ; cf. Cheyne, *EB.* 5033.

56. Thus God requited the wickedness of Abimelech which he had done to his father, in slaying his seventy brethren: 58. And the wickedness of the men of Shechem did God requite upon their head: and there came upon them the curse of Jotham the son of Jerubba'al.

cities must have been intensified by the fact that the assassination of Jerubba'al's Israelite sons was a Cana'anite movement (cf. p. 267); and, hostile at heart as they must have been to Abimelech as the Cana'anite nominee, they would naturally support him when it came to a conflict with the Cana'anites: and they probably formed the bulk, if not the whole, of his army. Cf. Mo. *ad loc.*

56. *Thus God requited, etc.* It is characteristic of E to draw a religious moral from the facts of history.

10. 1-5. *The 'Minor' Judges: Tola' and Ja'ir.*

The so-called 'minor' Judges, Tola' and Ja'ir (10¹⁻⁵), Ibzan, Elon, and 'Abdon (12⁸⁻¹⁵) appear scarcely to stand upon the same level as historical personages with Ehud, Barak, Gide'on, Abimelech, and Jephthah. Tola' is said to have been 'the son of Pu'ah the son of Dodo, a man of Issachar,' and to have 'dwelt in Shamir in the hill-country of Ephraim.' In Gen. 46¹³ P both Tola' and Pu'ah appear as sons, *i.e.*, doubtless, *clans* of Issachar; and this is also the case in Num. 26²³ P, 1 Chr. 7^{1ff.} Ja'ir the Gile'adite, whose thirty sons had thirty towns called Havvoth-Ja'ir, is the same as Ja'ir the son or *clan* of Manasseh who made conquests in Gile'ad which were afterwards known as Havvoth-Ja'ir (*i.e.* 'the tent-villages of Ja'ir'), according to Num. 32⁴¹ J, Deut. 3¹⁴, 1 Kgs. 4¹³. Elon is described as 'the Zebulonite'; and in Gen. 46¹⁴ P Elon is a son of Zebulun, and, according to Num. 26²⁶ P, founder of the *clan* of the Elonites. That Ibzan and 'Abdon are also clan-names may be inferred. We know that Ja'ir's thirty sons represent thirty village-settlements: when we read that Ibzan had thirty sons and thirty daughters, and that 'Abdon had forty sons and thirty grandsons, it is reasonable to infer that the writer's meaning is the same in these cases also. The statement that Ibzan made outside-marriages for his daughters, and brought in wives for his sons, doubtless refers to the numerous alliances and connexions with other clans which were formed by branches of the clan of Ibzan.

It is a further question whether these 'minor' Judges were included in the historical scheme of R^{E2}. In the survey of the course of Israel's history during this period which forms the introduction to his book in ch. 2¹¹⁻²³ (cf. pp. 52 ff.), R^{E2} traces the periods of oppression by foreign foes to Israel's declension from the service of Yahweh,

and regards the raising up of the Judges as deliverers as an act of condescension on Yahweh's part when punishment has been meted out. This view of history is faithfully followed out by the editor in the cases of the 'major' Judges; but in the brief notices of the 'minor' Judges mention of Israel's defection from Yahweh, and the naming of the particular foes into whose power they were delivered, are conspicuously absent. Of Tola' it is simply stated that he 'arose after Abimelech to save Israel'; and of Ja'ir even more briefly that he 'arose after him.' Ibšan, who is made to succeed Jephthaḥ, is said to have 'judged Israel after him'; and the same formula is used of Elon and 'Abdon. Thus it may be inferred with great probability that the notices of the 'minor' Judges were inserted into the book subsequently to the redaction of R^{E2}. The purpose of the interpolator may have been to raise the number of the Judges to *twelve*, and, so far as possible, to make them representative of the twelve tribes of Israel. Thus we have

'Othniel	Judah.
Ehud	Benjamin.
Barak	Naphtali.
Gide'on	West Manasseh.
Abimelech	
Tola'	Issachar.
Ja'ir	East Manasseh.
Jephthaḥ	Gad.
Ibšan	?
Elon	Zebulun.
'Abdon	Ephraim.
Samson	Dan.

If the Bethleḥem which is mentioned as the native city of Ibšan (*ch.* 12^{8,10}) is the Bethleḥem which is assigned to Zebulun in Josh. 19¹⁵ P, *i.e.* the modern Bêt Laḥm seven miles west-north-west of Nazareth, this city seems to have been on the border between Zebulun and Asher; and thus Ibšan may have been regarded as the representative of Asher. Re'uben and Sime'on are unrepresented, while Abimelech properly gives a second representative to West Manasseh; still, the scheme is sufficiently complete to make it probable that the theory above suggested was in the mind of the editor who added the notices of the 'minor' Judges.

Who this editor was may be inferred from the fact that his book contained the story of Abimelech, and that this usurper was counted by him as one of the Judges: cf. *ch.* 10¹. He can hardly have been other than the editor who reinserted the narrative of Abimelech into R^{E2}'s book, *i.e.* the late editor whom we have characterized as R^P.

For the grounds upon which the notice of Shamgar in *ch.* 3³¹ is to be regarded as still later than the work of R^P, cf. p. 76.

10. 1. R^r And after Abimelech there arose to save Israel Tola^a the son of Pu^aah, the son of Dodo, a man of Issachar;

10. 1. *Pu^aah.* Heb. פּוּאָה; so 1 Chr. 7¹. The form פּוּוּחַ Puwwah is given by Gen. 46¹³, Num. 26²³. The name is probably the equivalent of Ar. *fuwwah*, which denotes the species of madder called *Rubia tinctorum*, L., from the root of which a red dye is derived* (cf. Lane *s.v.*; Löw, *Pflanzennamen*, p. 251); whereas Tôla^a, which means 'worm' in Ex. 16²⁰ (more commonly fem. *Tôlî'ath*, cf. Bab. *tullu*), is used in Isa. 1¹⁸, Lam. 4⁵ to denote the crimson dye called cochineal (properly the *insect* from which the dye is prepared; so, more commonly, fem. *Tôlî'ath*). The coincidence suggests that kindred clans adopted kindred totem-objects.

Dodo. This name occurs again in 2 Sam. 23⁹ *K^erlê* = 1 Chr. 11¹²; 2 Sam. 23²⁴ = 1 Chr. 11²⁶. 2 Sam. 23⁹ *Kt.* gives the form Dodai; and similarly *𐤁𐤃𐤁𐤏* reads Δωδαι in || 1 Chr. The same form is favoured by the evidence of *𐤁𐤃𐤁𐤏* in 2 Sam. 23²⁴ and || 1 Chr. Dodai occurs in 1 Chr. 27¹, where the reference seems to be to the same man as is named in 1 Chr. 11¹² (called 'the Aḥohite' in both passages). The form Dodo may be paralleled by Dûdu, the name of an official (probably a Canaanite) in the service of the Pharaoh, which occurs in the T.A. Letters (cf. Knudtzon, Nos. 158, 164); cf. also דָּדָא Dada in Palmyrene (de Vogüé, *La Syrie centrale*, 93; Cooke, *NSI*. p. 301), and the names from cuneiform texts cited in *KAT.*³ p. 483.

The meaning of the name has been the subject of some discussion. The most probable theory regards both Dodo and Dodai as hypocoristic abbreviations of a fuller form such as Dodiel or Dodiyya (דּוּדִיָּה; cf. דּוּדָוָה Dodavahu, 2 Chr. 20³⁷). The element *Dôd* is then the same as the subst. which means 'uncle' on the father's side (used in 1 Sam. 14⁵⁰, 2 Kgs. 24¹⁷, *al.*), properly, it may be assumed, 'object of love' (so in Heb. the word often has the meaning 'beloved,' which is also seen in Bab. *dîdu*). Thus Dodo, Dodai, may mean 'the god is uncle' (i.e. *kinsman* or *patron* of the bearer of the name) †; or, conceivably, 'Beloved of the god': cf., for the latter sense, the name יְדִידְיָה Jedidiah, 'Beloved of Yah,' 2 Sam. 12²⁵; and David, *i.e.*, probably, 'Beloved' (by God). Cf. Cheyne, *EB.* 1122; Gray, *Heb. Proper Names*, pp. 60 ff. A passage of interest in this connexion is found in the Inscription of Mesha', where the Moabite king, in relating his success against Israel east of Jordan, says, 'The king of Israel had built Aṭaroth for himself: and I fought against the city and took it; and I slew the whole of it, even the people of the city, as a gazing-

* Eusebius explains Puah ἐρυθρά, *OS.* 200⁹⁸; Jerome, *rubrum*, *ib.* 6²¹.

† Cf. the South Arabian name Dâdi-kariba, 'My (divine) kinsman has (or is) blessed'; Hommel, *AHT.* p. 86.

and he dwelt in Shamir in the hill-country of Ephraim. 2. And he judged Israel twenty and three years, and died, and was buried in Shamir.

3. And after him there arose Ja'ir the Gile'adite; and he judged Israel twenty and two years. 4. And he had thirty sons who rode on thirty ass-colts; and they had thirty 'cities' (they

stock unto Chemosh and unto Moab. And I captured thence the altar-hearth of יוֹרֵה, and dragged it before Chemosh in Keriyyoth' (*Moabite Stone*, ll. 10-13). Here the word יוֹרֵה should perhaps be vocalized יוֹרֵה 'its (divine) Patron,' i.e. the God of the city * (Yahweh? Cf. ll. 17 f., where, after taking the city of Nebo, Mesha' states that he took the vessels of Yahweh, and dragged them before Chemosh). Failing this explanation, יוֹרֵה must be vocalized *Dôdô*, and regarded as the proper name of a deity, which may (on this hypothesis) perhaps be recognized in the O.T. proper names above discussed: cf. Baethgen, *Beiträge*, p. 234; *KAT.*³ p. 225.

Ἐ υἱὸς πατράδελφου αὐτοῦ, Ἐ 'patrui Abimelech,' *שׁ פ* יוֹס, treat Dodo, not as a proper name, but as the subst. meaning 'uncle' with suffix of the 3rd masc. sing.†: 'son of his (i.e. Abimelech's) uncle.' Such an explanation is excluded by the fact that, while Tola' is expressly described as 'a man of Issachar,' Abimelech, so far as he was Israelite in extraction, belonged to Manasseh. Several minuscules of Ἐ (grouped by Mo. as *Ḙ*^M) offer the reading καὶ ἀνέστησεν ὁ Θεὸς . . . τὸν Θωλα υἱὸν Φουα υἱὸν Καριε (or Καρηε) πατράδελφου αὐτοῦ, omitting the words 'a man of Issachar.' Here Καριε may represent the name קָרַח Kareah: cf. 2 Kgs. 25²³, Jer. 40⁸, *al.* The origin of this text is wholly obscure.

Shamir. The site is unknown. Ἐ^{AL} ἐν Σαμαρείᾳ.

4. *who rode, etc.* A similar statement is made in *ch.* 12¹⁴ with regard to 'Abdon's descendants. The detail is mentioned as a badge of rank: cf. *ch.* 5^{10a}.

cities. Reading עָרִים with all Versions, in place of עֲרִיִם 'ass-colts,' which has arisen from accidental imitation of the same word preceding.

* In the difficult expression in Am. 8¹⁴ 'as *the way* of Be'ersheba' liveth!' יוֹרֵה 'way' is plausibly emended by Winckler (*AF.* i. p. 194 f.) into יוֹרֵה. This gives the sense 'As thy (divine) patron liveth, O Be'ersheba', an excellent parallel to 'As thy god liveth, O Dan': cf. Ἐ ὁ θεὸς σου in place of יוֹרֵה.

† This explanation is also offered by *Y*, *שׁ פ* in 2 Sam. 23^{9,24}, 1 Chr. 11^{12,26}, and by a *Ḙ* doublet in 2 Sam. 23^{9,21}.

are called Havvoth-Ja'ir unto this day), which are in the land of Gile'ad. 5. And Ja'ir died, and was buried in K̄amon.

Havvoth-Ja'ir. Probably 'the tent-villages of Ja'ir.' Heb. *ḥavvāwā* is explained from Ar. *ḥiwaḏ*, 'a group of tents near together.' Most likely the Hivvites, who are mentioned among the peoples of Cana'an, obtained their name as originally inhabitants of such primitive village-communities.

which are in the land of Gile'ad. So Num. 32⁴¹, 1 Kgs. 4¹³, 1 Chr. 2²². In Deut. 3¹⁴, Josh. 13³⁰ R^D the Havvoth-Ja'ir are incorrectly localized in *Bashan*. On the origin of this error, cf. Driver, *Deuteronomy* (ICC.) p. 55.

5. *K̄amon.* Polybius (v. lxx. 12) mentions a Kamûn east of Jordan as captured by Antiochus the Great:—καὶ προάγων, παρέλαβε Πελλαν, καὶ Καμουν, καὶ Γεφρουν. The name of K̄amon is very possibly preserved in the modern K̄umêṁ, a village six and a half miles west of Irbid. About one mile north-west of K̄umêṁ, a ruined site K̄amm may correspond to the ancient city. It should be noted that the name Γεφρουν, which is coupled with Καμουν, i.e. doubtless the Ephron (עֶפְרֹן) of 1 Macc. 5⁴⁶, seems to be preserved in the Wādy el-Ġafr which lies some two miles north of K̄amm. Cf. Buhl, *Geogr.* p. 256.

10. 6–16. *Further apostasy receives its punishment.*

Besides the Commentaries, etc., cited throughout the book, cf. Stade, *ZATW.*, i. (1881) pp. 341–343; Stanley A. Cook, *Critical Notes on Old Testament History* (1907), pp. 24 ff., 33 ff., 48 f., 127 f.

This is a section which raises interesting questions in connexion with the original composition of the history of the Judges. As it now stands, it was clearly intended by R^{E2} as an introduction both to the narrative of the oppression of the 'Ammonites and the raising up of Jephthah as judge (*ch.* 10^{17–12⁷}), and to that of the oppression of the Philistines and the raising up of Samson as judge (*chs.* 13 ff.): cf. v. 7. The ordinary formulæ of the pragmatic scheme of R^{E2} may be traced in full in v. 6 (omitting the specification of 'the gods of' various nations), vv. 7, 10a: cf. the type-form given on p. 54. On the face of it, however, it is obvious that the whole section cannot have been composed by R^{E2} for the purpose which it now fulfils in his book. There is no reason why, at this particular point in his narrative, he should depart from his ordinary practice of introducing the history of each particular judge singly and in his regular brief form; and, as a matter of fact, the repetition of his ordinary formula at the beginning of the Samson-narrative, *ch.* 13¹, renders the mention of Israel's apostasy leading to the oppression of the Philistines (10^{6a, 7ba}) superfluous in *ch.* 10. Further, it should not escape notice that, if 10^{6–16} was actually composed by R^{E2} as an introduction to the narratives of the oppression of the 'Ammonites and Philistines *in that order*, he would

scarcely have employed the opposite order in *v.*^{7b}; 'and he sold them into the hand of the Philistines and into the hand of the children of 'Ammon.'

Closer examination reveals the fact that the phraseology of the section is in many points identical with that which characterizes the later strata of E; especially as seen in Josh. 24, Judg. 6⁷⁻¹⁰, 1 Sam. 7²⁻⁴, 10¹⁷⁻¹⁹, 12. The most striking phrases are 'we have sinned' (חטאנו) *vv.*^{10,15}, as in 1 Sam. 7⁶, 12¹⁰; 'oppress' (לחץ) *v.*¹², as in Judg. 6⁹, 1 Sam. 10¹⁸; 'foreign gods' (אלהי הנכר) *v.*¹⁶, as in Josh. 24^{20,23}, 1 Sam. 7³; 'put away' (הסיר), in reference to the 'foreign gods,' *v.*¹⁶, as in Josh. 24^{20,23}, 1 Sam. 7³ (on these phrases as generally characteristic of E², cf. Driver, *LOT*.⁹ p. 177); as well as the retrospect of Israel's past history, especially the deliverance from Egypt, *vv.*^{11,12}, as in Josh. 24^{6f}, Judg. 6⁸, 1 Sam. 10¹⁸, 12^{6,8}.

Thus it may be inferred that we have, in 10⁶⁻¹⁶, a section originally belonging to E's history of the Judges, which was incorporated by R^{JE} into his composite history, and then used by R^{E2} in place of (or it may be, in combination with) his ordinary brief introductory formula. The purpose which this section fulfilled in E's history seems to be indicated by the reference to the Philistines as the oppressors in *v.*^{7b} (so Bu., *RS*. p. 128); the fact that this people is mentioned first probably indicating that the reference to the children of 'Ammon which follows is a later addition, due to R^{JE}, and intended to make the section serve as an introduction to *ch.* 10¹⁷⁻¹²⁷ as well as to *chs.* 13 *ff.*

But, if this is so, this introduction from E to the narrative of a Philistine oppression cannot have referred to the Samson-story as given in Judges, since this is derived wholly from J (cf. p. 336)—apart from the fact that a section in which the religious motive is so fully developed can never have been designed to introduce a story of which the crude and primitive character is almost unrelieved. It is scarcely open to doubt that E's history of the Philistine oppression is that which now forms one strand of the composite narrative in 1 Sam.; and the proper conclusion to this narrative, as it took form under the same hand (E²), is found in the account of the deliverance from the Philistines as effected by Samuel, which is now contained in 1 Sam. 7 (so Mo., p. 276; S. A. Cook).

It is impossible accurately to determine how far R^{E2} felt it necessary to supplement his source; since, as we have noticed in the *Introduction* (p. xlvii ff.), his phraseology is modelled throughout upon that of E², and therefore cannot with certainty be differentiated from it. Probably he was responsible for the summary statement of Israel's apostasy which opens *v.*⁶; but the remaining formulæ which normally we associate with his pragmatic introductions were most likely already existent in the work of E². Thus, for example, *v.*⁷ down to 'Philistines,' which is cast in the well-known formulæ of R^{E2}, must,

6. R^{E2} And the children of Israel again did that which was evil in the sight of Yahweh,^{E2} and served the Ba'als, and the 'Ashtarts,^{R^P} and the gods of Aram, and the gods of Šidon, and the gods of Moab, and the gods of the children of 'Ammon, and the gods of the Philistines;^{E2} and they forsook Yahweh, and served him not. 7. And the anger of Yahweh was kindled against Israel, and he sold them into the hand of the Philistines, R^{JE} and into the hand of the children of 'Ammon. 8. E² And they brake and crushed the children of Israel in that year, R^{JE} eighteen years, even all the children of Israel who were beyond Jordan in the land of the Amorites, which is in Gile'ad. 9. And

if our theory of the origin of the section be correct, have already existed in E's introduction to the Philistine oppression.

The passages in vv.⁷⁻⁹ which serve to make the section suitable as an introduction to the narrative of the oppression of the 'Ammonites must be due to the Redactor who placed it before 10¹⁷⁻¹²⁷, i.e., we may assume, R^{JE}. The references in v.⁶ to the gods of various nations, and in vv.^{11,12} to various nations *besides* Egypt as oppressors (some of them, e.g. the Philistines and the 'Ammonites, out of place in a retrospect of past oppressions *and deliverances*) must be due to a much later hand, to whom the somewhat lengthy record of apostasy and its outcome seemed adapted for the insertion of such detailed lists.

10. 6. *the Ba'als and the 'Ashtarts.* Cf. ch. 2¹³ notes.

8. *they brake.* Heb. *ra'aš* (once again in O.T., Ex. 15^{6b}) perhaps = *raḥāṣu* in the T.A. Letters, which Zimmern (*KAT*.³ p. 653) regards as a Canaanism; cf. Kn. 127, l. 33; 141, l. 31, 'and may the bow-troops of the King my lord . . . shatter (*tī-ra-ḥa-aš*) the head of his enemies.'

in that year, eighteen years. As Mo. remarks, such a collocation is impossible. The eighteen years probably belongs to R^{E2}'s system of chronology, referring to the duration of the 'Ammonite oppression; while '*in that year*' is more suitable to the verbs at the beginning of the verse which suggest a signal catastrophe rather than a long-continued subjugation and oppression' (Mo.), and probably refer to the first stage of the Philistine aggressions, as narrated by E².

even all the children of Israel, etc. The facts related by R^{E2} in this verse and v.⁹ as to the extent of the 'Ammonite aggressions were probably derived by him from one of the ancient sources which narrated the story of Jephthah. Cooke's statement that 'the extension of the oppression to *all the children of Israci* on both sides of the Jordan is probably due to the latest editor' is groundless. The writer does not refer to the whole of Israel east and west of Jordan, but to all Israel in Gile'ad east of Jordan, and to certain tribes (Judah, Benjamin, Ephraim) west of Jordan which (he implies) were some-

the children of 'Ammon crossed the Jordan to fight also against Judah, and against Benjamin, and against the house of Ephraim; E² and Israel was in sore straits. 10. And the children of Israel cried unto Yahweh, saying, 'We have sinned against thee; [] for we have forsaken <Yahweh> our God, and have served the Ba'als.' 11. And Yahweh said unto the children of Israel, 'Did not [] Egypt, R^P and [] the Amorites, and the children of

what harassed by raids, though not oppressed in the same degree as the inhabitants of Gile'ad. That the Ephraimites at any rate were interested parties is proved by the narrative of *ch.* 12 ^{1ff.}

10. *for.* Reading כִּי simply with several MSS. of א, and א, F, S^P, in place of וְכִי 'and because,' R.V. 'even because.'

Yahweh our God. The addition of 'Yahweh' is supported by six MSS. of א, and by א^A, א^L, F. The phrase 'Yahweh our God' is characteristic of E² (as, subsequently, of D); and the proper name *Yahweh* is desiderated by the contrast with 'the Ba'als.'

11. *Did not Egypt, etc.* Reading

הָלֹא מִצְרַיִם וְהָאֲמֹרִי וּבְנֵי עַמּוֹן וּפְלִשְׁתִּים

with א^{AL}, S^h, א^L, F, S^P, and taking the list as part of the subject of the verb לְהַצִּיחַ in *cz.*¹². So Mo. (*SBOT.*), No., Kit., Kent.

א (supported by א^B, א, Σ.), by reading מִן 'from' before each of the peoples enumerated, offers an impossibly harsh anacoluthon, omitting an indispensable verb, which is supplied by A.V., 'Did not I deliver you from the Egyptians, etc.?' R.V., 'Did not I save you from, etc.?' Such a verb, whether הִצַּלְתִּי אֶתְכֶם (A.V.) or הוֹשַׁעְתִּי אֶתְכֶם (R.V.), could not be *understood* in Heb.; though it is conceivable that its omission may be due to an error of transcription. Against such a view, however, is the fact (noted by Mo.) that we should expect either verb to be followed, not by מִן 'from' simply, but by מִיַּד 'from the hand of.' Thus E², with whose work we are dealing, employs this expression exclusively after הִצִּיל 'deliver' both in Judg. and 1 Sam.: cf. Judg. 6⁹, 1 Sam. 7³, 10¹⁸, 12^{10,11}; so Judg. 8³¹ R^{E2}. In the same way הוֹשִׁיעַ 'save' is regularly followed by מִיַּד in Judg.: cf. 2^{16,18}, 8²², 10¹², 12², 13⁵; once by the synonymous מִכַּף, 6¹¹.

The emendation above adopted has, as we have seen, the pre-dominant support of the Versions, and offers the simplest solution of the textual difficulty. We cannot, however, exclude the possibility that הָלֹא מִצְרַיִם of א may originally have been followed by

Ammon, and [] the Philistines, 12. and the Šidonians, and Amalek, and 'Midian'^{E2} oppress you; and when ye cried unto me, I saved you from their hand? 13. But ye have forsaken

הַעֲלִיתִי אֶתְכֶם (cf. *ch.* 2¹ R^P, 6⁸, 1 Sam. 10¹⁸ E²) or הוֹצֵאתִי אֶתְכֶם (cf. Josh. 24⁵ E²), 'Did not I *bring you up* (or, *bring you out*) from Egypt?' and that the verb was lost through later blundering insertion of the names which follow at the end of the verse (so Bu., La., Cooke). The relationship of *v.*¹¹ to *v.*¹² will then exactly resemble that of *v.*⁸ (the bringing out from Egypt) and *v.*⁹ (oppression of surrounding nations) in 1 Sam. 12 E². In this case the reading of the Versions which we have followed represents an attempt to make sense of a text identical with *W*.

the Amorites. We find no specific allusion to the Amorites as oppressors; the fact, mentioned in *ch.* 1³⁴, of their forcing* the children of Dan from the vale into the hill-country being scarcely of sufficient importance, and also not followed by any signal act of deliverance. Taking 'Amorites' as a general designation for the inhabitants of Canaan (as is usual in E; cf. *note* on *ch.* 1¹ 'against the Canaanites'), it is conceivable that the allusion may be to the oppression of Šisera and 'the kings of Canaan' related in *chs.* 4, 5. Possibly, however, as suggested by S^P, הָאֲמֹרִי may be a corruption of הַמּוֹאבִּים 'the Moabites' (for the Gentilic form, cf. especially Deut. 2^{11,29}) or מוֹאָב 'Moab,' since it is rather surprising to find no allusion

to the oppression of this latter people, as related in *ch.* 3^{12f}. *Gr*^{AL}, while retaining οἱ Ἀμορραῖοι, adds καὶ Μωαβ after καὶ οἱ υἱοὶ Ἀμμων.

the children of 'Ammon. These are named in *ch.* 3¹³ as aiding 'Eglon king of Moab in his oppression of Israel; but such a passing allusion could not have been in the writer's mind—at any rate unless he had previously mentioned Moab (cf. *note* preceding). Probably, like the mention of the Philistines with which it is coupled, the allusion is to the narrative *following*; and since reference to *deliverance* from the 'Ammonites and Philistines (*v.*^{12b}) is historically out of place, we may regard the names as a later careless insertion.

12. *the Šidonians.* We know of no occasion on which these people played the rôle of oppressors of Israel. Possibly, as Mo. suggests, their insertion here may be due to the mention of Šidon in *v.*⁶.

'Amalek. Cf. *ch.* 3¹³, 6³, where the mentions of 'Amalek, though very possibly later than the main narratives in which they occur (cf. *notes ad loc.*), are earlier than the present passage.

Midian. So *Gr*^{BAL} (*Gr*^A before 'Amalek), and most moderns. Some MSS. of *Gr*, S^h, S., Y read 'Canaan'; while S^P reads 'Ammon,'

* וַיִּלְחֲצוּ—the same verb as לַחֲצוֹ 'oppressed' in 10¹².

me, and have served other gods; therefore I will no more save you. 14. Go and cry unto the gods whom ye have chosen; let *them* save you in the time of your distress.'

15. And the children of Israel said unto Yahweh, 'We have sinned; do *thou* to us whatsoever seemeth good in thy sight: only pray deliver us this day.' 16. And they put away the foreign gods from the midst of them and served Yahweh: and his soul was impatient for the misery of Israel.

having omitted the reference to the children of 'Ammon and the Philistines in *v.*¹¹. \mathfrak{H} 'Ma'on' is apparently the modern Ma'an some eighteen miles east-south-east of Petra. The Ma'onites (Heb. *Me'ânîm*) are mentioned in later times as antagonists of Judah (1 Chr. 4⁴¹, 2 Chr. 26⁷; and probably also 2 Chr. 20¹); but we have no record of any aggressions by them in the time of the Judges. On the other hand, mention of the Midianite oppression (*ch.* 6) is to be expected.

14. *whom ye have chosen.* For the use of the verb 'choose' in this connexion, cf. Josh. 24¹⁵ E², 'and if it be evil in your eyes to serve Yahweh, choose ye this day whom ye will serve.'

16. *and served Yahweh.* \mathfrak{E}^B adds *μόνω*, i.e. מָוֹן , as in 1 Sam. 7¹.

his soul was impatient. Lit. 'was short.' So elsewhere of Yahweh, Zech. 11⁸; of the Israelites, Num. 21^{4b}. With רוּחַ 'spirit' as subject, Mic. 2⁷, Job 21⁴. The antithetical idea—'was patient'—is expressed by נָפְטוּ הָאָרֶץ 'he *prolonged* his soul'; cf. Job 6¹¹.

The rendering of \mathfrak{E}^{AL} καὶ οὐκ ¹ἐνῆρέστησε (^Aἐνῆρέστησαν ἐν) τῷ λαῶ, καὶ ὠλιγοψύχησεν (¹ὠλιγοψύχησαν) ἐν τῷ κόπῳ Ἰσραὴλ seems to embody a doublet, the first clause being a rendering of נָפְטוּ בָעַם , and the second correctly reproducing the text and meaning of \mathfrak{H} .

10. 17–12. 7. *Jephthah.*

Besides the Commentaries, etc., cited throughout the book, cf. R. Smend, *Jeftas Botschaft an den König von Ammon*, ZATW. xxii. (1902), pp. 129–137.

The hand of R^{E2} is to be seen in 11^{33b} (cf. *ch.* 3³⁰, 4²³, 8²⁸). In 12^{7a} this editor employs the formula which he probably found already existing in the narrative of R^{JE} (cf. *ch.* 15²⁰, 16^{31b}, 1 Sam. 4^{18b}, 7¹⁵).

Discussion of the ancient source, or sources, of the narrative must take its start with an examination of 11^{12–28}, which relates the sending by Jephthah of an embassy to the king of 'Ammon, protesting against his encroachment upon the territory of Israel between the Arnon and the Jabbok, and substantiating Israel's claim to hold it by right of conquest from Sihon, king of the Amorites. It is a difficulty with regard to this argument, as put into the mouth of Jephthah, that, except for the single reference to 'Ammon at the end of *v.*¹⁵, it refers throughout not to 'Ammon but to Moab. Thus, *vv.*^{17, 18} state that

Israel, in approaching Canaan from the east, was careful not to encroach upon the territory of Moab, *i.e.* the country south of the Arnon; but was content to conquer and settle in the territory of the Amorite Šihon, north of the Arnon and south of the Jabbok. The appeal of *v.* 24 is obviously addressed to Moab: 'Those that Chemosh thy god dispossesseth—wilt thou not possess *them*? etc.' Chemosh was the national god of Moab; while the god who stood in this position to 'Ammon was Milcom. In the same way, reference is made (*v.* 25) to the example of an earlier king of Moab, Balaḵ the son of Šippor, who left Israel unmolested in the enjoyment of their newly acquired territory.

As regards the origin of *II* 12-28, two possibilities present themselves. Either the section is a late insertion into an otherwise homogeneous narrative, framed in order to establish Israel's claim to the territory between the Arnon and the Jabbok—possibly in view of some later encroachment of 'Ammon* (Mo., Cooke, etc.); *or*, the section, referring properly to Israel's relations with *Moab*, is part of a variant tradition, according to which Jephthah appeared as a deliverer of the Israelites in Gilead from the aggressions, not of the 'Ammonites, but of the *Moabites*. On this latter hypothesis, we may expect to find the strand which embodies this variant tradition interwoven throughout the narrative as a whole (Holzinger, followed by Bu., Cor., No., Kit., Kent).

The former theory depends upon the fact that Jephthah's speech, as given in *vv.* 15-27, appears to be drawn chiefly from Num. 20.21, exhibiting, here and there, verbal similarities (cf. *notes* on text). We must suppose that the interpolator, finding ready to his hand an ancient narrative which related the way in which Israel, in making their conquest and settlements east of Jordan, were careful to respect the old-established rights of *Moab*, adapted the facts extracted from this narrative so that they might apply equally to 'Ammon by the mere insertion of the words 'and the land of the children of 'Ammon' at the end of *v.* 16. This theory is vitiated by the fact that, while it is quite conceivable that the author of the interpolation may have thought that a narrative which illustrated Israel's care to avoid infringing the rights of the two kindred peoples, Edom and Moab, was applicable by inference to their attitude towards another kindred people ('Ammon), it offers no explanation of the reference to the example of Balaḵ, an earlier king of *Moab*, as a precedent, and (most markedly) it is obliged to assume that the writer is guilty of a gross error in confusing Chemosh, the god of the Moabites, with the god of the 'Ammonites. The fact has also been remarked that there is no evidence to prove that the section is very late in origin. It depends, as we have noticed, to some extent upon Num. 20 14-21, 21 13.21-24a, but by

* Mo. suggests that the occasion of the interpolation may have been the aggressions of the 'Ammonites upon the ancient territory of Israel at the beginning of the sixth century B.C., as mentioned in Jer. 49¹.

no means slavishly so*; and the conception of Chemosh in 7.²⁴ as a national deity, exercising a potency and influence in relation to his people comparable to that which Yahweh exercises over Israel, may be paralleled by the conception of the same deity's power within his own land which underlies the old narrative of 2 Kgs. 3^{26.27}. † It is at least unlikely that such a view should have found expression at a period when at any rate in prophetic circles a doctrine of high spiritual monotheism had gained currency.

Rejecting this theory, then, we are thrown back upon the alternative which regards 11¹²⁻²⁸ as forming part of an originally distinct narrative, in which Jephthah is raised up to meet the aggressions, not of the 'Ammonites, but of the Moabites. Looking carefully at 10¹⁷⁻¹² as a whole, and examining it in detail, we are led to the conclusion that, while evidence that the narrative is composite throughout is by no means so obvious as e.g. in the Gide'on-narrative, yet traces of the combination of two traditions varying in detail really do exist.

Thus we note that, according to 11¹⁻¹¹, Jephthah is an outlaw from Gile'ad, dwelling in the land of Tob, and is fetched thence by the elders of Gile'ad in order that he may act as their leader in repelling the 'Ammonite invasion. According to 11^{30.31.34} ff, however, his home is at Mispah of Gile'ad; and the fact that he has lived there some time as a person of consequence, possessing a considerable retinue of dependents, seems to be indicated by the terms of his oath—'The cometh-forth that cometh forth from the doors of my house to meet me' suggests some range of possibility as to the projected victim; and the idea that this may prove to be his only daughter is sufficiently remote not to have entered into his reckoning. We may also observe (with Frankenberg) that the words of Jephthah's daughter, 11³⁶, 'Forasmuch as Yahweh hath wrought for thee full vengeance upon thine enemies,' clearly indicate that Jephthah had a personal ground of quarrel with the 'Ammonites; apart from which, indeed, his vow is difficult to explain. This fact, however, is hard to reconcile with the representation of him in 11¹⁻¹¹ as an outsider, who undertakes at a price to organize resistance to the enemy.

Further, 10¹⁷ can scarcely stand in original relationship to 10¹⁸, 11¹⁻¹¹. According to 10¹⁷, the presence of an invading 'Ammonite army in Gile'ad has been met by an organized muster of the Israelites at Mispah. The double וַיִּחַי, 'and they encamped,' clearly implies two hostile armies in battle-array: cf. ch. 6³³, 7¹, 1 Sam. 4¹, 17^{1,2}, 28¹. From 10¹⁸, however, we learn, to our surprise, that the Israelite army is without a leader; and it is only at this stage that the Gile'adites conclude, after deliberation, that they have no man of their own fit to undertake command, and are obliged to send their elders to

* Cf. Kue. *Oud.* § 13¹³; § 19⁶.

† Cf. *NHTK. ad loc.*, and the present editor's *Outlines of O.T. Theology*, pp. 34 ff.

the land of Tob to fetch back Jephthah. Assuming for the moment that this difficulty is not insuperable, it is very strange that, while according to 10¹⁷ the 'Ammonite invasion has already taken place, and the critical conflict is impending, 11⁴ informs us (as though it were a fresh fact) that 'after a while the children of 'Ammon fought with Israel.' If, however, 10¹⁷ is not really of a piece with 11¹⁻¹¹, this mention of the 'Ammonite invasion in 11⁴ forms the appropriate prelude to the mission of the Gile'adite elders to fetch Jephthah, as related in 11⁵⁻¹¹.

Jephthah's proceedings, again, as related in 11²⁹, can only be explained as actuated by the necessity of raising an army before attacking the 'Ammonites. Yet according to 10¹⁷, as we have seen, the army is already mustered at Mišpah.

Thus we seem to have established several points which indicate that 10¹⁷ has no original relationship to 11^{1-11.29}, but belongs to a different narrative. If this be so, 10¹⁸ can be nothing else than the clumsy attempt of a redactor to fit 10¹⁷ on to 11^{1ff}. The statement 'he shall be head, etc.,' is clearly drawn from 11^{8b}.*

If, then, 10¹⁷ is distinct in origin from 11¹⁻¹¹, its proper sequel is probably 11¹²⁻²⁸, a section which we observed at the outset to be also distinct from 11¹⁻¹¹, as making Moab, and not 'Ammon, the aggressor. But 11^{30.31.34-40} has also been argued to be distinct from 11¹⁻¹¹, on the ground that Jephthah the influential householder at Mišpah is distinct from Jephthah the outlaw. On the other hand, we have seen that 11²⁹ coheres with 11¹⁻¹¹, and not with 10¹⁷. The resumption of 11^{29b} may be seen in 11^{32a}, where the redactor of the two narratives picks up the thread which has been broken by the insertion of 11^{30.31}. Traces of the fusion of two accounts may perhaps be seen in 11^{33a}, since we appear to have a double *terminus ad quem* for the rout—'until thou comest to Minnith,' and 'as far as Abel-ceramim.' Probably 'from 'Aro'er until thou comest to Minnith' belongs to the Moabite narrative, the 'Aro'er in question being the frequently mentioned city on the Arnon at the northern boundary of Moab which has been mentioned in v. 26; though this is uncertain (cf. *note ad loc.*). 'As far as Abel-ceramim' may then be supposed to come from the 'Ammonite

* It is a point worthy of notice that, in the account of the institution of the monarchy in Israel in 1 Sam. 8-12, where two practically complete narratives, from J and E respectively, have been combined, the opening words of RJE's connective narrative in 11¹²⁻¹⁵ are phrased in precisely the same form as Judg. 10¹⁸:—

'And the people said every man to his fellow, Who is the man
'And the people said unto Samuel, Who is he

that shall begin to fight with the children of 'Ammon?
that said, Shall Saul reign over us?

he shall be head over all the inhabitants of Gile'ad.'
bring forth the men that we may put them to death.'

narrative, unless it be taken as a further definition of the *terminus ad quem*.

Lastly, we observe that the transition from 11⁴⁰ to 12¹ is somewhat unexpected. The account of the sacrifice of Jephthah's daughter, and the yearly commemoration of this event which was thereafter established, seems naturally to wind up the narrative; and the events related in 12¹⁻⁶ give us the impression of belonging to an originally different source. We may assign 12¹⁻⁶, therefore, to the 'Ammonite narrative 11¹⁻¹¹, etc., and we do this with the more confidence through observation of the fact that Jephthah's words in *v.*³, 'and I passed over unto the children of 'Ammon, and Yahweh gave them into mine hand,' are an echo of 11^{29b,32}. *

Thus we may reconstruct two distinct narratives, which probably ran originally as follows, square brackets being used where details have now to be supplied by conjecture.

(1) 10¹⁷, 11^{12-28,30,31,33} (in part), 34-40.

[The Moabites oppress the Israelite inhabitants of Gile'ad (some details possibly derived from this narrative by R^{JE} in 10^{8b,9a}). Jephthah, an influential citizen of Mišpah, undertakes the defence of his country. On the rumour, possibly, of warlike preparations among the Gile'adites], a Moabite army is mustered, and encamps in Gile'ad; the Israelite force being brought together in readiness at its leader's native city (11¹⁷). Before joining battle, Jephthah has recourse to diplomacy, but without success (11¹²⁻²⁸). He, therefore, decides to attack the Moabites; and vows that, if Yahweh will grant success to his arms, he will offer up a human sacrifice from among the members of his household (11^{30,31}). [The battle results in a decisive victory for Israel, the rout of the Moabites and slaughter of the fugitives extending] over a specified area, and including the destruction of twenty cities (11³³ in part). On Jephthah's return in triumph to Mišpah, his only daughter is designated by fate as the sacrificial victim. Though torn by grief, he is faithful to the terms of his vow; and a yearly commemoration of Jephthah's daughter thereafter becomes an institution among the daughters of Israel (11³⁴⁻⁴⁰).

In this narrative 'the children of 'Ammon' has been substituted for 'Moab' or 'the Moabites' ‡ in 10¹⁷, 11^{12,13,14,27,28,30,31}, and additions referring to the children of 'Ammon have been made in *v.*^{15,36}. The object of these changes was, of course, to bring the narrative into

* The threat of the Ephraimites in 12^{1b}, 'we will burn thy house over thee with fire,' might be supposed to point to the narrative in which Jephthah is a householder in Gile'ad (11^{31,34}) rather than to that in which he is an outlaw. This is a point, however, which need not weigh against the conclusion adopted above; since the first essential of the Gile'adites' compact with their new ruler (11^{9,10}) would be the granting him a residence at Mišpah.

‡ While the expression 'the children of 'Ammon' is regularly used to denote the 'Ammonites, we do not find 'the children of Moab' used of the Moabites; though we know of no reason why such a phrase should have been avoided.

line with the parallel narrative in which Jephthah appeared as deliverer from the 'Ammonite aggressions; and the author of them was the redactor of the two narratives whom we must assume to have been R^{JE}.

The source from which this narrative is derived is indicated by the fact, already noticed, that 11¹²⁻²⁸ depends very largely upon Num. 20¹⁴⁻²¹, 21^{13.21-24a}. These sections belong mainly, if not wholly, to E; and thus we are justified in inferring that E is the source of the narrative which makes use of them.

(2) 11¹⁻¹¹ (except vv. 1b.2.5a, on which see below), 11^{29.32b.33} (in part), 12¹⁻⁶.

Jephthah, a Gile'adite without any tribal position owing to the accident of his birth, becomes an outlaw from Israelite territory, and takes up his abode in the land of Tob, where he gathers a band of desperadoes like himself, and gains a reputation as a successful free-booter. The 'Ammonites commence hostilities against the Israelites in Gile'ad; and the elders of Gile'ad [having made an unavailing appeal for help to the tribes on the west of Jordan,* and] having no one among themselves equal to the task of raising and leading an army, are obliged to have recourse to Jephthah in the land of Tob, and to entreat his services. He consents upon the understanding that, if successful, he is to become ruler of Gile'ad, and the compact is sealed 'before Yahweh' at Misphah (11¹⁻¹¹). After traversing the country of Gile'ad and East Manasseh in order to raise an army, Jephthah advances against the 'Ammonites (v. 29) in order to attack them; Yahweh gives them into his hand (v. 32b), and he smites them with a great slaughter as far as Abel-ceramim (v. 33 in part). After the battle, an armed force of Ephraimites crosses the Jordan and threatens Jephthah with reprisals, upon the false excuse that he did not summon them to aid him in the battle with the 'Ammonites. Once more gathering the Gile'adites to his banner, he puts the Ephraimites to the rout, and seizing the fords of the Jordan, cuts off all fugitives, so that forty-two thousand Ephraimites are slain (12¹⁻⁶).

Since the other narrative must be assigned to E, the inference is that the present narrative belongs to J; and in favour of this we may remark that the arrogant conduct of the Ephraimites (12^{1ff.}) is strikingly similar to their behaviour to Gideon as related in the J narrative, *ch.* 8¹⁻³. A narrative reflecting discredit upon the Ephraimites, and possibly coloured by tribal antagonism, is more naturally assigned to a Judæan than to an Ephraimite source.

It only remains to notice interpolations in the narrative which appear to be very late in origin.

11^{1b.2}. It is clear from 11⁷ that Jephthah's expulsion from Gile'ad was tribal and not family. The 'brethren' of v. 3 are therefore his fellow-

* It is possible, however, that 11²⁹ in its original form may have related an ineffectual attempt made by Jephthah to gain the assistance of these tribes. Cf. *note ad loc.*

clansmen and not his natural brothers, as seems to be implied by *v.*². Moreover, it is evident from the use of 'Gile'ad' in *vv.*^{1b,2}, as though it were the name of an individual, that we have here to do with the method of narration which characterizes the late priestly school of writers, in which districts, clans, and cities are spoken of as individuals. Instances of this method are frequent in the genealogies of P and 1 Chr. (cf. for 'Gile'ad' so treated, *note* on 'Machir' *ch.* 5¹⁴); and we have already found illustration of it in the accounts of the 'minor' Judges, which, as we saw, emanated from the latest redactor, R^P.

The term בִּגְדָתִי 'begat,' *v.*^{1b}, is very characteristic of P. Cf. CH.^P 30.

It is clear, however, that the main narrative 10¹⁷⁻¹¹¹¹ is literal and not figurative, and deals actually with the doings of individuals. Possibly the reference in *v.*² to Jephthah's expulsion, 'and they drove out Jephthah' may have been derived from the main narrative (so Bu.); cf. *v.*^{7a}. On the other hand, it is very possible that *v.*^{7a} combined with *v.*^{1a} may be the *source* of the allusion in *v.*², as it comes from the hand of R^P (so Mo.).

11^{5a}. This half-verse is superfluous by the side of *v.*⁴, and has the appearance of a late gloss. It is omitted by G^{AL}; while G^b appears to include it and to omit *v.*⁴.

11^{26aβ}. The reference to Israel's possession of Gile'ad as having lasted undisputed for three hundred years is obtained by computation of the periods of oppression and deliverance (including the periods assigned to the 'minor' Judges) given in the preceding narrative up to the beginning of the 'Ammonite oppression (exactly, three hundred and one years). This date must therefore have been inserted by R^P or by some later hand.

12^{7b}. The record of Jephthah's death and burial is given precisely in the form which recurs in 8³², 10^{2b,5}, 12^{12,15}, and represents the regular formula of R^P.

It has been maintained by some scholars (cf. Sta., *GVI.* i. p. 68; Wellh., *Comp.*³ p. 224) that the story of Jephthah is altogether without historical basis. Tradition supplies no historical details as to his campaign. The account of his birth (cf. 11^{1b}, 'Gile'ad begat Jephthah') and death and burial (cf. 12^{7b} **¶**, 'and he was buried in the cities of Gile'ad') makes him a shadowy figure who is evidently only the *heros eponymus* of an obscure Gile'adite clan, apparently of mixed origin (cf. 11^{1a}, 'the son of a harlot'). The story is supposed to have grown up round the yearly festival which was customary in the narrator's time (11^{39,40}), and which was, in origin, a celebration of the death of the virgin-goddess, for the observance of which in Palestine evidence is forthcoming from other sources (cf. *Additional note*, p. 332).

The probability that the women's festival of later times may have been erroneously explained as commemorative of the sacrifice of Jephthah's daughter does not, however, compel us to conclude that

17. R^{JE} And the children of 'Ammon E were called to arms,

the story of this sacrifice was invented in order to account for the festival. The fact of such a sacrifice is not inherently improbable. There is ample evidence to prove that human sacrifice was not altogether unknown and unpractised among the Israelites in early times (cf. *Additional note*, p. 329); though it seems to have been sufficiently rare to have evoked the feeling of horror which is implicit in the narrative. It is at least as likely that an originally independent tradition of the death of Jephthah's daughter may have come to be associated with a festival the idolatrous origin of which was forgotten, as that the story is a deliberate invention without historical basis. The absence—or rather, the paucity—of details as to Jephthah's campaign is no argument against its historical truth. It might equally be urged, on the other hand, that a mere inventor would have found no difficulty in supplying such details.

These considerations have their weight even upon the assumption that the narrative is derived from a single source. If, however, as has been argued above, we have a combination of two somewhat variant traditions from J and E, the case for an historical basis for the tradition is greatly strengthened; more especially as one of these narratives appears (at any rate in the form in which we know it) to have been independent of the story of the sacrifice with its commemorative festival. The details of 11^{1b}, 12^{7b}, which are cited by Wellh. in support of his theory of a clan-myth, have been shown above to be additions which are due to the post-exilic hand R^P.

10. 17. *the children of 'Ammon.* This is the ordinary designation of this people; 'Ammon by itself occurring only twice, viz. 1 Sam. 11¹¹ (but \mathfrak{C} , S^P 'the children of 'A.'), and the late (probably Maccabean) Ps. 83⁷, \mathfrak{H} ⁸. The land of the children of 'Ammon (in Assy. inscriptions Bit Ammân, or, in short form, Ammân) lay immediately east of the territory captured by the Israelites from Šihon king of the Amorites, which formed the southern part of Gile'ad, between the Arnon and the Jabbok, and from which Šihon appears previously to have expelled the Moabites (cf. 11¹³ *note*). The boundary between the two territories is given in Num. 21²⁴ (\mathfrak{C}) as Ja'zer; * a city which Eusebius places ten Roman miles west of Philadelphia and fifteen miles from Heshbon (OS. 264⁹⁸). The site intended seems to be the modern Hirbet Šâr

* \mathfrak{C} $\delta\tau\iota$ $\text{Ia}\zeta\eta\rho$ $\delta\rho\iota\alpha$ $\nu\acute{\iota}\omega\upsilon$ $\text{A}\mu\mu\omega\upsilon$ $\acute{\epsilon}\sigma\tau\iota\nu$. \mathfrak{H} $\text{בִּי עֵן נָבֹל בְּנֵי ע'}$ 'For the border of the children of A. *was strong*,' gives an unsuitable sense in the context; and \mathfrak{C} 's reading יְעָזֶר (of which ע is a relic) is generally adopted.

Josh. 13²⁵ P (probably influenced by David's conquests, as related in 2 Sam. 10. 11) assigns to the tribe of Gad 'half of the land of the children of 'Ammon as far as 'Aro'er which is to the east of Rabbah.' In contrast with this, Deut. 2¹⁹ represents Moses as forbidding the Israelites to encroach upon 'Ammonite territory.

and encamped in Gile'ad. And the children of Israel

—a name which may possibly preserve a relic of the ancient name, in spite of the difference of sibilant.* The name 'Ammon is preserved in the modern 'Ammân, the site of Rabbah or Rabbath-'Ammon, the chief city of the 'Ammonites, which was rebuilt in the second century B.C. as the Roman city Philadelphia, considerable remains of which still survive.

were called to arms. Cf. 6³⁴ note.

Gile'ad. The country immediately east of Jordan, when accurately described in the O.T., is divided into three divisions—the Mîshôr or 'Table-land' to the south, Gile'ad (or 'the Gile'ad') in the centre, and the Bashan to the north: cf. Deut. 3¹⁰, 4⁴³, Josh. 20⁸. This division corresponds with the physical characteristics of the country: cf. especially Smith, *HG.* pp. 534 f. The Mîshôr, 'an absolutely treeless plateau,' covers the southern half of the modern el-Belkâ, extending from the Arnon to a line a little north of Heshbon, 'practically coincident with the Wâdy Heshbân' (Smith, *HG.* p. 548). North of this, 'the country is mainly disposed in high ridges' of limestone, 'fully forested,' as far as the Yarmuk. This is the ancient Gile'ad, the name of which, if rightly connected with the Ar. *ġa'ad* 'hard, rough,' is to be understood as referring to the geological characteristics of the mountain-ridges (cf. Conder, in Smith, *DB.* 2 i. 1191a). North of the Yarmuk lies the Bashan (cf. Ar. *batneh* 'soft and smooth ground'), an ancient volcanic region, where 'the soil is rich, red loam resting on beds of ash,' and the rock black basalt.

Gile'ad is divided into halves by the Jabboḳ (cf. Deut. 3¹², Josh. 12^{2,5}, 13³¹). The southern half, together with the Mîshôr (*i.e.* all the country between the Arnon and the Jabboḳ) was conquered by Israel from Šihon king of the Amorites (Josh. 12²), and became the territory of the tribes of Gad and Re'uben (Deut. 3¹²). According to P in Josh., the Mîshôr fell to Re'uben (13¹⁵⁻²³), and South Gile'ad to Gad

* Philological purists question, or even categorically deny, the possibility of connexion between the names *Ya'zēr* and *Šār* on the ground of the difference between the sibilants. It is more than doubtful whether such an attitude is justified. That *z* and *š* were very easily confused, both within the Hebrew language itself and among the different Semitic languages, is proved by such variations as Heb. *zāḳ* and *šāḳ*, *zār* and *šār*, *zrb* and *šrb* (where the variation appears to be purely *accidental*, and not to embody any different shade of meaning); Heb. and W. Aram. *šdḳ*, but Palmyrene and Syr. *zdḳ*; Heb. *šayidh*, but Ar. *zād*, Aram. *z'wādhū*, Bab. *š(z)iditu*. If such interchanges as these are possible, it goes without saying that a place-name preserved for many centuries by means of popular pronunciation merely may quite conceivably have substituted *š* for an original *z*.

If *Šār* really represents *Ya'zēr*, the wearing away of the opening syllable with its weak consonants may be illustrated by Yible'ām and Bile'ām, modern Bel'ameh; Yizr'el, mod. Zer'in; 'Ayyālôn, mod. Yâlô; Bêth-'ēked, mod. Blt-kād; 'Aphēḳ, (probably) mod. Flḳ.

gathered themselves together, and encamped in Mišpah. 18. R^{JE} And 'the people of Israel' said every man to his fellow, 'Who is the man who will begin to fight with the children of 'Ammon? he shall be head over all the inhabitants of Gile'ad.'

(13²⁴⁻²⁸). North Gile'ad is assigned, together with the Bashan, to East Manasseh (Deut. 3¹³, Josh. 13²⁹⁻³³ P); and was probably conquered by Manassite clans from the west subsequently to the settlement in West Palestine: cf. *note* on 'Machir,' *ch.* 5¹¹.

Such is the more accurate application of the term 'Gile'ad'; though it seems at times to have been used with greater elasticity. Thus in Deut. 34¹ it denotes the whole of the country east of Jordan, as far north as Dan.: cf. also 1 Macc. 5^{20 ff.} Elsewhere, again, 'Gile'ad' is restricted exclusively either to the northern or the southern half of Gile'ad proper. In the present narrative (as in *ch.* 5¹⁷; cf. *note*) it denotes the southern half, including probably the Mishôr, *i.e.* the whole region between the Jabbok and the Arnon—the modern el-Belkâ. For the classified occurrences of the different usages, cf. BDB. *s.v.* The name of Gile'ad survives in the modern Ġebel Ġil'âd, the highest part of the mountain-range south of the Jabbok.

Mišpah. The site is unknown, and the various conjectures which have been put forward are devoid of all foundation. The name means 'place of outlook' (from the root *sāphā* 'to look out, watch'); hence we may infer that the city was situated on some eminence or spur of the Gile'ad-range overlooking a wide prospect. The Mišpah of Gen. 31⁴⁹ J can hardly be the same, since it must have lain *north* of the Jabbok on the north-east border of Gile'ad, overlooking Aramaean territory; unless, indeed, the verse is a later gloss upon its context, as there is some reason to suppose: cf. Driver, *Westm. Comm. ad loc.*

18. *the people of Israel.* Reading עַם יִשְׂרָאֵל in place of הָעָם יִשְׂרָאֵל 'the people, the princes of Gile'ad.' Here 'the princes of Gile'ad' is usually regarded as a late gloss, explicative of 'the people,' and intended to connect the verse with 11⁵. If this is the case, however, why do we not read 'the *elders* of G.,' as in 11^{5.7.8.9.10.11}? The term 'princes' is not used elsewhere in the narrative. Our emendation assumes that יִשְׂרָאֵל was misread as שְׂרֵי גִלְעָד; and that עַם, coming thus to be regarded as the Absolute, and not the Construct, State, received the addition of the Definite Article.

For the expression עַם יִשְׂרָאֵל, cf. 2 Sam. 18⁷, 19⁴⁰, 31⁴¹. In such a connexion עַם 'people' has almost the force of 'soldiers' or 'army'; cf. BDB. *s.v.*, 2d; *NHTK.* on 1 Kgs. 16¹⁶.

II. 1. J Now Jephthah the Gileadite was a mighty man of valour, and he was the son of a harlot: ^{R^p} and Gilead begat Jephthah. 2. And the wife of Gilead bare him sons; and when the wife's sons were grown up, they drave out Jephthah, and said to him, 'Thou shalt not inherit in our father's house, for thou art the son of another woman.' 3. J And Jephthah fled from his brethren, and dwelt in the land of Tob; and there

II. 1. *Jephthah.* The name means 'He (*i.e.* God) openeth' (*sc.* the womb?). The fuller form Jephthah-el is cited by Halévy as a proper name in Sabaeen (*Études Sabéennes*, 148¹), and occurs as a place-name in Josh. 19^{11,27} P. Cf. the proper name Pethahiah 'Yah has opened,' 1 Chr. 24¹⁶, *al.*

the son of a harlot. The mother may have been a non-Israelite; and seems, at any rate, not to have belonged to the father's clan. Jephthah, as his mother's son, was therefore outside the father's clan also. Cf. *note* on 'his concubine,' *ch.* 8³¹.

and Gilead begat, etc. Here the *district* is personified as father of Jephthah—a mark of late date for *vv.* 1b,2, which can have formed no part of the original narrative: cf. pp. 303 f. E^B , $\eta \epsilon \gamma \epsilon \nu \nu \eta \sigma \epsilon \nu \tau \omega \Gamma \alpha \lambda \alpha \alpha \delta$, E^{AL} , $\Sigma^h \kappa \alpha \iota \epsilon \tau \epsilon \kappa \epsilon \nu \tau \omega \Gamma \alpha \lambda \alpha \alpha \delta$, seem merely to represent attempts to improve the connexion with *v.* 1a, and not an originally different text $\text{וַיִּתְּלָךְ לָנֶגֶד}$.

3. *the land of Tob.* In 2 Sam. 10^{6,8} 'the men of Tob' are mentioned, together with the Aramaeans of Beth-Rehob and Zobah and the king of Ma'acah, as allied with the 'Ammonites in their war with David. $\tau \acute{\omega} \beta \iota \omicron \nu$ or $\tau \omicron \upsilon \beta \iota \omicron \nu$ east of Jordan, 1 Macc. 5¹³, the inhabitants of which are called $\tau \omicron \upsilon \beta \epsilon \iota \nu \omicron \iota$ or $\tau \omicron \upsilon \beta \iota \alpha \nu \omicron \iota$ in 2 Macc. 12¹⁷, is probably the same district. The Jerusalem Talmud makes the land of Tob identical with Šūsītha (*Shebiith*, vi. 1, fol. 36c), which is identified by Neubauer (*Géographie du Talmud*, p. 239) with Hippos in the Decapolis, *i.e.* probably the modern Šūsīyyeh on the eastern side of the Sea of Galilee. This would seem to suit Sayce's proposed identification (*Records of the Past*,² v. p. 45) with Tubi mentioned by Thutmose III. in a list of conquered cities a little before Astiratu, *i.e.* Tell 'Aštarah, this latter being twenty miles east-north-east of Šūsīyyeh. Conder (*Heth and Moab*, p. 176) and Smith (*HG.* p. 587) find the name Tob in the modern eṭ-Tayyibeh, south of the Yarmuk and some eight miles a little south of due west of Irbid. Buhl. (*Geogr.*, p. 257, *n*⁸⁶⁷) refers to another eṭ-Tayyibeh, some twenty-three miles east of Irbid, between Der'â and Boṣrâ.

worthless men. Lit. 'empty men,' as in *ch.* 9⁴. 'Worthless' is not altogether a satisfactory rendering. Heb. *rêḳīm*, as here used, does not specifically imply moral obliquity; but rather a lack of the qualities which command success in the leading of a regular life

collected themselves worthless men unto Jephthah, and they went out with him.

4. And after a while the children of 'Ammon fought with Israel. 5. Gl. And when the children of 'Ammon fought with Israel, the elders of Gile'ad went to fetch Jephthah from the land of Tob. 6. And they said to Jephthah, 'Come, and be our ruler, that we may fight with the children of 'Ammon.' 7. And Jephthah said to the elders of Gile'ad, 'Was it not ye who hated me, and drave me out from my father's house? Why then are ye come unto me now when ye are in straits?' 8. And the elders of Gile'ad said unto Jephthah, 'Therefore have we now returned unto thee; so go with us, and fight with the children of 'Ammon, and thou shalt be head over us, even over all the inhabitants of Gile'ad.' 9. And Jephthah said unto the elders of Gile'ad, 'If ye bring me back to fight with the children of 'Ammon, and Yahweh deliver them before me, I shall be head

('ne'er-do-wells'), and possibly also (as suggested by the usage of the adverbial form *rêkām*, 'with empty hands') a lack of material goods such as property and tribal status. Cf. the description of the men who attached themselves to David when he was leading the life of an outlaw in the cave of 'Adullam, 1 Sam. 22². These include unsuccessful, needy, and discontented men, to whom it is not necessary to suppose that any *moral* stigma was attached. In 2 Sam. 6²⁰, 2 Chr. 13⁷, *rêkīm* does seem to denote the absence of specific moral qualities. In post-Biblical Heb. the term comes to denote *intellectual* vacuity (cf. the use of *κενός* in Jas. 2²⁰); but is also often used as a general term of contempt (so probably 'Paká = נָקִי in Matt. 5²²).

went out with him. I.e. engaged in predatory forays.

5. *And when, etc.* Literally rendered, the Heb. runs, 'And it came to pass, when the children of 'A. fought with Israel, *and* the elders of G., etc.,' it being idiomatic in Hebrew to continue with 'and' after the time-determination, which is really a parenthesis. Thus, if we regard the first half of the verse as a later gloss (cf. p. 304), the 'and' connects v.^{5b} directly on to v.⁴. Cf. the similar *note* on ch. 1¹ 'the children of Israel enquired.'

6. *ruier.* Heb. *kāšîn* is the philol. equivalent of Ar. *kādy*—properly one who *decides* judicially. On the *n*-termination, cf. Bevan, ZA. xxvi. (1912), p. 37.

8. *Therefore, etc.* The words contain a tacit admission that they were in the wrong. At all costs it was necessary to secure Jephthah's aid without further parley. $\text{Ⲙ}^{\text{AL}} \text{ⲟϥ} \text{ⲟϣⲣⲱⲥ}$, i.e. בֵּן לֹא for בֵּן לְבֵן, is certainly incorrect.

over you?' 10. And the elders of Gile'ad said unto Jephthah, 'Yahweh shall be hearer between us; surely according to thy word so will we do.' 11. So Jephthah went with the elders of Gile'ad, and the people set him over them as head and ruler; and Jephthah spake all his words before Yahweh in Mišpah.

12. ^E And Jephthah sent messengers unto the king of ^{RJE} the children of 'Ammon, ^E saying, 'What hast thou to do with me, that thou art come unto me to fight against my land?' 13. And the king of ^{RJE} the children of 'Ammon ^E said unto the messengers of Jephthah, 'Israel took away my land when they came up out of Egypt, from Arnon even unto the Jabbok, and unto the Jordan: now, therefore, restore [it] peaceably.' 14. And

10. *hearer.* The expression is used in a judicial sense, as in 2 Sam. 15³, Deut. 1¹⁷, *al.* Cf. the manner in which the compact is sealed, as related in v. 11^b.

11. *and Jephthah spake, etc.* The reference is to the compact of v. 10. Jephthah was not content with a merely casual promise; but took care that it should be solemnly ratified at the local sanctuary of Mišpah, and therefore in Yahweh's presence as 'hearer.'

12. *unto the king of the children of 'Ammon.* Upon the reasons which compel us to suppose that the message was addressed to *Moab*, and that, throughout vv. 12, 28, 'the children of 'Ammon' has been substituted for 'Moab,' cf. pp. 298 f.

What hast thou to do with me? Lit. 'What to me and to thee?' *i.e.* 'What business have we with each other?' the regular idiom in deprecation of interference: cf. 2 Sam. 16¹⁰, 19²², ^U 23, 1 Kgs. 17¹⁸, 2 Kgs. 3¹³, 2 Chr. 35²¹, Matt. 8²⁹, Mark 5⁷, John 2⁴. The ordinary rendering 'What have I to do with thee?' obscures the sense.

13. *Israel took away my land, etc.* The excuse had some amount of justification if, as we gather from Num. 21²⁶, the territory in question, though captured by Israel from Šihon king of the Amorites, had previously been wrested by Šihon from Moab.

from Arnon. The modern Wādy Mōgib, which runs into the Dead Sea from the east, about twenty-two miles from its northern end. A description of the ravine of the Arnon is given on p. 221.

even unto the Jabbok. The modern Wādy ez-Zerkā, the principal tributary of the Jordan. The distance from the Arnon to the Jabbok is about fifty miles; and the breadth of the strip of territory from the Jordan to Hīrbet Šār (assuming this to be the site of Ja'zer; cf. 10¹⁷ note) about sixteen miles.

restore it. Reading sing. אֶתָּה (in reference to אֶרְצִי 'my land') with some MSS. of ^U, ^L, ^V, in place of ^U plur. אֶתָּהֶן.

Jephthah sent messengers yet again unto the king of ^{RJE} the children of 'Ammon, 15. E and said to him, 'Thus saith Jephthah, Israel did not take away the land of Moab,^{RJE} and the land of the children of 'Ammon. 16. E But when they came up from Egypt, Israel went through the wilderness unto the Red Sea, and came to Kadesh. 17. And Israel sent messengers unto the king of Edom, saying, "Prithee, let me pass through thy land"; but the king of Edom hearkened not: and also unto the king of Moab did he send; but he was unwilling: so Israel dwelt in Kadesh. 18. Then he went through the wilderness, and compassed the land of Edom and the land of Moab, and came along the eastern side of the land

15. *and the land of the children of 'Ammon.* Cf. pp. 299, 302.

16. *went through . . . to Kadesh.* Bu., following Wellh. and Holzinger, finds in this passage support for the theory of a more original narrative of the wilderness-journey, direct from the Red Sea to Kadesh, which was the scene of the giving of the Law. But, however probable may be the theory which locates Sinai or Horeb in the near neighbourhood of Kadesh (cf. pp. 109 ff.), no support can justly be drawn for this or any similar theory from the present passage; since Jephthah's sole concern was to relate the negotiations which took place *from Kadesh*, and any allusion to earlier events of the journey, *e.g.* the law-giving at Sinai, would have been wholly out of place. La. remarks justly, 'Surtout Jephté ne peut vraiment pas remonter au déluge; les faits du Sinai n'avaient rien à faire ici: il mentionne la sortie d'Égypte par la mer Rouge et arrive aussitôt à Cadès, point de départ des négociations.'

17. *And Israel . . . Edom.* Cf. Num. 20¹⁴ E, 'And Moses sent messengers from Kadesh unto the king of Edom.'

Prithee . . . land. Cf. Num. 20¹⁷ E, 'Prithee let us pass through thy land.'

but the king of Edom hearkened not. A summary of Num. 20¹⁸⁻²¹ E. *and also unto the king of Moab, etc.* We find no account of negotiations with Moab in Num. or Deut.

Israel dwelt in Kadesh. Cf. Num. 20^{1aβ} E, Deut. 1⁴⁶.

18. *Then he went . . . Edom.* Cf. Num. 20^{21b-22a}, 'So Israel turned aside from him. And they journeyed from Kadesh,' Num. 21⁴, 'by way of the Red Sea to compass the land of Edom.' All that intervenes in Num., from 20²² to 21⁴ down to 'Mount Hor,' is derived from sources other than E.

compassed. *I.e.* 'went round,' so as to avoid encroaching upon it.

and came along . . . Moab. Cf. Num. 21¹¹ E, 'and they encamped . . . over against Moab on the eastern side.'

border, and Šihon gathered together all his people, and they pitched in Jahaš; and he fought with Israel. 21. And Yahweh the God of Israel gave Šihon and all his people into the hand of

is to suppose that the **את** before **ישראל** is a corruption of **נתת**, which was already existent in the Heb. MS used by **Gr. M**, as it stands, is rendered by R.V. 'But Šihon trusted not Israel to pass, etc.'; but the Heb. construction is impossible. Had the writer wished to use the verb **האמין** in this connexion he would have written some such sentence as **וְלֹא הָאֱמִין ס' בִּישׁ' וְלֹא נָתַן לוֹ עֶבֶר וְנֹ' 'But Šihon did not trust in Israel, nor suffer them to pass, etc.'** Deut. 2³⁰, **וְלֹא אָבָה ס' מֶלֶךְ הַחֲשֹׁבֹן הָעֵבְרָנוּ בֹ' 'But Šihon king of Heshbon was not willing to let us pass by him.'**

and *Šihon gathered . . . Israel*. Cf. Num. 21²³ E, 'and Šihon gathered together all his people, and went out against Israel to the wilderness, and came to Jahaš, and fought with Israel'; Deut. 2³² 'and Šihon came out against us, he and all his people, to battle at Jahaš.'

in Jahaš. Heb. **בִּיהָצָה** 'in Jáhšah,' with so-called **ה** *locative* ending. So Jer. 48²¹, 1 Chr. 6⁷⁸, **מ** 63; cf. Num. 21²³, Deut. 2³² (where, however, the **ה** *loc.* may embody the sense of *direction towards*, after a verb of motion—'to Jahaš'). We find the form **יְהָצָה** Jáh^ašah, Josh. 13¹⁸. Elsewhere the form is Jáhāš; Isa. 15⁴, Jer. 48³⁴, *Moabite Stone*, ll. 19, 20. The site is unidentified. Our narrative suggests that the city must have lain on the south-east border of Šihon's territory, north of the upper reaches of the Arnon, and this view is supported by its mention in 1 Chr. 6⁷⁸ as a Levitical city in Re'uben next before *Ķedemoth*: cf. the reference in Deut. 2²⁶ to the wilderness of *Ķedemoth* (*i.e.* 'eastern regions') as the district outside Šihon's territory to the east from which Israel sent an embassy to him. Mesha' king of Moab says (*Moabite Stone, loc. cit.*), 'And the king of Israel had built Jahaš, and abode in it, while he fought against me. But Chemosh drove him out from before me; and I took of Moab two hundred men, even all its chiefs, and I brought them up against Jahaš, and took it, to add it unto Dibon.' This suggests proximity to Dibon (the modern *Dibān*), to the east of which the site of Jahaš is probably to be sought. Eusebius states (*O.S.* 264⁹⁴) that the site was shown in his day between Medeba and Dibon (if this is intended by *Δηβους*); but this would place it too far to the west, well into the interior of Šihon's territory.

21. *And Yahweh . . . smote them*. Cf. Deut. 2³³, 'And Yahweh our God gave him up before us, and we smote him and his sons and all his people.' Num. 21^{24a} E has simply 'and Israel smote him at the edge of the sword.'

Israel, and they smote them: so Israel possessed all the land of the Amorites, who dwelt in that land. 22. And they possessed all the border of the Amorites, from Arnon even unto the Jabbok, and from the wilderness even unto the Jordan. 23. So now, Yahweh the God of Israel hath dispossessed the Amorites from before his people Israel, and shouldest *thou* possess them? 24. Those that Chemosh thy god dispossesseth[†]—wilt thou not

so Israel possessed, etc. Cf. Num. 21²⁶ E, 'and Israel dwelt in all the cities of the Amorites.'

22. *And they possessed, etc.* Cf. Num. 21^{24b} E, 'and possessed his land from Arnon unto Jabbok, unto the children of 'Ammon; for 'Ja'zer¹ is the border of the children of 'Ammon' (on the reading, cf. *note* on 10¹⁷). In Deut. 2^{36.37} the conquered territory is defined as extending from 'Aro'er on the edge of the Wâdy Arnon as far as Gile'ad, *i.e.* the northern half of Gile'ad, north of the Jabbok (on the variations in the use of the term 'Gile'ad,' cf. *note* on 10¹⁷); and the fact is carefully noted that no encroachment was made on the territory of 'Ammon, this latter being defined as 'all the side of the Wâdy Jabbok and the cities of the hill country': cf. Josh. 12² R^D. Here the reference must be to the *upper course* of the Jabbok, which, starting eastwards in the neighbourhood of Hirbet Sâr (Ja'zer) takes a northward and then north-westward curve before turning due westward, and thus seems in this passage to be regarded as the (ideal) boundary between Israel and 'Ammon.*

23. *and shouldest thou, etc.* The italics, here and in v.²⁴, represent great emphasis in the original.

possess them. *I.e.*, of course, 'possess *their* territory.' So in v.²⁴.

24. *those that Chemosh, etc.* The speaker assumes just as real an existence for Chemosh as for Yahweh. He is no *monotheist* in the proper sense of the term, *i.e.* he does not hold the doctrine that Yahweh is the one and only God of the whole earth, and that the existence of other gods is a delusion. Yahweh is for him, doubtless, the sole object of Israel's allegiance and worship; but the holding of

* In Num. 21^{24b} it is doubtful whether 'unto Jabbok' defines the northern limit of the territory merely; or, taking a comprehensive survey of the whole course of the wâdy, makes the reference to define the northern *and* eastern borders. On the latter hypothesis, 'unto the children of 'Ammon' is a *further* definition of this north-east border-line in so far as the upper part of the Jabbok-wâdy is identical with the border of 'Ammon. The fact, however, that in our passage in Judg. 'unto Jabbok' clearly defines the *northern* limit of Sîhon's territory, 'from the wilderness' explaining the eastern limit, makes it probable that the expression is used in the same way in Num., the statement meaning—the strip of territory as defined from south to north, of which the eastern limit is the land of 'Ammon, marching with Sîhon's territory along a line which runs approximately north and south through Ja'zer. Cf. Gray *ICC. ad loc.*

possess *them*? so, all that Yahweh our God hath dispossessed from before us—*them* will we possess. 25. Now, then, art this faith (monolatry) does not hinder him from believing that Chemosh really stands in the same kind of relation to Moab as Yahweh does to his own nation; *i.e.* he thinks of Yahweh as the *national God* of Israel, not as the God of the whole earth. His religious belief thus differs from that of the eighth-century prophets and their successors, who proclaim a doctrine of virtual monotheism—*i.e.* a doctrine which, if not as yet in all respects worked out to its logical conclusion, yet undoubtedly contains all the elements of a full belief in the existence of one God only. Further passages in the O.T. which embody the more primitive conception are noticed and discussed in the editor's *Outlines of O. T. Theology*, pp. 34 ff.

Chemosh. Cf. *Introd.* to the narrative, p. 299. Chemosh is always mentioned elsewhere in the O.T. as the god of the Moabites; Num. 21²⁹, 1 Kgs. 11^{7,33}, 2 Kgs. 23¹³, Jer. 48^{7,13,46} †. In Num. 21²⁹, Jer. 48⁴⁶ Moab is called 'the people of Chemosh.' In the inscription of the *Moabite Stone* Mesha' king of Moab ascribes the oppression of Moab by Israel to the fact that 'Chemosh was angry with his land' (l. 5); and the turn in Moab's fortunes which is marked by successes against Israel is regarded as due to the renewal of the favour of the god (ll. 8 f., 33), who is pictured as directing Mesha's plan of campaign: 'And Chemosh said unto me, Go, take Nebo against Israel' (l. 14); 'Chemosh said unto me, Go down, fight against H̄oronên' (l. 32). Chemosh is represented as the leader in battle, 'Chemosh drave him (the king of Israel) out (of Jahas) from before me' (l. 19); the population of the city of 'Aṭaroth is utterly devoted to him as a 'gazing-stock' or spectacle over which he may gloat with satisfaction (רִית,* l. 12); and the altar-hearth of the divine Patron ‡ of the city is dragged before him at Keriyyoth as a trophy (ll. 12 f.). In this mode of thought, and the phraseology in which it finds expression, we cannot fail to trace close resemblance to the ideas which were current in Israel in early times as to Yahweh's relationship to His people.

Two kings of Moab, as known to us, bear names which are honorific to Chemosh—Chemoshkân, § *i.e.* '(He whom) Chemosh has established' (cf. בְּנֵיהוּ, יְהוֹיָכִן, similar forms in honour of Yahweh),

* Probably to be vocalized רִית, a contracted form from רִיאִית from the verb רָאָה. Cf. Halévy, *Revue Sémitique*, xiv. (1906), pp. 180 f.; Grimme, *ZDMG*. lxi. (1907), pp. 81 ff.

‡ Cf. note on 'Dodo,' ch. 10¹.

§ The second element in the name is doubtful, the letters being nearly illegible. The reading adopted is that of Lidsbarski, as the result of a fresh examination of the stone (cf. *Ephemeris für Semit. Epigr.* i. pp. 3 f.). The old reading, Chemoshmclekh, seems to be excluded by the fact that there is scarcely room for more than two consonants. Clermont-Ganneau has suggested Chemoshgad.

thou at all better than Balak the son of Šippor, king of Moab? Did he contend at all with Israel, or did he fight at all against them? 26. When Israel dwelt in Heshbon and its dependencies, and in 'Ar^oe^r and its dependencies, and in all the cities

the father of Meshā' (*Moabite Stone*, l. 1), and Kammusunadbi, the Assy. form of Chemoshnadab, *i.e.* probably 'Chemosh is liberal *or* princely' (cf. יהונדב, אבנדב), who is mentioned by Sennacherib as paying tribute in B.C. 701 (*K.B.* ii. p. 90). The Bab. form (ilu) Ka-mu-šu-šar-ušur '(god) Chemosh protect the king' occurs in a business-document of the sixth year of Cambyses (quoted in *KAT.*³ p. 472). Two seals of doubtful date and genuineness bear respectively the legends לנמשדק '(belonging) to Chemoshšedek,' לכמשיחי '(belonging) to Chemoshy^{eh}hi,' in Phoenician characters (cf. Lidsbarski, *Ephemeris für Semit. Epigr.* i. pp. 136 ff.); and each has a representation of the winged solar-disk, possibly, as Baethgen suggests (*Beiträge*, p. 14), connecting Chemosh with the sun.

dispossesseth. Reading ירִישֶׁךָ with Mo. in place of יִרְשֶׁךָ, R.V. 'giveth thee to possess.' The correction seems to be demanded by the parallel clause in the latter half of the verse, and the final כ may very probably have arisen through dittography from the initial letter of כְּמוֹת. On the verb *hōrīš*, meaning both 'to cause to possess' and 'to dispossess,' cf. *note* on 1¹⁹.

25. *Balak the son of Šippor.* The story of Balak and Bala'am, Num. 22²-24²⁶, is a composite narrative which raises problems of more than ordinary difficulty. Most scholars hold that the sources J and E are here combined: but the characteristics of J are not so well marked as those of E, and the existence of the former source has thus been questioned; whilst the question of the stages by which the narrative attained its present form affords scope for considerable difference of opinion. Cf. Gray's full discussion in *ICC.* pp. 307 ff.

26. *dependencies.* Lit. 'daughters.' Cf. *ch.* 1²⁷. The expression is commonly characteristic of J.

'*Ar^oer.* Vocalizing, as normally, עֲרֵעַר, in place of the anomalous עֲרֵעַר of *fl.* The city is the modern 'Ará'ir: cf. *note* p. 221. It is commonly mentioned as situated 'on the edge (lip) of the Wādy Arnon,' and as the southernmost limit of the territory conquered by Israel from Šihon.

עַ, in place of 'in 'Ar^oer' reads ἐν 'Ιαζην, and in place of 'by the side of Arnon,' Εἰς reads παρὰ τὸν 'Ιορδάνην, ὕ 'juxta Jordancem'; and these readings are adopted by Mo. (*SBOT.*, followed by La., Cooke) on the ground that '*Ar^oer* and the *Arnon* come from *az*,¹⁸ (cf. Num. 21¹³ ff.); while *Jaazer* and the *Jordan*, which are not suggested by anything in the context, are original.' More probably, as Bu.

which are by the side of Arnon,^{R^P} three hundred years; ^E why, pray, didst 'thou' not recover 'them' at that time? 27. *I*, therefore, have not sinned against *thee*; but *thou* doest *me* wrong in fighting against me. Let Yahweh, who is Judge this day, judge between the children of Israel and the children of ^{R^{JE}} 'Ammon.' 28. ^E Howbeit, the king of ^{R^{JE}} the children of 'Ammon' ^E hearkened not unto the words of Jephthah which he sent unto him.

29. *J* And the spirit of Yahweh came upon Jephthah, and he

(*Comm.*) suggests, they represent a later attempt to adapt the argument to Israel's relations with 'Ammon', instead of (as was originally intended; cf. pp. 298 ff.) with *Moab*. On Ja'zer, as marking the boundary between the territories of Israel and 'Ammon, cf. *notes* on 10¹⁷, 11²².

three hundred years. On the source of this figure, cf. p. 304.

why, pray. Lit. 'and why.' On the idiomatic use of ו copulative to give a forcible and sarcastic turn to a question, cf. *NHTK.* on 1 Kgs. 2²², and *note* on ch. 6¹³.

didst thou not recover them. Vocalizing הִצִּילָתָם with Ἐρρύσω αὐρούς, Stu., Mo., in place of הִצִּילָתָם (plural verb with object unexpressed). The sing. verb is in agreement with the context, the subject being, not the particular king of Moab addressed, but the land of Moab personified as an individual. Cf. v. 27^a, where 'I' clearly refers, not to Jephthah, but to Israel (cf. v. 15). Strictly speaking, we should expect a fem. suff. in reference to the 'cities' preceding; but such a use of masc. suff. for fem. is not uncommon: cf. G-K. § 135*o*.

27. *I, therefore, etc.* For the form and thought of the sentence, cf. 1 Sam. 24^{12b}, 'And I have not sinned against thee, but thou art hunting my life to take it.'

who is Judge this day. Connecting הַיּוֹם closely with הַיּוֹם, as the order of words seems to demand. So Mo. R.V., in agreement with accents (which connect הַיּוֹם more closely with the preceding הַיּוֹם than with the following הַיּוֹם), renders 'The Lord, the Judge, be judge this day,' making הַיּוֹם to refer to the verb יִשְׁפֹּט at the commencement of the sentence. For the invocation of Yahweh as arbiter between two parties, cf. Gen. 16⁶ J, 1 Sam. 24¹², 31¹³.

29. *And the spirit of Yahweh, etc.* Cf. ch. 3¹⁰ *note*.

and he passed, etc. The passage is obscure; but not so obscure as it appears to those scholars who fail to recognize the combination of two sources in the narrative (cf. the remarks of Mo., and the paraphrase of them given by Cooke). Looking at the opening statement of the verse, 'And the spirit of Yahweh came upon Jephthah,' and comparing it with the connexion in which the identical phrase (of 'Othniel)

passed through Gile'ad and Manasseh, and he passed over ^{to} Mizpeh of Gile'ad, and from Mizpeh of Gile'ad he passed over ^{<to>}

stands in 3¹⁰, and the similar phrase (of Gide'on) in 6³⁴, we may justly infer that what follows refers to Jephthah's efforts to raise an army to meet the 'Ammonites: nor is this inference invalidated by the fact that, according to 10¹⁷, an army had already been mustered (Mo., Cooke), since, as we have seen, this verse belongs to a different narrative. Even 11^{11a}, which, according to our analysis, belongs to the *same* source as 11²⁰, cannot be cited to the contrary (as by Mo.), since 'the people' of Gile'ad who made Jephthah their head can hardly have been already a fully organized army. They doubtless formed some part of the material for such an army; but the whole point of the narrative 11¹⁻¹¹ is that the Gile'adites resorted to Jephthah because they possessed no one of sufficient initiative not only to *lead* but also to *raise* an army at all adequate to meet the aggressor. Observing further that the closing statement of v.²⁰ (picked up and expanded in v.^{32a} after the interposition of a portion of the other source, vv.^{30,31}) speaks of Jephthah's advance to give battle to the 'Ammonites, it may be claimed that our inference that the middle part of the verse refers to the mustering of the army becomes a certainty.

Granted, however, that this is the case, it still appears most improbable that the narrative stands in its original form. The phrase *ויעבר את גלעד* can only be intended to mean 'and he *passed through* Gilead, etc.'; but in this sense the construction (*עבר* followed by the Accusative) is almost, if not quite, without parallel* (the regular construction is *עבר ב*). As the text stands, 'Gile'ad' is here, as elsewhere in the narrative, the region south of the Jabbok (cf. 10¹⁷ *note*), while 'Manasseh' most probably denotes the region to the north of the wady, *i.e.* East Manasseh. We cannot be sure that clans from West Manasseh had by this time crossed the Jordan and made their settlement in the east (they had not done so in the time of Deborah; cf. *note* on 'Machir,' *ch.* 5¹⁴); though this is a consideration which need not have weighed with a narrator who may have assumed that what was true of his own age was also true of an earlier period. Still, taking note of Jephthah's claim in 12² to have summoned *Ephraim* to his assistance without success (a statement which seems to presuppose an earlier reference in the narrative from

* Possible instances, *e.g.* Gen. 32³² *כאשר עבר את פנואל*, Josh. 16⁶ *[תאנת שלה] אותו [הגבול] ועבר*, are probably to be understood in the sense *pass by* (cf. with the Accus., Judg. 3²⁶, 2 Kgs. 6⁹), rather than *pass through*. In any case, these passages deal with *city-sites*, not with widely extended *districts* like Gilead and Manasseh. Notice the carefully marked contrast in Num. 20¹⁷, 21²² between *עבר ב* *pass through* or *traverse* a land, fields, vineyards, and *עבר* with Accus. *pass over* or *cross* the border of a land regarded as a definitely marked line.

to the children of Ammon. 30. ^E And Jephthah vowed a vow to Yahweh and said, 'If thou wilt indeed give ^{RJE} the children of 'Ammon^E into my hand, 31. then the person that cometh forth from the doors of my house to meet me, when I return in peace from ^{RJE} the children of 'Ammon,^E shall belong to Yahweh, and I will offer him up as a burnt offering.'

which it is drawn), it is not unlikely (as Holzinger and Bu. suggest) that 'Ephraim' may originally have stood in the present passage in place of 'Gile'ad'; in which case 'Manasseh' will ^{er} to West and not to East Manasseh. Thus (reading ^ל for ^א three times after ^{ויעבר}) the passage may have run 'and he crossed over (the Jordan) to Ephraim and to Manasseh, and he crossed over (again) to Mišpeh of Gile'ad.' The double ^{ויעבר}, if referring to his crossing and *re*-crossing the Jordan (cf. 6³³), is thus not redundant.

Even so, the passage must have been abbreviated from its original form, as 12² certainly presupposes prior mention of the fact that the appeal to Ephraim was fruitless. Probably the narrative was cut down and mutilated when the two sources J and E were pieced together; and this, possibly, in view of the fact that the narrative E in 10¹⁷ pictures the Israelite army as already mustered and encamped at Mišpah. Such a conclusion at any rate may suffice to account for the obscurity of the verse, which the view that it 'is a somewhat unskilful attempt to fasten the new cloth, *v.* 12²³, into the old garment' (Mo.), or (otherwise expressed) that 'an editorial hand has attempted to pick up the thread of the narrative after the long interpolation *vv.* 12²³' (Cooke) certainly does not do.

and he passed over to Mišpeh, etc. Reading ^ל for ^א, as seems to be demanded by the context. Whatever view be taken as to the precise form of the description of Jephthah's earlier movements (cf. *note* preceding), we can in the present statement scarcely find anything else than the account of his *return* to Mišpeh after raising his army, and immediately prior to his attack upon the foe. The forms Mišpeh, Mišpah appear to be used interchangeably with reference both to this locality and to others of the same name.

to the children of 'Ammon. Inserting ^ל before ^{בני עמון} with twelve MSS. of ^א.

^S *then the person that cometh forth, etc.* Lit. 'the comer-forth that ^S cometh forth'—a phrase which implies that from the first a *hu'* in sacrifice is contemplated. Ros., Stu., and others quote the reïgeskable parallel from Servius on *Aeneid*, iii. 331: 'Idomeneus de se ^{impe} Deucalionis natus, Cretensium rex, cum post eversam Trojare ^Hverteretur, in tempestate devovit diis sacrificaturum se de re, ^{que}, 'primum occurrisset. Contigit autem, ut filius ejus primus

32. ^{R^{JB}} So Jephthah passed over unto the children of 'Ammon J to fight against them, and Yahweh gave them into his hand.
33. And he smote them ^{E?} from 'Aro'er until thou comest to

occurreret : quem cum, ut alii dicunt, immolasset, ut alii, immolare voluisset, et post orta esset pestilentia, a civibus pulsus est regno.' Cheyne (*EB*. 2362) cites an Arabian tradition mentioned by Lyall (*Ancient Arabian Poetry*, Introd. p. xxxviii): 'Al-Mundhir had made a vow that on a certain day in each year he would sacrifice the first person he saw: 'Abid [a poet] came in sight on the unlucky day, and was accordingly killed, and the altar smeared with his blood.'

The narrator, though regarding the sequel of the vow—the fact that the victim should prove to be the hero's only child—as a terrible tragedy, yet does not seem to hold that such a vow is contrary to the spirit of Yahweh's religion. It is an extraordinary sacrifice, offered in a great emergency as a supreme bid for the active co-operation of the deity. Cf. the Moabite king's sacrifice of his firstborn son as a last resort (2 Kgs. 3 ^{26,27})—a costly sacrifice which is supposed by the narrator to have been effectual in arousing the god Chemosh, and thus enabling the Moabites to expel the invaders from their land.* On the further evidence for the occurrence of human sacrifice among the Israelites, cf. *Additional note*, p. 329.

33. *from 'Aro'er.* Besides the frequently mentioned ^{n. S}city on the edge of the Wâdy Arnon (cf. *v.* ²⁶ *note*), there was, according to Josh. 13 ²⁵ P, another city named 'Aro'er to the east of Rabbath-'Ammon, *i.e.* in 'Ammonite territory. Our ignorance as to the source of the present statement forbids our making a decision as to which 'Aro'er is here referred to. If (as we conjecturally suppose) the source is E, then the reference will be to 'Aro'er on the Arnon. If, on the other hand, the passage is an extract from J, the allusion probably is to the 'Aro'er of Josh. 13 ²⁵.

Minnith. The site is unknown. Eusebius (*OS*. 280 ⁴⁴) identifies it with a village called *Maavith*, four Roman miles from Heshbon, on the road to Philadelphia; a locality which, according to Buhl (*Geogr.* p. 266), would suit the modern ruins which bear the name *Hešrûm*. Such a position, however, appears unsuitable either to the Moabite (E) or the 'Ammonite (J) narrative. 'Unto Minnith' marks the extreme limit within which the twenty cities smitten must be pictured as lying; and clearly these can hardly have been *within the invaded territory*, *i.e.* *Israelite* cities which had previously been captured and occupied by the foe. Indeed, upon either view of the site of 'Aro'er, such an assumption is impossible, since 'Aro'er marks the *starting-point* of the conquest, which must be presumed to have extended to the N. mts.

* On this explanation of the somewhat obscure passage in 2 Kgs. 3 ²⁷, *et* *in* *there came great wrath, etc.*, cf. *NHTK. ad loc.*

Minnith, even twenty cities, J as far as Abel-ceramim, with a very great slaughter. R^{E2} So the children of 'Ammon were subdued before the children of Israel.

34. E And Jephthah came to Mispah unto his house; and behold his daughter coming forth to meet him with timbrels and with dances: and she was absolutely an only child; he had not beside [her] son or daughter. 35. And when he saw her, he rent his garments, and said, 'Alas, my daughter! thou hast indeed brought me low, and *thou* art become the supreme cause

Aro'er on the Arnon southward into Moabite territory (if the statement comes from E), or from 'Aro'er to the east of Rabbath-'Ammon presumably further eastward (if it comes from J).

Abel-ceramim. The name means 'meadow of vineyards'; and Eusebius (*OS.* 225⁵) informs us that in his day there was a village named Abel with productive vineyards (κώμη ἀμπελοφόρος) six miles from Philadelphia (Rabbath-'Ammon)—though in what direction he does not state. If we may assume that this is a correct identification, the statement 'as far as Abel-ceramim' is naturally to be assigned to J.

34. *and behold his daughter, etc.* So the Israelite women celebrate the triumph of their people in Ex. 15^{20 f.} E (exactly as here, 'with timbrels and with dances'), 1 Sam. 18^{6 f.}, Ps. 68¹¹ (H¹²).

she was absolutely an only child. The Heb. is extraordinarily emphatic—lit. 'and she only was an only child.' R.V., by omitting to render the Heb. רק, misses this emphasis altogether.

beside her. Reading מִפְּנֵיהֶּ with fem. suffix, in place of the erroneous מִפְּנֵיו 'beside him' of H. So G^{AL}, S^b, L, S^P.

35. *brought me low.* Lit. 'bowed me down.' The expression is very forcible.

the supreme cause of my trouble. Heb. בְּעֵקֶרִי. Lit. 'as (in the character of) my troublers,' the idiomatic ב *essentiae* (cf. BDB. *sub* ב I. 7) followed by the plural denoting *intensity* (the so-called *pluralis excellentiae*). R.V. 'thou art one of them that trouble me' misses the force of the expression altogether, supposing it to mean 'among my troublers.' We find exactly the same idiom in Ps. 54⁴ (H⁶), 'The Lord is *the great supporter* of my soul' (Heb. בְּסִמְכִי, lit. 'in the character of the supporters'); Ps. 118⁷, 'Yahweh is for me *my great helper*' (Heb. בְּעֻזִּי, lit. 'in the character of my helpers'). In both these passages (as in our passage) the feeble and erroneous rendering of R.V. implies that Yahweh is only one among many helpers!

The Heb. verb 'ākhar, for which the only general reading is 'to trouble,' denotes, as its occurrences prove, the causing of poignant

of my trouble; seeing that *I* have opened my mouth unto Yahweh, and cannot go back.' 36. And she said unto him, 'My father, thou hast opened thy mouth unto Yahweh; do to

distress or anxiety. In New Heb. it has the meaning 'to make turbid'; in Ar. *'akira* 'to be turbid.'

The renderings of Jephthah's words in \mathfrak{C}^B $\tauαραχῇ ἐτάραξάς με, καὶ σὺ ἦς ἐν τῷ ταραχῶ μου$, \mathfrak{S}^P $\text{לִּי־סִוָּתָאֲנִי־וְאַתָּה־עָרַבְתָּ־לִּי־מַיְמַיִם}$ 'Thou hast utterly overthrown me, and thou art to-day one of my overthrowers,' \mathfrak{F} 'deceperisti me, et ipsa decepta es,' suggest a Heb. original with the same verb in each clause. This may have been עָרַב; though in the thirteen other occurrences of this root none of these Versions represent it by the verbs which they use in this passage. \mathfrak{C}^{12} 's rendering of הכרע הכרעתני, $\epsilon\mu\pi\epsilon\pi\omicron\delta\omicron\sigma\tau\acute{\alpha}\tau\eta\kappa\acute{\alpha}\varsigma\ \mu\omicron\iota$ (so \mathfrak{C}^A in corrupt form, \mathfrak{S}^h $\text{לִּי־סִוָּתָאֲנִי־וְאַתָּה־עָרַבְתָּ־לִּי־מַיְמַיִם}$, \mathfrak{L} 'impedisti me') certainly suggests עָרַבְתָּנִי; cf. the rendering of עוֹבֵר by $\acute{o}\ \epsilon\mu\pi\omicron\delta\omicron\sigma\tau\acute{\alpha}\tau\eta\varsigma$ in 1 Chr. 2⁷. If, however, the first clause had originally run עָרַבְתָּנִי (עָרַב), or, as suggested by Houb., Grä., הָעָרַב הָעָרַבְתָּנִי (no occurrence of Hiph'il elsewhere), the following clause would be tautological, and we should suspect the existence of a doublet. The rendering of ואת היית בעברי given by the \mathfrak{C}^{AL} , \mathfrak{S}^h , \mathfrak{L} group, $\epsilon\iota\varsigma\ \sigma\kappa\acute{\omega}\lambda\omicron\nu\ \acute{\epsilon}\gamma\epsilon\nu\omicron\nu\ \acute{\epsilon}\nu\ \acute{o}\phi\theta\alpha\lambda\mu\acute{o}\iota\varsigma\ \mu\omicron\iota$ points to לְמִקְיַת הַיִּית בְּעֵינִי מִקְיַת (rendered by $\sigma\kappa\acute{\omega}\lambda\omicron\nu$ Ex. 10⁷, Deut. 7¹⁶, Judg. 8²⁷) being apparently taken by the translator in the sense of a *thorn* or *sharp-pointed instrument* (cf. its use in Job 40²⁴). More probably the Heb. was intended to mean 'Thou art become a snare in my sight,' *i.e.* an almost irresistible temptation to break the vow made to Yahweh, the existence of which he makes known to her in the next clause.

\mathfrak{T} , 'A., Σ ., Θ . support the text of \mathfrak{L} , from which there is no good reason to depart.

I have opened my mouth. The Heb. verb $p\bar{a}š\bar{a}$ 'to open' is similarly used (with subj. שִׁפְתַּי—'which my lips uttered') of making vows in Ps. 66¹⁴.

36. *do to me, etc.* Since the father has not actually *mentioned* his vow to the daughter, Bu. (*R.S.* p. 126) supposes that the narrative must have undergone abbreviation, the daughter's inquiry as to the cause of her father's distress, and his explanation of it, having fallen out. But Mo. is assuredly correct when he remarks, 'To me it seems, on the contrary, much more in accord with the native art of the storyteller that he lets the situation and a woman's quick presentiment suffice, without this prosaic explanation.'

me according to that which hath gone forth from thy mouth, forasmuch as Yahweh hath wrought for thee full vengeance upon thine enemies, ^{R^{JE}} even upon the children of 'Ammon.'

37. ^E And she said unto her father, 'Let this thing be done for me: let me alone two months, that I may go, ¹and wander free¹ upon the mountains, and weep over my maidenhood—I and my

that which hath gone forth, etc. The same expression is used of a vow in Num. 30² (וַיֵּשׁ).³

full vengeance. Heb. 'vengeances'—another case of the intensive plural. Cf., for other instances, G-K. § 124^e.

37. *and wander free.* Reading וַיֵּרֶדְתִּי with RSm., Kit., Cooke. Cf. the use of the verb *rûdh* in Jer. 2³¹ 'we have wandered at large'; and Ar. *râda* 'to go to and fro.'^{*} וַיֵּרֶדְתִּי 'that I may go *and go down* upon the mountains' is obviously impossible, it being a forced expedient to follow Kimchi, who explains that 'Mišpah, where Jephthah's house was, was higher than the surrounding mountains; or else the verb is used with reference to the valley which lay between Mišpah and the mountains.'[†] פ 'circumeam,' שׁ וְסָבַח 'walk about,' וְאֶתְנַחֵר 'and wander' (lit. 'extend myself') suggest our emendation וִירַדְתִּי; but may be simply paraphrasing וִירַדְתִּי in order to obtain the sense demanded by the context.

The view that וִירַדְתִּי is out of place, and should properly stand at the end of the verse, either as a gloss (Doorn.) or a genuine part of the text (Bu.), in the sense 'and then I will descend'—*i.e.* return from the mountains to offer myself as a willing victim—has nothing to commend it. If it is unnatural to speak of 'descending' from Mišpah to the mountains, the converse is equally unnatural; since Mišpah, as its name implies (10¹⁷ *note*), must have stood on a prominent height.

and weep over my maidenhood. Stanley (*Jewish Church*, I. Lect. xvi.) aptly compares the lament of Antigone (Sophocles, *Ant.* 890), of which

^{*} La. emends וְהִרַדְתִּי, the Hiph'il of the same verb in a similar sense (Internal Hiph'il as in Ps. 55³). This form should surely be vocalized וְהִרַדְתִּי, and not וְהִרַדְתִּי, as given by La.; ע"ו forms without separating vowel being rare (cf. G-K. § 72^k.).

[†] Kimchi actually brings forward the suggestion that וִירַדְתִּי may be explained from the verb *rûdh* which we have adopted in our emendation, and quotes Ps. 55³ in which the Internal Hiph'il occurs אֲרִיר בְּשִׁיחִי, 'I am restless (or toss to and fro) in my murmuring.' He then rejects this in favour of the explanation noticed above. Rashi is perplexed by the verb 'go down,' and explains that it is 'a term denoting lamentation, an example of which is seen in the passage (Isa. 15³) 'on their housetops and in their broad places every one lamenteth, running down (יָרַד lit. "going down") in weeping.'

companions.' 38. And he said, 'Go.' So he sent her away two months, and she went—she and her companions, and wept over her maidenhood upon the mountains. 39. And at the end of two months she returned unto her father, and he did to her that which he had vowed, she having never known a man. And it

the maiden's grief is 'the exact anticipation . . . sharpened by the peculiar horror of the Hebrew women at a childless death—descending with no bridal festivity, with no nuptial torches, to the dark chambers of the grave':—

ὁ τύμβος, ὃ νυμφεῖον, ὃ κατασκαφῆς
οἴκησις ἀείφρουρος, οἱ πορεύομαι . . .
καὶ νῦν ἄγει με διὰ χερῶν οὕτω λαβῶν
ἄλεκτρον, ἀνυμέναιον, οὔτε τοῦ γάμου
μέρος λαχοῦσαν, οὔτε παιδείον τροφῆς.

my companions. *Ḳerê* רְעוּתִי has the support of the analogous form רְעוּתִיָּה in *v.*³⁸. For the *Ḳt.* form רְעִיתִי, cf. רְעִיתִי, Cant. i^{9,15}, 2^{2,10,13}, 4^{1,7}, 5², 6^{4†}.

39. *and he did to her, etc.* Thus the narrator draws a veil over the final tragedy; but there can be no doubt that he intends to imply that the sacrifice was carried out. On the various explanations which have been offered in order to obviate this conclusion, cf. the very full note given by Mo., pp. 304 f. The earliest Jewish interpreters (*e.g.* *Ṭ.*, Josephus) and the Christian Fathers explained the passage in its natural sense; and it seems not to have been till the Middle Ages that another solution was sought. Thus Kimchi explains that Jephthah built a house for his daughter, in which she was kept in isolation from the world, and so in perpetual virginity; and that annually the daughters of Israel went to visit her and bewail her fate. This explanation, under differently modified forms, gained acceptance after Kimchi both among Jews and Christians. But the literal interpretation was never without its supporters, and is now the generally accepted view.

she having never known, etc. A circumstantial clause, of the form noted in Driver, *Tenses*, § 160. The emphasis laid on the virginity of the sacrificed maiden is perhaps bound up with the mythological motive which very possibly lies at the bottom of the yearly festival. Cf. *Additional note*, p. 332.

and it became a custom. Reading וְנָתַתִּי לָהֶק with La. The subject of the fem. verb וְנָתַתִּי is neuter; so exactly Ps. 69¹¹ וְנָתַתִּי לְתַרְבוֹתַי לִי 'and it became reproaches unto me.' On the use of the fem. in a neuter sense, cf. G-K. § 122*q*. The view of König (*Syntax*, § 323*h*) that the subject is the הִיא of the preceding sentence—'and she (the

became ¹¹ a custom in Israel; 40. yearly the daughters of Israel go to commemorate the daughter of Jephthah, four days in the year.

12. 1. J And the men of Ephraim were called to arms, and

maiden) became a pattern'—is very unlikely. **וַתְּהִי חֶק** makes the masc. **חֶק** the subject of the fem. verb—a want of concord which Bu. would remedy by reading **וַיְהִי**; but this does not give so idiomatic a phrase as that which we adopt.

Since the 'custom' refers to the women's festival mentioned in *v.* 40, it is clear that *v.* 39-40 are wrongly divided, and that **וַתְּהִי לְחֶק** should stand at the beginning of *v.* 40. As is noted by Le Clerc, Ros, etc., the reason for the division adopted by **פ** may be gathered from an addition in **ט**, according to which **חֶק** is explained, not as a 'custom,' but as an 'ordinance' forbidding the sacrifice of son or daughter, which is assumed to have been promulgated in order to obviate the recurrence of such a tragedy: 'It was made an ordinance in Israel in order that no man should offer up his son or his daughter for a burnt-offering, as Jephthah the Gile'adite did because he did not consult Phinehas the priest. If, however, he had consulted Phinehas the priest, he would have redeemed her at a price.'

40. *yearly*. Heb. **מִיָּמִים יְמִימָה**, lit. 'from days unto days,' *i.e.* 'from year to year,' in accordance with the idiomatic use of the plural **יָמִים**; cf. BDB. *s.v.* **יָמִים** 6 c.

the daughters of Israel go. The Imperf. **תֵּלְכֶנָּה** describes a frequentative action which still recurs in the writer's time. R.V. 'went,' *i.e.* 'used to go' (as though the annual custom had ceased) is certainly wrong.

to commemorate. On the meaning of the Heb. verb here used, cf. *note* on 'they recount,' *ch.* 5¹¹. The festival is discussed in *Additional note*, p. 332. Since the commemoration most probably took the form of a ceremonial *wailing*, we might expect some more specific term than **לְתַנּוֹת**. If the text should be emended, the easiest alteration would be **לְאֲנוֹת** 'to lament'; cf. the use of the verb in Isa. 3²⁶, 19⁸, and the substantival forms **וְאֲנִיָּה וְאֲנִיָּה** 'lamentation and mourning,' in Isa. 29², Lam. 2⁵. So Ball, privately.

12. 1. *And the men of Ephraim, etc.* On the resemblance between this incident and that recorded in *ch.* 8^{1ff}, cf. *note ad loc.*

were called to arms. Cf. *note* on 6³⁴.

passed over to Şaphon; and they said to Jephthah, 'Why didst thou pass over to fight with the children of 'Ammon without having called *us* to go with thee? We will burn thy house over thee with fire.' 2. And Jephthah said unto them, 'I had a quarrel—even I and my people, and the children of 'Ammon <oppressed me> sorely; and I 'summoned' you, but ye did not save me from their hand. 3. And when I saw that 'there was none' to save 'I put' my life in my hand, and passed over unto

to Şaphon. A city of this name is mentioned in Josh. 13²⁷ P, together with Succoth, as lying in the Jordan valley. This is identified by the Jerusalem Talmud (*Shebiith.* ix. 2, fol. 38 d) with מרתו, i.e. the Amathus of Eusebius and Jerome, twenty-one Roman miles south of Pella (*OS.* 91²⁷, 219⁷⁶), and the modern 'Amâteh, situated in the mouth of the Wâdy Râgib, about seven miles north of the Jabbok. But we should have expected the Ephraimites to have crossed the Jordan *south* of the Jabbok at the ford ed-Dâmiyyeh in order to reach Mişpah; and the position of Succoth, with which Şaphon is associated in Josh. 13²⁷, was probably south of the Jabbok: cf. p. 220. ע^B, 'A. Σ., Θ., Ψ, Σ^P render 'northward,' and this is adopted by R.V. text; but the rendering appears to be topographically impossible.

without having called us. Lit. 'and us thou hadst not called'—a circumstantial clause.

we will burn, etc. Cf. *ch.* 14¹⁵, 15⁶.

2. *I had a quarrel.* Lit. 'I was a man of strife.'

oppressed me. Supplying עננני, as suggested by ע^{AL} ἐταπείνων με (so L^L, S^b), with most moderns. This verb 'might easily be omitted by a scribe after עמון' (Mo.), and *some* verb is indispensable, unless (with Ψ 'contra filios Ammon,' Σ^P וְעַם אֲמֹנִים R.V. 'with the children of A.') we treat the ו as 'wāw of association': cf. cases cited by BDB. s.v. ו, 1 g.

and I summoned you. Reading Hiph'il וְאִזְעַק אֶתְכֶם, as in *ch.* 4^{10.13}, 2 Sam. 20^{4.5}. וְקָלַל וְאִזְעַק should be followed by אֶלְיָכֶם—'and I cried unto you' (cf. ע^{AL} καὶ ἐβόησα πρὸς ὑμᾶς).

The application made by the Gile'adites to the western tribes of Israel for help against the 'Ammonites finds a close parallel in 1 Sam. 11, where the inhabitants of Jabesh of Gile'ad seek help in this direction against the aggressions of Nahash, king of 'Ammon.

3. *that there was none to save.* Reading כִּי אֵין מוֹשִׁיעַ with ע^{AL}, S^b, Σ^P, Bu., Oort., No., La., Kit. For the phrase, cf. Deut. 28^{29.31}, 1 Sam. 11³, 2 Sam. 22⁴², Ps. 18⁴¹, וְ⁴². וְ כִּי אֵין מוֹשִׁיעַ 'that thou wouldest not save.'

I put, etc. Reading קָרַע וְאִתְּיָמָה in place of the anomalous קָלַ.

the children of 'Ammon, and Yahweh gave them into my hand : why then are ye come up unto me this day to fight against me?' 4. Then Jephthah gathered together all the men of Gile'ad, and fought with Ephraim ; and the men of Gile'ad smote Ephraim []. 5. And Gile'ad took the fords of the Jordan against Ephraim ; and whenever the fugitives of Ephraim said, 'Let me pass over,' the men of Gile'ad said to each, 'Art thou

וַאֲשַׁמָּה. On the phrase, as expressive of risking one's life, cf. *note* on *ch.* 5¹⁸, 'that scorned its life, etc.'

4. *and the men of Gile'ad smote Ephraim.* After these words **ו** adds **כִּי אָמְרוּ פְּלִיטֵי אֶפְרַיִם אֲתֵם נִלְעַד בְּתוֹךְ אֶפְרַיִם בְּתוֹךְ מְנַשֶּׁה** 'because they said, "Fugitives of Ephraim are ye Gile'adites, in the midst of Ephraim, in the midst of Manasseh,"' *i.e.* the Ephraimites taunted the Gile'adites with being, in origin, renegade members of their own tribe, without territorial status, and existing on sufferance in the territory of Ephraim and Manasseh. But, according to the earlier narrative, the reason why the Gile'adites smote Ephraim was not on account of any such taunt (however much this may be supposed to have exacerbated the combat), but because the Ephraimites forced battle upon them. It is not clear how the Gile'adites could, in one breath, be called 'fugitives of Ephraim,' and yet be charged with living 'in the midst of Ephraim' ; nor, again, is this latter expression, which seems to suggest that the Ephraimites owned or at any rate claimed territory in Gile'ad east of Jordan, susceptible of any explanation. The term *ḥalūṭim*, 'fugitives,' always elsewhere denotes survivors who have escaped from the battlefield,* and is in fact so used in *v.* 5. It is here that we find the solution of our difficulty. In the Heb. the first four words of the difficult sentence in *v.* 4, **כִּי אָמְרוּ פְּלִיטֵי א** 'because they said, "Fugitives of Ephraim,"' are, with one slight variation (Perfect **אָמְרוּ** for Imperfect), identical with the words of *v.* 5 rendered 'whenever the fugitives of Ephraim said.' It can hardly be doubted that these words from *v.* 5 have come into *v.* 4 through an error of transcription, and then, on the assumption that the subject of the verb **אָמְרוּ** refers back to 'Ephraim' preceding, and that the words 'fugitives of Ephraim' form the commencement of what the Ephraimites said, the sentence has been conjecturally filled out as we find it in **ו**. The words are lacking in the **℣** MSS. HP. 54, 59, 82, 84, 106, 108, 128, 134, and are marked by an asterisk in **℣**^b.

5. *took the fords, etc.* Cf. *ch.* 3²⁸, 7²⁴.

whenever . . . said. The Imperfect **אָמְרוּ** denotes recurrence.

* Heb. *pālat*, 'to escape,' seems properly to mean 'to survive,' and to be identical with Bab. *balātu*, 'to live.'

an Ephraimite?' And if he said, 'No,' 6. they said to him, 'Say now *Shibbóleth*,' and he said '*Sibbóleth*,' and 'was' not able¹ to pronounce aright. Then they laid hold on him and

6. *Say now Shibbóleth.* The word *Shibbóleth*, which may denote either 'stream' (Isa. 27¹², Ps. 69^{3.10}), or 'ear of corn' (Job. 24²⁴, Gen. 41^{5ff.}, *al.*), appears to have been selected at random as an example of a word commencing with the difficult letter שׁ (so Kimchi). We have no means of ascertaining the precise sibilant sound which the narrator represents by שׁ in the Ephraimite pronunciation. It is possible that it was actually שׁ (an emphatic *š*), which is the sibilant which represents the *š* of some Babylonian loan-words in Heb. (cf. שׁפּרָ = *šipru*, שׁרְגָנוּ = *šargānu*, etc.). Or, bearing in mind the fact that the word meaning 'ear of corn,' which is written with שׁ, *š*, in Heb., Aram., and Bab., is pronounced in Ar. with س, *s* (*sunbul*, *sunbula*), we may conjecture that the Ephraimites may have used the Ar. pronunciation; but since the narrator could not, in unpointed Heb., reproduce the difference between שׁ and שׁ, he was obliged to write שׁ in place of the latter in order to make his meaning clear. Kimchi states that the people of Šarēphath were unable to pronounce שׁ, *š*, and reproduced it as aspirated ת, *th* (*i.e.* probably תּ), and he suggests that the Ephraimite pronunciation may have been similar. Cf. the view of Marquart, *ZATW.*, 1888, pp. 151-155.

Of the parallels for the test cited by commentators, the most striking (quoted by Ber., etc.) is the incident of the Sicilian Vespers, Mar. 31, 1282, when the French were ordered to pronounce *ceci e ciceri*, and those who betrayed their nationality by pronouncing *c* as in French (*sesi e siseri*) were immediately cut down.

was not able. Reading לֹא יָדָל with שׁפּוֹסֵט with לֹא יָדָל, lit. 'he could not fix,' must be taken to imply ellipse of some such object as פִּי 'his mouth,' or שְׂפָתָיו 'his lips.' The view taken by BDB. and some commentators that the assumed object is לֵב 'the heart,' *i.e.* 'the mind' (as in the late passages, Job, 11¹³, Ps. 78⁸, 1 Chr. 29¹⁸, *al.*), and that the expression means 'he did not give attention,' is less probable. The error in pronunciation was clearly due to dialectical peculiarity and not to inattention; it being most unlikely that the Ephraimites would fail through carelessness if they realized (as they must have done) that it was a matter of life or death whether they satisfied the test or not. Apart, however, from the inelegancy of יָדָל followed by בָּן, the use of the simple Imperfect is singular in the midst of a series of Imperfects with ו consecutive. Twelve MSS.

slew him at the fords of the Jordan : and at that time there fell of Ephraim forty and two thousand.

7. R^{JE} And Jephthah judged Israel six years. R^p And Jephthah the Gileadite died, and was buried in 'his city', <in Mišpeh of> Gilead.

of **U** in place of יִכִּי read יִכִּי 'he *did not understand* how to speak aright.'

Then they laid hold . . . Jordan. At this point Bu. (followed by La.) proposes to insert the words of v. ¹ אַתֶּם פְּלִיטֵי א' 'for they said, "Ye are fugitives of Ephraim."' Since, however, the context deals with each individual case, we should have expected אַתָּה פְּלִיט א' 'Thou art a fugitive of Ephraim.'

7. *in his city, in Mišpeh of Gilead.* Reading בְּעִירֵי בְּמִצְפֵּה נִלְעָד with Stu., Doorn., Bu., Mo., La., Kent, Cooke. This text has the support of several minuscules of **Gr** which read ἐν τῇ πόλει αὐτοῦ ἐν Σεφε (or Σεφ) Γαλααδ. Here Σεφε seems to point to a Heb. original in which the מ of מִצְפֵּה was obliterated. Jos. (*Ant.* v. vii. 12) seems to have used a similar text, for he writes Αὐτὸς δὲ ἄρξας ἐξ ἑτῆ τελευτᾷ καὶ θάπτεται ἐν τῇ αὐτοῦ πατρίδι Σεβέη τῆς Γαλαδηνῆς δ' ἐστὶν αὐτῇ. **U** 'בְּעִירֵי נ' 'in the cities of Gilead,' is impossible ; it being quite illegitimate to render, with A.V., R.V., 'in *one of* the cities.' **T** follows **U**. **Gr**ⁿ ἐν τῇ πόλει αὐτοῦ ἐν Γαλααδ. **Gr**^{AL}, **S**^h ἐν τῇ πόλει αὐτοῦ Γαλααδ, **L**, **V** 'in civitate sua Galaad.' **S**^p בְּעִירֵי נִלְעָד 'in a city of Gilead.'

HUMAN SACRIFICE AMONG THE ISRAELITES.

(Cf. *ch.* 11³¹ *note.*)

Evidence shows that the practice of human sacrifice (especially the sacrifice of the firstborn) was not unknown among the Israelites ; though in historical times it seems to have been very exceptional. In pre-Mosaic times it was probably more frequent, if not customary. The Book of the Covenant (Ex. 20²²-23³³ E), many of the regulations of which probably grew up in Canaan at a period immensely earlier than the age of Moses,* seems expressly to contemplate that the normal fate of a firstborn son is that he should be sacrificed to

* The standpoint here assumed is that the Book of the Covenant represents very largely the consuetudinary legislation of Canaan from a period long prior to the entry and settlement under Joshua of those Israelite tribes (chiefly, if not solely, the Joseph tribes) who had come under the leadership and influence of Moses, and had thereby gained a higher and purer conception of Yahweh and the requirements of his religion. This view seems to explain the close connexion in many points of this early legislation with the Code of Hammurabi, which must

Yahweh. The enactment of 22^{20b} says, without qualification, 'The firstborn of thy sons shalt thou give to me'; and this is immediately followed by the enactment with regard to the firstborn of animals, which is couched in precisely similar terms: 'So shalt thou do to thine ox and to thy sheep: seven days it shall be with its mother; on the eighth day thou shalt give it to me' (27. 30). We know of course how the former enactment was interpreted elsewhere, and that in early legislation. The law of J in Ex. 34²⁰ lays down that 'Every first-born of thy sons thou shalt redeem'; and this is repeated in Ex. 13^{13b} P. Thus it appears probable that an animal-substitute may usually have been provided at an early period in Israel's history. The story of Abraham's projected sacrifice of Isaac in Gen 22 E was probably intended to show that the Father of the Faithful had been ready to make the most costly sacrifice, and God had graciously vouchsafed to be pleased with an animal in its place. Such a tradition (if we are justified in regarding it as ancient) was doubtless not without its influence in determining the interpretation of the old regulation. Mic. 6¹⁻⁸, if really the work of the eighth-century prophet, indicates that in the mind of the average Israelite of Micah's day there still lurked the idea that Yahweh might conceivably be propitiated by the sacrifice of a firstborn son as the most costly form of offering; but whether this idea was often, or ever, carried into practice at this period we cannot say. It is quite possible, as many scholars have thought, that the passage may be due to a prophetic teacher

(if not *in toto*, at least as regards a large part of its enactments) have been operative in Syria as well as in Babylonia *cir.* B.C. 2000 (on Hammurabi as king of the West as well as of Babylonia, cf. *Introd.* pp. lxi ff.). It explains also the extremely primitive character of many of the enactments of the Book of the Covenant; e.g. 21⁶, 22^{8,9} (¶ 7.8), where *hā-'ēlōhīm* can scarcely, except on the most forced exegesis, be explained otherwise than as 'the (household) gods'—probably identical with Teraphim. In 21⁶ the scene of the ceremony is clearly the master's own house (*not* the local sanctuary), just as it is in Deut. 15^{16f.}; the only difference being that in the later enactment the reference to *hā-'ēlōhīm* is dropped, doubtless as offensive to the purer form of Yahwism. In 22⁸ *hā-'ēlōhīm* are agents or means of *divination*, just as the Teraphim appears to have been (cf. *note* on ch. 17⁵). If this view of the origin of the legislation of the Book of the Covenant is correct, we can understand how a code which was probably from primitive times the property both of the Canaanites and of such Israelite elements as had not come under the influence of Mosaic Yahwism, may have contained an enactment enjoining the offering of the firstborn, which later on came, under the refining influence of Mosaic Yahwism, to be interpreted as satisfied by the redemption of the firstborn of man by the sacrifice of an animal.

On the view that the history of Israel's religion in early times is the history of a conflict between the high ethical Yahwism which was the outcome of the teaching of Moses, and a much cruder and more naturalistic form of Yahwism practised by Israelite tribes which had never been in Egypt nor come under the influence of the great teacher, cf. an article by the present editor entitled *A Theory of the Development of Israelite Religion in Early Times*, *JTS.*, Apr. 1908, pp. 321-352.

during the idolatrous reaction under Manasseh in the seventh century B.C., when it became the custom to sacrifice children as holocausts to the god Molech (cf. 2 Kgs. 21⁶, Jer. 3²⁴, 7³¹, 19⁴⁻⁶, 32³⁵, Ezek. 16^{20,21}, 23³⁷⁻³⁹). *

The same abuse is stated by the Deuteronomic redactor of Kgs. to have been practised in the reign of Ahaz (2 Kgs. 16³), and during the closing days of the Northern Kingdom (2 Kgs. 17¹⁷); but no allusion to such child-sacrifices is made by Isaiah in his prophecies which seem to belong to Ahaz's reign, nor by Amos and Hosea in their indictment of the sins of the Northern Kingdom; and it seems probable, therefore, that R^D in Kgs. may be erroneously attributing the corrupt practice of Manasseh's age to an earlier period. Ps. 106^{37 f.} is not evidence that the custom was general throughout pre-monarchic times; but we may probably infer from Isa. 57^{5 f.} that the seventh-century practice survived into post-exilic times among the degraded remnant of the Judean population which was left in Palestine during the exile. 2 Kgs. 17³¹ states that it was in vogue among a section of the foreign settlers who were introduced into the Northern Kingdom after the fall of Samaria.

The practice of the rite of child-sacrifice among the Canaanites is alluded to in Deut. 12³¹, 18^{9,10}, and forbidden to Israel (cf. Lev. 18²¹, 20² H). Excavation has brought to light numerous examples of the burial of infants of about a week old in jars in the vicinity of a sanctuary.† These are probably evidence for the practice of the sacrifice of the firstborn among the Canaanites; though it is only rarely that the remains of the infants appear to have been subjected to the action of fire. Another form of human sacrifice which has been attested by excavation is the foundation-sacrifice, in which the victim (infant or adult) has been buried (probably alive) in the foundations of a building. An instance of this form of sacrifice among the Israelites is perhaps to be found in 1 Kgs. 16³⁴; but, if this be so, the mere fact that the event is placed on record seems to indicate that it was very unusual.

* The phrase which is often used in allusion to this form of sacrifice—**העביר באש**, rendered by A.V., R.V., 'cause to pass through the fire' (sometimes **העביר** simply)—has been otherwise explained as though it referred to some rite of initiation. But the meaning of the expression is more probably 'make over' ('cause to pass over') to the deity 'by fire' (cf. the use of the verb in Ex. 13¹²); and the fact that this really denotes a sacrifice in which the victim was first slain and then burnt has been strongly maintained by Mo. (EB, 3184) by comparison of passages in which the phrase occurs with parallel passages in which the reference to the slaughter of children is unambiguous. Cf. especially Jer. 32³⁵ with 19^{5,6}; Ezek. 23³⁷⁻³⁹ with 16^{20 f.}

† Cf. Vincent, *Canaan*, pp. 188 ff.; Driver, *Schweich Lectures*, pp. 67 ff.; Stanley A. Cook, *Religion of Ancient Palestine*, pp. 38 ff.; Handcock, *Archæology of the Holy Land*, pp. 368 ff. On the foundation sacrifice generally, cf. Trumbull, *The Threshold Covenant*, pp. 45 ff. A different theory as to the buried infants has been offered by Frazer, *Adonis, Attis, Osiris*, pp. 82 f.

THE WOMEN'S FESTIVAL OF JUDGES, II. 40.

Whatever be the historical value of the story of the sacrifice of Jephthah's daughter, it is probable that the festival which existed in the narrator's time, and which he explained as commemorative of this traditional event, really had its origin in a cultus which was based upon mythology and not upon history. There is evidence for the practice of a similar ceremonial in Syria in later times. The worship of *Kóρη*, i.e. the heavenly virgin, by the inhabitants of Shechem is attested by Epiphanius (*Adv. haeres.* iii. 2, 1055), who supposed that the ceremonial sacrifice was connected with the commemoration of Jephthah's daughter. Porphyry (*De Abstinencia*, ii. 56) states that at Laodicea on the Syrian coast a virgin was in ancient times offered to Athena, and that the ceremonial still survived, a stag being substituted for the human sacrifice. Pausanias (III. xvi. 8) identifies the goddess who was thus honoured with Artemis, whose image, he tells us, had formerly stood at Brauron, but had been presented to the Laodiceans by Seleucus. Robertson Smith (*Religion of the Semites*,² p. 466) argues that the town of Laodicea was of much greater antiquity than its re-christening by Seleucus; and that, if the goddess in question had really been Greek, she would not have been identified with Athena as well as with Artemis. His conclusion is that she must originally have been a form of the native Syrian goddess 'Ashtart (cf. also Frazer's note in his edition of Pausanias, vol. iii. pp. 340f.). The connexion of this sacrifice with the Iphigenia-legend (as recognized by Pausanias) is clear; especially with that form of the legend in which a hind was substituted by Artemis as a sacrifice, in place of the maiden. It is much more likely that the Greek legend had its source in Western Asia (like many other elements of Greek mythology), than, conversely, that the legend, and the rites in which it was celebrated, penetrated from Greece into the Syrian littoral.

The resemblance between the stories of Iphigenia and Jephthah's daughter has often been remarked: cf., e.g., the series of parallels drawn by Capellus, *De voto Jephthae*, § xii. (*Annotata ad Libros Historicos V.T.*, Tom. ii. 1660, p. 2082). If this resemblance is more than accidental, it goes far to anticipate the objection which might be brought against the validity of the evidence which has already been adduced for the existence in Syria of rites analogous to the women's festival of Judg. II⁴⁰, viz. that the former is very late in comparison with the latter; since it is clear, from the early date at which the legend of Iphigenia appears in Greek mythology, that, if at all dependent upon Semitic cultus, it must testify to a cultus of very considerable antiquity.

As to the original significance of this cultus we are altogether without definite evidence, and can only make conjecture. Mo. (p. 305) thinks that 'the annual lamentation of the women of Gilead for Jephthah's daughter belongs to a class of ceremonies, the original

significance of which, often disguised by the myth, is mourning for the death of a god.' Jeremias (*OTLAE*. ii. pp. 168f.) would bring the sacrifice into connexion with the Tammuz-Ištar cult.

This latter cult appears to have been inherited by the Babylonians from their Sumerian predecessors, and is consequently of very high antiquity. It was borrowed from the Babylonians by the Phoenicians, among whom Tammuz was venerated under the title *Adon* 'lord'; and from the Phoenicians the Tammuz-Ištar myth spread westwards into Greece, in the well-known form of the story of Adonis and Aphrodite. We may gather from the O.T. some few traces of the cult in Israel, where, as elsewhere, it seems pre-eminently to have been practised among women.* Its central observance was ceremonial mourning for the *death of the god*, who typified the youthful sun of springtime, or, according to a variant conception, the luxuriant vegetation produced by this sun, which is cut off and destroyed by the fierce heat of the sun of midsummer. This mourning took place in the fourth month, which falls at or about the summer-solstice (cf. *OTLAE*. i. pp. 96 ff.), and which bears the name of Tammuz in the Babylonian (as in the later Jewish) calendar.†

The cult of Ištar, as the earth-goddess of fertility, stands in intimate connexion with that of Tammuz. She appears variously as his virgin-mother, sister, wife, and lover. Sometimes, indeed, Tammuz seems to have been regarded as feminine, and bore titles which properly belong to the goddess.§ The conception seems to vary according as

* Ezek. 8¹⁴ speaks of the women at Jerusalem weeping for Tammuz. In Isa. 17¹⁰ the phrase נְטָעֵי נַעֲמָנִים, which R.V. *text* translates 'pleasant plants,' is more probably to be rendered, as in the *marg.*, 'plantings of Adonis': cf. the Greek Ἀδωνίδος κῆποι, *i.e.* pots or baskets containing quick-growing, and quickly-fading, plants, which were dedicated to Aphrodite as emblems of her lover's beauty and early death (cf. Plato, *Phædrus*, 276 B; Theocritus, 15, 113). Some would find a similar reference in the allusion to 'gardens' in Isa. 1^{29,30}. In Dan. 11³⁷ the phrase חֲמַדַּת נָשִׁים 'the desire (desired one) of women,' which the context shows to be the title of a deity, probably refers to Tammuz (cf. the commentaries of Bevan and Driver *ad loc.*). The reference in Zech. 12¹¹ to 'the mourning of Hadad-Rimmon in the valley of Megiddo' is obscure, and the grounds for associating it with the Tammuz-wailing are highly precarious; while the supposition that an allusion to the ceremonial is to be found in 'the mourning for an only son' Am. 8¹⁰, and that the formulæ of lamentation for the dead mentioned in Jer. 22¹⁸, 34⁵ are derived from the cult, is most improbable. Cf. Baudissin, *Adonis und Esmun*, pp. 87-93.

‡ Succinct accounts of the Tammuz-myth and ritual in Babylonia are given by Sayce, *DB*. iv. pp. 676 f.; Cheyne, *EB*. 4893 f.; Zimmern, *KAT*.³ pp. 397 f.; Jastrow, *REBA*. pp. 343-350, 370 f. For greater detail, cf. Zimmern, *Der babylonische Gott Tamūz* (*Abhandl. der phil.-hist. Klasse der K. Sächs. Gesellsch. der Wissensch.* xxvii, 1909, pp. 701-738); Langdon, *Tammuz and Ishtar*, 1914. For the Phoenician form of the cult, cf. Baudissin, *Adonis und Esmun*, 1911. For the cult in its wider developments, cf. Frazer, *Adonis, Attis, Osiris*³, 1911 (many very questionable assumptions).

§ Cf. Zimmern, *Tamūzlieder*, pp. 211, 213; *Der Bab. Gott Tamūz*, pp. 7 ff.; Hommel, *Grundriss*, pp. 387 f., 395; Jastrow, *op. cit.* pp. 347 f.; Langdon, *op. cit.* pp. 16 ff.

8. ^{R^p} And after him Ibšan of Bethleḥem judged Israel.
 9. And he had thirty sons, and thirty daughters he sent abroad,
 and thirty daughters he brought in for his sons from abroad:
 and he judged Israel seven years. 10. And Ibšan died, and
 was buried in Bethleḥem.

11. And after him Elon the Zebulonite judged Israel; and
 he judged Israel ten years. 12. And Elon the Zebulonite died,
 and was buried in Aijalon in the land of Zebulun.

Ištar is regarded as the spontaneously-productive virgin (or sexless) Mother-Earth, or fertility is conceived as the result of union between Spring-Sun and Earth. When the former conception held force, Tammuz, as the emanation of Mother-Earth, might naturally be regarded as virgin and feminine like herself.

The Greek myth of the abduction of Kore-Persephone (a vegetation-goddess) to the Underworld, and her return to the earth in the spring, is ultimately of Babylonian origin. The relation between Demeter (originally the Earth-goddess) and Kore (the spring-vegetation) represents one form of the Tammuz-Ištar myth, just as the relation between Aphrodite and Adonis represents another form. It is probable that the yearly sinking of Kore (or the feminine Tammuz) to the Underworld may at one time have been marked (at least in Syria) by a virgin-sacrifice, for which in later times another offering (*e.g.* a hind) was substituted. We recall the fact already noticed that the sacrifice of the Shechemites mentioned by Epiphanius, and connected by him with the sacrifice of Jephthah's daughter, was made to Kore. The emphasis on virginity belongs to the basic conception of the Earth-mother herself as virgin or sexless. Cf. further, *Addenda*, pp. xvii ff.

Among the many virgin-sacrifices of early Greek mythology we may compare that of Polyxena, who, as her name implies—'she of the many guests'—is in origin a queen of the Underworld, the wife of Polydektor or Polydegmon (*i.e.* Hades, so-called as πολλοὺς δεχόμενος): cf. Murray, *The Rise of the Greek Epic*, pp. 121 f.

12. 8-15. *The 'Minor' Judges, Ibšan, Elon, and 'Abdon.*

On the 'minor' Judges generally, cf. pp. 289 f.

8. *Bethleḥem.* Jos. (v. vii. 13) takes this city to be Bethleḥem of Judah; and the same view is assumed by Rashi, Kimchi, and Levi ben-Gershon, who preserve a tradition that Ibšan was the same as Boaz the ancestor of David. There is, however, a northern Bethleḥem mentioned in Josh. 19¹⁵ P which is probably the modern Bêt Lahm, seven miles west-north-west of Nazareth, and it is not unlikely that this may be the city intended. Cf. p. 290.

12. *was buried in Aijalon.* Possibly the distinction drawn by 𐤀𐤋 between the name of the judge and that of his city is merely artificial.

13. And after him 'Abdon the son of Hillel the Pir'athonite judged Israel. 14. And he had forty sons and thirty grandsons, who rode upon seventy ass-colts: and he judged Israel eight years. 15. And 'Abdon the son of Hillel the Pir'athonite died, and was buried in Pir'athon in the land of Ephraim, in the hill-country of the 'Amalekites.

Ⲭ¹ reproduces both names as Αἰλωμ, *i.e.* 𐤀𐤋𐤍. So Nöldeke (*Untersuchungen zur Kritik des A. T.*, p. 184), Mo., La., Cooke.

13. *the Pir'athonite.* Pir'athon corresponds philologically to the modern Far'atâ, six miles west-south-west of Shechem. The Φαραθων fortified by Bacchides (1 Macc. 9⁵⁰) appears to have lain further south.

15. *in the land of Ephraim.* Some Ⲭ MSS. here read ἐν ὄρει Εφραιμ ἐν γῇ Σελλημ. This is adopted by Mo. (SBOT.) who supposes that ἐν γῇ Σελλημ = 𐤌𐤔𐤏𐤕𐤍 𐤓𐤕𐤍𐤔, *i.e.* the land of Sha'alim mentioned in 1 Sam. 9⁴. In support of this view he adduces the southern position of Pir'athon, as inferred from 1 Macc. 9⁵⁰, and the fact that the name 'Abdon occurs in the genealogical lists in Benjamin, 1 Chr. 8²³, 8³⁰ = 9³⁶. That Σελλημ = 𐤌𐤔𐤏𐤕𐤍 (in 1 Sam. 9⁴, Ⲭ^A Σααλειμ, Ⲭ^L Σεγαλειμ) is, however, a bold assumption; and, since 'Abdon is not an uncommon name, there is no reason for supposing that the Benjaminite 'Abdon of 1 Chr. must be identical with the 'Abdon of the present passage.

in the hill-country of the 'Amalekites. Cf. p. 132.

13. 1-16. 31. Samson.

Besides the Commentaries, etc., cited throughout the book, cf. B. Stade, *Ri. 14, ZATW.* iv. (1884), pp. 250-256; W. Böhme, *Die älteste Darstellung in Richt. 6¹¹⁻²⁴ und 13²⁻²⁴ und ihre Verwandtschaft mit der Jakveurkunde des Pentateuch*, ZATW. v. (1885), pp. 251-274; A. van Doorninck, *De Simsonsagen. Kritische Studien over Richteren 14-16*, *Theol. Tijdschrift*, xxviii. (1894), pp. 14-32.

On the solar-mythological interpretation of the story, cf. (selected bibliography) E. Meier, *Geschichte der poetischen National-Literatur der Hebräer*, 1856, pp. 97-108; G. Roskoff, *Die Simsonsage nach ihrer Entstehung, Form und Bedeutung, und der Heraclesmythus*, 1860; H. Steinthal, *The Legend of Samson* (trans. of an article in *Zeitschrift für Völkerpsychologie*, 1862), in Appendix to J. Goldziher, *Mythology among the Hebrews*, 1877; F. Baethgen, *Beiträge zur semit. Religionsgesch.*, 1888, pp. 161-173; H. Stahn, *Die Simsonsage*, 1908; A. Smythe Palmer, *The Samson-saga, and its place in comparative Religion*, 1913.*

This narrative introduces us to the period of the Philistine oppression, for the history of which the way has been prepared by the account of Israel's apostasy in 10⁶⁻¹⁶; cf. the reference to the

* Meier and Roskoff are selected as good representatives of the earlier writers on the subject, who were mainly concerned with drawing out the parallels between the deeds of Samson and those of Herakles. Steinthal goes much

Philistines in *v.7*.^{*} It was this oppression which led ultimately to the institution of the kingship in Israel; and, so far as we can gather from the oldest sources, the strong hand of the Philistines was not relaxed to any appreciable extent until some amount of consolidation had been achieved among the Israelites through the establishment of the monarchy. The narrative thus occupies its right chronological position in the Book of Judges, *chs.* 17-21 being of the nature of an appendix (cf. *Introd.* p. xxxvii).

The Samson-narrative, though consisting of a number of semi-independent stories, shows no sign of compilation from parallel and divergent sources; and the generally accepted view is that it has been extracted in its entirety from one of the two main ancient sources of Judg.[‡] That this source was J can hardly be doubted. Böhme has proved conclusively that *ch.* 13 must be derived from J. He notes the striking resemblances which it exhibits to the Gide'on-narrative 6¹¹⁻²⁴ J—the appearance of the Angel of Yahweh as the bearer of specific injunctions; the offering of a kid upon a rock-altar; the miraculous disappearance of the supernatural visitor, whilst the heavenly fire consumes the offering; the terror of the human actors on realization that they have seen a divine being, and their subsequent reassurance that Yahweh is well-disposed towards them. Especially striking is the verbal identity between *vv.* 5,7 and Gen. 16¹¹ J in the phrase הִנֵּה הָרָה וְיֹלְדָת בֵּן ‘Behold, thou art with child, and shalt bear a son,’ and *v.* 18^a and Gen. 32³⁰ J לָמָּה זֶה תִּשְׁאַל לִשְׁמִי ‘Wherefore, now, askest thou concerning my name?’ Other resemblances cited by Böhme are, *v.* 6 לֵי וְאֵת שְׁמוֹ לֹא הִגִּיד לִי ‘and his name he told me not,’ and Gen. 32³⁰ J הִנִּידָה נָא שְׁמֶךָ ‘tell me, prithee, thy name’; *v.* 10 וְהָרָץ וְהָגִיד ‘and she ran and told,’ and Gen. 24²⁸, 29¹² J, where the same two verbs are similarly coupled; the association of מָהַר ‘hasten’ and רוּץ ‘run’ in *v.* 10, as in Gen. 18^{6,7}, 24²⁰ J; *v.* 11 וַיֹּאמֶר אֲנִי

further than his predecessors in elaborating the solar-mythological theory; and, while laying himself open to grave criticism in many points of detail, he marks a distinct stage in the serious treatment of the subject. A valuable criticism of Steinthal is offered by Baethgen. Stahn is useful as giving a very full bibliography of earlier monographs, with brief summaries of the views of different scholars. Smythe Palmer deals with the subject in a far more detailed and systematic way than has been attempted by earlier scholars, bringing together a large and varied mass of material in support of his thesis. The value of the book would have been greatly enhanced if this material had been more critically sifted. The book is weakest in its Semitic philology, suggestions of a transparently fallacious character being too often accepted and built upon.

* On 10⁶⁻¹⁶, as originally intended by the E narrator to introduce, not the judgship of Samson, but that of Samuel, cf. p. 294.

‡ An attempt to prove compilation from the two main ancient sources of Judg. has been made by E. von Ortenberg, *Beil. z. Jahrestber. d. Gymn. zu Verden*, 1887; but has not met with acceptance among scholars. The present editor has not been able to obtain access to this publication.

'and he said, "I"' (*i.e.* 'I am he'), as in Gen. 27²⁴ J (elsewhere only 1 Kgs. 13¹⁴; cf. וַיֹּאמֶר אֲנִי 2 Sam. 2²⁰). In addition to these, we may note as characteristic J phrases, מַלְאֲךְ יְהוָה 'the Angel of Yahweh,' *vv.* 3.13.15.16.17.18.20.21 (on מַלְאֲךְ הָאֱלֹהִים *vv.* 6.9 cf. *notes*), הִנֵּה נָא 'Behold, now,' *v.* 3; עֲתָר 'intreat,' *v.* 8; בִּי אֲדֹנִי 'Oh, my lord' *v.* 8; לָמָּה זֶה 'Wherefore' *v.* 18; cf. *CH.* 4, 9, 48, 56*b*, 89*b*. Finally, the prolonged barrenness of the hero's mother is a trait which characterizes the J narrative; cf. Gen. 11³⁰ (Sarai), Gen. 25²¹ (Rebekah), Gen. 29³¹ (Rachel), which are the only occurrences of the adjective עֲקָרָה 'barren' in *narrative* outside Judg. 13^{2.3}.

While, however, *ch.* 13 thus abounds with indications that it is derived from J, the literary characteristics of J are absent from *chs.* 14-16. These latter chapters are entirely *sui generis*, full of the rough vigour and broad humour of the rustic story-teller, but lacking the literary grace and finish which distinguish the finer parts of J and E. It is obvious, moreover, that the religious motive which colours the narrative of *ch.* 13 is altogether absent from *chs.* 14-16. The birth-narrative prepares us for a Gideon or a Samuel, keenly alive to the fact that he holds a divine commission, and upheld in his performance of it by consciousness of the divine support. Samson, however, proves to have no commission at all, and recognizes no higher guide than his own wayward passions. Again, the fact can hardly be denied that the story-cycle of *chs.* 14-16 contains a mythological element which must be very primitive, and which is, in origin, far removed from the Yahweh-religion of J (cf. *Addit. note*, p. 391).

Yet that *ch.* 13 was written to introduce the narrative of *chs.* 14-16 cannot be questioned. Had it originally prefaced a Samson-narrative more in accordance with its own tone, we cannot imagine why this should have been rejected by a later editor in favour of the present narrative. Moreover, *chs.* 14-16 are not entirely without points of connexion with *ch.* 13. We notice 14¹⁴, the allusion to Yahweh's divine purpose working unseen through Samson's wayward inclination; and 16^{17a} 'No razor hath come up upon my head, for a Nazirite of God have I been from my mother's womb'—a statement which presupposes the injunction of 13^{5.7}. These are passages which lie upon the surface of the narrative, and are easily detachable from it without in any way affecting its sequence. The inference which may be drawn is that the J narrator made use of an ancient cycle of folk-tales which were current in his day, incorporating them into his work practically unaltered from their popular form, except for one or two touches such as we find in the passages above noticed.

This is the view of van Doorninck, who, however, is inclined to assign to the later narrator not merely the passages above mentioned, but also Samson's last prayer to Yahweh 16²⁸, and the three allusions to his feats of strength as inspired by the sudden inrush of the spirit of Yahweh in 14^{6.19}, 15¹⁴; whereas on other

occasions (*e.g.* 15⁸, 16⁹, *al.*) he appears to act without any such initiative. So drastic an elimination from the ancient folk-tales of all allusions to Yahweh's influence on the hero (a proceeding which, to be complete, should include 15^{18,19} in its present form) can hardly be accepted. However much the stories may, in their origin, have been coloured by the solar-mythological motive, it cannot be doubted that this motive had long been forgotten by the time that the tales were utilized by the J writer for his narrative: and, if this was so, and Samson's feats had come to be related as the actual deeds of an actual member of the tribe of Dan, it is natural that they should have come to be explained, like other events of a phenomenal character, as due to the active co-operation of the Spirit of Yahweh.* Such a presentation marks a stage midway between the purely pagan (non-Yahwistic) conception of the hero, and his adoption by the author of *ch.* 13 as the commissioned agent of Yahweh, of which the most salient feature is the interpretation of his long locks (originally in all probability a solar trait; cf. *Addit. note*, p. 404) as the distinctive badge of dedication to Yahweh, from his birth and even earlier, as a *Nazirite*—a conception which it is difficult to regard as originally inherent in the stories of *chs.* 14-16 (cf. *note* on 13⁵).

This view of the growth of the Samson-narrative is indicated in the text by the marking of the old story-cycle as J¹, and the later construction put upon it by the main J narrator (as embodied in *ch.* 13 and in the touches in *chs.* 14-16 above noticed) as J². The next stage was the full acceptance of Samson as a member of the series of divinely commissioned *Judges* by R^{JE}, whose hand is seen in 13^{5b}, and in this editor's ordinary formula of conclusion in 16^{31b}. The principal editor of our Book of Judges, R^{E2} (whose regular formula of introduction is seen in 13¹), appears to have laboured under a sense of the moral unsuitability of the hero for inclusion in such a category; and thus to have made extensive excisions from the narrative, including among them the account of Samson's death as a slave of the uncircumcised. Probably he would have been by no means averse from excluding him altogether, but found his figure too firmly enshrined in the popular imagination to allow of the practicability of so drastic a proceeding. R^{E2}'s revised account ended with *ch.* 15, as we may see by the occurrence of the concluding formula as to the length of the judgeship in 15²⁰, which is the formula of R^{JE}, adopted by R^E from 16^{31b} when 16^{1-31a} was cancelled.† At a later time the excised

* As a matter of fact, 14^{19a} is probably to be regarded as a later addition to the narrative (cf. *note ad loc.*), but not on the ground that it pictures Samson as animated by the Spirit of Yahweh; the particular phrase in which this is described being probably copied from 14⁶, where it seems to be an integral part of the narrative.

† The considerations which may have influenced R^{E2} in his inclusions and omissions from the story-cycle have been well indicated by Bu.:—'Down to the close of *ch.* 15, Samson is the husband of *one* wife, and love to her, along with

stories were once more inserted, as we have them in *ch.* 16, doubtless by the hand which restored the story of Abimelech and the Appendix, *chs.* 17-21 (*R^p*; cf. *note* on *ch.* 8²⁹⁻³²).

The Samson-narratives (*i.e.* the ancient story-cycle, *chs.* 14-16) stand alone in the O.T. as illustrations of a type of story emanating, not from the literary circle of the prophets, but from the popular traditions of the country-folk. As Bu. points out (*DB.* iv. p. 380 *a*), 'the ideal of the country-hero was exactly the same in Israel then as it is at the present day. The lion of a village must be first in success with the female sex, first in bodily strength, courage, and fondness for brawling, and first in mother-wit.' As has been argued elsewhere (cf. *Addit. note*, p. 391), the stories seem to exhibit strongly-marked traces of an ancient solar myth, the original significance of which had doubtless been forgotten when it was drawn upon to enrich the halo of the marvellous with which popular imagination loved to surround the deeds of the tribal hero. When, however, allowance has been made for this element in the narratives, there can be no doubt that they possess unique value as illustrating the village-life of the time, and the relations between Israelites and Philistines living in the border-country. The two villages Šor'ah and Eshta'ol, on the edge of the Shephelah, appear as the homes of a small cluster of Danite clans. The Danites must have been few in number; and it is very probable that the migration of the main part of the tribe to seek a new home in the extreme north (as related in *ch.* 18^{26ff.}, Josh. 19⁴⁷ J) may already have taken place. In any case, the Danites of the south were at this time confined within a very small district; and, together with the neighbouring clans of Judah, were in subjection to the Philistines, and stood in wholesome dread of sharing the responsibility of any action which might excite the animosity of their masters (cf. 15¹¹).

The question must remain open whether any historical reality is to be attached to the figure of Samson. It can hardly be denied that, given the existence of a cycle of stories relating to a mythical solar hero who had come to be popularly regarded as an historical individual, we have sufficient substratum to account for the whole Samson-tradition; such elements in the story as are originally unconnected with the solar myth belonging quite conceivably to the local colouring which was the work of popular story-tellers. There is, however, an abundance of analogy for the accretion of mythologi-

love to his native land is the motive of all his actions. But in *ch.* 16 he appears as the slave of sensual passion, caught in the toils of a succession of paramours, to the last of whom he even betrays the secret of the divine strength that animated him. If this itself must have appeared to the mind of *RD* [our *RE²*] quite unworthy of a God-called judge (cf. 2^{16,18f.}), his fate also was an unfitting one, namely that he should end his life as prisoner and slave of the unbelievers' (*DB.* iv. p. 378 *δ*).

cal tales round historical persons ; and the fact that is so should warn us against pronouncing a categorical opinion that the figure of Samson is wholly unhistorical.

Such a question is, however, of very slight importance. If we could grant the historical character of the whole Samson-narrative, Samson would still not be the initiator or furtherer of any movement, religious or political, in the history of Israel which would invest his figure with the slightest historical significance. The real value of the narrative lies in its local setting, which bears intrinsic evidence of being very true to life, and in its preservation of a mythical tradition, akin to that of other Semitic races, of the existence of which in Israel we should otherwise be ignorant.

13. 1. ^{R^E1} And the children of Israel again did that which was evil in the sight of Yahweh ; and Yahweh gave them into the hand of the Philistines forty years. **2.** ^{J²} And there was a certain man of Şor'ah, of the clan of the Danites, and his name

13. 1. the Philistines. On the origin of the Philistines, and their settlement in Cana'an, cf. *Introd.* pp. xcii ff.

2. a certain man. Heb. 'one man'—an indefinite use of אִישׁ 'one' which is usually somewhat characteristic of the North Palestinian dialect ; so in E in *ch.* 9⁵³ אִשָּׁה אַחַת 'a certain woman.' For the classified instances of אִישׁ in this sense, cf. *NHTK.* p. 209. This small point cannot, however, weigh against the evidence already adduced (p. 336) in proof that our narrative belongs to J. The whole phrasing of *v.*²¹ closely resembles that of *v.*¹ of 1 Sam. 1—a chapter which, if reliance is to be placed upon striking parallels in diction (cf. 1 Sam. 1^{11b} with *v.*^{5a,2}, 1 Sam. 1^{15a} with *v.*^{4a,3}, 1 Sam. 1^{20a,3,ba}, 3^{19a,1,3} with *v.*²⁴), should belong to J rather than (as commonly supposed) to E. The details added to the narrative by Jos. (*Ant.* v. viii. 2 f.) are apparently derived from his own imagination.

Şor'ah. The modern Şar'ah, fourteen miles due west of Jerusalem in the Shephelah, upon an elevation on the northern side of the wâdy eş-Şarâr (the wâdy of Sorek ; cf. 16⁴), up which the railway from Jaffa to Jerusalem now travels. Beth-shemesh, *i.e.* 'Temple of the Sun,' the modern 'Ain-šems, stands on a corresponding eminence on the opposite side of the wâdy, and its proximity may help to account for the solar-mythological traits which the story of Samson seems to exhibit (cf. *Addit. note*, p. 391). From the manner in which Şor'ah is named with the neighbouring village Eshta'ol in *v.*²⁶, *ch.* 16³¹, 18^{2,8,11} as the home of the Danites, it would appear that they were at this time nearly, if not wholly, confined to these two villages. The latter village, if rightly identified with the modern 'Ešûa' (cf. *v.*²⁵ *note*), is less than two miles off further up the wâdy to the north-east. The Danites must thus have been very few in number ; and it is to be

was Manoah; and his wife was barren and had not borne.
3. And the Angel of Yahweh appeared unto the woman, and said unto her, 'Behold, now, thou art barren and hast not borne; ^{Gl.} but thou shalt conceive, and bear a son. 4. J² Now,

noted that they are described, both in this narrative, and in *ch.* 18 ^{2.11.19}, as a *clan* (*mišpāhā*; *šebhet*, 'tribe,' occurs, however, in 18 ^{1.19.30}). Their limitation to this small district on the edge of the hill-country is explained in *ch.* 1 ³⁴; cf. further *note ad loc.*

Manoah. The manner in which the Manahtites of Šor'ah (הַמָּנַחֲתִי הַצֹּרְעִי lit. 'the Šor'ite Manahtites') are mentioned in 1 Chr. 2 ³⁴ has suggested to many commentators that Manoah may have been the eponymous ancestor of the clan-division of the Danites inhabiting Šor'ah. It seems, however, to be likely that the connexion in form between Manoah and Manahtites is merely accidental; the Manahtites being a Calibbite clan, a portion of which inhabited the district of Šor'ah in *post-exilic* times.* The Calibbites formed an element of the mixed tribe of Judah (cf. *note* on *ch.* 1 ¹²); and we are informed in Neh. 11 ²⁹ that Šor'ah was one of the cities occupied by the children of Judah after the Exile.

3. *the Angel of Yahweh.* Cf. *ch.* 2 ¹ *note.*

but thou shalt conceive, etc. The words have the appearance of an

* The composite genealogy of the Calibbites in 1 Chr. 2 ⁴²⁻⁵⁵ is very problematical; but it seems likely, as Benzinger and Curtis assume (commentaries *ad loc.*; cf. also *EB.* 530) that *vs.* 50-55 have to do with the *post-exilic* Calibbites, who, owing to the occupation of their former territory by the Edomites, were obliged after the Exile to settle further north. Thus we find part of the Manahtites at Šor'ah (*v.* 54), and another part in the neighbourhood of Kiriath-jearim (*v.* 52; read הַמָּנַחֲתִי for הַמָּנַחֲתִי). These two divisions are traced respectively to Salma and Shobal, who are said to have been 'sons,' i.e. *clans* of Caleb. These Manahtites can hardly be unconnected with Manahath, son of Shobal, who is mentioned in Gen. 36 ²³ P (cf. 1 Chr. 1 ⁴⁰) in the Horite division of the Edomites. Though Manoah is only mentioned by name in Judg. 13 and 16 ^{31a}, and not in the old story-cycle of *chs.* 14-16, the connexion of his name with Samson and Šor'ah must be of respectable antiquity (J²); and if he is really only the eponymous ancestor of the Manahtites, we must assume that, after the migration of the Danites to the north, the last remnant of the tribe soon disappeared from Šor'ah, and that the district was occupied by Manahtites at so relatively early a period that the J narrator, in writing his introduction to the Samson-stories, erroneously supposed that this Calibbite clan was Danite in origin. This is most improbable. The only remaining possibility seems to be the assumption that the tribe of Dan owed its origin, wholly or in part, to a Calibbite or related Edomite strain; but, had this been so, should we not expect Dan to be connected by tradition with Le'ah (like Judah) or at least with her handmaid Zilpah, rather than with Bilhah—a relationship which seems to imply early connexion with the Jošeph-tribes rather than with Judah?

The name Manoah is identical in form with the wādy el-Munāh which runs into the wādy Šarār from the direction of Tibneh (Timnah); but this is perhaps a mere coincidence.

therefore, prithee, take heed, and drink neither wine nor strong drink, and eat nothing unclean: 5. for, behold, thou art with child, and shalt bear a son, and a razor shall not come up upon his head; for the lad shall be a Nazirite of God from the womb:

awkward anticipation of the announcement of *v.*⁵. They are probably a gloss (so Bu., Böhme, etc.); and it seems likely that they were absent from the archetype of *Gr*^B. *Gr*^B now represents them by *καὶ συλλήμψῃ υἷόν, i.e. בְּוִרְיָת בֶּן*—probably an addition from another translation; contrast the rendering of הַנֶּזֶר הַזֶּה *ἡδὸν σὺ ἐν γαστρὶ ἔχεις*, in *v.*^{2.7} (so Mo.).

5. *and shalt bear.* On the Heb. Participial form, here and in *v.*⁷, *וְיָלַדְתָּ*, cf. G-K. § 80*d*. It occurs again in the parallel passage Gen. 16¹¹.

a Nazirite. Heb. *nāzîr* means 'dedicated' or 'consecrated' to the service of the Deity. The law regulating the Nazirite vow is given in the Priestly Code, Num. 6¹⁻²¹; but it relates to a vow taken for a limited period only, and not to a lifelong vow like that imposed upon Samson. According to Num. 6 the Nazirite is bound to observe three rules: (1) he must abstain from wine and all other products of the grape, including even the fresh and dried fruit; (2) he must allow the hair of his head to grow, and must not touch it with a razor so long as his vow lasts; (3) he must not come near a dead body, lest he incur defilement; no relaxation of the rule being allowed in the case of the death of father, mother, brother, or sister (wife and child are not mentioned). Failure to observe this rule, such as might be incurred through a sudden and unexpected death in his company, involved the abrogation of his vow. The hair of his head—which was regarded as the outward symbol of his consecration—was considered to be defiled, and he remained unclean until the seventh day, when he shaved his head, and on the eighth day made a specified offering. This being done, his head was once more consecrated by the priest, and he began again to perform the period of his vow; the days which had elapsed before his defilement being considered to be forfeited. The completion of his vow without defilement was signalized by the shaving of his head and the burning of the hair on the altar, with the offering of sacrifices and the observance of due formalities. Such a temporary vow is illustrated by Acts 21^{17 ff.}; and that vows of this kind were frequent in post-exilic times is indicated by such allusions as 1 Macc. 3⁴⁹, Jos., *Ant.* XIX. vi. 1; *B.J.* II. xv. 1.

The literary setting of the law of Num. 6 is, of course, like the rest of P, post-exilic; but there is no reason to doubt that in substance the law is ancient, like so many other laws which are codified in P. We note the resemblance between the regulation laid on Samson's

mother with regard to abstaining from all products of the vine (cf. especially *v.*¹⁴), and the regulation on this point as laid down in Num. 6^{3,4}. Apart from Samson, the only allusion to Nazirites in pre-exilic times is found in Am. 2^{11,12}, where they are coupled with the Prophets and spoken of as raised up by Yahweh to their vocation—the inference being that their vow was a lifelong one. This passage shows that the regulation of abstention from wine was fundamental; and this is a trait which connects the Nazirites with the Rechabites (Jer. 35), with whom they were probably also associated in enthusiasm for a purer and simpler form of Yahweh-worship (cf. 2 Kgs. 10^{15 ff.}), as opposed to the accretions (akin to Ba'al-worship) which were the outcome of the settled life in Cana'an.* The fact that Hannah, in dedicating her son to Yahweh all the days of his life, vows that a razor shall not come up upon his head (cf. 1 Sam. 1¹¹ with Judg. 13⁵) has been taken by many to imply that Samuel was another instance of a lifelong Nazirite; and this inference is strengthened if the addition of *Ἐ* in *v.*¹¹, καὶ οἶνον καὶ μέθυσαμα οὐ πίνειται, be regarded as a genuine part of the original text; but the probability is rather that the passage has undergone amplification 'with the view of representing Samuel's dedication as more complete' (*NHTS.*² *ad loc.*). Samuel is called a Nazirite in Ecclus. 46¹³ (Heb. text).

It is certainly a somewhat remarkable fact that, whereas such references as we have to the Nazirite vow in pre-exilic times seem to regard it as lifelong, the instances which occur in post-exilic times are temporary merely; ‡ but, in view of the scantiness of the evidence which we possess, there is nothing in this to indicate that the two forms of the vow were fundamentally different in conception,§ or did not coexist throughout Israel's history.

* Cf. the present editor in *JTS.* ix. (1908), pp. 330 f., 346 f.

‡ The view that St. John the Baptist was a lifelong Nazirite is plausible, but lacks evidence for its confirmation. The description given by Hegesippus of St. James the Just, the brother of our Lord, represents him as a lifelong ascetic, and uses language which is certainly based on the O.T. description of the Nazirite obligations:—Οὗτος δὲ ἐκ κοιτίας μητρὸς αὐτοῦ ἅγιος ἦν. Οἶνον καὶ σίκερα οὐκ ἔπιεν, οὐδὲ ξιμψυχον ἔφαγε. Ξυρὸν ἐπὶ τὴν κεφαλὴν αὐτοῦ οὐκ ἀνέβη, ἔλαιον οὐκ ἠλείψατο, καὶ βαλανεῖον οὐκ ἐχρήσατο. Cf. Eusebius, *HE.* ii. 23.

§ The most striking difference in the two forms of the vow—viz., that the temporary vow found its culmination in the *hair-offering*, whereas in the lifelong vow such an offering was an impossibility—is more apparent than real. The conception involved in this form of offering appears to be that the hair, as a living part of the human organism, represents the man's *personality*, which is equally consecrated to the service of the Deity whether the hair is offered by fire upon the altar at the conclusion of the vow, or remains inviolate upon the Nazirite's head throughout his life. What is essential to the conception is that the head of hair must not pass away from the sphere of consecration and be treated as something profane; and this is secured, in the temporary vow, by ceremonial burning, and, in the lifelong vow, by the death of the Nazirite.

On the conception involved in the *hair-offering*, cf. Robertson Smith, *Religion of the Semites*,² pp. 323 ff.

The failure of Samson to conform to the regulations prescribed to the Nazirite in Num. 6 has led to the assumption that in ancient times there must have been an essential difference in the character of the obligations imposed by the vow. Judging by the narrative of Samson's life, the only obligation which he recognized was the wearing of his hair unshorn (16¹⁷). He can scarcely be supposed to have abstained from wine; for at his marriage-festival he gives a feast, the Hebrew term for which (*mišṭé*, 14^{10,12,17}, from *šāthā* 'to drink') means *lit.* a *drinking-bout*; and that this feast was of the character which its name implies is expressly indicated by the statement that, in so doing, he did as other young men were accustomed to do in like circumstances (14¹⁰). It may be inferred also that his slaughter of the Philistines would have involved him in defilement through contact with the dead.* The conclusion of Cooke that 'there was nothing ascetic about the Nazirite in the early days,' and that 'abstinence from wine did not become a mark of this type of devotee till a later time (Am. 2¹²),' does not, however, solve the difficulty. The Samson-narrative as a whole is not self-consistent on this point. The birth-narrative, *ch.* 13, agrees well enough with Am. 2^{11,12}, and even with Num. 6, but cannot be reconciled with *chs.* 14-16. The injunction laid upon Samson's mother to abstain from wine and strong drink and from other products of the vine, and to avoid eating anything unclean, so far from not being binding on the child (as Cooke assumes ‡), is expressly based upon the fact that he is to be 'a

* The question has been raised by Gray (*JTS.* i, pp. 206 f.) whether Samuel, on the assumption that he was a Nazirite, could have been bound by the regulations which forbade the drinking of wine and the touching of a dead body. He 'used to be present on festal occasions when it can scarcely be doubted that wine was drunk, and we are never told that he himself abstained'; and he 'hewed Agag in pieces,' and so 'must have suffered pollution.' It is to be observed, however, that on the three occasions on which Samuel is said to have presided at a festival-meal (1 Sam. 9^{11 ff.}, 11^{14 f.}, 16^{2 ff.}), the meal was in every case sacrificial, and doubtless very different from Samson's rollicking 'drinking-bout.' If wine was drunk at such sacrificial feasts, there is no reason why Samuel should not have abstained. Was every Nazirite who was bound by the law of Num. 6 thereby debarred from taking part in such sacrificial meals during the period of his vow, or throughout his life if he was a lifelong devotee?

The slaying of Agag was a solemn execution 'before Yahweh' (1 Sam. 15³³); and it is at least an open question whether the slaughter of Yahweh's enemies carried defilement like ordinary contact with the dead. When war was 'consecrated' (cf. Jer. 6⁴, Joel 3⁹, 4⁹), *i.e.* a holy war proclaimed, were Yahweh's 'consecrated ones' (Isa. 13³), *i.e.* His warriors, who were under special regulations of purity and taboo (Deut. 23¹⁰⁻¹⁵, 2 Sam. 11¹¹), defiled by active participation in it? The Ark at any rate did not suffer pollution through going into battle at the head of the army.

It may be admitted, however, that we have not the same ground for assuming the prohibition of contact with the dead to have been characteristic of the early form of the Nazirite vow, as we have with regard to the prohibition of drinking wine.

‡ 'The restrictions are laid upon the mother; nothing is said about the child observing them' (p. 132).

R^{JE} and it is he that shall begin to save Israel from the hand of the Philistines.' 6. J² And the woman came and told her husband, saying, 'A man [] came unto me, and his appearance was like the appearance of []^a god, very awful; and I asked him not

Nazirite of God *from the womb*.' If, then, he is bound, through his mother, by this obligation when still unborn, *a fortiori* its stringency is not intended to be relaxed in his after-life. Yet not only, as we have seen, does he apparently drink wine, but he also eats honey which has been taken from the decomposed carcase of a lion; and in all this the narrator of *chs.* 14-16 evinces no consciousness that his hero is infringing the terms of his vocation. The conclusion to which we are led is that of Kue. (*Religion of Israel*, i. p. 308): 'Is it not evident from this that Samson has been *made* a Nazirite, although, with the exception of this one feature [his long locks], his whole history is opposed to this conception?' The author of *ch.* 13 (which, as we have seen, is later than the stories of *chs.* 14-16 which it introduces) seems to have assumed that the long locks with which his hero was endowed marked him as a Nazirite; and so in the birth-narrative he represented him as such—this inference being the easier owing to the fact that his supernatural strength was, according to the old tradition, bound up with the retention of his locks, just as a divine endowment might be granted to a Nazirite on the condition of the faithful performance of the terms of his vow. The difficulty of accepting Samson as a Nazirite is in itself a warrant for investigating the claims of a different explanation of the meaning of his long hair (*cf.* p. 404).

begin to save. In using this qualified phrase, R^{JE} (*cf.* p. 338) appears to be influenced partly by the difficulty of regarding Samson as an effective 'judge' (saviour), and partly by the fact that his history was to contain E's narrative of the signal deliverance under the judgeship of Samuel (1 Sam. 7; *cf.* especially *v.*¹³). M^o. explains 'begin to save' as meaning no more than 'be the first to save' (*cf.* 10¹⁸ 'begin to fight,' also R^{JE}); but this is less likely.

6. *a man.* Reading אִישׁ simply, with Bu., No., Kit., Ehr. *Cf.* *v.*¹⁰, where the woman alludes again to the visitor as 'the man.' אִישׁ הָאֵלֹהִים must be intended to mean 'a man of God' (an inspired man, or prophet); but this should naturally be אִישׁ אֱלֹהִים (*cf.* 1 Sam. 2²⁷, 9⁶, 2 Kgs. 1¹⁰, 4⁹), the use of the Definite Article before אֱלֹהִים making the whole phrase definite—'the man of God,' as in *v.*⁸ and very frequently elsewhere. It is probable that, as Bu. assumes, אִישׁ הָאֵלֹהִים has been carelessly added from *v.*⁸.

a god. Reading אֱלֹהִים, with Böhme, Holzinger, Bu., No., Kit.

whence he was, and his name he told me not. 7. And he said to me, "Behold thou art with child, and shalt bear a son; now, therefore, drink neither wine nor strong drink, and eat not anything unclean; for the lad shall be a Nazirite of God from the womb unto the day of his death."

8. And Manoah intreated Yahweh, and said, 'Oh, Lord, prithee let the man of God, whom thou didst send, come again unto us, and teach us what we shall do to the child that shall be born.' 9. And 'Yahweh' hearkened to the voice of Manoah, and the Angel of 'Yahweh' came again unto the woman, as she was sitting in the field; and Manoah her husband was not with her. 10. And the woman made haste, and ran, and told her husband, and said unto him, 'Behold the man hath appeared unto me that came unto me the other day.' 11. And Manoah arose, and went after his wife, and came unto the man, and said to him, 'Art thou the man that spake unto the woman?' And

The sense intended seems to be 'a *supernatural being*'; so probably in *v.*²². For this use of 'ēlōhīm, cf. 1 Sam. 28¹³, where the witch of 'Endor, when she has called up the shade of Samuel (and also, apparently, attendant spirits; cf. *NHTS.*² *ad loc.*), says, 'I see 'ēlōhīm (supernatural beings) coming up from the earth.' וְהָאֱלֹהִים מִלְאָךְ 'like the Angel of God'; but the regular expression elsewhere in the narrative (*vv.*^{3,13,15,16,17,18,20,21}; on *v.*⁹, cf. *note*) is 'the Angel of *Yahweh*'; and it appears to be not till *v.*²¹ that Manoah and his wife even suspect the *real* character of their visitor (*v.*^{16b}; cf. also *ch.* 6²²).

9. *And Yahweh . . . and the Angel of Yahweh.* Reading יהוה in both cases for האלהים; in the first case with *L*, *Y*, *S*^p, and in the second with *L*, *S*^p. As Mo. remarks, the substitution of האלהים in וְהָאֱלֹהִים may have been accidentally due to the proximity of אֵישׁ האלהים in *v.*⁸

10. *the other day.* Heb. בַּיּוֹם, lit. 'on the day,' *i.e.* the day which was noteworthy on account of the event with which it was connected.*

* The use of the Definite Article is somewhat similar in the phrase וַיְהִי הַיּוֹם וְנָ (1 Sam. 1¹, 14¹, 2 Kgs. 4^{8,11,18}, Job 1^{6,18}, 2¹⁴), where English idiom renders 'And there came a day when, etc.,' but which literally means 'And *the* day was, etc.,' *day* being defined on account of the events (to be related) which happened on it. Cf. the discussion in *NHTS.*² p. 6.

he said, 'I am.' 12. And Manoah said, 'Now, if thy word^f come to pass, what shall be the rule for the lad and his work?' 13. And the Angel of Yahweh said unto Manoah, 'Of all that I said unto the woman let her take heed. 14. Of all that cometh of the grape-vine she shall not eat, and wine and strong drink let her not drink, and anything unclean let her not eat: all that I have commanded her let her observe.' 15. And Manoah said unto the Angel of Yahweh, 'Prithee let us detain thee, and make ready before thee a kid of the goats.' 16. And the Angel of Yahweh said unto Manoah, 'Though thou detain

12. *Now, if, etc.* The 'if' is not expressed in Heb., the two clauses being placed side by side so as to form a virtual hypothetical sentence — 'Now, let thy word come to pass, what shall be, etc.,' implies 'Assuming that thy word, etc.' Cf. *ch.* 6¹³, lit. 'And *is* Yahweh with us, why, then, etc.,' *i.e.* 'If Yahweh *is*, etc.': Driver, *Tenses*, § 149. Perles (*Analekten*, p. 35) and La. propose to emend עֵתָה — 'At the time when thy word cometh true, what shall be, etc.' (cf. Ps. 105¹⁹ בּוֹא־דְּבָרוֹ עַד-עֵת 'Until the time when his word came to pass'); but the change is no improvement.

thy word. Reading sing. דְּבָרְךָ with many MSS. and Ⓢ, Θ., Ⓜ, Ⓢ^p, in place of Ⓜ plur. דְּבָרֶיךָ.

the rule for the lad. Heb. מִשְׁפָּט הַנֶּעַר. Heb. *mišpāt* is here used in its common sense of *ordinance* or *rule of life*. That this should be the sense intended seems to be demanded by the Angel's answer, which repeats the injunctions laid upon the woman. So R.V. *marg.* 'ordering.' R.V. *text*, 'What shall be the manner of the child?' interprets *mišpāt* in the sense which it seems to possess only elsewhere in 2 Kgs. 1⁷, 'What is the manner of the man that came up to meet you?' *i.e.* 'How would you describe him?' Apart, however, from the exceptional character of this use of *mišpāt* as the summary of *distinctive characteristics*, such a sense is less suitable to the context than that which we have adopted.

15. *make ready before thee.* As Mo. observes, the expression is a pregnant one, equivalent to 'make ready and set before thee.' La. assumes that לפניך 'before thee' implies something further, and so follows St. Augustine in supposing that Manoah is contemplating a sacrificial meal, which the Angel rejects in favour of a holocaust; but this view is expressly precluded by *v.*^{16b}, where we are told that Manoah was unaware of the extraordinary character of his guest.

16. *Though thou detain me, etc.* The J narratives Gen. 18^{1ff.},

me, I will not eat of thy bread; but if thou wilt prepare a burnt offering, to Yahweh shalt thou offer it.' For Manoah knew not that he was the Angel of Yahweh. 17. And Manoah said unto the Angel of Yahweh, 'What is thy name? When thy word¹⁷

Judg. 6¹¹⁻²⁴, which have strong points of resemblance to our narrative, differ somewhat as regards the guest's reception of the offer of hospitality. In Gen. 18 the supernatural visitors accept the offer and partake of the meal. In Judg. 6 the Angel of Yahweh, after assenting to Gide'on's proposal, converts the meal into a sacrifice. Here he refuses the meal, but suggests instead the offering of a sacrifice to Yahweh. The three narratives thus seem to mark an advance from a very primitive stage in which Yahweh Himself (cf. Gen. 18^{1,13*}) is thought to visit men and accept their hospitality, to later modification of the *naïveté* of the conception by substitution of the Angel of Yahweh for Yahweh Himself (cf. *note* on *ch.* 2¹ at end), and conversion of the meal into a sacrifice offered to Yahweh, who seems in the present passage to be definitely distinguished from His Angel.

17. *What is thy name?* Heb. מִי שְׁמֶךָ, lit. 'Who is thy name?'—perhaps through a sub-consciousness of the equivalence of the question to 'Who art thou?' Elsewhere (Gen. 32²⁸, Ex. 3¹³) מַה is used; and it is possible that ה and י, which are very similar in the old character, may have been confused in our passage.

when thy word . . . honour. Heb. כִּי־יָבוֹא דְבָרְךָ וְכַבְדֵּנוּךָ. ^{AL} 𐤊𐤁, ^V 𐤁𐤁, R.V. 'that when thy words come to pass we may do thee honour'; and this rendering is adopted by commentators generally without remark upon the difficulty of justifying it syntactically. The opening 'that' apparently represents the וְכַבְדֵּנוּךָ (so Ros. renders 'si eveniat quod praedixeris, ut honoremus te'), and this would have been the natural interpretation if the order of the sentence had been כִּי יָבוֹא דְבָרְךָ וְכַבְדֵּנוּךָ 'that we may do thee honour when thy word cometh to pass'; but it is more than doubtful whether such a rendering can be extracted from the sentence in its present order. It is perhaps just possible to render כִּי 'for' and treat what follows as a virtual hypothetical (cf. *note* on *v.* 12, 'Now, if, etc.')->'for, let thy word come to pass, and we will, etc.' (cf. ^U 𐤊𐤁, i.e. 'for, when (or if) thy word . . . we will, etc. '; cf. *v.* 12 *note*. On the whole, however, the rendering adopted above (so Stu.) is the most natural one.

thy word. Reading sing. דְבָרְךָ with ^{AL} 𐤊𐤁, many MSS. of ^U 𐤊𐤁, and ^U 𐤊𐤁, ^V 𐤁𐤁, in place of *Kt.* דְבָרֶיךָ.

* The confusion in this narrative between the sing. 'Yahweh' (*vv.* 1a, 3, 10a, 13, 17, 20, 22b, ff.) and the plur. 'three men' (*vv.* 2, 4, 5, 8, 9a, 16, 22a) is very obscure. Cf., however, the interesting remarks of Skinner, *ICC.* pp. 302 f.

cometh to pass we will do thee honour.' 18. And the Angel of Yahweh said to him, 'Wherefore, now, askest thou concerning my name, seeing that it is wonderful?' 19. And Manoah took the kid of the goats, ^{Gl.} with the meal-offering, ^{J²} and offered it up upon the rock to Yahweh.[] 20. And, when

18. *wonderful*. The adj. *pi'li* occurs only once again in the fem. *pi'liyyā* Ps. 139⁶,* which illustrates the meaning in the present passage :—

'Such knowledge is too *wonderful* for me ;
Too high, I cannot attain unto it.'

The root-meaning is *separate* from the ordinary, and so *surpassing* it. For the verbal form in the Niph'al with the sense *surpassing understanding*, cf. Ps. 131¹, Prov. 30¹⁸, Job 42³.

19. *with the meal-offering*. This use of *minhā*, which in pre-exilic literature is the ordinary term for *offering* generally, in the specific sense of *meal-offering*, is late, and characterizes the ritual of the Priestly Code. Böhme is therefore probably correct in regarding the reference here and in *v.*²³ as a late addition made for the sake of liturgical correctness.

and offered it up, etc. Manoah, we must assume, kindles his sacrifice in the ordinary way. Contrast 6²¹. The narrative of Jos. (*Ant.* v. viii. 3) is here strongly coloured by recollection of *ch.* 6¹⁸⁻²¹. Manoah regards the offering not as a sacrifice but as a mark of hospitality. It is the Angel who commands him to place 'the loaves and flesh, without the vessels,' on the rock, and who by touching it with the end of his rod converts it into a burnt-offering, then disappearing in the smoke of the sacrifice.

upon the rock. The reference seems to be to a *rock-altar*: cf. note on *ch.* 6²⁰. Such a primitive rock-altar exists at the present day in the neighbourhood of Şar'ah: cf. Kittel, *Studien zur hebräischen Archäologie und Religionsgeschichte* (1908), pp. 97-158 (with two plans); *Über primitive Felsaltäre in Palästina*, pp. 243-255 of *Hilprecht Anniversary Volume* (with photographs).

At the end of the verse *U* adds, וּמַפְלֵא לַעֲשׂוֹת וּמְנוֹחַ וְיִצְחָקוֹ רָאִים, i.e. 'and doing wondrously, and Manoah and his wife were looking on.' Here the Participle מַפְלֵא is without a subj., and cannot have thus stood originally. *Gr^{AL} al.* τῶ θαυμαστὰ ποιοῦντι (in apposition to preceding τῶ Κυρίῳ), *U* '(Domino,) qui fecit mirabilia,' presuppose

* In these passages *Kt.* should be vocalized מַפְלֵא, פִּלְאִיָּה. *Here* מַפְלֵא, פִּלְאִיָּה.

the flame went up from off the altar towards heaven, the Angel of Yahweh went up in the flame of the altar: and Manoah and his wife were looking on, and they fell on their faces to the ground. 21. And the Angel of Yahweh appeared no more unto Manoah and his wife. Then Manoah knew that it was the Angel of Yahweh. 22. And Manoah said unto his wife, 'We shall surely die, for it is a god that we have seen.' 23. And his

הַמַּפְלֵא לַעֲשׂוֹת 'who doeth (or who did) wondrously,' and this is adopted by Mo., La., Kent. Maurer (quoted by Stu.), Oet. suggest 'וְהוּא מַפְלֵא וְג' 'He (Yahweh) doing wondrously'; but, as Stu. remarks, it is awkward to have two circumstantial clauses (this and the following וְג' וּמוֹנָה) thus side by side. Oet. gives as an alternative 'וַיַּפְלֵא וְג' 'and he did wondrously'; cf. ἔ^{B} καὶ διεχώρισεν ποιῆσαι. Houbigant supplies a subj. וַיְהוֹה מַפְלֵא וְג' 'and Yahweh did wondrously.' R.V. 'and the angel did wondrously' could only be justified by the insertion of a subj. הַמַּלְאָךְ or הוּא. Kit. supposes that the words are misplaced, and should properly follow v.^{20a}—'and the Angel of Yahweh ascended in the flame of the altar in a most wonderful way.' It is, however, very superfluous to state at this point that the Angel's action was extraordinary.

It can hardly be doubted that the difficult words are really a marginal explanation—'doing wondrously'—of the rare adj. *pil'i* 'wonderful' in v.¹⁸ (*pil'i*, lit. 'extraordinary' is explained by the cognate verb *maphli*, 'making extraordinary as regards doing,' i.e. acting in an extraordinary way). This has crept into the text in the wrong place, together with erroneous repetition of the words 'and Manoah and his wife were looking on' from v.²⁰. So Ber., Böhme, Oort, Bu.

20. *the altar*. I.e. 'the rock' of v.¹⁹, which was evidently an ancient place of sacrifice (cf. the use of the verb וַיַּעַל 'and he offered it up'), and, as such, may be appropriately described by the term מִזְבֵּחַ. There is no reason for suspecting the originality of the verse (Stu.), or for supposing that 'the altar' has been substituted for 'the rock' by a later hand (Böhme).

went up, etc. The description is more specific than that of 6²¹, where the Angel merely vanishes from Gide'on's sight.

We shall surely die. Cf. 6²² note.

for it is a god, etc. The order of the Heb., כִּי אֱלֹהִים רָאִינוּ, is very emphatic. R.V. renders 'ĕlōhīm 'God'; but had this been intended we should have expected Manoah to have used the name

wife said to him, 'If Yahweh had been pleased to kill us, he would not have received at our hand a burnt offering ^{Gl.} and meal-offering, J² and would not 'have instructed us' [] 'thus' []

Yahweh, and not 'ēlōhīm: cf. the verse following. On the sense in which 'ēlōhīm is probably used, cf. *note* on v.⁶.

23. *and would not have instructed us thus.* Reading וְלֹא הוֹרְנוּ כִּזְאת in place of וְלֹא הִרְאֵנוּ אֶת-כָּל-אֱלֹהִים וְכַעַת לֹא הִשְׁמִיעֵנוּ כִּזְאת 'neither would he have shewed us all these things, nor would he at this time have told us such a thing as this.' The difficulty of וְלֹא's text is two-fold. (1) The expression כַּעַת 'at this time' (omitted in some *Gr* MSS., *L*, *V*) is very rare, occurring again only in *ch.* 21²², Num. 23²³, in both of which passages it causes some little difficulty and its originality is questioned. Granted that it means 'at this time' or 'just now,' its position in the sentence is strange, since, referring as it does very strikingly to לֹא הִשְׁמִיעֵנוּ, and not to the preceding וְלֹא הִרְאֵנוּ . . . לֹא לֶקַח, 'it seems to oppose the hearing, as recent, to the seeing and the sacrifice' (Mo.). Mo.'s suggested emendation כִּי עַתָּה 'for now,' is unsuitable apart from omission of all that precedes from לֹא לֶקַח to אֱלֹהִים and the reading of לֹא חָפֵץ for לֹא חָפֵץ—'Yahweh is not pleased to kill us; for now he would not have told us,' etc.

(2) If וְלֹא הִרְאֵנוּ וְנִי, 'neither would he have shewed us all these things,' refers to the sights which they had just witnessed, *i.e.* the appearance of the Angel and his subsequent proceedings, since it was on account of this appearance that Manoah supposed that Yahweh *would* slay them, it is obvious that it could not be adduced as a reason why He *would not* slay them. If, on the other hand, the verb 'shewed' refers to the information with regard to the birth of the child and his future, it is superfluous by the side of לֹא הִשְׁמִיעֵנוּ כִּזְאת 'he would not have told us, etc,' since it says the same thing with but slight variation.

Gr^{AL}, *L*, *S*^h render וְלֹא הִרְאֵנוּ by καὶ οὐκ ἂν ἐφώτισεν ἡμᾶς, which points to an original וְלֹא הוֹרְנוּ 'and would not have instructed us'; cf. their rendering of וְיִוְרְנוּ v.⁸ by καὶ φωτισάτω ἡμᾶς.* The fact that לֹא הוֹרְנוּ and לֹא הִשְׁמִיעֵנוּ are synonymous expressions seems to postulate the existence of a doublet. We assume, then, that וְלֹא הוֹרְנוּ was the original reading (cf. וְיִוְרְנוּ v.⁸), and

* The rendering is probably due (as Mo., *SBOT.*, observes) to false etymological association of הוֹרָה with אֹר. The verb is similarly rendered in 2 Kgs. 12², 17^{27,28}.

24. And the woman bare a son, and called his name Samson: and the lad grew up, and Yahweh blessed him. 25. And the

לֹא הִשְׁמִיעֵנו כּוֹחַ, a marginal variant or explanatory gloss, was subsequently introduced into the text. Later stages of corruption are represented by the alteration of הוֹרֵנוּ to הִרְאֵנוּ (thus making reference to seeing *and* hearing in place of the double reference to hearing), the glossing of the first כּוֹחַ by אֵל כָּל אֱלֹהִים, and its subsequent alteration to כֶּעֶת, and then to וּכְעֵת when taken to refer to the words which follow it. The conclusions of Mo. (SBOT.) and La. are similar.

24. *Samson*. Σῆμσῶν. The *a*-vowel of the English form, which is found in Σαμψων, Σ 'Samson,' represents the primitive vocalization.* Cf. the name Šamšānu cited by Hilprecht, *Business Documents of Murāshu Sons of Nippur*, pp. 27, 70.

The connexion of the name with Šēmeš 'sun' may be considered certain, and no other proposed explanation is at all plausible‡; but the precise meaning borne by the name is wholly vague. The view that it is a diminutive form—'little sun'—is not very probable, the only analogous formation that can be cited being 'išōn 'pupil of the eye'—apparently 'little man' (reflected in pupil)—formed from 'iš 'man': cf. G-K. § 86 g. More plausible is the suggestion that the termination makes the form adjectival; cf. ḫadhmōn 'eastern'; from ḫédhem 'east': G-K § 86 f. Samson might then mean 'solar one,' just as יְרִיחוֹ 'Jericho' very possibly means 'lunar' (*sc.* city)§; but the precise significance of such a title—whether 'sun-like,' 'solar hero,' or 'protégé of the sun-god'—is obscure. The proximity of Bethshemesh 'Temple of the Sun' to Samson's birthplace (cf. *note* on 'Šor'ah,' v. 2) suggests the likelihood that the hero's name was, in origin, honorific of the sun-god. It is possible, indeed, that the name may be hypocoristic for a fuller Šamši-el, 'Šamaš is God'; cf. 'Abdon, *ch.* 12^{13, 15}, *al.*, by the side of 'Abdi-el, 'Servant of God,' 1 Chr. 5¹⁵. Similar South Palestinian names are Shēshai and Shavsha (cf. p. 10), and possibly Shimshai of Ezr. 4^{8, 9, 17, 23}.

* Cf. *note* on *baggabôrîm*, pp. 168 f.

‡ The statement of Jos. (*Ant.* v. viii. 4), καὶ γενόμενον τὸ παιδίον Σαμψῶνα καλοῦσιν, ἰσχυρὸν δ' ἀποσημαίνει τὸ ὄνομα, is probably guesswork, it being unlikely that he connected it with šāmēn (Meier) in the sense 'robust': cf. *ch.* 3²⁹. Ewald (*III.* ii. p. 306) suggests derivation from New Heb. šimmēš, Aram. šammēš 'to serve,' in the sense 'servant' of God, *i.e.* Nazirite. Other views—*e.g.* that the name stands for Šamšōm, a reduplicated form from šāmēm, in the sense 'devastator' (cf. Ber.); or that it is to be explained from Ar. šamšam, 'vir fortis et audax' (Goliath quoted by Ros.)—are philologically impossible.

§ That the denominative termination -ā, as seen in יְרִיחוֹ, is probably an abbreviation of -ōn, is suggested by the parallel forms Megiddō, Megiddōn, and the adjectival forms Shilōnī from Shilō, Gilōnī from Gilō: cf. Stade, *Lehrbuch der heb. Gramm.*, § 296 e.

spirit of Yahweh began to impel him in Maḥaneh-Dan, between Şor'ah and Eshta'ol.

25. *to impel him.* *I.e.* to stir him up by a sudden access of frenzy in which he was moved to put forth his supernatural strength. The Heb. verb *pā'am* is used elsewhere of the *disquieting* of the human spirit through anxiety or perplexity; Gen. 41⁸, Dan. 2^{1,3}, Ps. 77⁴ (³)[†].

Maḥaneh-Dan. Possibly a hamlet dependent upon Şor'ah which was the home of Manoah; since the same definition of locality—'between Şor'ah and Eshta'ol'—is used in 16³¹ of the site of the family-sepulchre. The name, which means 'the camp of Dan,' is explained in *ch.* 18¹² as owing its origin to an encampment of the Danites to the west of Kiriath-Je'arim, when they were on the march from Şor'ah and Eshta'ol to seek a new home in the north. Kiriath-Je'arim, if rightly identified with Kuryet el-'Enab, is nearly eight miles east-north-east of Şor'ah. The existence in close proximity of two places bearing the same name Maḥaneh-Dan is very improbable; and since the connexion in which the name occurs in 18¹² favours its originality in that passage, it is very possible that it may be an erroneous insertion in the present context. S. A. Cook's proposal (*EB.* 2904; *Notes on O.T. History*, p. 88) to emend Manahath-Dan in both places, and to find allusion to the two divisions of the Manahtites, one in connexion with Kiriath-Je'arim (1 Chr. 2³²) and the other at Şor'ah (1 Chr. 2⁵⁴), is ingenious but not convincing. As we have noticed above (*footnote*, p. 341), the Manahtites seem to have been post-exilic Calibbite settlers in these districts, and to have had no connexion with the tribe of Dan.

Eshta'ol. Commonly identified with the modern 'Ešúa', not much more than a mile and a half to the north-east of Şor'ah; cf. *note* on Şor'ah, *v.* 2. On the rare (in Heb.) *Iphth'al* form of the name, which is possibly to be derived from the verb *šā'al* 'ask' in the sense 'ask for oneself,' and so may mean 'place of consulting the oracle' (the site of an ancient sanctuary), cf. the present editor's note in *JTS.* xiii. (1911), p. 83.

14. Doorn. and Sta. (followed by Mo., Bu., and most recent commentators) have rightly perceived that the narrative of this chapter has been extensively worked over, for the purpose of representing Samson, so far as was possible, in the light of a dutiful son. As the story stands, it seems as though Samson's parents, though at first strongly opposed to his wish to marry a Philistine maiden (*v.* 3), finally acquiesce and accompany him to Timnah in order to forward his plans (*vv.* 5, 10). There are, however, very obvious difficulties in the way of accepting such a situation. In *v.* 5, though Samson is accompanied by his parents, it is he alone who is confronted by the lion; and, when he has slain it, his parents are unaware of the fact (*v.* 6^b). We can only infer that he must have outstripped his parents on the

way (Kimchi), or turned aside along a bypath in the vineyards ; yet of this there is no hint in the narrative. In *v. 7.8* the parents disappear altogether ; and it is Samson alone who interviews the woman and arranges the preliminaries of the wedding, returning after a time to carry it through. In *v. 10a* the father appears in a belated way ; but it is Samson who makes the marriage-feast (*v. 10b*), and acts throughout on his own responsibility.

The account of the journeys to and from Timnah is also, as the narrative stands, very confused. After the first visit in company with his father and mother, the return to Šor'ah is assumed but not mentioned ; and *v. 8* narrates a second visit to Timnah of Samson by himself in order to get married (לקחתה). On the way down he visits the carcase of the lion and discovers the honey ; some of which he gives to his father and his mother. Yet we cannot suppose that he had returned to Šor'ah prior to the actual marriage-festival (*v. 10ff.*), since it was for the sake of this that he went to Timnah, as recorded in *v. 8* ; nor can we assume that his parents accompanied him again in *v. 8*, and that he gave them the honey on the way down or at Timnah, since it is not till *v. 10* that his father comes down (from Šor'ah).

The narrative at once becomes clear if, with Doorn. and Sta., we omit ואמו ואביו and read the sing. ויבא in *v. 5* ; omit *v. 6b* ולא הניד ; omit עשה ; omit לקחתה *v. 8* ; read שמשון in place of אביהו in *v. 10a*, and omit the name in *v. 10b*. In face of his parents' opposition to the match, Samson goes *alone* to Timnah, and returns after a few days to his parents' house at Šor'ah (*v. 8*), bringing them some of the honey which he has discovered on his journey home. The simple removal of לקחתה 'to marry her' in *v. 8* at once solves the difficulty noted above as to the journeys to and fro, by allowing the obvious inference that it was *on his return to Šor'ah* that he found the honey, and not, as the interpolator imagined, on going a second time to Timnah, after a return home unrecorded. He would naturally inspect the lion's carcase on the earliest opportunity. His second visit to Timnah, in order to celebrate his marriage, is recorded in *v. 10*, which originally ran 'And Samson went down unto the woman, and he made there a feast, etc.'

There is another point which confirms this view of affairs. From Samson's request to his parents in *v. 2* it is clear that he originally contemplated a marriage of the ordinary kind, when his father would have interviewed the father of the maiden and arranged the *môhar* (purchase-price), and the bride would have been brought back to the bridegroom's house at Šor'ah, where the feast would have been held. In this case the bridegroom's 'companions' who assisted at the function would have been young men from his own clan. According to *v. 11*, however, these 'companions' are not Danites but Philistines ; the feast, though provided by Samson, takes place not at Šor'ah but

at Timnah; and it is there, evidently, that the marriage would have been consummated (*v.*¹⁸, reading הִתְּרַה; cf. *note*) if Samson had not left in a rage after the unfair discovery of his riddle. This is still further borne out by *ch.* 15¹, where, on regaining his good temper, he returns to Timnah with a present for his bride, and expects to enjoy the rights of marriage at her father's house. It is evident, therefore, that after failing to persuade his parents to agree to such a marriage as he had at first contemplated, he arranges, without their consent, a marriage of the *ṣadīḳa* type (cf. *ch.* 8³¹ *note*), in which the custom was that the bride remained with her own people, the children of the marriage belonging to the mother's, and not to the father's clan, and the marriage-contract being frequently for a limited period merely.

This explains the fact that the bridegroom's 'companions' of *v.*¹¹ are Philistines and not Danites. The only difficulty, as this verse stands, is that they are selected, not by Samson, but by persons undefined who seem to have thought it wise to have a strong body of Philistines on the spot on account of the formidable appearance of the bridegroom. Here the fact that the narrative has been worked over is transparently evident. Probably the verse originally ran, 'And he (*i.e.* Samson) took thirty companions, and they remained with him'; but the policy of representing Samson's conduct in the best possible light, which seems to have dominated the reviser of the narrative, has led to alteration of the text—instead of Samson himself choosing his marriage-companions from among the uncircumcised, they were forced upon him; and a reason for this has to be invented and supplied.

As to when the narrative was thus extensively glossed we have no means of determining. Probably the additions were made in late post-exilic times (so Mo., *SBOT.*), though this is by no means certain. They are marked in the text by the symbol Gl., *i.e.* 'Gloss.'

Further interpolations (*vv.* 14 f.¹⁹) are noticed in their place.

14. 1. J¹ And Samson went down to Timnah, and saw a

1. *Timnah.* The form תִּמְנָתָה Timnātha with Accusative termination, which is natural in *vv.* 1a, 5a where *direction towards* is implied (ה *locative*; cf. Gen. 38^{12, 13, 14}), is used without this implication in *vv.* 1b, 2, 5b, Josh. 19⁴³; cf. *note* on Jahaš, *ch.* 11²⁰. תִּמְנָה Timnah occurs in Josh. 15^{10, 57}, 2 Chr. 28¹⁸. Timnah is the modern Tibneh, in the Shephelah, some four miles south-west of Šor'ah. The elevation of Šor'ah is 1171 feet above the Mediterranean, while that of Timnah is 800 feet; hence the use of the verb 'went down' here and in *vv.* 5, 7, 10, and conversely 'went up,' *vv.* 2, 19, of the homeward journey. Timnah, which is here a Philistine city, is assigned to Dan in Josh. 19⁴³ P; while in Josh. 15¹⁰ P it appears as a border-city of Judah. 2 Chr. 28¹⁸ mentions a Philistine raid on the Shephelah and

woman in Timnah of the daughters of the Philistines. 2. And he went up, and told his father and his mother, and said, 'I have seen a woman in Timnah of the daughters of the Philistines: now, therefore, get her for me to wife.' 3. And his father ^{Gl} and his mother ^J said to him, 'Is there not a woman among the daughters of thy brethren, or among all my folk, that thou art going to take a wife of the uncircumcised Philistines?' And

the Negeb in the reign of Aḥaz, when Timnah and neighbouring cities were captured from Judah.

a woman. Bu. comments on the uncommon use of *iššā* here and in *vv.* ^{2a.7.10} instead of *na'arā* 'maiden,' the ordinary term for an unmarried girl. He suggests that the 'woman' may have been a widow or divorced wife, or else that the term may be used with a shade of contempt. The latter suggestion is the more probable; cf. the application of the term to Delilah in *ch.* 16 ⁴.

2. *get her, etc.* The preliminaries of marriage, such as the settlement of the *môhar* (cf. p. 354), were a matter of arrangement between the fathers of the suitor and his desired bride: cf. the later version of the story of Gen. 34, especially *vv.* ^{4.6.8.12}. Samson addresses both his parents and uses the plur. verb קרו 'get ye.' This inclusion of the mother may be due to ^J in view of her prominence in *ch.* 13, or to a later hand for the same reason; but this is by no means certain. Though the negotiations rested with the father, there is no reason why he should not have been to some extent dependent on his wife's advice. In the following *v.* ^{3a} it is probable that ואמו 'and his mother' is an addition in imitation of *v.* ². Notice the sing. suffix of עמי 'my folk' in the father's speech, and the fact that Samson's response in *v.* ^{3b} is addressed to his father only.

3. *among the daughters of thy brethren.* 'Brethren' here = 'fellow-clansmen'; cf. *ch.* 16 ³¹, 9 ^{1.3}, 2 Sam. 19 ¹³. ^S^p presupposes אבִיךָ בְּבֵית אָבִיךָ 'in thy father's house,' i.e. thy family or clan; cf. 16 ³¹, and very frequently in P and Chr. (cf. references in BDB. p. 110a). This is adopted by Bu., No.; but the change is unnecessary.

my folk. ^{Gr}^L, ^S^p, Houbigant, Bu., Oort, No., La., עַמֶּיךָ 'thy folk' is plausible. But מִי עַמִּי is very natural in the father's mouth; and it is likely that the reading of ^{Gr}^L, ^S^p may have arisen under the influence of the preceding אֶחָיִךְ (so Mo.).

uncircumcised. A term of opprobrium, applied to the Philistines elsewhere in *ch.* 15 ¹⁸, 1 Sam. 14 ⁶, 17 ^{26.36}, 31 ⁴, 1 Chr. 10 ⁴. The Philistines appear to have been the only race known to the Israelites in early times who did not practice circumcision. Upon the diffusion of the custom, cf. articles in *DB.* and *EB.*, and Skinner, *Genesis*, ICC., pp. 296 f.

Samson said unto his father, 'Get *her* for me; for she it is that pleaseth me.' 4. J² And his father and his mother knew not that it was from Yahweh: for he was seeking an occasion against the Philistines. Now at that time the Philistines were ruling over Israel.

5. J¹ And Samson went down, ^{Gl.} and his father and his mother, J¹ to Timnah, and ^{Gl.} they J¹ came to the vineyards of Timnah: and, behold, a young lion came roaring to meet him. 6. And the spirit of Yahweh rushed upon him, and he rent it

Get her for me. Heb. אֶתְּהָ קַח-לִי, with very emphatic order of words—*her* and none other. Samson will brook no interference with his wayward inclinations.

pleaseth me. Lit. 'is right in mine eyes.' So v.^{7b}.

4. *And his father and his mother, etc.* The whole verse seems to have formed no part of the original narrative. The first half of the verse has a back reference to *ch.* 13, and was added, probably, by the author of that chapter (J²) in explanation of the fact that an inspired Nazirite should have determined to contract such a marriage-alliance (so Doorn.). To the same hand, probably, belongs the reference to the Philistine domination (possibly derived from 15¹¹), which would be superfluous if due to a *later* hand than R^{E2} in 13^{1b}, or even than R^{JE} in 13^{6b}.

an occasion. I.e. an opportunity for the provocation of hostilities.

5. *And Samson, etc.* Originally, 'And Samson went down to Timnah, and came, etc.' Failing to gain his father's co-operation, he starts off on his own account to contract a *ṣadiqa*-marriage. Cf. pp. 354 f.

a young lion. נָפִיר אֶרְיִית, lit. 'a young lion of the lions'; cf. the phrase נָרִי עֵיִים 'a kid of the goats.' Heb. *kēphîr* denotes a lion which has ceased to be a *gûr* or *whelp*, and has come to full growth and attained the power of hunting its own prey: cf. especially Ezek. 19^{2,3}; also Isa. 5²⁹, 31⁴, Am. 3⁴, Mic. 5⁷, Ps. 35¹⁷, 104²¹.

6. *And the spirit of Yahweh, etc.* Cf. note on *ch.* 3¹⁰. The verb *šālah*, which is applied to the powerful inrush of the divine impulse upon Samson here and in v.¹⁹, *ch.* 15¹⁴, is similarly used with reference to Saul in 1 Sam. 10^{6,10}, 11⁶ J.

he rent it. The Heb. verb. *šissa'* is used in Lev. 1¹⁷ P of *tearing open* a bird by its wings, when offered as a whole burnt-offering. This was done 'without dividing it,' i.e. without tearing it into two halves. The verb is also employed, together with the cognate substantive, of *cleaving the cleft* (*šéša'*) of the hoof, i.e. having a cloven hoof—one of the distinctive marks of sacrificially clean animals.

as one might rend a kid; and there was nothing in his hand: ^{Gl.} but he told not his father and his mother what he had done. 7. J¹ And he went down, and spoke to the woman; and she pleased Samson. 8. And he returned after a while ^{Gl.} to take her, J¹ and he turned aside to see the carcase of the lion: and,

Judging by these usages—especially by Lev. 1¹⁷—Samson must have torn the lion down the middle,* and may be supposed to have done this by tearing the hind legs apart, precisely as Gilgamesh's companion Engidu is represented as doing (Plate II., fig. 4), and also the colossal figure from Cyprus (perhaps Melkart-Herakles; Plate VI.).

In the Jerusalem *šāssa'* is used as the rendering of וִיפְּשְׁחֵנִי וִיפְּשְׁחֵנִי 'and he hath torn me in pieces' (as a lion rends its prey), Lam. 3¹¹.

as one might rend a kid. Lit. 'like the rending of a kid,' i.e. as easily as an ordinary man would perform the same action on a kid. Mo. renders 'as a man tears a kid,' and thinks that this, like Lev. 1¹⁷, may be a reference to some ceremonial act. The whole point of the description lies, however, in the ease with which Samson's extraordinary strength enabled him to perform the deed, rather than on the manner in which it was done.

and there was nothing, etc. Cf. the representations of Gilgamesh, etc., noticed above. Herakles is related to have strangled the Nemaean lion with his bare hands ‡ (cf. the references collected by Bochart, *Hierozoicon*, i. p. 754); and Pulydamas of Scotusa in Thessaly, moved by desire to emulate the feats of Herakles, is said to have slain a large and powerful lion on Mount Olympus without weapons (Pausanias, vi. 5).

but he told not, etc. An interpolation of the reviser of the narrative, based upon *וְלֹא*^{9b.16b}, and necessitated by the insertion of the words 'his father and his mother' in *וְלֹא*⁵. If Samson's parents were with him on the journey, it would be natural (apart from this statement) to suppose that they would hear of the incident, even if they did not witness it.

8. and he returned after a while, etc. Omitting the words 'to take her' as a later addition, the reference naturally is to Samson's return to Šor'ah after his visit to Timnah (cf. p. 354). The phrase מִיָּמִים 'after a while' is used in 11⁴, 15¹ of an indeterminate period, and, as the latter reference proves, can be used of quite a short period as well as of a long one (often, specifically, a year; cf. references in BDB. s.v. יוֹם, 6c).

* Mo. is not justified in stating that 'he tore the lion limb from limb.' Had he done this, there would not have been much of the carcase left for the bees to build in.

‡ Jos. (*Ant.* v. viii. 5) is possibly influenced by the Herakles-myth when he states that Samson strangled the lion (ἀγχεῖ τὰς χερσὶ).

behold, there was a swarm of bees in the body of the lion, and

there was a swarm of bees, etc. Bees will not build their combs in putrefying matter; but probably we are to picture the carcass as reduced to little more than a skeleton by jackals, vultures, or ants, and dried by the heat of the sun (cf. Post in *DB.* i. p. 264 a); or, as Mo. suggests, 'the body dried up, the skin and shrivelled flesh adhering to the ribs, the belly hollow.' It is true that the few days (presumably) before Samson's return from Timnah would hardly suffice for the building of combs and the gathering of a considerable store of honey; but clearly we cannot press the details of the narrative. Herodotus' story of the head of Onesilus, which, when an empty skull, was occupied by a swarm of bees which filled it with a honeycomb (*Hist.* v. 114) has often been compared by commentators.

An alternative theory is that we have here an instance of the widely spread ancient belief that bees were generated from putrefying animal-matter (cf. references in Bochart, *Hierozoicon*, ii. p. 502; Sachs, *Beiträge zur Sprach- und Alterthumsforschung*, i. p. 154; ii. pp. 92 f.); the origin of which has been supposed to be due to the fact that the drone-fly, *Eristalis tenax*, which is easily mistaken for a bee by those who are not entomologists, may have been observed to spend its larval stage within the carcasses of large animals.* This view,

* Cf. especially the monograph of Osten Sacken, *On the oxen-born bees of the Ancients* (1894). The difficulty which seems to lie in the way of regarding *Eristalis* as the supposed 'bee' which was generated from the carcasses of cattle is that the larva of this fly is *aquatic*, thriving in all kinds of liquid filth, but not in the solid tissues of a carcass. The body of a dead animal, such as Samson's lion, would speedily become infested with carrion-feeding larvae, such as those of *Calliphora* (the blue-bottle fly) and *Lucilia* (the green-bottle fly) which bear no resemblance to bees; but only by *Eristalis* if it happened to be lying in a pool of water (as was the case with the sheep, which seems to be the only certified instance known to Sacken in which this fly has actually been observed hovering over, or settling on, a carcass), or if the process of putrefaction had led to liquefaction of the viscera. It is worthy of notice, however, that the directions given by Virgil (*Georg.* iv. 295 ff.) for the production of bees from the carcass of a bullock, according to the Egyptian method—the bruising of the body while the skin remains intact and the apertures of the nose and mouth are carefully stopped—seem to be aimed at producing a fluid condition of the interior ('solvuntur viscera,' l. 302) after the lapse of the period during which the carcass is kept closed up in a narrow chamber; and such a condition would be favourable to the production of *Eristalis*, supposing that the fly could deposit its eggs in such a way that the larva could reach this internal fluid (e.g. if the skin of the bullock eventually burst). As a matter of fact, when, as Virgil goes on to relate, Aristaeus, who was the first to learn the secret, used this method—or something like it—to renew his stock of bees, and was successful, we are told (ll. 554 ff.) that

'Hic vero subitum ac dictu mirabile monstrum
Aspiciunt, liquefacta boum per viscera toto
Stridere apes utero et ruptis effervere costis.'

'Bees' thus produced may very well have been *Eristalis*.

honey. 9. And he scraped it out into his palms, and went on, eating as he went. And he came to his father and his mother, and gave to them, and they did eat: but he told them not that it was out of the body of the lion that he had scraped the honey. 10. And ^{Gl.} his father J¹ went down unto the woman, and ^{Gl.} Samson J¹ made there a feast, for so were the young men

while accounting for the (supposed) bees, would not explain the *honey* in the carcase; yet, once given the existence of such a belief as to the origin of bees, the story that honey was actually derived from such a source might easily follow.* It should be remarked, however, that the ancient theory connected bees specifically with the carcasses of *oxen* (whence it is termed *βουγολία*), just as it traced the origin of wasps to the carcasses of horses, etc.; and we nowhere find any suggestion that bees were generated from the bodies of other animals, *e.g.* lions.

On the theory that the story of the lion and the honey has a solar-mythological origin, cf. *Addit. note*, p. 405.

9. *he scraped it out.* The verb *rādhā*, which only occurs in this passage in the O.T., is used in post-Biblical Heb. of *extracting* or *scraping out* bread from an oven (if, for instance, it adheres to the oven in baking).

And he came, etc. According to Jos. he took three honeycombs from the breast of the lion, and gave them, not to his parents, but to the damsel at Timnah, together with the rest of the presents which he had brought for her. This alteration may be due to the difficulty noticed on p. 354, viz. that, as the text stands, he was on his way to *Timnah*, and his parents were not with him.

10. *And his father . . . feast.* Originally, 'And Samson went down unto the woman, and he made there a feast.' Cf. the discussion on p. 354.

a feast. *Ex*, *S*^P 'a seven days' feast' is probably based upon *vv.* 12.17. Had there been anything unusual about the length of the festivities we should have expected it to have been specified in this verse; but seven days seems to have been the customary period in ancient times (cf. Gen. 29²⁷ E, Tob. 11¹⁹), and is still customary at the present day among the Syrian peasantry (cf. Wetzstein, *Zeitschrift für Ethnologie*, 1873, pp. 287 ff.); so the duration of the feast did not call for specification.

for so were the young men, etc. The statement implies that the

* Such a process of legendary accretion is aptly illustrated by Osten Sacken (*op. cit.* pp. 18 f.) by a quotation from Massoudi (died A.D. 955 in Cairo) in his *Golden Meadows* (translated by Barbier de Meynard and Pavet de Courteille, Paris, 1861). Massoudi 'relates a conversation which took place in Arabia, and of which this is a fragment: "Had the bees which produced this honey deposited

wont to do. 11. ^{Gl.} And because they ¹feared¹ him, they ¹took thirty companions, and they remained with him. 12. And Samson said to them, 'Prithee let me propound a riddle to you: if ye can tell it me during the seven days of the feast,

narrator is referring to a custom which was obsolete, or at any rate unusual, in his own day. This can hardly refer to the giving of a feast, or to its duration—supposing that to have been originally specified (cf. *note* preceding). What calls for note is the fact that the feast was given 'there,' *i.e.* at the house of the bride's parents, instead of at the bridegroom's house (so Mo.).

11. *because they feared him.* Reading בִּירְאַתָּם אֹתוֹ, or בִּיר, with ^{Gr^{al}}, ^{U^l}, ^{S^h}, Jos. (διὰ δέος τῆς ἰσχύος τοῦ νεανίσκου), and many moderns. יִרְאַה is here, as frequently, Infin. Constr.; cf. G-K. § 45 *d*. וַיֵּדְאוּ אֹתוֹ בִּירְאַתָּם 'when they saw him,' is explained by Black, Mo. 'saw what a dangerous-looking fellow he was'; but surely, with all his coming and going to and fro, the Timnites must have been familiar enough with his appearance.

On the reasons for which we assume that *v.*^{11a} is the reviser's addition, and that *v.*^{11b} originally opened with sing. וַיִּקַּח 'and he (*i.e.* Samson) took,' cf. p. 355.

thirty companions. The υἱοὶ τοῦ νυμφῶνος, Matt. 9¹⁵, Mark 2¹⁹, Lu. 5³⁴. In the modern Syrian peasant-marriage they are termed in Ar. *ṣabāb al-'aris*, 'the bridegroom's young men,' and their number varies in accordance with the scale of the marriage-festivities, part of the cost of which they commonly defray. Probably the custom of choosing a large number of such companions dates from very early times, when the condition of the country was unsettled, and it was necessary to provide a bodyguard during the marriage-festival. Cf. Wetzstein, *op. cit.* p. 288, *n*².

12. *a riddle.* Heb. *ḥîdhā*, only in this chapter denoting a trivial conundrum invented to pose ingenuity. The term is used in 1 Kgs. 10¹ of the 'hard questions' with which the Queen of Sheba tested Solomon's wisdom; while in Ps. 49⁴ (⁵) 78², Prov. 1⁶ (R.V. in each case 'dark saying') it denotes a perplexing question of ethics or morals.

it in the body of a large animal?" asked Viad. The surveyor answered: "Hearing that there was a hive near the sea-coast, I sent people to gather the honey. They told me that they found at that place a heap of bones, more or less rotten, in the cavity of which bees had deposited the honey that they brought with them." Sacken's comment is: 'This case, as a parallel to Samson's bees, is a remarkable instance of the force of imaginative association in the human brain, and of the sameness of its illogical conclusion under similar circumstances.'

Gl. and find it out, J¹ I will give you thirty linen wrappers and thirty suits of festal apparel. 13. And if ye are not able to tell it me, *ye* shall give *me* thirty linen wrappers and thirty suits of festal apparel.' And they said to him, 'Propound thy riddle, and let us hear it.' 14. And he said to them,

'From the eater there came forth something to eat,
And from something strong came forth something sweet.'

and find it out. Heb. וּמְצֹאתָ, omitted by some MSS. of G and by L^L, and marked by an asterisk in S^b, stands in U in a most awkward position, and must be regarded (with Sta., Mo., etc.) as a gloss from v. 18^b. Had the expression formed a genuine part of the text, we should have expected 'If ye can find it out and tell it, etc.'

linen wrappers. Heb. *sādhîn* (Greek σινδών) was a large rectangular piece of fine linen, which might be worn either as a garment or as a sleeping wrap (cf. Mark 14^{51 f.}). It is mentioned in Isa. 3²³ among other articles of female attire; and in Prov. 31²⁴ as made by the capable woman, and sold by her to 'the Canaanites,' *i.e.* the Phœnician traders—a reference which perhaps gives us a hint as to the origin of the term in Greek. The word is well diffused in the other Semitic languages (Bab., Ar., Syr.), and is used in the Talmud of a curtain, wrapper, or shroud (cf. references given by Mo.; and for the last usage, cf. Matt. 27⁵⁹, Mark 15⁴⁶, Luke 23⁶³).

suits of festal apparel. Heb. *h'aliphôth b'ghādhîm*, as in 2 Kgs. 5^{6, 22, 23}; similarly, *h'aliphôth s'mālôth* twice in Gen. 45²² E. Here *h'aliphôth* is probably to be explained as meaning 'changes' (cf. the use of the word in Job 10¹⁷, 14¹⁴, Ps. 55¹⁹, U²⁰); 'changes of raiment' denoting the best garments, which were only worn on festal occasions, in distinction from the everyday dress. Cf. the use of the cognate verb of *changing* the raiment in Gen. 35² E, הִחֲלִיפוּ שְׂמֹלֶתֵיכֶם. Less probable is connexion (suggested by Delitzsch, *Assyr. Studien*, p. 112) with Assyr. *halûpu* 'to cover,' whence are derived *nahlapu*, *nahlaptu*, *nahluptu*, all meaning *garment* or *covering*; since, on this explanation, we have to regard *b'ghādhîm* (or *s'mālôth*) as standing in explanatory apposition to *h'aliphôth*—a term which, *ex hypothesi*, bears the same meaning.

14. A 3-beat distich:—

mēhā'ôkhêl yāšā mā'akhāl
ūmē'az yāšā māthôk.

And from something strong, etc. Heb. עַז and מְתוֹק, both of which are adjectives, are used indefinitely without the Article; hence the rendering adopted above rather than that of R.V., 'and out of the strong came forth sweetness.'

And they were not able to tell the riddle ^{Gl} for 'six' days. 15. And on the seventh day J¹ they said to Samson's wife, 'Beguile thy husband, that he may tell us the riddle, lest we burn thee

עו has normally the meaning 'strong' or 'fierce.' Bochart, however (*Hierozyicon*, ii. p. 523), remarks that we should expect a paradox in the contrast between עו and מתוק, just as we have one between האכל 'the eater,' and מאכל 'something to eat,' in the first line. He thinks that עו may have a range of meaning similar to the Latin *acer* (which may mean either 'pungent,' or 'fierce'), comparing Ar. *mirra* 'strength,' and *marîr* 'strong,' from the verb *marra*, 'to be bitter' (cf., however, *footnote*, p. 380); and so he renders 'ab acri prodiit dulce,' and in v.¹⁸, 'Quid dulcius est melle? Et quid acrius est leone?'

The need for such a paradox was felt by S^p, which renders סמך מן־הדבר נסמך 'and from something *bitter*, etc.' It might be brought out in English if we were justified in representing עו by some such rendering as 'something *biting*,' where the reference would of course really be to the biting (*i.e. ferocious*) lion, but the contrast with 'sweet' would immediately suggest that it referred to something of a biting (*i.e. acrid*) taste: cf. the word-play in *ch.* 15¹⁶. The difficulty is that we possess no evidence that עו was used in the sense *acrid* or *bitter*; yet the question is not set at rest by Mo. when he remarks that there is in reality only one antithesis in the couplet (that between 'eater' and 'something to eat'), and that it is unnecessary therefore to make out a perfect antithesis between the adjectives independently. The rhythmical parallelism of the clauses favours such an antithesis, in sense as well as in form.*

for six days. Reading עֶשְׂרֵת in place of חֲמִשָּׁה 'three,' which cannot stand alongside of v.¹⁵ 'and on the seventh day.' So Doorn., Mo. The alternative correction is to read 'the fourth day' in v.¹⁵; and this has the support of E^{BA}, L^L, S^p, and most moderns.

* It is, at any rate, a moot point whether 'az may not have been used in the sense *harsh* or *acrid*, and applied to a flavour. The adj. *mar* 'bitter,' which is commonly used of a flavour, denotes a *fierce* disposition in *ch.* 18²⁵, 2 Sam. 17⁸, Hab. 1⁶; and, conversely, it may be inferred that 'az, which is commonly used of a *fierce* disposition, may also have denoted a *bitter* flavour. The Ar. parallel offered by Bochart in illustration of connexion between the meanings *strong* and *bitter* is questionable; yet it seems likely that a similar range of meaning may have been possessed by the Heb. root קָשָׁה. This has the sense 'to be hard, severe, fierce' (so BDB.); and, in the adjectival form *kāšē*, is used in parallelism to 'az as a synonym in Isa. 19⁴ ('*harsh* lord . . . *fierce* king'). The root קָשָׁה from which is derived *kāššū'im* 'cucumbers,' was plausibly connected by the Jews with קָשָׁה; cf. *Aboda zara*, fol. xi. 1, 'Why are they called *kāššū'im*? Because they are as *harsh* (*kāšīn*) to the human body as a sword.' Similarly, Pliny (*Hist. Nat.* xix. 5) says of cucumbers, 'vivunt hausti in stomacho in posterum diem,

and thy father's house with fire: was it to beggar us that ye invited us ^{hither}?’ 16. And Samson's wife wept upon him, and said, ‘Thou surely hatest me, and dost not love me: thou

Adopting either emendation, it is impossible, however, to square the note of time with the narrative which follows, according to which, when the Philistines have persuaded Samson's bride to extract the answer of the riddle from her husband, she weeps over him the whole seven days during which the feast lasts (*v.*¹⁷). Clearly, then, the Philistines can have made no serious attempt to solve the riddle for themselves, but must have had recourse to the woman on the day when Samson propounded it to them. The note of time in *vv.*^{14, 15} must be due to a later hand, who, overlooking *v.*¹⁷, supposed that the Philistines would have spent at least part of the time in attempting to discover the answer themselves; and we may conclude (with *Sta.*) that the narrative originally ran ‘and they were not able to tell the riddle; and they said to Samson's wife, etc.’

15. *was it to beggar us.* Heb. הֲלִירִשְׁנִי. For the verb יִרֵשׁ in this sense, cf. the use of the Niph'al in Gen. 45¹¹ E, Prov. 20¹³, 23²¹, 30⁹. On the exceptional retention of י in the Infin. Constr. Kāl, cf. G-K. § 69 *m.* There is a variant vocalization הֲלִירִשְׁנִי which apparently treats the form as Pi'el.

hither. Reading הֵלֵם with five Heb. MSS., 𐤇, and moderns. הֵלֵם ‘or not’ is irregular in construction; לֹא אִם being usual in the second half of a disjunctive question: cf. G-K. § 150 *g, n*¹.

16. *surely.* כִּן has here an asseverative force, as in Gen. 20¹¹,

nec perfici queunt in cibis’ (both references cited by Ges., *Thes.* p. 1241 *b*). Both these passages refer to indigestibility rather than to flavour; yet there can be little doubt that there was a close connexion in thought between the indigestibility of the cucumber and its *bitter* or *acid* taste when eaten with the rind or in an over-ripe state. We may compare the incident related in 2 Kgs. 4³⁸⁻⁴¹, where, when wild gourds (probably *Citrullus colocynthis*, L., allied to the cucumber, the pulp of which is ‘intensely bitter,’ and forms ‘a drastic cathartic, and, in quantities, an irritant poison’; cf. Post in *DB.* ii. p. 250) have been accidentally included in the stew, the fact that ‘there is death in the pot’ is recognized by the *flavour*.

It may be added that this connexion between the Heb. roots קָטַע and קָשָׂא is made in full consciousness of the fact that in the former the *š* runs through Heb., Ar., and Aram., whereas in the latter, Heb. *š* = Ar. *ṣ* = Aram. *ṣ* (for *t* after *ḵ*). Such a difference does not imply original diversity of root; but may represent merely a slight differentiation in sound for the sake of marking a variation in the shade of meaning. Cf. the way in which *e.g.* the Heb. *ḵāṣā* appears in Ar. as *ḵaṣa* ‘to cut’ in the literal sense, but as *ḵaḍa* when denoting a metaphorical ‘cutting,’ i.e. ‘deciding.’

hast propounded the riddle to the sons of my people, and thou hast not told it to *me*.' And he said to her, 'Behold, I have not told it to my father or my mother, and should I tell it to *thee*?' 17. And she wept upon him the seven days during which the feast lasted; and on the seventh day he told her, because she pressed him sorely; and she told the riddle to the sons of her people. 18. And the men of the city said to him on the seventh day, before he entered 'the bridal chamber',

'What is sweeter than honey?
And what is stronger than a lion?'

Deut. 4⁶, 1 Kgs. 21²⁵, Ps. 32⁶. The restrictive meaning '*only*' is clearly not so suitable.

18. *before he entered the bridal chamber.* Reading הַחֲרָה as the last word in place of הַחֲרָה 'before the sun went down,' where the word for 'sun' is very uncommon (cf. *ch.* 1³⁵ *note*) and of anomalous form (with the old accusative ending). הַחֲרָה (cf. *ch.* 15^{1a}), first suggested by Sta., has been generally adopted; and is supported by *S*^p, in which the inexplicable לִסְסֹל must be an error for לִסְסֹל 'inner chamber' (חֲרָה is so rendered in *ch.* 16^{9.12}, 1 Kgs. 20⁵⁰, *al*; cf. references in Payne Smith, *Thesaurus Syriacus*, s.v. col. 50).* 'The Timnathites waited till the last moment, to heighten their triumph and his discomfiture' (Mo.).

It would appear from this passage that the marriage was not to have been consummated until the end of the seventh day of the festival; and this also seems to follow from *v.*²⁰, where, after Samson has rushed off in a rage, the bride is at once given in marriage to his 'chief friend,' clearly in order that she may escape the disgrace and ridicule which would have fallen upon her if the marriage had not been completed (cf. her father's words in 15²); but otherwise (we may presume) an unnecessary step to take. Such a custom of deferring the completion of the marriage is, however (apart from this instance), unknown to us. Jacob consummates his marriage with Le'ah upon the first of the seven days (Gen. 29²¹⁻²³ E); and the same practice is observed in the modern Syrian marriage (cf. Wetzstein, *op. cit.*)

What is sweeter, etc. A rhythmical 2-beat distich:—

mam-māthōk midd⁶bhās
šime-áz me^{7a}rl.

* The editor's attention was called to this point by Prof. Bevan.

And he said to them,

‘If ye had not plowed with this heifer of mine,
Ye would not have found out this riddle of mine.’

19. ^{Gl}. And the spirit of Yahweh rushed upon him, and he went down to Ashkelon, and smote thirty men ‘from thence’, and

If ye had not, etc. The 3-beat distich is rhymed upon the suffix of the 1st pers. sing. :—

*lûlē h'raštém b'eghlāthî
lô m'sāthém hîdāthî.*

The rendering ‘of mine’ for ‘my’ attempts to reproduce this in English. Cf. the similar rhyme in *ch.* 16 ²¹.

19. *and smote . . . riddle.* Reading מִשֶׁם for מֵהֶם, הִלְפֹתָם for הִלְפֹתָם, and omitting הִלְפֹתָם after וַיֵּתֶן, with \mathfrak{E}^{AL} , \mathfrak{S}^{h} , καὶ ἔπαισεν ἐκείθεν τριάκοντα ἄνδρας, καὶ ἔλαβε τὰς στολὰς αὐτῶν καὶ ἔδωκε τοῖς ἐπαγγέλαισι τὸ πρόβλημα. Cf. also F. \mathfrak{H} מֵהֶם ‘of them,’ *i.e.* of the Ashkelonites, *as assumed* from the preceding ‘he went down to Ashkelon,’ is very awkward; while הִלְפֹתָם ‘their spoil’ (lit. ‘what was *stripped off* them’; cf. 2 Sam. 2 ²¹) is so similar to הִלְפֹתָם that it is natural to regard it as a corruption, which has led, in turn, to the addition of הִלְפֹתָם after וַיֵּתֶן (‘he gave—not the spoil as a whole, but—the festal attire’). Adopting our emendation, the use of וַיֵּתֶן without expressed object—this being inferred from preceding הִלְפֹתָם—is very idiomatic; cf., with the same verb, Gen. 18 ^{7,8}, 20 ¹⁴, 21 ¹⁴, *al.*

Sta. and Doorn. are probably right in regarding the whole of *v.* ^{19a} as a later addition to the narrative. We need not press the improbability of Samson’s actually rushing off in his frenzy to a seaside town some twenty-three miles distant (cf. *ch.* 16 ³, where he carries the gates of Gaza to the top of a hill to the east of Hebron some thirty-eight miles off), getting exactly what he wanted (the suits of festal attire) from the bodies of the slaughtered Philistines, returning to pay his wager (the same night?), and then departing, still in angry mood, to his father’s house. Nor is the fact that nothing results from his raid on Ashkelon in the way of reprisal necessarily fatal to the originality of the verse. It is obvious, however, that the statement of *v.* ^{19b} ‘and his anger was kindled, etc.’ is curiously weak and inappropriate when following after *v.* ^{19a} (the superhuman access of frenzy denoted by וַיִּחַזַּק; cf. *v.* ⁶ *note*); but, on the rejection of *v.* ^{19a}, it forms a natural description of his rage at the underhand trick by which the Philistines had discovered the solution of the riddle. We assume, then, that the original story made Samson depart home

took 'their suits of festal apparel', and gave them [] to the tellers of the riddle. J¹ And his anger was kindled, and he went up to his father's house. 20. And Samson's wife was given to his companion, whom he had made his chief friend.

15. 1. After a time, however, in the days of wheat-harvest, Samson visited his wife with a kid of the goats; and he said, 'I will go in unto my wife into the bridal chamber.' But her father would not suffer him to go in. 2. And her father said, 'I verily thought that thou didst *hate* her, so I gave her to thy companion: is not her younger sister fairer than she? prithee

in anger without paying the wager, which had not been fairly won; and that the addition is due to an interpolator who thought that the story would be improved if he were represented as paying, and at the same time inflicting damage on his foes.

20. *And Samson's wife, etc.* Cf. note on v.¹⁸.

his companion. The φίλος τοῦ νυμφίου (Jo. 3²⁹), or, as we should say, *best man*; called in the modern Syrian wedding *wazīr*, i.e. vizier or *chargé d'affaires* (from *wazara* 'to bear a burden') to the king, as the bridegroom is termed during the seven days' festival (Wetzstein, *op. cit.*).

15. 1. *in the days of wheat-harvest.* This varies in Palestine in accordance with the elevation, the harvest of the Jordan valley being considerably earlier than that of the hill-country. In the district of Timnah wheat-harvest falls (according to La.) from mid-May to mid-June. The season is mentioned in view of the incident of vv.^{4,5}.

a kid of the goats. Cf. Gen. 38^{17 ff.} The gift seems to have been of the kind which was called *ṣadīk* among the ancient Arabians; and was probably made to the *ṣadīka*-wife on each occasion of such a visit. Cf. Robertson Smith, *Kinship*,² pp. 83, 93.

2. *I verily thought.* Heb. אָמַר אֶמְרָתִי, lit. 'Saying I said (to myself).' The force of the Infin. Absolute is to emphasize the mental process by which he arrived at his conclusion—much as we might say in colloquial English, 'What I *thought* was, etc.' Cf. Davidson, *Syntax*, § 86 a.

that thou didst hate her. Here the force of the Infin. Absolute in the phrase אָנֹכִי שָׂנְאָהּ can only be expressed by italicizing the verb; unless, with Mo., we render 'that thou didst certainly hate her.' R.V. 'that thou hadst utterly hated her' is very erroneous; the emphasis being not on the quality of the feeling denoted by the verb (*bitter* hatred), but upon the *accurate definition* of the feeling (hatred, and not love). A similar error is perpetrated by R.V. in v.¹³ (cf. *note*).

let her be thine instead of her.' 3. And Samson said to them, 'I am quits this time with the Philistines; for I am about to do them a mischief.' 4. And Samson went and caught three

3. *said to them.* \mathfrak{C}^{AL} , \mathfrak{S}^{h} , \mathfrak{L}^{L} , \mathfrak{F} read 'said to him.' This, however, is probably an alteration induced by the fact that the woman's father only is speaking in *v.*². In favour of \mathfrak{L} cf. *v.*⁷. As Mo. remarks, 'It is not necessary to suppose that in either case the words were spoken in their hearing; the threat was addressed to them.'

I am quits, etc. נִקְיָתִי is a Perfect of certitude. As the brilliant idea strikes him which, when put into action, will, he forsees, *wipe off all scores* which he owes to the Philistines, he speaks of it as an accomplished fact. Cf. Driver, *Tenses*, § 13.

The verb *nikkā*, as here used, followed by *min*, means *freed from obligation towards* (the obligation in this case being, of course, that of *taking vengeance*); and it would be best expressed by the old phrase '*quit of*,' as used *e.g.* in Shakespeare, *Coriolanus*, IV. v. 89:—

'To be full quit of these my banishers,
Stand I before thee here.'

The phrase is used (of gaining freedom from obligation of *service*) in Num. 32²², where Moses, in impressing upon the two and a half tribes that they can only gain the right to the territory conquered by all Israel east of Jordan if they in their turn will cross the Jordan with the other tribes, and help them to conquer the territory to the west, adds that, when this has been accomplished, 'afterward ye shall return, *and shall be quit of Yahweh and of Israel*' (וְהָיִיתֶם נָקִים מִיְהוָה וּמִיִּשְׂרָאֵל).

This sense is expressed by R.V. *marg.* and by La. R.V. *text* follows the Versions, Jewish commentators, and nearly all moderns in rendering, 'This time shall I be blameless in regard of the Philistines, when I do them a mischief'—an interpretation which is bound up with the rendering of 'כִּי-עָשָׂה אֲנִי וְג' as a temporal clause, which can scarcely be justified (we should surely expect כִּי עָשִׂיתִי 'when I shall have done,' etc). עָשָׂה is to be explained as *Futurum instans*; cf. the rendering given above.

4. *three hundred foxes.* Since the fox is a solitary animal, it has been supposed by many that the reference is to *jackals*, which live together in large packs, and could be caught in numbers without great difficulty. It is, however, a very doubtful expedient to attempt to explain Samson's feats by depriving them of the element of the marvellous.

hundred foxes, and took torches and turned tail to tail, and put a torch between every two tails in the midst. 5. And he set fire to the torches, and turned them loose into 'the fields' of the Philistines, and burned both shocks and standing corn and vineyards <and> olives. 6. And the Philistines said, 'Who hath done this?' And they said, 'Samson, the son-in-law of the Timnite; because he took his wife, and gave her to his companion.' Then the Philistines went up, and burned her and her father's <house> with fire. 7. And Samson said to them, 'If ye do after this manner, surely I will be avenged of you, and after that I will cease.' 8. And he smote them leg upon thigh with a

took torches, etc. Commentators generally have noted the remarkable resemblance of the action here ascribed to Samson to the custom which was observed at Rome during the festival of Ceres, when foxes with burning torches attached to their brushes were hunted through the Circus (Ovid, *Fasti*, iv. 679 ff.). This point is discussed in *Addit. note*, pp. 393 f.

5. *into the fields.* Reading בְּשָׂדוֹת with Bu., in place of בְּקִמּוֹת 'into the standing corn,' which occurs only here in the plur., and is not very suitable before the following statement 'and burned both shocks and standing corn' (קָמָה sing.).

and vineyards and olives. Reading וְעֵדֶר-כֶּרֶם וְזֵית with G, E, in place of וְעֵדֶר-כֶּרֶם וְזֵית (rendered by R.V. 'and also the olive-yards'; as though כֶּרֶם—elsewhere always *vineyard*—here meant 'yard' or 'plantation' of olives). Vineyards and olives are thus coupled in Ex. 23¹¹ E, Deut. 6¹¹, 28^{39,40}, Josh. 24¹³ E, 1 Sam. 8¹⁴, 2 Kgs. 5²⁶, Neh. 5¹¹, 9²⁵. S^p, ט וְעֵדֶר-כֶּרֶם וְזֵית. There is no reason to suppose, with Mo., that the words 'are probably an addition by a later hand, exaggerating the mischief.'

6. *and her father's house.* Reading וְאֶת-בֵּית אָבִיהָ with many MSS. of H, G^{AL}, S^b, S^p, Mo., Bu., etc. (cf. *ch.* 14¹⁵), in place of וְאֶת-אָבִיהָ 'and her father.'

7. *surely I will be avenged of you.* Heb. בִּי אִם-נִקְמָתִי בָכֶם. The particles כִּי אִם are closely connected, with a strong asseverative force, and נִקְמָתִי is a Perfect of certitude: cf. the precisely similar construction in 2 Kgs. 5²⁰ (*note* on construction in *NHTK.*), Jer. 51¹⁴. כִּי אִם is so used, followed by the *Imperfect*, in 1 Sam. 26¹⁰ (*note* in *NHTS.*), 2 Sam. 15²¹ *Kt.*; cf. also 1 Sam. 21⁶, Ru. 3¹² *Kt.*

8. *leg upon thigh.* Heb. *śōp* denotes the *leg* generally, or specifi-

great slaughter, and went down, and abode in a cleft of the crag 'Eṭam.

9. Then the Philistines went up, and encamped in Judah, and

cally the *shank* from the knee downwards, as distinct from the thigh; while *yārēkh* is used of the *thigh*, or rather, the whole of the upper part of the leg from the hip down to the knee (cf. Ar. *warik* 'hip' or 'buttock'). The only plausible explanation of the difficult expression *šōk 'al yārēkh* is that it is a wrestler's term, akin to the English *cross-buttock*, which is thus described in the *Sporting Magazine*, xxx. (1808), 247 A:—'A cross-buttock in pugilism is, when the party, advancing his right leg and thigh, closes with his antagonist, and catching him with his right arm, or giving a round blow, throws him over his right hip, upon his head.' Cf. D'Urfey, *Collin's Walk* (1690), ii. p. 74:—

'When th' hardy Major, skill'd in Wars,
To make quick end of fight prepares,
By strength o'er buttock cross to hawl him,
And with a trip i' th' Inturn maul him.'

Castle (*Lexicon heptaglotton*, 3716) and Le Clerc connected the phrase with wrestling; but supposed that the *leg* (*šōk*) of the victor was impacted *against the thigh* ('*al yārēkh*) of the vanquished. To Smythe Palmer (p. 225) belongs the credit of connecting the phrase with a cross-buttock, in view of the cylinder-seals in which Gilgamesh is figured as wrestling with an antagonist, and throwing him across his own thigh (cf. Plate II, fig. 5).

The Versions were evidently puzzled by the phrase. *℣* renders literally *κνήμην ἐπὶ μηρόν*; *℥* 'ita ut stupentes suram femori imponent'; *ס"י* *מֵעַל מִתְּסֵס סִבְמָן לִבְתֵּס* 'from their legs even to their loins'; *פ"י* *פֶּרְשִׁין עִם רַגְלָאִין* 'horsemen with footmen.* Other attempted explanations—such as those of Kimchi, 'shank over thigh,' as they fell in precipitate flight (or, as we might say, 'heels over head'), and Ges., *Thes.*, 'in frusta eos concidit ita ut membra eorum, crura et femora, alia super aliis disjecta jacerent'—merely serve to illustrate the lengths to which perverted ingenuity can go.

the crag 'Eṭam. A city of Judah named 'Eṭam is mentioned in 2 Chr. 11⁶ as built by Rehoboam; and the order in which the name occurs, between Bethlehem and Tekoa, favours a site at or near the modern Urṭās, near which is a spring called 'Ain 'Aṭān: *SWP. Mem.*

* This rendering inverts the order of the phrase, *šōk* being interpreted of those who go on foot (cf. Ps. 147¹⁰); while the sense attributed to *yārēkh* may be gathered from the Ar. verb *waraka*, which (according to Kazimirski, *Dict. Ar.-Français*) may mean 'Appuyer un côté du corps sur le dos du cheval et voyager ainsi.'

spread themselves abroad in Lehi. 10. And the men of Judah said, 'Why have ye come up against us?' And they said, 'To bind Samson have we come up, to do to him as he hath done to us.' 11. Then three thousand men from Judah went down

iii. p. 43. This, however, is too far removed from the scene of Samson's exploits. Schick, *ZDPV.* x. (1887), pp. 143 f., and Hanauer, *PEF. Qy. St.*, 1896, pp. 162 ff., have plausibly suggested the rock called 'Arâḵ Isma'in, near Ḥirbet Marmîtâ, some two and a half miles east-south-east of Şor'ah, in which there is a cave which exactly suits the description of our narrative. 'The cave is approached by descending through a crack or fissure in the very edge of the cliffs overhanging the chasm of wâdy Isma'in. The crack is scarcely wide enough to allow one person to squeeze through at a time. It leads down to the topmost of a long series of rudimentary steps, or small artificial foot-ledges, cut in the face of the cliff, and descending to a narrow rock terrace running along the front of the cave, and between it and the fragments of massive wall (belonging to an ancient Christian cœnobium)': Hanauer, *op. cit.*, p. 163.

9. and spread themselves abroad. Heb. וַיִּנְטְשׁוּ again in this sense in 2 Sam. 5^{18,22}.

in Lehi. As the narrator is about to record the incident from which, according to his tradition, the place obtained its name of *Leḥî* 'jawbone,' he uses the name here and in *v.*¹⁴ proleptically. Probably the name was originally given to some hill or ridge on account of its resemblance to a jawbone. Commentators generally compare the Greek *ὄρον γνάθος*—the name of a promontory at the southern end of Laconia; cf. Strabo, VIII., v. 1. Schick (*ZDPV.* x. pp. 152 f.) proposes to identify Lehi with Ḥirbet eṣ-Şiyyâḡ, a hill with ruins a little south-west of 'Arâḵ Isma'in. Ḥirbet eṣ-Şiyyâḡ means 'ruin of the goldsmiths'; but such a name is very strange in this locality, and the view is plausible that Şiyyâḡ really represents the Greek *σιαγών*, which is the rendering of Lehi employed by 'A., Σ., Jos. (*Ant.* v. viii. 8 f.), and by *Gr* in *v.*¹⁴ ff.

Lehi is mentioned again in 2 Sam. 23¹¹ (emended text*) as the scene of an exploit of Shammah, the son of Agee, one of David's heroes, in withstanding and smiting a large number of Philistines single-handed. On the suspicious similarity between the deeds of Samson, Shammah, and Shamgar, cf. p. 75.

11. three thousand men. The huge numbers here and in *v.*¹⁶, *ch.*

* Reading 'Now the Philistines were gathered together 'to Lehi' (i.e. לְלֵחִי) for the very obscure לְלֵחִי of *Gr*, after *Gr* *ἐπὶ σιαγῶνα*). This emendation is generally accepted.

unto the cleft of the crag 'Eṭam, and said to Samson, 'Knowest thou not that the Philistines are ruling over us? What then is this that thou hast done to us?' And he said to them, 'As they did to me, so have I done to them.' 12. And they said to him, 'To bind thee are we come down, to deliver thee into the hand of the Philistines.' And Samson said to them, 'Swear to me that ye will not fall upon me yourselves.' 13. And they spake to him, saying, 'Nay, but we will *bind* thee, and deliver thee into their hand; but we will not *slay* thee.' So they bound him with two new ropes, and brought him up from the crag. 14. As soon as he came unto Leḥi, the Philistines came shouting to meet him: and the spirit of Yahweh rushed upon him, and the ropes that were upon his arms became like flax that hath been burnt with fire, and his bonds melted from off his hands. 15. And he found a fresh jawbone of an ass, and put forth his hand, and took it, and smote therewith a thousand men. 16. And Samson said,

'With the red ass's jawbone 'I have reddened them right red';
With the red ass's jawbone I have smitten a thousand men.'

16²⁷ are of a piece with the marvellous character of the narrative as a whole.

13. *Nay, but we will bind thee, etc.* The use of the Infinitive Absolute here—lit. 'binding we will bind thee . . . but slaying we will not slay thee'—is intended to emphasize what they *will* do, in distinction from what they will *not* do; and can only be rightly reproduced in English by the use of italics. R.V. 'we will bind thee fast, etc.' is erroneous in supposing the emphasis to be on the *security* of the binding. Cf. the similar error in *v.*² (*note* on 'that thou didst *hate* her').

14. *melted.* Heb. וַיִּמְסוּ, a graphic description of the powerlessness of the bonds as against Samson's strength.

15. *a fresh jawbone.* Heb. מְרִיחָה, lit. 'moist,' explains how the jawbone was suitable for use as a weapon. Had it been old and dry it would have been too brittle.

16. *with the red ass's jawbone, etc.* A 4-beat distich:—

Bil'ḥī haḥ^amôr ḥāmôr ḥimmartim
Bil'ḥī haḥ^amôr ḥikkēthi 'eleph²îš.

We vocalize the first stichos בִּלְחִי הַחֲמֹר חֲמֹר חִמַּרְתִּים. There is a play upon the word for *ass* (*ḥ^amôr*), which means lit. the *reddish*-

coloured animal, and the verb (*ḥāmar*; in Pī'ēl, *ḥimmēr*) applied to the slaughtered Philistines, which is explained from Ar. *ḥamara*, properly 'to be or to make red,' used e.g. of *skinning* a sheep so as to *make it appear red*, and in Conj. II. (the equivalent of the Heb. Pī'ēl) of *dyeing* a thing *red* (so Lane). Cf. the use of the P^eal'al in Heb. in Job. 16¹⁶, 'my face is reddened (*ḥ'marmērū*) from weeping.' The pun is suggested to Samson by the appearance of the blood-stained corpses.* As an alternative possibility, we might vocalize as Ḳal תַּמְרָתִּים, and regard the verb *ḥāmar* as a denominative from *ḥēmôr* with the meaning 'treat as an ass' (in this case, by *belabouring* them), a sense which is also possessed by *ḥamara* in Ar. Thus, if we were justified in coining (not for the first time †) a verb *to ass* in this sense, we might bring out the word-play by rendering:

'With the jawbone of an ass I have thoroughly assed them.'

This explanation is adopted by Levesque (*Revue Biblique*, 1900, pp. 89 ff.), who reproduces the assonance excellently by use of the French *rosse*=*a sorry jade* and the denominative verb *rosser*=*to beat or belabour violently*, properly, *to treat as a jade* (cf. Littré, *Dict. de la lang. Franç.*, 1761):—

‘Avec une mâchoire de rosse, je les ai bien rossés.’

So also La.

הִמְרוּתַיִם is rendered by A.V., R.V. ‘heaps upon heaps,’ with *marg.* Heb. ‘an heap, two heaps’ (cf. $\text{רָחַם רְחֵמַתַּיִם}$ *ch.* 5³⁰), upon the assumption that הִמְרוּ (though identical with the word for ‘ass’ preceding) has the same meaning as הֶמוֹר Hab. 3¹⁵ (text very suspicious), plur. הִמְרוֹיִם Ex. 8¹⁰ J; and this is the sense which was probably intended by the vocalization. עַל , however, treats the two words as Infin. Absol. and Finite verbs, $\epsilon\chi\alpha\lambda\epsilon\iota\phi\omega\nu \epsilon\xi\eta\lambda\epsilon\upsilon\sigma\alpha \alpha\upsilon\tau\omicron\upsilon\varsigma$; and the other Versions explain הִמְרוּתַיִם as a verbal form:— עַל ‘delevi eos,’ $\text{כִּפְסֵן כֶּסֶף מֵעוֹלָם}$, ‘I have heaped some of them in heaps,’ עַל $\text{רְמִיתֵנּוּ דְגוּרֵינוּ}$, ‘I have cast them in heaps.’

The view that we should read Infin. Absol. *Ḳal*, coupled with a Finite verb, either *Ḳal* or *Pi'el*, is adopted by most moderns; but very various meanings are assigned to the verb. J. D. Michaelis

* This explanation occurred to the present editor, and was adopted by him as given above, before he noticed that he had been anticipated by Zenner, *Zeitschr. für kath. Theol.*, 1888, p. 257, quoted and followed by Cheyne, *EB.* 2340.

‡ The verb *to ass*, in the sense 'to call an ass,' is quoted by the *New English Dictionary* from G. Harvey, *Pierces Supererogation* (1592), 57:—'He . . . bourdeth, girdeth, asseth the excellentest writers of whatsoever note that tickle not his wanton sense.'

17. And when he had finished speaking, he cast away the jawbone out of his hand; so that place was called Ramath-lehi. 18. And he was sore athirst, and called unto Yahweh, and said, 'Thou hast given this great victory by the hand of thy servant; and now, I must die of thirst, and fall into the hand of the uncircumcised.' 19. Then God clave the Mortar that is in Lehi, and there came water thereout; and when he had drunk, his spirit returned, and he revived: wherefore its name

(quoted by Ros.) connected the רָמַת rendering with Ar. *hamara* in the sense *to skin* or *shave*, and this explanation is adopted by Doorn. (followed by Bu. doubtfully, No., Kit.), 'I have thoroughly flayed or shaved them.' Mo. (followed by Bu. doubtfully, Cooke), 'I have heaped them up in heaps'— הִמְרִי —perhaps a casual denominative, invented for the paronomasia'; cf. רָמַת . It is a defect in these and other explanations, as compared with those given at the beginning of this *note*, that the play upon *h'môr* 'ass' is one of *sound* merely, apart from any connexion in *meaning*.

17. *Ramath-lehi*. Here *Râmāth* is explained by וַיִּשְׁלֶךְ 'be cast away,' as though derived from *rīmā* 'to cast or throw'—the name being taken to mean 'the throwing of the jawbone.' With such a derivation we should expect the form to be vocalized *R^emath*. *Râmāth* should be derived from the root *rām* 'to be high'; and there can be no doubt that the name really means 'the height of Lehi'; cf. the proper names רָמָה or הָרָמָה 'the height,' רָמַת הַמִּצְפָּה 'the height of the outlook-point,' etc. The story is based upon an unphilological interpretation of the name.

19. *Then God clave, etc.* The story probably embodies a trace of solar mythology: cf. *Addit. note*, p. 406.

the Mortar. Heb. *ham-makhtēš*—doubtless a circular depression in the rock or soil, of the appearance of a mortar, from the side of which the spring issued. There was a place called 'the Mortar' at Jerusalem: Zeph. 1¹¹.

that is in Lehi. Lehi is here, of course, the *place*, as is proved by the statement at the end of the verse that the spring was in existence in the narrator's own day. The rendering of בְּ , סָב , A.V., R.V. *marg.* suggests that the spring issued from a 'hollow place' in the actual *jawbone*.

his spirit returned. Heb. וַתֵּשֶׁב רִיחוֹ . So exactly in 1 Sam. 30¹³ of the return of *animation* and *vigour* after faintness. Heb. *rūah* is the essential principle of life, the removal of which from the body results in death (cf. Ps. 104²⁹).

he revived. Lit. 'he lived.'

was called 'Ēn-haḳ-ḱōrē, which is in Leḥi, unto this day. 20. R^{E1} And he judged Israel in the days of the Philistines twenty years.

16. 1. J¹ And Samson went to Ġaza, and saw there a harlot,

'Ēn-haḳ-ḱōrē. The name means 'the spring of the caller,' and is explained by the narrator as referring to Samson; cf. the statement of v. 18 'and he called (*way-yiḱrā*) unto Yahweh.' *Haḳ-ḱōrē*, however, is the Heb. term for the *partridge* in 1 Sam. 26²⁰, Jer. 17¹¹, referring to its call-note, which is a familiar sound in the hill-country of Palestine; and modern commentators (following J. D. Michaelis) consider that the name of the spring was *the Partridge-spring*, and that the explanation given by the narrator, like that of Ramath-leḥi, represents a later adaptation of the meaning. It is tempting to suppose that, if *haḳ-ḱōrē* really here refers to a bird, 'the caller' may in this case be, not the partridge, but its near relative the *quail* (elsewhere called *s'lāw*), which is likewise distinguished by a very clear and resonant call-note.* Bochart (*Hierozoicon*, ii. p. 99) quotes from Athenaeus (ix. 47) the myth that Herakles, when slain by Typhon, was restored to life by smelling a quail—whence arose the proverb among the Greeks,

*Ορτυξ ἔσωσεν Ἡρακλῆν τὸν καρτερόν.

According to Eudoxus (Athenaeus, *loc. cit.*), the Phoenicians annually sacrificed a quail in commemoration of the resurrection of Herakles in the month Peritius (Feb.-Mar.), at the season when the quail returns to Palestine in great numbers (cf. Robertson Smith, *Religion of the Semites*,² p. 449)—a ceremony which is almost certainly to be brought into connexion with the solar myth: cf. *Addit. note*, p. 406. If the quail was thus sacred to Herakles-Melkart, the possibility is opened that the bird may have played a part in the story which related the revival of Samson's vital powers (וחשב רוחו); though, if this was so, the original connexion was so remote from (*or* so explained away by) the narrator that 'the caller' became, not the bird, but the hero himself.

20. *And he judged, etc.* On this notice as the conclusion of the Samson-narrative in R^{E2}'s book, cf. p. 338.

16. 1. Ġaza. Heb. גַּזָּא. The English form of the name is from Γαζα, in which the Γ reproduces the harder form of γ—a consonant which, when Heb. was a spoken language, must have repre-

* Cf. Tristram, *Nat. Hist.* p. 232:—'A few remain there [in Palestine] throughout the winter, but their numbers are suddenly reinforced at the end of March, when every patch of grass resounds with their well-known peculiar call-note.'

and went in unto her. 2. <And it was told> to the Ġazathites, saying, 'Samson hath come hither.' And they came round about, and laid wait for him all 'day' in the gate of the city; and they kept quiet all night, saying, 'when the morning dawns we will

sent two distinct sounds, akin respectively to ξ and ξ in Ar.:

cf. G-K. § 6 *e*. The modern Ar. name is Ġazzeḥ (identical with the Heb. form); and the city, which in ancient times was of considerable importance as a trade-centre on the caravan-routes to Egypt and Arabia, still possesses a considerable population: cf. Smith, *HG*. pp. 181 ff. Ġaza is some thirty-six miles south-east of Şor'ah.

2. *And it was told.* Supplying וַיִּנָּד with \mathfrak{E}^B καὶ ἀνγγέλην, \mathfrak{E}^{AL} καὶ ἀπγγέλην, \mathfrak{S}^P אַתְּחִיב, אַתְּחִיב, and all moderns. \mathfrak{V} reads, 'quod cum audissent Philistiim.' \mathfrak{H} is untranslatable without a verb.

all day. Reading כָּל־הַיּוֹם with Kit., in place of כָּל־הַלַּיְלָה 'all night,' erroneously copied from the latter half of the verse. The point of the statement 'and they kept quiet all night, saying, etc.' must be that during the night they were off their guard, relying upon the supposition that, *so long as the city-gates were closed*, Samson could not escape. It was thus—as they imagined—unnecessary for them to be back at their post till dawn; but Samson baffled them by rising in the middle of the night and removing the gates. It must therefore have been not *all night* that they laid wait for him in the gate of the city; but so much of the preceding *day* during which, after Samson's arrival, the gates remained open, and it was necessary to guard them. We may safely rule out any such explanation of \mathfrak{H} as that they kept watch all night, but fell asleep at their post (unawakened even by the noise of the tearing up of the gates!), or that Samson overawed or otherwise quelled their attack—since such details, had they been presupposed, would certainly have been mentioned in the narrative. Stu. (who was the first to put forward the explanation above adopted) simply omits the first כָּל־הַלַּיְלָה; and is followed by Sta., Doorn., La. Mo. conjectures that the whole sentence, 'and they came round about . . . gate of the city,' is a later addition 'intended to make Samson's escape the more wonderful by exaggerating the precautions which the Philistines took to prevent it.' So No.

When the morning dawns. Heb. עַד־אֹרֶן הַבֹּקֶר may perhaps mean 'Till the morning dawns': with ellipse of 'Wait,' which is supplied in translation by \mathfrak{E}^{AL} Ἔως φωτός πρωὶ μέινωμεν. Cf. *note* on 'at morning,' *ch.* 6³¹. It is unnecessary to follow Mo. (*SBOT.*) in supplying נִחְפָּה (cf. 2 Kgs. 7⁹).

slay him.' 3. And Samson lay until midnight, and arose at midnight, and laid hold of the doors of the city-gate, and the two posts, and plucked them up together with the bar, and put them upon his shoulders, and carried them up to the top of the hill that is in front of Hebron.

4. Now afterwards he loved a woman in the wâdy of Sorek, whose name was Delilah. 5. And the lords of the Philistines came up unto her, and said unto her, 'Beguile him, and see by what means his strength is great, and by what means we may

3. *and laid hold, etc.* Cf. the description of the probable construction of the gates given by Mo. The bar let into the two posts, and stretching across the gates, would keep the latter firmly locked in position, and enable Samson to carry off the whole, when plucked up, 'in one piece.'

in front of Hebron I.e. to the east of it—the sense which is always possessed by עַל-פְּנֵי, except when following the verb נִשְׁקָה ('look out over'); cf. the instances collected by Mo. and by BDB. p. 818*b*. The distance from Gaza to Hebron is some thirty-eight miles; but this is a mere detail to the narrator. The connexion of Samson with a point so far removed from the scene of most of his exploits is obscure, unless we are justified in suspecting a solar *motif*: cf. *Addit. note*, pp. 406 f.

4. *the wâdy of Sorek.* The modern wâdy eṣ-Ṣarâr on the northern edge of which Ṣor'ah is situated (cf. *note* on *ch.* 13²). The name Sorek (which is the name of a choice kind of grape-vine) is preserved in Ḥirbet Sûrîk,* two miles west of Ṣor'ah.

Delilah. We are not told whether the woman was a Philistine, or an Israelite in the pay of the Philistines, though the general trend of Samson's inclinations favours the former supposition. Her name is Semitic in *form*; but this affords no indication as to her nationality, since Semitic names appear to have been largely used among the Philistines (cf. Ṣidkâ, Ṣilbêl, etc.). On the probable meaning of the name, and its importance in relation to the mythological element in the story, cf. p. 407.

5. *the lords of the Philistines.* Cf. *note* on *ch.* 3³¹.

by what means his strength is great. Heb. בְּמָה לַחֲזֵי גִדּוֹל. A.V., R.V. render 'wherein his great strength lieth,' with G, F; but

* The law which governs the interchange of sibilants in Heb. and Ar. would lead us to expect Ṣûrîk. The use of *s* in the Ar. form is perhaps an indication that the later Heb. pronunciation of the name substituted ס for שׁ (the two consonants are often interchanged in Heb.).

prevail over him and bind him, so ^{to} reduce him; and we ourselves will each give thee eleven hundred shekels of silver.' 6. And Delilah said unto Samson, 'Tell me by what means thy strength is great, and by what means thou mayest be bound so as to reduce thee.' 7. And Samson said unto her, 'If they bind me with seven fresh bowstrings which have not been dried,

such a rendering would only be legitimate; ^{הַזֶּה} were read.* ^{לְדוֹל} without the Definite Article can only be predicated. 'By what means' suggests the supposition that his strength depended upon some magic charm (so Le Clerc, Mo., etc.).

to reduce him. I.e. to reduce or overcome his strength; Heb. ^{לְעַנּוֹתוֹ}. This seems to be the meaning rather than A.V., R.V. text 'to afflict him,' marg. 'to humble him'; Mo., ^{לְעַנּוֹתוֹ} to torment him.' Cf. note on v.¹⁹.

will each give thee. 'Each' probably refers to twelve lords of the principal Philistine cities. Cf. ch. 3³.

eleven hundred shekels of silver. Why this particular sum is fixed, rather than what we should term a round sum, 'not be said. Commentators display a singular unanimity in repeating Reuss' suggestion that the meaning is a full thousand, or *one* a thousand. If this is so, we can only say that they allowed a substantial margin. The sum mentioned in ch. 17² happens to be the same.

The value of the Heb. silver shekel, as calculated by Kennedy (DB. iii. 420 a) was about 2s. 9d.; so the sum promised by each of the princes would have amounted to something like 151 in our money. Money at this period was not coined; but the value of the metal was determined by weight. The verb *šākal* 'to weigh' (from which the subs. shekel is derived) is commonly employed in descriptions of money-transactions: cf. Gen. 23¹⁶ P, 1. 22¹⁶ E, 1 Kgs. 20³⁰, *al*.

7. *seven fresh bowstrings.* For Heb. *yēther* in this sense, cf. Ps. 11², and the usage of the Ar. *watar*, Syr. *yathrā*. The bowstrings were, no doubt, of twisted gut which was still moist (the lit. meaning of ^{לְיָחִים}), and therefore less likely to fray or break. The rendering of A.V., R.V. text 'green withs (withes)'—cf. Jos. κλήμασιν . . . ὀπείλου—is improbable in itself and without support in usage. The number *seven* was probably considered to have a magical virtue.

* Maurer (*apud* Ros.) cites ^{אֶתְחִיבֶם אֶתְּךָ} 'your other brother,' Gen. 43¹⁴, as an instance of an adj. without the Article qualifying a subs. male definite by a pronominal suffix. This single instance, however (which may be due to textual corruption) does not prove the possibility of such a usage in the present passage.

then shall I become weak, and shall be like any other man.' 8. Then the lords of the Philistines brought up to her seven fresh bowstrings which had not been dried, and she bound him with them. 9. Now she had liers-in-wait abiding in the inner chamber. And she said unto him, 'The Philistines are upon thee, Samson!' And he snapped the bowstrings just as a strand of tow is snapped when it feeleth fire. So his strength was not known. 10. And Delilah said unto Samson, 'Behold, thou hast mocked me, and told me lies: now, prithee, tell me by what means thou mayest be bound.' 11. And he said unto her, 'If they only bind me with new ropes wherewith no work hath been done, then shall I become weak, and shall be like any other man.' 12. So Delilah took new ropes, and bound him with them, and said unto him, 'The Philistines are upon thee, Samson!' Now the liers-in-wait were abiding in the inner chamber. And he snapped them from off his arms like a thread. 13. And Delilah said unto Samson, 'Hitherto thou hast deceived me, and told me lies: tell me by what means thou mayest be bound.' And he said unto her, 'If thou weave the seven locks of my head along with the web, <and beat up with

like any other man. Heb. בְּאֶחָד הָאָדָם, lit. 'like one of mankind.'

9. *The Philistines, etc.* The alarm is given, not to call out the ambush, but to test the success of the experiment. When this proves a failure, the Philistines must, of course, be supposed to remain in hiding, so that Samson is unaware of their presence, and thinks that Delilah is merely playing with him in order to gratify her own curiosity.

when it feeleth the fire. Lit. 'when it *smelleth* the fire,' i.e. without actual contact. For the simile, cf. *ch.* 15^{14b}.

11. *with new ropes.* Cf. *ch.* 15¹³.

13. *the seven locks, etc.* The precise sense in which Heb. *mahl^hphôth* is used—whether of natural *curls* or *plaits*—is uncertain, the etymology of the word being obscure.* *Ἐ* σείπας or *βοστρύχους*, *Ἐ* 'crines,' *ס*^p חֲסִמֹת, 'plaits,' *נ*רילת *id.* We are reminded of the way in which Gilgamesh is represented on seal-cylinders, with hair divided into curling locks; though these are always *six* in number (not *seven*, as stated by Jeremias, Cooke, and Smythe Palmer), three falling on

* The explanation given by BDB. for the sense '*plaits*,' 'so called from *inter-twining*, *passing through* each other, of the strands,' is based on the fact that the verb *hālah*, which commonly means 'to pass on or away,' seems in two passages

the pin, then shall I become weak, and shall be like any other man. 14. So, when he slept, Delilah took the seven locks of his head, and wove them along with the web, and beat up with the pin, and said unto him, 'The Philistines are upon thee,

each side of his face: cf. Plate II., figs. 3, 4, 5; Plate III., figs. 1, 2. On the probable solar significance of this characteristic, cf. *Addit. note*, p. 404.

13, 14. and beat up . . . the web. Adding וְתַקְעָה בִּיתָר וְחִלִּיתִי וְהִיְיִתִּי כְּאַחַד הָאָדָם: וְיִהְיֶה בְּשִׁבְכּוֹ וְתַקַּח דְּלִילָה אֶת־שִׁבְעַ מַחְלָפוֹת רֹאשׁוֹ וְתֶאָרְגַּ עִם־הַמַּסְכָּת. The words are necessary to complete both Samson's directions and also the account of the way in which Delilah exactly carried them out: cf. the correspondence between his words and her actions in *vv.*^{7,8}, ^{11,12}, ^{17b,19}. They have fallen out of *℣* through homœoteleuton; the scribe's eye passing from the first occurrence of עִם־הַמַּסְכָּת 'along with the web' to the second. The missing words occur, with variations, in MSS. of *℣*, and in *ℒ*¹, *ℒ*^b. We follow the reading of *℣*^b, according to which *vv.*^{13b,14aa} run καὶ εἶπεν πρὸς αὐτήν, 'Ἐὰν ὑφάνης τὰς ἐπὶ τὰς σειρὰς τῆς κεφαλῆς μου σὺν τῷ διάσματι καὶ ἐνκρούσης τῷ πασσάλῳ εἰς τὸν τοίχον, καὶ ἔσμαι ὡς εἰς τῶν

to have the sense 'to pass through (cf. *ch.* 5²⁶ *note*); but the connexion in idea which is here assumed appears somewhat uncertain (unless—as privately suggested by Prof. Margoliouth—we may justify such a transition in meaning by the analogy of the Ar. root *marra*, 'to pass by or beyond, pass along,' from which are derived *marîr* 'a rope that is slender and long, and strongly twisted,' 'amarra 'more or most tightly twisted'—an elative form). The comparison of Ges., *Thes.*, with Ar. *ḥalîf*, 'contortus, convolutus,' is derived from Golius; but this meaning is not given by modern Ar. lexicons. There is an Ar. word *ḥalîf* which means 'a woman who lets her hair fall down her back behind' (Ar. *ḥalafa* meaning 'to come after, succeed' temporally, and also 'to come behind or at the back' locally); and *ḥalf* denotes 'the location or quarter which is behind' (Lane), and is used e.g. of joining the hands *behind the back* (Dozy). This suggests the possibility that *maḥalāphôth* may properly denote *locks which fall down the back*. Cf. the description given of Gilgameš when, after his conquest of Humbaba, he washed and polished his arms, put on fine raiment, and 'caused his long hair to fall down upon his back' (*unaššik kimmatsu eli širîšu*; Tab. VI., l. 2. The passage is one which unmistakably embodies a solar motif: cf. *Addit. note*, pp. 396 f.). It is worthy of notice that *maḥalāphā* is, in form, the exact equivalent of Bab. *maḥlaptu*, which denotes something which *covers* or *clothes*. Possibly the word may have existed in Heb. in the sense of *trapping* or *adornment*, and may have been applied to a curl. More probable, however, than any of these suggestions is connexion with Heb. *ḥālaph* in the sense *to sprout*: cf. Ps. 90^{4,5} (K^{al}), Job 14⁷ (Hiph'il)—a meaning which, though explained by BDB. as derived from the idea *to show newness*, is rather to be associated with Bab. *elēpu*, *to sprout*, applied to a tree (*ka iṣi*), or *to be long*. מַחְלָפוֹת רֹאשִׁי would then properly denote 'the sproutings (long tresses) of my head': cf. the use of the verb צָמַח 'to sprout' in *v.*²² of the fresh growth of the hero's hair after it had been cut off.

ἀνθρώπων ἀσθενής. καὶ ἐγένετο ἐν τῷ κοιμᾶσθαι αὐτὸν καὶ ἔλαβεν Δαλειδα τὰς ἐπτὰ σειρὰς τῆς κεφαλῆς αὐτοῦ καὶ ὕφανεν ἐν τῷ διάσματι κτλ. Here εἰς τὸν τοίχον appears to be an explanatory gloss, due to misunderstanding of the meaning of וְתַקַּעַת בֵּיתָר (see below); but the rest of the passage presupposes a clear and self-consistent original.* So. Mo. The text of \mathfrak{G}^{AL} offers a conflation between that of \mathfrak{G}^{B} and a variant text which is preserved most nearly in the group of MSS. cited by Mo. as \mathfrak{G}^{LP} (cf. *SBOT*). In this latter text the most noteworthy variation is in the commencement of v.¹⁴, καὶ ἐκοίμισε αὐτὸν Δαλιδα, καὶ κατέκρουσεν κτλ. Hence Bu. reads וַתִּשְׁנֶה וַתִּצְרַח וְג' (cf. v.¹⁹).

The precise nature of the test which is thus described has been elucidated by Mo. (*Proceedings of the American Oriental Society*, 1889, pp. clxxvi ff.; cf. also *Comm.* and *SBOT*. So, previously, Braun, *De Vestitu Sacerdotum Hebraeorum*, Amstel., 1698, p. 252, who is followed by Stu.). Mo. seems, however, to be incorrect in assuming that the loom was of the upright kind: cf. Kennedy, article 'Weaving' in *EB.*, who points out that, in the ancient Egyptian representations, which are given by him (col. 5279), and by Mo., *SBOT. Eng. trans.*, p. 86, the looms are really horizontal; though absence of perspective makes them appear at first sight to be upright. We should probably picture a horizontal loom of the simplest sort, in which two pairs of posts firmly fixed in the ground hold the yarn-beam and the cloth-beam respectively. A piece of unfinished stuff (the *maššē/kheth* 'web') is standing in the loom; and Delilah, having manœuvred so as to get Samson to sleep with his head on her knees beside the loom, weaves his long hair into the warp with her fingers, and beats it up tightly into the web by means of the *yāthēdh*, i.e. the 'pin' or 'batten' (a flat piece of wood with a thin edge), so that his hair actually becomes part of the finished material.‡ When aroused

* בִּישְׁכְּבו is adopted as the original of ἐν τῷ κοιμᾶσθαι αὐτὸν because שָׁכַב , properly 'to lie down to rest,' is regularly rendered by *κοιμᾶν* in \mathfrak{G} (151 cases cited in Hatch and Redpath's *Concordance*); whereas only one passage (Isa. 5²⁷) is cited in which יָשָׁן is so rendered.

‡ Cf. the description of a modern Bedawin loom given by Palmer (*Desert of the Exodus*, i. p. 125), who, in referring to his visits paid to Bedawin encampments, tells us that 'On one of these occasions I noticed an old woman weaving at the tent door. Her loom was a primitive one, consisting only of a few upright sticks upon which the threads were stretched: the transverse threads were inserted laboriously by the fingers, without the assistance of a shuttle, and the whole fabric was pressed close together with a piece of wood. Beside her stood a younger female spinning goats' hair to supply the old lady with the material necessary for her task.' So, too, Rob. (*BR.*³ i. 169) relates that 'Just before setting off [from 'Akabah], we saw in one corner the process of manufacturing the goats' hair cloth of which the common Arab cloaks are made. A woman had laid her warp along the ground for the length of several yards, and sat at one end of it under a small shed, with a curtain before her to ward off the eyes of passers-by. She wove by passing the woof through with her hand, and then driving it up with a flat piece of board having a thin edge.'

Samson!’ And he awoke from his sleep, and plucked up [] the loom and the web. 15. And she said unto him, ‘How canst thou say, “I love thee,” when thy heart is not with me? three times already thou hast deceived me, and hast not told me by what means thy strength is great.’ 16. And when she

by the alarm, Samson leaps up; and, as he raises his head, he pulls the four posts of the loom out of the ground, and carries off web and loom together attached to his hair.

The \mathfrak{E} addition $\epsilon\iota\varsigma\ \tau\omicron\nu\ \tau\omicron\iota\chi\omicron\nu$, noticed above, assumes erroneously that *yāthēdh* (as in *ch.* 4^{21,22}, 5²⁶) denotes a *peg* which Delilah *hammered into the wall* ($\kappa\alpha\iota\ \epsilon\nu\kappa\rho\acute{o}\upsilon\sigma\eta\varsigma\ \tau\hat{\omega}\ \pi\alpha\sigma\sigma\acute{\alpha}\lambda\phi\ \kappa\tau\lambda.$, $\kappa\alpha\iota\ \epsilon\pi\eta\epsilon\nu\ \tau\hat{\omega}\ \pi\alpha\sigma\sigma\acute{\alpha}\lambda\phi\ \kappa\tau\lambda.$; cf. \mathfrak{E} ‘et clavum his circumligatum terrae fixeris’) in order to secure the web; and a similar error is probably responsible for the insertion of הִיתָר in *v.*^{14b} \mathfrak{H} (cf. *note*). That *yāthēdh*, however, can be used in other senses is proved by Deut. 23¹⁴, where it denotes an implement for digging. \mathfrak{S}^P renders $\mathfrak{N}\mathfrak{O}$, *i.e.* the ‘cross-beam’ of the loom to which the warp is attached; so \mathfrak{T} אַכְסֵן in *v.*^{14b}, but in *v.*^{14a} סִכְתָּא ‘peg.’ The meaning of Heb. *maššēkheth* ‘web,’ from *nāśakh* ‘to weave’ (cf. Ar. *nasāḡa*), may be illustrated by the usage of the nearly identical form *maššēkhā*, which occurs in Isa. 25⁷ (‘the web that is woven over all nations’), 30¹ (‘to weave a web’), and in Isa. 28²⁰ in the sense of ‘(woven) bed-spread.’ Kennedy (*EB.* 5282) supposes that *maššēkheth* and *maššēkhā* primarily denote the ‘warp,’ and then by metonymy the ‘web,’ on the ground that the post-Bib. Heb. verb *hēśekh* is used of *setting the warp* in the loom. This view, however, is opposed by the relation of Heb. *nāśakh* to Ar. *nasāḡa*, which certainly means ‘to interweave.’

14. *the loom.* הִיתָר הָאָרֶגַּל is intended to mean ‘the peg of the loom.’ הִיתָר (which is condemned as an insertion by the anomalous use of the Article with the Construct State) must have been originally a marginal addition made by a scribe who, taking יָתָר in *v.*^{14a} to mean the *peg* with which Delilah *fastened* the web to the wall or ground, desiderated a reference to Samson’s plucking this out when he freed himself. As we have seen, however (preceding *note*) יָתָר has quite a different meaning, and it was the loom itself which Samson pulled up.

15. *How canst thou say, etc.* Cf. *ch.* 14¹⁶.

when thy heart, etc. Mo. brings out the sense by rendering, somewhat paraphrastically, ‘seeing that thou dost not confide in me.’ ‘Heart,’ as he points out, is used not of the *affections*, but of ‘the inner man with its secret thoughts.’ Cf. *v.*¹⁷, ‘he told her all his heart.’

pressed him sore with her words continually, and urged him, his soul was impatient unto death. 17. And he told her all his heart, and said to her, J² No razor hath come up upon my head, for a Nazirite of God have I been from my mother's womb: J¹ if I be shaven, then my strength will depart from me, and I shall become weak, and shall be like all other men.' 18. And when Delilah saw that he had told her all his heart, she sent and called the lords of the Philistines, saying, 'Come up this once, for he hath told ^{me} all his heart.' And the lords of the Philistines ^{came up} unto her, and brought up the money in their hand. 19. And she made him sleep upon her knees, and called for a man, and ^{he} shaved off the seven locks of his head; and ^{he} began ^{to be reduced}, and his strength departed from him. 20. And she said, 'The Philistines are upon thee, Samson!' And he awoke out of his sleep, and said, 'I will go out as at

17. *no razor . . . womb.* As to the grounds upon which this passage is to be regarded as an addition to the old story by the author of *ch.* 13, cf. pp. 337 f. Its excision from the narrative causes Samson's answer ('If I be shaven, etc.') to commence in precisely the same form as in *vv.* 7, 11, 13.

18. *hath told me.* Reading יָלַי for *Kt.* הָלַי, with ארז, many MSS. of *℣*, and all Versions.

came up. Reading וַיַּעֲלֵה, the regular tense form in narration, with many MSS. of *℣*, in place of the irregular וַעֲלֵה.

19. *and he shaved off.* Reading וַיַּגֵּל. *℣* וַתַּגֵּל 'and she shaved off'; but, if Delilah did this herself, it is not clear why the man should have been needed.

and he began to be reduced. Reading וַיַּחֲלֵל לְעֻזּוֹ (or לְעֻזּוֹ) with *℣*^{AL} καὶ ἥρξατο ταπεινοῦσθαι, *℣*^h *ܠܥܝܙܐ ܕܗܝܬܐ ܕܡܝܬܐ ܕܡܝܬܐ*. The reference is to the gradual ebbing away of his strength as he is shorn of his locks. Cf. *v.* 5 *note*, and the use of עָנָה in Ps. 102²³ (*℣* 21), 'He *weakened* my strength in the way.' *℣* וַתַּחֲלֵל לְעֻזּוֹ 'and she began to afflict him,' has the support of *℣*^B, *℣*ⁿ, *℣*, and is paraphrased by *℣* 'et coepit abigere eum, et a se repellere.' Whatever meaning, however, be read into the statement, it involves (coming as it does before 'and his strength departed from him') something of a *hysteron-proteron*; since it would be only *after* his loss of strength that Delilah would venture to treat him with contumely.

other times, and shake myself free'; not knowing that Yahweh had departed from him. 21. And the Philistines laid hold on him, and bored out his eyes; and they brought him down to Gaza, and bound him with bronze fetters; and he did grind in the prison-house. 22. But the hair of his head began to grow when he had been shaved.

23. And the lords of the Philistines gathered themselves together to sacrifice a great sacrifice unto Dagon their God, and

20. *and shake myself free.* The expression suggests that Delilah had bound him (cf. *v.*⁶), in addition to causing his locks to be shaved off; and Mo. may be right in his conjecture that a statement to this effect has been accidentally omitted.

not knowing, etc. Heb. 'וְהוּא לֹא יָדָע וְג', a circumstantial clause.

that Yahweh, etc. Doorn. supposes that כָּחוֹ 'his strength' originally stood in place of 'Yahweh'; cf. *v.*^{10bβ}. Cf., however, the remarks on pp. 337 f.

21. *and he did grind.* The Heb. יָהִי טוֹחֵן implies that this was his constant occupation. On grinding as a badge of degraded servitude, cf. *note* on *ch.* 9⁵³. It is probable, however, that the reference in Samson's case is not to a mere handmill, but to a heavy mill such as would usually be turned by an ox or an ass. The reference may very possibly embody a solar motif: cf. *Addit. note*, p. 408.

22. *But the hair of his head, etc.* This statement carries the mind of the sympathetic reader beyond the immediate blackness of the hero's fate, by hinting at the *dénouement* in which Samson will perform his greatest feat of all.

23. *Dagon.* A Philistine deity who had a temple not only at Gaza, but also at Ashdod (1 Sam. 5¹, 1 Macc. 10^{83 f.}; 11⁴), and (if the text of 1 Chr. 10¹⁰ is to be trusted) at Beth-she'an. Beth-Dagon ('Temple of D.') was the name of a city in the Shephelah which is assigned to Judah in Josh. 15^{41 P}; and the same name was borne by a city on the border of Asher, apparently east of Carmel and not far from the border of Zebulun; Josh. 19^{27 P}. The former of these names may show Philistine influence in the Shephelah; while the latter conceivably indicates the presence of the kindred people called Takkara, whom we know to have settled at Dor, a little south of Carmel (cf. *Introd.* p. xcvi). Among modern Ar. place-names, we find Bêt-Degân*

* Whether this is the same as the Beth-Dagon of Josh. 15⁴¹ is doubtful. It is so identified by Eusebius (*OS.* 235¹⁴), Βηθ Δαγων. φυλῆς Ιουδα. καὶ ἔστιν ἐν κώμῃ μεγίστῃ Καφαρ Δαγων μεταξύ Διοσπόλεως καὶ Ιαμύλας. The site lies outside the Shephelah properly so called (cf. *note* on *ch.* 1⁹); but the list of cities in Josh. in which the name occurs is so confused that we can draw no certain conclusion.

five and a half miles south-east of Jaffa, with a ruined site Daġūn a little further south. One of these, no doubt, is the Bit-Daganna mentioned before Joppa by Sennacherib in his Prism-inscription: cf. *KB.* ii. p. 92.

It seems probable, however, that Dagon was not a foreign deity introduced from the west by the sea-peoples in their influx into Cana'an, but rather a native Semitic deity, adopted (like Ba'al-zebul,* the god of 'Eḡron, 2 Kgs. 1^{2f.}) after their settlement in the land. There is another Bêt-Deġān some seven miles east of Nâblus (Shechem), whither we have no reason for supposing that Philistine influence ever extended. It can hardly be doubted that Dagon is identical with the god Dagan, who is known to us from the cuneiform inscriptions. Dagan is sometimes connected with the god Anu (e.g. by the Assyrian kings Šamši-Adad VII., *KB.* i. p. 174, and Šargon, *KB.* ii. p. 38), occupying in relation to Anu the position which is commonly filled by Enlil, to whom there is reason for assuming that he was regarded as the equivalent.† Among the T.A. Letters there are two from a Cana'anite vassal of the king of Egypt named Dagan-takala (Winckler, *KB.* v. Nos. 215 f.; Knudtzon, Nos. 317 f.); and the name of the deity is especially frequent as an element in proper names of the Babylonian First Dynasty period, several of which (e.g. Yašub-(ilu)-Dagan, Yašmaḡ-(ilu)-Dagan, etc.) appear, from the verbal forms which they embody, to have been borne by Western Semites (men of Amurru; cf. *Introd.* p. lix); cf. the way in which Ḥammurabi, in the introduction to his Code (iv. 27), speaks of Dagan as *his creator* (*bānišu*). We first meet with Dagan in the theophoric names of two successive rulers of the city-state of Nîsin, Idin-Dagan and Išme-Dagan, dated by King *cir.* B.C. 2250 (*Sumer and Akkad, Appendix II.*). These rulers, though members of a dynasty which used the Sumerian language|| and adopted Sumerian customs, yet bear Semitic names (meaning respectively 'Dagan has given' and 'Dagan has heard'); and there is thus some ground for the conjecture of Meyer (*GA.*² I. ii. pp. 501 f.) that the dynasty of Nîsin may have been of Amorite origin, and may have brought the worship of Dagan with them from the west.¶

The view that Dagon was represented as half man and half *fish* is based upon supposed connexion of the name with Heb. *dāgh* 'fish,'

* On this form of the name, as original rather than Baal-zebul of 𐤁𐤏, cf. p. 5.

† Cf. the full discussion of Jensen, *Kosmologie*, pp. 449 ff.

§ Cf. the lists given by Thureau-Dangin, *Lettres et contrats de l'époque de la Première Dynastie Babylonienne*.

|| Cf. the inscriptions given by Thureau-Dangin, *Die Sumerischen und Akkadischen Königsinschriften*, pp. 204-207.

¶ Cf. also for this view, Zimmern, *KAT.*³ p. 358; Jastrow, *RBA.* i. pp. 219 ff. King, who formerly maintained the Sumerian origin of the dynasty of Nîsin (*Sum. and Akk.*, pp. 284, 303), now holds it to have been Semitic (*Bab.* pp. 131 ff.).

and first appears in the commentaries of Rashi and Kimchi on 1 Sam. 5; * but, apart from this assumed etymology, it can claim no external support. The Assyrian representations of a deity part man and part fish, figured in Riehm, *HWB.*² i. p. 290, in the article 'Dagon,' represent Ea-Oannes † (cf. the quotations from Eusebius and Helladius given in *OTLAE.* i. p. 48), whom we have no reason to associate with Dagon. More plausible is the association of the name with Heb. *dāghān* 'corn,' put forward by Philo of Byblos, who states that Dagon was the inventor of corn and the plough, and was known as *Zeûs ἀπόρριος*. Granted this connexion, we may either suppose, with Sayce (cf. *HCM.* p. 326), that the worship of an originally Sumerian deity travelled westward to Canaan, and a native etymology having been found for his name, he 'became a god of corn, an agricultural deity who watched over the growth and ripening of the crops'; or (as seems more probable), that the name of an originally Amorite corn-deity came to be used to denote *corn*, much as the Romans derived *cerealia* from *Ceres*, and used the term to denote 'cereal crops.' It is worth noticing, in this connexion, that among the Babylonian First Dynasty names there occurs *Izrah-(ilu)-Dagan*, i.e. 'Dagan sows,' § a name in which the thought may have been that the god of sowing sows the seed of a man. Cf. the

* The difficult passage 1 Sam. 5⁴ states that, after the image of the deity had lost its head and hands, עָלָיו נִשְׁאַר דָּגוֹן 'only Dagon was left upon him' (i.e., apparently, 'belonging to him' or 'of him'). It is upon this passage that Kimchi bases his statement that Dagon was fish from the navel downwards, and human above—a view which he cites as a generally received opinion ('They say, etc.'). Wellh.'s emendation דָּגוֹן for דָּגוֹן 'only his fishy part was left' (*TBS. ad loc.*), supports this view, but has not gained general acceptance. We seem to need some word meaning 'stump' or 'trunk,' such as is suggested by the rendering *πλῆν ἡ βίαυς Δαγῶν ὑπελείφθη*. Cf. *NHTS.*² *ad loc.*

‡ Cf. also *TB.* ii. p. 60, figs. 99 and 100; and Jastrow, *Bildermappe zur Religion Bab. und Assy.*, figs. 70a and 95, who takes the figure clad in a fish-skin to represent, not the god himself, but his priest.

§ *Izrah* probably stands for יֹרַע, *h* in early cuneiform representations of Amorite words standing for the weaker *a* as well as the stronger form of *y*. Cf. *Yašmah-(ilu)-Dagan* already cited = יִשְׁמַעֲרֵגַן. *Yadih-ilu* = יִדְעֵאֵל (as in 1 Chr. 7^{6,10,11}, 11⁴⁵, 26²), and cases cited in *Introd.* p. lxxv, footnote. It may be admitted, however, that there is not the same certainty that *Izrah* is an Amorite Imperfect as exists in the case of the first elements in such First Dynasty names as *Yašmah-(ilu)-Dagan*, *Yašub-(ilu)-Dagan*, *Yamlik-ilu*, *Yakun-(ilu)-Adad*, etc., where the verbal forms are clearly not Babylonian, and, in *Yašmah*, we have the original *a* of the preformative syllable of the Imperf. *ḫal* preserved as in Ar. (cf. *yazkur* = יֹזְכֵר among the T.A. glosses; p. 169 note). If, as assumed, *Izrah* = יֹרַע, we must suppose that in this case the thinning process from *a* to *i* has already taken place. It is possible, however, that the form may be præterite of the Bab. verb *zarāhu* 'to shine,' = Heb. זָרַח.

to rejoice: and they said, 'Our god hath given into our hand Samson our enemy.' 25. And when their hearts were merry they said, 'Call Samson, that he may make sport for us.' So they called Samson from the prison-house, and he made sport

place-name יִרְעָאֵל Jezre'el, *i.e.* 'the god sows,' which, if (as is doubtless the case) it goes back to Cana'anite times, may represent a dedication to Dagon.*

25.24. The change in order of verses follows the suggestion of Bu. (so No., Kit., Cooke). 'And when the people saw him' (*v.*²⁴) is out of place until Samson has been fetched and brought in to the festival (*v.*²⁵); but, with the transposition, the reference of *v.*²⁴ is most appropriate, and the narrative runs smoothly. La. retains the order of *¶* on the view that the Object in 'when they saw him' is the god Dagon, whose image was carried in procession or otherwise exhibited; but this is most improbable.

25. *when their hearts were merry.* *Kt.* פִּי טוֹב (Perfect) and אָרַע פִּיטוֹב (Infin. Constr.) are equally idiomatic. The Massoretes substitute the construction which is found in 2 Sam. 13²⁸, Hos. 10¹, Est. 1¹⁰, possibly failing to recognize טוֹב of *Kt.* as a Perfect. The occurrences of this Perfect form are often difficult to distinguish from the Adjective; but the real existence of such a form (verb middle *a*, like בָּשָׂה) is proved by the occurrence of the plur. טֹבוּ, Num. 24⁵, Song 4¹⁰.

that he may make sport for us. Whether the reference is to minor exhibitions of strength and dexterity, or to the exercise of his jesting proclivities, is not clear. *S*^v, Ar. suppose that he was to *dance* before them.

and he made sport. Here *¶* somewhat strangely varies the spelling

* It is very possible that the passage in the Sarcophagus-inscription of Eshmun'azar, king of Sidon, ll. 18 f., should be rendered, 'And, moreover, the Lord of kings gave us Dor and Joppa, the excellent land of Dagon, which is in the field of Sharon' (so Schlottmann, Movers, and Blau, as cited in *CIS*, I. p. 18). The phrase אֶרֶץ רֶגֶן הָאֲדָרָה is taken, however, by most scholars mean 'the excellent corn-land.' On this view, the passage seems to illustrate the fact that the region inhabited by the worshippers of Dagon was principally noted for its *dāghān* 'corn' (as is still the case in modern times)—a fact which has its importance in relation to the view above discussed that Dagon was a corn-deity.

Sayce (*HCM*, p. 327) cites a seal preserved in the Ashmolean Museum as bearing the inscription Ba'al-Dagon in Phoenician letters, together with the representation (among other symbols) of an ear of corn. The reading is, however, very doubtful. Lidzbarski (*EpheMERIS für Nordsemit. Epigr.*, i. p. 12) thinks that it should more probably be read Ba'al-regem; whilst the ear of corn requires considerable ingenuity for its detection.

before them : and they made him stand between the phi on
24. And when the people saw him, they praised their god, m no
said,

‘Our god hath given
Our enemy into our hand,
And him who laid waste our land,
And who multiplied our slain.’

man
-ticle
-bius
ason
the
who
was
ther

of the verb, using the form צחק which is found elsewhere only in an
Pentateuch (so invariably ; thirteen times) and in Ezek. 23³², where ^{five}
עצ. ^{25a}. ²⁷ we have the ordinary form שחק. Very possibly the vari^d of
may be due merely to a copyist. It is noteworthy, however, th^{ing}
place of מ וַיִּצְחַק לְפָנֵיהֶם, G^{AL}, S^h read καὶ ἐνέπαιζον αὐτῷ, i.e. pro^{ba}ably
וַיִּתְעַלְלֵנוּ (cf. the G renderings of this verb in ch. 19²⁵, 1 Sam. 31⁴,
al.), ‘and they made sport of him,’ i.e. *insulted* him. This text
appears to lie at the back of the doublet of G^B καὶ ἐράπιζον αὐτόν
(perhaps a corruption of the reading of G^{AL}) which follows after
καὶ ἔπαιξεν ἐνώπιον αὐτῶν—an accurate rendering of the text of M.
Jos. (*Ant.* v. viii. 12) seems to support the reading of G^{AL} when he
states that the Philistines sent for Samson ὅπως ἐνυβρίσωσιν αὐτῷ παρὰ
τόν ποτόν. It is conceivable that G^{AL} may represent the original
text, and that the variation of spelling in M may be due to the fact
that the text has been altered by a later hand.

24. *and said.* Reading וַיֹּאמְרוּ with G^A καὶ εἶπαν, in place of M
כִּי אָמְרוּ ‘for they said.’ So Bu., No. Clearly the words which
follow embody the expression of praise, and not simply the reason for
it. כ and ו were frequently confused in the older form of writing :
cf. instances collected in *NHTK*. p. 177.

Our god, etc. The words fall into a rough rhythm, with recurrent
rhyme upon the suffix -nū ‘our’ :—

Nāthān 'elōhēnū
bēyād hēnū 'eth 'ōyēbhēnū
wē'eth mah'arīb h'aršēnū
wā'šer hīrbhā 'eth h'lālēnū.

Such rhymes are by no means infrequent, especially in short poetical
pieces or proverbial sayings preserved by story-tellers in their narra-
tives. In longer poems they are occasional ; but not used systemati-
cally or extensively. Cf. Gen. 4²³, 27^{23a}, 49^{6a, 11. 25a}, Ex. 15^{2, 9}, Num.

to rej^c And Samson said unto the lad that held his hand, 'Suffer Sams^c that I may feel the pillars^{Gl} whereon the house is supported, I^d, J^d and may lean upon them.' 27. Now the house was they^d of men and women; and all the lords of the Philistines they^d there, and upon the roof were about three thousand men

place,

less²⁸, * 23^{9a, 21b, 23}, 24^{7b, 21b, 22}, Deut. 32^{2a, 6b, 9, 25b, 30b, 35, 41a}, 33^{3, 8, 10b, 18, 25}, dedic¹ 14^{18b}, 1 Sam. 18^{7b}, 2 Sam. 1^{20b}. Occasional instances may be found in the Psalms; e.g. 2^{3, 6, 11}, 6², 18^{12a, 15, 19, 21, 23, 29, 37, 45, 47, 49, 51}, al.

25: most frequent and approximately systematic use of rhyme is in (so 1. Song of Songs: cf. the present editor's note in *JTS*. x. pp. 584 ff. of p 1

(v.²⁵) 5. that I may feel. *Kerē* וְהִמְיִטְנִי from מוֹרֵט (cf. Ps. 115⁷; Kal priat¹ 27²¹ †), *Kt.* וְהִמְיִטְנִי from יָמוּט (otherwise unknown). Since (מִשִּׁיט) is the verb ordinarily used in the sense required, it is probable that we should read וְהִמְיִטְנִי.

whereon the house is supported. Doorn. is probably right in regarding these words as a gloss from v.²⁰. Samson would hardly have risked betraying his purpose by using them.

27. Now the house, etc. Apparently we are to picture a banqueting hall with one side open to a courtyard, the roof on this side being supported by a pair of central pillars. Samson makes sport in the courtyard where he can be seen both by those inside the building and by those on the roof. Having thus exhibited his powers, he is brought forward and placed between the pillars—possibly in order that the lords of the Philistines and the other more important people within the hall may obtain a closer view of him.

Doorn. regards the latter half of the verse (from 'and upon the roof, etc.') as a gloss in exaggeration of the foregoing; while Mo. (followed by Bu., etc.) would delete the middle part ('and all the lords . . . men and women'), upon the ground that the Article with the Participle הַרְאִים then refers naturally to הַאֲנָשִׁים וְהַנְּשִׁים. It is difficult to believe, however, in view of the great emphasis in v.^{50b} upon the huge number slain, that the verse as thus attenuated is more

* Here we observe the scheme of rhyming lines 1, 2, and 4, with non-rhyming 3, as in Arabic poetry:—

kī ēš yāse'ā mēHešbōn
lehābhā mikkiryāth Šihōn
'ākhelā 'Ar Mō'ābh
ba'alē bāmōth 'Arnōn.

Cf. Num. 24^{21b, 22}, and the instances cited from the Song of Songs in *JTS*. loc. cit. p. 586.

and women, looking on while Samson made sport. 28, on Samson cried unto Yahweh, and said, 'Lord Yahweh, p no remember me, and pritheer strengthen me only this oncan God, that I may avenge myself upon the Philistines inicle vengeance^e ¹ for¹ my two eyes.' 29. And Samson grasped^{ius} two middle pillars whereon the house rested, and leaned ^{on} them, one with his right hand, and the other with his left. ^{he} And Samson said, 'Let my soul die with the Philistines!' ^{ho} he bowed himself mightily; and the house fell upon the ^{as} ^{ker} and upon all the people who were therein. So the dead an

original in form. On the use of the Def. Art. in הָרָאִים, cf. (of § 126 x. ng an

28. *this once*. Heb. הַפֶּעַם הַזֶּה. We should expect הַזֶּה הַפֶּעַם or הַפֶּעַם simply (cf. *ch.* 6³⁰, Gen. 18³², Ex. 10¹⁷). 31⁴,

in one vengeance for my two eyes. Reading אַחַת בְּשִׁטִּי עֵינִי text for נָקָם אַחַת מִשִּׁטִּי עֵינִי. He prays that at one stroke he ^{αὐτόν} exact an adequate vengeance for his grievous loss. So ^B after This meaning is adopted by R.V. *text*, but cannot be extracted ^{of} of אַחַת. אַחַת as it stands. אַחַת can only mean 'a vengeance for (*lit.* of) ^{on} ^{παρὰ} my two eyes'; and this rendering is adopted by R.V. *marg.*, Ki² Rashi, and most moderns. But, jester as Samson was, the ^{original} and pathos of the context seem to forbid the idea that he ^{ie} ^{fact} facing death with a jest on his lips.

30. *Let my soul die*. The use of נַפְשִׁי 'my soul' as a ^{of} ^{נפש} synonym for 'me' is frequent in Heb., especially in poetry. The *nēphēs* (properly, that which *breathes*) is the principle of life which animates the *bāsār* 'flesh,' and the exit of which results in death. It is not 'soul' in the sense in which we use the term, *i.e.* of the immortal *ego*.

he bowed himself. Probably we are to picture Samson as grasping the pillars with either arm, and then bending forward so as to force them out of the perpendicular. Mo., who renders עָלֵיהֶם וַיִּפְמֶה in *v.*²⁹, 'and he braced himself against them,' explains וַיִּט here as meaning 'he thrust,' supposing that 'standing between the two columns, he pushed them apart by extending his arms.' Such a sense attached to נָטָה may perhaps be justified by its use to denote the *stretching forth* of the hand (Ex. 8¹, Isa. 5²⁵, *al.*), though it is not very natural without expression of the object ('his hands or arms'); nor is it easy, on this interpretation, to justify וַיִּלָּפֹת *v.*²⁹. If he pushed the pillars apart, he would hardly have *grasped* them.

to rejd to death at his death were more than those that he
Samsco death in his life. 31. And his brethren and all his
theyr's house went down, and took him, and brought him up,
they buried him between Šor'ah and Eshta'ol, in the grave of
theyjoah his father. R¹² And he judged Israel twenty years.

place, *did to death*. This rendering of הָמִית (which would ordinarily
less ranslated 'he slew') is adopted in order to bring out the para-
dedicical word-play which is intended in the original.

25 I. *went down*. Cf. note on 'Timnah,' *ch.* 14¹.
(so I. *between Šor'ah, etc.* Cf. *ch.* 13²⁵ note.

of p
(v. 25)
priat

שָׁמֶשׁ
that

THE MYTHICAL ELEMENT IN THE STORY

OF SAMSON

whhe view has frequently been put forward that the story of Samson
gardiains many legendary elements derived from the solar mythology
riskeh seems to have been the common property, not merely of the
itic peoples, but of other races widely distinct from them. In

27. respect, it has been argued, the Hebrew Samson is analogous to
hall whoenician Melkart and to the Babylonian Gilgameš among the
suppoes, as well as to the Greek hero Herakles, the main features
courtyose portrait may well have been derived from Semitic sources.*
and b. subject is one which lends itself very readily to theorizing;
brouglhere can be no doubt that the arguments which have been
adduced to prove that the whole, or the major part, of Samson's
exploits are based upon a solar myth are insufficiently attested.
When this has been said, it must be affirmed, on the other hand, that
there *are* certain elements in the story which seem to have been
drawn ultimately from solar mythology; and the evidence that this
is so can hardly be ignored.

The *name* Samson or Šimšon, connected as it doubtless is with
Heb. Šémeš 'sun' (cf. note on *ch.* 13²⁴), has of course been adduced
as an argument for the theory of the solar myth. Bu. (*DB.* iv.
p. 381 a) maintains on the contrary that the derivation 'tells rather
against than in favour of this view, for it is not the way with a nature-

* The comparison of the deeds of Samson with those of Herakles is as old as
Eusebius (*Chron.*, ed. Schoene, p. 54), Philastrius (*de Haeres.* c. viii), and
Augustine (*de Civ. Dei*, xviii. 19). That Herakles represents the sun is main-
tained by Macrobius (*Saturnal.* i. xx) upon etymological grounds:—'Et re
vera Herculem solem esse vel ex nomine claret. Ἡρακλῆς enim quid aliud est
nisi Ἥρας id est aeris κλέος? quae porro alia aeris gloria est, nisi solis
illuminatio?'

myth to borrow or even to derive the name of its hero from the cosmical object which it describes.' Be this as it may, it can hardly be denied that the name must have been in origin *honorific* of the sun, and so must indicate the existence of sun-worship in the locality—a fact which is indeed attested by the place-name Beth-shemesh, 'Temple of the Sun,' in the immediate neighbourhood of the scene of the hero's exploits.

We are probably justified in going further, and in associating this sun-worship, not with an alien Canaanite clan inhabiting the district, but with the tribe (or rather *clan*) of Dan itself. As is well known, the Heb. *Dān* means 'Judge,' and is so explained in Gen. 30⁶ J or E, 49¹⁶ J. The tribe of Dan is one of the four Israelite tribes whose descent is traced, not from a wife of Jacob, but from a hand-maid—a tradition which is probably to be interpreted as meaning that these tribes were regarded as not belonging to Israel by full-blooded descent, but as occupying in some way or other an inferior position among the tribes. Very possibly they were settled in Canaan prior to the entry of the Joseph-tribes under Joshua, and were only incorporated into the Israelite confederation at a later period (cf. *Introd.* pp. cvi f.).

As regards Dan, we may gain support for this view from the old poem of Gen. 49. The statement of v.¹⁶,

'Dan shall judge his people
As one of the tribes of Israel,'

is scarcely satisfied by the jejune explanation that he shall maintain his independence as successfully as any other tribe (so, many commentators). It undoubtedly implies that he will vindicate his claim to be reckoned as an Israelite tribe, *i.e.* will raise himself out of a position in which he was looked down upon as outside the full blood-brotherhood.

Now in the case of two of the handmaid-tribes, Gad and Asher, it seems clear that the tribal names were originally the names or titles of deities (cf. the remarks on pp. 197 f.). It is not, therefore, unlikely that the name *Dān* referred originally to a divine *Judge* who was regarded as the patron of the clan. The god of the Babylonian Pantheon who was pictured as the Judge *par excellence* was Šamaš the Sun-god, whose common title among the Babylonians and Assyrians was *Dān* (*i.e.* *Daian*) *šamê u iršiti*, 'Judge of heaven and earth': cf. the numerous references under the heading 'Šamaš, Richter (Gott der Gerechtigkeit)' in Jastrow, *RBA.* ii. 2, p. 1098; and the citations under *dānu* 2 in Muss-Arnolt, *Dict.* i. p. 258. If, then, we may assume that the ancient patron-deity of the tribe of Dan was the Sun-god under his aspect of divine Judge, we shall not be surprised if we find relics of solar mythology surviving in a euhemerized form among the folk-traditions of the tribe.

Can we, however, lay our finger upon any such mythological elements in the story of Samson with reasonable probability? The one incident which must *certainly* be interpreted as the product of folk-mythology is the fox-story of *ch.* 15³⁻⁵. It is impossible to suppose that this can be unconnected with the ceremonial hunting of foxes with blazing torches attached to their brushes which took place annually in the Circus at Rome during the Cerealia, April 19, as stated by Ovid (*Fasti*, iv. 679 ff.). Ovid cites, in explanation of this custom, a tale which he had heard from an old countryman of Carseoli. A twelve-year-old farmer's son, having caught a vixen-fox which had repeatedly robbed his father's hen-roosts, wrapped it in straw and hay, to which he then proceeded to set fire. The fox, escaping, rushed through the fields of corn and set them in a blaze; hence a law was formulated at Carseoli dealing with the fate of captured foxes.* Clearly this story is nothing more than a popular invention in explanation of an ancient rite, the origin and significance of which had passed into oblivion. Preller (*Römische Mythologie*,³ ii. pp. 43 f.) brings the ceremony into connexion with the Robigalia, which were celebrated at the same time of year (April 25), when (as he states) young puppies of a red colour were sacrificed in the grove of Robigus, the spirit who was supposed to work in the *robigo*, i.e. the red rust or mildew which was so apt to attack the corn when approaching maturity. Here he seems to be not quite accurate. The sacrifice of red sucking whelps (*rutilae canes*), together with an augury made from their *exta* (*augurium canarium*), took place outside the Porta Catularia at Rome, and appears to have been a moveable festival, distinct, at least in origin, from the offering of the *exta* of a sheep and a dog at the grove of Robigus, which was situated at the fifth milestone on the Via Claudia: cf. Ovid's description, *Fasti*, iv. 901 ff. Yet the two rites were doubtless closely connected, if not (at any rate in later times) identified: cf. Warde Fowler, *Roman Festivals*, pp. 88 ff.; Pauly-Wissowa, *Real-Encyc. der class. Altertumswiss.*, iii. col. 1981 (*s.v. Cerealia*); Wissowa, *Religion und Cultus der Römer*, p. 163. The resemblance in colour between the sacrificed puppies and the foxes is not likely to be accidental; and it is probable, as Preller supposes, that both the red puppies which were deemed an appropriate sacrifice to Robigus, and also the red foxes which

* Precisely what this fate was to be escapes us owing to a corruption of the text. The best MSS. read:—

'Factum abiit, monimenta manent: nam dicere certam
Nunc quoque lex volpem Carseolana vetat.'

Here 'nam dicere certam' yields no sense; and has been corrected into 'nam vivere captam,' which is found in some inferior MSS. Other suggestions which have been offered are 'namque icere captam,' 'namque ire repertam,' 'namque urere captam,' 'incendere captam,' etc. Cf. Warde Fowler, *Roman Festivals*, p. 78; Postgate, *Corp. Pt. Lat.* i. p. 519.

were hunted at the festival of the corn-goddess Ceres, were typical of the red-coloured blight with its destructive burning properties,* which in the one case it was hoped might be averted by the sacrifice,† and in the other was supposed, by a kind of sympathetic magic, to be chased away so that it might not do damage to the crops.

Now the ancient theory as to the origin of rust was that it was due to the action of the *hot sun* upon the corn-stalks when left damp by the dew.§ The view of Steinthal and Smythe Palmer is thus highly plausible that, in the incident of Judg. 15³⁻⁵, Samson plays the part of the Sun-god with his fiery heat, letting loose the destructive plague of rust which burns up the standing corn of the Philistines. That the Roman custom is to be traced ultimately to a Semitic source (whence it was derived, possibly, as Bochart, *Hierozyicon*, i. p. 857, supposed, through the Phoenicians) may be inferred from the fact that it took place in the latter part of April—the period when, in Syria, the corn is approaching maturity and the danger of rust is to be apprehended, but some considerable time before the crop reaches such a stage in Italy.|| It may well have been, therefore, ‘that the rite was transferred bodily to Latin soil without any rectification of season to make it significant’ (Smythe Palmer, p. 105).

* *Robigo* is also termed *uredo* in Lat., as *burning up* the crops, just as rust is dialectically termed *brand* in Norfolk, Suffolk, and Devon for the same reason (cf. Wright, *Dialect Dict.* i. 376). Smythe Palmer (pp. 101 ff.) cites the Greek *λάμπουρος* ‘torch-tail’ applied to the fox, and compares the German *Brand-Fuchs* (occurring dialectically in Eng. as *brant-fox*), a term which associates the fox with *burning* on account of its red colour.

‡ Ovid versifies the prayer which he heard the Flamen Quirinalis utter when offering the *exta* at the grove of Robigus:

‘Aspera Robigo, parcas Cerealibus herbis,
Et tremat in summa leve cacumen humo.
Tu sata sideribus caeli nutrita secundi
Crescere, dum fiant falcibus apta, sinas.

Parce, precor, scabrasque manus a messibus aufer,
Neve noce cultis; posse nocere sat est, etc.’

§ Cf. Ovid, *Fasti*, iv. 917 ff.:

‘Nec venti tantum Cereri nocuere, nec imbres,
Nec sic marmoreo pallet adusta gelu,
Quantum si culmos Titan incalfeit udos:
Tunc locus est irae, diva timenda, tuae.’

Pliny (18, 68, 10) mentions this as the commonly accepted view, but contradicts it: ‘Plerique dixere, rorem inustum sole acri frugibus rubiginis causam esse et carbunculi vitibus: quod ex parte falsum arbitror, omnemque uredinem frigore tantum constare, sole innoxio.’ Columella (*Arbor.* 13), Palladius (i. 55), and Servius (*ad. 1 Georg.* 131) supposed the cause to be ‘malae nebulae.’

|| ‘The corn harvest in middle Italy took place in the latter half of June and in July.’—Warde Fowler, *op. cit.* p. 154.

We have dealt at length with this single incident, because it may be claimed that it proves decisively the real existence of a mythological element in the story of Samson; and, further, suggests very strongly that this element is solar in character—an inference which, when taken in connexion with the known existence of sun-worship in the locality in which the hero's exploits are laid, and the solar significance of his name (cf. pp. 352, 392), may fairly be claimed to be raised to a reasonable certainty. The gaining of such a vantage-ground provides justification for further advance, in the confidence that, however speculative in detail such investigations may be, the theory with which they are bound up is not in itself illusory, but possesses a solid basis in fact.

In the *notes* on the text, comparison has more than once been drawn between the exploits or characteristics of Samson and those of the Babylonian hero Gilgamesh. The fact that Gilgamesh is a solar hero is well established. As he is known to us from the famous Epic,* he is not identical with Šamaš, for he is represented as under the protection and patronage of that deity. 'Šamaš loves him' (Tab. I. col. v. l. 21); he figures as patron to him and to his friend Engidu (II. iii. 27 ff.; VI. 171 ff.); the mother of Gilgamesh makes an offering to Šamaš before her son's expedition against the giant Humbabi, and asks why the god has placed in her son a ^{great} hero which sleeps not, and so dominates him that he incites him to the most dangerous exploits (III. ii. 8 ff.). Yet there can be no doubt that the hero is a *double* of the Sun-god; and the fact that his exploits find their ultimate explanation in the passage of the sun through the heavens is transparently obvious.

Thus, for example, *he follows the course of the sun, and goes where no one but the sun has been*. Most important, in this connexion, is the account of the journey which he undertakes, after the death of Engidu, in search of the secret of immortality (IX., X.). We find him arriving at the mountain of Mâšu, ‡ where scorpion-men guard the entrance and exit of the sun. In spite of the terrible and death-dealing aspect of these warders, he prevails upon them to admit him through the gate; and he journeys for twelve double-hours along a route where the darkness is dense, until he emerges once more into the light of day. Here he finds himself in a garden in which grows the tree of the gods, the branches of which, formed of

* The cuneiform text of the Epic has been edited by Haupt, *Das babylonische Nimrod-Epos*. Transliteration and translation with notes by Jensen in *KB*. vi. pp. 116 ff.; Dhorme, *Choix des textes religieux assyr.-bab.*, pp. 182 ff., 100 ff. Translation and discussion by Ungnad and Gressmann, *Das Gilgamesch-Epos*. More or less detailed outlines by Jeremias, *Izdubar-Nimrod*; Zimmermann, *KAT*.³ pp. 566 ff.; Ungnad, *TB*. i. pp. 39 ff.; La., *ERS*.² pp. 342 ff.; Rogers, *CP*. pp. 80 ff.

‡ *Mâšu* = 'twin.' The mountain thus appears to be the twin- (double-peaked) mountain which appears in representations of the God Šamaš emerging through the gates of sunrise, which attendants throw open to him: cf. Pl. III., fig. 3.

precious stones, produce rare fruits. The custodian of this garden is the maiden Siduri-Sabîtu, who sits on a throne by the shore of the ocean. Gilgameš' aim is to cross this ocean, in order to reach the abode of his ancestor, Uta-napištim (the Babylonian Noah), who, after surviving the Flood, has, with his wife, been raised to immortality by the gods, and dwells beyond the ocean. He at least may be expected to possess the secret by which death may be escaped. In answer to the hero's inquiries as to the possibility of a crossing, Sabîtu replies :—

'O Gilgameš, there hath never been a passage,
And no one, from all eternity, hath crossed the ocean.
The warrior Šarvāš hath crossed the ocean ;
But save for Šarvāš, who shall cross ?
Difficult is the passage, laborious its course,
And deep are the waters of death which bar its access.
Why then, O Gilgameš, wilt thou cross the ocean ?
When thou arrivest at the waters of death, what wilt thou do ?'

The ocean, then, is the western ocean which is regularly crossed by the Sun in his journey towards the region of sunset. The narrative goes on to relate how, by the aid of Uta-napištim's mariner, Ur-Šanabi, Gilgameš succeeds in making the passage, and safely reaches the abode of his ancestor, from whom he learns the narrative of the Flood—with which in the present connexion we are not concerned.

Moreover, Gilgameš not only traverses the sun's path, but *he undergoes changes which indubitably illustrate the phases through which the sun passes during its yearly course.* In illustration of this we may quote first a most important passage at the commencement of Tab. VI., following immediately after the victory over Humbaba, of which only a fragmentary account survives in Tab. V.

'He washed his weapons, he furbished his weapons,
He caused his long hair to fall down upon his back.
He doffed his soiled raiment, he donned his clean raiment,
With . . . he clothed himself, and bound on a doublet ;
Yea, Gilgameš decked himself with his diadem, and bound on a doublet.

To the beauty of Gilgameš majestic Ištar raised the eyes ;

"Come, Gilgameš, be thou my spouse !

Thy fruit to me, I pray thee, yield !

Be thou my husband ; let me be thy wife !

Let me yoke for thee a chariot of lapis lazuli and gold,

With wheels of gold, with horns of diamond ;

Thou shalt yoke daily the great steeds.

Into our house enter thou mid the perfume of cedar.

Into our house when thou enterest,
 <They that sit on> thrones shall kiss thy feet ;
 Beneath thee shall prostrate themselves kings, lords, and
 nobles ;
 The . . . ? of the mountain and land shall bring thee tribute.”

Gilgameš rejects Ištar's advances, reminding her of the sad fate of former lovers whom she has quickly spurned and made the victims of various misfortunes through which their vital force is lost. As Jastrow *RBBA*. pp. 127 f.) remarks, ‘The tale is clearly a form of the general nature-myth of the union of sun and earth, which, after a short time, results in the decline of the sun's force. Tammuz, an ancient personification of the sun of the springtime, is named as the first of Ištar's lovers ; he becomes her consort and is then slain by the goddess and consigned to the nether world, the abode of the dead. The promise made by Ištar to Gilgameš to present him with a chariot of lapis lazuli, and to shelter him in a palace of plenty, unmistakably points to the triumph of the sun when vegetation is at its height. Tammuz and Ištar, like Gilgameš and Ištar, thus represent the combination of the two principles which bring about life ; and upon their separation follow decay and death.’*

In revenge for this rebuff, Ištar persuades her father Anu to send a heavenly bull to destroy Gilgameš ; but the beast is slain by the hero and his friend Engidu (cf. Pl. III. fig. 2). Gilgameš dedicates the horns to his god Lugal-banda, and returns in triumph to his city of Erech. Tabs. VII. and VIII. are unfortunately very fragmentary ; but enough remains for us to gather that Engidu is suddenly afflicted with some fell disease, and, after taking to his bed, dies at the end of twelve days. The cause of his malady does not appear from the text as it now stands ; but we are probably right in inferring that it was due to the curse of Ištar, following upon the failure of her first attempt to punish Gilgameš (cf. the account of Engidu's deliberate insult offered to the goddess, Tab. VII. ll. 178 ff.). Gilgameš' grief at the death of his friend is vividly portrayed at the end of Tab. VII. ; and from the beginning of Tab. VIII. we learn that its poignancy is increased by the thought that the same fate must ultimately overtake him also :

‘ Gilgameš for Engidu his friend
 Bitterly weepeth and wandereth through the desert :
 “ Must not I too die like Engidu ?
 Grief hath pierced mine inward part ;
 I fear death, and I wander through the desert.” ’

* The description of the chariot is (as Dhorme notes) strikingly similar to Ovid's description (*Metam.* ii. ll. 107 ff.) of the chariot of the Sun :—

‘ Aureus axis erat, temo aureus, aurea summae
 Curvatura rotae, radiorum argenteus ordo,
 Per juga chrysolithi positaeque ex ordine gemmae
 Clara repercusso reddebant lumina Phoebus.’

It is at this point that he forms the resolution to seek out his ancestor Uta-napištim, who by some means (as yet unknown to him) has gained immortality, and who may possibly be able to hand on the secret to him. He at once, therefore, sets out upon the journey which we have already outlined.

In the course of this journey, as indeed prior to it, those whom he encounters comment in identical terms upon the shocking spectacle which he presents : *

‘Why is thy strength consumed, thy face bowed down?
Thy heart is in evil case, thy features are perished,
And there is sadness in thine inward part;
Thy face is like that of one that hath journeyed far;
. . . distress and grief enflame thy face,
. and thou wanderest through the desert.’

To each of these inquiries he replies by asking why he should not appear thus, seeing that he has just lost so close a friend. It seems, however, to be clear that he is afflicted by something more than grief, and that in all probability the disease which has destroyed Engidu has fastened its hold upon him also. At any rate, when he reaches Uta-napištim, he is in a terrible condition, as appears from the words of his ancestor in which he directs the sailor, Ur-Šanabi, to take him to a washing-place where he may bathe and restore his health (xi. 251 ff.) : —

‘The man before whom thou didst walk,
Whose body is covered with boils,
The beauty of whose flesh is marred with scales—
Take him, Ur-Šanabi, to the washing-place bring him;
His boils in water let him wash (white) as snow;
Let him cast off his scales, and let the sea bear (them) away;
Fair let his body appear;
Let the turban of his head be renewed;
With a robe let him be clothed, his garment of modesty;
Until he come to his city,
Until he come to his own way,
Let the garment not become threadbare,† but let it be new—
be new!’

Uta-napištim’s directions are followed, and Gilgameš is able to make the return-voyage, reaching Erech in perfect health, and clad in fair attire. The account of his actually finding, and then through

* So, some one whose name has disappeared, viii. v. 7 ff.; Ur-Šanabi, x. iii. 1 ff.; Uta-napištim, x. iv. 42 ff. There is every reason to suppose that the same inquiry should be restored and put into the mouth of Siduri in x. i. 33 ff.

† Lit. ‘throw off grey hair,’ i.e. perhaps, its surface-wool, or, as we might say, *lose its nap*. A different explanation is given by Haupt, *A/SL*. xxvi. (1909), p. 16.

an accident losing, the magic herb by means of which he might have secured immortality, does not concern our present purpose.

Here, then, we have, in a parable the inner meaning of which is transparently obvious, an account of the sun's triumph in springtime, followed by its gradual decline in force as it starts on its long journey towards the waters of death. This culminates in the last stage of disease when it reaches its goal, where it undergoes a process of lustration, so that, when it appears once more in the east, it possesses its original beauty and glory. The meaning of the story of Engidu, who actually dies as the result of Ištar's malice, may perhaps not be affirmed with equal certainty; but the whole trend of evidence goes to suggest that he is a chthonic deity, typifying the reproductive vigour of animal-nature in the springtime, which dies away as the year passes onward on its course.*

Were it necessary to add anything in support of this clear evidence that Gilgamesh is a solar hero, it might be found in the material which

* This is suggested by the description of his early life as a companion of the beasts of the field, and by the satyr-like form—half man and half bull—in which he is represented upon early seal-cylinders: cf. Pl. II. fig. 5; Pl. III. fig. 2. He is described in I. iv. 6 as *lulā amēlu* 'the man of animal-desire.'

It is a hopeless task to attempt to construct a wholly satisfactory and consistent explanation of the cosmology of the Gilgamesh-epic; Cf., on this subject, Jeremias, *Izdubar-Nimrod*, pp. 66 ff.; Jensen, *Das Gilgamesch-Epos*, pp. 77 ff.; Zimmern, *KAT.*³ pp. 566 ff.; Dhorme, *Choix des textes religieux assyr.-bab.*, pp. 271 f., 278 f.; Ungnad and Gressmann, *Das Gilgamesch-Epos*, pp. 154 ff. The view that the twelve tablets present us with the sun's doings during the twelve months of the year, and that each of these is associated with its appropriate zodiacal sign, seems to be improbable. It may be worked out in a few instances, but breaks down in the majority. Thus, Tab. III., which relates the beginning of the adventures of Gilgamesh and Engidu, might stand for *Gemini* (though the cementing of the friendship between the two heroes takes place as early as the end of Tab. I.); Tab. VI. which contains the Ištar-incident might stand for *Virgo*; and, most strikingly, Tab. XI., the Flood-narrative, for *Aquarius*. If, however, the creation of Engidu, who, as we have already remarked, is figured as half bull, represents *Taurus*, we should expect to find the account of this in Tab. II. and not in Tab. I.; and the Scorpion-men of the mountain of Māšu (*Scorpio*) should appear in Tab. VIII. rather than in Tab. IX., unless indeed they stand also for *Sagittarius*: cf. the representation of a scorpion-man as an archer on an ancient boundary-stone (v. R. 57; *OTLAE*. i., fig. 2, p. 11), and also on the seal-cylinders figured by Delaporte, *Cylindres orientaux*, Pl. XXI. figs. 313, 316. Probably the truth is that some of the incidents in the Epic do represent the course of the sun through the zodiacal stations, but not (at least in the form in which the Epic has come down to us) in any consistent order, or, at anyrate, in an order which is marked by the twelve tablets into which the poem is divided.

Again, it seems probable that the incidents of the poem typify not merely the yearly course of the sun, but that there is a combination of the yearly and daily courses which it is difficult or impossible to unravel. Gilgamesh's adventure at the mountain of Māšu, where he starts a journey of twelve double-hours over the route of the sun—*harran (ilu) Šamši*—is most naturally to be understood of the daily circuit of twenty-four hours; though, in view of the fact that all the way the darkness is dense, and it is only at the end of the journey that he emerges into the

is supplied by the ancient seal-cylinders of Babylonia. On these we not infrequently find the figures of Gilgameš and the Sun-god used interchangeably in precisely similar settings. One such series is illustrated on Pl. II. Here in figs. 1 and 2 we have a figure described in pictographic writing as *ilu Šamaš*, who contends with antelopes and lions. In fig. 3 Gilgameš likewise contends with the same animals, the arrangement of the figures being identical with that of figs. 1 and 2. That the central figure in fig. 3 is intended for Gilgameš is indicated by his full-face representation (peculiar to figures of Gilgameš and Engidu), and by the arrangement of his hair in six locks; cf. the Gilgameš-figures on Pl. III figs. 1, 2. There are similar series which are no less significant.*

light 'before the sun,' we should expect the reference to be to the *nocturnal* course of the sun from west to east, which should rather occupy six double-hours or twelve hours. His journey across the ocean with Ur-Šanabi occupies one month and fifteen days before he comes to the waters of death. Since the condition in which we find him at this point, in the last stage of disease, can hardly denote anything else than the winter-solstice, when the power of the sun is at its lowest ebb, it may be that this voyage represents the half of the winter-quarter; the corresponding half being occupied by the return of the sun after purification in a condition to renew once more his yearly course.

It is impossible, again, to attain any degree of certainty in attempting to define the conception of the Epic as to the earthly counterpart of the heavenly course of the sun. Jensen places the cedar-mountain where the hero and his friend conquer the giant Humbaba among the mountains of Elam to the east of Babylonia, over which the sun rises. Thence Gilgameš reaches his city of Erech where he is at the climax of his glory. From this point Jensen would make him pursue his course due west across the Syrian desert to the Lebanon and Anti-Lebanon, which he regards as the twin-mountain of Māšu, and over the whole length of the Mediterranean Sea to the waters of death—the Atlantic. This view is adopted by Zimmern; though it is difficult to see how the Atlantic can have come within the Babylonian horizon. Of course Jensen and Zimmern have the Pillars of Hercules in their minds; but the Phoenicians must surely have been the earliest Semitic traders to get so far west. Other scholars find the name Māšu in the Syro-Arabian desert, which Ašurbanipal calls the land of Maš, and describes as 'a place of thirst and languor, wherein no bird of heaven flies, nor do wild asses and gazelles graze there': cf. *KB*. ii. p. 220; Delitzsch, *Paradies*, pp. 242 f. Across this they would make Gilgameš travel not due west but south-west, till he reaches South Arabia, where dwells Siduri who is termed Sabitu, *i.e.* on this interpretation 'the Sabaean': cf. Hommel, *AHT*, pp. 35 f. This perhaps agrees better with the sun's course as viewed from the northern hemisphere—not due west across the zenith, but south-west. Yet the theory of a very early date for the origin of the Sabaean kingdom is now not regarded as probable.

* Cf., in Delaporte, *Catalogue des Cylindres orientaux . . . de la Bibliothèque Nationale*, Pl. IV. fig. 41, a figure described as *ilu Šamaš* in conflict with a human-headed bull; Pl. V. fig. 43, a similar figure unspecified contending with the same human-headed bull, in company with Engidu contending with a lion; fig. 45, Gilgameš with the human-headed bull (duplicated), and Engidu with the lion; fig. 44, Gilgameš with the human-headed bull *together with* a figure like that of fig. 43 contending with another bull of the same kind, and Engidu with the lion. We may notice also, in Hayes Ward, *Cylinders . . . in*

The adventures of Gilgameš and Engidu form favourite subjects for representation on seal-cylinders in the Sumerian and early Semitic Babylonian period, as well as in later times. The heroes are most commonly depicted in conflict with beasts—either Gilgameš attacks a wild bull or water-buffalo while Engidu is similarly engaged with a lion, or Gilgameš by himself is seen in conflict with the latter beast: cf. Pl. II. fig. 4; Pl. III. figs. 1, 2. In spite of the fragmentary condition of parts of the Epic, it affords us ample evidence that the two heroes were mighty hunters.*

The space which we have devoted to the Gilgameš-epic may seem to be out of all proportion to its importance in relation to the story of Samson; but this is not really so. In the first place, it has enabled us to establish the fact of the existence of a Semitic solar myth in a form of which the significance is incontrovertible, and the widespread influence of which in countries adjacent to Babylonia can easily be demonstrated. In Pl. IV. we have Gilgameš as pictured by the Assyrians; Pl. V. illustrates the fact that the hero and his companion were familiar to the Hittites of Carchemish; Pl. VI. exhibits the movement of the same myth westward to Cyprus, the colossal figure clearly exhibiting Assyrio-Babylonian influence in the treatment of the beard and hair (cf. p. 498), and in the manner in which he is rending the lion.† This last figure is probably rightly identified with the Phoenician Melkart, whose influence on the Greek myth of

the Library of J. Pierpont Morgan, Pl. v. fig. 22, a figure marked *ilu Šamaš* attacking a lion by seizing its tail and one hind leg and placing a foot on the back of its neck; Delaporte, *op. cit.*, Pl. III. fig. 22, Gilgameš attacking a lion in precisely the same way (duplicated); cf. also Pl. II. fig. 21.

* Sayce, *ET*. xxiv. (1912) p. 39, in endeavouring to identify the hero of the seal-cylinder representations with a supposed Namra-Uddu (*i.e.* the Biblical Nimrod) and *not* with Gilgameš, makes the assertion, 'Gilgameš was not a hunter, and he never struggled with lions or held slaughtered animals in his hands.' This statement strangely overlooks the words which are addressed to Gilgameš in VIII. v. 5,

' <In the passes> of the mountain thou didst slay lions,'

as well as the refrain of the hero's lament over Engidu (cf. X. v. 11),

' <My friend who with me> slew the lions, etc.'

Cf. also, in Gilgameš' description to Uta-napištim of the difficulties of his journey (X. v. 31 f.),

' The *kāsu*-bird, the *bušu*-bird, the lion, the panther, the jackal(?), the stag, the ibex, the wild bull,

Their <flesh> I eat, and with their skins I <clothe myself>.'

It is highly probable that one of the Tabs. III., IV., or V., which are very fragmentary, originally contained an account of a lion-combat, possibly corresponding to the zodiacal station *Leo*.

† Cf. the representation of Engidu and the lion in Pl. II. fig. 4.

Herakles in many of its details can scarcely be gainsaid.* The proved existence of such a solar myth is the most weighty fact which can influence our decision as to whether solar elements do or do not enter into the Samson-tradition. In comparing Samson with Gilgameš in our search for solar traits, we are not bolstering up the merely hypothetical interpretation of one series of traditions by the scarcely less hypothetical interpretation of another series; but we are testing the former series by that which, in the latter, may be regarded as a well-ascertained conclusion.

In the second place, for a right estimation of the character of the Samson-narrative, it is as important to notice the *contrast* which it offers to the Gilgameš-epic as it is to register the points of resemblance between the two stories. The Gilgameš-epic as a whole (and this is also true of the Herakles-saga) moves in a plane which is wholly mythical. Gods and goddesses take their part in the sequence of events like ordinary mortals. The hero and his friend are distinguished as semi-divine by the use of the determinative prefix *ilu* 'god,' before their names. Indeed, the fact that Gilgameš possesses a divine strain in his blood is more than once emphasized in the Epic (I. ii. 1; IX. ii. 16) by the statement

'Two-thirds of him are god, and his third part is human.'

* Wilamowitz-Moellendorf, in his edition of Euripides, *Herakles*, i. p. 276 (1st ed., 1889), dismisses the theory of the derivation of the Greek Herakles from old Babylonian sources with great contempt, having clearly never taken the trouble to investigate and appreciate the evidence which can be advanced in its favour. Later on (pp. 290 ff.) he goes on to enumerate the earliest elements in the Herakles-myth as follows:—(1) the descent of the hero from the highest gods; (2) the conflict with the lion; (3) the conflict with giants; (4) the journey to the Underworld, and the conquest of death; (5) the journey to the garden of the gods. As a matter of fact, as Jeremias (*Izdubar-Nimrod*, pp. 70 ff.) points out, these are the very incidents which can be most strikingly paralleled from the Gilgameš-epic. In his 2nd edition (1895) Wilamowitz-Moellendorf makes grudging concession to Jeremias that 'the resemblance of Herakles to "Izdubar-Nimrod" is of course remarkable in the highest degree (allerdings höchst merkwürdig). Naturally this also struck the ancients, and necessarily led to identification, as e.g. the Cyprian representation of the Geryones-adventure demonstrates: *Journ. of Hell. Stud.*, xliii. 74.' It may be observed that this concession does not touch Jeremias' point that the *earliest* elements in the Herakles-myth (*teste* W.-M.) are those which find closest parallel in the Babylonian-myth.

Jeremias further remarks that it is reasonable to hold that, just as we have the series Ištar—'Ashtart—Aphrodite, so we also have the series Gilgameš—Samson—Herakles; a conclusion which may be accepted with substitution of the Phoenician Melkart for the Israelite Samson, the conception of whom can hardly have had any direct influence on Greek mythology. The line of transference was probably Babylonian—Phoenician—Greek; while Samson, as is argued above, seems to represent a lateral development of the myth in a very diluted form. Herodotus (ii. 44) states that he visited the temple of Herakles at Tyre; and that this was of very great antiquity, being said to be contemporary with the foundation of the city, which he places at 2300 years before his time. That this Herakles was the god Melkart (*i.e.* 'King of the city') admits of no doubt.

The world in which events are enacted is not our world ; or at any rate it is ours only in a very remote and symbolical sense.* The Samson-narrative (and here we are referring to *chs.* 14-16, apart from the later-added *ch.* 13) is markedly different. Samson indeed performs prodigies of strength which are incredibly marvellous ; but the *whole setting* of the narrative, so far from being artificial, is as fresh and true to life as almost anything contained in the O.T. It leaves us no doubt that we are breathing the natural atmosphere of the border-country between the Israelites and Philistines, and are witnessing scenes of social intercourse such as must have been of everyday occurrence at the period with which the narrator deals.†

Again, the author of the Gilgamesh-epic was an educated man of great literary ability.§ He had evidently reflected much on the problems of life and death ; and, had we had occasion to refer to his speculations as to human mortality, we might have quoted passages of wonderful beauty and pathos. He seems to have been versed in the astronomical knowledge of his day. The *technique* of the poem is highly developed, and its descriptive power (as witnessed *e.g.* by the Flood-story) of a very high order. In contrast, the charm of the Samson-narrative lies in its artlessness, and in the fact that it comes straight from the lips of the rustic story-teller, whose sole equipment consisted in a retentive memory, a sense of humour, and a native power of description. Whether it be possible or not to explain every detail of the Gilgamesh-epic as an integral part of the solar myth, there can be no question that this method, if applied to the Samson-narrative, goes very widely astray. The whole narrative is so intimately bound up with the occurrences of everyday life, and quite possibly with the actual doings of an historical individual, that the fallaciousness of such a method is self-evident.

Thus it is clear that the difficulty of distinguishing the solar traits in the Samson-narrative is very considerable. A particular incident may bear resemblance more or less close to a characteristic *motif* in the stories of other solar heroes ; but unless it is impossible to regard it as an actual incident which may have occurred in real life, its interpretation as a solar trait must remain extremely precarious. To take a single example : Samson slew a lion single-handed, and so did Herakles, and Gilgamesh very possibly slew several ; but, again, similar incidents are recorded of David (1 Sam. 17^{34 f.}) and Benaiah (2 Sam. 23²⁰) ; and we have, in these latter instances, no ground for regarding the feat as other than historical, because it is the kind of feat that a strong and brave man might reasonably accomplish.

Bearing these considerations in mind, we may proceed to notice

* Cf. the last paragraph of the first *footnote*, p. 400.

† Cf. the remarks on p. 339.

§ In speaking of the author, in the singular, it is not intended to express any opinion as to the unity, or composite character, of the Epic. All that is affirmed is true of the Epic as a whole, whether it be the work of one or more authors.

certain points in the Samson-narrative which may very well owe their origin to solar mythology.

Among these the most striking is the conception that the strength of the hero lies in his long hair, and that when this has been shaved off he becomes powerless; just as the sun when adorned with his rays (which are pictured as hair in the literature of all nations*) is endowed with great strength, but sinks into weakness when he loses these in the winter-season. We have noticed how Gilgameš, when he figures as the glorious sun of springtime, is said to wear his long hair falling down his back; and this hair is prominent in early seal-cylinder representations of the Babylonian hero, arranged in six curling locks which fall on either side of his head (cf. Pl. II. figs. 3, 4, 5; Pl. III. figs. 1, 2), with which we may compare the six rays which are depicted as issuing from the shoulders of the Sun-god (Pl. III. fig. 3). Samson's hair was also arrayed in locks, though these were seven and not six.† We are not definitely told that Gilgameš loses his long locks when his strength fails him and he becomes the victim of disease, § though, since they are so prominently mentioned as a mark of his beauty when at the height of his youthful power, it is perhaps not an unfair inference that he is to be pictured as deprived of them in his affliction (cf. the remarks as to his changed appearance quoted on p. 398). When he is washed clean and free from disease 'the turban of his head' || is renewed; but no mention is made of his locks, which, if they were lost, must be pictured as gradually growing again. The sun does not arrive at its full strength and glory at the turn of the year. Samson's hair began to grow again after it was cut off, but some time elapsed before he was able to put forth his pristine strength. In the *note* on *ch.* 13⁵ we have observed how ill the conception of the author of this chapter that Samson was a Nazirite fits in with the portrait of him which is to be gathered from the older *chs.* 14-16, and have concluded that the view that he was under such a vow must probably be regarded as a later interpretation of the meaning of his long locks. If we are right in explaining them as an ancient solar trait, we can now understand why the author of *ch.* 13, who endeavours to view Samson and his

* Cf. the admirably full body of evidence collected by Smythe Palmer in *ch.* iv.

† We have noticed above (*note* on *ch.* 16¹³) that the statement that Gilgameš wore his hair in *seven* locks, which seems to emanate from Jeremias (cf. *OTLAE.* ii. p. 172), is incorrect. For the possible meaning of Samson's *seven* locks, cf. the conjectures put forward by Smythe Palmer, *ch.* v., who cites instances of the Sun-god depicted as adorned with *seven* rays, the most striking of which is perhaps the Pompeian wall-painting figured by Roscher, *Lexikon der griech. u. rom. Mythol.*, 2003.

§ Smythe Palmer's statement (p. 221) that when Gilgameš 'begins to fail and fall ill' he 'loses his hair in which lay his strength,' unfortunately goes beyond his facts as they may be gathered from the Epic. It is an inference merely.

|| Bab. *parsigu* ša *kaḫḫadišu*. The term *parsigu* is used elsewhere of a *bandage*.

doings from the standpoint of a pious Yahweh-worshipper (cf. p. 338), should have read a different meaning into this characteristic.

Much more doubtfully significant as a solar trait is Samson's slaying of the lion, though greatly emphasized as such by many writers; because, as we have already remarked, it is the kind of deed which might naturally have been performed by a strong man, or might naturally be ascribed to him, without the involving of any symbolical meaning. The term which is used to describe the hero's *rending* of the lion *does* seem, however, to suggest connexion with the Gilgamesh-myth: cf. *notes* on *ch.* 14⁶. A similar connexion may possibly be traced in the fact that the incident occurs early in Samson's career and immediately prior to his being ensnared by the charms of Philistine womankind, which leads to his ultimate undoing. Gilgamesh' lion-slaying feats must, as we have noticed,* have occurred a little before the Istar-incident which marks the beginning of the hero's misfortunes.†

A much clearer trace of solar mythology is to be found in the story of the bursting forth of the spring at Ramath-lehi to satisfy

* Cf. *footnote* *, p. 401.

‡ The present writer can attach no weight at all to Steinthal's theory that the story of the honey in the lion's carcass belongs to the solar myth with the symbolical meaning that, when the sun is in the zodiacal sign *Leo* (i.e. in July), honey is most plentiful. This theory is built up upon a series of assumptions, any one of which is open to question. It is assumed that no other explanation of bees building in a carcass is satisfactory; whereas, as we have seen (cf. *note* on 14⁸), this may be explained either by the supposition that the carcass was hollow and sun-dried, or by the *βουγυρία*-theory. Again, the claim that this explanation offers the Philistines a possibility of solving the riddle, which is otherwise insoluble apart from a knowledge of the facts, can hardly carry weight. Samson's wit was not of so high a class that he must be deemed incapable of a very bad, and so, unfair riddle; especially as the story makes it clear that he was confident that he would win the wager. And lastly, the assumption that July is the month when honey is most plentiful seems to be based upon experience of the habits of bees in the temperate regions of Europe where flowers abound throughout the summer, and to overlook the fact that in the sub-tropical climate of Palestine the flowering season ceases and herbaceous vegetation is burnt up by about the middle of May, after which (presumably) the bees are living on their store of honey, and the supply is gradually *decreasing*.

Steinthal's further conjecture that Samson's slaying of the lion typifies the milder sun of autumn extinguishing his own burning rays (the lion representing the fierce heat of midsummer) is in itself so incredible that it requires no refutation. It may be noticed, however, that it seems to involve a kind of *hysteron-proteron*; for the autumnal sun stifles the heat of midsummer *before* the bees—which typify the fact that honey is plentiful in midsummer—establish themselves in the carcass.

At the same time, the fact is undoubted that in Babylonian mythology the lion is closely associated with the god Nergal, who typifies the hot sun of midsummer; the choice of this animal being no doubt dictated by its fierce and destructive disposition, its tawny colour, and its shaggy mane which suggests not remotely the rays of the sun.

Samson's need. Abundant evidence exists in proof that springs—and especially hot springs—were associated with the sun or with solar heroes.* Athenaeus (xii. 512) states that all hot springs which break forth from the earth are sacred to Herakles: cf. also Diod. Sic., iv. 23, v. 3; Strabo, pp. 60, 172, 425, 428; Livy, xxii. 1; *al.* The original idea seems to have been that such springs are warmed by the sun during his nocturnal course under the earth. Cf. especially the account given by Herodotus (iv. 181) and Lucretius (*De Rerum Natura*, vi. 848 f.) of the spring of the sun in the oasis of Ammonium (Siweh) in the Libyan desert, which is cold by day but boiling hot at night. The point is interesting as definitely connecting Herakles with the sun. In some cases at any rate (cf. Diod. Sic. *loc. cit.*) the traditional connexion with the solar hero was that the springs had been caused to burst forth in order that he might bathe in them when weary.

That cold springs were also associated with the sun by the Semites is proved by the occurrence of the name 'En-shemesh 'the spring of the sun,' Josh. 15⁷, 18¹⁷—the modern 'Ain el-Hôd 'the Apostle's spring,' a little east of Bethany on the road to Jericho; and 'Ain-šems, the modern Ar. name of Beth-shemesh. Whether the hero bathes in the warm spring, as does Herakles, or drinks from the cool spring, as does Samson, the effect is the same, viz. the restoration of his vitality which through weariness or faintness has reached a low ebb. The conception seems to be bound up with the restoration of the sun's power in the springtime: cf. the way in which Gilgamesh has to bathe in order to free himself from his disease and renew his beauty—a figure which, as we have seen (pp. 398 f.), typifies the renewal of the sun's powers after he has reached his lowest ebb at the winter-solstice.

If any weight may be attached to our suggestion (*ch.* 15¹⁰ *note*) that, in the name 'Ēn-haḳ-ḱōrē given to the spring of Lehi, ḱōrē originally denoted not the partridge but the *quail*, we seem here to trace the combination of a kindred mythical conception as to the return of the sun in springtime. The reason why the quail was sacrificed by the Phoenicians to Herakles-Melkart in the early spring, and the reason why Herakles was thought to have been restored to life by smelling this particular bird, was that the quail was the bird which—as its Greek name ὀρνίς, Sanskrit *Vartikā* 'the returning one,' denotes—was *par excellence* the migrant whose reappearance heralded the return of the sun in the spring. Hence, according to Max Müller (*Science of Language*, ii. p. 506) is derived Ortygia (the name of the island which was otherwise called Delos 'the bright'), which was regarded as the birthplace of Apollo, the young Sun-god of springtime.

The incident of Samson's removal of the gates of Ġaza, and his

* Cf. the evidence brought together by Smythe Palmer, *ch.* xi.

on a hill to the east of Hebron, is probably connected with the conception that the sun, in rising, issues through a door with the conception of the extremity of the eastern horizon. Cf. the representation of the Sun-god Šamaš passing through such gates, which are held open for him by attendants: Pl. III. fig. 3. The subject is frequently figured on Babylonian seals. Samson's conception which he moves through after spending the night in company with his paramour rising in Ps. 19⁵ (M⁶):

sun at his

he is like a bridegroom issuing from his bridal chamber;

'And he rejoiceth like a mighty man to run the course.'

He r

to look for any symbolical meaning in the names Gaza

It is reasonable, these particular cities being probably merely part of the and Hebron of the story. It is possible, however, that some particular local setting of Hebron may have acquired a name as the hill over which, from the Shephelah, the sun was regularly observed to rise.

which, from the story of Samson's paramour, Delilah, is of some importance

The name almost certainly the influence of Babylonian thought as exhibiting a comparison with the Bab. proper names *Dalil*-(*ilu*)-

upon the story of *Ištar*,* 'worshipper of Ištar,' though (so far as the *Ištar*, *Dilil*-(*il* knows) it has not before been made, is obvious.

present writer 'shipper' or 'devotee,' may be assumed to be a hypo-

Delilah, 'worshipper' full form *Delilat-Ištar* (or 'Aštar).† As applied to

characteristic for the connotation of this name (at least according to the

a woman, the of the tale) can hardly be mistaken. Delilah must

original form of a prostitute devoted to the service of the goddess

have been a sacred prostitute (*ḫadištu*, *ḫarimtu*, *šamḫatu*, or *kazratu*). The

(Heb. *ḫēdēšā*, of these consecrated female worshippers with Ištar

close connexion with Gilgamesh is illustrated by the Epic in the

in her relations VI. 184 ff. We may compare also Tab. I. iii. 1 ff.,

narrative of Tab. I. living the life of a wild man among the beasts

where Engidu, who was led away by the attractions of such a *ḫarimtu* and

of the field, is decivilized. It is Samson's relations with Delilah

adopts a life of civil life of his undoing, just as it is through Ištar that

which prove the cause are brought about. We may compare the way

Gilgamesh' misfortune:

; *Alphabetisches Verzeichniss der Assyrischen und*

* Cf. T. N. Strassmaier, 1975.

Akkadischen Wörter, 1835 course, common in Heb. proper names: e.g. Nathan

† Such a contraction is, of course, 'used' (sc. of Yahweh).

for Nathan'el, or Baruch, 'Blessed' an active participle, while *Dilil* in the cognate

In *Dalil*-(*ilu*)-*Ištar*, *Dalil* is a 'worship' for 'worshipper.' Heb. *Delilā*

form appears to be a substantia passive form; but this is not necessarily so,

might appear at first sight to be the form *ḫātil* may result from an original

since, as G-K. § 84^{al} points out, the form *ḫātil*. At the same time it is likely that

active *ḫātil* as well as from a passive of the word (Bab. *dalālu* properly = 'to

submit one-self') would favour the derivation.

in which the hatred of Hera is the prime cause of the labours and sufferings of Herakles.

Possibly, though not certainly (since the incident^t is one which might very well have happened in real life; cf. p. 403), the story of Samson as a blinded captive grinding in the prison-house may have a solar significance, based on the fact that the sun, powerful as he is, yet covers the same beaten track day after day, and so may be conceived to be the victim of some external compulsion, which obliges him to perform the same allotted task daily without variation. If, as seems probable, the mill at which Samson grinds is to be pictured, not as a small hand-mill, but as a large mill, which is ordinarily turned by an ox or ass which travels round and round in an unvarying track, the analogy is the more striking. Probably the same idea lies at the root of the story that Herakles was under compulsion to perform his labours at the bidding of the weak and tyrannical Eurystheus.

Finally, the account of Samson's death can hardly be dissociated from the solar myth. The point has been so thoroughly illustrated by Smythe Palmer (*ch.* xv.) that it is needless to treat it at length. By pulling down the western pillars which were thought to support the vault of heaven* (Job 26¹¹), the sun overwhelms himself and the world with the darkness of night. The idea is aptly illustrated by Homer's description of sunset (*Il.* viii. 485 f.):

ἐν δ' ἔπειτ' Ὠκεανῷ λαμπρὸν φάος ἡέλιος,
ἔλκον νύκτα μέλαιναν ἐπὶ ζείδωρον ἄρουρα.

The red glow of sunset probably suggested the idea of a great carnage wrought by the downfall of the sky-temple; just as, in the Herakles-myth, it suggested the conception of the hero's glowing funeral-pyre on Mount Oeta. In the words of Smythe Palmer—'We may suppose, then, that some such thoughts as these were present to the primæval gazer on the changing drama of sunset. See! the mighty sun has fallen! His enemies were too strong for him! In dying, he has dragged down the bright sky after him! The pillars of heaven are broken and darkness comes crashing down! But see! the place where he fell is red with the carnage of his foes! The clouds which obstructed him and exulted over him are ensanguined—involved with him in a common ruin!' (*op. cit.* p. 180).

17. 1-18. 31. *The story of Micah and the Danites*

The fact that this narrative is composite is very evident; and it can hardly be doubted that we have to do with two originally independent parallel narratives (so Vatke, Ber., Bu., Mo., etc.), rather

* We may compare the pillars set up by Hercules at Gades, the westernmost point of the then-known world.

† To Vatke (*Die biblische Theologie*, 35, p. 268) belongs the credit of first

than with a single narrative which has undergone extensive interpolation (Wellh.,* Kue., La., Gress.). It is not, however, always easy to disentangle the strands with any certainty, probably because the two versions of the story were originally closely similar in detail.

According to 17¹⁻⁴, Micay^{hu} (מִיכָיָהוּ) restores the stolen silver, which is then made into a graven image (and a molten image). The idol (or idols) is placed in Micay^{hu}'s own house. In 17⁶, however, we are told that the man Micah (מִיכָה a shorter form of מִיכָיָהוּ) already possessed a temple (בֵּית אֱלֹהִים), for which he made an Ephod and Teraphim, and installed one of his sons as priest. Here we note that the graven image and molten image of 17³⁻⁴ stand over against the Ephod and Teraphim of 17⁶; and the inference that the one pair may be peculiar to the first narrative (which we may term A), while the other pair is peculiar to the second narrative (provisionally called B), is confirmed, rather than the reverse, by the curious way in which all four are mentioned together in 18^{14,17,18}, and three of them in 18²⁰—passages which have all the appearance of having been filled out by a redactor. In 18^{30,31} the graven image is mentioned by itself, just as it occurs without the molten image in 18²⁰; and this fact, taken in connexion with the fact that the verb וַיְהִי 'and it was' in 17⁴ seems clearly to refer to *a single idol*, and not to two (graven image *and* molten image), suggests (as perceived by Mo.) that the narrative A originally referred to a graven image only, and that the molten image is a late interpolation, possibly made in view of the fact that the silver was handed over to a 'smelter' (צֹרֵף).

Further, it can hardly be doubted that 17⁷⁻¹³ combines two accounts of the appearance of the Levite on the scene. In 17⁷ he is introduced as 'a youth' (נֶעָר) who was a Levite, who happened to be sojourning 'there'—*i.e.*, obviously, in Micah's village or the near neighbourhood of it. In 17⁸, however, where he is termed 'the man' (הָאִישׁ), he sets forth from Bethlehem of Judah to sojourn where he may find employment, and chancing to arrive at Micah's home, he is hired by him as priest (זוּז. 8-11a). The terms in which Micah, in v.¹⁰, invites the Levite to become to him 'a father and a priest' appear absurdly inappropriate if the latter was very young, as is implied by the term *nā'ar* used in v.⁷, which denotes little more than a mere boy.

perceiving that our story, as it stands, contains repetitions and discrepancies which are only to be explained by the hypothesis of the combination of two parallel narratives. He correctly perceived that the *sacra* are differently described in the two narratives, though erring in the supposition that the wandering Levite appears in one narrative only, his place in the other being taken by Micah's son (*ch.* 17⁵), who is the Jonathan of *ch.* 18³⁰ of the *tribe* of Manasseh. The general outline of the two stories is briefly indicated by Vatke, and not worked out in detail. Mo. (*Comm.* pp. 367 f.) gives a convenient summary of the analyses adopted by different scholars.

* In an appendix to *Comp.*³ (pp. 363 ff.) Wellh. adopts the theory of two parallel narratives.

As a matter of fact, in *v.*^{11b}, where the term *nā'ar* is next used, it is stated that 'the youth' became to Micah 'like one of his sons.' We have here, then, a clear mark of differentiation. According to 17^{7.11b.12a}, a youthful Levite of the clan of Judah [is adopted or hired by Micah] and becomes like one of his own sons, being installed as priest. According to 17^{8-11a.12b.13}, a Levite from Bethlehem of Judah, of mature age, is travelling in search of employment when he receives an offer from Micah which he accepts (*v.*^{11a}), and takes up his abode in his house (*v.*^{12b}).^{*} Micah then congratulates himself (*v.*¹³) on having obtained the services of a *Levite*—clearly as opposed to those of his own non-Levitical son (*v.*⁵). This last point indicates that 17^{8-11a.12b.13} belongs to the narrative B, to which we have assigned *v.*⁵; hence 17^{7.11b.12a} is to be assigned to A, to which it is quite suitable.[‡]

We have thus accounted for the whole of *ch.* 17 except *v.*⁶—a statement which, repeated as it is, in whole or in part, in 18^{1a}, 19^{1a}, 21²⁵, is clearly editorial, inserted for the purpose of explaining a condition of religion and morality which, from the editor's own standpoint, was a very low one. Whether this editor is the pre-exilic redactor of the old narratives (R^{JE}), or the post-exilic redactor who added the Appendix (*chs.* 17-18, 19-21) to Judg., may be considered an open question. In the view of some scholars (*e.g.* Kue., Bu., Cor., Driver, *LOT*.⁹, Cooke) the form of expression used by the editor implies without a doubt that when he wrote there *was* a king in Israel, and that therefore his standpoint is earlier at any rate than the close of the Judæan monarchy. Such a conclusion is questionable. It is obvious that an exilic or post-exilic editor, surveying the course of Israel's past history, may equally well have drawn a distinction between pre-monarchic and monarchic times, regarding the former in comparison with the latter as an unsettled and disorganized period. Further, the occurrence of the statement in 17⁶ is clearly called forth by the (from the editor's point of view) irregularities of cultus which the old narrative relates—the use of images, etc., in Yahweh-worship and the appointment of a non-Levitical priest. Is it likely that R^{JE}, living, as we must assume, at or about the time of the idolatrous reign of King Manassah, would have explained such irregularities by the fact that the kingship had not yet been established, regarding the kingship as a moderating and restraining influence, favouring a relative

* The reason why this half verse is referred to this narrative rather than to the other is that we are told in 18^{15a} that the youthful Levite had a house of his own.

‡ It is possible that *v.*^{12aa} may belong to B, leaving only the words 'and the youth became his priest' to A. This is a point which it is impossible to settle decisively. The words 'from Bethlehem of Judah' in *vv.*^{7.8} belong to B; cf. *v.*^{9b}. A's description of the Levite's native place is given more vaguely in the words 'of the clan of Judah,' *v.*⁷. We may infer, then, that the second occurrence of 'from Bethlehem of Judah' (*v.*⁸) is redactional, in order to explain the reference 'from the city,' after the intervening words in *v.*⁷ from A.

purity of cultus? Such a view is surely more closely allied to the constitutional and priestly aspect of religion which we see *e.g.* in a post-exilic writer like the Chronicler, than to the highly spiritualized aspect which characterizes prophetic thought in the seventh century B.C. Again, the position occupied by the statement in 21²⁵, rounding off a composite narrative which admittedly contains a large post-exilic element, suggests that it, like other redactional matter in the narrative, is due to R^p.

The explanatory note in 18^{1bβ} ('for there had not fallen, etc.') has the appearance of a late addition. 18^{1ba} is naturally continued by 18². In 18^{2a}, however, the description of the spies who are sent out by the Danites is somewhat unwieldy, and may well be composite. Comparison of 18^{11a} suggests that the words 'from their whole number, men of valour' are alien to the rest of the description; for by their excision this latter tallies exactly with the description of the band of warriors in *v*.^{11a}. In continuation, the words 'to spy out the land and to explore it' seem to be redundant by the side of the following 'and they said unto them, "Go, explore the land"'; and in view of the established fact that we are dealing with two parallel narratives, we may suspect that these are parallel passages from the two sources. The main strand of 18^{2a} is marked as B by its parallelism with 18^{11a}; and by the fact that it seems properly to be continued by 18^{2b}, which belongs to that source. Thus the two insertions, 'from their whole . . . valour,' 'to spy out . . . explore it,' are left by inference to A, to which the phrase 'to spy out, etc.' seems to belong in *vv*.^{14a, 17a}.

In 18^{2b} the spies arrive at Micah's house and spend the night there; but in 18³ it is when they are *near* the house of Micah (עַם בֵּית מִיכָה) that they happen to recognize the voice of the youthful Levite, and this causes them to *turn aside* thither (וַיִּסְּרוּ שָׁם), *i.e.* arrests them on their journey, and turns them out of the way. Clearly, then, 18^{2b} and 18³ are from different sources; and it is interesting to observe that the former is connected with B by the rather curious use of the prep. עַד in the phrase 'as far as (lit. *up to*) the house of Micah,' exactly as in 17⁸, 18^{13b}; and the latter with A by its reference to 'the youth, the Levite'; cf. 17^{7, 11b, 12aβ}, 18¹⁵.

The dialogue in 18^{3b-6} may be suspected of containing elements from both narratives. In *v*.^{3b} the final question 'and what is thy business here?' is perhaps redundant after the question preceding. If, as there is no reason to doubt, the first two questions connect with *v*.^{3a}, and are addressed to the youthful Levite, they belong to A. The last question may then be assigned to B, from which, in continuation, *vv*.⁴⁻⁶ seem to be drawn: notice in *v*.⁴ the reference to the agreement under which the Levite was hired to become priest, which recalls 17^{10, 13} (the phrase הִיָּה לְכֹהֵן is common to 17^{10, 13}, 18^{4b}); and the reference in *v*.^{6a} to 'the priest,' whereas in A the regular phrase is 'the youth, the Levite.'

In the description of Laish and its inhabitants in 18⁷, the words 'dwelling in security after the manner of the Šidonians' are marked as alien to the preceding by the use of the fem. **וְיָשְׁבָת**, which cannot refer to **הָעָם** 'the people,' but must presuppose a reference in its own source to **הָעִיר** 'the city' (fem.). It is also clear that the phrase 'dwelling in security' is superfluous by the side of 'quiet and secure' which follows. This latter phrase (**שָׁקֵט וְבִטָּח**) refers naturally to 'the people' (**הָעָם** masc.) of the early part of the verse; cf. **עַל עַם שָׁקֵט וְבִטָּח** 'unto a people quiet and secure,' *z.*²⁷—a passage which, as we shall see, belongs to B. The remaining statements in the verse appear to belong to the same narrative; cf. *z.*^{10b.28aa}. We may thus assign the whole of *z.*⁷ to B, except the intrusive passage 'dwelling . . . Šidonians,' which is presumably derived from A.

18⁸⁻¹⁰ presents something of a problem. Most likely 'to Šor'ah, etc,' in *z.*⁸ belongs to a different source from 'unto their brethren.' The question 'What news have ye?' in *z.*^{8b} seems to demand as answer, not the exhortation of *z.*^{9aa}, but the statement of fact 'We have seen the land, etc.,' *z.*^{9aβb}. The proper continuation of *z.*^{9aa} seems to be found in *z.*^{10aa}, which gives a reason for the hortatory form in which it is couched; but *z.*^{10aβ}, 'for God hath given it, etc.,' which connects most lamely on to *z.*^{10aa}, is admirably fitted as the continuation of *z.*^{9b}, 'be not slothful to go to enter in to possess the land.' On removal of this statement, *z.*^{10b}, 'a place, etc.,' falls naturally into apposition with 'the land is broad,' which, no doubt, it immediately followed in the original source. This division of sources yields us two narratives, each of which is practically complete in itself; as we may see by placing them side by side.

A

⁸And they came unto their brethren, and their brethren said to them, 'What news have ye?'
⁹[And they said,] 'We have seen the land, and, behold, it is very good: and will ye be still? be not slothful to go in to possess the land, ¹⁰for God hath given it into your hand.'

B

⁸[And they came] to Šor'ah and Eshta'ol, ⁹and said, 'Arise! and let us go up against Laish, for ¹⁰when ye come [thither] ye shall come unto a people secure, and the land is broad—a place where there is no lack of anything that is in the earth.'

Our decision as to the sources is based upon the parallelism of the one narrative with *z.*^{27a}, which undoubtedly belongs to B.

18¹¹⁻¹³ read as a single narrative; and this is marked as B by the recurrence of the phrase 'and they came as far as (**עַד**) the house of Micah,' as in 17^{8b}, 18^{2b}. At the end of *z.*¹² the words 'behold, etc.,' which define more precisely the position of Mañaneh-Dan in relation to Kiriath-jé'arim, are probably a gloss.

In 18¹⁴⁻¹⁹ we have a combination of two accounts of the theft from Micah's sanctuary. These seem naturally to divide themselves as follows :—

A

¹⁴ Then answered the five men that went to spy out the land, and said unto their brethren, 'Do ye know that there is in these houses a graven image? Now therefore consider what ye will do.' ¹⁵ And they turned aside thither, and came unto the house of the youth the Levite, and asked him of his welfare. ¹⁶ And the six hundred men girt with their weapons of war were standing at the entrance of the gate : ^{17a} and the five men that went to spy out the land went up ; they went in thither, they took the graven image.

B

^{17b} And while the priest was standing at the entrance of the gate, with the six hundred men that were girt with the weapons of war, ¹⁸ these others went into the house of Micah, and took the Ephod and Teraphim. And the priest said unto them, 'What do ye?' ¹⁹ And they said to him, 'Hold thy peace, lay thy hand upon thy mouth, and go with us, and be to us a father and a priest : is it better for thee to be a priest to the house of one man, or to be priest to a tribe and to a clan in Israel?'

Here we notice that *v.*^{14a} and *v.*^{17a} are connected by the phrase 'to spy out the land' (לְרַגֵּל אֶת-הָאָרֶץ), which also occurs in *v.*^{2a}, belonging apparently to the A narrative. Other marks of this narrative are 'their brethren' *v.*¹⁴, as in *v.*⁸; 'they turned aside thither' *v.*¹⁵, as in *v.*^{3b}; 'the youth the Levite' *v.*¹⁵, as in *v.*^{3a}; cf. 17^{7a.11b.12aβ}. The characteristic marks of B are 'the priest' *v.*^{17b.18}, as in *v.*^{6a}; 'and be to us a father and a priest' *v.*¹⁹, as in 17¹⁰.

Further, it is not unnatural to assume that in *v.*¹⁷ the first object mentioned, viz. הפסל 'the graven image,' is original, and that the others are redactors' additions; whereas, in the curious phrase of *v.*¹⁸ את פסל האפוד, which as it stands can only mean 'the graven image of the Ephod,' it is probable that פסל has been carelessly inserted by the redactor, and that the original narrator wrote ויקחו את האפוד ואת התרפים. This conclusion, which has been adopted in the distribution of sources given above, thus apportions a description of the theft to each of the two narratives.

Besides the conflate allusions to the *sacra* in these verses and in *v.*¹⁴, we have assigned to the redactor 'Laish' in the curious expression 'the land Laish' in *v.*¹⁴ (Laish of *v.*^{7.27.29} is a *city* and not a land; and, had the name been assigned to the surrounding district, the phrase would have been ארץ לַיִש 'the land of Laish.' In A the

spies explore 'the land' unnamed—cf. *vv.*^{9a, 17a}; the city Laish belongs to B); 'the house of Micah' *v.*^{15a}, explicative (from the redactor's point of view) of 'the house of the youth, the Levite'; 'that were of the children of Dan' *v.*^{16b}—awkward in position and redundant.

On the removal of these redactional additions, the whole remaining text can be made, as we have seen, to fall into two narratives which read connectedly; yet there are difficulties in the apportionment of *vv.*^{16, 17} which appear to be insuperable. Closely parallel as the two narratives doubtless were, it is scarcely credible that the phrase 'six hundred . . . weapons of war' occurred in that form in *each* (*vv.*^{16a, 17b}); nor, again, that the phrase 'standing at the entrance of the gate' is common to both, referring in the one (*v.*^{16a}) to the six hundred, and in the other (*v.*^{17b}) to the priest. In *v.*^{17a} the asyndeton *באו שמה לקחו* 'they went in thither, they took, etc.' is extraordinarily harsh in the Heb., and can scarcely be original; while in *v.*^{17b} the construction *והכהן נצב . . . ושש וג'* 'and the priest was standing . . . with (lit. *and*) the six hundred, etc.' though it is possible to justify it syntactically (cf. *note ad loc.*), yet imparts to the sentence an unnatural appearance.

We must conclude, therefore, that these two verses have undergone such an amount of alteration—probably owing to textual corruption and the introduction of marginal glosses—that it is impossible to ascertain their original form.*

*v.*¹⁸²⁰⁻²⁹ shows no trace of the combination of two narratives. It is clearly the direct continuation of *v.*¹⁹, which, as we have seen, belongs to B. Notice, as a mark of this narrative, the repeated reference to 'the priest,' *vv.*^{20, 24, 27}. Redactional additions are—the introduction of 'and the graven image' in *v.*^{20a}; the topographical note in *v.*^{28a, b}; and, probably, *v.*²⁹ from 'after the name of Dan' to the end. The final statement, *v.*^{29b}, is framed precisely in the form of Gen. 28^{19b}.

The two verses *v.*¹⁸^{30, 31} have occasioned considerable discussion. Clearly, they cannot be the work of a single writer; since, while *v.*³⁰, according to *℣*, speaks of the worship of the graven image as existing at Dan 'unto the day of the captivity of the land'—*i.e.*, we must sup-

* It is possible, of course, by cutting out portions of *vv.*^{16, 17} as marginal doublets, to reduce the narrative of the theft to a single account, which is then to be assigned to the source B. Such a measure is suggested by *℣*^B, in which *vv.*^{17, 18} run as follows:—*καὶ ἀνέβησαν οἱ πέντε ἄνδρες οἱ πορευθέντες κατασκέψασθαι τὴν γῆν, καὶ εἰσῆλθον ἐκεῖ εἰς οἶκον Μειχαία, καὶ ὁ ἱερεὺς ἐστῶς καὶ ἔλαβον τὸ γλυπτὸν καὶ τὸ εἰδωλὸν καὶ τὸ θεράπειον καὶ τὸ χωνευτόν. καὶ εἶπεν πρὸς αὐτοὺς ὁ ἱερεὺς, κτλ.* On the basis of this it is open to conjecture that B's account may have run *ויעלו חמישת האנשים ויבאו בית מיכה והכהן נצב שמה ויקחו* 'and the five men went up and came to the house of Micah and the priest was standing there and they took'. Such a process of selection and rejection is, however, too arbitrary to be accepted as a *conclusion*. *℣*¹ offers a single account: by omission of *vv.*^{17b, 18a}; but this may be due to homœoteleuton *καὶ τὸ χωνευτόν*—cf. *℣*^A which offers the full text of *℣*.

pose, until B.C. 734, when Tiglath-Pileser IV. overran Northern Israel and deported the inhabitants (2 Kgs. 15²⁹; cf. Rost, *Keilschrifttexte Tiglat-Pileasers*, pp. 78 ff; Rogers, *CP.* pp. 320 f.), *v.*³¹ refers it simply to the period during which the house of God was at Shiloh—*i.e.* down to the capture of the Ark by the Philistines and the death of 'Eli, as related in 1 Sam. 4; after which we hear no more of the sanctuary of Shiloh, and are probably justified in inferring that it had suffered destruction (cf. Jer. 7^{12,11}, 26^{6,9}, Ps. 78^{60 ff.}). Mo. refers *v.*³¹ to the narrative which we distinguish as A, and supposes that *v.*³⁰ belongs to the other narrative, B, 'the graven image' having been substituted by an editor for 'the Ephod,' and the reference to the captivity of the land being also a late alteration (cf. *SBOT.*). If, however, 'the Ephod' had originally been mentioned, it would hardly have been cut out of the narrative; the redactional practice in regard to the *sacra* being that of conflation, and not substitution.

The probable explanation of the origin of the duplication in the two verses is suggested by Kimchi's conjecture that 'the captivity of the land' refers to the capture of the Ark and its sequel, upon the basis of which Houbigant substitutes הָאָרֶץ 'the Ark' for הָאָרֶץ 'the land.' 'All the time that the house of God was in Shiloh' has been glossed by the explanation 'up to the day when the Ark went into captivity,' with reference to the narrative of 1 Sam. 4: cf., for the use of לָלֶךְ 'go into captivity' in this connexion, 1 Sam. 4^{21,22}, 'glory hath gone captive from Israel.'* If this is so, it is further probable that *v.*^{31a} is a marginal gloss on *v.*³⁰, offering the variant וַיִּשְׁיֵמוּ 'set up' for וַיִּקְיֵמוּ 'reared up,' and explaining הַפֶּסֶל as the image made by Micah. The mention of the name of the priest—'Jonathan, the son of Gershom, the son of Moses'—is undoubtedly ancient, and must emanate from one of the old narratives—presumably from the narrative to which 'the graven image' of *v.*^{30a} belongs, *i.e.* A; but it is difficult to suppose that a fact of so much interest (the grandson of *Moses*) originally found mention at the close of the narrative for the first time. We should expect the Levite's name to have been mentioned at the point at which he is first introduced; and very possibly a trace of it may survive in the final words of *ch.* 17⁷ (cf. *note ad loc.*).

We may then regard *v.*³⁰ down to 'Danites' and *v.*^{31b} as belonging to the narrative A.

Assuming the existence of a double strand of narrative in the story of Micah to be proved, the presumption is that the two narratives were derived, like other double narratives in Judg., from J and E respectively: yet, owing to the lack of phrases which might guide us

* Kimchi compares Ps. 78⁶¹,

'And He delivered into captivity (לְטַבִּי) His strength,
And His glory into the hand of the adversary.'

in assigning either narrative to one or other of these sources, it is difficult or impossible to pass any decisive verdict. The only really characteristic phrase in either narrative seems to be *רָגַל* 'to spy out,' which occurs in 18^{2,14,17}—passages which we have assigned to our narrative A. This phrase is characteristic of E in the Hexateuch; cf. Gen. 42^{9,11,14,16,30,31,34}, Josh. 2¹, 6^{22,23}, to which we may perhaps add Num. 21³² (E?). The verb is only found in J in Josh. 7². It occurs again in Deut. 1²⁴, Josh. 6²⁵ (R^{JE}), 14⁷ (R^D). Another point which favours the assigning of this narrative to E is the fact that the description of the circumstances which led to the making of the idol in 17²⁴ is almost certainly intended to cast contempt and ridicule upon it: cf. *notes ad loc.* A similar motive dominates E's narrative of the theft of Laban's Teraphim in Gen. 31; cf. *vv.*^{34,35}, where Rachel conceals the idols from her father by sitting upon them. E's opposition to idolatry is well-marked: cf. the references to the putting away of 'strange gods' in Gen. 35²⁻⁴, Josh. 24¹⁴⁻²⁵, 1 Sam. 7^{3,4}.

As an indication that our narrative B is derived from J, we may notice the way in which Šor'ah and Eshta'ol figure in this narrative as the home of the Danite clans in 18^{2,8,11}, as in the Samson-narrative, 13²⁵, 16³¹. The phrasing of 18¹¹ *מִמְשַׁפַּח הָרָנִי מִצֶּרֶעָה וּמֵאִשְׁתָּאֵל* is closely similar to 13^{2a} *אִישׁ אֶחָד מִצֶּרֶעָה מִמְשַׁפַּח הָרָנִי*.

If the foregoing analysis is approximately correct, the story of Micah and the Danites presents a combination of two ancient narratives from J and E which were, in all essentials, strikingly similar. The whole complexion of the story, in both traditions, is naïve and archaic. With the exception of E's account of the origin of the graven image in 17²⁻⁴, there is nothing in either narrative which suggests disapproval of Micah's proceedings in establishing a private sanctuary for the practice of an idolatrous form of Yahweh-cultus; and this fact, together with the picture of the wandering Levite seeking a livelihood as best he could, and of the movements of the Danites in search of a new home in the north when (as stated in *ch.* 1³⁴ J; cf. *note*) the pressure of alien foes rendered their earlier home too constricted for them, bears upon its face the unmistakeable stamp of historical truth, unmodified by the thought of a later age. The story, then, may take rank with the history of Abimelech, *ch.* 9, as one of the most ancient and valuable historical sources which we possess dealing with the conditions of life in Canaan during the period of the Judges.

If, as there seems to be no reason to doubt, the tradition which makes the Levite a grandson of Moses is historical, and if, again, the reference means that he was Moses' grandson in the literal sense, and not simply a more remote descendant ('son of Gershom' being used in the wider sense of *descendant*), then the narrative must obviously relate to events which took place very early in the period

covered by the Book of Judges. That this is so is favoured by the allusion to the tribe of Dan in the Song of Deborah, where it seems to be pictured as settled in its northern home in security, and so wrapped up in seafaring interests as to ignore the call to united tribal action issued by Deborah: cf. *ch.* 5¹⁷ *note*. The Danites of Šor'ah and Eshta'ol, as they appear in the story of Samson, were probably a small remnant left behind in the ancient home after the migration of the main body of the tribe had taken place (cf. p. 339).

17. 1. E Now there was a man of the hill-country of Ephraim, whose name was Micay^ehu. 2. And he said to his mother, 'The eleven hundred shekels of silver which were taken from

17. 1. *Micay^ehu*. Heb. מִיכָיָהּ here and in *v.*⁴. The form, of which מִיכָה Micah is an abbreviation, was perhaps originally used throughout the E narrative. Another form of the name is מִיכָיָה, which occurs in Jer. 26¹⁸ *KZ*. with reference to the prophet מִיכָה.

2-4. The text of these verses in *℣* is clearly disarranged; the disarrangement being as old as the Versions. In *v.*^{2a} the words spoken by the mother have fallen out (וְגַם אָמַרְתָּ בְּאָזְנִי can only mean 'and didst also say in mine ears,' אָמַר being regularly followed by the words spoken.* R.V. 'and didst also speak it in mine ears' is an illegitimate rendering: had this sense been intended, we should have expected דִּבַּרְתָּ for אָמַרְתָּ). In *v.*^{3a} Micay^ehu returns the money to his mother; in *v.*^{3bβ} she declares her intention of returning it to him; and in *v.*^{4a} he returns it to her once more in order that she may hand it over to the silversmith. Bu. was the first to observe that the words of *v.*^{3bβ} 'and now I will restore it to thee' must be part of Micah's speech in *v.*^{2a}. He places *vv.*^{3bβ-4a} after *v.*^{2a}, and excises *v.*^{3a} as a repetition of *v.*^{4a} (in *Comm.* excising also the two words וְתֹאמַר אָמֹ in *v.*^{4b}). The reconstruction proposed by Mo. seems to be superior to this, and has been adopted above. Mo. holds that the missing words of the mother's adjuration in *v.*^{2a}—which Bu. supposes to have been suppressed owing to the terrible character of the curse (but cf. *note* on 'didst take an oath')—are the words of *v.*^{3ba}, which have been misplaced in the general dislocation of the text, and are there introduced by the gloss וְתֹאמַר אָמֹ. He agrees with Bu. in placing *v.*^{3bβ} after *v.*^{2a}, and in regarding *v.*^{3a} as a repetition of *v.*^{4a}; but he leaves *v.*^{4a} in the position

* Ex. 19²⁵ J וַיֹּדֶר מֹשֶׁה אֶל הָעָם וַיֹּאמֶר אֲלֵהֶם is a very curious exception; and it seems probable that the words spoken by Moses have disappeared in the piecing together of the sources. In Gen. 4⁸ J וַיֹּאמֶר קַיִן אֶל הָבֶל אָחִיו, the words spoken by Cain, which are missing in *℣*, are found in the Versions.

thee, concerning which thou didst take an oath, and also didst say in mine ears, ζ_3^{ba} . "I do surely consecrate the silver to

in which it stands in \mathfrak{U} , the fact that, by the removal of $v.3^{ba}$ to $v.2^a$, the whole of $v.3$ is accounted for, rendering the position of $v.4^a$ before $v.4^b$ highly suitable.

2. *concerning which thou didst, etc.* Lit. 'and thou didst, etc.' The Personal Pronoun of the 2nd fem. sing. preserves the more primitive form, *Kt.* אַתָּי, which occurs elsewhere sporadically in O.T., and seems to be specially characteristic of the North Palestinian (Ephraimitic) dialect. Cf. *NHTK.* p. 208.

didst take an oath. Heb. אָלִית. The oath was the solemn promise to devote the silver to Yahweh's service. Such an oath brought a curse upon the person who violated it, whether this were the maker of the oath, or any one else who misappropriated the consecrated thing. It was, no doubt, the fear of this curse which caused Micah to confess to the theft and to make restitution; and very possibly his mother may have suspected his guilt when she made the adjuration in his hearing. The verb 'ālā invariably means 'to take an oath' before God (1 Kgs. 8³¹=2 Chr. 6²², Hos. 4², 10⁴; Hiph'il, 'cause to take such an oath,' 1 Sam. 14²¹, 1 Kgs. 8³¹=2 Chr. 6²²†), and *does not* mean 'utter a curse' (R.V. *text*, Bu. *), i.e. 'curse the thief' (Mo. *Comm.*,† Cooke). Had such a sense been intended, it would have been expressed by another verb (*killēl* or 'ārur). The subst. 'ālā, which means 'oath' before Yahweh, may be used in the sense 'curse'; but only of a curse which results *from the violation of such an oath* (different therefore from *kēlālā*, which is used e.g. of the curse of Jotham, *ch.* 9⁵⁷, and of Shime'i's cursing David, 1 Kgs. 2⁸).

I do surely consecrate. Heb. הִקְדֵּשׁ הִקְדֵּשְׁתִּי. The Perfect appears to be used in accordance with the idiom noted by Driver, *Tenses*, § 10, 'to describe the immediate past, being generally best translated by the present.' As the words pass her lips, she *has effected* the consecration. Cf. Gen. 14²², 'lift up (הִרְמֹתִי) my hand to heaven'; 1 Sam. 17¹⁰, 'I reproach (הִרְפֵּתִי) the armies of Israel this day.' It is of course possible to render as an Aorist, 'I did surely consecrate,' i.e. in time past, prior to the theft; but it is more likely that the idea

* Bu. so far misunderstands the meaning of the verb as to suggest that the form may originally have carried an Accusative suffix אֶלִיתִי 'didst curse *him*' (!)

‡ In *SBOT.* Mo. brings out the correct sense by rendering 'didst make a solemn declaration'; though this is not so forcible as 'didst take an oath,' since it does not so clearly imply that a penalty was attached to its violation.

Yahweh from my hand ¹alone, to make a graven image ^R and a molten image ²—^E behold, the silver is with me; it was I that took it; ³^b and now I will restore it to thee.' And his mother said, 'Blessed of Yahweh be my son!' 3. [] 4. So he

of making the silver sacred to Yahweh occurred to her owing to its loss. If it was not found, *she* was under no further obligation, whereas the thief (as noticed above) would bring himself under a curse.

from my hand alone. Reading לְבַדִּי in place of לְבִנִּי with ^{AL} ^h ^L, Mo., La. Mo. seems rightly to explain the point of the restriction implied by the words:—'No one else can fulfil the vow of consecration, and, by having an image made, lift the taboo from the rest of the silver.' In the phrase יְדֵי לְבַדִּי, the speaker says lit. 'the hand of me, in my separateness'—an idiom which is exactly paralleled by Ps. 71¹⁶ צְדִיקְתֶּךָ לְבַדִּךָ 'thy righteousness alone.' Bu.'s stricture that 'my hand alone' should be יְדֵי לְבַדִּךָ is therefore unwarranted.

לְבִנִּי means 'for my son,' *i.e. on his behalf*, in order that he may benefit by the piety of the action. Assuming לְבִנִּי to be a corruption of לְבָרִי, the reading can only have arisen subsequently to the dislocation of the text by which the mother's words appeared to be spoken *after* Micah's confession of the theft. The dedication is made in expiation of his guilt.

a graven image and a molten image. Etymologically *pésel* denotes an idol *carved* or *hewn* out of wood or stone, while *maššēkhā* denotes one which is *cast* of metal in a mould. In spite of its etymology, however, *pésel* may also denote a cast-metal idol (probably sometimes an idol with a core of wood or base metal overlaid with precious metal), as is proved by such passages as Isa. 40¹⁹, 44¹⁰ (where it is connected with the verb *nāśakh* 'to cast'), Jer. 10¹⁴, 51¹⁷ (connected with *šōrēph* 'smelter,' the term rendered 'silversmith' in *v.*⁴ of our narrative). As has been shown above (p. 409), the original *E* narrative seems to have mentioned a single idol only, termed *pésel*, which was *cast* by the *šōrēph* out of the silver; but a later hand, taking *pésel* etymologically as a *graven* image, added *ū-maššēkhā* on the ground that the context demanded mention of a *cast* or *molten* idol.

with me. *I.e.* 'in my possession'—an idiomatic usage of the prep. 'with'; cf. cases cited by BDB. *s.v.* אִתִּי, 3 a.

it was I, etc. Heb. אֲנִי לְקַחְתִּי. Emphasis is expressed by the use of the separate Personal Pronoun before the verb.

Blessed of Yahweh, etc. The mother's blessing neutralizes the curse which would have resulted from misappropriation of the consecrated silver.

restored the silver to his mother. Then his mother took two hundred shekels of silver, and gave them to the silversmith, and he made thereof a graven image ^{R^p} and a molten image: E and it was in the house of Micay^{hu}. 5. J And the man Micah had a sanctuary; and he made an Ephod and Teraphim, and

4. *two hundred shekels.* We are not told what became of the remaining nine hundred shekels. Kimchi supposes that the two hundred shekels were merely the payment made to the silversmith for making the idol out of the rest of the silver; while Ros., Stu., Ber., etc., assume that the nine hundred shekels were devoted to the building and furnishing of the sanctuary. Mo. thinks that the woman was under no obligation to devote the whole of the silver to Yahweh—‘The intention of the dedication (*v.* 3) was not to devote the whole of the treasure to the making of an image, but to compel the thief to restore it by putting the whole under a taboo until she herself had made, from this silver, an image of Yahweh.’ This view is accepted by Bu., La. There is, however, much to be said for the view first put forward by Auberlen (*Studien und Kritiken*, 1860, p. 548), and adopted by Kue., that, after the woman had got back the silver through the expedient of consecrating it to Yahweh, her avarice caused her to seek to fulfil the vow by devoting merely an insignificant portion of it, and keeping back the major part. Cf. the parallel offered by the action of Ananias and Sapphira, Acts 5. Both mother and son are thus represented in an odious light; and it is wholly in the manner of the E narrator to make his point allusively (cf. Gen. 31^{31,35}), and not to labour it in a heavy-handed manner.

5. *a sanctuary.* Heb. בֵּית אֱלֹהִים ‘a house of God (*or* gods).’ Whether this is to be pictured as a small shrine within, or attached to, Micah’s own house (cf. the parallel narrative in *v.* 11^β), or as a separate building, is not clear.

an Ephod. Cf. the full discussion in *note on ch.* 8²⁷. Reference to the present passage occurs on pp. 240, 242.

Teraphim. The nature of the object, or objects, denoted by this term is highly obscure. That some kind of idol is intended appears from Gen. 31^{30,32} E, where Laban accuses Jacob of having stolen his ‘gods’ (*’ēlōhīm*); and that this was an image in human form seems to be clear from 1 Sam. 19^{13ff.}, where Michal is related to have placed the Teraphim in David’s bed in order to simulate him, and thus to facilitate his escape from Saul’s emissaries. If the Teraphim of this passage was a complete human figure, we must infer that it was life-size; but the life-sized image of a human head or bust might have served Michal’s purpose almost equally well. Laban’s Teraphim, which Rachel hid by placing them under a camel’s saddle and sitting upon them (Gen. 31³⁴ E), must, if they were complete human figures, have been much smaller. Like the plural *’ēlōhīm*, the plural Tera-

installed one of his sons, and he became his priest. 6. R^P In

phim may denote one image (1 Sam. *loc. cit.*) or more than one (Gen. *loc. cit.*; cf. the plural suffixes *עליהם* . . . *והטמם* in v.³⁴).

It is clear that Teraphim were employed as oracle-givers. In Hos. 3⁴, as in our narrative, they are mentioned together with the oracular Ephod; and in 1 Sam. 15²³, Zech. 10², Ezek. 21^{21,22}, *ו*^{26,27} with the form of divination called *kēsem*, i.e., as we know from the passage in Ezek. and the use of the root in Ar., a method of casting lots by shaking headless arrows out of a quiver. It is possible that the association of Teraphim with familiar spirits and wizards in 2 Kgs. 23²⁴ may connect them with the practice of necromancy. The view that they were a form of household-god is based upon their occurrence as the property of private individuals (Laban, Micah, David); and many scholars suppose that their cult was connected with ancestor-worship: cf. Schwally, *Das Leben nach dem Tode*, p. 36; Stade, *GVI.*² i. p. 467; Nowack, *Hebr. Archäologie*, ii. p. 23. Very possibly they were identical with the *ēlōhīm* mentioned in the Book of the Covenant, Ex. 21⁶, 22^{8,9}, on which cf. *Footnote*, p. 330.*

The derivation of the word *terāphim* is obscure. A plausible suggestion connects it with *rephāim* 'ghosts' or 'shades' of the dead. If this is so, the root of both is probably to be seen in Bab. *rabū* or *rapū*, which is used of the *sinking* of the heavenly bodies into the Underworld: cf. the use of Heb. *רפה* in this sense in *ch.* 19⁹. *Terāphim*, then, like *rephāim*, will denote, not the *weak* or *flaccid ones* (as the latter term is commonly explained), but *those who have sunk down to* or *disappeared* in the Underworld: cf. the use of the Iph^{te}al of *rabū* in iv.² R. 30, No. 2, Obv. 24, 25, (*ilu*) *Šamaš irtabi ŠU ana iršitim mītūti*, 'The Sun-god sinketh, the Sun-god sinketh, into the Land of the Dead.'[†] So Ball, *Proc. Brit. Acad.*, vii. p. 16.

installed. The Heb. phrase *millē yadh*, lit. 'filled the hand of,' is the technical expression for installation in the priestly office: cf. (besides v.¹⁹) Ex. 28⁴¹, 29^{9,29,33,35}, Lev. 8³³ (all P), Lev. 16³², 21¹⁰

* The curious explanation of Teraphim which is found in the Jerusalem *T* and in Pirkê d^e Rabbi Eli'ezer (early ninth century A.D.), identifying the object with the head of a sacrificed first-born son, pickled in salt and oil, upon the tongue of which was laid a charm written upon a thin plate of gold, and which was then hung upon the wall, and worshipped and consulted as an oracle-giver (cf. references in Buxtorf, *Lexicon Chald. Talm. et Rabbin.*, s.v. *תרפים*), closely corresponds with the description of the rites of the pseudo-Šābians of Harrān, as known to us at the period of the Mohammedan expansion (cf. discussion and authorities cited in Chwolson, *Die Šābier*, ii. pp. 19 ff., 150 ff., 388 ff.), and the two cannot be independent: but whether the Šābian rites were of remote antiquity, and, if so, whether they had any connexion with the Teraphim-cult, is wholly unknown to us.

† Here *ŠU=šanītu*='repetition' (Br. 10840), indicating that the preceding words are to be repeated, as in the Sumerian text of this bilingual fragment.

those days there was no king in Israel: every man was used to do that which was right in his own eyes.

7. ^E Now there was a youth J from Bethlehem of Judah, ^E of the clan of Judah, and he was a Levite, and he sojourned there.
8. J And the man departed from the city, ^{R^E} from Bethlehem of Judah, J to sojourn where he might chance: and he came to the hill-country of Ephraim, as far as the house of Micah, in

(both H), Num. 3³ P, 1 Kgs. 13³³, 1 Chr. 29⁵, 2 Chr. 13⁹, 29³¹, and metaphorically of the consecration of an altar, Ezek. 43²⁶ †. The expression is usually supposed to refer to the ceremony of filling the hands of the person to be consecrated with the choice portions of the sacrifice for a wave-offering: cf. Ex. 29²²⁻²⁵, Lev. 8²⁵⁻²⁸ (both P). These portions are called *millū'im* in Ex. 29³⁴, Lev. 8²⁵.

In Bab. and Assy. inscriptions, however, the same phrase *umallī kâta* is used more generally in the sense of *entrusting authority to* any one, usually with some one of the gods as subject. Thus, e.g. it is said of Adadnirari IV. *ša (ilu) Ašur malkut lâ šanân umallû kâtuššu* 'whose hand (the god) Ašur filled with an unrivalled kingdom' (KB. i. pp. 188, 190): cf. Muss-Arnolt, *Dict.* i. p. 542, where other examples are cited.

6. *In those days, etc.* On this statement as the work of the latest redactor, R^p, cf. p. 410. The statement is no doubt called forth here to explain the (from the late priestly standpoint) grave irregularity of the appointment of a non-Levitical person to exercise priestly functions.

7. *Bethlehem of Judah.* The modern Bêt-Lahm, five miles south of Jerusalem. The definition 'of Judah' is perhaps intended to distinguish the city from the northern Bethlehem of Zebulun, on which cf. *ch.* 12⁸ note.

of the clan of Judah. The difficulty raised by this statement that the Levite was a Judean by birth is discussed in *Addit. note*, p. 436.

and he sojourned there. Heb. וְהוּא גֵר־יִשָּׁם. The statement implies that he was enjoying the rights of protection extended to an alien *gēr* or sojourner by the clan with which he dwelt. Cf. the parallel narrative in וְלָגַר בַּאֲשֶׁר יִמְצֵא ^u.⁸ Considering, however, that in the present passage the words גֵר יִשָּׁם contain the identical letters of the name גֵרְשֹׁם Gershom (cf. the explanation which is offered of the meaning of the name in Ex. 2²² J), and also that the mention of the Levite's name at the end of the narrative (*ch.* 18³⁰) and not at the beginning is very strange, it is possible that וְהוּא גֵר יִשָּׁם may be a relic of an original וְשִׁמְוֹן יְהוֹנָתָן בֶּן־גֵרְשֹׁם 'and his name was Jonathan, the son of Gershom.' Cf. *Addenda*, p. xx.

order to accomplish his errand. 9. And Micah said to him, 'Whence comest thou?' And he said unto him, 'I am a Levite from Bethlehem of Judah; and I am going to sojourn where I may chance.' 10. And Micah said to him, 'Abide with me, and be to me a father and a priest, and I will give thee ten

8. *in order to accomplish his errand.* Heb. לַעֲשׂוֹת דְּרָכּוֹ, lit. 'to make (or do) his way.' Cf. Isa. 58¹³ דְּרָכֶיךָ לַעֲשׂוֹת 'not doing thy ways' (i.e. 'thy wonted *pursuits*'—less specific, but yet parallel). Heb. *d'rek*h, which is frequently used in the sense of *journey* (cf. cases cited by BDB. s.v. דֶּרֶךְ 2), here seems to be used of *the object of the journey*, just as it is in *ch.* 18^{5,6} (noted by Mo.) and, more generally, in Deut. 28²⁰, Josh. 1⁸, 1 Sam. 18¹¹, *al.* The point of the statement is, of course, not that the Levite came to Micah's house with the specific expectation of finding work there and nowhere else, but that up to arriving at that point he had not as yet accomplished the object of his journey, and so had it in view. The rendering here adopted is favoured by Mo. (*Comm.*), Ehr.

R.V. renders 'as he journeyed,' and so Mo. (*SBOT.*) 'in the course of his journey,' and this explanation is generally adopted: but it is opposed (if not precluded) by the facts that such a use of an Infin. with ל appears to be unparalleled,* and that the phrase 'make a journey,' though natural enough in English, is not found elsewhere in Heb.

10. *a father.* For the title as a term of respect, cf. BDB. s.v. אב, 8.

The addition at the end of the verse, וַיֵּלֶךְ הָלֵי, is clearly a corrupt duplication of וַיֵּאָלֶה הָלֵי at the commencement of 7.¹¹ (so most moderns); being marked as such by the repeated הָלֵי, and

* No. objects (against Mo., *Comm.*) to the explanation which we have adopted, and renders (in accordance with R.V., etc.) 'auf seine Reise,' asserting that לַעֲשׂוֹת is a gerundial usage of the Infin. with ל, and should fall among the cases cited in G-K. § 114 o. In the very miscellaneous list of cases embodied in this section, the uses of the Infin. with ל may be classified as follows:—*Purpose* ('in order to'), Lev. 8¹⁵, 1 Sam. 20²⁶, Ps. 63³, 101⁸, 104^{14f}, Prov. 2⁸; *Reference* or *closer definition* ('as regards' or 'through'), Gen. 3²², 18¹⁹, 34^{7,15}, Num. 14³⁶, 1 Sam. 12¹⁷, 14³³, 19⁵, 2 Sam. 3¹⁰, 1 Kgs. 2^{2f}, 14⁸, Jer. 44^{7f}, Ps. 78¹⁸, 103²⁰, 111⁶, Prov. 8³⁴, Neh. 13¹⁸; *Consequence* ('so as to'), Ex. 23², Lev. 5^{4,22,26}, Prov. 18⁵. If, however, לַעֲשׂוֹת דְּרָכּוֹ really means 'in making his journey,' such a usage of ל is *circumstantial*, and cannot be brought under any of the preceding categories. Such a rendering makes לַעֲשׂוֹת the equivalent of כַּעֲשׂוֹת or בַּעֲשׂוֹת (or, more properly, of כַּעֲשׂוֹתוֹ or בַּעֲשׂוֹתוֹ).

shekels of silver a year, and a suit of apparel, and thy living.' []
 11. And the Levite consented to dwell with the man; E and the youth became to him like one of his sons. 12. And Micah installed the Levite, and the youth became his priest, J and was in the house of Micah. 13. Then said Micah, 'Now I know that Yahweh will do me good, seeing that the Levite hath become my priest.'

18. 1. R^p In those days there was no king in Israel; J and in those days the tribe of the Danites were seeking them an inheritance to dwell in; R^p for there had not fallen unto them unto that day <a land> for an inheritance among the tribes of Israel. 2. J And the children of Dan sent from their clan five

by the unsuitability of the verb to the context. The words could only mean 'and the Levite *went*,' i.e. 'departed' (cf. Gen. 18³³, 34¹⁷, 1 Sam. 14³, 15²⁷, *al.*). R.V. 'went *in*' (*sc.* to Micah's house) would require וַיֵּבֶא at least. The words are omitted by E.

11. *consented*. On the usage of the Heb. verb *hō'il*, cf. ch. 1²⁷, *note* on 'persisted.'

13. *Now I know, etc.* A Levite as priest is regarded as highly desirable, but not as vitally necessary.

18. 1. *In those days . . . Israel*. Mo. refers R^p's statement here to the close of the preceding part of the narrative, in reference to the (from the later point of view) ritual irregularities which are there related. His view is that 'Jerome erroneously joined the words to the following: "In diebus illis non erat rex in Israel, et tribus Dan quaerebat possessionem sibi, etc."; and was naturally followed in the division of the chapters which was introduced in the Latin Bible in the thirteenth century, and from it into the printed Hebrew Bible.' This conclusion is adopted by No., La., Cooke. It may be observed, however, that, while the full form of the comment concludes a narrative-section in 17⁶ and 21²⁵, the shorter form (as in this passage) *opens* the narrative of ch. 19. It is not clear why the statement should not be intended to explain the independent and lawless action of the Danites as related in ch. 18.

for there had not fallen, etc. The subject of the verb is missing in וַי. We must supply אֶרֶץ 'a land' with Stu.: for the constr. נפלה ארץ בנחלה cf. Num. 34², Josh. 13^{6,7}. ὅτι οὐκ ἐνέπεσεν αὐτῇ . . . κληρονομία possibly presupposes a text in which נחלה stood as subject in place of וַי בנחלה.

men ^E from their whole number, men of valour, J from Šor'ah, and from Eshta'ol, ^E to spy out the land and to explore it; J and they said unto them, 'Go, explore the land': and they came to the hill-country of Ephraim, as far as the house of Micah, and spent the night there. 3. ^E When they were by the house of Micah, they recognized the voice of the youth, the Levite: and they turned aside thither, and said to him, 'Who brought thee hither? and what doest thou in this place? J and what is thy business here?' 4. And he said unto them, 'Thus and thus hath Micah done for me, and he hath hired me, and I am become his priest.' 5. And they said to him, 'Prithee enquire

2. *from their whole number.* *I.e.* representatives of the whole *ḥan* (its several branches). Heb. *kəšôthām* means lit. 'their *extremities*'—a 'condensed term for what is included within extremities = the whole' (BDB. *s.v.* קצה). The idiom is well elucidated by Num. 22⁴¹, 'and he saw from thence *the uttermost part of the people*' (קצה העם), *i.e.* by implied inclusion, *the whole of them*. Cf. *NHTK.* on 1 Kgs. 12³¹.

from Šor'ah and from Eshta'ol. Cf. notes on 13^{1.25}.

to spy out. Heb. *riggēl* is a denominative from *réghele* 'foot,' like Lat. *vestigare* from *vestigium*. On the usage of the verb as characteristic of ^E cf. p. 416.

3. *When they were by . . . they recognized.* Heb. הֵמָּה עִם בֵּית מִיכָה וְהֵמָּה הֵכִיל, lit. 'They were by the house of Micah, and they recognized.' The great emphasis upon the Personal Pronoun in each clause throws the two clauses into vivid antithesis, the object being to emphasize the circumstances in which the fact narrated in the second clause took place. This usage is very idiomatic: cf. Driver, *Tenses*, §§ 168, 169.

by the house. Heb. עִם בֵּית, lit. 'with the house,' *i.e.* close to it. For this idiomatic use of the preposition, cf. *ch.* 19¹¹ ('near Jebus'), Gen. 35⁴, Josh. 7², 2 Sam. 20⁸, 1 Kgs. 1⁹, *al.*

they recognized the voice. The view put forward by Stu. that Heb. *kôl*, 'voice,' here means *dialect*, by which the Danites recognized the Levite as a Judæan and not an Ephraimite, is most improbable. The obvious meaning is that they happened to have known him personally before, when he was living in Judah. Cf. for the closeness of local association between the tribes of Dan and Judah, *ch.* 15¹⁴.

and what is thy business here? Heb. וְמָה לְךָ פֶּה, lit. 'and what to thee here?'

5. *Enquire of God.* Cf. note on *ch.* 1¹. We note the fact that while the Danites' request is 'Enquire of 'ēlōhîm,' the response (*v.* 6)

of God, that we may know whether our journey on which we are going shall be prosperous.' 6. And the priest said to them, 'Go in peace: before Yahweh is your journey whereon ye go.'

is 'Before *Yahweh* is your journey, etc.' Here, though the ordinarily unquestioned conclusion is that *'ēlōhīm* denotes 'God,' and is synonymous with 'Yahweh,' the possibility presents itself that the two terms, as they stand, may embody a distinction with a difference. The reference of *'ēlōhīm* may be to the *Teraphim*, regarded as the *medium* rather than the source of the divine response: cf. the use of *hā-ēlōhīm* in Ex. 21⁶, 22^{8,9} (noted on p. 330), and Micah's reference to 'my gods,' v. 24 (cf. Gen. 31^{30,32} E), as well as *Bēth-ēlōhīm*, ch. 17⁵, if this means properly 'house of gods.' If this be so, the force of the prep. ב may very possibly be 'by' or 'through': cf. Num. 27²¹ P, 'He (Joshua) shall stand before Ele'azar the priest, who shall enquire for him by the judgment of the Urim before Yahweh' (וּשְׁאֵל לוֹ בַּמִּשְׁפָּט הָאוּרִים לִפְנֵי יְהוָה); Ezek. 21²¹ (21²⁶), 'He (the king of Babylon) enquired through the Teraphim' (שָׁאֵל בְּתִרְפִּים); here it is of course possible to render 'he enquired of the Teraphim'; 1 Sam. 28⁸, where Saul says to the witch of 'Endor, 'Prithee divine for me through the familiar spirit' (קְסוּמִי נָא לִי בְּאוֹב), and, with reference to the same incident, 1 Chr. 10¹³, 'and also, for that he (Saul) enquired through the familiar spirit' (וְגַם לְשֹׂאוֹל בְּאוֹב).* Upon this explanation, the Danites say, 'Enquire through *'ēlōhīm*' (or, vocalizing בְּאֱלֹהִים 'through the *'ēlōhīm*'), and the Teraphim, when thus interrogated, returns the answer, 'Before Yahweh is your journey whereon ye go.' Even with retention of the ordinary sense of *šā'al b'*, 'enquire of,' the primary meaning may be, 'Enquire of the oracle'—a sense which likewise implies that *'ēlōhīm* is not identical with Yahweh, but simply voices His attitude towards the project of the Danites.

A distinction in phraseology, identical with that of our passage, is drawn in ch. 20¹⁸, 'They enquired of (or through) *'ēlōhīm* . . . and *Yahweh* said'; cf. also 1 Sam. 14³⁷, 2 Sam. 16²³.

our journey. I.e. the object of it, 'our errand': cf. note on ch. 17⁸.

6. *before Yahweh.* Heb. *nōkhah*, rendered 'before,' means lit. 'in front of' or 'opposite.' So Mo., 'under the eye of Yahweh.'

* Here, whatever be the precise meaning of *'ōbh*, rendered 'familiar spirit' (on which cf. *NHTK*, p. 354; Driver, *Deuteronomy*, ICC., p. 226; T. W. Davies in *EB*, 1120 f.), it is clear that the enquiry is made *through* and not *of* the *'ōbh*. The response comes from the spirit of Samuel, and the *'ōbh* acts merely as intermediary.

7. So the five men went, and came to Laish, and saw the people that were therein, ^E dwelling in security, after the manner of the ^Sidonians, ^J quiet and secure, and there was no 'want of any'—

7. *Laish*. Heb. לַיִשׁ means 'lion.' In Josh. 19⁴⁷ ^J the name is given as לֶשֶׁם *Leshem*—a variant form which ought probably (as suggested by Wellh., *De gentibus et familiis Judaeis*, p. 37) to be vocalized לֶשֶׁם, *i.e.*, לַיִשָּׁם *Lêshâm*, the same name as לַיִשׁ with formative termination: cf. עֵיטָם '*Eṭām* from עֵיט '*ayit* 'bird of prey' (so Gray, *Heb. Proper Names*, p. 93).

Eusebius and Jerome locate Laish or Dan four Roman miles from Paneas (the modern Bānyās) on the way to Tyre (*OS.* 114²⁶, 249³²), and state that it is here that the Jordan breaks forth (*OS.* 136¹¹, 275²³). The site intended is no doubt the modern Tell el-Kādy, an oblong mound, from the western side of which there issues a copious stream which forms one of the sources of the Jordan.* *Jos.* (*BJ.* IV. i. 1) knows this site as Daphne, and states that its springs, beneath the temple of the golden bull, supply water to the little Jordan, which flows into the great Jordan. This identification is accepted by Rob. (*BR.*³ iii. pp. 390 ff.) and most modern writers. The Ar. name Kādy, which like Heb. Dan means 'judge,' may possibly offer a point of connexion. Smith (*HG.* pp. 473, 480) prefers to find the site of Laish-Dan at Bānyās,† on the ground that the meadows and springs of the upper Jordan could not be held against an enemy without also holding Bānyās and its castle; but, as Cheyne not unjustly remarks (*EB.* 997), 'From Judg. 18 we do not gather that Laish was a place of exceptional natural strength; its inhabitants were a peaceful folk, who trusted not in their fortress but in their remoteness from troublesome people like the Danites.'

dwelling. On the fem. form יוֹשֵׁבֶת, as implying a fem. antecedent הָעִיר 'the city,' in the source from which the extract is derived, cf. p. 412.

in security. *I.e.* without apprehension of danger from outside. Heb. לְבֵטָח.

and there was no want . . . earth. Reading יֵאֵין מִחֶסֶד כָּל-דָּבָר יֵאֵינָהּ בָּאָרֶץ as in *v.*¹⁰, with Ber., Bu., Mo. (*SBOT.*), No., La., Kit,

* This stream has not been indicated in Map I.

† Theodore (on Jer. 4¹⁵) and Jerome (on Ezek. 48¹⁸, and Am. 8¹⁴) speak of Paneas as occupying the site of Dan.

Why Smith (p. 473) should say that Bānyās is 'scarcely an hour to the north' of Tell el-Kādy is not clear. His own maps, like the *SWP. Great Map*, locate it nearly due east.

thing <that is> in the earth, [] and they were far from the Šidonians, and had no dealings with 'Aram'. 8. E And they came unto their brethren J to Šor'ah and Eshta'ol: E and their brethren said to them, 'What news 'have ye'?' 9. J And they

Cooke, Gress., in place of **וַאִין־מַכְלִים דָּבַר בְּאַרְיִן**. Here the curious **מַכְלִים דָּבַר**, which can only be understood as 'one insulting (or humiliating) in a matter,' very early caused difficulty, and was glossed by **יִרְחֹט עֶצֶר** 'one usurping coercive power'* (omitted by **Gr^A**) which has crept into the text of **ו**. This explanation of the latter phrase as a gloss is simpler and more natural than the view of Bu. (based on **Gr^L** *κληρονόμος θησαυροῦ*, **Gr^E** 'magnarumque opum') that it is an integral part of the text, meaning 'possessing riches,' i.e. either **אֶצֶר** or **עֶצֶר** of which two readings **ו** **עֶצֶר** represents an amalgamation.

far from the Šidonians . . . Aram. Lying at the southern mouth of the valley which runs between the Lebanon and Hermon ranges, Laish was isolated from Šidon by the Lebanon range to the north-west, and from Aram-Damascus[‡] by the Hermon range to the north-east. The reading **אַרָּם** 'Aram,' which is offered by **Gr^{AL}**, **S^b**, **U^L**, **Σ.**, is adopted by Bu., La., Kit., Gress., and is undoubtedly superior to **ו** **אַרָּם**—'had no dealings with mankind.' The reference to Šidon requires a more definite antithesis.

8. *What news have ye?* Reading **מָה אֶתְכֶם**, lit. 'what is with you?' with Wellh. (*Comp.³* p. 365), No., Kit., in place of **ו** **אֶתְכֶם** which offers an incomplete sentence, 'What ye?' For the use of **אֶת** 'with,' cf. 2 Kgs. 3¹², Jer 27¹⁸, where the word of Yahweh is said to be *with* a prophet, i.e. revealed to him; and the employment of the preposition in the sense 'known to' in Job 12³, 14⁵.

Gr^B, making the words part of the speech of *the spies*, renders *καὶ εἶπον τοῖς ἀδελφοῖς αὐτῶν τί ὑμεῖς κάθησθε*; i.e. **וַיֹּאמְרוּ לְאַחֵיהֶם מָה אֶתְכֶם**. Such an inquiry, however, is redundant by the side of **וַיִּשְׁבּוּ**. **וְאֶתְכֶם מַה־יִּשְׁבּוּ** 'and will ye be still?' in *v.⁹*, apart from the fact that we should expect **לְמָה** rather than **מָה**. **Gr^{AL}**, though agreeing with

* The subs. **עֶצֶר** is a *ἄπαξ λεγόμενον*, but the sense implied appears to be sufficiently guaranteed by the usage of the verb **עָצַר**.

‡ It seems probable that the narrator is thinking of the kingdom of Damascus rather than of the small Aramaean states in the immediate neighbourhood (Beth reḥob and Ma'achah) to which Mo. alludes.

said, 'Arise! and let us go up¹ to Laish¹: for ^E we have seen the land, and, behold, it is very good: and will ye be still? be not slothful to go to enter in to possess the land. 10. J When ye come, ye will come unto a people secure, and the land is broad: E for God hath given it into your hand; J a place where there is no want of anything that is in the earth.'

11. Then there set forth from thence of the clan of the Danites, from Šor'ah and from Eshta'ol, six hundred men girt with weapons of war. 12. And they went up, and encamped in

𐤀 in making the words an address *to* the spies, yet, like 𐤂^B, has the reading *κάθησθε*; and Mo. deduces from this the possibility that שבים may be the corruption of an original מְשִׁיבִים—'What (news) are ye *bringing back*?' Bu.'s suggestions מָה [רָ] אַתֶּם 'What have ye seen?' or מָה [מָצָ] אַתֶּם 'What have ye found?' are improbable.

9. *Arise!* The sing. קוּמָה is used as a stereotyped interjection in place of the plur. (which appears in several Codd., probably as a correction). Cf. הִבָּה 'Come!'—originally 'Give!' or 'Permit!'—addressed to a plurality of persons, Gen. 11^{3.4.7}; לָבָה 'Come!' addressed to a woman, Gen. 19³²; רְאֵה 'Behold!' addressed to Israel in the plural, Deut. 1⁸.

let us go up. On the use of the verb 'ālā 'go up,' in the general sense of making a military expedition, cf. *ch.* 1¹ *note*.

to Laish. Reading לִיִּשָּׁה with No., in place of 𐤀 עֲלֵיהֶם 'against them,' the suffix of which has no antecedent. 𐤂^A ἐπ' αὐτήν, *i.e.* עֲלֵיהָ, may represent the first stage in the corruption.

It is worthy of notice, however, that there exists a doublet in 𐤂^{AL} *at*, 𐤂^h (marked by obelus) which may possibly contain the original text. This runs in 𐤂^L as follows: εἰσῆλθαμεν καὶ ἐμπεριεπατήσαμεν τὴν γῆν ἕως εἰς Λαισα, καὶ εἴδομεν τὸν λαὸν τὸν κατοικοῦντα ἐν αὐτῇ ἐπ' ἐλπίδι κατὰ τὸ σύγκριμα τῶν Σιδωνίων καὶ μακρὰν ἀπέχοντας ἐκ Σιδῶνος, καὶ λόγος οὐκ ἦν αὐτοῖς μετὰ Συρίας· ἀλλὰ ἀνάστητε καὶ ἀναβῶμεν ἐπ' αὐτούς, ὅτι κτλ. This is accepted as original by La. in the following form: בָּאנוּ וַנִּתְחַלֵּץ בְּאַרְצָן עַד-לִישָׁה:

וַנִּרְאֶה אֶת-הָעָם אֲשֶׁר בְּקִרְבָּהּ יוֹשֵׁב לְבִטָּח בְּמִשְׁפַּט צִידָנִים וְרוֹחוּקִים קוּמָה 𐤀, הִמָּה מְצִידָנִים וְדָבָר אֵין-לָהֶם עִם-אַרְצָם קוּמוּ. This provides us with the necessary antecedent to עֲלֵיהֶם; but the passage is somewhat unnecessarily tautological after 𐤂⁷, and may have been constructed in imitation of that verse.

Ḳiriath-je'arim, in Judah: wherefore that place was called

12. *Ḳiriath-je'arim*. The name means 'woodland-town.' Eusebius places the city nine (*OS.* 271¹⁰) or ten (*OS.* 234⁹¹) Roman miles from Jerusalem on the road to Diospolis (Lydda). The site intended has been identified, since Rob. (*BR.*³ ii. pp. 11 f.), with Ḳuryet el-'Enab ('town of grapes'), or el-Ḳuryeh,* and the position suits the connexion in which Ḳiriath-je'arim is mentioned in Josh. 9¹⁷ among the Gibe'onite cities Gibe'on, Kephirah, and Be'erother; and also the description of the northern boundary-line of Judah as described in Josh. 15^{8ff.} P, where, after running just south of Jerusalem to the hill to the west of the valley of Ḥinnom and north of the vale of Repha'im, it continues in a north-westerly direction to the spring of the waters of Nephtoah (probably Liftâ †), Mount 'Ephron (unidentified), and Ḳiriath-je'arim (Ḳuryet el-'Enab), where it takes a turn (ז. ונסב¹⁰) south-westward to Mount Se'ir, and passing along the northern shoulder of Mount Je'arim § where Chesalon (Keslâ) is situated, it descends to Beth-shemesh ('Ain-šems) and passes on to Timnah (Tibneh). Cf. also the description of the southern boundary of Benjamin in Josh. 18^{14ff.} P.

* The village is often called Abû Gôš after a celebrated family of bandits which resided there during the earlier half of the nineteenth century.

‡ The interchange between *n* and *l*, as seen in Nephtoah, Liftâ, may be illustrated by Heb. *nîškâ* and *liškâ* 'chamber,' Heb. *nâḥaš* (root of *nâḥāš* 'serpent') and *lâḥaš* 'to hiss,' Bab. *nêšu* and Heb. *lâyiš* 'lion,' New Heb. *nâḥaṣ* and Bib. Heb. *lîḥaṣ*, Aram. *nêḥaṣ* and *leḥaṣ*, 'to pick up,' Heb. *nâthan* and Aram. *neṯan* and *neṯal* 'to give,' Heb. *'almānâ* and Aram. *'armelâ* 'widow,' etc. The interchange is not confined to Semitic: thus the English *Lincoln* appears in Northern French as *Nicole*; *level* is from Old French *livel*, which has become *niveau* in modern French; *lilac* comes ultimately from the Persian *lilak*, a variation of *nilak* 'blue'; etc.

If, as seems likely, the *n* in Nephtoah is formative, and the root is *pâthaḥ* 'to open,' in the sense of *an opening in the rock for the exit of water* (cf. the use of the verb in Isa. 41¹⁸, Ps. 105⁴¹), the disappearance of the final guttural *h* in Liftâ may be illustrated by the fact that both *pâthaḥ* and *pâthâ* occur in Heb. in the sense of *opening*. Liftâ possesses 'a large spring and the stones of some very ancient buildings at the E. entrance to the village' (Baedeker, *Palestine*,³ p. 18).

§ הר שעיר 'the hairy, i.e. scrubby, mountain' (cf. Ar. *šarâr*, 'tangled, or, abundant and dense, trees') and הר יערים 'the woodland-mountain' appear respectively to denote the hill on which Saris stands to the north of the wâdy el-Iamâr, and the hill on which Keslâ stands, south of the same wâdy. Both hills are still covered by scrub and the remains of old woods: cf. *SWP. Great Map*, xvii., and Buhl, *Geogr.* p. 91. Baedeker, *Palestine*,³ p. 16, in describing the road from Jaffa to Jerusalem in the neighbourhood of Saris, says: 'The hills are overgrown with underwood; besides the wild olives the carob-tree is frequently observed.' Similarly, Macmillan's *Guide to Palestine*,⁵ p. 15: 'On either side of the road are rocky heights, with olive-trees occupying every point of vantage, and amongst them may be seen many carob-trees, conspicuous by their handsome dark green foliage. There are also several fine oak and terebinth trees.'

Maḥaneh-Dan, unto this day: R^p behold, it is to the west of Kiriath-je'arim. 13. J And they passed on thence to the hill-country of Ephraim; and they came as far as the house of Micah. 14. E Then answered the five men that went to spy out the land R¹⁵ Laish, E and said unto their brethren, 'Do ye know

The rival identification (proposed by Henderson and Conder, *SWP. Mem.* iii. pp. 43 ff.) is the ruined site 'Ermâ, on the southern side of the wâdy Şarâr about four miles east of 'Ain-Şems. This suits the proximity to Beth-Shemesh, which is suggested by 1 Sam. 6^{20,21},* but is irreconcilable with the description of the boundary of Judah as noticed above,† and (as Cheyne points out, *EB.* 2680) is too near Şor'ah and Eshta'ol to suit the present narrative.

Maḥaneh-Dan. Cf. note on ch. 13²⁵.

to the west of. Lit. 'behind.' Cf. the phrase 'behind (*i.e.* to the west of) the wilderness' in Ex. 3¹ E, and contrast the phrase '*in front of* Hebron,' ch. 16³ note.

14. *the land Laish.* On Laish (the *city*) as a gloss inserted by the redactor of the two narratives, cf. p. 413.

Now therefore consider, etc. *Verbum sap.* For the phrase, cf. 1 Sam. 25¹⁷.

15-18. The two accounts, which are here interwoven, seem to have been further confused by later glossing (cf. p. 414), but the general situation is surely not so obscure as Mo. (who is closely followed by Cooke) makes out. Some difficulty is caused by the repeated reference (*vv.* 16, 17) to 'the entrance of the gate.' The term *šā'ar* 'gate' is never applied to the door of a house; yet it is clear from *vv.* 14, 22 that Micah's house was one among a few others forming a small village, certainly not surrounded by a massive wall with a gate. Mo., while rightly remarking, upon *v.* 14, that 'Micah evidently lived in an open village,' yet explains *v.* 16 as meaning that 'the main body [of Danites] halted without the village,' and speaks later on of 'the armed men at the entrance of the village'—an expression

* The statement of Jos. (*Ant.* vi. i. 4) that Kiriath-Je'arim was in the neighbourhood of Beth-shemesh is probably based merely upon this narrative.

† Leaving out of account the plausible identification of Nephtoah with Liftâ, the mere fact that Kiriath-je'arim occupies a position on the boundary-line between the valley of Hinnom (Josh. 15⁸) and Chesalon (*v.* 10) seems absolutely to exclude the site 'Ermâ. How could the line run from Hinnom to 'Ermâ (presumably along the upper course of the Wâdy Sarâr), strike north-east to Chesalon (Keslâ) at an acute angle, and then return south-west at a still more acute angle, over the shoulder of the hill on which Chesalon is situated, so as to reach Beth-shemesh? As a matter of fact, we are told in *v.* 10 that, after reaching Kiriath-je'arim, the boundary (so far from striking north-eastward) turned westward (יָמָה 'towards the sea') to Mount Se'ir and Chesalon.

that there is in these houses ^{RJE} an Ephod, and Teraphim, ^E and a graven image ^R and a molten image? ^E Now therefore consider what ye will do.' 15. And they turned aside thither, and came unto the house of the youth the Levite, ^{RJE} the house of Micah, ^E and asked him of his welfare. 16. ^{E?+Gl.} And 'the' six hundred men, girt with their weapons of war, that were of the children of Dan, were standing at the entrance of the gate: 17. and the five men that went to spy out the land went up; they went in thither, they took the graven image, ^{RJE} and the

adopted *verbatim* by Cooke. Neither of these scholars explains what kind of 'entrance' he pictures an unwalled village as possessing; yet it is clear that the phrase 'the entrance of the gate' must postulate a *real gate* *; and the natural inference seems to be that Micah, as a man of some position, had a house surrounded by a courtyard, ‡ and that it was at the gate of this courtyard, and not outside the village, that the men at arms were standing whilst their companions slipped inside (cf. La.). If this was so, the difficulty does not seem very great. The Danites might endeavour to distract the priest's attention by parleying at the gate, yet it would still be possible for him to observe the movements of the five spies, and to intervene with his feeble protest as recorded in v. 18.

16. *the six hundred men, etc.* We must read ^{וְהָאֵלֹהִים} as in v. 17, in place of ^{וְהָאֵלֹהִים} indefinite.

17. *went up.* The precise significance with which the verb is used is obscure. Ros. and Stu. assume from it that Micah's sanctuary was an *'āliyyā* or upper chamber on the roof of his house, to which the ascent would have been by an external staircase; but such an inference is precarious. It is not impossible that *'ālā* may be used simply of an aggressive entry, in much the same way as it is frequently employed of making a hostile expedition (cf. *ch.* 1¹ *note*), without implication of an actual *ascent*.

they went in thither, they took, etc. The asyndeton is very harsh in the Heb., and can hardly be the work of the original narrator. Wellh. § (in Bleek, *Einleitung* ⁴, p. 198) and Bu. suggest that the two Perfects should be vocalized as Imperatives (^{בָּאוּ שָׁמָּה לְקַחוּ}), and

* Whether the statement of Ex. 32²⁶ J that Moses 'stood in the gate of the camp' implies that the camp of Israel was surrounded with a *zarība* or barricade with an actual gate is not clear; but in any case 'gate' by itself has not the same definiteness as ^{פֶּתַח הַיִּשְׁעַר}, lit. 'opening of the gate,' in our narrative.

‡ Cf. Warren in *DB.* ii. p. 432a: 'In the villages there is usually a court attached to the house, in which the cattle, sheep, and goats are penned.'

§ Wellh. retracts this suggestion in *Comp.* ³ p. 366.

Ephod, and the Teraphim, ^{R^p} and the molten image. J+Gl. And while the priest was standing at the entrance of the gate, with the six hundred men that were girt with the weapons of war, 18. J these others went into the house of Micah, and took ^{R^{JE}} the graven image, J the Ephod, and the Teraphim, ^{R^p} and the molten image. J And the priest said unto them, 'What do ye?' 19. And they said to him, 'Hold thy peace, lay thy hand upon thy mouth, and go with us; and be to *us* a father and a priest: is it better for thee to be priest to the house of one man, or to be priest to a tribe and to a clan in Israel?' 20. And the priest's heart was glad, and he took the Ephod, and the Teraphim, ^{R^{JE}} and the graven image, J and went in the midst of the people. 21. So they turned and departed, and put the little ones and the cattle and the goods before them. 22. When they were a good way from the house of Micah, the men that were in the houses which were near to Micah's house were called to arms, and followed hard after the children of Dan. 23. And they cried unto the children of Dan. And they turned their faces, and said to Micah, 'What aileth thee, that thou art up in arms?' 24. And he said, 'My gods that I made ye have

that the words originally formed the continuation of the spies' advice in *v.*¹⁴—'Now, therefore, consider what ye will do: go in thither, take the idol, etc.' This destroys the terse suggestiveness of *v.*¹⁴ as it stands in *ff.* We might parallel the asyndeton in narrative by *ch.* 20³¹ (הַנְּתִיקוּ), 20⁴³ (הִרְדִּיפוּהוּ . . . בָּתְרוּ); but here again the originality of the text may be questioned.

And while the priest, etc. Lit. 'And the priest was standing . . . and these went in, etc.' For the construction, cf. Driver, *Tenses*, § 169.

with the six hundred, etc. Lit. 'and the six hundred.' The construction may be justified as an instance of '*שֵׁשׁ* of association' (cf. BDB. p. 253*a*); yet it is not very natural, and tends to accent our suspicions as to the state of the text.

19. *lay thy hand, etc.* For the expression, cf. Mic. 7¹⁶, Job 21⁶, 29⁹, 40⁴, Prov. 30³².

21. *the goods.* Heb. כְּבוֹד only here; but cf. the usage of the masc. כְּבוֹד in Gen. 31¹, Isa. 10³, *al.*

22. *when they were, etc.* Lit. 'They were a good way from . . . and the men that were, etc.'—a circumstantial construction similar to that noticed in *v.*³.

were called to arms. Cf. note on *ch.* 6³⁴.

23. *art up in arms.* Lit. 'art called to arms' as in *v.*²². The

taken away, and the priest, and are departed, and what have I more? and how then say ye unto me, "What aileth thee?" 25. And the children of Dan said unto him, 'Let not thy voice be heard near us, lest hot-tempered men fall upon you, and thou lose thy life and the life of thy household.' 26. And the children of Dan went their way: and when Micah saw that they were stronger than he, he turned and went back unto his house. 27. And *they* took that which Micah had made, and the priest that had belonged to him, and came unto Laish, unto a people quiet and secure, and smote them at the edge of the sword, and the city they burned with fire. 28. And there was no deliverer, because it was far from Sidon, and they had no dealings with 'Aram¹; R^p and it is in the vale which belongeth to Beth-rehob. J And they built the city, and dwelt therein. 29. And they called the name of the city Dan, R^p after the name of Dan their father: howbeit Laish was the name of the city at the first. 30. E And the children of Dan reared up for themselves the graven image: and Jonathan, the son of Gershom, the son of Mo¹ses, he and his sons became priests to the tribe of the

passive verb, which seems inappropriate as addressed to Micah who was the *musterer*, of course contemplates the whole company as *mustered*.

25. *hot-tempered men*. Heb. אֲנָשִׁים מָרִי נֶפֶשׁ, lit. 'men bitter of soul,' i.e. of *fierce* (or *acrid*, Mo.) *temper*, and so, easily roused. On this use of the adjective *mar*, cf. *footnote*, p. 363.

27. *that which Micah had made*. Heb. אֵת אֲשֶׁר עָשָׂה מִיכָה, without expressed antecedent. The reference of course is to the Ephod and Teraphim of the J source; and Mo. is perhaps right in his suggestion that these originally stood in the narrative, but were omitted by the redactor of the two sources in order to make the statement more general (including the graven image).

28. *Aram*. For the emendation, cf. *v.*¹ *note*.

Beth-rehob. Cf. *note* on Rehob, *ch.* 1³¹. 'The vale' (Heb. *hā-ēmeḳ*) in which the city was situated is the broad plain of el-Buḳā' between the two Lebanon ranges.

30. *Moses*. מְנַשֶּׁה 'Manasseh,' with *Nūn* *ṭlūyā* ('suspended')—a rabbinic device intended to spare the reputation of Moses by not stating openly that he was the grandfather of a priest who practised idolatry. The fact that the reference is really to Moses was, however, acknowledged by early Jewish scholars: cf. e.g. the words of Rashi: 'Because of the honour of Moses was the *Nūn* written so as to alter

Danites Gl. up to the day when 'the Ark' went into captivity. 31. And they set them up the graven image of Micah which he had made, E all the time that the house of God was in Shiloh.

the name. The *Nûn*, however, is suspended to tell thee that it was not Manasseh but Moses.' The name Manasseh was explained as referring, not to the ancestor of the tribe bearing that name, but to the idolatrous king of Judah of the 7th century B.C., on the ground of likeness of character between him and Micah's priest: cf. Kimchi's remarks on *ch.* 17⁷. Three other cases of a 'suspended' letter occur in the Heb. Bible, viz. Ps. 80¹⁴, Job 38^{13,15}. In many Heb. MSS. and early editions מנשה is written without *Nûn* *lûyâ*. Cf., for a full conspectus of Rabbinic discussion on the subject, Ginsburg, *Introduction to the Massoretico-critical edition of the Hebrew Bible*, pp. 334 ff.

'Moses' is the reading of some G^{MSS.}, L^L, F, and appears in the conflate text of G^{MSS.}, S^h. 'Manasseh' appears in G^{BAL}, S^P, T.

the Ark. Reading הָאָרֶץ in place of הָאֶרֶץ 'the land.' The grounds upon which this emendation is adopted are explained on p. 415.

31. *all the time . . . in Shiloh.* Shiloh is the modern Sêlûn in the hill-country of Ephraim, some nineteen miles north of Jerusalem and twelve miles south of Shechem. It appears in 1 Sam. 1-4 as the site of 'the House of Yahweh' (1 Sam. 1^{7,21}, 3¹⁵), which was apparently not a mere tent but a solid structure (called *hékâl* 'temple' in 1 Sam. 1⁹, 3³) with doors (1 Sam. 3¹⁵) and door-post (1 Sam. 1⁹).^{*} This sanctuary had the custody of the Ark of Yahweh (1 Sam. 3³, 4^{3ff.}), having apparently succeeded Bethel in this capacity (cf. *note* on 'unto Bethel,' *ch.* 2¹). After the defeat of Israel and the capture of the Ark by the Philistines (1 Sam. 4^{10ff.}) we hear no more of the sanctuary of Shiloh; and though the narrative of 1 Sam. draws a veil over its fate, the assumption that it was destroyed by the Philistines seems to be justified, both from the allusions in Jer. 7^{12,14}, 26^{6,9},[‡] Ps. 78^{60ff.}, and from the fact that the Ark, when restored by the Philistines, did not return thither but remained in private custody at Kiriath-je'arim (1 Sam. 6^{20,21}, 7¹) until brought up by David to Jerusalem (2 Sam. 6), and that the principal centre of Yahweh-cultus in Saul's reign was not at Shiloh but at Nob (1 Sam. 21.22).

* The passage in 1 Sam. 2²² which refers to the sanctuary as 'the Tent of Meeting' is not found in G, and is generally regarded by scholars as an interpolation: cf. *NHTS.*² *ad loc.*

‡ The view which has been advanced by some scholars that Jer. 7^{12,14}, 26^{6,9} does not refer to the destruction of the sanctuary at Shiloh in 'Eli's time, but to a disaster (otherwise unmentioned) which was recent and still fresh in men's minds when Jeremiah wrote, is purely gratuitous. The deep and lasting impression which was made by the tragedy of 1 Sam. 4 is sufficiently illustrated by Ps. 78^{60ff.}

The meaning of the note of time 'all the time that, etc.' is very obscure. We can scarcely be intended to infer a coincidence between the *cessation* of the Dan-cultus and that of the Shiloh-cultus. The view of Ber. that the allusion is to the rough correspondence in time between the supersession of Shiloh by Jerusalem as the principal seat of Yahweh-cultus, and the supersession of Micah's image by Jerobo'am's costly golden bull and the merging of the particular cultus of the Danites into that of the northern half of Jerobo'am's kingdom, does not commend itself as at all likely.* More probably the reference is not to the *cessation* of either cultus, but to the fact that the establishment of the sanctuary at Dan was *of the same antiquity* as the establishment of the house of God at Shiloh.

THE ORIGIN OF THE LEVITES

(Cf. *ch.* 17⁷ note)

The terms in which the Levite is introduced in the story of Micah raise, in its most acute form, a difficulty with regard to the tribe of Levi which appears, on present evidence, to be almost insuperable. If Levi was, as is generally assumed throughout the O.T., in origin an independent Israelite tribe, possessing full tribal rights (the third son of Le'ah; Gen. 29³⁴ J), how can the Levite of our narrative be spoken of as having clan-connexions with the tribe of Judah. (מִמִּשְׁפַּחַת יְהוּדָה)? The distinction between the Levite's position in Judah and in Ephraim is well marked; for it is stated that, whereas he belonged to the clan of Judah, he *was sojourning* merely in Ephraim, *i.e.* he was a *gēr* or stranger enjoying certain rights of protection whilst living with a tribe of alien origin to himself: cf. the similar allusion to the Levite of *ch.* 19¹ (sojourning in the hill-country of Ephraim). Hence it has been supposed by many that the Levites were in origin not members of a separate tribe, but a *priestly caste* marked out by a special ritual training handed down from father to son. This view is thought to gain support from Ex. 4¹⁴ R^{JE}, where Yahweh, in addressing Moses, speaks of 'thy brother Aaron the Levite.' Driver (*Camb. Bib. ad loc.*) remarks, 'As Moses, equally with Aaron, belonged to the tribe of Levi (Ex. 2¹), the term, as applied distinctively to the latter, must denote, not ancestry, but pro-

* Even if we assume the very doubtful conclusion that the establishment of Yahweh's seat at Jerusalem marks the close of the Shiloh-period, there still, according to Biblical chronology (cf. 2 Sam. 5⁵, 1 Kgs. 2¹¹, 11⁴²) remains a difference of at least seventy years between David's bringing up of the Ark to Jerusalem and the establishment by Jerobotam of the bull-worship at Dan; or, if we suppose that the Jerusalem-period dates from the completion of the Temple in the seventh year of Solomon, a difference of at least thirty-three years.

fession.' He thinks (citing MacNeile, *West. Comm. ad loc.*) that 'there must have been a period in the history of the "Levites" when the term was "the official title of one who had received the training of a priest, regardless of the tribe of which he was a member by birth."' According to this view the name *Lēwī* is rightly connected in Gen. 29³⁴ J with the verb *lāwā* 'to be joined' or 'to attach oneself'; but originally in the sense of those who have attached themselves to distinctively priestly functions, *i.e.*, as we might say, *clerics* as distinct from laymen: cf. the use of the verb in Num. 18^{2,4} P, where they are spoken of as *attached* to Aaron for the service of the Tabernacle (וַיִּלְוֵהוּ, וַיִּבְלֵהוּ), and in Isa. 56⁶ which alludes to the strangers *who are attached* (הַנִּלְוִים) to Yahweh to minister to him. The

theory gains greatly in plausibility if we may assume a connexion between *Lēwī* and the term *lawī'u* (fem. *lawī'at*) which, according to Hommel (*AHT.* p. 278), is used in Minaean inscriptions to denote priests and priestesses of the god Wadd.*

The outstanding objection to this theory, which has never been met, lies in the fact that in the (in the main) very early poem ‡ which is known as the 'Blessing of Ja'cob,' Gen. 49, Levi appears as a purely secular tribe, and, together with Sime'on, is censured for some act of aggression and violence which is regarded as having brought a curse upon them resulting in their dispersion among the other tribes (נָזַל⁵⁻⁷). The event to which allusion is here made is naturally to be found in the treachery practised by Sime'on and Levi upon the Shechemites, as related in Gen. 34 (J and P combined), which may very well have led to such reprisals as decimated the two Israelite tribes and forced their remnants to seek a new home in other parts of the land. As a matter of fact, we know from Judg. 1^{3,16,17} that, at a somewhat later—but still, very early—period, Sime'on is found seeking a settlement in the Negeb in the midst of Judah, with which tribe it seems ultimately to have become merged (cf. *note* on *ch.* 1³). It is by no means improbable that the remnant of Levi may in like manner have sought a home in this region; and such an hypothesis would sufficiently

* Professor Margoliouth suggests (privately) the comparison of *Lēwī* with Ar. *wely*, the ordinary Mohammedan term for a *saint*—properly one who *is near* to God, *i.e.* in intimate association with Him, from the root *wala* 'to follow after, be near to.' For connexion of *wala* with לָוֶה, cf. Ar. *waṣa*, Heb. צוה, both in Pi'el with sense 'to enjoin'; Ar. *waḥa*, Heb. חוה, both 'to declare or reveal.'

‡ According to Skinner (*Genesis, ICC.*, pp. 510 f.), 'the Blessing' is a composite production, the earliest portions (on Re'uben, Sime'on and Levi) referring to events in the remote past, and probably composed before the Song of Deborah; those on Issachar, Dan, and Benjamin at any rate earlier than the establishment of the monarchy; while that on Judah presupposes the existence of the Davidic monarchy. The Joseph-section may be, in whole or in part, still later; but this is a very disputed question.

explain the fact that a Levite could be spoken of as 'of the clan of Judah,' much as the clan of Caleb came to be regarded as belonging to the tribe of Judah, though in origin distinct from it (cf. note on *ix.* 1¹²).

In 'the Blessing of Moses,' Deut. 33, belonging probably to the period of the divided monarchy, * Levi is regarded (in contrast to Gen. 40³⁻⁷) as entrusted with priestly functions; but still figures none the less as a *zaddik*, and on a par in this respect with the other tribes of Israel. There seems no good reason to doubt that there may be truth in the constant Israelite tradition that a tribe originally secular came at a particular period to be invested with such functions, though the tradition as to the circumstances which led to this may very well have fluctuated.† The one basic fact probably is that the Levites inherited the privilege *from Moses*, who, according to Ex. 2¹E, was himself a member of the tribe, and who, in the only early account which we possess of the Tent of Meeting (Ex. 33⁷⁻¹¹E), appears as the sole intermediary between Yahweh and Israel.

What, however, are we to infer as to the relative periods to which these events in the history of the tribe belong? To assume, as some scholars have done, that the Shechem-incident of Gen. 34, though placed by the narrator in Patriarchal times, properly refers to the period of the Judges, is surely very wide of the mark. In the first place, there is a sharp contrast between the antique tone of Gen. 34, in which tribes figure symbolically in the guise of individuals, and the vivid realism of the story of Abimelech in Judg. 9, which, while it also centres round Shechem, is as true to the life as any historical portion of the O.T. Again, while Gen. 34 brings Simeon and Levi into connexion with Shechem, the Book of Judges has nothing in this connexion to tell us of these tribes, but pictures *Margashite* clans as occupying the district—for elements of the Joseph-tribes concerning which tradition is strong that they invaded Canaan from the east under Joshua at some period subsequent to the Exodus from Egypt. Simeon, however, is pictured, at the same period or earlier, as already settled with Judah in the south (Judg. 1³¹⁻³³); and a similar inference with regard to Levi may be drawn 'as we have seen' from the genuinely old story of Judg. 17, 18, according to which the Levite was a native of Bethlehem in Judah, but a *goy* merely in Ephraim. Lastly, the whole tone of Gen. 40³⁻⁷, which has nothing but a curse for Levi as a predatory secular tribe which, with Simeon, is regarded

* Cf. the allusion to Judah in 1.7, with Driver's note (J.C.C. 2d Ser.).

† On the one hand, we have the tradition of Ex. 32²⁵⁻²⁶C and E combined, where the zeal of the Levites on Moses' side as against the bull-worshippers appears as the cause of their selection; on the other, the allusion of 'the Blessing' in Deut. 33⁸ seems to point to a tradition which related the testing of the fidelity of the tribe at Masah and Meribah (an explanation of the origin of these names different from that which is given in *ix.* 9-12 combined Num. 20¹³P); Deut. 32⁸ alludes to the selection of the tribe of Yahweh for the performance of priestly functions without specifying the circumstances.

as a disgrace to its kindred, stands, as we have noticed, in striking antithesis to Deut. 33⁸⁻¹¹; and as surely as the latter reflects the work and personality of Moses and the priestly privileges conferred by him on his tribe, so does the former point to an age when the name and reputation of Israel's great religious leader lay as yet in the bosom of the future.

If, where all is vague and uncertain, it be possible to bridge the gulf between the secular and sacred tribe of Levi by a structure of which the outlines appear to offer an approximation to reality, we may picture the Joseph tribes as already settled in Egypt, possibly for a considerable period, while the Le'ah-clans of Sime'on and Levi

which, after expulsion from central Canaan, have, together with clans of Judah, settled in the far south, in close contact, and on amicable terms, with their North Arabian neighbours—move across the Egyptian frontier in time of drought and famine with that ease with which we gather from Egyptian inscriptions that Semitic Bedawin tribes were admitted even after the fall of the Hyksos and under the restored Theban aristocracy of the Eighteenth and Nineteenth Dynasties.* This would account for the birth of Moses of Levitical parents in Egypt, and the subsequent events through which he escapes from Egypt as a political refugee and settles in Midian,† receives a revelation at Sinai, leads the tribes out of Egypt, and conducts them to the scene of the 'Theophany, which lay probably in the neighbourhood of Kadesh-Barnea', south of the Negeb, which seems to

* Cf. the two Egyptian inscriptions given by Breasted, *AR*, iii. §§ 10 ff., 636 ff. The first of these is attached to a mutilated relief depicting officials receiving instruction as to the reception of Asiatic refugees who, in time of distress, petition for a home in the domain of Pharaoh 'after the manner of your fathers' fathers since the beginning.' This, according to the inscription, is granted by Pharaoh. This inscription belongs to the reign of Haremheb, the first king of the Nineteenth dynasty; or possibly, as Breasted prefers to think, to one of the later kings of the Eighteenth dynasty under whom Haremheb held the position of general. The second inscription, which belongs to the reign of Mineptah of the Nineteenth dynasty (the assumed Pharaoh of the Exodus; cf. *Introd.* p. civ), is a letter from a frontier official in which he informs his superior that certain Edomite Bedawin have been allowed to pass the frontier and pasture their flocks in the Wādy Tūmilāt close to Pithom, *i.e.* in the district of Goshen.

† That Sime'on at any rate joined the Joseph tribes at a subsequent period is perhaps to be inferred from the tradition embodied in Gen. 42^{24,30} ff.

‡ The story of Moses' escape to Midian, where he marries the daughter of a Midianite chieftain and settles down for a time, is remarkably paralleled by the Egyptian tale of Sinuhe, who was a political exile in the reign of Sesostis I. of the Twelfth dynasty, some 700 years earlier. Sinuhe escapes from Egypt to a region in or near Canaan, and is hospitably received by the local chieft, whose daughter he eventually marries and becomes himself a sheikh of the tribe for some years, after which he returns, like Moses, to Egypt. Cf. Breasted, *AR*, i. §§ 486 ff.; Maspero, *Popular Stories of Ancient Egypt*, pp. 68 ff.; Alan Gardiner, *Notes on the Story of Sinuhe* (translation pp. 168 ff.). The parallel shows how well within the range of historical probability the Biblical story lies.

have formed their headquarters during the wilderness-period (cf. pp. 109 ff.).

Here we find him, according to the oldest tradition (cf. especially Ex. 18^{14ff.}, 33⁷⁻¹¹ E) occupying the position of supreme, or rather *sole*, exponent of religion as intermediary between Yahweh and Israel. Nothing, according to this tradition, is said of any participation by Aaron in these priestly functions—still less of his occupying the supreme position in the priesthood. In the only instance, indeed, in which Aaron is brought into connexion with the Tent of Meeting in the old narrative, he goes there with Miriam to receive a sentence of condemnation and rebuke for having ventured to speak against Moses, who is specified as God's servant with whom He is accustomed to speak mouth to mouth (Num. 12 E). In view of these facts, it at once becomes obvious that, in the expression 'thy brother Aaron the Levite' of Ex. 4¹⁴ J, which came under discussion at the beginning of this *note*, either the specification 'the Levite' does *not* distinctively denote priestly profession, or if (as seems more likely) it *does* do so, it must represent *the later point of view*, according to which Aaron and not Moses was the priest *par excellence*, and so is without value as regards any bearing upon the question of the *origin* of the Levites.

It seems not unlikely that, after a period spent in the neighbourhood of Kadesh-Barnea' (the wilderness-sojourn), while the Joseph-tribes eventually broke off from this centre, and travelled round the land of Edom in order to enter Cana'an from the east of Jordan, bearing with them the Ark of Yahweh with its priestly (Levitical) caretakers, the main part of the tribe of Levi, which, *ex hypothesi*, had even prior to the Exodus possessed associations with the North Arabian clans (subsequent elements of the tribe of Judah) inhabiting the region south of the Negeb, preferred to throw in its lot with these Judaeans, and so moved up northward with them at their conquests in the Negeb and the hill-country beyond it, which came later on to be known as the heritage of the tribe of Judah (cf. *Addit. note*, p. 44).

This theory appears satisfactorily to account for the tribal connexion of the Levites with Judah, as found *e.g.* in Judg. 17^{7ff.}, 19¹. It also offers an explanation of the story of the golden bull in Ex. 32, in which (at any rate in the form of the narrative which has come down to us) Aaron appears in an unfavourable light as the maker of the image, and the Levites in a favourable light as uncompromising adherents to the pure form of Yahweh-worship. The inference lies near to hand that the narrative, in its present form, was intended as a polemic against the bull-worship of the Northern kingdom.* The

* The narrative of Ex. 32 is composite, vv. 1-6.15-24.35 being assigned to E, and vv. 25-34 (in which the Levites figure as champions on Moses' side against the idolatry) to J; while vv. 9-14 exhibit marks of a later hand, and are usually attributed to the redactor R^{JE}. Both J and E (written from the standpoint of the

words, 'These be thy gods, O Israel, which brought thee up out of the land of Egypt' (Ex. 32⁴) are identically the same as are put into the mouth of Jerobo'am in 1 Kgs. 12²⁸, in the account of this king's institution of the bull-worship at Bethel and Dan. As spoken by Jerobo'am, the plural 'gods' naturally refers to the two images of Bethel and Dan: but in the Exodus-narrative it is difficult, if not impossible, to justify the plural as applied to the single image. If, then, at the period at which the story of Ex. 32 took shape, 'Aaron' stands as the representative of the bull-worship of the Northern kingdom, we may infer that 'the sons of Levi' are the priestly families of the kingdom of Judah, who are the champions of a purer form of cultus.* It seems to follow that, while the 'sons of Aaron' were connected with the early sanctuaries of the Joseph-tribes, Bethel, Shiloh, and Nob, the main Levite stock supplied the priestly needs of Judah in the days when this tribe lived in comparative isolation from the central and northern Israelite tribes; ‡ though single Levites might wander northward in search of a livelihood, through exercise of the priestly functions which they were fitted to discharge by birth as well as by training.§

prophetic schools of the two kingdoms) are keenly antipathetic to the bull-worship. It is possible, however, 'that—although Jerobo'am himself appointed non-Levitical priests (1 Kgs. 12³¹)—there may have been among the priests of the calves some who traced their ancestry to Aaron, and claimed him as the founder of the calf-worship in Israel. If this were the case, it would make Aaron's condemnation the more pointed' (Driver, *Camb. Bib. ad loc.*).

* Jerobo'am's appointment of non-Levitical priests to his newly equipped sanctuaries (1 Kgs. 12³¹) may have been dictated by political motives, owing to the close association of the Levites with the tribe of Judah.

‡ It is worthy of notice that, though Samuel, who was an Ephraimite, held a position at the sanctuary at Shiloh which we might have expected a Levite to fill, he *is nowhere termed a Levite*; and this is surely a very surprising fact upon the assumption that the term 'Levite' denotes official and not tribal status. His example goes to prove that in northern Israel at that period it was not deemed *necessary* that a priestly official should be a Levite by birth, rather than that a man trained for the priesthood, whatever his tribe, *ipso facto* became a Levite by profession.

§ If, as we have assumed, the remnant of the tribe of Levi found in early times a home among the North Arabian (Judaean) clans to the south of the Negeb; and if, again, members of this tribe came to adopt a wandering life in search of a livelihood as priests; is it beyond the range of possibility that some of them may have migrated southward into Arabia, and may thus account for the use of the term *lawi'u* to denote a priest, which we have noticed as occurring in the Minaean inscriptions from el-'Olâ?

19. 1—21. 25. *The outrage at Gibe'ah, with its consequences.*

Besides the Commentaries, etc., cited throughout the book, cf. Güdemann, *Tendenz und Abfassungszeit der letzten Capitel des Buches der Richter*, *Monatsschrift für Gesch. u. Wissenschaft d. Judenthums*, xviii. (1869), pp. 357-368; W. Böhme, *Richter c. 21*, *ZATW.* v. (1885), pp. 30-36.

In *ch.* 19 signs of duplication in the narrative are evident in *v.* 1.¹⁵—most strikingly in the speech of *v.* 9^b, where repetition of statement is combined with variation in number, the speaker using the plural in one set of clauses and the singular in the other: 'Behold, prithee, the day hath waned toward evening; prithee stay ye the night; and ye shall arise early to-morrow for your journey' (לִינוּ . . . וְהִשְׁכַּמְתֶּם לָרֶכֶב); 'Behold the day hath closed in; stay thou the night here, and let thy heart be merry . . . and thou shalt depart to thy home' (לִין . . . לְבָבְךָ . . . וְהִלַּכְתָּ לְאַהֲלֶךָ). In *v.* 4a.^{9b} the expression 'his father-in-law, the damsel's father,' is inelegantly redundant; and we observe that, while the former designation stands alone in *v.* 7^b, the latter so stands in *v.* 3b.^{5b.6b.8}. The expression 'the damsel's father' (predicating no position of relationship to the husband on the father's part) is suitable to the damsel's position as concubine merely and not a full wife; whereas the term *hōthēn* 'father-in-law' seems (at any rate to us) somewhat surprising in such a connexion, and it is reasonable to infer that it may belong to a version of the story in which the girl held the full status of a wife. Possibly a trace of this may be found in the statement of *v.* 1^b, 'he took to him a wife, a concubine,' where אִשָּׁה may be derived from one narrative, and פִּילגֶשֶׁת from the other.* Further, the father's offers of hospitality are couched in two different phrases, each of which occurs twice—'Strengthen thine heart,' *v.* 5b.^{8aβ} (in each case put into the mouth of 'the damsel's father'); 'Let thine heart be merry,' *v.* 6b.^{9ba}. We may notice also *v.* 2^b 'some time, four months'—a double (indefinite *and* definite) note of time (cf. *note ad loc.*); *v.* 4a, 'he abode with him three days,' but *v.* 4^b, 'and they stayed the night there'—*i.e.* apparently, the *first* night; 'they (he) arose early in the morning,' *v.* 5aβ.^{8aa} (cf. *v.* 9bβ), beside 'the man (he) rose up to depart,' *v.* 5aβ.^{7a.9aa}; 'he came over against Jebus,' *v.* 10aβ, but 'they were near Jebus,' *v.* 11aα, as though the proximity to this city were now mentioned for the first time; in *v.* 12^b the man specifies Gibe'ah as the place at which they will spend the night, but in *v.* 13 he again speaks (without any intervening response from his lad), and proposes Gibe'ah *or* Ramah (here it is clear that, while the response to *v.* 11 is contained in *v.* 12, *v.* 13—alien to this account—is continued by *v.* 11, the question 'Gibe'ah or Ramah'?

* This inference is of course precarious. אִשָּׁה פִּילגֶשֶׁת may be a compound term 'concubine-wife' (or simply 'concubine-woman,' like אִשָּׁה נְבִיאָה 'prophetess-woman, *ch.* 4⁴): cf. נָשִׁים פִּלְגִישִׁים 2 Sam. 15¹⁶, 20³.

being settled by the sun's disappearance whilst they are 'alongside of the former city'.

On the basis of these facts, we may make (somewhat tentatively) the following distribution. To the main narrative may be assigned *v.*^{1b} (omitting *אִשָּׁה* 'wife'); *vv.*^{2,3} (omitting 'four months' in *v.*^{2b}); 'the damsel's father' in *v.*^{1a}; *v.*^{1b}; 'and they arose early in the morning' in *v.*^{5a}; *v.*^{5b} (*except* 'unto his son-in-law'); *v.*⁶ (*except* 'and let thine heart be merry'); *v.*^{7b}; *v.*⁸ (*except* 'on the fifth day'); *v.*^{9a}; in *v.*^{9b} 'the damsel's father,' and the portions of the speech which are addressed to a plurality of persons (as noted above); *vv.*^{10b,11,12,15}. This narrative, which runs almost continuously, seems to bear clear indications that it is derived from J. We may notice the use of *לִקְרֹאת* 'to meet' in *v.*^{3b} of going to welcome a guest, as in the J passages Gen. 18², 19¹, 29¹³; *סַעַר לֶבֶךְ פֶּת לֶחֶם* 'strengthen thine heart with a morsel of bread,' *v.*⁵ (so *v.*⁸ without *פֶּת לֶחֶם*), which closely resembles Gen. 18⁵ J, *וְאַקַּח פֶּת לֶחֶם וְסַעַדוּ לִבְכֶּם* 'and let me take a morsel of bread, and strengthen ye your hearts'; the immediately following *וְאַחֵר תֵּלְכוּ* 'and afterward ye shall depart,' compared with *אַחֵר תַּעֲבִירוּ* 'afterward ye shall pass on' which immediately follows in Gen. 18⁵ (cf. also *אַחֵר תֵּלֵךְ* Gen. 24⁵⁵ J); the use of *הַתְּמַחְמָה* 'tarry' or 'delay,' *v.*⁸, as in Gen. 19¹⁶, 43¹⁰, Ex. 12³³, all J; *וְהִשְׁכַּמְתֶּם מֶחֱרָ לְדִרְכְּכֶם* 'and ye shall arise early to-morrow for your journey,' *v.*⁹, as in Gen. 19² J, *וְהִשְׁכַּמְתֶּם וְהִלַּכְתֶּם לְדִרְכְּכֶם* 'and ye shall arise early, and shal: depart for your journey.' The phrase of *v.*^{1b} *בִּירְכְּתִי הָרָא אֶפְרַיִם* 'in the *furthermost parts* (lit. *sides* or *flanks*) of the hill-country of Ephraim' (so also in *v.*¹⁸) is most easily explicable from a Judaeen point of view.

This J narrative is continued by the remainder of the chapter, which reads as a single continuous narrative. Points which connect *vv.*^{16,21} with J are as follows: *וַיִּשָּׂא עֵינָיו וַיִּרְא* 'and he lifted up his eyes and saw,' *v.*¹⁷, as in Gen. 13¹⁰, 18², 24⁶³, 33¹, 43²⁹, Josh. 5¹³, all J, as against Gen. 22^{4,13} E; *אָנָּה תֵּלֵךְ* 'whither goest thou?' *v.*¹⁷, as in Gen. 16⁸, 32¹⁷ (*ח*¹⁸) J; *מֵאֵין תָּבוֹא* 'whence comest thou?' as in *ch.* 17⁹ J, cf. Gen. 29⁴, 42⁷ J (Josh. 9⁸ doubtful, but assigned to J by Holzinger); *גַּם הֶבֶן גַּם מִסְפּוֹא* 'both straw and provender,' *v.*¹⁹, exactly as in Gen. 24²⁵ J, whilst the two substantives are similarly coupled in Gen. 24³² J, and the remaining occurrences of *מִסְפּוֹא* 'provender' (Gen. 42²⁷, 43²⁴) are confined to this document; use of *גַּם . . . גַּם* 'both . . . and,' *v.*¹⁹, cf. CH.^J No. 11; use of *יֵשׁ* 'there is,' *v.*¹⁹ twice, cf. CH.^J No. 84; *אֵין מִחְסוֹר כָּל דָּבָר* 'there is no want of anything,' *v.*¹⁹, as in *ch.* 18^{7,10} J; *רַק בְּרָחוּב אֵל תֵּלֵךְ* 'only do not spend the night in the market-place,' *v.*²⁰, cf. Gen. 19² J, *בְּרָחוּב נִלְיִן* 'we will spend the night in the market-place'; *וַיִּרְחֲצוּ רַגְלֵיהֶם* 'and they washed

their feet,' *v.21*, cf. Gen. 18⁴, 19², 24³², 43²⁴ (all J).* The account of the outrage, *v.22ff.*, is parallel phrase by phrase with Gen. 19^{4ff.} J in so remarkable a manner as to compel the conclusion that one narrative must have been deliberately modelled on the other. The action taken by the Levite after his return home is strikingly paralleled by Saul's action when summoning the tribes to the assistance of Jabesh of Gile'ad, 1 Sam. 11 J. The closeness of verbal coincidence is exhibited in the comparison which follows :—

Judg. 19.²² They were making merry, when behold the men of the
Gen. 19.⁴ They had not yet lain down, when the men of the

Judg. 19. city, base fellows, surrounded the house (נִסְכּוּ אֶת הַבַּיִת)
Gen. 19. city, the men of Sodom, surrounded the house (נִסְכּוּ עַל הַבַּיִת)

Judg. 19. . . .

Gen. 19. . . .⁵ 'Where are the men who came unto thee to-night?

Judg. 19. 'Bring forth the man who came unto thine house, that we
Gen. 19. 'Bring them forth unto us that we

Judg. 19. may know him.' ^{23a} And the man, the owner of the house,
Gen. 19. may know them.' ⁶ And Lot

Judg. 19. went forth unto them, and said unto them, 'Nay, my
Gen. 19. went forth unto them, . . .⁷ and said, 'Nay, my

Judg. 19. brethren, do not act wickedly, I pray you. ²⁴ Behold,
Gen. 19. brethren, do not, I pray you, act wickedly. ⁸ Behold, now,

Judg. 19. my daughter, who is a virgin, and his
Gen. 19. I have two daughters who have not known a man ;

Judg. 19. concubine ; let me, pray, bring them forth and humble
Gen. 19. let me, pray, bring them forth unto you,

Judg. 19. ye them, and do to them that which is good in
Gen. 19. and do to them according to that which is good in

Judg. 19. your sight ; but to this man ye shall not do a thing of this
Gen. 19. your sight ; only to these men do not do a thing

Judg. 19. wantonness, ^{23b} inasmuch as this man hath entered into my
Gen. 19. forasmuch as they have entered into the

Judg. 19. house.' . . .

Gen. 19. shadow of my roof.' . . .

* One characteristic E phrase, אִמָּתָךְ 'thy handmaid,' is to be noted in *v.19*. J's ordinary expression in this sense is שִׁפְחָה.

Judg. 19.²⁹ And he entered into his house, and took a knife, and took
 1 Sam. 11.⁷ And he took a yoke of oxen,

Judg. 19. hold of his concubine, and cut her up (וַיִּנְתְּחֶהָ), limb by limb,
 1 Sam. 11. and cut them up (וַיִּנְתְּחֶהֶן),

Judg. 19. into twelve pieces, and sent her throughout all the border of
 1 Sam. 11. and sent them throughout all the border of

Judg. 19. Israel. 20¹ And all the children of Israel came out
 1 Sam. 11. Israel. . . . And they came out

Judg. 19. (or were called to arms) . . . like one man.
 1 Sam. 11. (or were called to arms) like one man.

The second narrative in *ט"ז*.¹⁻¹⁶ is fragmentary, and seems to have been used merely as a supplement. It may be traced in the use of *אִשָּׁה* 'wife,' *ז*.^{1b}; 'four months,' *ז*.^{2b}; *ז*.^{4a} (*except* 'the damsel's father'); *ז*.^{5a} (*except* 'and they arose early in the morning'); 'and let thine heart be merry' in *ז*.^{6bβ}; *ז*.^{7abα}; *ז*.^{9aα}, and the parts of the speech in *ז*.^{9b} in which the man is addressed in the singular (as noted above); *ז*.^{10a.13.14}. Since the other narrative has been identified as J, it is natural to infer that the present narrative may be derived from E, though there occur no characteristic E phrases to substantiate this view. It may be noted, however, that Hosea¹, in alluding (9⁹, 10⁹) to 'the days of Gibe'ah' as marking the depth of depravity to which Israel was capable of sinking, appears to have this narrative in mind,* and also to assume that so allusive a reference will be sufficient to recall it to those for whom he is writing; and, if this is so, we must conclude that the story formed part of the historical tradition of the Northern Kingdom, whether in written (E) or oral form.

Redactional links, supplied by R^{JE}, are probably to be seen in the words 'unto his son-in-law,' *ז*.⁵, an explicative addition to J suggested by *חַתָּנוּ* 'his father-in-law' of E; 'on the fifth day,' *ז*.⁸, with back-reference to *ז*.^{5a}. Lastly, *ז*.^{1a} is obviously from the same hand as 17⁶, 18^{1aβ}, 21²⁵, viz. R^P.

Passing on to *chs.* 20, 21, we are confronted by a far more intricate problem. In *ch.* 19 the story, as we have it from J and (so far as we can judge from its fragmentary remains) in the parallel source which we have assigned to E, bears at least a superficial appearance of

* This is the only natural explanation of the allusion: cf. Cheyne's note (*Camb. Bib. ad loc.*): 'The prophet's language is correct from his own point of view. True, Israel as a people took summary vengeance on the Benjaminites for the outrage of Gibe'ah. But the seed of wickedness remained, and developed into evil practices worthy only of the Gibe'ah of old.' The interpretation of *ט* on Hos. 10⁹ finds reference to the election of Saul as king; and this explanation has been revived by Wellh., *Comp.*³ p. 233, n¹; Stade, *GLI.* i. p. 580; Nowack, *Handkommentar, ad loc.*; but it cannot be regarded as at all plausible. Cf. the discussion by Mo., *Comm.* pp. 405 f.

antiquity, and might, for ought that tells to the contrary, be assumed to embody a genuinely historical tradition. In *chs.* 20, 21, the whole atmosphere of the story is different. The tribes of Israel, when in receipt of the Levite's gruesome summons, assemble 'as one man' (20^{1,8,11}) and form themselves into *hā-ʿēdhā* 'the congregation' (20¹, 21^{10,13,16})—a term which, in this connotation, is elsewhere characteristic of P in the Hexateuch.* Their assembling is expressed by the verb *nīḫhal* (20¹), *i.e.* 'assembled themselves as a *ḫāhāl*,' this substantive being the term employed in 21^{5,8}, and in the phrase 'the assembly of the people of God,' 20²—expressions which are nearly confined to D and P.

Moreover, from this point onwards, a large part of the detail of the story is manifestly unhistorical. Considering that the old narratives of Judg. as a whole exhibit the tribes of Israel as for the most part disunited and struggling to maintain their bare existence against alien races, fighting each for its own hand, and only at the best attaining a very limited measure of cohesion when it was a matter of life or death in face of a common foe, it is impossible to entertain the credibility of the picture of a judicially constituted assembly of all Israel, mustered at short notice to sit in judgment upon Gibe'ah for an outrage (however heinous) committed against a single individual. Such an appeal as that made by the Levite may no doubt have aroused a large measure of support (cf. 1 Sam. 11 J), and resulted in reprisals upon the guilty city, if not upon the tribe of Benjamin to which it belonged, which may, as related, have rallied to its support; but this can surely not have happened in the form and on the scale pictured in the narrative as it now stands. The huge numbers of the narrative are certainly unhistorical. 25,000 Benjaminites + 700 men of Gibe'ah are mustered to oppose 400,000 men of Israel (20^{15,17}). On the first day's battle the Benjaminites slay 22,000 Israelites, apparently without themselves suffering a single casualty (20¹⁹⁻²¹). On the second day the Israelites lose 18,000, while the Benjaminites come off with the same immunity as before (20^{24,25}). On the third day as the result of Israel's ruse the tables are turned, and the Benjaminites lose 25,100 men (20³⁵; cf. 7⁴⁴⁻⁴⁶), the whole tribe being exterminated with the exception of a bare 600 (20⁴⁷). Contrast with these figures the statement of the Song of Deborah, which puts the whole fighting force of Israel at 40,000 (5^{8b}). Again, if the fact that

* העדה 'the congregation' occurs 77 times in Ex., Lev., Num., and Josh.; עדה without def. art. once; עדת (בני) ישראל 'the congregation of (the children of) Israel' 37 times; עדת יהוה 'the congregation of Yahweh' 4 times. All these occurrences belong to P, the expression being wholly absent from J, E, and D. Outside the Hexateuch the only occurrences of העדה are 1 Kgs. 8⁵ RP=2 Chr. 5⁶, 1 Kgs. 12²⁰, and the four instances in Judg. 20, 21 noticed above. These calculations are based on Davidson's *Hebrew Concordance* (with addition of עדת בני ישׁ Num. 1³, 26, omitted by Davidson).

Saul, a member of the tribe of Benjamin, was elected the first king of Israel, does not necessarily cast doubt upon the story of the disgrace of the tribe, and its reduction to the verge of extinction at some date not very long previous,* yet the account of the total destruction of the inhabitants of Jabesh of Gile'ad is at any rate rendered somewhat improbable by the fact that the city appears as a fortified city of some strength in the narrative of 1 Sam. 11. Indeed, the conjecture lies near to hand that the whole story of Judg. 19-21 may have taken its rise out of antipathy to the memory of Saul—his native city Gibe'ah, his tribe Benjamin, and the men of Jabesh of Gile'ad who owed him a debt of gratitude (1 Sam. 11) which they were not forgetful to repay to the best of their ability (1 Sam. 31^{11ff.}) being in turn held up to execration by the narrator.†

Close examination of *chs.* 20, 21 reveals the presence of a mass of discrepancies, repetitions, and dislocations which sufficiently proves that the narrative in its present form must have resulted from a very complicated process of combination and later working over. The following points may be noted:—

According to 20¹ the Israelites gather *unto Yahweh* at *Misphah*. Misphah may be assumed therefore to have been the site of an important sanctuary: cf. 20^{3a}, 21^{1.5b,8a}. In spite of this, however, they have, according to 20^{18.26}, 21², to go up to *Bethel* to consult the oracle of Yahweh.

20^{3a}, the mention of the fact that the Benjaminites heard of the mustering of the Israelites, interrupts the sequence of the narrative in the midst of which it stands, and does not receive its natural continuation until *v.* 14.

The gathering of all the men of Israel against Gibe'ah in 20¹¹ refers, as it stands, not to mobilization (already mentioned in *v.* 1), but to the beginning of active hostilities. We should expect the negotiations

* On the assumption of the substantially historical character of the narrative of Judg. 19-21, it is of course possible that the events narrated may have occurred early in the period of the Judges, and so perhaps some two hundred years before the days of Saul. Saul speaks of the tribe of Benjamin as 'the smallest of the tribes of Israel' (1 Sam. 9²¹ J), and the smallness of the tribe might be explained by the circumstances narrated in Judg. 20^{35.47ff.}; but it should be remarked that the fact of the smallness of Benjamin is inherent in the whole tradition that he was Jacob's youngest son. The narrative of Judg. 20 does not suggest that the tribe was *originally* a small one, but rather the contrary; 25,700 fighting men as against 400,000 men mustered from the rest of Israel pictures Benjamin as not markedly smaller than the average of the other tribes. It is possible therefore (in view of the suggestion put forward above that the story is coloured by antipathy to Saul and his tribe) that, so far from the smallness of the tribe in subsequent times being due to the disaster which it suffered in the days of the Judges, the story of the disaster may be a spiteful invention suggested by its smallness in the narrator's day (in face of the genuinely old tradition which implies that the tribe was small from the first, and not that it *became* small after having previously been normal in size).

† Cf. Güdemann, *op. cit.*; Wellh., *Comp.*³ p. 232 f.; Kue. *Ord.* § 209.

of *v. 12.13* to have *preceded*, and not to have followed, so extreme a measure, and to have taken place whilst the Israelites were still assembled at Mišpah, and prior to the investment of Gibe'ah.

The consulting of the oracle at Bethel, 20¹⁸, as to which of the tribes shall begin the attack, results in the specification of Judah; but there is no allusion to this in what follows. It is Israel as a whole, and not Judah simply, which offers battle to Benjamin and meets with disaster on the first day (*vv. 19-21*); and there is no mention of the separate action of other tribes on the second and third days, nor, on the other hand, of a change in the strategy resulting in the combination of all the tribes as a *new* measure.

20²², where the Israelites, in spite of the first day's disaster, take courage and again join battle, should follow and not precede *v. 23* in which they are overwhelmed by the disaster (of the first day) and consult the oracle as to whether they are to resume hostilities on the second day (*v. 24*).

20^{27a} must originally have been directly continued by *לֵאמֹר* 'saying' of *v. 28*, and cannot, as at present, have been separated from it by the lengthy and awkward parenthesis.

20³⁵ relates the smiting of 25,100 Benjaminites, *i.e.* the whole of their force except the 600 survivors of *v. 47*, and in *v. 36a* it is stated that the remnant of the Benjaminites realized that they were defeated; yet in *v. 37b* we find the Israelites still giving ground to Benjamin with the object of drawing them off from Gibe'ah, and it is not till *v. 41* that the Israelites, at the appointed signal, face about and confront the Benjaminites.

The account of the smiting of the 25,100 Benjaminites (20³⁵) is repeated at a later stage in the narrative, *vv. 44-46* (here in a round number 25,000).

20^{45a} —the flight of the survivors to the crag of Rimmon—is repeated in *v. 47a*, obviously as a resumption of the narrative after the insertion of an interpolation. The purpose of this interpolation is plain, *viz.*, to square the 18,000 of *v. 44a* with the 25,100 of *v. 35a* by the addition of 5000 + 2000 in *v. 45*, resulting in the total given in *v. 46*.

The remorse of 'the people' at the practical extinction of one tribe from Israel having been described with some detail in 21⁴⁻⁴, it is at least strange that it should be mentioned again, as though it were a fresh piece of information, in *v. 6*.

The inquiry of 21⁵ anticipates that of *v. 8*. While *v. 8* is clearly in place, offering itself as it does as a possible solution of the question put forward in *v. 7*, 'How shall we do for wives for them?' etc., *v. 6* as clearly comes too early in the narrative.

21⁹ is redundant after *v. 8b*; and though it might be just possible to refer both to the same narrator by explaining that *v. 8b* states that as a matter of fact Jabesh of Gile'ad was unrepresented in the army, and that this was then *found out* by the numbering of *v. 9*, yet this

repetition is most inelegant, and it is clear that, for the purpose of the narrative, either *v.*^{8b} or *v.*⁹ by itself is amply sufficient.

The question of 21¹⁷, 'How shall a remnant be left to Benjamin, etc.,' is strange if steps had already been taken to provide wives for the major part of the surviving Benjaminites; and the inference at once suggests itself that the sparing of the maidens of Jabesh and the rape of the maidens of Shiloh may have belonged to two different accounts of the manner in which wives were obtained for the Benjaminites, and that these accounts have been harmonized in *v.*¹³⁻¹⁶ by the explanation that the former were not sufficient, and therefore some further source of supply had to be found.

In spite of this complication, there exists a clue, the following of which seems to lead us far in the process of unravelling the different sources of the narrative. The Israelites are described by three distinct phrases. Thus we have (A) 'the children of Israel,' answering to 'the children of Benjamin,' both terms naturally construed with a plural verb; (B) 'the men of Israel,' a collective term (אִישׁ יִשְׂרָאֵל), corresponding to 'Benjamin' as a description of the Benjaminites; both of these terms are usually construed with a singular verb; (C) 'the people,' a term which appears to be used exclusively in passages which are marked by phraseology and standpoint as belonging to the latest hand of all, and in short insertions of the character of glosses in their context.*

Using this criterion, we may construct two parallel and self-consistent narratives A and B. A is practically continuous, except for omission of the account of the setting of the ambushade (after *v.*²⁸), and the ruse by which it captured the city (after *v.*^{34a}); while B, which has been drawn upon for an account of these facts, lacks the account of Israel's defeat on the first (after *v.*²⁰) and second (after *v.*^{25a}) days, of the earlier stage of the battle on the third day (after *v.*^{33a}), and of the escape of the surviving Benjaminites—details which are sufficiently supplied by the narrative of A.†

* It is of course not implied that there is anything in the ordinary Heb. usage of הָעָם 'the people' which favours the view that it is a late usage, since the fact is evident that the contrary is the case. Our postulate merely is that, as used in the *present narrative*, its occurrences happen to stand either as manifest glosses or in close association with phrases and ideas which manifestly belong to the latest stratum.

‡ The division of the sources allows, in places, room for a small amount of ambiguity. Is 20^{37b} superfluous after 20^{37a}? Probably not. While the first half of the verse mentions the onset of the ambushade, the second half describes the *manner* in which it was made (viz. by deployment), and its result. The manner in which allocation is made of 20^{45a, 47} depends upon the assumption that both A and B probably mentioned the escape of the surviving Benjaminites to the crag of Rimmon, and upon the possibility that the difference סָלַע הַרמוֹן *v.*^{45a, 47a}, סָלַע רָמוֹן *v.*^{47b}, 21¹³ may mark the different sources. It is of course

A

¹ Then all the children of Israel were called to arms as one man unto Yahweh at Mišpah. ^{3a} And the children of Benjamin heard that the children of Israel had gone up to Mišpah; ¹⁴ and the children of Benjamin were gathered together out of the cities unto Gibe'ah, to go out to battle with the children of Israel.

¹⁹ And the children of Israel arose in the morning, and encamped against Gibe'ah. ²¹ And the children of Benjamin came out from Gibe'ah, and felled of Israel to the ground in that day two and twenty thousand men.

²³ And the children of Israel went up, and wept before Yahweh until the evening; and they enquired of Yahweh, saying, 'Shall I again approach to battle with the children of Benjamin my brother?' And Yahweh said, 'Go up against him.'

²⁴ So the children of Israel drew near against the children of Benjamin on the second day; ²⁶ and [the children of Benjamin] again felled to the ground of the children of Israel eighteen thousand men. ²⁶ Then all the children of Israel went up . . . and wept, and sat down there before Yahweh until the evening.

^{27a} And the children of Israel enquired of Yahweh, ²⁸ saying,

B

¹¹ Then all the men of Israel were gathered together against the city as one man in confederacy.

²⁰ And the men of Israel went out to battle with Benjamin; and the men of Israel set the battle in array against them at Gibe'ah . . .

²² And the men of Israel took courage, and again set the battle in array in the place where they had set it in array on the first day. ^{25a} And Benjamin went out to meet them from Gibe'ah on the second day . . .

impossible to regard *v.* ^{45aa} and *v.* ^{47a} as being parallel accounts of the escape to the crag from the two sources for the reason already given, p. 448), where it is shown that *v.* ^{47a} represents the redactor's resumption of *v.* ^{45aa} after his interpolation. The B narrative as allocated contains two references to 'the children of Benjamin,' in place of the ordinary 'Benjamin' or 'the men of Benjamin,' viz. ²⁰ ⁴⁸, ²¹ ¹³; but both these are rather different from the ordinary allusions, referring, not to the army in the field, but in the first case to those who remained at home (old men, women, and children), and in the other to the survivors specified as being on the crag of Rimmon.

'Shall I again go out to battle with the children of Benjamin my brother, or shall I forbear?' And Yahweh said, 'Go up; for to-morrow I will deliver him into thine hand' . . .

³⁰ And the children of Israel went up against the children of Benjamin on the third day, and set themselves in array against Gibe'ah as aforetime. ³¹ And the children of Benjamin went out to meet them, and were drawn away from the city; and they began to smite and kill as aforetime in the field about thirty men of Israel. ³² And the children of Benjamin said, 'They are smitten down before us as at the first': but the children of Israel said, 'Let us flee; and draw them away from the city into the highways.' ^{33b} And the ambushade of Israel burst forth from its place on the west of Geba', ^{34a} and they came in front of Gibe'ah, even ten thousand chosen men out of all Israel. . . . And the battle was sore, ³⁵ and Yahweh smote Benjamin before Israel: and the children of Israel felled of Benjamin on that day twenty-five thousand, one hundred men. ^{36a} And the children of Benjamin saw that they were smitten; ^{45aa} and they turned and fled toward the wilderness unto the crag of Rimmon, ^{47aβ} even six hundred men. . . .

²⁹ And Israel set an ambushade against Gibe'ah round about.

^{33a} And all the men of Israel rose up from their place, and set themselves in array at Ba'al-tamar . . .

^{34b} but *they* knew not that evil was closing upon them. ^{36b} And the men of Israel gave place to Benjamin, for they trusted in the ambushade which they had set against Gibe'ah. ³⁷ And the ambushade hastened and made an onset against Gib'eah: and the ambushade opened out, and smote all the city at the edge of the sword. ³⁸ Now the appointment between the men of Israel and the ambushade was, that when they should make a beacon of smoke to rise up out of the city, ³⁹ the men of Israel should face about in the battle. And Benjamin began to smite and kill among the men of Israel about thirty men; and they said, 'Surely they are utterly smitten before us as in the first battle!' ⁴⁰ Then the beacon began to ascend from the city in a column of smoke; and when Benjamin looked back, behold, the holocaust of the city rose up toward heaven. ⁴¹ And the men of Israel faced about; and the men of

21.⁶ And the children of Israel were moved to pity for Benjamin their brother, and said, 'One tribe is cut off to-day from Israel.'⁷ And they said, 'How shall a remnant be left to Benjamin, that a tribe be not blotted out from Israel,¹⁸ seeing that *we* are not able to give them wives of our daughters?' for the children of Israel had sworn, saying, 'Cursed be he that giveth a wife to Benjamin.'¹⁹ And they said, 'Behold, there is the feast of Yahweh in Shiloh yearly.'²⁰ And they commanded the children of Benjamin, saying, 'Go, and lie in wait in the vineyards;²¹ and see, and, behold, if the daughters of Shiloh come forth to dance in the dances, then come ye forth from the vineyards, and snatch ye every man his wife from the daughters of Shiloh, and go to the

Benjamin were dismayed, for they saw that evil had closed upon them.⁴² So they turned before the men of Israel unto the way to the wilderness; but the battle overtook them, and they that were from the city were destroying them in the midst,⁴³ and they beat down Benjamin, and pursued him from Noḥah as far as over against Geba' towards the east.⁴⁴ And there fell of Benjamin eighteen thousand men . . .^{47b} And they abode on the crag of Rimmon four months.⁴⁸ And the men of Israel turned back unto the children of Benjamin, and smote them at the edge of the sword, both inhabited city, and cattle, and everything that there was; moreover all the cities that there were they set on fire.

21.¹ Now the men of Israel had sworn in Mišpah, saying, 'There shall not any of us give his daughter to Benjamin to wife.' . . .⁷ 'How shall we do for wives for them, seeing *we* have sworn by Yahweh not to give them of our daughters to wives?'⁸ And they said, 'What one is there of the tribes of Israel that came not up unto Yahweh to Mišpah? And, behold, there had come no man to the camp from Jabesh of Gile'ad.'¹⁰ So they sent thither twelve thousand men of the most valiant, and commanded them, saying, 'Go, and smite the inhabitants of Jabesh of Gile'ad at the edge of the sword, with the women and the little ones;¹¹ but the virgins ye shall save alive.' And they did so.¹² And they found of the inhabitants of Jabesh of Gile'ad four hundred

land of Benjamin. ²² And when their fathers or their brothers come to complain unto you, ye shall say, 'Grant them graciously to us; for we took not every man his wife in battle: for if ye had given them to us, ye would now be guilty.' ²³ And the children of Benjamin did so, and took wives according to their number of the dancers that they had forcibly carried off: and they went and returned unto their inheritance, and built the cities, and dwelt in them. ^{24a} And the children of Israel departed thence at that time, every man to his tribe and to his clan.

virgin girls, that had not known a man; and they brought them unto the camp. ¹³ Then they sent, and spake unto the children of Benjamin that were on the crag of Rimmon, and proclaimed peace to them. ¹⁴ And Benjamin returned at that time, and they gave them the women that they had saved alive of the women of Jabesh of Gile'ad. . . . ^{24b} And they went out thence every man to his inheritance.

The occurrences of phrase (C) 'the people' are 20^{2a, 8a, 10a, 16, 22a, 26a, 31b, *}, 21^{2, 4, 9, 15}. The fact that this phrase is an editorial gloss in 20^{22a, 26a} is obvious; whilst in 20^{2a} it is associated with the phrase 'the assembly of the people of God' (קהל עם א') which is of a piece with the late priestly conception of Israel as 'the congregation' (העדה) in v.¹; and in 20²ⁱ, 21²⁻¹ with the going up to *Bethel* and the offering of sacrifices. Here Bethel is doubtless regarded, from the post-exilic standpoint, as the single sanctuary for sacrifice at this time, legalized as such by the presence of the Ark and the ministration of Phinehas as Aaron's lineal descendant: cf. *ch.* 2¹⁻⁵. The writer accepts the allusion to Mišpah in the two older narratives as the *place of muster*, but does not recognize it as a *sanctuary*, in spite of the fact that the expression 'unto Yahweh' and the allusion to the oath taken there seem to imply that it was such. It is probable that in 20²⁶ mention of Mišpah as the place to which 'the children of Israel went up' was cut out by him when he inserted 'and all the people, and came to Bethel'; and a similar excision may have been made in 20²³.

The conception of all Israel acting together as a politico-ecclesiastical body (*ʿēdhā*) seems to be based upon the expression 'as one man,' which, if our analysis is correct, occurs both in A (20¹) and in B (20¹¹). This latter expression, while not in itself a mark of post-exilic date (see below), was admirably fitted to form the text of the post-exilic writer's expansion. The *ʿēdhā* is naturally conceived as acting in accordance with a strictly judicial procedure, as appears

* The occurrence in 20^{31a} לקראת העם א' disappears under our emendation לקראתם. Cf. note *ad loc.*

in 20^{3b-13}; and it should not be doubted that this passage (though the section *vv.* 3b-8 is commonly assigned by scholars to the oldest narrative) belongs, at least in its present form, to the latest hand. The fact that it breaks the connexion which must once have existed between *v.* 3a and *v.* 14 favours the view that it is an interpolation. Besides the two occurrences of 'the people' (*vv.* 8a, 10a), we may notice, as marks of this hand, the use of זמה 'lewdness' in *v.* 6 (in this sense a characteristic phrase of H and Ezek.), 'the country of the inheritance of Israel' in *v.* 6, and the phrase בער הרע 'extirpate the wickedness,' *v.* 13 (D and later). The details of the outrage as described by the Levite are naturally drawn by the late hand from the old narrative of *ch.* 19; but the statement of *v.* 5b 'me they thought to have slain' is a softening down of the grossness of 19^{22b}, which possibly marks the superior refinement of a later age.

The account of the numbering of the two rival armies in *vv.* 15-17 has been assigned, in its present form, to the late hand, the main determining factor being the combination of the phrases 'the children of Benjamin' (*v.* 15), 'this people' (*v.* 16), 'the men of Israel' (*v.* 17). Both the narratives A and B, however, deal with large numbers in their account of the battle, and may therefore be conjectured to have made mention of the original numbers of the two hosts; and fragments of their accounts may well have been incorporated by the late hand. There is an obvious connexion between the 25,000 Benjaminites + 700 men of Gibe'ah, and A's account of the 25,100 who fell in battle, leaving 600 survivors. The verb התפקר where used again in the narrative (21⁹) undoubtedly belongs to the late hand.

The account in *v.* 18 of the consulting of the oracle at Bethel as to which tribe shall open the attack, and the designation of Judah—a proceeding which, as we have already noticed (p. 448), seems to have no effect whatever upon the subsequent course of action—is of great interest. Clearly it has been taken straight from the J narrative *ch.* 1^{1,2}, without regard for its appropriateness; and since it was R^p who added the Introduction *ch.* 1^{1-2,5} to Judg., it is fair to assume that the extract is due to this redactor, and that it is his handiwork which we have been discussing as 'the late hand,' and not some originally distinct and independent source. We have already observed that the designation of Bethel as Israel's proper sanctuary goes back to *ch.* 2¹⁻⁵.

In 21¹¹ ידעת מיטכב זכר and in *v.* 12 the addition למיטכב זכר seem to be derived directly from Num. 31^{17,18,35} P. For the older narrative the phrase לא ידעה איש suffices; cf. *ch.* 11³⁹.

The remaining passages assigned to R^p fall into the following groups:—passages governed by the conceptions of the *'ēdhā* and of Bethel as the sacrificial centre, and by reference to 'the people,' 20²⁶ in part 27b, 28a in part 21^{2-5, 9, (10, 13, in part) 15, 16}; harmonistic links, 20^{15a, 3b, 46, 47a, 48},

21^{14b}; statistical notes introduced by בל אלה, 20^{25b, 35b, 44b} (so ז. 46^b; cf. כל זה ז. 16^b, and for שלף חרב ז. 2b, 15a, 17a, 46^b, ch. 8¹⁰); topographical notes, 20^{31b} in part, 21^{12b, 19} in part (cf. ch. 18^{12b, 19, 28a, 29}; and for the descriptive phrase 'which is in the land of Cana'an,' 21^{12b, 19}, cf. Josh. 22^{9, 10} P); 21²⁵, cf. 17⁶, 18^{1a}, 19^{1a, 2}.

There still remains the question of identification of the sources A and B. As regards B this seems sufficiently clear. The phrase 'the men of Israel' occurs in 19³⁰ as restored after E, and this passage is the continuation of the preceding J narrative in that chapter, and may well have been the antecedent to our narrative B. The account of the ruse by which the city of Gibe'ah was ambushed and burnt, and the panic-stricken Benjaminites caught between two forces of Israel, which has been assigned to B, bears close resemblance to the ruse by which 'Ai was captured and destroyed, as related in Josh. 8 which is mainly from J. Cf. especially ז. 34^b, 'but they did not know (והם לא ידעו) that evil was closing upon them,' with Josh. 8^{14b}, 'but he did not know (והוא לא ידע) that there was an ambush against him behind the city'; ז. 40^b 'and Benjamin looked back, and, behold, the holocaust of the city rose up toward heaven,' with Josh. 8^{20a} 'and the men of 'Ai looked back and saw, and, behold, the smoke of the city rose up toward heaven'; ז. 42^{aa} 'so they turned . . . unto the way to the wilderness,' with Josh. 8¹⁵ 'and they fled by the way to the wilderness'; ז. 42^{a, b} 'but the battle overtook them, and they that were from the city were destroying them in the midst' (בתוך), with Josh. 8^{21b, 22}, 'then they turned again and smote the men of 'Ai. And the others came forth out of the city against them; so they were in the midst of Israel (ויהיו לישראל בתוך), some on this side, and some on that side; and they smote them, etc.'; ז. 48 'and the men of Israel turned back unto the children of Benjamin, and smote them at the edge of the sword,' with Josh. 8^{24b}, 'and all Israel turned back unto 'Ai, and smote it at the edge of the sword.' The description of the muster of the men of Israel 'as one man' (20¹¹) and the large number of Benjaminites slain (18,000 according to 20⁴⁴), cannot be said to be inconsistent with J's authorship. In the narrative of 1 Sam. 11, part of J's account of the circumstances which led to Saul's election to the kingship, which is of acknowledged antiquity as compared with the parallel narrative from E, and which, in 11⁷, shows close affinity to the J narrative in Judg. 19 (cf. p. 445), it is stated that, on the receipt of Saul's summons, the Israelites were called to arms 'as one man,' and the muster produces the incredible numbers of 300,000 Israelites and 30,000 men of Judah. There is no ground whatever for the assumption that exaggeration of numbers is peculiar to post-exilic narrative. Any narrative, whether pre- or post-exilic, if committed

to writing long after the events which it narrates, seems to have been liable to this failing. We have already noticed (cf. p. 120) that, in contrast to the modest assessment of 40,000 able-bodied men of Israel given by the contemporary Song of Deborah, the narrative of J in Ex. 12^{37b}, Num. 11²¹ estimates the men who came out of Egypt as 600,000. The very fact that our narrative in 19²⁰ states that the Levite divided his concubine into *twelve* pieces, and sent her throughout all the border of Israel, pictures Israel as already a federated entity of twelve tribes, and paves the way for the description of a unanimous response (contrast the *historical* account of the merely partial response to Deborah's summons), and for an incredibly high estimate of the muster. While, however, we assign the narrative B to J, the fact cannot be overlooked that this narrative, in *ch.* 19 as in *chs.* 20, 21, must belong to the latest stratum of J. The fact that it exhibits throughout so close a verbal connexion with various other parts of J (Gen. 19¹⁻⁸, 1 Sam. 11⁷, Josh. 8), proves that the dependence is on its side and not *vice-versâ*, and therefore that it has been constructed by a process of selective imitation, and must be much later than the old narratives which it has employed, and, in its present form at least, almost certainly unhistorical. On the other hand, the fact that the author has employed J, and J only, as his model, and that his phraseology is uncoloured by the influence of later literature,*

* Exception will doubtless be taken to our inclusion of 21^{7,8,10,12-14a} (in the main) as part of J, this being a narrative which many critics (*e.g.* Mo.) regard as the latest part of the narrative, on the ground that it is based on Num. 31^{1ff.}—the carrying out of the *hérem* or ban upon Midian—a story which is assigned with good reason to a secondary stratum of P. The striking points of connexion between the two narratives which are adduced are (1) the fact that the number of warriors sent to execute the *hérem* is the same in each narrative, viz. 12,000, and (2) the phrase which occurs in Judg. 21^{11,12} to mark the distinction between the married and unmarried women (לֹא יָדְעָה אִישׁ לְמִשְׁכָּב זָכָר), as compared with Num. 31^{17,18,35}. It should be recollected, however, that the custom of the *hérem* was very ancient; and that, when this was practised, the saving of the unmarried girls as slave-concubines must have been frequent, if not regular (cf. Deut. 21¹⁰⁻¹⁴). The phrase noted under (2) *does* seem to have been derived from the narrative of Num., as remarked above. On the other hand, we should not overlook such distinctions between the two narratives as the regular and exclusive use of הָרַג 'kill' in Num. (*vv.* 7-8*bis.* 17*bis.* 19) as contrasted with הָכָה לְפִי חֶרֶב 'smite at the edge of the sword' in Judg. 21¹⁰, הָחֵרִים 'ban or devote to destruction' *v.* 11; הָטָף בְּנִשִּׁים 'the young among the women' in Num. 31¹⁸, but נָעָרָה בְּתוּלָה 'virgin-girls' in Judg. 21¹². The identity in number, 12,000, is, it may be admitted, somewhat striking; but, if on this score we are to infer connexion between the two narratives, the dependence is quite as likely to be on the side of the late narrative in Num. as *vice-versâ*. The involving of Jabesh of Gile'ad in the odium which falls upon Gibeah and upon the whole tribe of Benjamin fits in so well with the theory that the story as a whole makes an attack upon the memory of Saul (cf. p. 447) that it is difficult to suppose that the whole Jabesh-narrative was only inserted as a very late afterthought.

seems to indicate that we are right in regarding him as pre- and not post-exilic.*

The origin of the narrative A is far more dubious. If B is rightly identified with J, it is natural to look for indications of the hand of E in the companion-narrative, more especially as the second source in 19¹⁻¹⁵ has been conjecturally assigned to E; and since the use of high numbers in 20^{21,25,35} does not (as we have just noticed) necessarily imply a post-exilic point of view, there is no *prima facie* reason why this narrative should not date from pre-exilic times. No signs of E's phraseology are, however, apparent in the narrative; while, on the other hand, there are several indications that it, like B, was acquainted with J's account of the attack on 'Ai in Josh 7, 8: cf. *ch.* 20^{23,26}, 'they wept before Yahweh until the evening,' with Josh. 7⁶, 'he fell on his face to the earth before the Ark of Yahweh until the evening'; 20^{31a} 'they were drawn away (הִנְתָּקוּ) from the city,' *v.* 32^b, 'Let us flee and draw them away (וְנִתְקַנּוּהוּ) from the city,' with Josh. 8^{5bβ,6aa}, 'and we will flee before them . . . until we have drawn them away (עַד הִתְקִינוּ אוֹתָם) from the city,' 8^{16bβ} 'and they were drawn away (וַיִּנְתָּקוּ) from the city'; *ch.* 20³² 'And the children of Benjamin said, "They are smitten down before us as at the first" (כְּבִרְאִשְׁנָה); but the children of Israel said, "Let us flee, etc.,"' with Josh. 8⁶ 'for they will say, "They are fleeing before us as at the first" (כַּאֲשֶׁר בְּרִאִשְׁנָה); so we will flee before them'; *ch.* 20^{31a} 'and they came over against (מִנְּגִד ל) Gibe'ah,' with Josh. 8¹¹, 'and they came over against (נִגַּד) the city.' These facts, together with the artificial appearance of the narrative of the three days' battle (which, however, is scarcely more marked than in E's narrative in *ch.* 7²⁻⁸), and, especially, the fact that the *combination* of A and B appears to have been effected, not by a pre-exilic redactor (such as R^{JE}), but by R^P himself (cf. especially the redactional link 21^{14b-16}), seem to favour the conclusion that we have in A a post-exilic narrative of unknown provenance, possibly containing some independent and relatively ancient elements (*e.g.* the story of the rape of the maidens of Shiloh †), but otherwise perhaps ultimately based upon the older J narrative with which it was eventually com-

* It may be noted that the J writer is characterized, in the account of the battle, by an unusual fondness for placing the subj. before the verb when the subj. changes in the sequence of the narrative:—cf. 20^{33a} וּבָלַ אִישׁ יִשְׂרָאֵל קָמוּ, 20^{37a} וְהָמִשְׁאֵת וּבְנִימִין הָחֵל, 20^{39b} וְהָמוּעַד הָיָה, 20^{38a} וְהָאֲרָב הִחִישׁוּ, 20^{41a} וְהָחֵלָה, 20^{43a} וְאִישׁ יִשְׂרָאֵל שָׁבוּ, 21^{1a} וְאִישׁ יִשְׂרָאֵל הִפָּךְ, 20^{41a} וְהָחֵלָה נִשְׁבַּע.

† The fact that this story is probably ancient has been generally recognized. Unlike other parts of the narrative which have the superficial appearance of antiquity, but are really based on other narratives (cf. the foregoing discussion of the J narrative), it appears, so far as we can judge, to be independent; and it may well be that, if any part of *chs.* 19-21 is historical as it now stands, such an historical element may be contained in this story. It seems not impossible that it may have been derived ultimately from the E source.

bined by R^p. The narrative A, as of unknown source, has been marked in the text by the symbol X.*

* The foregoing analysis was worked out independently by the present editor prior to consultation of the attempted analyses of other scholars, and differs very widely from them. Chapters 20 and 21 have not unnaturally given scope for great divergency of opinion among commentators in the past; but, speaking generally, it may be said that in the main some agreement in the guiding principle of analysis has been reached by the most recent writers, as represented, *e.g.*, by Mo. (*Comm.* and *SBOT.*), Bu. (*Comm.*), No., Driver (*LOT.*⁹, p. 170), Kent. This principle appears to be that, since *ch.* 19 'is old in style and representation,' its continuation in *chs.* 20, 21 must have been similar, the assumption being that such similarity should be found in absence of the element of exaggeration and incredibility. Thus, drastic elimination is made, not merely of the passages which picture Israel as organized as an 'ēdhā (assigned by us to R^p), but (in spite of 1 Sam. 11⁷⁻⁸ J) of all passages which speak of Israel as acting 'as one man,' and which deal with incredibly large numbers. Mo. (*SBOT.*) assigns to J 20^{1aα.1bβ.3-8.14.19.29.36.37a.38.39} (om. 'as in the first battle')^{40.41.44a.47}, 21^{1.15.16b-19a.20b.21.22aα.22b.23}, and regards the rest of the narrative as a post-exilic Midrash, 20^{11.18.23.24.27b.28aα.37b}, 21^{4.5.8} end ('unto the assembly')¹⁹ (from 'which is north,' etc.) being redactional. Driver (on the basis, mainly, of the analyses of Bu. and No.) assigns to the earlier source (except a few words here and there) 20^{1aα.1bβ.3-8.14.19.29.31-34.36b.37a.38.40-42.44a.47}, 21^{1-6-8.10-12} (in briefer form)¹³⁻¹⁴ (with 'they' for 'the whole congregation')^{15.17-25}. These analyses give us, as the oldest (presumably historical) narrative, the account of the outrage as given in *ch.* 19, with the Levite's summons to Israel; the assembling at Mišpah and an enquiry into the circumstances of the crime, followed by a *one day's* battle in which by aid of an ambush the Benjaminites are defeated and almost exterminated; and, lastly, provision of wives for the survivors [by saving the unmarried maidens of Jabesh, and] by capture of the maidens of Shiloh.

The fallaciousness of an analysis which is based on the view that the older narrative can be recovered by elimination of all that is patently unhistorical has been sufficiently demonstrated by the foregoing discussion. 'The antiquity of *ch.* 19 is (as Wellh. rightly recognizes) more apparent than real, since, as we have seen, this narrative (at least in part) is framed in close imitation of older J stories—a fact which leads us with some reason to question its historical value. Why, *e.g.*, should we accept the account of the Levite's method of appeal to the tribes of Israel, which is manifestly connected with 1 Sam. 11⁷, and at the same time reject both the allusion to the Israelites' assembling 'as one man' (though this identical phrase occurs in the same verse of 1 Sam. 11), and also the use of high numbers (though this is paralleled by 1 Sam. 11⁸)? Again, if, as cannot be denied, the account of the ambushing of Gibe'ah (generally accepted as ancient) depends on Josh. 8, why should not the account of success attained by this ruse have been preceded by a narrative of two days' failure, on the analogy of Joshua's first failure against 'Ai, as related by the J narrative in Josh. 7? Lastly, what ground exists for the supposition that a narrative which bears strongly the stamp of J phraseology, and is obviously modelled on earlier J elements, was continued by the story of the rape of the Shilonite maidens, which contains no J phrases and is independent of any earlier similar narrative?

On the other hand, the merit of the criterion for analysis which we have adopted (cf. p. 449) rests in the fact that, without any sleight of hand, it immediately resolves the confusion of the narrative as it now stands, and offers us two parallel and nearly continuous narratives, together with the additions of a later redactor, the object of which can easily be divined. The distinction in the usage

19. 1. R^p Now in those days, when there was no king in Israel, J there was a certain Levite sojourning in the furthestmost parts of the hill-country of Ephraim, who took to him ^Ea wife, J a concubine out of Bethlehem of Judah. 2. And his concubine 'was vexed' with him, and went away from him unto

19. 1. *in those days.* *I.e.* in the days of the Judges, rather than (as Mo. thinks) 'loosely dating the following story in the period of the Danite migration.'

When there was no king, etc. Cf. p. 410.

a certain Levite. Lit. 'a man, a Levite'; so *ch.* 20⁴ 'the man, the Levite,' *ch.* 18^{3,15} 'the youth, the Levite.' The man is only twice described as a Levite, being elsewhere mentioned merely as 'the man': hence Bu. supposes that the words לוי גר 'a Levite sojourning' are a late insertion under the influence of the preceding narrative—but this hypothesis has little to support it.*

the furthestmost parts. Heb. *yarkêthê*, lit. 'sides' or 'flanks,' is used of the *innermost recesses* of a cave, 1 Sam. 24⁴, a house, Am. 6¹⁰, a ship, Jon. 1⁵, the pit (*i.e.* She'ol), Isa. 14¹⁵, or of the *remote parts* of the north, Isa. 14¹³, *al.*, or, of the earth, Jer. 6²², *al.* Hence the expression as here used is taken by Mo., Cooke to refer to the most northerly parts of Ephraim, from the Judæan point of view. More probably the reference is to the actual flanks of the hill-country, whether to the east or west, which, lying away from the main route from south to north (which then, as now, must have run along the centre of the range) might, especially from the Judæan standpoint, be viewed as somewhat remote.

2. *was vexed with him.* Reading וַתִּזְעַק עָלָיו with Böttcher, Houb., Grätz, Mo. (*SBOT.*), Kit. Cf. א^{AL}, ש^h, ז^l και ὀργισθη αὐτῷ (the root זעק is rendered by ὀργίζειν in 2 Chr. 16¹⁰). For זעק followed by על, cf. Prov. 19³. וַתִּזְנֶה עָלָיו וַיִּזְנֶה, R.V. 'played the harlot against him,' can hardly be original; for (1) the context

of the phrases 'the men of Israel' and 'the 'children of Israel' was observed by Ber. as one of his criteria; though he does not work it out consistently, and also fails to distinguish the redactional passages from the sources. His analysis is as follows:—A 20 1.2b-10,14.(18).19.24-28.29-36a.47, 21 5-14.24; B 20 2a.11-13.15-17.20-23.29b-41.45.46.48, 21 1-4.15-23.

* Bu. finds fault with the constr. וַיְהִי אִישׁ לְוִי גֵר on the ground that we should expect גֵּר וְהָיָה לְוִי; but it is difficult to see any essential difference between the participial usage in our passage and, *e.g.*, Gen. 25² וַיַּעֲקֹב אִישׁ תָּם יָשֵׁב אֶהְלִים 'and Ja'cob was a simple man, dwelling in tents.'

her father's house, unto Bethlehem of Judah, and was there some time, E four months. 3. J And her husband arose, and

demands that the cause of estrangement should be a passing tiff and not an act of unfaithfulness, and (2) the constr. זנה followed by על of the person against whom the offence is committed is unparalleled (the verb is regularly in this sense followed by מן 'away from,' by itself or in combination with another prep., מאחרי, מעל, מתחת).

סנאס זאססו^p reproduces ז; and it is probable that ἔ^B και ἐπορεύθη ἀπ' αὐτοῦ, F 'quae reliquit eum,' Jos. (*Ant.* v. ii. 8) καταλιπούσα τὸν ἄνδρα, are merely paraphrases of the same reading: cf. the comment of Levi ben-Gershon, who explains that the verb must be taken to mean simply that the woman forsook him, and not in its ordinary sense, otherwise it would have been unlawful for the Levite to fetch her back. ובסרת עלוהי^ט, 'despised him,' may also be a paraphrase, unless ובסרת represents נתבזה (Dathe); but here again the following עליו forms a difficulty (only found in the late passage, Neh. 2¹⁹). The same objection is valid against the easy emendation ונתבזה, adopted by Michaelis, Ewald (*HI.* ii. p. 352), Stu., Wellh. (*Comp.*³ p. 230), etc.; this verb being ordinarily (if not exclusively*) transitive and followed by an accusative in the sense *cast off* or *spurn* a personal or impersonal object. Mo. suggests, as another possibility, that the original of καὶ ὤργισθη αὐτῷ was ותאנה עליו, that this verb was corrupted into נתנצה ('she committed adultery'), which, again, was later on corrected into ונתבזה upon the ground that the woman was not a wedded wife. This suggestion (favoured by Bu., No., La.) is almost too ingenious; and, as Mo. himself observes, the prep. ב (and not על) is regularly used after the verb אנה.

some time, four months. Heb. ימים ארבעה חדשים. Here ימים (as in *ch.* 14⁸, 15¹) seems to refer to a period of *indefinite length*, which is then accurately defined by ארבעה חדשים; ‡ and the natural inference is that the latter definition is a gloss upon the former, or rather (as assumed in our analysis) that it is derived from the parallel source (cf. the precision of this source in *שם*^{4,5}, 'three days,' etc.). The appositional relation between ימים and ארבעה חדשים is hardly

* It may, however, be possible that זנה, when used absolutely (cf. *e.g.* Ps. 74¹, 77⁸, Lam. 3³¹) may possess the sense 'to be angry,' which regularly belongs to the Bab. equivalent *zīnū*. If this be so, it is not inconceivable that the verb might be construed with על 'was angry *against*,' much as the Bab. verb is construed with *itti*, 'be angry *with*' (cf. the illustration cited p. 59).

‡ ימים וארבעה חדשים, 1 Sam. 27⁷, is of course different; this meaning 'days (*i.e.*, by usage, a year) and four months.'

went after her, to speak kindly to her, to bring [†]her[†] back again, having his lad with him, and a couple of asses, and [†]he came[†] to her father's house: and when the damsel's father saw him, he came joyfully to meet him. 4. E And his father-in-law, J the damsel's father, E detained him; and he abode with him three days: J and they did eat and drink, and stayed the night there. 5. E And on the fourth day J they arose early in the morning, E and he rose up to depart: J and the damsel's father said ^{RJE} unto his son-in-law, J 'Strengthen thine heart with a morsel of bread, and afterward ye shall depart.' 6. So they sat down, and did eat, both of them together, and drank: and the damsel's father said unto the man, 'Prithee consent, and stay the night, E and let thine heart be merry.' 7. And the man rose up to depart: but his father-in-law urged him, J and he stayed the night there again. 8. And he arose early in the morning ^{RJE} on the fifth day J to depart: and the damsel's father said, 'Prithee strengthen thine heart'; so they tarr[†]ied[†] till the day declined, and did eat,

identical with the very idiomatic usage of ימים when it pleonastically follows the statement of a definite period, as e.g. in חֹדֶשׁ יָמִים 'a month of time' (lit. 'a month, days'). Cf., on this latter usage, the discussion in Ges., *Thes.* 585b, where the analogous usage of *zamān* 'time,' in Ar. is cited.

3. *to speak kindly to her.* Lit. 'to speak to her heart.' Cf., for this idiom, Gen. 34³, 50²¹, 2 Sam. 19⁷, ^ח 8, Isa. 40², Hos. 2¹⁴, ^ח 16, Ru. 2¹³, 2 Chr 30²², 32⁶†.

to bring her back again. Reading לְהַשִּׁיבָהּ, in place of להשיבו.

and he came. Reading וַיָּבֹא with ^{AL} ^h ^h, and moderns, in place of וַתָּבִיֵּאָהּ. Mo. plausibly suggests that the readings of ^ח here and in the preceding להשיבו—which he renders 'that she might win him back'—are early alterations based upon the corruption וְהוֹנָה in v.², on the view that, since the man was the injured party, it was for the woman to make the advances towards reconciliation.

5. *Strengthen thine heart.* Heb. סָעֵד לִבְךָ. Here the Imperative is to be pronounced ^s^e ^ʾ^ʾ ^ʾ ^ʾ (not ^s^e ^ʾ^ʾ ^ʾ ^ʾ) the conjunctive accent *Darga* which it bears being used as a substitute for *Methegh*: cf. G-K. § 64c, n².

8. *So they tarried.* Reading וַיִּתְמַהֲמְהוּ with La., in place of ^ח וַהֲתִמְהֲמְהוּ which can only be an Imperative (so all Versions). Since, however, in v.⁹ the father uses the fact that the day has declined as

both of them. 9. E And the man rose up to depart, J he and his concubine and his lad ; E and his father-in-law, J the damsel's father, E said to him, J ' Behold, prithee, the day hath waned to setting, prithee stay ye the night : E behold, the day hath closed in ; stay thou the night here, and let thy heart be merry ; J and ye shall arise early to-morrow for your journey, E and thou shalt

a reason why they should stay the night, and leave (presumably in good time) on the morrow, he would scarcely in the first place have urged them to tarry till the decline of day before starting on their return. Mo. notes the fact that certain groups of \mathfrak{C} MSS. (cited by him as \mathfrak{C}^{MN}) offer (in place of והתמהמהו, which is rendered by \mathfrak{C}^{AL} καὶ στρατεύθητι, \mathfrak{C}^{B} καὶ στρατεύσον*) the reading διεπλάνα αὐτόν or διεπλάτυνε αὐτόν (cf. Field, *Hex.*, *ad loc.*), i.e. וַיִּפְתָּהוּ ; whence he conjectures that the original text may have run וַיִּפְתָּהוּ וַיְתַמְּהֵמָה, 'and he persuaded him, and he lingered,' etc. This gives an excellent sequence, and is accepted by Bu., No., Kit., with the modification וַיְתַמְּהֵמָה ; but the method of constructing a composite text from two variant readings must be deemed somewhat questionable.

and did eat. \mathfrak{C}^{AL} adds καὶ ἔπιον (so \mathfrak{S}^{h} with obelus) ; cf. *vii.*^{4,6}.

9. the day hath waned to setting. Heb. רָפָה הַיּוֹם לָעֶרֶב, lit. 'the day hath sunk down so as to set.' 'Day' is here used by metonymy for 'sun,' as sometimes in English : cf. passages cited in the Oxford *New Eng. Dict.* s.v. 'set' II. 9 b. The use of *nāphā* may be paralleled by Bab. *rabū* or *raḫū* which is used of the *sinking* of the sun to the Underworld : cf. Muss-Arnolt, *Dict.* p. 949, and *note* on 'Teraphim,' p. 421. There is no ground for substituting נטה רפה with Mo. SBOT. \mathfrak{C} εἰς (τήν) ἑσπέραν reads לָעֶרֶב for לָעֶרֶב, which may be original.

behold, the day hath closed in. Heb. הִנֵּה הַנּוֹת הַיּוֹם, lit. 'behold, the closing (declining) of day.' Heb. *hānā*, which is elsewhere used in the special sense of *encamping*, is here a synonym of *nāfā* (cf. *v.*⁸) in the sense *bend down* or *decline*, which, as is shown by the cognate languages (Ar., Syr.) is the original meaning of the root.

\mathfrak{C}^{B} , \mathfrak{S}^{p} omit הנה הנות היום, thus removing the duplication in the invitation which probably marks the different sources (cf. p. 442). \mathfrak{C}^{AL} καταλύσον (^lδῆ) ὥδε ἔτι σήμερον seems to have arisen through combination with the preceding לינו נא and the reading of הנה as

* Mo. notices that the original \mathfrak{C} reading is clearly στρατεύθητι (for στραγγεύθητι) which is found in the HP. codd. 15, 18, 64, 65 ; \mathfrak{S}^{h} ןס״ל. This has become στρατεύθητι through the not uncommon confusion between Γ and Τ in uncial writing ; and στρατεύσον represents a grammatical correction.

depart to thy home.' 10. And the man would not stay the night; but he rose up and departed, and came over against Jebus^R (that is Jerusalem): J and with him were a couple of asses saddled; his concubine was with him also. 11. When they were near Jebus, the day 'was far spent'; and the lad said unto his master, 'Prithee come, and let us turn aside into this city of the Jebusites, and stay the night in it.' 12. And his master said unto him, 'We will not turn aside into the city

הָנָה (apparently הָנָה עוֹד הַיּוֹם); but we are not justified in looking to this rendering for the original text (as does Mo., followed by Cooke), since לַיִן should be followed by הַלַּיְלָה 'to-night,' and not by הַיּוֹם 'to-day.'

to thy home. Lit. 'to thy tents': cf. for this usage *ch.* 7⁸, 20⁸, Deut. 16⁷, Josh. 22^{4,6,7,8}, 1 Sam. 13², 2 Sam. 19⁹, 20^{1,22}, 1 Kgs. 8⁶⁶, 12¹⁶. According to Driver (on Deut. *loc. cit.*), 'the expression is a survival from the time when Israel was a nomadic people and actually lived in tents; it remained in use long after the "tents" had given place to permanent "houses."' Since, however, Heb. *'ôhel* is the philological equivalent of Ar. *'ahl* 'community of settlers,' Bab. *âlu* 'city,' originally 'settlement,' it is perhaps truer to say that we have in this Heb. usage a survival of the wider and more primitive usage of the term.

10. *Jebus.* Apart from the present narrative, this name is only applied to Jerusalem in 1 Chr. 11^{4,6} (a narrative expanded from 2 Sam. 5^{6ff} in which the name Jebus does not appear). The manner in which it is explained here by the editorial addition 'that is Jerusalem' seems to suggest that it was the more ancient name; but that this cannot be so is proved by the occurrence of the latter name in the form Urusalim in the T.A. Letters of the fourteenth century B.C. (cf. Knudtzon, Nos. 287, 289, 290 = Winckler, Nos. 180, 182 + 185, 183).

his concubine, etc. The addition *καὶ ὁ παῖς αὐτοῦ*, found in some MSS. of *℣*, is probably due to a precisionist.

11. *was far spent.* Reading יָרַד (lit. 'had gone down') in place of the inexplicable כָּר of *℣*. יָרַד, however, does not occur elsewhere of the decline of day,* the nearest parallel being 2 Kgs. 20¹¹, where it is used of the decline of the shadow on the step-clock of Aḥaz.

12. *the city of foreigners who, etc.* Reading plur. נִכְרִים for sing. נִכְרִי, and masc. הַמָּה for fem. הָנָה with several MSS. of *℣*.

* Why Mo. (*SBOT.*) should cite 1 Kgs. 1²⁵ as a parallel is inexplicable.

of foreigner^s, 'who¹ are not of the children of Israel, but we will pass on as far as Gibe'ah.' 13. E And he said to his lad,


Gibe'ah. The name occurs elsewhere, as here, without the Def. Art. גִּבְעָה; and also, as in *vv.* 13, 14, 15, *al.*, with the Def. Art. הַגִּבְעָה 'the Hill' *par excellence* as being גִּבְעַת הָאֱלֹהִים 'the Hill of God,' *i.e.* the site of an ancient sacred place, 1 Sam. 10^{5,*} The city is sometimes defined as 'Gibe'ah of Benjamin' (1 Sam. 13¹⁵, 14¹⁶; 'G. of the children of B.,' 2 Sam. 23²⁰; cf. 'G. which belongeth unto B.' in *v.* 14 of our narrative), or 'Gibe'ah of Saul' (1 Sam. 11⁴, 15³¹, Isa. 10²⁹). Some confusion has arisen here and there in the O.T. between Gibe'ah and Geba' (a masc. form also meaning 'hill'); but that the two sites are distinct is proved by Isa. 10²⁸⁻³³, where both are mentioned. The site of Geba' has been certainly identified in the modern Ġeba' south of the wâdy Suwênî, five and a half miles north-north-east of Jerusalem. We must read Geba' for Gibe'ah in *ch.* 20⁴³, 1 Sam. 13², 14² (cf. 13¹⁶, 14⁵); and, conversely, Gibe'ah for Geba' in *ch.* 20¹⁰, 1 Sam. 13³ (cf. 10^{5,10}).

The present narrative makes it clear that Gibe'ah lay close to the road which runs north from Jerusalem to Nâblus, and was reached from Jerusalem rather sooner than Ramah (cf. *v.* 13); and, further (*ch.* 20³¹), that not far off from it the road divided, one branch going to Bethel—*i.e.* the main northern road, and the other to Gibe'on (on the reading, cf. *note ad loc.*)—*i.e.* the road by the two Bethhorons to Joppa. Further evidence is furnished by the statement of Jos. (*BJ.* v. ii. 1) that Titus, when advancing against Jerusalem from Gophna (Ġifnâ) on the road from Samaria, pitched his camp in the Valley of 'Thorns, near a village called Gibe'ah of Saul, about thirty stadia (*i.e.* rather over three miles) from Jerusalem, in order to await reinforcements coming from Emmaus (Nicomolis), *i.e.* 'Amwâs, which would naturally arrive by the Bethhoron road. Similarly, Jerome † describes how Paula journeyed from Nicopolis by the ascent to Upper and

* That גִּבְעַת הָאֱלֹהִים is identical with הַגִּבְעָה, which was Saul's native city, is evident from the narrative of 1 Sam. 10^{5,10-16}. When Saul is seized with the prophetic ecstasy, 'those who knew him before time' (*v.* 11), who, according to this narrative, give rise to the proverb, 'Is Saul among the prophets?' are clearly his fellow-townsmen; and when he ceases to prophesy (*v.* 13), we find him (*vv.* 14ff.) at home among his relatives without further travelling (read probably in *v.* 13b הָבִיתָה 'he came home'—as in 1 Kgs. 13⁷⁻¹⁵, *al.*—for הַבְּמָה 'to the high-place,' with which we should expect וַיַּעַל 'he went up'—not וַיָּבֵא: so Wellh., Driver, Kennedy, H. P. Smith, etc.). The identification of גִּבְעַת הָאֱלֹהִים proposed by Smith, *HG.* p. 250, with Râm-Allah (meaning in Ar. 'the Hill of God') a mile west of Bireh is therefore out of the question, since it is impossible that Gibe'ah of Saul can have lain so far to the north.

† 'The Pilgrimage of the holy Paula' (translated in *Palestine Pilgrims' Text Society*, i. (cf. § 6).

THE DISTRICT ROUND GIBE'AH



Road ===== .

Track - - - - -

Heights in English feet

↓ $1\frac{1}{8}$ miles by road
to Jerusalem

Scale one inch to a mile



(Based on Survey of Western Palestine, Sheets XVII and XVIII, by permission of the Palestine Exploration Fund)

Lower Bethhōron, beholding on her right Aijalon and Gibe'on, and resting awhile at Gibe'ah before continuing her journey to Jerusalem.

It is clear from these facts that Gibe'ah must have lain close to the junction of the two roads, and south rather than north of this junction; and adding the fact (derived from Jos.) that the distance of the city from Jerusalem was not less than three miles, the possibilities of site are confined within narrow limits.

The site proposed by Rob. (*BR.*³ i. pp. 577-579), following a suggestion made by Gross (*Theol. Stud. u. Kritiken*, 1843, p. 1082) is Tell (*or* Tulêl) el-Fûl, a high Tell crowned by the remains of a fortress some three hundred or four hundred yards to the east of the north road, about three miles due north of Jerusalem and two miles due south of Ramah (er-Râm). This has been accepted by many moderns. Objection is raised to the identification by Féderlin (*Revue Biblique*, 1906, p. 271) and Hagemeyer (*ZDPV.* xxxii., 1909, pp. 1 ff.) on the ground that there exist no traces of an ancient village, such *e.g.* as the rock-hewn cisterns which must necessarily have existed on such a site. Féderlin favours Hirbet eş-Şôma', on a small eminence about six hundred yards south of Tell el-Fûl, where there are considerable remains, among which are to be found about fifteen cisterns. This is probably too far south of the junction of the two roads, and too close to Jerusalem, unless we accept the variant statement of Jos. in his account of the Judges-episode (*Ant.* v. ii. 8) where he gives the distance as twenty stadia only (this, however, has not the same appearance of comparative accuracy as the statement in *BJ.*). Hagemeyer proposes the ruins called Hirbet el-Hawânî, five hundred yards north-west of Tell el-Fûl, and actually *on* the main road. Here there are the remains of massive walls, and ancient cisterns, and the upper part of the wâdy Bêt Hannîna to the west may represent the Valley of Thorns. This identification, however, seems to be excluded (1) by the fact that it is unconnected with a hill, and so could scarcely have borne the name הַנְּבֵעָה, and (2) by the fact that it is actually *on* the road, whereas the verb וִסְרוּ in v.¹⁵ of our narrative implies that the Levite's party had to 'turn aside' from the road for some little way before reaching the city.

All things considered, the ruined site Hirbet Râs eş-Tawîl, about half a mile north-east of Tell el-Fûl and three-quarters of a mile nearly due east of the junction of the two roads, and also a little south of the wâdy el-Hâfy (which may have been the Valley of Thorns*), merits

* It is worthy of notice that the wâdy el-Hâfy joins the wâdy es-Suwênî a few miles east of Hirbet Râs eş-Tawîl. Ar. es-Suwênî means 'the little acacias,' *i.e.* thorny trees of the Mimosa tribe (of course distinct from the American tree called acacia in England): cf. the name Šeneh 'thorn-bush' applied to the 'tooth of rock' on one side of the wâdy in 1 Sam. 14⁴. Ἀκανθα denotes the acacia in Herod. ii. 96, and is used by Θ. as the rendering of Heb. שִׁטָּה 'acacia.' The supposition is therefore plausible that in the time of Jos. the name 'Valley of Thorns' (Ἀκανθῶν ἀνλών) may have been applied to *both* branches of the wâdy—the wâdy el-Hâfy as well as the wâdy es-Suwênî.

‘Com^e’, and let us draw near to one of the places, and stay the night in Gibe’ah or in Ramah.’ 14. So they passed on and went their way; and the sun went down upon them close to Gibe’ah, which belongeth to Benjamin. 15. J And they turned aside there to go in to stay the night in Gibe’ah; and he went in, and sat down in the market-place of the city; and there was no man that took them into his house to pass the night. 16. And, behold, an old man came in from his work, from the field, at evening: and the man was from the hill-country of Ephraim, and was sojourning in Gibe’ah; but the men of the place were Benjaminites. 17. And he lifted up his eyes, and saw the way-faring man in the market-place of the city; and the old man said, ‘Whither goest thou? and whence comest thou?’ 18. And he said unto him, ‘We are passing from Bethlehem of Judah unto the furthestmost parts of the hill-country of Ephraim: from thence am I, and I went as far as Bethlehem of Judah; and I am going ‘unto my home’; and there is no man that

further investigation as a possible site. This site is mentioned as an alternative to Tell el-Fül by Sir C. Wilson (Smith *DB.*², s.v. ‘Gibe’ah’) and by Mo. It is marked by ancient remains: cf. *SWP. Mem.* iii. p. 124.

13. *Come.* *K^erê* לָכֶה for *K^t.* לָךְ.

Ramah. Cf. ch. 4⁵ note.

14. *which belongeth to Benjamin.* In distinction from other sites bearing the same name, e.g. the Gibe’ah of Judah (Josh. 15⁶⁷), and the Gibe’ah of Phinehas in the hill-country of Ephraim (Josh. 24³³).

15. *market-place.* Heb. *r^ehōbh*, lit. ‘broad place,’ was an open space in the city, usually near the gate, which served as a meeting-place for business or social purposes. Cf. especially Job 29⁷, 2 Chr. 32⁶, Neh. 8^{1.3.16}.

16. *and the man was, etc.* The fact that the old man was merely a sojourner in Gibe’ah is emphasized in order that his conduct may by contrast bring the inhospitality of the Gibe’athites into bolder relief. On the sacred duty of hospitality in the East, cf. Cheyne, *EB.* 2128.

18. *unto my home.* Reading אֶל בֵּיתִי with *Ε* εἰς τὸν οἶκόν μου (cf. v.²⁹), in place of אֶת־בֵּית יְהוָה, which has no doubt arisen through a copyist’s mistake of בֵּיתִי for an abbreviated בֵּית, to which the fact that the man was a Levite may have been a contributory cause. Cf. the errors of *Ε* in rendering τὸν θυμόν μου (חַמְתִּי) for

taketh me into his house. 19. Yet there is both straw and provender for our asses, and there is bread and wine also for me, and for thine handmaid, and for the lad with thy servants: there is no want of anything.' 20. And the old man said, 'Peace be to thee; howsoever let all thy wants lie upon me; only do not pass the night in the market-place.' 21. So he brought him into his house, and foraged for the asses; and they washed their feet, and did eat and drink. 22. They were making merry, when, behold, the men of the city, men that were sons of Belial, surrounded the house, beating on the door, and spake unto the master

חַמַּת יְהוָה in Jer. 6¹¹, *θυμοῦ μου* (אִפִּי) for אֵף יְהוָה in Jer. 25³⁷. Cf. *NHTS.*² p. lxix, n².

21. *foraged*. Heb. *bālal*, only used here, is a Denominative verb from subs. *bēlil* 'fodder' (properly *moistened* or *mixed* fodder), with the meaning 'to give fodder.' Thus the relation between the verb and subs. is exactly reproduced by the English use of 'forage' as subs. and (hence) as verb.

22. *men that were sons of Belial*. Heb. אֲנָשִׁי בְנֵי-בְלִיעַל 'men, sons of B.', with Suspended Construct State: cf. G-K. § 130 e.*

The meaning of Belial, or rather, *bēliyyā'al*, is highly obscure. The form, as vocalized, is evidently a compound, the first element of which is the negative *bēli*. It is in connexion with the second element that difficulty arises. If we put aside the Talmudic explanation (*Sanhedrin*, 111 b, 'sons who have broken the yoke of Heaven from off their necks') which implies a different vocalization from בִּלְיָ, *bēli* + 'ōl, 'without yoke'—adopted by Jerome in the present passage, 'filii Belial (id est, absque jugo)'—the explanations in debate at the present day are two. (1) The second element *yā'al* is taken as a subs. meaning 'worth,' which, though otherwise unknown in Heb. or any other Semitic language, is *assumed* from the existence of the verbal form in the Hiph'il modification, *hō'il*, with the meaning 'to be profitable.' *Bēliyyā'al* is thus supposed to mean 'worthlessness'; and this is the generally accepted modern explanation, adopted e.g. by BDB., and appearing in R.V. *marg.* (2) The explanation of *yā'al* as an apocopated Imperfect from *yā'alē* '(that which) comes up' is as old as Kimchi, who supposes that 'not coming up' has the sense 'not prospering,' i.e. 'ne'er-do-well.' So Hupfeld among moderns.

The objection that the context in which the term is regularly used requires something much stronger than a merely negative term, e.g.

* Perhaps, however, we ought to read אֲנָשִׁים for אֲנָשִׁי, as in *ch.* 20¹³ Deut. 13¹⁴, 1 Kgs. 21¹⁰.

of the house, the old man, saying, 'Bring forth the man who came unto thy house, that we may know him.' 23. And the man, the master of the house, went out unto them and said unto them, 'Nay, my brethren, do not wickedly, I pray you: seeing

malignity or *dangerous wickedness* may perhaps be met by the parallels offered by other languages in which terms originally negative have come to assume a very definite positive meaning—*e.g.* ἀσέβης, German 'Unheil,' Old Eng. 'naughty' (cf. *NHTK.* p. 245). A real objection is, however, advanced by Cheyne (cf. *EB.* 525 f., and articles in *ET.* there cited) when he points out that neither explanation suits the occurrence of the word in 2 Sam. 22^{5,6} = Ps. 18^{4,5} (ἦ^{5,6}) which must be deemed crucial for its interpretation. This passage runs—

'Billows of Death encompassed me ;
Torrents of *B'liyyā'al* o'erwhelmed me ;
Toils of She'ol surrounded me ;
Snares of Death * confronted me.'

Here *B'liyyā'al* is parallel to Death and She'ol, and Cheyne with great plausibility suggests that it denotes the Abyss as '(the place from which) one comes not up' ; cf. the Bab. *mât la târi* 'the Land of No-return,' a title of the Underworld. That there was, in Heb. thought, a definite connexion between the ideas of the Abyss and abysmal wickedness is proved by the use of the term *hawwā*, or more frequently the intensive plur. *hawwōth*, as that which characterizes the wicked man's 'inward part' (Ps. 5⁹, ἦ¹⁰), or, which he plots or meditates (Ps. 38¹², ἦ¹³, 52^{2,7}, ἦ^{4,9}, 55¹¹, ἦ¹², *al.*). *Hawwā* corresponds to Ar. *hāwiya*, 'a deep pit, hell,' Syr. *hawthā*, 'gulf, chasm' (cf. BDB. p. 217 *b*), and its only satisfactory rendering as used in the cases noted is Cheyne's 'engulfing ruin' (now generally adopted). On this analogy it is reasonable to assume that *b'liyyā'al*, as the Abyss from which there is no ascent, came to be applied to wickedness of an appalling and catastrophic character. Lagarde has acutely pointed out (*Prophetæ Chaldaice*, p. xlvii) that in Ps. 41⁸ (ἦ⁹) the derivation of *b'liyyā'al*, as understood by the poet, seems to be given. If we vocalize דָּבַר for דִּבֶּר, the passage runs—

'A plague of *b'liyyā'al* is poured out upon him ;
And now that he hath lain down he shall arise no more.'

Here stichos *b* indicates that *dibher b'liyyā'al* in stichos *a* is to be understood as 'a plague of not rising up' (*i.e.* 'from which one does not arise'), or, as we should say, 'a mortal sickness.'

* The repeated מוֹת is suspicious. Possibly we should emend צִלְמוֹת 'deep darkness' with Cheyne, *Book of Psalms*², *ad loc.*, who rendered the four terms 'Deathland . . . Ruinland . . . She'ol . . . Gloomland.'

that this man hath come into my house, do not this wantonness. 24. Behold my daughter, who is a virgin, and his concubine, let me, pray, bring them out, and humble ye them, and do to them that which is good in your sight; but to this man ye shall not do any such wantonness.' 25. But the men would not hearken to him: so the man laid hold on his concubine, and brought her out unto them outside; and they knew her, and abused her all the night until the morning, and let her go when the dawn arose. 26. Then came the woman at the approach of day, and fell down at the doorway of the man's house where her lord was, till daylight. 27. And her lord arose

In 2 Cor. 6¹⁵ Βελιαλ or Βελιαρ is used, as often in Apocalyptic literature (cf. references in *EB*. 525), as a name of Satan.

23. *wantonness*. Heb. *n'bhālā*. The term denotes the action of a person (called *nābhāl*) who is morally insensible of the claims of either God or man. In the present passage *n'bhālā* is used, as most often, of *immorality* viewed as a callous disregard of the rights of other people. Cf. Driver's notes in *Parallel Psalter*, Glossary, p. 457; *NHTS*.² p. 200.

A.V., R.V., in rendering *nābhāl* 'fool,' *n'bhālā* 'foolishness,' are not only inadequate but misleading. Driver renders 'senseless,' 'senselessness'; but an objection to this rendering is that the English terms would not naturally be understood (apart from explanation) to convey the meaning of *moral and religious insensibility*. There seems to be no English rendering of *nābhāl* which suits all occurrences. Perhaps the best general rendering is 'impious,' if we may use this adj. to denote one who lacks *pietas* in the full and wide sense in which the term is employed in Latin. When, however, the term *nābhāl* expressly contemplates a man's attitude towards his fellowmen, the rendering 'churl' may be more appropriate. Cf. Abigail's summary of the character of her husband in 1 Sam. 25²⁵— 'Churl (*Nābhāl*) is his name, and *churlishness* (*n'bhālā*) is with him.' The character of the *nābhāl* is summarized in Isa. 32^{5f}. (A.V., R.V. here 'vile person'; *n'bhālā* v.⁶ 'villainy').

24. *Behold my daughter, etc.* The view of Ber. that this verse is a later interpolation from Gen. 19⁸ is improbable in view of the fact that the whole narrative is closely modelled on Gen. 19^{2ff}. in the first place (cf. p. 444).*

* The abnormal suffix-form פִּלְגִּישׁוֹ is doubtless an error for פִּלְגִּישׁוֹ; cf. vv. 25, 26, 27, 29 (G.-K. § 91d). For the masc. plur. suffixes אֹתָם (twice), לָהֶם, we should of course expect the fem.; but such a use of masc. for fem. is frequent (cf. instances collected by König, *Syntax*, § 14).

in the morning, and opened the doors of the house, and went out to go on his way, and, behold, the woman his concubine was fallen down at the doorway of the house, with her hands on the threshold. 28. And he said unto her, 'Up, and let us be going'; but there was none that answered: then he took her up upon the ass; and the man arose, and went to his place. 29. And he entered into his house, and took his knife, and laid hold on his concubine, and divided her, limb by limb, into twelve pieces, and sent her throughout all the border of Israel. 30. [] And he commanded the men that he sent, saying, 'Thus

28. *but there was none that answered.* The addition of עַל־מִסְבָּתָּהּ MSS. עַל־מִסְבָּתָּהּ adds an unnecessary explanation, and is clearly a gloss.

30. *And he commanded . . . and speak.* Reading $\text{וַיִּצַּח אֶת־הָאֲנָשִׁים אֲשֶׁר יִשְׂרָאֵל הִנְהִיחָהּ בְּדַבָּר הַזֶּה לְמִיּוֹם עֲלֹת בְּנֵי יִשְׂרָאֵל לֵאמֹר כֹּה תֹאמְרוּ לְכָל־אִישׁ יִשְׂרָאֵל הַיּוֹם הַזֶּה שִׁמּוּ לָכֶם עָלֶיהָ עֵצָה וּדְבָרוּ$. This text follows עַל־מִסְבָּתָּהּ , which, after a text corresponding to $\text{וַיִּצַּח אֶת־הָאֲנָשִׁים אֲשֶׁר יִשְׂרָאֵל הִנְהִיחָהּ בְּדַבָּר הַזֶּה לְמִיּוֹם עֲלֹת בְּנֵי יִשְׂרָאֵל לֵאמֹר כֹּה תֹאמְרוּ לְכָל־אִישׁ יִשְׂרָאֵל הַיּוֹם הַזֶּה שִׁמּוּ לָכֶם עָלֶיהָ עֵצָה וּדְבָרוּ}$ in ז. 20^{11} , offers the doublet $\text{καὶ ἐνετείλατο τοῖς ἀνδράσιν οἷς ἐξαπέστειλεν λέγων Τάδε ἐρεῖτε πρὸς πάντα ἄνδρα Ἰσραὴλ Εἰ γέγονεν κατὰ τὸ ῥῆμα τοῦτο ἀπὸ τῆς ἡμέρας ἀναβάσεως υἱὸν Ἰσραὴλ ἐξ Αἰγύπτου ἕως τῆς ἡμέρας ταύτης; θέσθε δὴ ἑαυτοῖς βουλὴν περὶ αὐτῆς καὶ λαλήσατε.}$ That this rendering has a genuine Hebrew text behind it is proved by the mistranslation $\text{πρὸς πάντα ἄνδρα Ἰσραὴλ}$, which clearly represents the collective expression $\text{לְכָל אִישׁ יִשְׂרָאֵל}$ (cf. ch. 20^{11} , *al.*). It is to be expected that the Levite should have entrusted his envoys with a verbal message; and the exhortation 'Take ye counsel,' etc., comes more naturally from him than from those to whom the messengers are sent. In $\text{וְהָיָה כָל־יִשְׂרָאֵל לֵאמֹר כֹּה תֹאמְרוּ לְכָל־אִישׁ יִשְׂרָאֵל הַיּוֹם הַזֶּה שִׁמּוּ לָכֶם עָלֶיהָ עֵצָה וּדְבָרוּ}$ the tenses are difficult, and, if part of the original narrative, can only be taken as frequentatives—'And it kept happening that everyone that saw would say,' etc.; but such a use of the frequentative is hardly natural. Assuming the text which we adopt to represent the original, the corruption in $\text{וַיִּצַּח אֶת־הָאֲנָשִׁים אֲשֶׁר יִשְׂרָאֵל הִנְהִיחָהּ בְּדַבָּר הַזֶּה לְמִיּוֹם עֲלֹת בְּנֵי יִשְׂרָאֵל לֵאמֹר כֹּה תֹאמְרוּ לְכָל־אִישׁ יִשְׂרָאֵל הַיּוֹם הַזֶּה שִׁמּוּ לָכֶם עָלֶיהָ עֵצָה וּדְבָרוּ}$ may have arisen as follows. The words 'And he commanded . . . men of Israel' were omitted through homoeoteleuton, the preceding ז. 29 ending with 'Israel.' The speech 'Hath there been,' etc. being thus disconnected, and the spokesman undefined, attempt was made to solve the difficulty by insertion of 'And it was so, that everyone that saw it said,' the fact that this is a late gloss being indicated by the tenses $\text{וְהָיָה . . . וְהָיָה}$, which are to be regarded as Perfects with *weak* ו , not ו consecutive. The substitution of לֵאמֹר for הִנְהִיחָהּ interrogative at the beginning of the speech may have arisen through dittography of the final ל of יִשְׂרָאֵל .

shall ye say to all the men of Israel>, “‘Hath¹ there been ‘such a deed as this¹ since the day that the children of Israel came up from [] Egypt unto this day? Take ye ‘counsel¹ concerning it, and speak.”’

20. 1. X Then all the children of Israel ‘were called to arms’ R^p and the congregation was assembled X as one man, R^p from

Bu., Mo. (*SBOT.*), No., La., Kit. *BH.*, Cooke prefer to construct a text from C^A v. 30a, C^A , H v. 30b, H v. 30a; *i.e.* after receiving the Levite’s message, the spectators respond by echoing it in substance. Such repetition is, however, from the literary point of view, almost intolerable; and it is difficult to justify the conflate text. We certainly cannot explain the omission of the injunction to the messengers in H through homoeoteleuton (‘unto this day’ in the words of the messengers and in the response of the spectators) as is done by Mo. and Cooke, since such homoeoteleuton would naturally result in omission of the response of the spectators and not *vice versa*, the scribe’s eye passing from the first עַד הַיּוֹם הַזֶּה to the second and omitting all that came between. How could it pass from the second to the first and omit all that came before the first? On the other hand, the text of C^A (*i.e.* the second reading which we take to be original) *might* have omitted H v. 30a by homoeoteleuton; but in this case we should expect omission also of C^A , H v. 30b which, as forming part of the Levite’s message, must *ex hypothesi* have preceded H v. 30a.

take ye counsel, etc. The expression שִׁמּוּ עֲצָה, ‘Apply (*lit.* set) counsel,’ does not occur elsewhere: cf., however, *ch.* 20^{7b} הָבוּ לָכֶם וְדַבֵּר הֵלֶם, ‘Give here your advice and counsel,’ with the same Ethic Dative לָכֶם (it is possible that we should read וְדַבֵּרוּ for וְדַבֵּר as in 20^{7b}). שִׁמּוּ-לָכֶם עָלֶיהָ עֲצוֹ וְדַבֵּרוּ H , ‘set [your mind] upon it, take counsel, and speak,’ implies an ellipse of לִבְכֶּם after שִׁמּוּ, as in Isa. 41²⁰. Houb., Stu., etc., read לָכֶם for לִבְכֶּם. The verb עוֹן ‘take counsel’ (for the normal יַעֲזֵן) occurs once again in Isa. 8¹⁰.

20. 1. *were called to arms.* Reading וַיִּצְעֲקוּ with Bu. in place of H וַיֵּצְאוּ ‘came out,’ etc., to battle (Mo.). The emended verb is more natural in connexion with the words following ‘unto Yahweh at Mispah.’ The same emendation is probably to be made in the parallel passage 1 Sam. 11⁷ on the authority of C : cf. *NHTS.*² *ad loc.*

the congregation. Cf. p. 446.

Dan even to Be'er-sheba', and the land of Gile'ad, X unto Yahweh at Mišpah. 2. R^p And the chiefs of all the people, <out of> all the tribes of Israel, took their stand in the assembly of the people of God, even four hundred thousand footmen that drew sword. 3. X And the children of Benjamin heard that the children of Israel had gone up to Mišpah. R^p And the children of Israel said, 'Tell how this wickedness was brought to pass.' 4. And the Levite, the husband of the murdered woman, answered and said, 'To Gibe'ah which belongeth to Benjamin I came, even I and my concubine, to spend the night. 5. And the citizens of Gibe'ah rose up against me, and surrounded the house against me by night; me they thought to have slain, and my concubine they humbled so that

from Dan, etc. So (defining the northern and southern limits of the land of Israel) 1 Sam. 3²⁰, 2 Sam. 3¹⁰, 17¹¹, 24^{2,15}, 1 Kgs. 4²⁵ (¶ 5⁵).† With inverted order, 1 Chr. 21², 2 Chr. 30⁵.†

the land of Gile'ad. Gile'ad is used here in its widest sense of all the Israelite territory east of Jordan. Cf. *note* on ch. 10¹⁷.

unto Yahweh. According to this narrative, Mišpah seems to be regarded as the site of an important sanctuary. Cf. the remarks on pp. 447, 453.

Mišpah. The accepted site is the modern Neby Samwīl on a lofty eminence (2935 feet) five miles north-west of Jerusalem, appropriately named 'place of outlook' (cf. *note* on the eastern Mišpah, ch. 10¹⁷) as commanding the country round for a great distance. Neby Samwīl is about three and a half miles nearly due west of Hirbet Rās eṭ-Ṭawīl, and a little north of due west of Tell el-Fūl (cf. *note* on Gibe'ah, ch. 19¹²). Cf. Map, p. 465.

2. *the chiefs.* Heb. *pinnôth* (1 Sam. 14³⁸, Isa. 19¹³, Zech. 10⁴) is explained as a figurative usage of the word meaning 'corner' (*i.e.* 'corner-stone') of a building. Cf. the usage of the Ar. *rukn* 'corner-stone,' and then 'noble.'

out of all the tribes, etc. Reading מְכָל-שִׁבְטֵי with Grä., in place of כָּל-שִׁבְטֵי ' (even) all the tribes,' which, as it stands, is awkwardly explicative of הָעָם 'the people.' G^A, V render 'and all the tribes.' The ו which we insert may easily have fallen out through haplography after הָעָם.

four hundred thousand footmen. On the huge numbers, cf. pp. 446.

me they thought to have slain. On this statement as compared with 19^{22b}, cf. p. 454.

5. *they humbled.* G^{AL}, L, S^b add καὶ ἐνέπεισαν αὐτῇ, *i.e.* וַיַּעֲלֵנוּ אֹתָהּ as in ch. 19²⁵.

she died. 6. Then I took hold of my concubine, and divided her, and sent her throughout all the country of the inheritance of Israel, because they had committed lewdness and wantonness in Israel. 7. Here ye all are, ye children of Israel; give here your advice and counsel.' 8. And all the people arose as one man, saying, 'We will not any of us go to his home, neither will we any of us turn unto his house: 9. but now this is the thing which we will do to Gibe'ah; <we will go up> against it by lot, 10. and will take ten men of an hundred of all the tribes of Israel, and an hundred of a thousand, and a thousand of ten thousand, to fetch victual for the people, that they may do [] to Gibe'ah¹ of Benjamin according to all the wantonness that

6. *lewdness.* Heb. *zimmū*, as applied to sins of unchastity, is characteristic of H—Lev. 18¹⁷, 19²⁹, 20^{14 bis}, and of Ezek. where it is used metaphorically of idolatry under the figure of whoredom and adultery—Ezek. 16^{27.43.68}, 22⁹, 23^{21.27.29.36 44.48 bis.49}, 24¹³; so also in Jer. 13²⁷. Elsewhere of adultery, Job 31¹¹. Scholars who hold that *vv.*^{3b-8} belong to the oldest narrative are forced by these facts to suppose that *zimmū* is a later insertion, the original narrative running simply 'because they had committed wantonness in Israel.'

8. *to his home.* Lit. 'to his tent.' On the usage of the phrase, cf. *ch.* 19⁹ *note*. Perhaps we ought here to read the plur. לְאָהֶלָיו, as is usual, rather than the sing. לְאָהֶלָּו.

9. *we will go up, etc.* Inserting נֶעְלֶה with Ἐξ ἀναβησόμεθα ἐπ' αὐτήν ἐν ἀλήρῳ. So Ros., Stu., Mo., etc. This verb may easily have fallen out before עליה. ה reads simply 'against it by lot,' which clearly cannot be original. נחמני עלה בערבה 'we will apportion ourselves against it by lot,' נִמְנֵן חֲלֹסֹתָו 'we will cast lots against it,' represent different attempts to fill the lacuna. Bu.'s נִפְּלָה גִּזְרָל is less probable than the emendations adopted. The reference of the casting of lots appear to be to *v.*¹⁸, where Judah is selected to begin the attack, a statement which, as we have seen (p. 448), seems to stand out of relation to the main narrative in which all the tribes take part simultaneously in the battle.

10. *that they may do to Gibe'ah, etc.* Omitting לְבוֹאֵם, which is intruded in ה between לעשות and לגבע. R.V. renders ה, 'that they may do, when they come to Gibe'ah of Benjamin, according to all

‘they’ have done in Israel.’ 11. J Then all the men of Israel were gathered together against the city as one man, in confederacy. 12. R^p And the tribes of Israel sent men through all the tribe¹ of Benjamin, saying, ‘What is this wickedness that is brought to pass among you? Now therefore deliver up the men, the sons of Belial, that are in Gibe’ah, that we may put them to death, and extirpate ‘the’ wickedness from Israel.’ But <the children of> Benjamin were not willing to hearken to the voice of their brethren the children of Israel. 14. X And the

etc.’; but, apart from the extreme awkwardness of the position of לְבֹאִם, the use of the prep. ל in a temporal sense (in place of כ or ב) is unparalleled. לְבֹאִם is possibly a corruption of לְנִבְעָת which has come in from the margin, where it was noted as a correction of לְנִבְעָת. ℣^a, reading לְבָאִים for לְבֹאִם, and placing it before לַעֲשׂוֹת, renders τοῖς εἰσπορευομένοις ἐπιτελέσαι τῇ Γαββᾶ, κτλ. This yields a tolerable sense; but may be suspected of being a correction of the text of ℣^L, S^h, where we have the order of ℣—ἐπιτελέσαι τοῖς εἰσπορευομένοις Γαββᾶ, κτλ.

to Gibe’ah. Reading לְנִבְעָת in place of ℣ לְנִבְעָת, which is an obvious error: cf. note on ch. 19¹².

they have done. Reading plur. עָשׂוּ with ℣^a, S^h, S^p, in place of ℣ sing. masc. עָשָׂה. Had the city been individualized, we should have expected the fem. sing.: cf. G-K. § 122 *h*.

12. tribe of Benjamin. Reading שִׁבְטֹת with the Versions for plur. שִׁבְטֵי of ℣, which probably arose through unintentional imitation of שִׁבְטֵי יִשְׂרָאֵל at the beginning of the verse. The same error is found in 1 Sam. 9²¹. The Jewish commentators explain the plur. by the assumption that ‘tribes’ is here equivalent to ‘clans’ (מִשְׁפָּחוֹת), Kimchi referring to the term Benjaminite clans enumerated in Gen. 46²¹; but such a usage is very improbable.

sons of Belial. Cf. 19²² note.

the wickedness. The Def. Art. is necessary before רָעָה. Its omission in ℣ is due to erroneous division of the words—וּנְבַעְרָה רָעָה for וּנְבַעְרָה הָרָעָה—or to haplography.

the children of Benjamin. So Ḳ^rē, many MSS. of ℣, ℣, S^p, ℣. Kt. ‘Benjamin’ simply.

children of Benjamin were gathered together out of the cities unto Gibe'ah, to go out to battle with the children of Israel.
 15. ^{R^p} And the children of Benjamin were mustered in that day from the cities twenty and 'five' thousand men that drew sword, not including the inhabitants of Gibe'ah, [] even seven hundred

14. *out of the cities.* \mathfrak{C} , \mathfrak{S}^p presuppose מֵעָרֵיהֶם 'out of their cities.'

15. *twenty and five thousand.* So \mathfrak{C}^{AL} , \mathfrak{S}^h , \mathfrak{Y} , in place of \mathfrak{U} , 'twenty and six thousand.' The correction is necessary in view of the statement that after 25,100 had fallen (*v.*³⁵) the survivors numbered 600 (*v.*⁴⁷). The narrator is very precise in the matter of numbers, and we are hardly justified in following Kimchi, who suggests that the 1000 who are unaccounted for in comparison of the 26,700 of \mathfrak{U} with the numbers given in *vv.*^{35,47} combined may have fallen in the battles of the first two days. According to the parallel account (J) 18,000 Benjaminites fell in battle (*v.*⁴⁴), and the redactor is content (*vv.*^{45f.}) to raise this number to a round total of 25,000, ignoring the odd 100.

15b.16. *not including, etc.* The text adopted follows \mathfrak{Y} , 'praeter habitatores Gabaa, qui septingenti erant viri fortissimi, ita sinistrâ ut dextrâ proeliantes, etc.' This differs from \mathfrak{U} in omitting התפקרו in *v.*^{16b}, and מכל העם הזה שבע מאות איש בחור in *v.*^{16a}. So \mathfrak{C} , \mathfrak{S}^p , except that in *v.*^{15b} they retain התפקרו, which they treat as a relative sentence (\mathfrak{C}^B οὗ ἐπεσκέπησαν, \mathfrak{C}^{AL} οὗτοι ἐπεσκέπησαν, \mathfrak{S}^p **וְנִלְמַנָּה**), a course which is followed by A.V., R.V.; but illegitimately, since such a rendering demands the insertion of אִשָּׁר before the verb, or (as Bu. suggests), of הָמָה. As \mathfrak{U} stands, the meaning of לבר מישיבי הנבעה התפקרו can only be 'not including the inhabitants of Gibe'ah were they (the Benjaminites) numbered.' It is obvious, however, that the inclusion of התפקרו in the text destroys the balanced contrast between the openings of *vv.*^{15,17}, . . . ויתפקרו בני בנימין . . . , and ויאיש ישראל התפקרו, lit. 'and were numbered the children of Benjamin . . . and the men of Israel were numbered'—a variation of order which is very idiomatic in Heb. (called by Driver, *Tenses*, § 160, *Obs.*, 'the Hebrew equivalent of μέν . . . ἔ of the Greeks'). As for *v.*^{16a}, omitted by \mathfrak{Y} , \mathfrak{C} , \mathfrak{S}^p —it is true that such omission *might* be due to homoeoteleuton (אִישׁ בחור); yet it seems in the highest degree unlikely that both the inhabitants of Gibe'ah and the left-handed warriors should have been described originally by identically the same phrase, '700 chosen men.' An alternative emendation of the text, favoured by some scholars, is to end *v.*¹⁶

chosen men 16. [] that were left-handed : all of these were used to sling a stone at a hair and not let it miss. 17. And the men of Israel were mustered, not including Benjamin, four hundred thousand men that drew sword ; all of these were men of war. 18. And they arose, and went up to Bethel, and enquired of God, and the children of Israel said, 'Who shall go up for us first to battle with the children of Benjamin?' and Yahweh said, 'Judah first.' 19. ^X And the children of Israel arose in the morning, and encamped against Gibe'ah. 20. ^J And the men of Israel went out to battle with Benjamin ; and the men of Israel set the battle in array against them at Gibe'ah. 21. ^X And the children of Benjamin came out from Gibe'ah, and felled of Israel to the ground in that day two and

with **התפקרו**, making its subj. to be the children of Benjamin, and to retain *v.*¹⁶ as it stands in **℣**, thus taking the genuine mention of the 700 chosen men to be to the experts with the sling. The objection to such a text (which has no support from the Versions) is that it leaves us in ignorance of the number of the Gibe'athites—an omission which, in a tale which is so exact in its numbers, is very unlikely.

Adopting our text, it is the Gibe'athites who form the corps of left-handed slingers ; and it is worthy of notice that the warriors who, according to 1 Chr. 12^{III}, joined David at Şiklag, and who 'were armed with bows, and could use both the right hand and the left* in slinging stones and in shooting arrows from the bow,' were 'of Saul's brethren of Benjamin,' and their leaders are stated to have been Gibe'athites.

15. *chosen men.* Heb. **יִשׁ בָּהִיזִר**, *i.e.* young warriors in the prime of manhood.

18. *went up to Bethel.* On the site of Bethel, cf. *ch.* 1²² note. It lies eight miles to the north-east of Mişpah (Neby Samwil). On the introduction of the sanctuary at Bethel, here and in *v.*²⁶, 21², as alien to the conception of the narrative which pictures the tribes as assembling 'unto Yahweh' at *Miṣpah*, cf. pp. 447, 453. **F** takes Bethel to refer to 'the house of God' at *Shiloh*, on the assumption that the Ark was at Shiloh from the days of Joshua' (Josh. 18¹⁰) to those of 'Eli (cf. Mo. on *v.*^{27.28}).

enquired of God. Cf. note on *ch.* 1¹. On the incident recorded in this verse as modelled directly upon *ch.* 1¹⁻², cf. pp. 448, 454.

21. *felled . . . to the ground.* Heb. **וַיִּשְׁחָתוּ . . . אֶרְצָהּ**. The rendering of A.V., R.V., 'destroyed down to the ground,' accords

* Cf. the explanation of the phrase **יָד מִיְּמִינוֹ** given by **Ⓢ**, **ⓕ**—not simply 'left-handed,' but 'ambidextrous.'

twenty thousand men. 22. J And ^{R^p} the people, J the men of Israel, took courage, and again set the battle in array in the place where they had set it in array on the first day. 23. ^X And the children of Israel went up, and wept before Yahweh until the evening; and they enquired of Yahweh, saying, 'Shall I again approach to battle with the children of Benjamin my brother?' And Yahweh said, 'Go up against him.' 24. So the children of Israel drew near against the children of Benjamin on the second day. 25. J And Benjamin went out to meet them from Gibe'ah on the second day, ^X and again felled to the ground of the children of Israel eighteen thousand men: ^{R^p} all these drew sword. 26. ^X Then all the children of Israel, ^{R^p} and all the people, ^X went up, ^{R^p} and came to Bethel ^X and wept, and sat down there before Yahweh, ^{R^p} and fasted that day ^X until the evening, ^{R^p} and offered burnt offerings and peace-offerings before Yahweh. 27. ^X And the children of Israel enquired of Yahweh, ^{R^p} (for the Ark of the covenant of

with the conventional rendering of *hišhith*, but offers an unnatural expression in English. Ball points out (verbally) that in the present use of *hišhith* we have a preservation of the original meaning of the verb as seen in the Bab. *šahātu* of the T.A. Letters, which means 'to fall,' and would therefore in the causative stem (Hiph'il) naturally signify 'to fell.' So *נָפַל*.^{25.35} (in the last case with om. of *אֶרֶץ*, 'to the ground'). Cf. for the sense 'cause to fall' in Pī'ēl, Gen. 38⁹.

23. *And the children of Israel went up.* We expect the place to which they went up to be mentioned. Probably this was originally specified as Mišpah by the X narrator, and this name was cut out by ^{R^p} so as not to conflict with his own conception of Bethel as the central sanctuary. Cf. v.²⁶, where the words 'and came to Bethel' have been inserted by ^{R^p}.

26. *burnt offerings and peace-offerings.* The burnt offering (wholly consumed by fire on the altar) is here a *piaculum*, and is followed by the peace-offering as a communion-feast shared by Yahweh and His worshippers with the purpose of ratifying and strengthening the covenant-bond. On the origin and conception of these two forms of sacrifice, cf. the present writer's *Outlines of O.T. Theology*, pp. 55 ff. The precise meaning of *šélem*, conventionally rendered 'peace-offering,' is somewhat obscure. For different views, cf. BDB. p. 1023.

27. *the Ark of the covenant of God.* This form of allusion to the Ark ('of the covenant, etc.') is due in the first place to Deuteronomic influence. In ancient narratives it is called 'the Ark' simply, or 'the Ark of Yahweh' (or 'of God'). Cf. the conspectus of allusions in *NHTK*. pp. 31 f.

God was there in those days, 28. and Phinehas, the son of Ele'azar, the son of Aaron, stood before it in those days,) X saying, 'Shall I again go out to battle with the children of Benjamin my brother, or shall I forbear?' And Yahweh said, 'Go up; for to-morrow I will deliver him into thine hand.' 29. J And Israel set an ambuscade against Gibe'ah round about. 30. X And the children of Israel went up against the children of Benjamin on the third day, and set themselves in array against Gibe'ah, as aforetime. 31. And the children of Benjamin went

28. *Phinehas*. There seems to be no doubt that the name is the Eg. *Pe-nḥēsi*, 'the negro,' i.e. 'child of dark complexion'; cf. Lauth, *ZDMG.* xxv. (1871), p. 139; W. M. Müller in *EB.* 3728, and, for the general usage of the term *nḥēsi*, *AE.* p. 112. The Eg. origin of the name is an important point in favour of the historical existence of its bearer*; and this is strengthened by the fact that the name reappears as the name of a descendant†—the second son of 'Eli (1 Sam. 1³, *al.*).

stood before it. The phrase, which is here employed of the *service* of the Ark as the typical embodiment of Yahweh's manifestation, is used elsewhere of the Levites' ministrations 'before Yahweh' (Deut. 10⁸, 18⁷, Ezek. 44¹⁵), and in the mouths of the prophets to illustrate their conception of their relation to Yahweh (1 Kgs. 17¹, 18¹⁵, 2 Kgs. 3¹⁴, 5¹⁶). *Standing in the presence* of a master is the natural attitude of a servant who is ready to execute his behests (cf. 1 Kgs. 1², 12⁶, Jer. 52¹², *al.*).

31. *to meet them.* Reading לִקְרֹאתָם conjecturally in place of וַיִּקְרָא הָעָם לִקְרֹאת הָעָם 'to meet the people,' on the ground (argued above, pp. 449, 453) that the use of הָעָם is elsewhere in the narrative characteristic of the redactor R", and that the change which we here presuppose is a very easy one.

* In the same way, the identity (generally accepted) of the name Moses (Heb. *Mōšē*) with the Egyptian *Mōsi*, which appears as an element in theophorous proper names, e.g. Aḥmosi, Thutmosi, and also as a name by itself, is historically important. Had Moses been merely a legendary national hero, Israelite historians would hardly have invested him with an Egyptian name.

† That the family of 'Eli represented the ancient legitimate priestly line—therefore the line of descent from Ele'azar—seems to follow from 1 Sam. 2^{27ff.} The theory of the Chronicler (1 Chr. 24³) that Šadoq was a descendant of Aaron's firstborn son Ele'azar, and Abiathar ('Eli's great-great-grandson) a descendant of his youngest (fourth) son Ithamar, is clearly a device intended to legitimize the claim of Šadoq's family to the highpriesthood. We note, however, that, according to the earlier theory of 1 Sam. 2³⁵, Šadoq (who is clearly hinted at: cf. 1 Kgs. 2²⁷) is to be raised up on account of his superior moral claims as representing the mind of Yahweh, and nothing is said about his prior claim by birth, the contrary being in fact implied by *vv.* 27, 28. Of Šadoq's antecedents prior to his appointment by David we really know nothing. Cf. Wellh., *Prolegomena*, pp. 126, 138 f.

out to meet 'them', and were drawn away from the city; and they began to smite and kill ^{R^p} of the people, ^X as aforetime, ^{R^p} in the highways, of which the one goeth up to Bethel and the other to Gibe'on, ^X in the field, about thirty men of Israel. 32. And the children of Benjamin said, 'They are smitten down before us, as at the first': but the children of Israel said, 'Let us flee, and draw them away from the city into the highways.' 33. J And all the men of Israel rose up¹ from their

and were drawn away. Reading וַיִּנְתְּקוּ with Ehr. in place of הִנְתְּקוּ, which is anomalous in form (we should expect הִתְקוּ) and also awkward as an asyndeton. As Ehr. remarks, the ה may easily have arisen through a misreading of ו.

in the highways . . . Gibe'on. Reading גִּבְעֹנָה in place of גִּבְעָתָה 'to Gibe'ah,' with Bu., No., La., Kit., Cooke.

Heb. *m^esillā* denotes, not a mere beaten track, but a properly 'made' highroad. Whatever view be taken as to the precise site of Gibe'ah (cf. 19¹² note), there is no doubt that it was on (*i.e.* just off) the main northern road which led to Bethel: therefore, on the reading of גִּבְעֹנָה, the distinction here so clearly drawn between the *two* highroads is hardly explicable. Half a mile north-west of Tell el-Fûl and nearly due west of Hirbet Râs eṭ-Ṭawîl the northern road forks, one branch running north-west, and reaching Gibe'on (el-Ġib) after three miles. Both roads 'go up' on the whole. The elevation at the fork is 2462 feet. The Bethel-road reaches Bîreh (2824 feet) in some five miles, and then makes a further continuous rise to Bethel (2890 feet), which it reaches two miles further on. The Gibe'on-road falls at first in crossing the wâdy ed-Dumm (2298 feet) at three-quarters of a mile, and then makes a steady rise to Gibe'on (2535 feet) some two miles further. A line drawn from Mišpah (Neby Samwîl) to Hirbet Râs eṭ-Ṭawîl actually crosses the fork of the road: consequently a hostile army approaching Gibe'ah (assumed to have been at the latter site), and feigning a disordered retreat in order to draw the Gibe'athites away from their city, would naturally be spread out over the two roads. Cf. Map, p. 465.

in the field. According to our analysis of the sources, this is not a description of the site of Gibe'on or Gibe'ah, but the direct continuation of 'began to smite and kill as aforetime.' in the narrative of X. The object of the Israelites' feint of retreat was to draw the Benjaminites away from the city-precincts into the *open country* (cf. Josh. 8^{24a}), and thus to facilitate the capture of the city by the ambush.

33. *And all the men of Israel rose up, etc.* Here we have in J the direct continuation of v.²⁹. Having laid the ambush, the main army makes a move to begin the attack. The *order* of the sentence,

place, and set themselves in array at Ba'al-tamar: ^X and the ambushade of Israel burst forth from its place 'on the west of'

וּבְלִי יִשְׂרָאֵל קָמוּ, with the subj. brought into prominence by being placed first, offers an intentional antithesis to *v.*²⁹ (the ambush was laid thus, *but* the main army, etc.).*

The construction of קָמוּ מִמְּקוֹמָם, is hardly tolerable. We must read sing. קָם in agreement with the collective אִישׁ יִשְׂרָאֵל, the narrative then continuing with the plur. verb וַיַּעֲרֹכוּ as in *vv.*^{20.22}; or, accepting the plur. verb with the collective sing. subj., as in *vv.*^{36b.37.48}, adopt the plur. suffix מִמְּקוֹמָם.

Ba'al-tamar. Unidentified. Eusebius (*OS.* 238⁷⁶) states that in his day there still existed a Beth-tamar near Gibe'ah.

burst forth. Heb. מָגַיַח. The verb *gāḥ* is only used elsewhere in the O.T. of water bursting forth, Job. 38⁸, 40²³, Ezek. 32² (doubtful) —cf. *Gihôn*, 'the Gusher,' the name of the spring outside Jerusalem; or, of a child bursting forth from the womb, Mic. 4¹⁰, Ps. 22¹⁰ (doubtful), cf. Job. 38⁸ already cited. The verb is frequent in Aram. in the Aph'el, followed by the accus. קָרַב 'battle,' in the sense 'movere bellum.' The emendation מִשְׁעָנִיחַ 'looked forth' (cf. *ספ' מַלְכָּא בְּדִסְסָא*), proposed by Grä., is much inferior to מָגַיַח.

on the west of Geba'. Reading לְ מִמְּעָרָב with *Gr.^{AL}*, *S^b*, *H*, and most moderns, in place of מִמְּעָרָה. *Ma'aré* (treated by R.V. *text* as a proper name: cf. *Gr.^B ἀπὸ Μαρααβῆ*) is rendered 'meadow' by R.V. *marg.* (A.V. 'meadows'), on the assumption that it means a *bare, naked place* ‡ (i.e. devoid of trees?): cf. the rendering of מִישָׁר מִישָׁר 'plain.' § Such a bare open space would obviously be the last place which an ambush would choose for concealment. *S^p* מִן הַמְּעָרָה 'from the cave' (מִמְּעָרָה) which is in Geba',

* The hopeless difficulty in which this half-verse has involved commentators, upon the ordinary assumption that it is a continuation of the narrative immediately preceding, is well set forth by Mo. Mo. himself hesitates upon the verge of the conclusion which we have adopted:—'It might be suspected that the half-verse came from the older narrative, in which it would have a passable sense and connexion after *v.*²⁹, but the construction is so negligent, not to say ungrammatical, that the conjecture is hardly to be entertained.' Cf., however, the remarks on the construction made above. With the slight emendation there advocated it is perfectly idiomatic.

‡ עֲרוֹת 'bare places' (?) in Isa. 19⁷, rendered by R.V. 'the meadows by the Nile,' is itself too dubious to be quoted in support.

§ According to *SWP. Great Map*, xvii., there actually exists a Sahel Ġeba', i.e. 'plain of Ġeba', south-east of the village of Ġeba', but this appears too remote from the scene of action. Cf. *Map*, p. 465.

Geba', 34. and they came in front of Gibe'ah, even ten thousand

and this is improved upon by Ar., the half-verse being rendered, 'and the ambuscades were in the caves of Geba', looking forth (מִיִּטְנִיחַ) from their positions,' the plur. 'caves' being substituted for the sing. probably on the ground that *one* cave would not suffice for such a force (Ros.). *

Geba' is nearly two and a half miles north-north-east of Hirbet Râs eṭ-Ṭawîl, and three miles from Tell el-Fûl; so that, if 'to the west of Geba'' is literally interpreted, the ambuscade must have been placed at a considerable distance from the city. Not improbably, however, we may think of it as concealed in the valley which runs from the western side of Geba' down to Hizmeh (so La.), from which it could rapidly proceed up the wâdy el-Hâfy to Râs eṭ-Ṭawîl. Cf. Map, p. 465.

Mo. effects a complete agreement with the Versions upon which we base our emendation by reading 'west of *Gibe'ah*' (ἔ^{AL} ἀπὸ δυσμῶν τῆς Γαββα, ἢ 'ab occidentali urbis parte'); but this surely cannot be correct, since west of Gibe'ah was the very direction in which the Benjaminites were advancing to the attack of the Israelite host. The whole account of the stratagem seems to indicate that the ambush attacked Gibe'ah from the east or north-east, while the Benjaminites were being drawn off to the west.

34. *in front of Gibe'ah*. Heb. מִנְּגֶד לְגִבְעָה. The sense of מִנְּגֶד is somewhat obscure. It may be supposed that it denotes something more definite than 'in view of,' and is intended to describe the quarter from which the city was approached; and, if this is so, we may conjecture that it has the sense often possessed by the analogous expression לְפָנַי 'before,' viz. 'eastward of': cf. BDB. *s.v.* פָּנִים, 7a (*d*). This is the quarter from which the city could be approached unobserved, and from which it would naturally be approached from the south-west of Geba'. Such a meaning suits the use of מִנְּגֶד in the similar description of the capture of 'Ai in Josh. 8. Here the ambuscade is west of 'Ai (*v.*⁹), and the main army of Israel, advancing from the Jordan valley, would naturally come 'in front of the city' (*i.e.* eastward of it) before encamping on the north of it (*v.*¹¹). La. takes a different view, holding that 'in front of' means that the ambuscade placed itself between the Benjaminites and Gibe'ah so as to cut off retreat—therefore, *to the west of* it. A different reading offered by twenty-seven MSS. of \mathfrak{H} and presupposed by \mathfrak{T} (מִדְּרוֹם) is מִן־נֶגֶב 'to the south of.' This might describe the position of a force coming up the wâdy Zimry to attack Râs eṭ-Ṭawîl; yet the reading is hardly to be preferred to that of \mathfrak{H} .

* Three caves are marked at Geba' in the *SHP. Great Map*, xvii.

chosen men out of all Israel, and the battle was sore ; J but *they* knew not that evil was closing upon them. 35. ^X And Yahweh smote Benjamin before Israel : and the children of Israel felled of Benjamin on that day twenty-five thousand one hundred men : ^{R^p} all these drew sword. 36. ^X And the children of Benjamin saw that they were smitten : J and the men of Israel gave place to Benjamin, for they trusted in the ambushade which they had set against Gibe'ah. 37. And the ambushade hastened, and made an onset against Gibe'ah : and the ambushade opened out, and smote all the city at the edge of the sword. 38. Now the appointment between the men of Israel and the ambushade was [] that when they should make a beacon of smoke to rise up

even ten thousand, etc. The reference is to the ambushade.

but they knew not, etc. The subj. is clearly the Benjaminites who are the victims of the ruse ; and the fact that they are not mentioned in the earlier half of the verse is an indication that we are dealing in this latter half with the other source (J). The antecedent statement in J must have described how the Benjaminites sallied forth to meet Israel at Ba'al-tamar (*v.* 33a) ; cf. Josh. 8¹⁴, where the latter half of the verse bears a marked resemblance to the present passage.

35. *felled.* Cf. note on *v.* 21.

twenty-five thousand one hundred men. I.e. all but the 600 survivors mentioned in *v.* 47. Cf. note on *v.* 15.

37. *opened out.* I.e. deployed. Heb. וַיִּקְרַע. Cf. *ch.* 4⁶ note.

38. *appointment.* Heb. *mō'ēdh*, lit. (here) 'appointed time' (as very frequently ; cf. BDB. *s.v.* *ia*). The signal of the smoke-beacon indicated the *mō'ēdh* for Israel's *volte-face*, but was not itself the *mō'ēdh* (we have no parallel for *mō'ēdh* = 'appointed signal').

was, that when, etc. Omitting the *vox nihili* הָרֵב before לְהַעֲלוֹתָם with some MSS. of *℣*, *ℑ*^p, *ℑ*, and all recent commentators, as corrupt dittography of the immediately preceding הָאֵרֵב 'the ambushade.' *וַיִּסְנֹן לְאֶסְקָא*, lit. 'that they should *make great* to send up,' is followed by R.V., 'that they should make a *great* cloud of smoke, etc.' (A.V. is similar.) This rendering apparently regards הָרֵב as apocopated Imperat. Hiph'il of רָבָה—a view which would be just possible if the injunction were couched in the *oratio recta* (הָרֵב לְהַעֲלוֹת 'make great to send up,' i.e. 'send up as much as you can !'), but is of course out of the question when it is expressed obliquely with the suffix form לְהַעֲלוֹתָם. Some MSS. of *ℑ* read הָרֵב 'sword,' which appears in *℣*^{AL} *μάχαιρα* thrown into the sentence without any intelligible

out of the city, 39. the men of Israel 'should' face about in the battle. And Benjamin began to smite and kill among the men of Israel about thirty men; 'and' they said, 'Surely they are utterly smitten before us, as in the first battle.' 40. Then the beacon began to ascend from the city in a column of smoke; and when Benjamin looked back, behold, the holocaust of the city rose up toward heaven. 41. And the men of Israel faced about; and the men of Benjamin were dismayed, for they saw that evil had closed upon them. 42. So they turned^r before

connexion. Et^v τῆς μάχης (connecting with preceding μετὰ τοῦ ἐνέδρου) appears to represent an attempt to make sense of this.

a beacon. Heb. *mas'ēth*, lit. 'an uplifting.'

39. *the men of Israel should face about.* Reading וַיִּהְיוּ after the happy suggestion of Mo. (adopted by Driver, *ET*. xviii. p. 332, and Cooke). The Perf. with ו consecutive (idiomatically continuing the Infinitive construction: cf. Driver, *Tenses*, § 118) states the other side of the pact. וַיִּהְיוּ 'and the men of Israel faced about,' anticipates *v.* 41a, and makes the Israelites *anticipate the appointed signal* which is not given till *v.* 40. The attempt of some scholars (*e.g.* Kit., La.) to explain the verb as meaning here 'faced about in flight' (which they had already done in *v.* 36b), and in *v.* 41a 'faced about to make a stand,' is obviously futile.

and they said. Reading וַיֹּאמְרוּ in place of כִּי אָמְרוּ 'for they said.' Obviously the conclusion drawn by the Benjaminites was the *result* of their preliminary success in smiting Israel. The text of וַיִּשְׁמַע can only be explained as meaning that they began to be successful because they supposed that the same result was bound to ensue as on the preceding days. This, however, is clearly not the intention of the narrative. The confusion of ו and כ is not uncommon: cf. *ch.* 16²⁴, 1 Sam. 2²¹ פָּקַד כִּי וַיִּפְקַד (Et καὶ ἐπεσκέψατο), Jer. 37¹⁶ כִּי בָא וַיָּבֵא (Et καὶ ἦλθεν); conversely 1 Kgs. 22³⁷ וַיָּמָת for כִּי מָת (Et ὅτι τέθνηκεν), Isa. 39¹ וַיִּשְׁמַע for כִּי שָׁמַע (Et ἤκουσεν γάρ, and so וַיִּשְׁמַע in 2 Kgs. 20¹²).

40. *The holocaust of the city.* Heb. כָּלִיל הָעִיר. The rendering adopted is that of Mo., who points to Deut. 13¹⁷ for a similar use of *kālil* in allusion to the destruction of a city by fire: 'And thou shalt burn with fire the city and all its spoil as a holocaust to Yahweh thy God.' R.V., rendering 'the whole of the city,' has to supply the words 'in smoke' after 'went up.' The similar passage in Josh. 8²⁰ has 'the smoke of the city went up toward heaven.'

42. *they turned.* Reading וַיִּפְּנוּ in agreement with the singulars

the men of Israel unto the way to the wilderness ; but the battle overtook them, and they that were from 'the city' were destroying them in the midst¹, 43. 'and they beat down' Benjamin,

לְיִבְהֵל proceeding, and the sing. suffix of הַרְבִּיקָתָהּ following, in place of וַיִּפְּנוּ plur. So Bu., No., Kit. *BH*.

from the city. Reading מִהָעִיר with *Y* ('sed et hi qui urbem succenderant'), some MSS. of *Gr*, Mo. The reference is, of course, to Gibe'ah. The ambuscade, having burned the city, now joined in the attack of the Benjaminites in the field. Cf. Josh. 8²². מִהָעָרִים, 'from the cities,' must have arisen through dittography of the initial מ of מִשְׁחִיתִים immediately following.

in the midst. Reading בְּתוֹךְ with Mo., No., La. (cf. *Y* 'ex utraque parte,' *S*^P בְּתוֹךְ וּמִכָּא, *ט* מִכָּא וּמִכָּא), as in Josh. 8²², 'And these others [the ambuscade who had just burned the city] came out of the city against them ; so they were in the midst of Israel [lit. they were, as regards Israel, in the midst, בְּתוֹךְ], some on this side, and some on that side : and they smote them,' etc. The meaning of the phrase is the same in our passage, viz. that the Benjaminites were 'in the midst' of the Israelite forces, caught between the main army and the ambuscade which has issued from the city. In וַיִּכּוּ, R.V. 'in the midst thereof,' the reference of the suffix is obscure, and we may regard the ו as properly the ו consecutive belonging to the verb which opens the next verse. Cf. *note* following.

43. *and they beat down . . . Geba'.* Reading וַיִּפְּתוּ אֶת־בְּנֵימִין in place of וַיִּרְדְּפוּהוּ הַרְדִּיפּוּהוּ, in place of וַיִּכּוּהוּ עַד נֶכַח נֶבֶעַ, בְּתוֹךְ אֶת־בְּנֵימִין הַרְדִּיכּוּהוּ עַד נֶכַח הַנֶּבֶעַ, rendered by R.V. 'They enclosed the Benjamites about, [and] chased them, [and] trode them down at [their] resting-place, as far as over against Gibeah.' The text of וַיִּכּוּ is undoubtedly very corrupt. כָּתְרוּ, 'they surrounded,' is strange in the description of a *pursuit*; and if the verb is preserved uncorrupted it seems almost necessary to regard the statement 'they surrounded Benjamin' as a marginal gloss upon בְּתוֹכָם in the preceding verse. Our emendation וַיִּפְּתוּ (so Ehr.) is based on *Gr*^B καὶ κατέκοπτον, *Gr*^{AL} καὶ ἔκοψαν; cf. the use of the verb in a similar connexion in Num. 14⁴⁵ (*Gr* καὶ κατέκοψαν αὐτούς), Deut. 1⁴⁴. The disappearance of ו consecutive before the verb may be due to the fact that it has been taken as the suffix of the preceding בְּתוֹכָם, which should be בְּתוֹךְ (cf. *note* preceding). The suggested emendations פָּתְתוּ or פָּרְתוּ have not the same support in usage.

‘and’ pursued him ‘from Nohah’ [] as far as over against ‘Geba’ towards the east. 44. And there fell of Benjamin

הַרְרִיכָהוּ, הַרְרִיפָהוּ are suspicious as being asyndeta. The Hiph’il of רָדַף is otherwise unknown. The Hiph’il הַרְרִיךְ can hardly mean ‘trod down,’ the sense which is assigned to it by A.V., R.V. (we should expect קָל; cf. Isa. 63³); but probably (as noted by Ros.) the meaning intended is ‘overtook,’ as in the Ar. Conjugation iv. and Syr. Aph’ēl of the verb. The close similarity between the two verbs marks them as doublets; and one of them at least must be deleted from the text.* We read וַיִּרְדָּפֵהוּ with La., Ehr. on the assumption that וי has been misread ה (cf. *note* on ‘and were drawn away,’ v.³¹), and delete הַרְרִיכָהוּ as a doublet.

מְנוּחָה, ‘rest’ or ‘resting-place,’ is treated by R.V., Ber., Ke., Oct. as an Accus. of place; but such a usage would be quite without parallel even if the subs. had the Def. Art. prefixed. The sense in which the word is used in its context has proved a crux to the Versions. G^{AL}, καταπαῦσαι αὐτὸν κατὰπαυσιν, treats it as a second Accus. after the preceding verb. S^P (connecting with following verb) regards מְנוּחָה as an adverbial Accus., סְכַנְכְּסַתְּ, ‘and quietly (easily?) slew him’—hence A.V. ‘trode them down with ease,’ and similarly Ros., and Böttcher in Winer’s *Zeitschr.* II. i. p. 62; but this is a misuse of the meaning of מְנוּחָה. F, T, G^B treat the initial מ of מְנוּחָה as the particle מן: so F somewhat paraphrastically, ‘nec erat ulla requies morientium,’ i.e. מן of separation, ‘apart from rest’; T (connecting with preceding verb) רדופונן מבית ניההן, ‘they chased them from their resting-place’; G^B καὶ ἐδίωξαν αὐτὸν ἀπὸ Νουα, treating נוּחָה as a place-name with מן as the *terminus a quo*. This last explanation, adopted by Houb., is favoured by Mo., who cites Nohah named in 1 Chr. 8² as the fourth ‘son,’ i.e. *clan* of Benjamin, and so possibly the name of a Benjaminite city or village. This we have adopted in our text (with La., and Driver in *ET*. xviii. p. 332) in default of a better solution; though, since it cannot be maintained with Mo. (*SBOT*.) that the *terminus ad quem* ‘as far as over against Geba’ requires a *terminus a quo* (there is none e.g. in Num. 14⁴⁵, Deut. 1⁴⁴), it must be admitted that the emendation is extremely precarious.† The only alternative seems to be to follow Bu. (with No., Kit., Cooke) in omitting מְנוּחָה as due to dittography, on the view that a scribe accidentally duplicated the words בְּנִימִין הַרְרִיפָהוּ and the duplication eventually became מְנוּחָה הַרְרִיכָהוּ.

* It is conceivable that both may be marginal variants of הַרְבִּיקָתָהוּ in the preceding verse.

† Luther and Stu. treat מְנוּחָה as a place-name defining the *terminus ad quem*, ‘unto Menuhah,’ this being further defined by ‘as far as, etc.’ Cf. for this *ch.* 7²², ‘toward Šeredah, as far as the edge of Abel-meholah.’

eighteen thousand men: ^{R^p} all these were men of valour.
 45. ^X And they turned and fled toward the wilderness unto the
 crag of Rimmon. ^{R^p} And they gleaned of him in the highways
 five thousand men, and they followed hard after him as far as
 'Geba', and they smote of him two thousand men. 46. So all

In ^U 'as far as over against Gibe'ah to the east,' 'Gibe'ah' is certainly an error, since, as Mo. remarks, 'the Israelites clearly did not desist from pursuit in the immediate vicinity of Gibe'ah, that is, at the very start.' Since the fugitives had as their objective the crag of Rimmon to the north-east (cf. *note* on *v.*⁴⁵ for the site), it is natural to suppose that we should read 'Geba', the two names (as noted on p. 464) being often confused. So Mo., Bu., La., Kit., Driver (*ET.* xviii. p. 332), Cooke. Why the pursuit ended at the point indicated hardly calls for solution, the reasonable inference being that the ultimate survivors had at this stage succeeded in getting clear away. Mo. remarks that 'Geba (Geba') lies in the line of flight from Gibeah (Tell el-Fûl) toward Rammôn, and the great wady es-Suweinit, with its difficult passage between Geba' and Makhmās, would naturally check the pursuit.' Similarly, Cooke—'Jeba' lies on the way to Rammon; but before the fugitives could reach their place of refuge (Rimmon, *v.*⁴⁵) the narrow defile of the Wadi Suwēnit (1 Sam. 14^{4ff.}), between Jeba' and Machmās would stop further pursuit.' The present writer can, however, state, from personal inspection of the wady, that at any point at which it would naturally be encountered in a flight from Tell el-Fûl or Râs et-Ṭawîl to Rammôn it could be crossed without much difficulty. Only if the fugitives had gone out of their way towards the east, and then struck off northward at an angle, would they have found the wady a formidable obstacle. Cf. Map, p. 465.

44. *all these, etc.* Heb. אֶת-כָּל-אֵלֶּה אֲנִשִּׁי הָיִל here and in *v.*⁴⁶, with אֵת introducing the Nominative with some emphasis—a mark of late and inferior style: cf. G-K. § 117 *m.*

45. *the crag of Rimmon.* Eusebius and Jerome (*OS.* 146⁵, 287⁹⁸) mention a village named Rimmon fifteen Roman miles north of Jerusalem. The identification by Rob (*BR.*³ i. p. 440) with the modern Rammôn, three and a half miles east of Bethel, 'situated on and around the summit of a conical chalky hill, and visible in all directions,' is generally accepted. Cf., however, *Addenda*, p. xxi, where the claims of a rival identification are discussed.

as far as Geba'. Reading עַד-גִּבְעָה with Mo. (Paβaa, Paβa is the reading of the group of ^U MSS. cited by Mo. as ^U), in place of ^U, עַד-גִּבְעָה which, as vocalized, can only be regarded as a proper

that fell of Benjamin were twenty and five thousand men that drew sword in that day: all these were men of valour. 47. But there turned and fled towards the wilderness unto the crag of Rimmon X six hundred men; J and they abode on the crag of Rimmon four months. 48. And the men of Israel turned back unto the children of Benjamin, and smote them at the edge

name 'unto Gid'om'—a locality which is otherwise quite unknown to us.

There should be no doubt that the emendation adopted is correct. The reference occurs in the redactor's interpolation, *vz.*^{15aβb.46}, the sole object of which is, not to supply *fresh* topographical information, but (cf. p. 448) to cure the discrepancy between the figure 18,000 in *v.*⁴⁴ (J), as compared with 25,100 in *v.*³⁵ (X). As a means of accomplishing this, he had in his sources *two scenes of action* to which the slaughter of further Benjaminites (making up, in round numbers, 25,000, *v.*⁴⁶) might be assigned: (*a*) the battlefield, which, as we learn from *vz.*^{31.32}, extended over the *m^esillôth*, 'highways,' west and north-west of Gibe'ah (cf. *note* on *v.*³¹); (*b*) the line of flight, which is described in *v.*⁴³ as extending (from the battlefield) 'as far as over against Geba.' Thus, on the view that the 18,000 fell on the battlefield before the flight (a deduction implied by the placing of *v.*⁴⁴ before *v.*^{45aa}), he assigns (*a*) an additional 5000 as the result of a grape-gleaning (for the use of the verb *ôlêl*, cf. the subs. *ôlêlôth* in *ch.* 8² *note*), i.e. a careful going over the *m^esillôth* a second time to wipe out stragglers; and (*b*) 2000 more as overtaken in the pursuit before it was abandoned on reaching 'as far as Geba.'

A casual suggestion thrown out (though not adopted) by Mo. in a footnote in his *Comm.* (p. 444) is that we might vocalize the word in *ח* as an Infinitive, עֲרֵי-נִדָּעִם 'till they cut them off': cf. the use of the verb in *ch.* 21⁶, 'One tribe is cut off (נִדָּעַ) to-day from Israel.' This has been adopted by succeeding commentators (so Bu., No., La., Kit., Cooke). Clearly the syntax will not admit of such a reading. Considering that Benjamin is referred to in the sing. both immediately before (אֲחֵרָיו) and immediately after (מִמֶּנּוּ), the writer's choice, had he meant to use such an Infinitive, would have lain between עֲרֵי-נִדָּעִן (cf. 1 Kgs. 22¹¹, Ps. 18³⁸), and, preferably, אֲחֵי עֲרֵי-נִדָּעִם (cf. Jer. 9¹⁶, 49³⁷, Deut. 7²⁴, 28⁴⁸, *al.*).

The reading of *ס*^p, 'Gibe'on,' is adopted by Grä.; but this city lay in the wrong direction.

48. *turned back unto the children of Benjamin.* The reference is to the non-combatants (old men, women, and children) whom they found at home in the cities and villages.

of the sword, both 'inhabited' city, and cattle, and everything that there was; moreover all the cities that there were they set on fire.

21. 1. Now the men of Israel had sworn in Mišpah, saying, 'There shall not any of us give his daughter to Benjamin to wife.' 2. R^p And the people came to Bethel, and sat there until the evening before God, and lifted up their voice, and wept sore. 3. And they said, 'Wherefore, O Yahweh, God of Israel, hath this come to pass in Israel, that there should be missing to-day one tribe from Israel?' 4. And on the morrow the people rose up early, and built there an altar, and offered burnt offerings and peace-offerings. 5. And the children of Israel, said, 'Who

both inhabited city. Vocalizing מְעִיר מְתָם, lit. 'both city of men,' as in Deut. 2³¹, 3⁶, Job 24¹², with several Heb. MSS., Stu., Wellh., Mo., etc., in place of מְעִיר מְתָם, which, if genuine, would seem to mean 'both city of *entirety*,' whence R.V. 'both entire city.' The subs. מְתָם only occurs again in Isa. 1⁶, Ps. 38^{3.7} (39^{1.8}) in a different connexion ('soundness' of body). Even with our emendation the sequence (lit.) 'from city of men unto cattle, unto everything, etc.' is rather strange. שׁ reads מִכָּל אֲנָשׁ סְבִיבָן לַחֲבִיבִין, which, if not merely a paraphrase, presupposes מִאָּדָם וְעַד-בְּהֵמָה וְנֶגְדָם 'from mankind to cattle, etc.': cf. Gen. 6⁷, 7²³, Ex. 9²⁵, 12¹², Lev. 27²⁸, Num. 3¹³, Jer. 50³, 51⁶², Ps. 135⁸. This reading, which is adopted by Grä., is certainly easier. Kit. מִמְּתָם 'from men,' omitting עִיר.

21, 4. *and built there an altar.* The statement is difficult to explain in view of 20^{26-28a}, according to which Bethel was the scene of the priestly ministrations of Phinehas, and the Israelites had already offered there the same forms of sacrifice as are mentioned in the present passage—clearly (it is implied) on the ancient altar pertaining to the sanctuary. Mo. and Bu. regard the statement relating to the new altar as a gloss; but, considering that the Bethel-passages, here and in *ch.* 20, appear to emanate from the late redactor R^p, it is difficult to conjecture what purpose a still later interpolator could have in view in making a fresh altar take the place of the old and orthodox altar as pictured by the priestly writer. May we conjecture that certain elements from one of the sources underlie R^p's work in 20^{26-28a}, and that among these there was an allusion to the building of an altar at *Mišpah*?

is there from among all the tribes of Israel that came not up in the assembly unto Yahweh?' For the great oath had been pronounced concerning him that came not up unto Yahweh to Mišpah, saying, 'He shall surely be put to death.' 6. X And the children of Israel were moved to pity for Benjamin their brother, and said, 'One tribe is cut off to-day from Israel. 7. J How shall we do for wives for them, R^p for the survivors, J seeing *we* have sworn by Yahweh not to give them of our daughters to wives?' 8. And they said, 'What one is there of the tribes of Israel that came not up unto Yahweh to Mišpah?' And, behold, there had come no man to the camp from Jabesh of Gile'ad R^p unto the assembly. 9. And the people were mustered, and, behold, there was not there a man of the inhabitants of Jabesh of Gile'ad. 10. J So R^p the congregation

5. *for the great oath, etc.* The definite form in which the reference is couched seems to point to a recognized formula, the provisions of which were well understood (Mo. compares 1 Sam. 14^{21.26.28}). Failing this explanation of the Def. Art., we must infer that it points back to an earlier mention of the oath—in which case it is probable that here again we have an element from one of the sources. R.V. 'for they had made a great oath, etc.,' does not bring out the force of the Heb.

6. *is cut off.* Lit. 'is hewn *or* lopped off,' like a branch from a tree (so Mo., who compares Isa. 10³³, 14¹²). In place of נִגְדָע some MSS. read נִנְרַע 'is withdrawn *or* subtracted,' which, though possible, is not so forcible as the accepted text.

7. *for them, for the survivors.* Here 'for them' originally found its reference in a part of J's narrative which has been omitted by R^p. Thus, to make the allusion clear, R^p has added 'for the survivors' (cf. v. 16a).

8. *Jabesh of Gile'ad.* The name is preserved in the wādy Yâbis, which runs into the Jordan from the east about nineteen miles north of the mouth of the Jabbok; but the site of the city has not been identified. Eusebius (*OS.* 225⁹⁸, 268⁸¹) describes it as lying 'on the mountain' (table-land) beyond Jordan six Roman miles from Pella on the road to Gerasa. Rob. (*BR.*³ iii. p. 319) proposes the ruined site ed-Dêr on the southern edge of wādy Yâbis, six miles from the Jordan; but this site, though the right distance from Pella (H. Faḥil), is off the road to Ġeraš, and, according to Merrill, unmarked by really ancient remains. Merrill (*DB.* ii. p. 524) favours the ancient site Meryamin on the northern side of wādy Yâbis; but this, though stated by him to be 'about seven miles from Pella,'

J sent thither twelve thousand men of the most valiant, and commanded them, saying, 'Go, and smite the inhabitants of Jabesh of Gile'ad at the edge of the sword, with the women and the little ones. 11. ^{R^p} And this is the thing that ye shall do; every male, and every woman that knoweth cohabitation with a male ye shall devote to destruction, J<but the virgins ye shall save alive.' And they did so.> 12. And they found of the inhabitants of Jabesh of Gile'ad four hundred virgin girls, that had not known a man ^{R^p} in respect of cohabitation with a male;

appears, as measured on the map, to be not more than two or three miles distant.*

Jabesh is mentioned elsewhere in the O.T. solely in connexion with the history of Saul. It was the rescue of the city from Nahash the 'Ammonite which (according to the J narrative 1 Sam. 11) gave Saul the opportunity of proving his ability as a leader and led to his election to the kingship; and in grateful memory of this rescue the inhabitants of Jabesh, after the death of Saul at the battle of Mount Gilboa, recovered his body from the wall of Beth-she'an where it had been hung by the Philistines, and buried it, together with the bodies of his sons, in or near their city (1 Sam. 31^{s-13}). David, on his succession to the kingship at Hebron, sent a message of thanks to the Jabeshites for this action (2 Sam. 2^{4ff.}), and eventually brought back the bones of Saul and his sons from Jabesh and buried them in the ancestral tomb of Kish in the land of Benjamin (2 Sam. 21^{12ff.}). The selection of this city—so friendly and faithful to Saul—for a shameful part in a narrative which deals with an atrocious deed committed by Gibe'ah, Saul's native city, suggests with some reason that the leading motive in the story may have been deep antipathy to the memory of Saul and his adherents. Cf. p. 447.

11. *but the virgins . . . did so.* Adding וְאֵת־הַבְּתוּלוֹת תַּחֲיוּ וַיַּעֲשׂוּ כֵן after E^B τὰς δὲ παρθένους περιποιήσεσθε. καὶ ἐποίησαν οὕτως. Cf. E 'virgines autem reservate.' The addition is indispensable in view of the fact that the saving of the virgin girls was the prime purpose of the expedition.

12. *four hundred virgin girls.* It is not unlikely that, according to J, there were only four hundred surviving Benjaminites to be provided with wives.

* There is a discrepancy in the position of Meryamîn as given by the Smith-Bartholomew map and the *EB*. map the former placing it barely two miles south-east of H . Faḥil and three and a quarter miles north-west of deir Halāweh (ed-Dēr), while the latter places it nearer the wādy Yābis, three and a half miles south-east of H . Faḥil and two and a half miles north-west of ed-Dēr. Smith's Map VI. in *HG*. agrees more nearly with *EB*.

J and they brought them unto the camp ^{R^p} to Shiloh, which is in the land of Cana'an.

13. J Then ^{R^p} the whole congregation J sent, and spake unto the children of Benjamin that were on the crag of Rimmon, and proclaimed peace to them. 14. And Benjamin returned at that time, and they gave them the women that they had saved alive of the women of Jabesh of Gile'ad; ^{R^p} and yet so they did not find enough for them. 15. And the people were moved to pity for Benjamin, because that Yahweh had made a breach in the tribes of Israel. 16. And the elders of the congregation said, 'How shall we do for wives for the survivors, seeing that women have been destroyed out of Benjamin?' 17. ^X And they said, 'How shall a remnant be left to Benjamin, that a tribe be not blotted out from Israel, 18. seeing that *we* are not

to Shiloh. Why the camp should be represented as transferred from Mišpah (or Bethel) to Shiloh cannot be divined. Mo. thinks that the editor may be already shifting the scene to prepare for the narrative of *vv.* ^{19 ff.}, though, as he adds, 'that story is really quite incompatible with the presence of the Israelite encampment at Shiloh.'

which is in the land of Cana'an. The same curious definition is found in Josh. 21 ², 22 ⁹, with reference to Shiloh, both passages belonging to the Priestly source. The second passage, which relates how the two and a half tribes leave Shiloh to return to Gile'ad, east of Jordan, suggests that 'in the land of Cana'an' may be the equivalent of 'west of Jordan,' as distinct from east of it (cf. Josh. 22 ¹⁰); but in any case, the fact that the site of Shiloh has to be defined at all indicates a very late date for the comment. Cf. the exact description of the site in *v.* ¹⁹.

15. *Yahweh had made a breach.* For the phrase, cf. 2 Sam. 6 ⁸. Similarly (verb פָּרַץ) 2 Sam. 5 ²⁰, Ex. 19 ^{22, 24}.

17. *How shall a remnant be left.* Reading אֵיךְ תִּשָּׁאֵר פְּלִיטָה as suggested by some MSS. of Ἐπὶ πῶς ἔσται κληρὸς διασωζόμενος κτλ., with Mo. (who offers the alternative verb תִּנָּחֵץ), La., Kit., Driver (*ET.* xviii. p. 332), Cooke. יְרִשֶׁת פְּלִיטָה לְב' 'An inheritance of a remnant for (or pertaining to) Benjamin,' is freely expanded by A.V., R.V. into 'There must be an inheritance for them that be escaped of Benjamin'; but even if we grant the legitimacy of this rendering, there still remains the difficulty that the question deals with the *territory* of Benjamin, whereas the context makes it clear that the immediate concern was to secure that *the tribe itself* should not be

able to give them wives of our daughters?' for the children of Israel had sworn, saying, 'Cursed be he that giveth a wife to Benjamin.' 19. And they said, 'Behold, there is the feast of Yahweh in Shiloh yearly,' ^{R^p} which is on the north of Bethel, on the east of 'the' highway which goeth up from Bethel to Shechem, and on the south of Lebonah. 20. ^X And 'they' commanded the children of Benjamin, saying, 'Go and lie in wait in the vineyards; 21. and see, and, behold, if the daughters of Shiloh come forth to dance in the dances, then come ye forth from the vineyards, and snatch ye every man his wife from the daughters of Shiloh, and go to the land of Benjamin. 22. And

blotted out. Oort reads תִּיָּצֵא 'let there be left, etc,' following ^{S^p} סִמְלֵי־נִשְׁלָחֵם וְיָבִיאוּ לַחֲבֵרָתָם; while Bu., No., prefer נִשְׁאִירָה 'let us leave, etc.'

19. *Behold there is, etc.* Bu. is doubtless right in regarding these words as addressed to the Benjaminites, and as directly continued by v. ^{20b} in the original narrative. The insertion of the topographical note in v. ¹⁹ has necessitated the resumption, 'And they commanded, etc.'

the feast of Yahweh. The Heb. term *hag* properly means 'a pilgrimage' (cf. Ar. *ḥaġġ*); and though the description of the festival suggests that it was local in character, it may have been attended by pilgrims from the country round. Cf. the description of the position occupied by Shiloh as the religious centre for festival-pilgrimages in 1 Sam. 1, 2.

which is on the north, etc. The modern Sêlûn (cf. *ch.* 18 ³¹ *note*) is, as described, nearly ten miles north-north-east of Bêtîn (Bethel), two miles east of the high road to Nâblus (Shechem), and three miles east-south-east of el-Lubbân (Lebonah).*

of the highway. Vocalizing לְמִסְלָה with the Def. Art., in place of מִסְלָה.

20. *And they commanded.* וַיִּצְוּ ^{K^r} in place of Kt. וַיִּצְוּ.

21. *if the daughters of Shiloh come out.* On the plur. masc. predicate before a plur. fem. subj., cf. G-K. § 145 *φ*.

* In the phrase מִצְפֹּנָה cf., for the Construct State before the prep., G-K. § 130 *a*, *n* ³, and, for the ה *locative* with the Construct State, G-K. § 90 *c*. The normal phrase is מִצְפֹּנָה, cf. *ch.* 2 ⁹, *al*.

when their^r fathers or their^r brothers come to complain unto 'you', 'ye' shall say, 'Grant them^m graciously to us; for we took not every man his wife in battle: for 'if' ye had given them to 'us', ye would now be guilty.' 23. And the children of

22. *their fathers or their brothers.* Reading fem. suffixes אֶבְיֹתָן, in place of the erroneous masc. suffixes of אֲחֵיהֶן. Similarly we must read אֶתְּהֶן or אֶתָּן (Ezek. 16⁵⁴) for אֶתָּהֶם in the request 'Grant them graciously, etc.' With the mention of the *brothers* as likely to be prominent in demanding satisfaction, cf. Gen. 34^{7ff.}, 2 Sam. 13^{20ff.}

To complain. On *Kt.* לָרִיב, cf. *ch.* 6³² note. אֲרֵרֶה substitutes the normal לָרִיב.

unto you. Reading אֲלֵיכֶם with G^{1A}, S^b, F, in place of אֲלֵינוּ 'unto us.' The aggrieved Shilonites would naturally complain directly to the captors, rather than to Israel at large.

ye shall say. Reading וְאָמַרְתֶּם in place of וְאָמַרְנוּ 'we will say.' The emendation is necessitated by that immediately preceding, and by the words of the speech which follow ('to us,' 'for we took not every man his wife, etc.').* The retention of וְאָמַרְנוּ involves emendation of the speech: cf. *notes* following.

Grant them graciously . . . be guilty. Reading לָא for לֹא (as suggested by Stu.) and לָנָּה for לָהֶם. The Benjaminites are to appeal to the complaisance of the Shilonites, adducing two reasons: (1) that the Shilonites were not bound to a vendetta on account of the rape, since the maidens had not been captured in *battle*; (2) nor, on the other hand, had they *given* their daughters to the Benjaminites, and so they were not guilty of infringing the oath (*v.* 1⁴). The measure adopted by the Benjaminites had in fact steered a middle course between capture with bloodshed, which must have forced a quarrel on the Shilonites, and request for the maidens as a voluntary gift, which, if granted by the Shilonites, would have brought them under the curse. The double Accus. in הִגֵּנוּ אֶתָּן is exactly paralleled by Ps. 119²⁹ תִּזְכֶּנִּי חֲנֻנִי, 'Graciously grant me Thy law.' The Def. Art. in בְּמִלְחָמָה does not necessarily refer to any specific battle (cf. 1 Sam. 26¹⁰, 30²⁴, 2 Sam. 19⁴), though it is possible to find in it an allusion to the great battle of *ch.* 20.

* The renderings of A.V., 'because we reserved not to each man his wife, etc.' R.V., 'because we took not for each man [of them] his wife etc.' stand in daring disregard of the meaning of the common Heb. idiom.

DESCRIPTION OF THE PLATES

PLATE I.

TWO scribes taking note of spoils after an Assyrian victory. The bearded man is writing Assyrian in cuneiform upon a clay tablet, using an angular stylus which is held through the full of the hand to impress the characters upon the soft clay. The other man, who is marked by his shaven face as a foreigner, is writing with a pen upon a roll of leather or papyrus, and employing, no doubt, the West Semitic alphabetic script, to make his entry in a language which we may conjecture to be Aramaic. It is interesting in this connexion to note that a general list of titles and offices contained in ii. R. 31, 64b-65b mentions together A.BA *mât Aššur-a-a* and A.BA *mât Ar-ma-a-a*, *i.e.*, perhaps, 'an Assyrian secretary' and 'an Aramaean secretary' (the honorific title A.BA='elder' is here thought to correspond to *duššarru* 'tablet-writer,'* the Heb. *ṭiphšar* of Nah. 3¹⁷, Jer. 51²⁷). The representation is part of a large relief from Kouyunjik (Nineveh) figured in Layard, *Monuments of Nineveh, 2nd Series*, Pl. 26, and is now in the British Museum, Kouyunjik gallery, west wall, series Nos. 4-8. It dates from the seventh century B.C. Similar pairs of scribes are figured in Layard, *op. cit.*, Plates 26, upper tier, 19, 29 (both with scrolls), 35, 37, 50. Cf. the remarks on this Plate on pp. 255 f. of the Commentary.

PLATE II.

Figs. 1 and 2. A figure described in pictographic writing as *ilu Šamaš* (the Sun-god) contends with antelopes and lions.

Fig. 3. Gilgameš contends with antelopes and lions. The arrangement of the figures is identical with that of figs. 1 and 2, the only difference being that Gilgameš takes the place of *ilu Šamaš*. That the figure on this seal is Gilgameš is indicated by his full-face representation, and the arrangement of his hair in six locks: cf. Plate III. figs. 1 and 2. Cf. p. 400.

* Cf. Delitzsch, *Paradies*, p. 258; *Beiträge zur Assyriologie*, i. p. 218; *Sumerisches Glossar*, p. 4.

Fig. 4. Gilgameš and Engidu struggling with a bull and lion respectively. On the manner in which Engidu is tearing asunder the hind legs of the lion, cf. *note* on Judg. 14⁶.

Fig. 5. Three Gilgameš-figures wrestling with similar figures. The vanquished figure appears to have been thrown by impact of the victor's thigh against his leg—a form of throw which may perhaps be intended by the obscure phrase שוק על ירך 'leg upon thigh' in Judg. 15⁸ (cf. *note ad loc.*). Cf. also the seal figured by Hayes Ward, *The Seal Cylinders of Western Asia* (1910), fig. 199.

The five figures included in this Plate are reproduced by permission from Delaporte's *Catalogue des Cylindres orientaux . . . de la Bibliothèque Nationale*.

PLATE III.

Fig. 1. Gilgameš struggling with a lion. He appears to be throwing it by impact of his knee against its back, or by turning it across his thigh (cf. description Plate II. fig. 5), possibly in order to break its back (cf. Hayes Ward, *op. cit.*, fig. 157). This is the finest figure of Gilgameš in existence. Note especially the characteristic arrangement of his hair in six locks. The seven locks or plaits (מחלפות) of Samson may perhaps be analogous. Cf. pp. 379 f., 404.

Fig. 2. On the left, Gilgameš and his friend Engidu contend with the heavenly bull (the bull of Anu). On the right, Gilgameš is represented in contest with a lion. This seal illustrates very clearly the fact that, in this and similar representations, we really have to do with scenes from the Gilgameš-epic (against the view of Sayce, as quoted, p. 401, *footnote*). The description of the contest with the heavenly bull (sent against Gilgameš by the god Anu at the request of Ištar, in revenge for the hero's rejection of her advances : cf. p. 397 of the Commentary) exists in a fragmentary state on Tab. VI. ll. 92 ff. of the Epic. Engidu is described as taking the bull 'by the root (thick part) of its tail' (*ina kubur zibbatīšu*, l. 147) and 'by its horns' (ll. 134 f.), exactly as he is doing on the cylinder-representation. Engidu is always figured with the face and torso of a man, but with the hind legs, tail, horns, and ears of a bull. When first introduced in the Epic he is described as human, but dwelling among the beasts of the field and sharing their characteristics (Tab. I. col. ii. ll. 35 ff.). Having been enticed away from their society, he becomes the inseparable companion of Gilgameš, and the sharer of his adventures.

Fig. 3. The Sun-god (*ilu Šamaš*) issuing through the gates of sunrise, which are held back by attendants, and stepping on to a

double-peaked mountain—probably the mountain of *Māšu* ('twin-mountain') mentioned in the Gilgameš-epic as standing at the gates of sunrise. Cf. pp. 395, 399 f., 406 f.

The three figures in this Plate are reproduced by permission of the Trustees of the British Museum from wax-impressions specially made for the writer through the kindness of Dr. L. W. King.

All the figures in Plates II. and III. are examples of Sumerian or early Semitic Babylonian art not later than the third millennium B.C.

PLATE IV.

Gilgameš with the lion as represented in Assyrian art. The relief is from the palace of Sargon (reigned B.C. 722-705) at Khorsabad (*Dûr-Šarrukîn*), and is now in the Louvre. From a photograph by Braun et C^{ie}.

PLATE V.

Two reliefs from Carchemish, illustrating the spread of the Gilgameš-myth to the Hittites.

Fig. 1. Two identical full-faced figures like Engidu as represented on Babylonian seals, with hind quarters, tail, horns, and ears of a bull, but human face and torso, holding spear and advancing left and right. Two lion-headed human figures behind, wearing short tunics. One threatens Engidu with a weapon.

Fig. 2. A figure full-faced like Gilgameš, but with Hittite cap, kilt, and boots, holds a lion or lioness by the hind legs with his right hand and a bull by the horns with his left hand. A stag and two lion-cubs (?) are in the field. These figures of Gilgameš and Engidu are the only full-faced figures among the representations from Carchemish.

Dr. D. G. Hogarth, who dates the reliefs about the ninth century B.C., points out that, while Babylonian or Assyrian influence is manifest, the technique is characteristically Hittite, the relief returning quite steeply to the bed of the plane. Contrast the Assyrian figure of Gilgameš in Plate IV.

The figures are reproduced, by permission of the Trustees of the British Museum, from *Carchemish: Report on Excavations*, 1914, ed. D. G. Hogarth.

PLATE VI.

A colossal figure from Amathus in Cyprus: height 4 m., 20, breadth of shoulders 2 m. The art is Phoenician; and the figure, which doubtless represents Herakles-Melkart, illustrates the spread of the

Gilgameš-myth westward. M. Al. Sorlin-Dorigny, who describes the figure in the *Gazette Archéologique*, 1879, pp. 230-236, states that it originally had an ornament on the top of the head, inserted a little behind the horns, in a hole measuring four centimetres in diameter and twelve centimetres in depth. From the edge of this hole all the locks of hair diverge, some, short and wavy, falling over the forehead, others, long and smooth, forming six tresses ('ondulations') in the Assyrian manner, then dividing themselves into three great bunches of curls which rest on the neck and shoulders. The two horns are imperfect. Assyrian influence is very marked in the treatment of the beard.

It will be observed that, while the figure generally suggests Gilgameš, especially as regards hair and beard, there is more than a suggestion of Engidu in the horns and in the manner in which he is rending the lion by tearing its hind legs asunder (cf. Plate II. fig. 4).

The figure is reproduced from Perrot et Chipiez, *Histoire de l'art dans l'antiquité*, iii., fig. 386, by arrangement with Messrs. Chapman and Hall, Ltd., who own the rights of reproduction in England.

On Plates IV.-VI., as illustrating the widespread influence of the Gilgameš-myth, cf. p. 401 of the Commentary.

NOTE ON THE MAPS OF PALESTINE

The Maps of Palestine at the end of this volume have been prepared by Messrs. Bartholomew, who are responsible for the coloured contours and all other physical features. The site-identifications have been carefully weighed by the present editor, whose aim has been to admit no identification which does not seem to him to be reasonably assured upon historical and philological grounds.

The editor is indebted, in the first place, to the Map of Western Palestine, in twenty-six sheets, from surveys conducted under the auspices of the *PEF.* (scale one inch to the mile: cited in the Commentary as *SWP. Great Map*), and to the Arabic Name List prepared for the Survey by Prof. Palmer: for the modern names in Map V. he is chiefly indebted to the map of the Negeb in *EB.*, and to Prof. Guthe's *Bibelatlas* (1911), as well as to the excellent map by Dr. Hans Fischer in *ZDPV.* xxxiii (1910).

The identification of ancient sites depends upon the labours of a number of investigators in the past, among whose works mention may be made of Dr. Robinson's *Biblical Researches in Palestine* (a work which, though based upon travels undertaken so far back as 1838 and 1852, still possesses very considerable value), the *Memoirs* of the Survey of Western Palestine published by the *PEF.*, Sir G. A. Smith's *Historical Geography of the Holy Land* (first published in 1894), and Prof. F. Buhl's *Geographie des alten Palästina* (1896).

The only British *maps* of Palestine marking ancient sites which are thoroughly trustworthy are those contained in *EB.*; and the help afforded by these was usefully supplemented by Prof. Guthe's *Bibel-atlas* already mentioned. Other British maps depend chiefly upon the site-identifications contained in the *SWP. Mem.*, and embodied in the maps published by the *PEF.* which mark ancient sites; and these, while offering much that is valuable, are unfortunately vitiated by many identifications which are highly dubious, and by some which are positively misleading.* This stricture extends, unfortunately, in some degree even to the folding map (scale four miles to one inch) published under the direction of Mr. J. G. Bartholomew and edited by Dr. G. A. Smith, which is in many respects the most useful general map which can be employed.†

As occasion arose in the Commentary, the attempt has been made to note and illustrate the modifications which ancient Biblical names

* Dr. Driver's warning (*NHTS.*² p. xcv) may well be reiterated:—'The identification of a modern with an ancient site depends mostly, it must be remembered, in cases in which the ancient name itself has not been unambiguously preserved, partly upon historical, but very largely upon philological considerations: and men who are admirable surveyors, and who can write valuable descriptions of the physical features, topography, or antiquities of a country, are not necessarily good philologists.'

‡ Since the maps for the present Commentary were printed, there has appeared (1915) the long-expected *Atlas of the Historical Geography of the Holy Land*, edited by G. A. Smith and J. G. Bartholomew. This is a work which takes first rank among Biblical Atlases for beauty of execution, and which contains much that is of first importance to the student—notably the valuable maps of Jerusalem at different periods, and modern Jerusalem illustrating recent discoveries, which have already appeared in G. A. Smith's *Jerusalem* (1907), and the sectional maps of Palestine on the scale of one inch to four miles which represent a revision of the folding map to which allusion has been made above. These latter maps will naturally be the most consulted of all that are contained in the Atlas; and it is therefore to be noted with regret that they have not undergone the thorough revision which was anticipated by Dr. Driver when he expressed the conviction (*VHTS.*² p. xcv) that the forthcoming Atlas was 'likely to prove in all respects adequate and trustworthy.' To take some points which strike the eye—sect. iii. still contains the preposterous identification of Betsaanim with Sabel el-Ahmâ which depends (cf. *note* on *ch.* 4¹¹) upon A.V.'s erroneous rendering of 'ēlôn 'terebinth' as 'plain.' In the Orographical map 11-12 the 'plain of Zaanaim' still stands; and here and in sect. map vii. we have the 'plain of Mamre' (A.V.'s error for *terebinths* of Mamre). In sect. vi. Gibe'ah is identified with Geba' and both with the modern Jeba' (Geba'), in face of the cogent Biblical evidence noted on *ch.* 19¹² that Gibe'ah is distinct from Geba', and of Dr. Smith's own adoption (*Jerusalem*, ii. p. 92, n³) of the commonly received identification of the former with Tell el-Fûl. Other impossible, or highly improbable, identifications (hardly palliated by the fact that they are marked with a query) are 'Ain-Helweh = Abel Meholah (cf. *ch.* 7²² *note*), 'Osh el-Ghurâb = Rock 'Oreb (*ch.* 7²⁵ *note*), Kh. 'Ermâ = Qiriath-Je'arim (*ch.* 18¹² *note*), Tell Deir-'Allah, north of the Jabboḳ = Succoth (surely, in spite of the Talmudic identification with Dar'ala, to be looked for south of the Jabboḳ: cf. p. 220). The identifications of Kefr Ḥasan with Ashnah, and of Ta'lat Heisa with the Ascent of Luḥiṭh, which are now (as contrasted with

have undergone in their reproduction in modern Arabic form.* This is a subject which needs, and would repay, more detailed and systematic study than it has as yet received, at any rate in this country. The only scientific attempt to grapple with the subject (so far as the present writer is aware) is that by G. Kampffmeyer in his articles entitled *Alte Namen in heutigen Palästina und Syrien* in *ZDPV.* xv. (1892), pp. 1-33, 65-116; xvi. pp. 1-71, which well repay careful study. Even a superficial examination of the site-identifications which have so far been fixed or proposed suggests that, while, on the one hand, we have to be on our guard against conclusions which have been drawn in ignorance of philology, yet, on the other hand, there is danger lest we should be limited by too strict a regard for the philological laws, as ordinarily understood, which govern correspondence between Hebrew and Arabic forms. When, as must have happened in a multitude of cases, ancient names have been preserved for centuries merely by oral transmission among ignorant peasants, it is surely inevitable that they should sometimes have assumed a form which, as compared with the original, would seem to be incapable of being brought under the laws of correct philological interchange. Further, there is evidence which indicates that, in some few cases at least, the modern name as transmitted has assumed a form which possesses no sort of philological connexion with the ancient name, and has been suggested merely by a rough assonance with its original. Such a case has been noted in the modern name of the Nishon, Nahī el-Muḡaṭṭā', *i.e.* 'river of the ford,' which has almost certainly arisen through assonance with the ancient city-name Megiddo of unknown meaning in the near vicinity.† Other instances are probably to be seen in the modern name 'Aid el-Mâ, 'the feast of water,' or, in a variant form, 'Aid el-Miyyeh, 'the feast of the one hundred,' which has been plausibly suggested as the modern equivalent of 'Adullam,

the folding map) marked with a query in deference to Dr. Driver's strictures in *ET.* xxi. pp. 495, 563 f., should surely have been omitted altogether. We also find, without so much as a query, the very questionable identifications el-Lejjûn = Megiddo, instead of (as now established) Tell el-Mutesellim nearly a mile to the north (cf. *ch.* 1²⁷ note), Tûbâs = Thebez (cf. *ch.* 9⁵⁰ note), Tell esh-Sheri'ah = Sharūhen, edh-Dhaheriyeh = Debir (an identification which, though generally accepted, is really based upon a wholly false etymological conclusion drawn by Conder, and is therefore at best nothing more than a guess at the site, apart from any connexion in name: cf. *ch.* 1¹¹ note). On the other hand, the identification of Liftâ with Nephtoah, which is philologically sound and also suitable to the description of Josh. 15⁹, 18¹⁵ (and which the present writer would have included in his own map without a query, if he had made the investigation embodied under *ch.* 18¹² before the completion of the map) is not noticed at all; and Kuryet el-'Enab, which strong probability marks as the site of Kiriath-Je'arim (cf. *ch.* 18¹² note) is simply marked (with a query) as the site of the obscure Kiriath of Josh. 18²⁸ (where the text is very possibly at fault).

* Cf. the footnotes pp. 21, 23, 24, 27, 29, 282, 306, 377, 430.

† Cf. note on 'the rills of Megiddo,' *ch.* 5¹⁹.

and in 'Ain Şarah for the well (or cistern) of Şarah (2 Sam. 3²⁰). Doubtless a number of such cases might be collected.

Even when we find a satisfactory correspondence between a modern and an ancient name, this in itself by no means settles the problem of identification. It is clear that there has occurred a certain amount of drifting of ancient place-names, the names being now attached to modern villages or to remains which cannot go back so far as O.T. times. Instances of this may be seen in Erihâ (= Jericho, Heb. *Yerîhō*) which is now the site of a modern village one and a half miles south-east of the mound called Tell es-Sultân which undoubtedly represents the site of ancient Jericho; Umm Lâkis, which probably preserves the ancient name of Lachish,* though the ancient site of this city is fixed with high probability at Tell el-Hasy, three miles to the south-east; Zer'in, which corresponds accurately with Jezre'el, though, as Prof. Macalister has recently pointed out (cf. *ch.* 6³³ *note*), the modern site contains no remains of an antiquity approaching the O.T. period.

To be ideally complete, the evidence for identification of an ancient site should be threefold:—(a) The philological equivalence between the ancient and modern names should be satisfactory. (b) The site should be attested by the evidence afforded by Biblical and extra-Biblical historians. (c) Examination *in situ* should be able to prove the existence of remains of a sufficient antiquity.

The meaning of the geographical terms which occur in Arabic in the maps is as follows:—

'*Ain* = spring.

Bîr or *Bîreh* = well.

Ġeb. = *Ġebel* = mountain.

Ġisr = bridge.

H. = *Hirbet* = ruin (ruined site).

Kefr = village.

Nahr = river.

Râs = head (headland).

Sahel = plain.

Ta'lat = ascent.

Tell = mound (usually formed by débris of ruined city).

W. = *Wâdy* = watercourse (cf. p. 88).

* The interchange between *k* and *ḵ* which is involved has been thought to constitute a difficulty. Cf., however, the converse interchange in the modern Kânah as compared with the ancient Kānah (cf. p. 24).

The following orthographical corrections of names in the maps should be noted :—

MAP II.

For Hapharaim read Ḥapharaim.

„ Gilboa „ Gilboa'.

MAP III.

For Wâdy Ḳanâh (*W. Ḳânah*) read Wâdy Ḳanah (*W. Kânah*).

„ *Kefr Ânâ* read *Kefr 'Ânâ*.

„ *Mukmâs* „ *Muḥmâs*.

„ Ebal „ 'Ebal.

„ Ṣor'ah „ Ṣor'ah.

„ Miẓpeh „ Miṣpeh.

„ *er-Rummâneh* read *Rammôr*.

Before *Liftî* add *Nephtoah*.

„ Ḥ. Ṣâr add *Ja'zer*?

MAP IV.

For Ḥ. *Gâlâ* read Ḥ. *Ġâlâ*.

„ *Ziklag* „ *Ṣiklag*.

„ *Beth-zur* „ *Beth-ṣur*.

„ *Nezib* (*Bêt Nasîb*) read *Neṣîb* (*Bet Naṣîb*).

MAP V.

For *Bozrah* read *Boṣrah*.

INDICES

I. GENERAL INDEX

- Aaron, 436, 440 f.
 Abd-Aširta, lxxii, lxxvi, lxxviii, lxxx, xcii, 196.
 'Abdi, 'Abdiel, 278.
 Abdi-Tirši, cxvii.
 'Abdon, ciii, 289 f., 335.
 Abel-ceramim, 321.
 Abel-meholah, 220 ff.
 Abiathar, lii, 239, 478.
 Abi-eshu', lix.
 Abi'ezer, 134, 179, 187, 227.
 Abimelech, xxxvii, xlix, cii, ciii, 76, 263, 265, 266 ff., 250.
 Abi-milki, 265.
 Abishua', lix.
 Abram, Abraham, lxxiv, lxxx, lxxxv, cix, cx, cxi, cxiv f., 9; meaning of name, 250.
 Acacia, 465.
 'Acco, 28.
 'Achšah, 13.
 Achzib, xiii, 29.
 Acre, 28.
 Adad-Nirari I., lxxix.
 Adad-šunr-našir, ci.
 Adam, city of, xiii, 219.
 Adoni in compound names, 4.
 Adoni-bezek, 4.
 Adoni-šedeq, lxxxvi, cxvii, 5 f., 41, 81, 264.
 Adonis. See 'Tammuz.'
 'Adullam, 500.
 Aegean pottery, xciv.
 Aeginetans, 6.
 Afkâ, 29.
 Agag, execution of, 344.
 Ağbêhât, 231.
 Agum-Kakrime, lxiv.
 Ahab, liii, xcvi.
 Ahaziah of Israel, liii.
 Ahētaton, lxx.
 Ahijah, lii.
 Ahiman, 9 f.
 Ahimelech, lii.
 Ahitub, lii.
 Ahlab, 28.
 Ahlamu, lxxix, lxxxiii.
 Ahmosi I., lxvi, lxvii, cxii, cxv, cxvi.
 Ahnaton, lxx, lxxii, lxxiii, lxxix, lxxxvii, lxxxviii, cxii, cxiv, 253. See also 'Amenhotp IV.'
 'Ai, cviii, 21.
 'Aid el-Ma, 'Aid el-Miyyeh, 500.
 Aijalon, 8, 32, 334.
 'Ain 'Aṭân, 370.
 'Ain Dilbeh, 14.
 'Ain es-Sultân, 15.
 'Ain Ġâlûd, 205, 208 f.
 'Ain Ġidî, 16.
 'Ain Hegîreh, 14.
 'Ain el-Ḥelweh, 220.
 'Ain el-Ḥôd, 406.
 'Ain Kudês, 34, 110.
 'Ain Mâhil, 27.
 'Ain Šarah, 501.
 'Ain-šems, xciv, cvii, 340, 406, 430.
 'Akaywaša, xcii.
 Akiya, lxx, lxxxvi.
 'Akkâ, 28.
 Akkad, lxii; Semitic dynasty of, lvf., lx.
 'Akrabbim, ascent of, 33 f.
 Alasa, xcvi.
 Aleppo, lxii.
 Alphabet, names of letters in Greek and Hebrew, 262. See also 'Writing.'
 Alphabetic script, xcvi, 254 ff., 495.
 Altar, primitive rock-, 192, 349, 350; built of stones, 192, 199; at Bethel, 488.
 'Amaleq, 'Amaleqites, li, lxxix, 17, 68, 110, 132, 185, 297.
 Amarna Tablets. See 'Tell el-Amarna.'
 Amathus, 'Amâteh, 326.
 Amenhotp I., lxvii.
 Amenhotp II., lxix, cxii, cxv, cxvi.
 Amenhotp III., lxix, lxx, lxxii, lxxiii, lxxxiii, cxiii, cxvi, 253.

- Amenhotp **IV.**, lxix, lxx. See also 'Aḥnaton.'
- Amḥaruna, 19.
- Ammiditana, lviii, lxii, lxxx.
- Ammizaduga, lviii.
- 'Ammon, children of ('Ammonites), liii, cx, 297, 298 ff.; land of, 305.
- Ammonium, oasis of, 406.
- Ammu* or *Ammi* in proper names, lviii.
- Amon, priesthood of, lxxxvii, lxxxviii, xcvi; temple of, lxvii, xcix; barge of, xcvi, xvii; 'Amon-of-the-Way,' xcvi.
- Amor. See 'Amurru.'
- Amorite, Amorites, lviii ff., lxxiii, lxxxvii, cviii, 3, 30, 41, 297, 385.
- 'Amos, xxxviii.
- Amraphel, lxii, cx, 249.
- Amurru, Amor, lvi, lix, lxi, lxii, lxiv, lxvi, lxxiii, lxxix, lxxx, lxxxi, lxxxv, lxxxvii, xc, xcv, cxiv, 41, 196; language of, lxi, 166. See also 'West Semitic language.'
- 'Amwās, 464.
- 'Anakites, 9, 10, 20, 46.
- 'Anatā, 30.
- 'Anath, 30, 76.
- 'Anath-bethel, 30.
- 'Anath-el, lxvi.
- 'Anath-yahu, 30.
- 'Anathoth, 30.
- Anatolian strain in Assyrians, c.
- Anatum, Antum, consort of Anu, 30; hypocoristic form, 76.
- Angel of Yahweh (of God), 35 f., 89, 151, 186, 192, 341, 346.
- Antigone, 323 f.
- Anu, 30, 76, 385, 397, 496.
- Anum-pi-Sin, lxxxiii.
- Aphik, 29.
- Aphrodite, 333, 402.
- Apil-Sin, lviii.
- Apollo, 406.
- '*Apuriu*, '*Apriu*, cxiv.
- Aquarius*, 399.
- Arabia, central, early common home of Semites, lvi, lx; north, cviii, 9, 10, 439, 441; south, lix, lxi, 400.
- Arabic language, exhibiting primitive formations, lx.
- 'Arad, 16, 44 f.
- ARAD-Ḥiba, lxxiii, lxxiv, lxxv, lxxvii, lxxviii, lxxxi, lxxxii, lxxxiv, lxxxvi, cxvii, 256; nationality of, lxxxvi.
- 'Arāk Isma'in, 371.
- Aram-Damascus, 428.
- Aram-naharaim, lxxx, 66.
- Aramaeans, lxxix f., cx f.
- Aramaic language, influence of environment upon, lx; a dialectical form of the language of Amurru, lxi, 175; dockets in, on cuneiform tablets, 255.
- Aramäisms, 129, 172 ff.
- Arami the son of Gus, cii.
- Arandaš, lxxxvi, lxxxix.
- Arawna (Araunah), Aranya, lxxxvi, 20.
- Arbela, 43.
- Arethusa, xiii, c.
- Arik-dên-ili, lxxix.
- Arioch, lxii.
- Ark of God (of Yahweh), 3, 37, 242, 344, 415, 435, 440, 477.
- Armenians, lxxi.
- Arnon, 221, 305, 306, 312, 314.
- Arnuanta, lxxxvi, xcix.
- 'Aro'er, 'Arā'ir (by Arnon), 221, 316, 320; (in 'Ammonite territory), 320.
- Artakhšatrā (Artaxerxes), lxxxiv.
- Artamanya, lxxxiv, lxxxvi.
- Artāššumara, lxvii, lxxxvi.
- Artatama, lxix, lxxxvi; (grandson), lxxii, lxxiii.
- Artemis, 85, 332.
- Arumah, 281.
- Arvad, lxviii, xci, ci.
- Aryans in Western Asia, lxxxiv f.
- Arzawa, letters, lxxi, lxxxiii f.; sons of, lxxxii, lxxxiii f.
- Asher, lxxxix, civ, cvi, cvii, 27 f., 29, 143, 197 f.
- 'Ashera, cvii, 195 ff.
- Ashkelon, lxxiii f., xc, xcii, 19, 282, 366.
- 'Ashtar-Chemosh, 30, 59, 244, 248.
- 'Ashtart, 'Ashtarts, xxxv, cxxi, 58 f., 332, 402, 407.
- 'Ashtoreth. See "'Ashtart.'
- Asiatic refugees in Egypt, 439.
- Ašira, 196.
- Aširtu, Ašratu, 196.
- 'Aškālān, 19, 282.
- Ass, 124, 292.
- Aššur, lxii.
- Assyria, Assyrians, lxvi, lxviii, lxix, lxx, lxxix, xcv, xcvi, xcix, c f.; chronology, liii; Biblical names in Annals of, 99.

- Ašurbanipal, 285, 400.
 Ašur-dân I., ci.
 Ašur-uballiš, lxx, lxxix.
 Athena, 332.
 'Athtar, 59, 261.
 Aṭirat, 196.
 Atlantic, 400.
 'Attar, 59.
 Attila, 285.
 Avaris, lxx f.
 Awan, lv.
 Ay, lxxxvii, lxxxviii.
 Aziru, lxxiii, lxxvi, lxxviii, lxxxvii.

 Ba'al, Ba'als, xxxv, cxx, cxxi, 57 f.
 Ba'al a title of Yahweh, 201.
 Ba'al-berith, 266.
 Ba'al-Gad, xcix, 63.
 Ba'al-ḥanan, 202.
 Ba'al-Ḥermon, xcix, 63.
 Ba'al-tamar, 480.
 Ba'al-ya, 202.
 Ba'al-yadha', 201.
 Ba'al-zebul, 5, 385.
 'Babel und Bibel' controversy, 244.
 Babylonia, Babylon, Semites in, lv f., lvii ff.; First Dynasty of, lviii ff., lxi, lxiii, lxiv, lxxxv, 43, 76, 99, 196, 197, 243 ff.; Second Dynasty of, lviii, lxiv; Third Dynasty of, lviii, lxxv, lxxxii, ci (see also 'Kaššites'); struggle with Assyria, c f.; names of kings of First Dynasty, lviii f.; chronology, lvi, lviii, cxvi; language (Semitic) in inscriptions of early rulers of Akkad, lvii; prevalence and persistency of Semitic Bab. language in Babylonia, lx; influence of language upon Hebrew, lxii f.; influence of civilization of, upon Cana'an, lxiv; theory of origin of alphabet from linear script of, 262; rhythm of poetry of, 97.
 Badyra, Bod'el, xcvi.
 Bai-ti-tu-pa-ira, 12.
 Balak, 299, 316.
 Bányás, 63, 427.
 Barak, xxxvi, cii, 78 ff., 85, 87.
 Barbarossa, 285.
 Bar-Gus, cii.
 Barley-bread, 119.
 Bar-rekub, inscriptions of, 173 f., 254, 264.
 Bar-šur, 264.
 Baš'annim, 82, 90.
 Bashan, 306.
 Bayawa, lxxviii.
 Be'er, 276.
 Be'er-sheba', cx, 43, 251.
 Bees in carcase of lion, 359, 405.
 Be'shtērā, 58.
 Belial, xl, 467 f.
 Bēlit-UR.MAḤ.MEŠ, lxxvii.
 el-Belkā, 306.
 Benaiah, 403.
 B'nê-Ḥanor, 269 f., 271, 280.
 Ben-Hadad II., liii, cii.
 Ben-Hadad III., cii.
 Benjamin, 20, 21, 133 f.; smallness of tribe of, 447.
 Berossus, lv.
 Bēsān, 23, 219.
 Beššūm, 82, 90.
 Bēt-Degān, 384, 385.
 Bēt-Ḡibrin, 8.
 Beth-'anath, xc, cvii, 30.
 Beth-Arbel, 43.
 Beth-barah, 225.
 Beth-Dagon, 384.
 Bethel, xx, cviii, 21, 37, 441, 447, 448, 453, 476, 477, 479, 488.
 Beth-ḥoron, cviii.
 Bethlehem, of Zebulon, 290, 334; of Judah, 422.
 Beth-millo, 271 f.
 Beth-reḥob, 29, 428, 434.
 Beth-she'an, xciii, 23, 24, 219, 220, 222, 223, 490.
 Beth-shemesh (in the north?), cvii, 30; (in the south), cvii, 10, 340, 392, 406, 430.
 Beth-shiṭṭah, 219.
 Bethuel, lxxx.
 Bētin, 21.
 Bēt-Laḥm, 290, 334, 422.
 Bezek, 4.
 Bezkeh, Ḥirbet, 5.
 Biblical sites, identification of, 499 ff.
 Bilhah-tribes, cvii, cx.
 Bireh, 276, 479.
 Biridašwa, lxxxiv, lxxxvi.
 Biridiya, lxxvii, lxxxii, lxxxiv, lxxxvi.
 Bir-idri, liii, cii.
 Bit-Daganna, 385.
 'Blessing of Ja'cob,' cvi, 437.
 'Blessing of Moses,' 4, 438.
 Blood-feud, 199.
 Bochim, 37.

- Boghaz Keui, documents from, lxi, lxxi, lxxii, lxxvi, lxxx, lxxxiv, lxxxvi, xci, xcix, 41, 84, 254.
 'Book of the Wars of Yahweh,' xl, 106.
 Boundary-stones, 71.
Brand-Fuchs, 394.
Brant-fox, 394.
 Buckthorn, 275.
 el-Bukā', xcix, c, 62, 434.
 Bull of Anu, 397, 496; human-headed, 400.
 Burnaburiaš, lxx.
 Burnt offering, 477.
 Caesura, in Hebrew poetry, 160; in Babylonian, 161.
 Cain, 14.
 Caleb, Calibbites, xl, 8, 9, 10, 12 f., 46, 341.
 Cana'an, earliest settlement of Semites in, lv f.; neolithic inhabitants of, lvii; language of, lxi; influence of Babylonian civilization upon, lxi ff.; events leading to invasion and conquest of, by Egypt, lxxv ff.; at period of T.A. Letters, lxxiii ff.; non-Semitic element in, lxxiii ff.; settlement of Philistines in, xcii ff.; decline of Egyptian authority in, xciv ff.; period of freedom in, from external interference of any great power, xcvi ff.; Israel's settlement in, xxxiv f., lxxiv, lxxx f., ciii ff., 1 ff.; partition of, 3; 'seven nations' of, 63; kings of, lxx, lxxiv, 144; king of, 84, 145.
 Cana'anite, Cana'anites, lviii, lxxiii, 3, 30, 41, 297.
 Cana'anite 'glosses' in T.A. Letters, lxi, 99, 166, 167, 168, 169.
 Canon, Hebrew, xxxiv, cxxi.
 Caphtor. See 'Kaphthor.'
 Carchemish, lxxix, lxxxii, xcix, ci, cii; bas-reliefs from, 401, 497.
 Caria, Carians, xciv f.
 Carmel, in Judah, 16; Mount, xciii, 28.
 Carseoli, 393.
 Cassites. See 'Kaššites.'
 Ceres, Festival of, 369, 393.
 Chaboras, 66.
 Chariots, 20, 151.
 Chedorla'omer, lxii.
 Chemosh, 299, 314 ff., 320.
 Chemoshkān, 315.
 Chemoshnadab, 316.
 Chemoshšedek, 316.
 Chemoshy'hi, 316.
 Chesalon, 430.
 Chronology, of Judges, 1 ff.; Biblical, from Abraham to entry into Cana'an, cxii, cxv ff.; early Babylonian, lvi, lviii, cxvi.
 Cilicians, xc.
 Circumcision, 356.
 Clay tablets, use of, in Cana'an, lxxix f., 253.
 Cochineal, 291.
 Coleridge's *Christabel*, rhythm of, 96.
 Commagene, xcix.
 Concubinage, 265.
 'Congregation' of Israel, 446.
 Corn, rust in, 393 f.; harvest in Syria and in Italy, 394.
 Cosmology of Gilgamesh-epic, 399 f.
 Covenant, 60; Book of the, 252, 329 f.
 'Crag, the,' 34.
 Creation-epic, Babylonian, lxiii, 161.
 Crete, Cretans, xciv f.
 Cross-buttock, 370.
 Crypt, 286.
 Cubit, 70.
 Cuneiform script, in Syria and Cana'an, lxiv, lxxix, 253 ff.; in Asia Minor, lxxix.
 Cup-marks, 192.
 Cushan-rish'athaim, 64 ff.
 Cybele, 85.
 Cyprus, xcvi; Cypriote script, 263.
 Daberath, 81.
 Dādi-kariba, 291.
 Dagan, lxii, 244, 385 f.
 Dagan-takala, lxxvii, lxxix.
 Dagon, 384 ff.
 Dagun, 385.
Dalil-(ilu)-Ištar, Dilil-(ilu)-Ištar, 407.
 ed-Dāmiyyeh, 219 f., 221, 223 f., 231, 326.
 Dan, Danites, xx, xcix, cvi f., 31, 142 f., 339, 340, 341, 392, 411, 417, 436.
 Danauna, xciii, xciv.
 Danonim, xciv.
 Daphne, 427.
 Dapur, xc.
 Dardaniāns, xc.
 Daroma, cviii.
 David, xx, xciv, 68, 403; name, 291; northern limit of kingdom of, xcix f.

Death of Samson, 408.
 Debir, conquest of, 8; site of, 10 f.
 Deborah, xxxvi, xxxvii, cii, cvi, cvii, 78 ff., 85; Song of, xl, ciii, cxx, 29, 47, 78, 417; compared with Prose-narrative, 78 ff.; literature on, xiv, 94 f.; metrical form of, 96 ff., 158 ff.; strophic arrangement of, 101 f.; corrupt condition of text of, 102; translation of, 103 ff.; discussion of, 105 ff.; ascription of authorship to prophetess, 116; climactic parallelism of, 169 f.; language of, 171 ff.
 Debûriyyeh, 81, 88.
 Delilah, 377, 407.
 Delos, 406.
 Delphi, xviii, 85.
 Demeter, xvii ff., 85, 334.
 'Deploy,' 87.
 ed-Dêr, 489 f.
 Descent, through father, 264; through mother, 265.
 Deuteronomic editor (R^D), in Joshua', xliii ff., cv, 1; in Kings, xlv.
 Deuteronomic hand, (D²) in Judges, xlix, 55, 61.
 Deuteronomic school, xli, xliii ff.
 Deuteronomy (D), origin and promulgation of, xlv f.
 Dibon, Dîbân, 313.
 Disarmament of Israelites, 119.
 Dodo, Dodai, etc., 289, 291 f.
 Dor, xcv, xcvi, 23 f., 384.
 Drinking, different methods of, xiv f., 210 ff.
 Drone-fly, 359.
 Dudhâlia, lxii.
 Dûdu, cxiii, 291.
 Ea, 30.
 Ea-Oannes, 386.
 Ear-rings, 235.
 East, children of the, 68, 185.
 'Ebal, Mount, 269.
 Edom, Edomites, cx, 33, 34, 109, 110, 311, 341.
 'Eglon, 67 ff., 297.
 Egypt, domination of, by Hyksos, lxx, cxii; expulsion of Hyksos from, lxvi, cxv, cxvi; invasion and conquest of Palestine and Syria by kings of the Eighteenth dynasty of, lxvii ff.; correspondence discovered at Tell el-Amarna in, lxix; relations of, with Mitanni,

lxviii, lxix; intrigues of Hittites against, lxxi f., lxxxvii; relations of the Amorites Abd-Aširta and Aziru with, lxxiii, lxxx; Ḥabiru and SA. GAZ undermine authority of, in Canaan and Syria, lxxiii ff.; loss of hold on Asiatic dominions by later kings of Eighteenth dynasty, lxxxvii f.; restoration of Asiatic empire by kings of Nineteenth dynasty, lxxxviii ff.; collision of, with Philistines and other sea-peoples, xcii f.; Exodus of Israelites from, liii, civ, cv, cvi; loss of Asiatic empire by kings of Twentieth dynasty of, xcv ff.; connexion of Joseph-tribes with, cviii f.; influx of Semites into, during Empire-period, cxiii f.
 Egyptian, Semitic names in, lxviii, xc, cxiv; hieratic character, theory of origin of alphabet from, 261 f.
 Ehud, xxxvi, xxxvii, cii, 67 ff.
 'Ekron, 19.
 Elam, Elamites, lxi, lxii, lxxxi, ci.
 Elders surviving Joshua', xxxv, xxxviii, li, 56.
 Ele'azar, 478.
 Elephantine, Jewish garrison at, 30.
 Eleutheropolis, cviii, 8.
 'Eli, xxxvi, xlix, lii, 415; family of, lii, 478.
 Elisha's fountain, 15.
 Elohîm, preference of E narrative for use of, xxxviii, 178. See also 'God,' and Index of Hebrew terms, s.v.
 Elohist document. See 'Ephraimitic document.'
 Elon, Elonites, ciii, 289 f., 334.
 Emmaus, 464.
 Emutbal, lxi.
 'En-gedi, 16.
 Engidu, 107, 358, 395, 397, 398, 399, 400, 401, 407, 496, 497, 498.
 'Ēn-ḥaḡ-ḡōrē, 375, 406.
 Eriel, cii.
 Enlil, lv, 30, 385.
 Enlil-kudur-ušur, ci.
 Ephah, 192.
 Ephod, lii, 3, 236 ff., 409, 415.
 Ephraim, cvii, 25, 132, 222, 226, 327.
 Ephraimitic document (E), xxxvii ff., xlii ff., cxxi, 3, 46, 52 ff., 67 f., 83, 177, 178, 179, 180, 181, 182, 183, 184, 186, 235, 241, 268, 289, 294, 303, 316, 415 f., 440, 445, 457.

- 'Ephron, 293.
 Erech, lv, 397, 398, 400.
 Ereskigal, xix, 257.
 Eridu, lxii.
 Erihâ, 15, 501.
 'Ermâ, 431.
 Esagila, lxiv.
 Esdraelon, 203.
 Esh-ba'al, 201.
 Eshmun'azar, Sarcophagus-inscription of, cxiii, 153, 387.
 Eshta'ol, 339, 340, 353, 416.
 Ešûa', 340, 353.
 'Etam, 370.
 Euphrates, 66.
 Eurytheus, 408.
 Evil spirit sent by God, 276 f.
 Exodus, the. See 'Israel.'
- Far'ah, 187. See also 'Wâdy Far'ah.'
 Fârân, Gebel, 109.
 Far'atâ, 187, 335.
 Fig, 273.
 Fire, supernatural, 192.
 First-born, sacrifice of, 329 f.
 Flamen Quirinalis, 394.
 Flavia Neapolis, 269.
 Flood-narrative, xl, 396, 399, 403.
 Fortuna, temple of, 238.
 Foundation-sacrifice, 331.
 Four, as divine title, 9, 43 f.
 Foxes, 368; Samson's, 393 f.
- Ga'al, 267, 278.
 Ga'ash, Mount, 57.
 Gad, cvii, 142, 197, 306.
 Gades, 408.
 Galilee, 30; Sea of, cviii.
 Gâlûd, Mount, 207 ff.
 Ġaza, Ġazzeħ, 19, 185, 375 f.
 Ge, xix.
 Geba', Ġeba', xxi, 464, 480 f., 486.
 Gebal, xcvi. See also 'Rib-Adda.'
 Gebalites, xcix, 63.
Gemini, 399.
 Gera, 69.
 Gerizim, Mount, 269, 272.
 Gershom, xx, 415, 416, 422.
 Geshur, 10.
 Gezer, lxxiii f., xcii, xciv, xcvi, 25 f.; agricultural calendar from, 253, 261.
 el-Gib, 479.
 Gib'eah, xxi, xxxvii, ciii, 442 f., 464 ff., 479, 481, 486.
 Gib'e'on, 464, 465, 479.
 Gide'on, xxxvi, xxxvii, cii, ciii, 176 ff.
 Ġifnâ, 464.
 Ġil'ad, Ġebel, 307.
 Gilboa', Mount, 205, 206, 208.
 Gil'e'ad, cv, 142, 207 f., 306 f., 318, 472.
 Gilgal, xxxiv, cv, 2, 36 f.
 Gilgameš, 358, 379, 391, 395 ff., 495, 496, 497, 498; Epic of, 97, 107, 161, 242, 380, 395-407, 496, 497.
 Gilu-Ĥipa, lxxii, lxxxvi.
 God, moral government of, cxxi; not to be seen by human eyes, 193; inciting men to their own ruin, 276 f.; ('*elôhim*') as title of supernatural being, 36, 346, 350; as title of judges, 117. See also 'Yahweh.'
 Golden bull, 440 f.
 Gophna, 464.
 Goshen, cix, 439.
 Graven image, 409, 415, 419.
 Greek alphabet. See 'Alphabet.'
 Grinding, possible significance of Samson's, 408.
- Ĥabiraeon (*Ĥabirâ*), lxxxi, lxxxiii.
 Ĥabiru, identity of, lxxiii ff.; identification of, with Hebrews, lxxiv, lxxx f., lxxxiii, cxi.; philological equivalence of name, with '*ihkrî*', lxxiv f.; connexion of, with SA.GAZ, lxxv ff.; 'Ĥabiru-gods,' lxxvi, lxxvii; addition of KI to name, lxxviii, lxxxiii; aggressions of, in Cana'an, lxxiii, lxxvii, lxxx f., lxxxii, civ, cxi, cxvi ff.; connexion of, with Sûtû, lxxix; Aramaean nomads, lxxx; early mention of, in Babylonia, lxxxi, cx; called Šasu by the Egyptians, lxxxviii; proposed identification of, with Kaššites, lxxx f.; proposed identification of, with Hittites, lxxxii f.; literature dealing with, lxxxiii.
- Ĥabor, 66.
 Hadad-Rimmon, mourning of, 333.
 el-Ĥadi'reh, 84.
 Hair, worn long, 107 f.; -offering, 343; of Samson and of Gilgameš, 404, 495, 496, 498.
 Hamath, cii, 63; Entry of, xcix f., 63.
 Hammurabi, lviii, lxi, lxii, lxiv, lxxxii, lxxxiii, lxxxv, cx, cxv, 42, 196, 197, 330, 385; Code of, lxii, lxiii, 329, 385.
 Ĥamor. See 'Benê-Ĥamor.'

Ḥana, Ḥani (king lom), lxiii, lxiv, lxxxv.
 Handmaid-tribes, cvi f., cviii, 392.
 Ḥani (deity), lxiii f.
 Haran, Ḥarran, ci, cx, cxv, 249, 250.
 Ḥarbišihu, lxxxi.
 Ḥaremḥeb, lxxxviii, cxii, 439.
 Har-ḥereš, 32.
 el-Ḥarīṭiyyeh, 78, 84.
 Ḥarod, spring of, 205.
 Harosheth, 78, 84.
Ḥarri, lvii, lxxxiv.
 Ḥaru, lvii, lxxxviii, xcii.
 Ḥašor, cxvii, 78, 84.
 Ḥaṭhor, 197, 261.
 Ḥatšepsut, lxvii.
 Ḥatti (city), lxix, lxxi.
 Ḥattušili I., lxix.
 Ḥattušili II., lxxix, lxxxvi, lxxxviii, xci, 84.
 Ḥaurân, lxxxviii, xci, 231.
 Ḥavvoth-Ja'ir, 289, 293.
 el-Ḥawânit, Ḥirbet, 465.
 Ḥayân, 174. See also 'Hyân.'
 'Heart,' as seat of intellect, 125, 274, 382.
 Hebrew language, origin and connexions of, lxi; influence of Babylonian on, lxii f.; words elucidated from other Semitic languages, 171; original pronunciation of, 99, 159; alphabet. See 'Alphabet.'
 Hebrew manuscripts, early, abbreviation in, 124, 149, 466; transposition in copying, cxxiii, 124, 210, 417; marginal glosses and doublets incorporated into the text of, cxxiii f., 113, 130, 232; confusion of letters in, cxxiii, 123, 149, 225, 348; ditto-graphy in, cxxiii, 225, 423.
 Hebrew poetry, rhythm of, 96 ff., 158 ff., 272 f., 365, 366, 372, 388; rhyme in, 388 f.; Climactic parallelism in, 169 f.
 Hebrews, identification of, with Ḥabiru, lxxiv, lxxx f., lxxxiii, cxi; movements of, westward, cii, cix f.; supposed identity of 'Apuriu' (*Apriu*) with, cxiv. See also 'Israel.'
 Ḥebbron, site, 9; elevation of, 7, 11; Hittites at, lxxxv f.; conquest of, by Judah (Caleb), cv, 8; in Samson-narrative, 377.
 Ḥelbah, 28.
 Heliopolis, 32.

Hera, 408.
 Herakles compared with Samson, 335, 358, 375, 391, 402, 403, 406, 408; Herakles-Melkart, 497.
 Hermon, 428; Little, 206.
 Ḥeshbon, Ḥesbân, 306, 312.
 Ḥešrum, 320.
 'Hexameter,' term applied to Hebrew poetry by Josephus, 98.
 Hexateuch, xxxviii, xxxix, xl, xli, xlix.
 Ḥipa, Ḥepa, lxxxvi.
 Hittites, invasion of Babylonia by, lxiv, lxxxiv; Anatolian origin of, lxiv, lxxi; oldest references to, lxiv; racial connexions of, lxxi; language of, lxxi; foundation of empire of, lxxii; excavation of capital city of, lxxi; movements of, in Syria, lxxi f., lxxxvii ff.; relations of, with Egypt, lxxviii, lxxxix ff.; relations of, with Mitanni, lxxii, lxxxvii; fall of empire of, xcix; a racial element in Syria-Palestine, lxxxiii ff.; one of 'the seven races' of Cana'an, lxxxv f., 63; connexion of Jebušites with, lxxxvi f.; at Hebron, lxxxv f.; proposed connexion of Ḥabiru with, lxxxii f.; principalities of, in Syria, xcix f., ci, 23; southern frontier of, in Syria, xcix f., 23, 62 f.; relations of, with Aramaeans, ci f.; allusions to, in Judges, 23, 62, 63; in the Lebanon, xiii, 62 f.; Hittite names in Judges, 76, 84, 113; Gilgameš pictured by, 401, 497; literature dealing with, lxxi f.
 Hivvites, 6, 62, 293.
 Ḥizmeḥ, 481.
 Ḥobab, 14 f.
 Ḥomš, xcix, c.
 Horeb. See 'Sinai.'
Ḥorim, lvii.
 Ḥormah, 18, 44, 45.
 Horse, Sumerian name for, lxv; introduced into Babylonia by Kašsites, lxv; introduced into Egypt by Hyksos, lxvi; in ancient warfare, 151; gallop of, reproduced in rhythm, 151.
 Hosea', religious standpoint and influence of, xlv, 184, 242.
 Ḥriḥor, xcvi, 23.
 Ḥûleh, Lake, 78.
 Ḥumbaba, 380, 395, 400.

- Hunusa, 285.
 Husham, 65.
 Hyân, lxxv, lxxvi.
 Hyksos, domination of Egypt by, lxxv;
 meaning of name, lxxv; racial charac-
 ter of, lxxv f.; expulsion of, from
 Egypt, lxxvi; royal names of, lxxvi;
 chronology of, lxxvi f.; supposed con-
 nexion of Israel in Egypt with, cxii,
 cxv, cxvi.
 Ibleâm, 23.
 Ibšan, cxiii, 289 f., 334.
 Ibzîk, Hîrbet, 5.
 Idin-Dagan, 385.
 Idomeneus, 319.
 Iezer, 134.
 Ilu-bi'di, cii, 245.
 Indra, lxxxiv.
 Iphigenia, 332.
 Irhulêni, cii.
 Isaac, lxxx, cx; story of Abraham's
 projected sacrifice of, 330.
 Ish-ba'al, 201.
 Israel, migration of ancestors of, to
 Cana'an, cix ff.; settlement of tribes in
 Cana'an, lxxiv, lxxx f., cv ff., i ff.,
 44 ff., 47 ff., 439 f.; name displaces
 earlier name Ja'cob, cx, cxi; hand-
 maid-tribes of, cvi f., cviii, 392;
 tribes of, personified as individuals,
 cix; entry of tribes into Egypt,
 cxi ff.; duration of sojourn of tribes
 of, in Egypt, cxii; Exodus of, from
 Egypt, xl, l, li, liii, civ, cv, cvi, cviii,
 cxv, cxvi, cxviii, 439; wilderness-
 wanderings of, l f., cix, 439 f.; exter-
 nal allusions to tribes of, cxii f., cx f.,
 cxv; mention of, by Mineptah, xcii,
 civ, cv, cxi, cxviii; influence of Baby-
 lonian civilization upon, lxiv; con-
 ception of tribes as political unity in
 early times, xxxvi, l, cvi, 235, 267,
 446, 453; ideal northern limit of
 kingdom of, xcix f.; Divine Inspira-
 tion guiding religious evolution of,
 cxix. See also 'Hebrews,' and
 names of separate tribes.
 Išme-Dagan, 385.
 Issachar, cviii, 136, 289 f.
 Ištâr, 58 f., 396, 397, 399, 402, 405,
 407.
 Itakama, lxxii.
 Ithamar, 478.
 Jabbok, 305, 306, 314.
 Jabesh of Gile'ad, 447, 489 f.
 Jabin, cxvii, 78, 80 f., 84.
 Ja'cob, lxxx, cx f.
 Ja'cob-el (personal name), lxxvi, cxiii,
 cxv; (place-name), lxxviii, civ, cxi.
 Ja'el, 79 f., 92 f., 113.
 Jahas, 313.
 Ja'ir, cxiii, 51, 135, 289 f., 292 f.
 James the Just, St., 343.
 Ja'zer, 305 f., 314.
 Jebuš, 7, 463.
 Jebusites, lxxxvi f., 7, 20, 21.
 Jehoshaphat, xxxviii.
 Jehovistic document. See 'Judaean
 document.'
 Jephthah, xxxvi, xxxvii, xlix, cii, 226,
 293, 295, 298 ff.; daughter of, 321 ff.,
 332 ff.
 Jeraħme'el, Jeraħme'elites, cviii, 9, 12,
 45, 136, 252; meaning of name, 252.
 Jeremiah, xliii.
 Jericho, xxxiv, cv, cviii, 3, 15, 69.
 Jerobo'am I., liii, 4.
 Jerobo'am II., xxxvii, xcix, 4.
 Jerubba'al, 178, 201 f., 264.
 Jerusalem, in time of T.A. Letters,
 lxxiii, lxxviii, cxvii; antiquity of
 name, 463; racial character of Jebu-
 site inhabitants, lxxxvi f.; capture of,
 6 f.; elevation of, 7; Temple at, xx.
 Jethro, 14 f., 251 f.
 Jezre'el, 202, 387; Vale of, 202 f.
 Jogbehah, 231.
 John the Baptist, St., 343.
 Jonathan the priest, 415, 422, 434.
 Jordon, fords of, 75, 225, 327.
 Jošeph, story of, cix, cxiii; Jošeph-
 tribes, cviii f., cxviii, 21, 49 f., 392,
 439 f.; in Egypt, cviii ff.
 Jošeph-el?, lxxviii, civ, cxv.
 Joshua', xxxv, xxxviii, li, lxxiv, civ ff.,
 cxvi ff., 1, 2, 22, 56, 438; Farewell-
 address of, xlii f., xlv.
 Jotham's parable, 272 ff.
 Judaean document (J), xxxviii ff., cv,
 cvi, cvii, cviii, 1, 46, 47 ff., 55, 67 f.,
 83, 176, 177, 178, 180, 181, 182, 183,
 184, 235, 268, 303, 316, 336 f., 415 f.,
 440, 443 ff., 454, 455 ff., 458.
 Judah, cviii f., 45 ff.; northern bound-
 ary of, 430; southern boundary of,
 33 ff., Wilderness of, 15 f.
 Judges, Book of, title, xxxiii; period

- covered by, xxxiii, cxx, place of, in Hebrew Canon, xxxiv, cxi; structure of, xxxiv ff.; first introduction to (R^P), xxxiv f., 1 ff.; second introduction to (R^E 2), xxxv, xxxvii, xxxviii f., 52 ff.; appendix to, xxxvii; religious pragmatism of, xxxv f., cxi, 54; J & E in, xxxvii ff.; continuation of in 1 Sam., xxxviii; editors of, xli ff. (see also 'Redactors of Judges'); date of redaction of, 1; chronology of, 1 ff., civ, cxviii; permanent religious value of, cxviii ff.; Hebrew Text of, cxii ff.; Versions of, cxiv ff.
- Judges of Israel, place of, in history, xxxiii f.; raised up by Yahweh, xxxv; local character of influence of, xxxvi, liii f.; historical character of, cii f.; achievements of, wrought by divine strength, cxii; meaning and use of Hebrew term 'Judge,' xxxiii, 59, 66, 85.
- Kadašman-Enlil II., lxxix.
- Kadašman-Ḥarbe I., lxxix.
- Ḳadesh on the Orontes, lxvii, lxviii, lxxii, lxxxix, xc, xcv, xcix, c, 23, 63.
- Ḳadesh-Barnea', xl, cv, cviii, cix, 18, 34, 44, 68, 110, 311, 439 f.
- Ḳadiš, 82.
- Kalumu, Inscription of, lxvi, xcv, 174, 254.
- Ḳamm, 293.
- Kammusunadbi, 316.
- Ḳamon, 293.
- Kamušu-šar-ušur, 316.
- Kaphtor, xciii f.
- Kara-indaš I., lxxxii.
- Karduniaš, lxix, lxxix, lxxx, lxxxii.
- Ḳârî, xcv.
- Ḳarḳar, battle of, liii, cii, 230.
- Ḳarḳor, 230.
- Ḳarn Šarṭabeh, 220, 222, 224.
- Karnak, lxvii, xci, xcix.
- Kashsha-rishat, 64.
- Kaši, lxxxii.
- Kaššites (Cassites), lxv, lxvi, lxxix, lxxx ff., lxxxv, c, 64, 244.
- Kaššu, lxxx, lxxxii.
- Kataonians, xc.
- Katna, xci.
- Ḳaṭṭath, 27.
- Ḳedesh of Issachar, 82.
- Ḳedesh of Naphtali, 78, 80 ff., 89.
- Ḳefr Ḥâris, 57.
- Ḳefr Išûa', 56.
- Ḳeftiu, Ḳeftians, xciv.
- Ḳé'ilah, lxxxiv.
- Ḳenaz, Ḳenizzites, 12 f.
- Ḳenites, cviii, cix, 14, 45, 251 f.
- Ḳerêthî, xciv.
- Keslâ, 430.
- Ḳêtlînîth, Ḳêtônîth, 27.
- Ḳeṭurah, cix, 184.
- Key, 74.
- Kinahḫi, 41.
- Kinship, 265, 267, 270 f.
- Kinza, Kidša, lxxii.
- Ḳiriath-arba', conquest of, 8; meaning of name, 9, 43 f.
- Ḳiriath-jé'arim, 341, 430, 431.
- Ḳiriath-sepher, 11 f.
- Kiš, lv.
- Ki-šavaš, 10.
- Ḳishon, 78, 79, 88, 147, 500.
- Ḳiṭron, 27.
- Knossos, excavations at, xciv, 263.
- Ḳoa', lxxix.
- Kore, worship of, xvii ff., 332, 334.
- Kudur-Mabuk, lxi, lxxxii.
- Kudurra, lxxxii, lxxxiii.
- Kumanî, ci.
- Ḳumém, 293.
- Kummuḫ, xcix.
- el-Ḳurnul, 16.
- Ḳuryet el-Enab, el-Ḳuryeh, 430.
- Kuš, 64.
- Kuššar, lxxii.
- Ḳuteineh, Ḥirbet, 27.
- Ḳutû, lxxix.
- Laban, lxxx, cx, cxi, 416.
- Labaya, lxxvii, lxxxiv; sons of, lxxiii, lxxxii, lxxxiii.
- Lachish, cxvii, 501; cuneiform tablet from, 253; signs on potsherds from, 261.
- Lagamal, lxii.
- Laish, 412, 413, 427, 428.
- Laodicea, sacrifice at, 332.
- Lappidoth, 85.
- Larsa, lxi, lxii, lxxxii, lxxxiii.
- Le'ah-tribes, cx.
- Leather as writing-material. See 'Skin.'
- Lebanon, Lebanons, xiii, lxviii, lxxii, lxxx, lxxxiv, lxxxvii, lxxxix, xc,

- xcvi, xcix f., ci, cv, 62 f., 428; as 'twin-mountain' (Māšû), 400; inscription from, 254.
 Left-handed, 69 f., 476.
 'Leg upon thigh,' 369 f., 496.
 Lehi, 371, 406.
 Leo, 401, 405.
 Lēshām, 427.
 Levi, Levite, Levites, cix, 269, 409, 416, 459; origin of, 436 ff.
 Libyans, xcii, xcv.
 Liftā, xx, 430, 500.
 Lihhyān, 10.
 Lion, slain by Samson, xix, 357 f., 405; slain by Gilgameš, 401, 495, 496, 497, 498; associated with Nergal, 405.
 'Lip' as a topographical term, 220 f.
 Loins, 264.
 Loom, 381 f.
 Loṭ, cx.
 Lugal-banda, 397.
 Luka. See 'Lycians.'
 Lunar worship, among early Hebrews, cx. See also 'Moon-god' and 'Yahweh.'
 Luz, 23.
 Lycia, Lycians, xc, xcii, xciv.
- Ma'achah, Ma'achathites, 135, 428.
 Ma'ān, 298.
 Machir, cvi, 134 f.
 Maḥalliba, 28.
 Maḥaneh-Dan, 353, 431.
 Maher-shalal-ḥash-baz, 260.
 Mahrûl, 27.
 el-Mahrûk (Makhrûd), 222, 224.
 el-Maḡrah, Gubel, 110.
 Malkatu, 250.
 Malki-šedek (Melchizedek), lxxxvii.
 Ma'lûl, 27.
 Manahtites, 341.
 Manasseh, cv f., 24, 50, 134 f., 222, 318; substitution of, for Moses, 434 f.
 Manetho, lxxv, lxvi.
 Manoah, 341.
 Manôthû, 10.
 Manyā, lxxxiv.
 Ma'on, 16.
 Ma'onites, 298.
 Maps of Palestine, 498 ff.
 Marduk, lxiv.
 Marmitā, Ḥirbet, 371.
- Marriage-customs, 265, 354 f., 356, 360 f., 365.
 Maš, 400.
 Mašawaša, xcv.
 Maššah, 438.
 Massoretic Text, vocalization of, 159.
 Māšu, 395, 399 f., 497.
 Mattiuaza, lxxxiv, lxxxvii.
 Meal-offering, 349.
 Mediterranean, 400; Mediterranean origin of alphabet, theory of, 263.
 Megiddo, lxvii, lxxviii, lxxxiv, 23, 78, 82, 145, 203, 500; alphabetic letters from, 261.
 Melkart, 358, 391, 401, 402, 406, 497.
 Mēni, 10.
 Merg 'Ayyûn, xcix.
 Merg ibn 'Āmir, 202, 204.
 Meribah, 110, 438.
 Merib-ba'al, 201.
 Merom, 78.
 Meroz, 151.
 Meryamin, 489 f.
 Mesha', lxi, 18. See also 'Moabite Stone.'
 Meshech, xcix.
 Mesopotamia, 66.
 Micah, xx, xxxvii, xlix, cii, ciii, cvii, 240, 408 ff.
 Micayehu, 417.
 Midian, cix, 110, 184, 297.
 Mikmash=Muḡmās, xiii.
 Milcah, 250.
 Milcom, 299.
 el-Milh, 16.
 Milkili, lxxiii, lxxvii, lxxxii.
 Mill, millstone, 288.
 Millo, 271 f.
 Minaean language, lix; inscriptions, 437, 441.
 Mineptah, liii, xci f., civ, cv, cxi, cxii, cxviii, 26, 439.
 Minnith, 320.
 Minoans, xciv; Minoan script, 263.
 Minor Judges, the, xxxvi, 289 ff., 334 f.
 Minos, xciv.
 Miriam, 440.
 Mishôr, 306, 307.
 Mišpah, in Gile'ad, cx, 307, 319; in Benjamin, 447, 453, 472, 477, 479, 488; Land of, 62.
 Mitanni, Mitannians, lxviii, lxix, lxx, lxxii, lxxiii, lxxx, lxxxiv f., lxxxvii,

- cii; language of, lxxxv; kingdom of, lxxxv.
- Mitra, lxxxiv.
- Moab, cx, 68, 298 ff.; Moabites spoke Hebrew, lxi.
- Moabite Stone* (inscription of Mesha'), lxi, lxiii, 18, 30, 59, 155, 174, 253, 291, 313, 315, 316.
- Molech, child-sacrifice to, 331.
- Molten image, 409.
- Money, primitive, 145, 378.
- Monolatry, 314 f.
- Moon-god, cvii, 9, 44, 196 f., 249 ff.
- Moreh, 206.
- Mortar, the, 374.
- Moses, name of, cix, 478; connexion of, with Levites, cix, 438 ff.; at Midian, 439; father-in-law of, 15, 251; Theophany made to, 189, 248 f.; leads tribes out of Egypt, cvi, cviii; connexion of, with Joshua', cxvi; religious influence of, cvii, cix, cxx f., 329 f.; as typical intercessor, xliii; Blessing of, 4, 438; descendant of, 415, 416, 434 f.
- Muġāret el-Ga'y, xxi.
- Muraşşas, 151.
- Muršili, lxxxix, xci, 84.
- Mûsâ, Ġebel, 110.
- Muškaya, xcix.
- Must, 274.
- Muwattalli, lxxxix, xc, xci.
- Mylitta, 59, 198.
- Mysians, xc.
- Nabaŋaeans, 54.
- Nāblus, 269.
- Nabonidus, lvi, 249.
- Nahalol, 27.
- Naharîn, lxxvii, lxxviii, lxxix, lxxii, lxxviii, lxxxv, lxxxix, xci, 66.
- Naḥor, lxxx.
- Nahr el-'Auġa, 24.
- Nahr Ġâlûd, 206.
- Nahr el-Kelb, lxxxix.
- Nahr el-Muġaţţâ', 145, 500.
- Namryma, Narima, lxxviii, 66.
- Namyawaza, lxxvii, lxxix, lxxxiv.
- Nāphath (Nāphôth) Dor, 24.
- Naphtali, cvii, 29, 79, 81, 137.
- Narâm-Sin, lvi.
- Nāsatya-twins, lxxxiv.
- 'Navel' as a topographical term, 283.
- Nazirite, 337, 338, 342 ff., 404.
- Neby Dahy, Ġebel, 206.
- Neby Samwil, 472, 479.
- Nebuchadnezzar, xvi.
- Necromancy, 421.
- Nefertiti, lxxii.
- Negeb, cviii, 7, 16, 439; conquest of, xl, cv, 44 ff.
- Nemaeon lion, 358, 403.
- Neolithic inhabitants of Palestine, lvii.
- Nephtali, xx, 430, 500.
- Nergal, 405.
- Nerigal and Ereškigal, story of, 257.
- Nesubenebdu, xcv ff.
- Nicopolis, 464.
- Nimrod, 401.
- Nineveh, lxii.
- Ninib-tukulti-Ašur, lxxxi.
- Nisaba, lxiii.
- Nisin, lv, 385.
- Nob, 441.
- Nobaḥ, 51, 135, 231.
- Nubia, lxxxvii f.
- Number, exaggeration of, 120, 446, 455 f., 458.
- Oath, 418, 489.
- 'Obed, 278.
- Oeta, Mount, 408.
- el-'Olâ, 10, 441.
- Old Testament, religious value of, cxviii ff.
- Olive, 273.
- Onesilus, 359.
- 'Ophrah, 187.
- 'Oreb, 225 f.
- Origen, transliteration of, from Hebrew, 166, 167, 168.
- el-'Ormeh, 282.
- Ortygia, 406.
- 'Othniel, xxxvi, ciii, 12 f., 64 ff.
- Ox-goad, 77.
- Paddan-Aram, lxxx.
- Palms, city of, xxxiv, 15, 69.
- Panammu, inscription of, 173 f., 254.
- Paneas, 63, 427.
- Papyrus, use of, as writing material, xcvii, 255, 258, 259, 260.
- Papyrus Anastasi I., xci.
- Papyrus Golénischeff, xcvi.
- Parallelism, Climactic, 169 ff.
- Paran, 109.
- Partridge, 375.
- Paula, pilgrimage of, 463.

Peace-offerings, 477.

Peg, 93, 152.

Pe-kanan, xcii, 41.

Pe-nhēsi, 239, 478.

Pentameter, term applied to Hebrew poetry by Josephus, 98.

Penuel, 223 f., 228, 233.

Perizzites, 6.

Persephone, xviii, xix, 334.

Persian, old, cuneiform writing of, 262.

Perversion of proper names, 5, 58, 64, 65 f., 228 f., 434.

Petra, 34.

Phaestos disk, xciv.

Philadelphia, 306.

Philistines, invasion of Cana'an by, xcii f.; origin of, xciii f.; connexion of, with Minoans of Crete, xciv; head-dress of, xciv; connexion of, with Lycians and Carians, xciv f.; 'Lords of,' 62; Dagon, deity of, 384 ff.; theory of introduction of alphabetic script to Cana'an by, 263; oppression of Israelites by, lii, liii, 295 ff., 335 f.; Samson's relations with, 335 ff.; un-circumcised, 356.

Phinehas, lii, 325, 478.

Phoenicia, Phoenicians, lxviii, lxxiii, lxxv, lxxviii, lxxxii, lxxxviii, lxxxix, xciii, xcvi ff., 28, 143, 400; inscriptions, lxi, 254.

Pictographic script, 255.

Piers Ploughman, rhythm of, xiv.

Pig, relation of, to Tammuz, xvii f.

Pillars of Hercules, 400, 408.

Piping to flocks, 141.

Pir'athon, 335.

Pithom, civ, cxvi.

Poetry, Hebrew. See 'Hebrew poetry.'

Polydetector, Polydegmon, 334.

Polyxena, 334.

Porta Catularia, 393.

Priestly redactor. See 'Redactors.'

Promontorium album, 28

Prophets, teaching and spiritual appeal of, cxviii f., cxxi; Prophetic schools, xxxiv, xl, xli ff.

Ptolemais, 28.

Pu'ah, 289, 291.

Pudu-Ḥipa, lxxxvi.

Pulasati. See 'Philistines.'

Pulydamas of Scotusa, 358.

Puppies, sacrificed, 393.

Quail, sacred to Herakles, 375, 405.

Ra'amšes (store-city), civ, cxvi.

Rabbah, Rabbath-'Ammon, 306.

Rabbinic exegesis, 73.

Rachel, cx, 416.

Ramah, er-Rām, 86, 465.

Ramath-lehi, 75, 374, 405.

Ra'messe I., lxxxviii.

Ra'messe II., liii, lxxxix ff., civ, cxii, cxiv, cxv, cxvi, cxviii, 27.

Ra'messe III., xcii ff., xcvi.

Ra'messe IX., xcvi.

Ra'messe XII., xc.

Rammôn, xxi, 486.

Ras el-Abiyāḍ, 28.

Ras et-Tawil, Ḥirbet, 465, 472, 479, 481, 486.

Ras 'Umm el-Ḥarrubeh, 222.

Rebekah, lxxx, cx.

Rechabites, 343.

Redactors of Judges:—

RJE, xli, xlix f., 55, 63, 181, 182, 194, 226, 268, 294, 295, 298, 301, 303, 338, 345, 410, 445.

RE², xxxiii, xli ff., 52 ff., 59, 61, 176, 184, 266, 268, 293 f., 295, 298, 338.

RP, I, 1, 2, 55, 76, 263, 268, 290, 304, 339, 410 f., 424, 454, 457, 458.

Reed-pen, 258, 260.

Rehob, 29.

Rehob'ani, liii, xcvi.

Rephidim, li, 68.

er-Restān, xiii, xc, c, cii.

Retenu, Upper, lxvii, xciv.

Re'uben, cviii, 306.

Réuel, 15.

Revelation of Yahweh, progressive, 189.

Revised Version, criticism of renderings of, 25, 75, 86, 90, 106, 108, 116, 117, 123, 139, 147, 148 f., 157, 189, 190, 205, 212, 229 f., 234, 321 *bis*, 325, 347, 348, 350 *bis*, 357, 368, 372, 377, 378, 418, 423, 476, 485, 493; *margin*, 93, 148 f., 205, 207, 390, 480.

Rhyme. See 'Hebrew poetry.'

Rhythm. See 'Hebrew poetry.'

Rib-Adda, lxxiii, lxxv, lxxviii, lxxix, lxxx, lxxxii.

Riblah, c.

Righteous acts of Yahweh, 129.

Rimmon, xxi, 448, 486.

Rimmon, lxi, lxxxi, lxxxiii, cx.

Rimmon, lxxix, Robigus, 393 f.

- Rock-altar. See 'Altar.
 Romulus, 494.
 Roof-chamber, 71.
Rosse, rosser, 373.
Ruḥizzi, lxxxiv.
Ruṣmānya, lxxxiv.
 Rust in corn, 393 f.
- Sabaeen kingdom, 400; language, lix.
 Sabbath, 251.
 Šābians, pseudo-, 421.
 Sabine women, rape of, 494.
 Sacrifice, 191, 477; human, 320, 329 ff.; of firstborn, 329 f.; child-sacrifice to Moloch, 331; foundation-, 331; virgin-, 332 ff.; of red puppies, 393; of pigs, xviii.
 Šadok, 478.
 eš-Šafā, nakb, 17, 33, 35.
 eš-Šāfiyyeh, 35.
 Safrāneh, c.
 Sagalassos, xcii.
 S.A. GAZ (people), lxxv ff., lxxxviii, cxi, cxvii f., 26.
Sagittarius, 399.
 Saida, 28.
 Šakaluša, xcii, xciii.
 Sakere, lxxxvii.
 Salitis, lxxv.
 Šalm, 229.
 Salma, 341.
 Šalmon, Mount, 286.
 Šalmunna', 228.
 Salt, City of, 16; covenant of, 42; symbolical use of, 285.
 Salt Sea, 34.
 Sam'al, cii, 173.
 Samaria, capture of, by Sargon, xlvi; ostraka from, 253, 258.
 Šamaš. See 'Sun-god.'
 Šamšānu, 352.
 Šamši-Adad VII., 385.
 Samson, xxxvi, xxxvii, xl, xlix, lii, liv, cii, 10, 75, 293, 294, 335 ff.; meaning of name, 352, 391; solar-mythological element in story of, xix, 337, 338, 377, 380, 384, 391 ff.
 Samsu-ditana, lxiv.
 Samsu-iluna, lix, lxiv.
 Samuel, judge, xxxvi, xlix; last address of, xlii f., xlv; as typical intercessor, xliii; length of judgeship of, li f.; a Nazirite(?), 343, 344; not a Levite, 441.
- Sangara, 76.
 Saphon, 326.
 Šār, Hīrbet, 305 f., 310, 314.
 Sarah, 250.
 Šar'ah, xix, 340, 349.
 Šardina, Sardis, Sardinia, xcii, xciii.
 Sarēthan, 219 ff.
 Šar-Gani-šarri, lv, lvi.
 Sargon of Akkad, lv f., lx.
 Sargon of Assyria, xlvi, 385.
 Saris, 430.
 Šarpanitum, lxiv.
 Šarratu, 250.
 Šarru-kin, Sarru-ukin. See 'Sargon.'
 Šasu, lxxv, lxxix f., lxxxviii.
 Šattā, 219.
 Saul, lii, lxxix, ciii, 444, 447, 455, 490.
Scorpio, 399.
 Scorpion-men, 395, 399.
 Scribes, Assyrian and West Semitic, 256, 495.
 Sea-country, people of, lxiv.
 Seafaring life adopted by Israelite tribes, 143.
 Seals, Hebrew inscribed, 253.
 Sebaita, xiii, 17.
 Šedad, c.
 Šedek, 41 ff.
 Šeffūriyyeh, 27.
 Šēh Sa'd, xci.
 Seil ed-Dilbeh, 14.
 Se'ir, lvii, cxx, 109; in Judah, 430.
 Se'irah, 74.
 Šela', 34.
 Semites, early movements of, lv ff.; early common home of, lvi.
 Semitic languages, development of, from a common original, lx; influence of environment upon, lx; primitive connexion with Sumerian, lvii.
 Šeneh, 465.
 Šennacherib, Prism-inscription of, 28, 385.
 Šephath, xiii, 17, 45.
 Serabit, inscription from, 261.
 Serbal, Gebel, 111.
 Šerdanu (*amēlu Šerdani*), lxxix, xcii.
 Šerēdah, 219 ff.
 Serpent, relation of, to Earth-goddess, xix.
 Servant of Yahweh, the, 56.
 Sety I., lxxxviii f., civ, cvi, cxviii, 27.
 Seven as divine title, 9, 43 f., 251.
 Seventy, as large round number, 264.

- Sha'albim, 33.
 Shalmanešer III., xcvi, cii, 71, 230.
 'Shameful thing' substituted in text for Ba'al, 5, 58, 202.
 Shamgar, xxxvii, ciii, 75 ff., 113, 290.
 Shamir, 292.
 Shammah, 75, 77.
 Sharon, lxxiv.
 Sharuhen, lxvi.
 Shavsha, 10, 352.
 She'ar-yashub, 260.
 Shechem, xxxv, lxxiii, lxxviii, lxxx, lxxxi, cviii, cix, cxi, 4, 56, 134, 269 f., 437 f.
 Shekel, 236, 378.
 Shephelah, 7 f., 20.
 Shēshai, 9 f., 352.
Shibboleth, 328.
 Shiloh, 37, 415, 435 f., 441, 476, 491, 492.
 Shin'ar, lxii, lxxviii.
 Shisha, 10.
 Shishak, xcvi.
 Shobal, 341.
 Sibitti, 43 f., 251.
 Sicilians, xciii.
 Šidkā, 377.
 Šidon, 28; Šidonians, 297, 422.
 Siduri-Sabitu, 396, 398, 400.
 Šihon, 306, 310, 312 f.
 Šiklag, 68.
 Šilbēl, 377.
 Siloam-inscription, 253.
 Sime'on, lxxv, civ, cviii f., 4, 46, 269, 437 ff.
 Simyra, lxxviii.
 Sin. See 'Moon-god.'
 Sin-muballit, lviii, lxi.
 Šinai, cxx, 68, 109 ff., 112, 251, 311.
 Singar, Ġebel, lxxviii.
 Singara, lxxviii.
 Sinuhe, tale of, 439.
 Šippōri, 27.
 Širah, well of, 501.
 Šišera, lxvii, 78 ff., 34.
 Siweh, 406.
 eš-Šiyyāḡ, 371.
 Skin, use of, as writing material, 255, 259.
 Sobah, c.
 Solomon, date of accession of, liii, cxv; kingdom of, xcix.
 eš-Šōma', Ġirbet, 465.
 Southsayer, 283.
 Šor'ah, xix, 339, 340, 416.
 Sorek, Wādy of, 340, 377.
 'Soul,' as principle of life in man, 390.
 Spirit of Yahweh. See 'Yahweh.'
 Springs, in solar mythology, 405 f.
 'Stand before,' 478.
 Stone, as place of execution, 271; standing-, 272.
 Stylus, for writing cuneiform, xvii, 254 f.; Hebrew terms for, 259 f.
 Šubandu, lxxiv.
 Šubbiluliuma, lxvii, lxxxvii, lxxxviii, xci.
 Šuccoth, 220, 228.
 Sudanese mercenaries, lxxxii.
 Sumer, Sumerians, lvi, lxii, lxiv, c, 385, 386; deities of, lvii; influence of civilization of, lxiii f.; language, ultimate connexion of Semitic bilinguals with, lvii; legal code of, lxiii.
 Sumu-la-ilu, lix.
 Sun, supposed effect of, on corn, 394; course of, in the heavens, 395 f., 399 f., yearly phases of, 396 f., 399; chariot of, 397.
 Sun-god, cvii, 42, 333, 392, 395, 396, 400, 406, 407, 421, 495, 496.
 Šuriḡ, Ġirbet, 377.
 Šūsitha, 308.
 Šūsiyyeh, 308.
 Šutarna, lxxxiv.
 Šutatarra, lxvii.
 Šutū, Šutū, lxxvii, lxxix f., lxxxiii, cxi.
 Šuwardata, lxxvii, lxxxiv.
 Synchronistic History of Babylonia and Assyria, c.
 Syria, Semites in, lvi, lviii; inclusion of, under name Amurru, lix; connexion of Hyksos with, lxvi; influx of Hittites into, lxvi, lxxi; invasion and conquest of, by Egyptian kings, lxvii ff.; sons of chieftains of, educated in Egypt, lxxviii; condition of, at period of T.A. Letters, lxx ff.; caravan-service through, lxx; non-Semitic element in population of, lxxxiii ff.; struggle of Egypt with Hittites in, lxxxix ff.; Hittite principalities in, xcix; Aramaeans in, ci f.; Syrian desert, lxxix f. See also 'Cana'an.'
 Ta'anach, Ta'annuk, 23, 79, 82, 131.
 Tab'al, Tab'el, 06.

- Ṭabbath, 223.
 Tablet for writing, 259.
 Tabor, xc, 79 f., 87, 234.
 Ṭakkara, xcii ff., xcvi, xcvi, 24, 384.
 Talmai, 9 f.
 Tammuz, xvii ff., 333 f., 397.
 Ṭanṭurah, 24.
 Tarḥulara, 84.
 Tarḥundaraba, lxxxiii.
 Ṭadu-Ḥipa, lxxii, lxxxvi.
 eṭ-Ṭayyibeh, 308.
 Tebeš, 234, 287.
 Tell Abū Kudīs, 82.
 Tell el-Amarna Letters, lxi, lxix ff.,
 lxxxviii, ci, cxi, cxii, cxiii, cxvi, cxvii,
 cxviii, 20, 26, 41, 66, 76, 99, 144, 253,
 256 ff., 265, 463, 477.
 Tell 'Arād, 16.
 Tell (Tulēl) el-Fūl, 465, 472, 479, 481,
 486.
 Tell Ġezer, 25.
 Tell el-Ḥasy, 501.
 Tell el-Ḳādy, xcix, 427.
 Tell Ma'in, 16.
 Tell el-Mashūṭa, civ.
 Tell el-Mutesellim, 23, 82.
 Tell eš-Šāfiyyeh, xciv.
 Tell eš-Šihāb, lxxxviii.
 Tell es-Sultān, 15.
 Tell el-Yahudiyyeh, lxxv.
 Tell Zif, 16.
 Temple, building of, by Solomon, l.
 Tentamon, xcvi, xcvi.
 Tent of Meeting, 440.
 Tent-peg. See 'Peg.'
 'Tents' = 'home,' 463.
 Teraphim, 117, 409, 416, 420 f., 426.
 Terebinth, 90, 187.
 Teuwatti, lxxxix.
 Thebes, lxx, lxxxvii, xcvi.
 Theocracy, conception of, 183.
 Thesmophoria, xviii f.
 Thirty, as title of Moon-god, 44.
 Threshing-board, 229.
 Threshing-floor, 204.
 Ṭhutmosi I., lxxvii, lxxxv.
 Ṭhutmosi II., lxxvii.
 Ṭhutmosi III., lxxvii f., lxxxv, lxxxix,
 cxii, cxiv, 26.
 Ṭhutmosi IV., lxix, lxxii.
 Tibneh (N.W. of Bethel), 56; (in
 Shephelah), 355, 430.
 Tid'al, lxii.
 Tiglath-Pileser I., lxxix, xcix, ci, 285.
 Tiglath-Pileser IV., cii, 415.
 Tii, lxxii.
 Timnah (N.W. of Bethel), 56; (in
 Shephelah), 355, 430.
 Timnath-ḥereš, Timnath-šeraḥ, 56.
 Titus, 464.
 Tob, land of, 308.
 To'i, To'u, cii.
 Tola', ciii, 289 f.
 Torches in pitchers, 216.
 Totemism, xviii, 225, 291.
 Tribal names transferred to places or
 districts, cxi.
 Trumpet, 215.
 Tūbās, 287.
 Tubi, 308.
 Tuḥi, cii.
 Tukulti-Ninib I., ci.
 Tunip, lxxxv, xci.
 Turuša, xcii.
 Tušratta, lxxii, lxxxvii.
 Tuḥanaton ('Tuḥanḥamon), lxxxvii.
 Tuwēl ez-Ziyāb, 226.
 Tyre, xcvi, 402.
 Tyrrhenians, xcii.

Ummān Manda, lxii.
 Ur, lv, lxxxiii, cx, 249, 250.
 Urim and Tummim, 3, 239 f.
 Ur-Šanabi, 396, 398, 400.
 Urṭās, 370.
 Urukagina, lxiii.
 Urusalim, 20, 463.
 'Ušš el-Ḡurāb, 226.
 Uta-napištim, 396, 398, 401.

 Vale, the, 19, 203 f.
 'Valley of Thorns,' 464, 465.
 Vandalian Church, 77.
Vartikā, 406.
 Varuna, lxxxiv.
 Vine, 273.
 Virgin-sacrifice, 332 ff.
Virgo, 399.

 Wadd, 437.
 Wādy el-'Ariš, 34.
 Wādy Beḥameh, 23.
 Wādy Bit Ḥannina, 465.
 Wādy ed-Dummi, 479.
 Wādy Far'ah, 207, 220, 222, 223, 224,
 225.
 Wādy el-Fiḳrah, 33 f.
 Wādy eg-Ḡōzeleh, 225.

Wādy el-Hāfy, 465, 481.
 Wādy Ḥesbān, 306.
 Wādy of Jezre'el, 185.
 Wādy Kāna, 24.
 Wādy el-Kelt, 15, 88.
 Wādy el-Mālih, 220.
 Wādy Mōgib, 310.
 Wādy el-Munnāb, 341.
 Wādy Rāgib, 326.
 Wādy eṣ-Ṣarār, 340.
 Wādy Šerrār, 185.
 Wādy eṣ-Šuwēniṭ, xxi, 465, 486.
 Wādy Tūmilāt, lxxv, civ, cix, 439.
 Wādy Yābis, 222, 489.
 Wādy ez-Zerkā, 310.
 Wādy Zimry, 481.
 Warad-Sin, lxi, lxii.
 Wašaša, xciii.
 Watches, night-, 216.
 Weaving, 381.
 Wenamon, narrative of, xcv, xcvi ff., 23, 24, 258.
 West Semitic language (language-group), 253; Arabian affinities in, lviii f., lx; alphabet, 254 ff.
 Wheat-harvest in Palestine, 367, 394.
 Whistling, effect of, on animals, 141 f.
 Wilderness-journey, Israel's, 311.
 Wine, new. See 'Must.'
 Wine-press, 187, 274.
 Witch of 'Endor, 426.
 Writing, reference to, in Judges, 232; use of cuneiform in Cana'an, lxix f., 253; earliest known documents in West Semitic language, 253 f.; development of cuneiform from pictographs, 254; cuneiform script and alphabetic script possibly co-existent in Cana'an in early times, 254 f.; explanation of paucity of written documents from Palestine, 255; method of writing cuneiform, xvii, 255, 495; Aramaic dockets on cuneiform tablets, 255; T.A. Letters written by West Semitic scribes, 256; use of alphabetic script in Assyria, 256, 495; exercises in writing cuneiform script, 257; West Semitic alphabet really a syllabary, 258; early use of papyrus in Cana'an, xcvi, 258; terms used in O.T. in connexion with writing, 258 ff.; earliest traces of West Semitic alphabet, 261; theories as to origin of West Semitic

alphabet, 261 ff. See also 'Alphabet,' 'Papyrus,' 'Stylus,' 'Cana'anite glosses,' 'Hebrew MSS.'

X, unknown source, 458.

Yabni-el, cxvii.

Ya'di, lxvi, xcv, 173 ff.

Yahweh, predilection of J narrative for use of name, xxxviii; Yahweh Šebhā'ōth, xl; Sinai, ancient seat of, cxx, 109, 251; Mosaic Yahwism in conflict with naturalistic Yahwism, cxx, 330; covenant of, cxxi, 60; spirit of, inciting men to action, cxx, cxxii, 66, 203, 317, 337 f., 357, 372; Israel's leader in battle, cxx, cxxii, 91, 109; consultation of oracle of, 3, 239 f., 425 f., 476 f.; sacred ban of, 18, 231, 456; mentioned on Moabite Stone, 18; Angel of, 35 f., 89, 151, 192, 346; title 'Servant of,' 56; strengthening Israel's foes, 68; connexion of, with phenomena of the storm, 91; 'arm of,' 129; 'righteous acts of,' 129; as King of His people, 183; name as denoting progressive revelation, 189; *Yahweh šālōm*, 193; relation of Ashera-cult to worship of, 196 f.; Asher possibly a surname of, cvii, 198; title 'Ba'al' applied to, 201 f.; originally an Amorite deity, 243 ff.; name revealed to Moses with uniquely new significance, 248 f.; early identification of, with Moon-god, 249 ff.; as national God (in restricted sense), 314 f.; human sacrifice to, 319 f., 329 f.; Teraphim in connexion with worship of, 330, 426. See also 'God.'

Yālō, 32.

Yanhamu, lxxviii, cxiii.

Yapaḥi, lxxix, cxvii, 26.

Yaphia', cxvii.

Yarimuta, cxiii.

Yarmuk, 306.

Yarmuth, cxiii.

Yašdata, lxxiv.

Ya-u, Ya-u-tum, etc., in proper names, 243 ff.

Ya'u-bi'di, cii, 245, 246.

el-Yemen, naḥb, 33.

Yeno'am, xci.
 Verimóth, cxiii.

Zabum, lix.

ez-Zâhariyyeh, io f.

Zakar-ba'al, xcvi ff., 258.

Zakir, Inscription of, lxiii, cii, 173 f.,
 254.

Zamama-šum-iddin, cl.

Zebah, 228.

Zebul, 279 f., 281-284.

Zebulun, cviii, 26, 79, 81, 239.

Ze'eb, 225 f.

ez-Zib, xiii, 29.

Zilpah-tribes, cx.

Zimrida, cxvii.

Ziph, 16.

Ziphron (Zifrân), c.

Zirdamyašda, lxxxiv.

Zodiac, 359.

II. INDEX OF GRAMMATICAL AND PHILOLOGICAL OBSERVATIONS

(The reference is to Hebrew unless otherwise specified)

- Accusative, adverbial**, 149.
- Arabic Place names, modern**, 499 ff.; modification of consonants in, xx, 24, 27, 29, 282, 306, 500, 501; modification of final *-el* to *-in* in, 21; dropping of final syllable in, 23; dropping of preformative *ʾ* in, 23, 306; formation of, by assonance with ancient names, 85, 145, 500.
- Article, Definite, idiomatic usages of**, 213, 287, 346, 489; with Construct State, 231; omission of, with Adjective, 378.
- Asyndeton**, 432.
- Babylonian Permansive compared with Hebrew Perfect**, lxiii.
- Babylonian Praeterite compared with Hebrew Imperfect with *Wāw* consecutive**, lxiii.
- Bilateral roots**, xiii, xvi, 40, 69, 92.
- Case-endings**, 167.
- Circumstantial clause**, 324, 326, 384, 425, 433.
- Construct State, before Preposition**, 136; Suspended, 150.
- Darga**, as substitute for *Methegh*, 461.
- Dativus incommodi**, 67, 277.
- Diminutives**, 27, 352.
- Egyptian expression of Semitic Dual-ending**, 66.
- Egyptian *r* representing *l* in another language**, 84; cf. lxxxviii, lxxxix bis, xci, xcii, xciii.
- Emphasis, expression of**, 321, 357, 367, 372, 419, 425.
- Hypocoristic affixes in Babylonian**, 76, 246.
- Hypothetical sentence, virtual**, 347.
- Imperative, original form of, in *Ḳal***, 166; 2nd pers. sing. masc. as Interjection, 429.
- Imperfect, anomalous use of**, 38; in pictorial description, 148; describing recurrence, 176, 185, 325, 327; emphatic form of, 152 f.; masc. form of 2nd pers. plur. referring to fem. subject preceding, 129, 237.
- Infinitive Absolute, usage of**, 73 f., 367; misunderstood by R.V., 25, 367, 372.
- Infinitive Construct with *ו***, 105 f.; with *ל*, 423.
- Interchange of Consonants in Semitic languages**, 111, 174, 430.
- Iphth'āl in Hebrew**, 353.
- Jussive in place of Imperative**, 149.
- Modus energicus* in Arabic**, 152, 169.
- Nūn t'liyyā***, 434.
- Order of Sentence**, 212, 457, 475, 479.
- Participle, usage of**, 213, 227, 368, 384; Active *Ḳal*, original form of, 166; Pu'āl, dropping of preformative *ו* in, 228.
- Pashā* in *ftl***, 38.
- Pausal forms, antiquity of**, 168.
- Perfect, idiomatic usages of**, 368, 369, 418; with *Wāw* consecutive after Infinitive, 483; with weak *Wāw*, 73, 214, 470; 2nd pers. fem. sing. of, with archaic termination, 116.
- Permansive. See 'Babylonian.'**
- Phonetic Complement in cuneiform**, lxxvi.
- P'el, final vowel of**, 167.
- Pluralis excellentiae* (intensive plural)**, 321, 323.
- Pronoun, Personal, 2nd pers. fem. sing.**, 418.
- Segholate Nouns, original pronunciation of**, 167.
- Sibilants, interchange of, in Semitic**, 111, 306, 328, 377.
- Substantive in place of Adjective**, 193, 231.
- Substantives ending in *-ūth***, 153.
- Tenses, sequence of**, 176, 328.
- Tone in Arabic**, 159.

- Transposition of Consonants in Semitic Roots, xv, 437.
- Trilateral Roots, modification in, 69, 116.
- Verb **ו** doubled, weakened forms of, 112.
- Vocalization, original form of, in Hebrew, 166 ff.
- Wāw* consecutive, usage of, 93, 227, 483.
- Wāw* explicative, 194.
- Wāw* introducing sentences with sarcastic turn, 187, 317.
- Wāw* of association, 326, 433.
- נ** introducing Nominative, 486.
- ב**, usage of, 230, 321.
- ה** locative, 72, 224.
- ל**, usage of, 204.
- כ** introducing direct narration, 190.
- ס** of norm, 7.
- ע**, harder form of, represented by **פ** in Greek, xix, 376; softer form of, represented by **ף** in cuneiform, lxxv, 386.
- ע**, usage of, 200, 224, 225.
- פ**, usage of, 425.
- ק** originally doubled in Hebrew, 168.
- ש** preformative in verbal forms, xvi.

III. INDEX OF FOREIGN TERMS

(The order of the English alphabet is followed)

HEBREW (INCLUDING CANA'ANITE 'GLOSSES'
FROM THE T.A. LETTERS)

- abbâr*, 151.
ābhar, 318.
ākhar, 321.
ālā, 418.
ālā, 3, 429, 432.
āliyyā, 71, 432.
allā, 'allōn, 86.
āmā, 276.
āmāl, 153.
āmēlīm, 153.
ānōk, 20.
āran, 283.
āphuḏdā, 237, 241.
ārāh, 114.
ārakh, 198 f.
ās^hrōth sōnékhā 58.
az, 363.
badiu, 166.
bālāl, bōlāl, 467.
barḡānīm, 230.
bāsār, 390.
bāšar, 278.
baṭnu, 167.
bēliyā'al, 467 f.
bēšā', 145.
bēṭah, 231.
biḡā, 62, 203.
bōšeth, 5, 58, 202.
dāgh, 385.
dāghān, 386.
Dāleth, 262.
dārōm, cvii f.
d^hlūthōth, 259.
dorbhān, dorbhōnā, 77.
dūš, 229 f.
ēdhā, 446, 453.
ehyeh, 189.
ē'ā, 'ēlōn, 'ēlīm, 86, 90, 187.
ēleph, 189.
ēlōhim, 36, 117, 346, 350, 421, 425 f.
ēmek, 19, 112, 144, 202, 203 f.
ēphōth badh, 238.
ēśnābh, 155.
ēt, 260.
gālāl, galgal, 37.
gāraph, 146.
gath, 187, 274.
g^hdhērōthāyim, 141.
Gelil hag-gōyīm, 29.
gēr, 422, 436, 438.
giāh, 480.
gillāyōn, 250.
gilyōn, 260.
Gīmel, 262.
gōmedh, 70.
gullath, 13.
gūr, 357.
hābhut, 187.
hag, 492.
hāḡak, 258.
hālaph, 154, 379 f.
hālāphōth b^hghādīm, 362.
halmūth, 153.
hāmōr, hāmar, 372 f.
hāmūšīm, 213.
hāram, hē^herīm, 17 f., 144.
hāraš, 258.
hārath, 258.
harri, 168.
hās, 71.
h^hšōšerā, 215.
hāthān, 15.
hawwā, hawwōth, 468.
hē'ebhēr bū'ēš, 331.
hem'ā, 93.
hērem, 18, 44, 286, 456.
hēreph, 143.
hēreṭ, 259; hēreṭ 'ēnōš, 260.
hēšebh, 237.
hēšekh, 382.
hīdhā, 361.
hīlūlīm, 278.
hīphhīs, 271.
hīshūth, 477.
hīthnaddēbh, 106, 109.
hīseḡ, 68.

hō'il, 25, 424.
hōmer, 192.
hōreš, 84.
hōrīs, xlv, 19, 316.
h'ia, *mōšā*, xxxiii, 59.
hōthēn, 15.
'išōn, 352.
'iššā, 356.
'iṭṭēr, 69.
kaddīm, 215.
kadhmōn, 352.
kāhāl, *niḫhal*, 446.
kālīl, 483.
kārā, xiv f.
kāšm, 309.
kāthabb, 258.
kedhem, *kidēm*, 147.
kedhēšim, *kedhēšōth*, 58, 407.
kedhūmim, 147.
kēn, 137.
kēphār, 357.
kérem, 278.
kedsem, 421.
kedhōthām, 425.
kēthābh 'aššūrī, 262.
kikk'rōth lēhem, 228.
kiššā'im, 363.
kōl, 425.
lēket, 227.
Lēwī, *lāwā*, 437.
limmēdh, 77.
lūah, 259.
mā'arākhā, 198 f.
maddīm, 70.
madh, *middin*, 122.
māhā, 259.
māhaḳ, 154.
maḥ'lāphā, 379 f.
maḥ'nē, 219.
maḥṣu, 168.
makhtēš, 374.
malmedh, 77.
māōz, 198.
maš, 25.
maš'abbim, 129.
māšak, 87, 136.
maš'ēth, 483.
maššēbhā, *maššēbhōth*, 197, 272.
maššēkhā, 'graven image,' 242, 419.
maššēkkeheth, *maššēkhā*, 'web,' 381 f.
mazzālōth, 146.
m'ārā, xix.
m'bhō, 22.
m'gillā, 259.

m'hōḳ'kīm, 122, 136.
m'il, 238.
mēlekh, 265.
m'ōnēn, 283.
mēār, 42.
m'šillā, 479.
millē yadh, 421.
millā'im, 422.
mīma, *mēma*, 168.
mīnhā, 70, 191, 349.
mīnhārōth, 185.
mīphrās, 143.
mīšd'rōnā, 73.
mīšōr, 203, 306, 307.
mīšpāha, 189.
mīšpāt, 347.
mīšp'thāyim, 141.
mīšē, 344.
mōēdh, 482.
mōhar, 354, 356.
mōkēš, 39 f.
mōrāgh, 209.
mōthēth, 288.
mūlīthā, 272.
nā, 190.
nār, li.
nārā, 356.
nāhal, xiii, 88.
nākaš, 40.
naḳṣapu, *naḳṣapti*, 169.
nāšakh, 'weave,' 382.
nāšakh, 'cast,' 419.
nāzār, 342.
nēbhālā, *nābhāl*, 466.
nēpheš, 122, 390.
nēzem, 235.
niḳḳā, 368.
nōḳah, 426.
nūā, 273.
'ōbh, 425.
'ōhel, 463.
'ōlēlōth, 'ōlēl, 227, 487.
'ōrēhā, 114.
pā'am, 353.
pā'mē, 155.
pah, 39 f.
pārā, *pēdā*, 107 f.
pāraš, 116.
par'edhōnā, 72.
pāšā, 322.
pāšat, 282.
pē, 284.
pēlaggōth, *pēluggōth*, 136.
pēlah rékkeh, 288.

pēlīṭim, *pālaṭ*, 327.
pērāzī, 6.
pērāzōn, 115.
pērāzōth, 115.
pēsel, 419.
pēšilim, 71.
pil'ī, 349, 350.
pinnōth, 472.
pōh^azīm, *paḥ^azūth*, *paḥaz*, 271.
rā'aš, 295.
rāham, 155.
rāmā, 374.
rāphā, xx, 462.
rēhayim, 288.
r'ḥōbh, 466.
rēkīm, *rēkām*, 308 f.
r'phāim, 421.
Rēš, 262.
rībḥ, 201.
rōsⁿīm, 109.
rūaḥ, 227, 374.
rūdḥ, 323.
rušunu, 169.
šā'al bē, 426.
šā'ar, 431.
šādē, 262.
šādhār, 73.
šādhē, 111 f., 144.
šādhin, 362.
šādhūdh, 154.
sah^arōnim, 235.
šahri, 167.
šākal, 378.
šālah, 66, 357.
šālam, 287.
šāphā, 307.
šāphaṭ, 59, 85; *šōphēṭ*, *šōph^eṭim*, xxxiii, 1.
šāraḥ, 142.
šāraph, 208.
šārīm, 232.
šāsā, lxxix.
šatē, 167.

šēbher, xvi, 214.
šēbket, 136.
š'ḥōrōth, 124.
š'lūl, *š'lil*, 213.
š'mikhā, 92.
šēphēl, 152.
šēpher, 259.
šēren, 62.
š'riah, 286.
š'rikōth 'ādḥārīm, 141 f.
šīaḥ, 125.
šīšād, *šēšād*, 357.
šippūy, 241.
šittū, 465.
šōḳ, 369.
šōphār, 215.
šōp^erīm, 259.
šū'ru, 167.
terāphim, xx, 421.
ṭibbār, *ṭabbār*, 283.
ṭinnā, 129, 325.
ṭiphšar, 495.
ṭirōš, 274.
tōlā'ath, 291.
tōmer, 86.
tōrā, 206.
tormā, 281.
tūr, 22.
'ūgābh, 142.
yākaš, 40.
yārēkh, 264, 370.
yark^ethē, 459.
yāšabh, 86, 123.
yāthēdh, 80, 381 f.
yaskur, 169, 386.
yēḳebḥ, 187, 274.
yēther, 378.
yibbēbh, 154.
yukabid, 168.
zānah, 460.
zēḳēnīm, 232.
zimmā, 473.
zuruk, 168.

BABYLONIAN AND ASSYRIAN (INCLUDING SUMERIAN)

A.BA, 495.
 ADDA, lxi.
ālu, 463.
 AMA.UŠUMGAL.ANNA, xix.
amēlu, lxxiv.

ANŠU.KURRA, lxx.
Arba'ilu (*ālu*), 43.
balālu, 327.
 BAR, PAR, xvi.
bēlit taḥāzi, 59.

DA, 262.
dātu, 291.
dānu, 392.
dāšu, 229.
 DUMU.ZI, *Du'ūzu*, *Dūzu*, xvii.
duppu, 259.
dupšarru, 495.
elēpu, 380.
galāsu, 209.
 GAM, 262.
 GAR.ZA, 116.
habbatum, *habātu*, lxxvi.
halāpu, *naḥlaptu*, 362.
ḥarimtu, 58, 407.
Ḥarrānu, 249.
ḥaṭṭu, *ḥaṭātu*, 260.
ḥazan(u), *ḥazianu*, lxxiv.
ḥuršu, *ḥursu*, 85.
ibru, lxxxiii.
ištarāti, 59.
kadādu, 262.
 KA.DI, xix.
kaḏištu, 58, 407.
kapāru, *kuppuru*, xvi.
karittu, 59.
kazratu, 407.
kēnu, 137.
kettu, 42.
 KI, lxxviii.
Kīmta rapaštum, lviii.
Kīmtum kettum, lix.
 KIRRUD.DA, 72.
 KIŠ, lv.
kuḏnu, 147.
 KUR, 112.
lulā amēlu, 399.
manzazu, *manzaltu*, 146.
 MAR.TU, lix, 41.
 MAR.ZA, 116.
māt la tāri, 468.
mātu, 112.
 MEŠ, lxxvi.
mēšāru, 42.
mī, *ma*, 247.

muallidat, 59, 199.
mulū, 272.
nīmelu, 154.
 PA, 263.
parašdinnu, 72.
parāsu, 116.
parsigu, 404.
paršu, 116.
pašātu, 282.
pirištu, 116.
pirtu, 107.
pū, 284.
pulggu, *pulukku*, 139.
rabū, *rapū*, xx, 421, 462.
raḥāšu, 295.
rēšu, 262.
 RU, 262.
ruššunu, 109.
šabrū, *šabrātu*, xvi, 214.
šaddu, 39.
šadū, 112.
šagāšu, lxxvi.
 SA.GAZ, lxxv ff., 25.
šahātu, 477.
šalāmu, 287.
šamḥatu, 407.
šāpiṭu, xxxiii.
šāru, 133.
šaššu, 10.
šatāru, 258.
seseru, *sisseru*, 84.
 SI.PA, (*abnu*), 285.
šīfru, *šapāru*, 259, 325.
šīšū, lxx.
 ŠU, 421.
talīmu, 10.
tultu, 291.
umalli kātu, 422.
urudū, 152.
urzunu, 109.
zarāḥu, 386.
 ZI, ZIDA, ZIDE, 262.
zinū, 460.

ARAMAIC (INCLUDING SYRIAC).

abbūbhā, 142.
āmal, 154.
biššudā, 145.
biškū, *beškū*, 5.
graph, 146.

ḥarat, 259.
ḥarrēph, 143.
hawthā, 463.
hillūtā, 279.
ilānā, 86.

kîn, 137.
māthā, 112.
p^{er}d, 107.
p^{er}saṭ, 282.
pulāgā, 140.
rēšā, 262.
ṣaphrā, 207.
ṣaššā, 358.

ṣerihā, 286.
ṣiharā, *ṣahrā*, 235.
tannī, 129.
teḥm, 10.
ṭibbūrā, 283.
yabbēbh, 154.
yathrā, 378.

ARABIC.

'*ahl*, 463.
'*ahlu-lwabar*, 152.
'*aḡdama*, 147.
'*amila*, '*amal*, '*amil*, 153 f.
'*amm*, lviii.
'*anna*, 283.
baḡ'a, 145.
baṭn, 265.
baṭneh, 306.
ḡafara, 207.
Dāl, 262.
ḡarīḡ, 286.
faḡ, 40.
faḡīḡ, 265.
far', 107.
farā'a, 107, 108.
furḡah, *firād*, *farāḡa*, 143.
fuwwah, 291.
ḡala, 260.
ḡal'ad, 306.
ḡanna, 283.
ḡarafa, 146.
Ġim, 262.
ḡū'al, 278.
ḡaḡḡ, 402.
ḡalafa, *ḡalf*, 380.
ḡalīf, 380.
ḡamara, 373.
ḡamīs, 213.
ḡaruma, 18.
ḡašša, *ḡiṣṣah*, 126.
ḡātin, 15.
ḡāwiya, 468.
ḡaḡḡ, 139.
ḡilāl, 279.
ḡadūm, 148.
ḡādū, 309.
ḡanna, 138.

kara'a, xiv. f.
laḡd, 286.
lawī'u, *lawī'at*, 437, 442.
leben, 93.
madda, 123.
maḡaḡa, 154.
manzil, *al-manāzil*, 146.
marra, 363, 380.
masaka, 136.
minhara, *minhar*, 185.
muḡāra, xix.
nasaḡa, 382.
rāda, 323.
rakā'a, xv.
rukṇ, 472.
ṣabāb al-'arīs, 361.
ṣadāḡ, 265, 367.
ṣadīḡa, 265, 355, 367.
saḡ, 283.
sahel, 90.
ṣahr, 235.
ṣaḡūr, *ṣuḡra*, 124.
ṣalama, 287.
sāra, 133.
ṣarḡ, *saraḡa*, 286.
sunbul, *sunbula*, 328.
tahlil, 279.
ṭanna, 129.
'ulliya, '*illiya*, 71.
wādy, 88.
waḡa, 437.
walaḡa, xiv.
warik, *waraka*, 370.
waṣa, 437.
watar, 378.
wazīr, 367.
wely, *wala*, 437.
zamān, 461.

GREEK.

'Αδώνιδος κῆποι, 333.
 ἄκανθα, 465.
 ἀντλητρίαι, xviii.
 ἀσεβής, 468.
 Ἀχαιοί, xcii.
 Βεελζεβουλ, 5.
 Βελιαλ, Βελιαρ, 46α.
 βουγονία, xix, 36α.
 Γάμμα, 262.
 Δαναοί, xciii.
 Φαξός, 'Οαξός, 'Αξός, xciii.
 Ζῆτα, 262.
 'Ηλιοδῶρος, lxxxiv.
 κενός, 309.
 Κόρη, 332.
 λάμπουρις, 394.
 μέγαρον, xviii.
 Μέλισσα, 85.
 μητρόπολις, 9.
 Μισωρ, 42.

Μόσχοι, xcix.
 Μυλιττα, 59, 198.
 "Ονου γνάθος, 371.
 ὀπισθόδομος, 271.
 ὄρνυξ, 406.
 πεδινή, 8.
 πεδίων, 8.
 πυγμή, 70.
 'Ρακά, 309.
 'Ρῶ, 262.
 σινδών, 362.
 στρατόπεδον, 219.
 Σινδνκ, 42.
 σῦριγξ, 142.
 Τευκροί, xciii.
 τύραννος, 62.
 Τυρσηνοί, xcii.
 υἱοὶ τοῦ νυμφῶνος, 361.
 φίλος τοῦ νυμφίου, 367.
 Ζεὺς ἀρότριος, 386.

LATIN.

acer, 363.
Achivi, xcii.
aerarium, 271.
augurium canarium, 393.
cerealia, 386.
Citrullus colocynthis, 364.
dividere, 127.
Eristalis tenax, 359.

furtum licio et lance conceptum, 239.
pietas, 469.
Pistacia terebinthus, 187.
Rhamnus palaestina, 275.
robigo, 393 f.
Rubia tinctorum, 291.
sibila, 141.
uredo, 394.

IV. INDEX OF PASSAGES FROM OTHER BOOKS
 DISCUSSED


Gen. 4⁸ . . . 417.
 Gen. 10¹⁹ . . . 224.
 Gen. 14 . . . lxi f.
 Gen. 16¹³ . . . 193.
 Gen. 18^{1ff.} . . . 348.
 Gen. 23 . . . lxxxv f.
 Gen. 24² . . . 264.
 Gen. 30¹¹ . . . 197 f.
 Gen. 34 . . . 438.
 Gen. 43¹⁴ . . . 378.
 Gen. 47²⁷ . . . 204.

Gen. 48^{21, 22} . . . cxi, 270.
 Gen. 49⁵⁻⁷ . . . 437.
 Gen. 49¹⁶ . . . 392.
 Ex. 3¹² . . . 189.
 Ex. 3¹⁴ . . . 189 f., 248 f.
 Ex. 12⁴⁰ . . . cxii.
 Ex. 18^{8ff.} . . . 252.
 Ex. 19²⁰ . . . 417.
 Ex. 21⁶ . . . 117, 330.
 Ex. 22^{8, 9} . . . 117, 330.
 Ex. 24⁹⁻¹¹ . . . 252 f.

Ex. 28	236 ff.	1 Sam. 8 ^{6,7}	183.
Ex. 32	440 f.	1 Sam. 11 ¹²⁻¹⁵	301.
Ex. 32 ³²	259	1 Sam. 12	xlii f.
Ex. 33 ¹⁹	189 f.	1 Sam. 13 ¹	lii.
Ex. 34 ⁶	253.	1 Sam. 13 ⁵	20.
Num. 6 ¹⁻²¹	342.	1 Sam. 14 ¹²	233.
Num. 14 ⁴⁰⁻⁴⁵	44 f.	1 Sam. 14 ¹⁸	3, 239, 242
Num. 21 ¹⁻³	18, 44 f.	1 Sam. 14 ⁴¹	3, 240.
Num. 21 ²⁴	305, 314.	1 Sam. 23 ⁶	239.
Num. 21 ²⁸	270, 389.	2 Sam. 1 ^{21a}	112.
Num. 22 ²⁻²⁴ ²⁵	316.	2 Sam. 23 ¹¹	371.
Num. 26 ^{29 ff.}	134.	2 Sam. 24 ⁶	xcix, 23.
Num. 31 ^{1 ff.}	456.	1 Kgs. 4 ¹²	xviii, 221 f.
Num. 32 ²²	368.	1 Kgs. 5 ³⁽¹⁷⁾	115.
Num. 32 ³⁹	50.	1 Kgs. 12 ^{28,31}	441.
Num. 34 ^{3,5}	34.	2 Kgs. 1 ⁷	347.
Deut. 1 ⁴¹⁻⁴⁶	44.	2 Kgs. 3 ^{26,27}	320.
Deut. 32 ⁸	37.	Isa. 8 ¹	259 f.
Deut. 32 ⁴²	107 f.	Isa. 17 ¹⁰	333.
Deut. 33 ²	109 f.	Isa. 19 ¹⁸	32.
Deut. 33 ^{6b}	4.	Isa. 30 ⁸	259.
Deut. 33 ²³	cvij f.	Isa. 30 ²²	242 f.
Deut. 33 ²⁹	198.	Isa. 57 ⁹	133.
Josh. 1 ⁵	189.	Isa. 63 ⁹	36.
Josh. 7, 8	455, 457.	Jer. 7 ^{12,14}	435.
Josh. 8 ¹⁷	21.	Jer. 26 ^{6,9}	435.
Josh. 11 ³	62.	Ezek. 13 ²⁰	149.
Josh. 13 ¹³	51.	Ezek. 16 ^{3,45}	lxxxvii.
Josh. 14 ¹⁵	9.	Ezek. 44 ^{18b}	237.
Josh. 15 ¹⁻⁴	34.	Hos. 2 ⁸⁽¹⁰⁾	241.
Josh. 15 ^{8 ff.}	430, 431.	Hos. 5 ⁸	133.
Josh. 15 ¹⁴⁻¹⁹	8.	Hos. 8 ¹⁰	184.
Josh. 15 ⁶³	6, 20.	Hos. 9 ^{10, 10^c}	445.
Josh. 16 ^{10b}	26.	Am. 2 ^{11,12}	343.
Josh. 17 ^{1b,2}	134 f.	Am. 3 ⁵	40.
Josh. 17 ¹⁴⁻¹⁸	49 f.	Am. 8 ¹⁴	292.
Josh. 18 ^{14 ff.}	430.	Mic. 6 ¹⁻⁸	330.
Josh. 19 ¹⁵	27.	Zech. 12 ¹¹	333.
Josh. 19 ²⁴	28.	Ps. 35 ^{5,6,7}	124.
Josh. 19 ¹⁷	31, 51.	Ps. 54 ⁵⁽⁶⁾	321.
Josh. 19 ⁵⁰	32.	Ps. 69 ³¹⁽³²⁾	104.
Josh. 23	xliii f.	Ps. 118 ⁷	321.
Josh. 24	xlii f.	Job 6 ¹⁹	114.
Josh. 24 ^{28,31}	52 f.	Job 31 ³²	114.
Josh. 24 ³⁰	32.	Dan. 11 ³⁷	333.
1 Sam. 1 ²²	200.	1 Chr. 2 ⁴²⁻⁵⁵	341.
1 Sam. 2 ²²	435.	1 Chr. 7 ¹⁴⁻¹⁶	135.
1 Sam. 5 ⁴	386.	Eccles. 50 ^{12^{cc}}	199.





CENTRAL PALESTINE (NORTHERN PORTION)




CENTRAL PALESTINE (SOUTHERN PORTION)

COLOURED SCALE
OF ALTITUDE



The Edinburgh Geographical Institute


Scale - 8 Miles to an Inch



Roads

John Bartholomew & Co










Fig. 1



Fig. 2




Fig. 3



Fig. 4




Fig. 5




Fig. 1




Fig. 2





Fig. 3








Fig. 1





Fig. 2



L. B. Cat. No. 1137

06130

DEC 18 '62

- 64 -

... ..

DEC 15 79

2930

DEC 10 1958

MAY 21 1980

DEC 7 '81

NGV 80

2223893

C-100



3 5002 00093 4542

The book of Judges with introduction and

BS 1305 .B5 1920

Bible.

The book of Judges with
introduction and notes

